

PROJECT ID: PROJECT NO. JOCS\_DDC JOC2013E-2

### THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF PUBLIC BUILDINGS

30-30 THOMSON AVENUE LONG ISLAND CITY, NEW YORK 11101-3045 TELEPHONE (718) 391-1000 WEBSITE www.nyc.gov/buildnyc

LAW

# VOLUME 1 OF 2

# **BID BOOKLET**

JOB ORDER CONTRACT - ELECTRICAL WORK- BOROUGH OF BROOKLYN & STATEN ISLAND (EXCEPT: COURTS, CORRECTION & JUVENILE DETENTION PROJECTS)

LOCATION: BOROUGH: CITY OF NEW YORK Boro Wide Boro Wide

CONTRACT: PIN NUMBER: ELECTRIC WORK E-2 8502016RQ0007C



Date:

September 1, 2015





Dr. Feniosky Peňa-Mora Commissioner

Charlette Hamamgian, Esq. Agency Chief Contracting Officer Lorraine Holley Deputy ACCO Competitive Sealed Bid Contracts

May 06, 2016

CERTIFIED MAIL - RETURN RECEIPT REQUEST ARCADIA ELECTRICAL CO., INC. 1005 WYCKOFF AVE. RIDGEWOOD, NY 11385

RE:

FMS ID: JOCS\_DDC E-PIN: 85016B0036001 DDC PIN: 8502016RQ0007C JOC2013E-2: JOB ORDER CONTRACT -ELECTRICAL WORK- Brooklyn & Staten Island NOTICE OF AWARD

Dear Contractor:

You are hereby awarded the above referenced contract based upon your bid multiplier in the amount of 1.0785\* submitted at the bid opening on November 18, 2015. Within ten (10) days of your receipt of this notice of award, you are required to take the actions set forth in Paragraphs (1) through (3) below. For your convenience, attached please find a copy of Schedule A of the General Conditions to the Contract, which sets forth the types and amounts of insurance coverage required for this contract.

- (1) Execute four copies of the Agreement in the Contracts Unit, 30-30 Thomson Avenue, 1<sup>st</sup> Floor, Long Island City, New York (IDCNY Building). A Commissioner of Deeds will be available to witness and notarize your signature. The Agreement must be signed by an officer of the corporation or a partner of the firm.
- (2) Submit to the Contracts Unit four properly executed performance and payment bonds. If required for this contract, copies of performance and payment bonds are attached.
- (3) Submit to the Contracts Unit the following insurance documentation: (a) original certificate of insurance for general liability in the amount required by Schedule A, and (b) original certificates of insurance or other proof of coverage for workers' compensation and disability benefits, as required by New York State Law. The insurance documentation specified in this paragraph is required for registration of the contract with the Comptroller's Office.

\*\$5,000,000.00 Maximum Contract Amount

· · ·



On or before the contract commencement date, you are required to submit all other certificates of insurance and/or policies in the types and amounts required by Schedule A. Such certificates of Insurance and/or policies must be submitted to the Agency Chief Contracting Office, Attention: Risk Manager, Fourth Floor at the above indicated department address.

Your attention is directed to the section of the Information for Bidders entitled "Failure to Execute Contract". As indicated in this section, in the event you fail to execute the contract and furnish the required bonds within the (10) days of your receipt of this notice of award, your bid security will be retained by the City and you will be liable for the difference between your bid price and the price for which the contract is subsequently awarded, less the amount of the bid security retained.

Sincerely,

oriain Holly

Lorraine Holley

.

,

.

#### <u>Bid Tab</u>

Descript	ion	JOC2013E-2: JOB ( WORK- Brooklyn &	DRDER CONTRACT - E & Staten Island	CLECTRICAL				
Bid Date		11/18/2015	FMS ID	JOCS_DDC				
Estimate	d Cost	\$5,000,000.00	Client Agency	DDC				
Bid Secu	rity	\$15,000.00	PLA	YES				
Time Allo	owed	1095CCD	Contract Manager	Brenda Barreiro				
Addendu	m	0	Project Manager	JOE TABIA				
PIN		8502016RQ0007C	E-PIN	85016B0036				
Selective ]	Bidding	□Yes ⊠No	Consultant	IN-HOUSE				
Bid Rank		Vendor	Bid Multiplier	Security Type				
1	ELMHUR	ST ELECTRIC CORP	e. 0.9819	Bond				
2	ARCADIA	ELECTRICAL CO., J	INC. 1.0785	Bond				
3	MSR ELEC CONSTRU	CTRICAL CTION CORP	1.1620	Bond				
4		ELECTRIC ANCE CORP	1.3725	Bond				
5	RNH ELEC	CTRIC COMPANY, IN	NC. 1.7500	Check				
<b>SUBCC</b>	SUBCONTRACTORS:							

Plumbing:Blue Steel ContractorsHVAC:Blue Steel Contractors.

onaine Ho Recorder: Brenda Barreiro Ext.1041 Approver:

Bid Tab Pin: 8502016RQ0007C

Page 1 of 1

APT E-PIN #: 85016B0036

#### **Qualification Form**

List previous projects completed to meet the special experience requirements for this contract. Please photocopy this form for submission of all required projects.

Name of Contractor: Arcadia Electrical Co., Inc.
Name of Project: Family Life Center Catherine Street
Location of Project:78 Catherine St., New York NY
Owner or Owner's representative (Architect or Engineer) who is familiar with the work performed:
Name: DOHS / DDC - Navinchandra Patel
Title: Project Officer Phone Number: 718-391-1187
Brief description of work completed: Installation of CCTV System
Was the work was performed as a prime or a subcontractor:Prime
Amount of Contract: \$349,372.44
Date of Completion:5/19/15
******************
Name of Contractor: Arcadia Electrical Co., Inc.
Name of Project: DOT - Harper Street
Location of Project: 30-01 Harper St. Queens NY
Owner or Owner's representative (Architect or Engineer) who is familiar with the work performed:
Name: <u>NYC DDC - Albert Moy</u>
Title: Project Officer Phone Number: 646-772-9721
Brief description of work completed: Furnish and Install 4000 Amp Service
Was the work was performed as a prime or a subcontractor: Prime
Amount of Contract: \$1,955,741.84
Date of Completion: 1/23/15

APT E-PIN #: 85016B0036

#### **Qualification Form**

List previous projects completed to meet the special experience requirements for this contract. Please photocopy this form for submission of all required projects.

Name of Contractor:	Arcadia Electrical Co., Inc.
Name of Project:	Bloomingdale Library
Location of Project: _	150 West 100th Street, New York
Owner or Owner's rep	presentative (Architect or Engineer) who is familiar with the work performed:
Name: Flora Tash	
Title: Project O	fficer Phone Number: 718-391-2288
Brief description of wo	ork completed: Fire Alarm & Emergency Lighting
Was the work was per	formed as a prime or a subcontractor:
Amount of Contract:	\$140,290.62
Date of Completion: _	5/21/14
***********	******
Name of Contractor: _	Arcadia Electrical Co., Inc.
Name of Project:	Belmont Branch Library
Location of Project:	610 E.186th Street, Bronx NY
Owner or Owner's repr	esentative (Architect or Engineer) who is familiar with the work performed:
Name: Richard	
Title: Project C	Officer Phone Number: 347-234-0294
Brief description of wor	k completed: Fire Alarm Upgrade
Was the work was perfo	ormed as a prime or a subcontractor:
Amount of Contract:	\$117,8796.40
Date of Completion:	8/2013

APT E-PIN #: 8

85016B0036

#### BID FORM THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF PUBLIC BUILDINGS

#### BID FOR FURNISHING ALL LABOR AND MATERIAL NECESSARY AND REQUIRED FOR:

#### PROJECT ID: JOCS\_DDC

Name of Bidder: Arcadia Electrical Co., Inc.

Date of Bid Opening: \_\_\_\_\_11/18/15

Bidder is: (Check one, whichever applies) Individual () Partnership () Corporation (X)

Place of Business of Bidder: 1005 Wyckoff Avenue Ridgewood NY 11385

Bidder's Telephone Number: 718-418-0106

Residence of Bidder (If Individual): \_\_\_\_\_N/A

If Bidder is a Partnership, fill in the following blanks:

Names of Partners

Residence of Partners

the second s

N/A

If Bidder is a Corporation, fill in the following blanks: Organized under the laws of the State of <u>New York</u>

Name and Home Address of President: Stephen Gianotti, 216-15 31st Rd., Bayside NY 11360

Name and Home Address of Secretary: \_\_\_\_\_\_\_ Stephen Gianotti, \_\_\_\_\_ 216-15 31st Rd., Bayside NY 11360

Name and Home Address of Treasurer: \_\_\_\_\_\_ Stephen Gianotti, \_\_\_\_\_ 216-15 31st Rd., Bayside NY 11360

APT E-PIN #: 85016B0036

**BID FORM** 

The above-named Bidder affirms and declares;

1. The said bidder is of lawful age and the only one interested in this bid; and no person, firm or corporation other than hereinbefore named has any interest in this bid, or in the Contract proposed to be taken.

2. By submission of this bid, each bidder and each person signing on behalf of any bidder certifies, and in the case of a joint bid each party thereto certifies as to its own organization, under penalty of perjury, that to the best of its knowledge and belief: (1) the prices in this bid have been arrived at independently without collusion, consultation, communication or agreement, for the purpose of restricting competition, as to any matter relating to such prices with any other bidder or with any competitor; (2) unless otherwise required by law, the prices quoted in this bid have not been knowingly disclosed by the bidder and will not knowingly be disclosed by the bidder prior to opening, directly or indirectly, to any other bidder or to any competitor; and (3) No attempt has been made or will be made by the bidder to induce any other person, partnership or corporation to submit or not to submit a bid for the purpose of restricting competition.

3. No councilman or other officer or employee or person whose salary is payable in whole or in part from the City Treasury is directly or indirectly interested in this bid, or in the supplies, materials, equipment, work or labor to which it relates, or in any of the profits thereof.

4. The bidder is not in arrears to the City of New York upon debt or contract or taxes, and is not a defaulter, as surety or otherwise, upon any obligation of the City of New York, and has not been declared not responsible, or disqualified, by any agency of the City of New York or State of New York, nor is there any proceeding pending relating to the responsibility or qualification of the bidder to receive public contracts except as set forth on the Affirmation included as page 9 of this Bid Booklet.

The bidder hereby affirms that it has paid all applicable City income, excise and other taxes for all years it has conducted business activities in New York City.

The bidder, as an individual, or as a member, partner, director or officer of the bidder, if the same be a 5. firm, partnership or corporation, executes this document expressly warranting and representing that should this bid be accepted by the City and the Contract awarded to him, he and his subcontractors engaged in the performance: (1) will comply with the provisions of Section 6-108 of the Administrative Code of the City of New York and the non-discrimination provisions of Section 220a of the New York State Labor Law, as more expressly and in detail set forth in the Agreement; (2) will comply with Section 6-109 of the Administrative Code of the City of New York in relation to minimum wages and other stipulations as more expressly and in detail set forth in the Agreement; (3) have complied with the provisions of the aforesaid laws since their respective effective dates, and (4) will post notices to be furnished by the City, setting forth the requirements of the aforesaid laws in prominent and conspicuous places in each and every plant, factory, building and structure where employees engaged in the performance of the Contract can readily view it, and will continue to keep such notices posted until the supplies, materials and equipment, or work labor and services required to be furnished or rendered by the Contractor have been finally accepted by the City. In the event of any breach or violation of the foregoing, the Contractor may be subject to damages, liquidated or otherwise, cancellation of the Contract and suspension as a bidder for a period of three years. (The words, "the bidder", "he", "his", and "him" where used herein shall mean the individual bidder, firm, partnership or corporation executing this bid).

#### 6. Compliance Report

The bidder, as an individual, or as a member, partner, director, or officer of the bidder, if the same be a firm, partnership, or corporation, (1) represents that his attention has been specifically drawn to Executive CITY OF NEW YORK
Department of Design and Construction
Page 14
BID BOOKLET
SEPTEMBER 2008



APT E-PIN #: 85016B0036

Order No. 50, dated, April 25, 1980, on Equal Employment Compliance of the contract, and (2) warrants that he will comply with the provisions of Executive Order No. 50. The Employment Report must be submitted as part of the bid.

The bidder, as an individual, or as a member, partner, director, or officer of the bidder, if the same be a firm, partnership, or corporation, executes this document expressly warranting that he will comply with: (1) the provision of the contract on providing records, Chapter 8.

7. By submission of this bid, the bidder certifies that it now has and will continue to have the financial capability to fully perform the work required for this contract. Any award of this contract will be made in reliance upon such certification. Upon request therefor, the bidder will submit written verification of such financial capability in a form that is acceptable to the department.

8. In accordance with Section 165 of the State Finance Law, the bidder agrees that tropical hardwoods, as defined in Section 165 of the State Finance Law, shall not be utilized in the performance of this Contract, except as the same are permitted by the foregoing provision of law.

9. The bidder has visited and examined the site of the work and has carefully examined the Contract in the form approved by the Corporation Counsel, and will execute the Contract and perform all its items, covenants and conditions, and will provide, furnish and deliver all the work, materials, supplies, tools and appliances for all labor and materials necessary or required for the hereinafter named work, all in strict conformity with the Contract, for the prices set forth in its bid.

10. <u>M/WBE PARTICIPATION REQUIREMENTS</u>: By signing its bid, the bidder agrees to the Vendor Certification and Required Affirmations set forth below. The Vendor Certification and Required Affirmations will be deemed to satisfy the requirement to complete Section V of Part II of Schedule B: M/WBE Participation Requirements.

#### Section V: Vendor Certification and Required Affirmations:

Ihereby:

- 1) acknowledge my understanding of the M/WBE participation requirements as set forth herein and the pertinent provisions of Section 6-129 of the Administrative Code of the City of New York and the rules promulgated thereunder;
- 2) affirm that the information supplied in support of this Subcontractor Participation Plan is true and correct;
- 3) agree, if awarded this Contract, to comply with the M/WBE participation requirements of this Contract as established on each individual Task Order, the pertinent provisions of Section 6-129, and the rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract;
- 4) agree and affirm that it is a material term of this Contract that the Vendor will award the total dollar value of the M/WBE Participation Goals that are established on each individual Task Order issued pursuant to this Contract, unless a full waiver is obtained or such goals are modified by the Agency; and
- 5) agree and affirm, if awarded this Contract, to make all reasonable, good faith efforts to meet the M/WBE Participation Goals established on each individual Task Order issued pursuant to this Contract, or if a partial waiver is obtained or such goals are modified by the Agency, to meet the modified Participation Goals by soliciting and obtaining the participation of certified MBE and/or WBE firms.



3.

APT E-PIN #: 85016B0036

#### SCHEDULE OF PRICES


The Contractor shall perform all Work required, necessary, and proper for or incidental to completing the Work called for in each individual Job Order issued pursuant to this Contract using the Construction Task Catalog® and Technical Specifications incorporated herein with the following Adjustment Factors:

1. <u>Normal Working Hours:</u> Contractor shall perform any or all items of work during Normal Working Hours called for in the individual Job Orders in accordance with the Contract Documents for the unit price specified in the Unit Price Book (UPB) multiplied by the adjustment factor of:



(Specify to four (4) decimal places)

 Other Than Normal Working Hours: Contractor shall perform any or all items of work during Other Than Normal Working Hours called for in the individual Job Orders in accordance with the Contract Documents for the price specified in the Construction Task Catalog® multiplied by the adjustment factor. <u>Other Than Normal Working Hours Adjustment Factor</u> must be equal to or greater than the Normal Working Hours Adjustment Factor inserted above).




(Specify to four (4) decimal places)


3. <u>Non-Prepriced Adjustment Factor:</u> Contractor shall perform any or all items of work called for in the individual Job Orders in accordance with the Contract Documents for items not specified in the Construction Task Catalog® for the price as determined from Article 3B of the Contract multiplied by the Non-Pre-Priced Adjustment Factor of:



(Specify to four (4) decimal places)

4. <u>Award Criteria Figure:</u> Contractor shall include, in the space provided below, the Award Criteria Figure calculated on the page 18.





NOTICE - The attention of Bidders is particularly called to the fact that, unless the Bid is made in strict conformity with the directions given, it will be considered non-responsive and may be rejected.

APTE-PIN#: 85016B0036

#### **BASIS OF CONTRACT AWARD**

The following formula has been developed for the sole purpose of evaluating bids and awarding the Contract. Each bidder must complete the following Award Criteria Formula.

#### AWARD CRITERIA FORMULA

Line 1.	Normal Working Hours Adjustment Factor	1.0700
Line 2.	Multiply Line 1 by 0 .85	0.9095
Line 3.	Other Than Normal Working Hours Adjustment Factor	1.0800
Line 4.	Multiply Line 3 by 0.05	0.0540
Line 5.	Non-Prepriced Adjustment Factor	1.1500
Line 6.	Multiply Line 5 by 0.10	0.1150
Line 7.	Summation of lines 2, 4 and 6	1.0785
7		(Award Figure)

The bidder shall complete the Award Criteria Formula and transfer the final Award Criteria Figure to the space provided on the Schedule of Prices. A contract will be awarded to the responsive and responsible bidder with the lowest Award Criteria Figure subject to the limitations appearing in the Contract Documents. The City reserves the right to revise all arithmetic errors in calculations for correctness.

APT E-PIN #: 85016B0036

#### **BIDDER'S SIGNATURE AND AFFIDAVIT**

<u>WARNING!</u> If M/WBE goals have been established for this Contract, you MUST complete and submit the Affirmations on the 2nd page of the Subcontractor Utilization Plan (or a preapproved waiver) at the time you submit your bid. Failure to comply will result in the rejection of your bid.

Arcadia Electrical Co., Inc. Bidder: By: Stephen Gianotti President (Signature of Partner or corporate officer)

Attest: (Corporate Seal) Secretary of Corporate Bidder

Affidavit on the following page should be subscribed and sworn to before a Notary Public

APT E-**PIN #:** 

85016B0036

#### **AFFIRMATION**

The undersigned bidder affirms and declares that said bidder is not in arrears to the City of New York upon debt, contract or taxes and is not a defaulter, as surety or otherwise, upon obligation to the City of New York, and has not been declared not responsible, or disqualified, by any agency of the City of New York, nor is there any proceeding pending relating to the responsibility or qualification of the bidder to receive public contracts except None

(If none, the bidder shall insert the word "None" in the space provided above.)

ity_	Ridg	lewood	State NY	Zip Code	11385
HE	CK ON	E BOX AND INC			11303
J	Α-	Individual or S SOCIAL SEC	Sole Proprietorship* URITY NUMBER	· ·	
		"************************************	- #		
ſ	В-	Partnership, J EMPLOYER I	oint Venture or other unincorpo DENTIFICATION NUMBER	rated organization	
		internet all'ho ao aola tao a la	jerten v B		
p	<b>C</b> -	Corporation EMPLOYER II	DENTIFICATION NUMBER		
		112958700	•		÷.
	X	19 auit	,Stephen Gianotti	• · · · · · · · · · · · · · · · · · · ·	
	Signal	lure			
	Presi	ident			

This affirmation must be signed by an officer or duly authorized representative.

\*Under the Federal Privacy Act the furnishing of Social Security Numbers by bidders on City contracts is voluntary. Failure to provide a Social Security Number will not result in a bidder's disqualification. Social Security Numbers will be used to identify bidders, proposers or vendors to ensure their compliance with laws, to assist the City in enforcement of laws, as well as to provide the City a means of identifying of businesses which seek City contracts.

> **JACQUELINE LUDEMANN** Notary Public, State of New York Commission No. 01LU6193834 Qualified in Queens County Commission Expires Oct. 14, 20

Jacqueline hudeman

# SCHEDULE B – M/WBE Participation Requirements for Master Service Agreements That Will Require Individually Registered Task Orders

### Part I: M/WBE Participation Goals

Part I to be completed by contracting agency

Con	tract	Oven	view	

APT E- Pin # Project Title/ Agency	Various	FMS Project ID#: JOCS DDC			,			
PIN #	Job Order Contract					· ·	<u> </u>	
Bid/Proposal Response Date	WEDNESDAY, NO	VEMBEI	R 18, 2015	**************************************				
<b>Contracting Agency</b>	Department of Design an			<u> </u>		<del>،</del>		
Agency Address	30-30 Thomas Ave	City	_Long Islar	nđ	State		Zin Onda	
Contact Person	Donna Pope		Title				Zip Code	e and a second second second
Telephone #	(718) 391-1556	· · · · · · · · · · · · · · · · · · ·	Email		ide nye go		innaci Oppol	tunity
Project Description (ette	ch additional pages if necessary)		a haana haan	and Manters of course				

**JOC's Contracts** 

M/WBE Participation Requirements for Construction, Professional and Standard Services Master Services Agreements That Will Require Individually Registered Task Orders

The Master Services Agreement awarded pursuant to this solicitation is subject to Minority and Women-Owned Business Enterprises (M/WBE) participation requirements established in Section 6-129 of the New York City Administrative Code. Depending on the scope of work and the availability of M/WBEs to perform such work, agencies may set M/WBE participation goals on each individual task order issued pursuant to such agreement. If M/WBE participation goals are established for an individual task order, Prime Contractors will be required to submit a completed Schedule B – M/WBE Utilization Plan unless a full waiver is obtained. If Prime contractors submit a Schedule B, they will be required to fulfill the M/WBE participation goals on each individual task order, except to the extent that a full or partial waiver is obtained or such goals are modified by the agency. Please refer to the Notice for Prospective Contractors for more information.

Prime Contract Industry <u>CONSTRUCTION</u>

APT E-11-2958700 85016B0036 Tax ID #: PIN #: SCHEDULE B - Part II: Subcontractor Participation Plan Section I: Prime Contractor Contact Information Tax ID # 11-2958700 FMS Vendor ID # 0001546831 **Business** Name Arcadia Electrical Co., Inc. **Gregory Choquette** Contact Person Address 1005 Wyckoff Avenue Ridgewood NY 11385 Telephone # gc@arcadiaelectrical.com Email 718-418-0106 Section II: General Contract Information Enter brief description of all the type(s) of subcontracts for all/any services you plan on subcontracting if awarded this contract. Use additional sheets if necessary. 2 3 Unknown at time of bic 9 Scopes of Subcontract 10 Work 11 12 13 14. 15. 16. 17. Section V: Vendor Certification and Required Affirmations

#### Thereby:

1) acknowledge my understanding of the M/WBE participation requirements as set forth herein and the pertinent provisions of Section 6-129 of the Administrative Code of the City of New York ("Section 6-129"), and the rules promutgated thereunder;

2) affirm that the information supplied in support of this Subcontractor Participation Plan is true and correct:
3) agree, if awarded this Contract, to comply with the MAVBE participation requirements of this Contract as established on each individual Task Order, the pertinent provisions of Section 6-129, and the rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract:
4) agree and affirm that it is a material term of this Contract that the Vendor will award to certified MBEs and/or WBEs the total dollar value of the MAWBE Participation Goals that are established on each individual Task.

Agency; and 5) agree and affirm, if awarded this Contract, to make all reasonable, good faithefforts to meet the M/WB/E

Participation Goals established on each individual Task Order issued pursuant to this Contract, or If a partial waiver is obtained or such goals are modified by the Agency, to meet the modified Participation Goalsby soliciting and obtaining the participation of certified MBE and/or WBE firms.

Signature	Date	11/13/15	
Print Name Stephen Gianotti	Title	President	

#### **PLA PROJECT**

#### ATTACHMENT 1 – BID INFORMATION <u>PROJECT ID:</u> JOCS\_DDC

#### **DESCRIPTION AND LOCATION OF WORK:**

Job Order Contracts for Electric/Plumbing/HVAC - Agency Wide JOC2013E-1 DDC PIN 8502016RQ0006C / E-PIN: 85016B0035 JOC2013E-2 DDC PIN 8502016RQ0007C / E-PIN: 85016B0036 JOC2013E-3 DDC PIN 8502016RQ0008C / E-PIN: 85016B0037 JOC2013P-1 DDC PIN 8502016RQ0009C / E-PIN: 85016B0038 JOC2013P-2 DCC PIN 8502016RQ0010C / E-PIN: 85016B0039 JOC2013H-1 DDC PIN 8502016RQ0011C / E-PIN: 85016B0040 JOC2013H-2 DDC PIN 8502016RQ0012C / E-PIN: 85016B0041 JOC2013H-3 DDC PIN 8502016RQ0013C / E-PIN: 85016B0042

#### **DOCUMENTS AVAILABLE AT:**

Department of Design and Construction, Contract Section 30-30 Thomson Avenue- First Floor, Long Island City, NY 11101

#### SUBMISSION OF BIDS BEFORE BID OPENING:

#### TIME TO SUBMIT: ON OR BEFORE WEDNESDAY, NOVEMBER 18, 2015 AT 2:00 P.M. BIDS MUST BE CLOCKED IN PRIOR TO BID OPENING.

#### PLACE TO SUBMIT:

Department of Design and Construction, Contract Section 30-30 Thomson Avenue-1<sup>st</sup> Floor Contract Unit, Long Island City, NY 11101

#### **BID OPENING:**

PLACE OF BID OPENING:	Department of Design and Construction, Contract Section, 1 <sup>st</sup> Floor Bid Room 30-30 Thomson Avenue Long Island City, NY 11101
DATE AND HOUR:	WEDNESDAY, NOVEMBER 18, 2015 AT 2:00 P.M.
	LATE BIDS WILL NOT BE ACCEPTED

#### **BID SECURITY:**

Bid Security, in the amount of \$15,000, shall be required for each General Construction, Plumbing, HVAC and Electrical bid submitted. Bid Security may be in the form of a certified check or bid bond.

#### PERFORMANCE AND PAYMENT SECURITY:

Performance and Payment Bonds will not be required at contract award. However, during the performance of the contract, the Contractor shall be required to provide Performance and Payment Bonds for each Job Order in excess of \$1,000,000 in an amount equal to 100% of the Job Order Price. Such security shall be in accordance with the requirements set forth in the Contract Documents. The City shall reimburse the Contractor the actual and reasonable cost of such security, with no mark-up for overhead and profit. The Contractor shall provide a copy of the cancelled check for the required security, as well as any other documentation required by the Commissioner.

#### AGENCY CONTACT PERSON:

Lorraine Holley, 30-30 Thomson Avenue, 1<sup>st</sup> Floor, Long Island City, NY 11101 <u>Telephone:</u> (718) 391-3170 or (718) 391-1016 <u>Fax:</u> (718) 391-2615

#### **Pre-Award Process**

The bidder is advised that as part of the pre-award review of its bid, it may be required to submit the information described in Sections (A) through (E) below. In the event the bidder fails to submit the required information within the specified time frame, its bid may be rejected as nonresponsive.

• Sections (A) through (E): If required, the bidder must submit the information described in Sections (A) through (E) below within five (5) business days following receipt of notification from DDC that it is among the low bidders. Such notification from DDC will be by facsimile or in writing and will specify the types of information which must be submitted.

(A) **Contractor's Bid Breakdown**: If required, the bidder must complete and submit the Contractor's Bid Breakdown Form described on page 21 of this Bid Booklet.

\*\*\*\*\*\*\*\*

- (B) **Project Reference Form:** If required, the bidder must complete and submit the Project Reference Form set forth on pages 28 through 30 of this Bid Booklet. The Project Reference Form consists of 3 parts: (1) Similar Contracts Completed by the Bidder, (2) Contracts Currently Under Construction by the Bidder, and (3) Pending Contracts Not Yet Started by the Bidder.
- (C) Copy of License: If required, the bidder must submit a copy of the license under which the bidder will be performing the work. Such license must clearly show the following: (1) Name of the Licensee, (2) License Number, and (3) Expiration date of the License. A copy of the license will be required from bidders for the following contracts: Plumbing Work, Electrical Work and Asbestos Abatement.
- (D) **Financial Information**: If required, the bidder must submit the financial information described below:
  - (1) Audited Financial Statements: Financial statements (Balance Sheet and Income Statement) of the entity submitting the bid, as audited by an independent auditor licensed to practice as a certified public accountant (CPA). Audited financial statements for the three most recent fiscal years must be submitted. Each such financial statement must include the auditor's standard report.

If the bidder does not have audited financial statements, it must submit an affidavit attesting to the fact that the bidder does not have such statements. In addition, the bidder must submit the following documentation covering the three most recent fiscal years: signed federal tax returns, unaudited financial statements, and a "certified review letter" from a certified public accountant (CPA) verifying the unaudited financial statements.

Unless the most recent audited or unaudited financial statement was issued within ninety (90) days, the bidder must submit interim financial information that includes data on financial position and results of operation (income data) for the current fiscal year. Such information may be summarized on a monthly or quarterly basis or at other intervals.

(2)

Schedule of Aged Accounts Receivable, including portion due within ninety (90) days.

(E) **Project Specific Information**: If required, the bidder must submit the project specific information described below:

- (1) Statement indicating the number of years of experience the bidder has had and in what type of construction.
- (2) Resumes of all key personnel to be involved in the project, including the proposed project superintendent.
- (3) List of significant pieces of equipment expected to be used for the contract, and whether such equipment is owned or leased.
- (4) Description of work expected to be subcontracted, and to what firms, if known.
- (5) List of key material suppliers.
- (6) Preliminary bar chart time schedule
- (7) Contractor's expected means of financing the project. This should be based on the
- assumption that the contractor is required to finance 2X average monthly billings throughout the contract period.
- (8) Any other issues the contractor sees as impacting his ability to complete the project according to the contract.

In addition to the information described in Sections (A) through (E) above, the bidder shall submit such additional information as the Commissioner may require, including without limitation, an explanation or justification for specific unit price items.

The bidder is further advised that it may be required to attend a pre-award meeting with DDC representatives. If such a meeting is convened, the bidder will be advised as to any additional material to be provided.

Page 34 of 37

#### OFFICE OF THE MAYOR BUREAU OF LABOR SERVICES CONTRACT CERTIFICATE

Description and Address of Proposed Contract:	Address				
Telephone Number:	Auuess				<del></del>
Name and Title of Signatory:					
Name and Title of Signatory:	Telephone Number:				
Contracting Agency or Owner: Project Number: Proposed Contract Amount: Description and Address of Proposed Contract: Names of Subcontractors in the amount of 750,000 or more on this contract (if not known at this time,					
Contracting Agency or Owner: Project Number: Proposed Contract Amount: Description and Address of Proposed Contract: Names of Subcontractors in the amount of 750,000 or more on this contract (if not known at this time,					Marris 11 (111
Project Number: Proposed Contract Amount: Description and Address of Proposed Contract: Names of Subcontractors in the amount of 750,000 or more on this contract (if not known at this time,		- ·			
Proposed Contract Amount: Description and Address of Proposed Contract: Names of Subcontractors in the amount of 750,000 or more on this contract (if not known at this time,	Contracting Agency or Owner:	•			
Proposed Contract Amount: Description and Address of Proposed Contract: Names of Subcontractors in the amount of 750,000 or more on this contract (if not known at this time,	Project Number:				
Description and Address of Proposed Contract:					
Names of Subcontractors in the amount of 750,000 or more on this contract (if not known at this time,					
	Names of Subcontractors in the amount of 750,00 state indicating that trades will be subcontracted):	00 or more on this c	contract (if not	known at this t	ime,
	Names of Subcontractors in the amount of 750,00 state indicating that trades will be subcontracted):	00 or more on this c	ontract (if not	known at this t	ime,

hereby affirm that I am authorized by the above-named contractor to certify that said contractor's proposed contract with the above-named owner or city agency is less than \$1,000,000. This affirmation is made in accordance with Executive Order No. 50 (1980) as amended and its implementing regulations.

Date

Signature

WILLFUL OR FRAUDULENT FALSIFICATION OF ANY DATA OR INFORMATION SUBMITTED HEREWITH MAY RESULT IN THE TERMINATION OF ANY CONTRACT BETWEEN THE CITY AND THE BIDDER OR CONTRACTOR AND BAR THE BIDDER OR CONTRACTOR FROM PARTICIPATION IN ANY CITY CONTRACT FOR A PERIOD OF UP TO THREE YEARS. FURTHER, SUCH FALSIFICATION MAY RESULT IN CRIMINAL PROSECUTION.

CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

Page 38

#### VENDEX COMPLIANCE

(A) <u>Vendex Fees</u>: Pursuant to Procurement Policy Board Rule 2-08(f)(2), the contractor will be charged a fee for the administration of the VENDEX system, including the Vendor Name Check process, if a Vendor Name Check review is required to be conducted by the Department of Investigation. The contractor shall also be required to pay the applicable required fees for any of its subcontractors for which Vendor Name Check reviews are required. The fee(s) will be deducted from payments made to the contractor under the contract. For contracts with an estimated value of less than or equal to \$1,000,000, the fee will be \$175 per Vendor Name Check review. For contracts with an estimated value of greater than \$1,000,000, the fee will be \$350 per Vendor Name Check review.

(B) <u>Confirmation of Vendex Compliance</u>: The Bidder shall submit this Confirmation of Vendex Compliance to the Department of Design and Construction, Contracts Section, 30-30 Thomson Avenue – First Floor, Long Island City, NY 11101.

Bid Information: The Bidder shall complete the bid information set forth below.

 Name of Bidder:
 Arcadia Electrical Co., Inc.

 Bidder's Address:
 1005 Wykcoff Avenue Ridgewood NY 11385\_\_\_\_\_\_

 Bidder's Telephone Number:
 718-418-0106

 Bidder's Fax Number:
 718-418-0425

 Date of Bid Opening:
 November 18,2015

 Project ID:
 JOC2013E-2

<u>Vendex Compliance</u>: To demonstrate compliance with Vendex requirements, the Bidder shall complete either Section (1) or Section (2) below, whichever applies.

(1) <u>Submission of Vendex Questionnaires to MOCS</u>: By signing in the space provided below, the Bidder certifies that as of the date specified below, the Bidder has submitted Vendex Questionnaires to the Mayor's Office of Contract Services, Attn: VENDEX, 253 Broadway, 9<sup>th</sup> Floor, New York, New York 10007.

Date of Submission:

By: \_

(Signature of Partner or corporate officer)

Print Name:

(2) <u>Submission of Certification of No Change to DDC:</u> By signing in the space provided below, the Bidder certifies that it has read the instructions in a "Vendor's Guide to Vendex" and that such instructions do not require the Bidder to submit Vendex Questionnaires. The Bidder has completed TWO ORIGINALS of the Certification of No Change set forth on the next page of this Bid Booklet.

By:

(Signature of Partner or corporate officer)

Print Name: Stephen Gianotti, President

Page 39

# **Certificate of No Change Form**



- Please fill in all the fields and DO NOT leave any field blank.
- Please submit two completed forms. Copies will not be accepted.
- Please send both copies to the agency that requested it, unless you are advised to send it directly to the Mayor's Office of Contract Services (MOCS).
- A materially false statement willfully or fraudulently made in connection with this certification, and/or the failure to conduct appropriate due diligence in verifying the information that is the subject of this certification, may result in rendering the submitting entity non-responsible for the purpose of contract award.
- A materially false statement willfully or fraudulently made in connection with this certification may subject the person making the false statement to criminal charges

Stephen Gianotti

Ι,

\_\_\_\_, being duly sworn, state that I have read

#### Enter Your Name

and understand all the items contained in the vendor questionnaire and any submission of change as identified on page one of this form and certify that as of this date, these items have not changed. I further certify that, to the best of my knowledge, information and belief, those answers are full, complete, and accurate; and that, to the best of my knowledge, information, and belief, those answers continue to be full, complete, and accurate.

n addition, I further certify on behalf of the submitting vendor that the information contained in the principal questionnaire(s) and any submission of change identified on page two of this form have not changed and have been verified and continue, to the best of my knowledge, to be full, complete and accurate.

I understand that the City of New York will rely on the information supplied in this certification as additional inducement to enter into a contract with the submitting entity.

### Vendor Questionnaire This section is required.

This refers to the vendor questionnaire(s) submitted for the vendor doing business with the City.

Name of Submitting Entity:Arcadia Electrical Co., Inc
Vendor's Address:1005 Wyckoff Avenue, Ridgewood, NY 11385
Vendor's EIN or TIN: <u>11-2958700</u> Requesting Agency: <u>NYC Department of Design &amp; Construction</u>
Are you submitting this Certification as a parent? (Please circle one) Yes
Signature date on the last full vendor questionnaire signed by the submitting vendor: <u>12/15/14</u>
Signature date on changed submission, if applicable, for the submitting vendor:
Mayor's Office of Contract Services

### **Principal Questionnaire**

This section refers to the most recent principal questionnaire submissions.



	Principal Name	Date of signature on last full Principal Questionnaire	Date(s) of signature on Changed Submission (if applicable)
1	Stephen Gianotti	12/15/14	
2			
3			
4			
5			
6			
	heck if additional changes were subn	nitted and attach a document with the	e date of additional submissions.

## **Certification** *This section is required.*

This form must be signed and notarized. Please complete this twice. Copies will not be accepted.

**Certified By:** Stephen Gianotti Name (Print) President Title Arcadia Electrical Co., Inc. Name of Submitting Entity 11/13/15 Signatur Date JACQUELINE LUDEMANN Notary Public, State of New York **Notarized By:** Commission No. 01LU6193834 Qualified in Queens County Commission Expires Oct. 14, 20. MADAN Public County License Issued License Number Sworn to before me on: 11/13/15 Date Mayor's Office of Contract Services

253 Broadway, 9th Floor New York, NY 10007 Phone: 212-788-0010 Fax: 212-788-0049

# **Certificate of No Change Form**



- Please fill in all the fields and DO NOT leave any field blank. ٠
- Please submit two completed forms. Copies will not be accepted.
- Please send both copies to the agency that requested it, unless you are advised to send it directly to the Mayor's Office of Contract Services (MOCS).
- A materially false statement willfully or fraudulently made in connection with this certification, and/or the failure to conduct appropriate due diligence in verifying the information that is the subject of this certification, may result in rendering the submitting entity non-responsible for the purpose of contract award.
- A materially false statement willfully or fraudulently made in connection with this certification • may subject the person making the false statement to criminal charges

Stephen Gianotti Ι,

being duly sworn, state that I have read

#### Enter Your Name

and understand all the items contained in the vendor questionnaire and any submission of change as identified on page one of this form and certify that as of this date, these items have not changed. I further certify that, to the best of my knowledge, information and belief, those answers are full, complete, and accurate; and that, to the best of my knowledge, information, and belief, those answers continue to be full, complete, and accurate.

In addition, I further certify on behalf of the submitting vendor that the information contained in the principal questionnaire(s) and any submission of change identified on page two of this form have not changed and have been verified and continue, to the best of my knowledge, to be full, complete and accurate.

I understand that the City of New York will rely on the information supplied in this certification as additional inducement to enter into a contract with the submitting entity.

## Vendor Questionnaire This section is required.

This refers to the vendor questionnaire(s) submitted for the vendor doing business with the City.

Name of Submitting Entity:
Vendor's Address:1005 Wyckoff Avenue, Ridgewood, NY 11385
Vendor's EIN or TIN: <u>11-2958700</u> Requesting Agency: <u>NYC Department of Design &amp; Construction</u>
Are you submitting this Certification as a parent? (Please circle one) Yes
Signature date on the last full vendor questionnaire signed by the submitting vendor:
Signature date on changed submission, if applicable, for the submitting vendor:
Mayor's Office of Contract Services 253 Broadway, 9th Floor New York, NY 10007

Phone: 212-788-0010 Fax: 212-788-0049

### **Principal Questionnaire**

This section refers to the most recent principal questionnaire submissions.



2

	Principal Name	Date of signature on last full Principal Questionnaire	Date(s) of signature on Changed Submission (if applicable)
1	Stephen Gianotti	12/15/14	
2			
3			
4			
5			
6			
Cr	neck if additional changes were subn	nitted and attach a document with the	date of additional submissions.

### Certification This section is required.

This form must be signed and notarized. Please complete this twice. Copies will not be accepted.

**Certified By:** Stephen Gianotti Name (Print) President Title Arcadia Electrical Co., Inc. Name of Submitting Entity 11/13/15 Signature Date JACQUELINE LUDEMANN Notary Public, State of New York Notarized By: Commission No. 01LU6193834 Qualified in Queens County Commission Expires Oct. 14, 20 AL CO AN CO otan Public County License Issued License Number Sworn to before me on: 11/13/15 Date Mayor's Office of Contract Services

Mayor's Office of Contract Services 253 Broadway, 9th Floor New York, NY 10007 Phone: 212-788-0010 Fax: 212-788-0049

#### IRAN DIVESTMENT ACT COMPLIANCE RIDER

#### FOR NEW YORK CITY CONTRACTORS

The Iran Divestment Act of 2012, effective as of April 12, 2012, is codified at State Finance Law ("SFL") §165-a and General Municipal Law ("GML") §103-g. The Iran Divestment Act, with certain exceptions, prohibits municipalities, including the City, from entering into contracts with persons engaged in investment activities in the energy sector of Iran. Pursuant to the terms set forth in SFL §165-a and GML §103-g, a person engages in investment activities in the energy sector of Iran.

- (a) The person provides goods or services of twenty million dollars or more in the energy sector of Iran, including a person that provides oil or liquefied natural gas tankers, or products used to construct or maintain pipelines used to transport oil or liquefied natural gas, for the energy sector of Iran; or
- (b) The person is a financial institution that extends twenty million dollars or more in credit to another person, for forty-five days or more, if that person will use the credit to provide goods or services in the energy sector in Iran and is identified on a list created pursuant to paragraph (b) of subdivision three of Section 165-a of the State Finance Law and maintained by the Commissioner of the Office of General Services.

A bid or proposal shall not be considered for award nor shall any award be made where the bidder or proposer fails to submit a signed and verified bidder's certification.



Each bidder or proposer must certify that it is not on the list of entities engaged in investment activities in Iran created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law. In any case where the bidder or proposer cannot certify that they are not on such list, the bidder or proposer shall so state and shall furnish with the bid or proposal a signed statement which sets forth in detail the reasons why such statement cannot be made. The City of New York may award a bid to a bidder who cannot make the certification on a case by case basis if.

- (1) The investment activities in Iran were made before the effective date of this section (i.e., April 12, 2012), the investment activities in Iran have not been expanded or renewed after the effective date of this section and the person has adopted, publicized and is implementing a formal plan to cease the investment activities in Iran and to refrain from engaging in any new investments in Iran; or
- (2) The City makes a determination that the goods or services are necessary for the City to perform its functions and that, absent such an exemption, the City would be unable to obtain the goods or services for which the contract is offered. Such determination shall be made in writing and shall be a public document.

CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

#### BIDDER'S CERTIFICATION OF COMPLIANCE WITH IRAN DIVESTMENT ACT

Pursuant to General Municipal Law §103-g, which generally prohibits the City from entering into contracts with persons engaged in investment activities in the energy sector of Iran, the bidder/proposer submits the following certification:

#### [Please Check One]

#### **BIDDER'S CERTIFICATION**

- By submission of this bid or proposal, each bidder/proposer and each person signing on behalf of any bidder/proposer certifies, and in the case of a joint bid each party thereto certifies as to its own organization, under penalty of perjury, that to the best of its knowledge and belief, that each bidder/proposer is not on the list created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law.
- I am unable to certify that my name and the name of the bidder/proposer does not appear on the list created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law. I have attached a signed statement setting forth in detail why I cannot so certify.

Dated:

Queens , New York

SIGNATURE

Stephen Gianotti PRINTED NAME

President

TITLE

Swarn to before me this day of Nov , 20 15

**'ublic** 

Dated:

JACQUELINE LUDEMANN Notary Public, State of New York Commission No. 01LU6193834 Qualified in Queens County Commission Expires Oct. 14, 20

# BID BOOKLET PART B

APT E-PIN #: \_\_\_\_ 85016B0036

#### BID BOND 1 FORM OF BID BOND

#### KNOW ALL MEN BY THESE PRESENTS. That we,

Arcadia Electrical Co., Inc., 1005 Wyckoff Avenue, Ridgewood, NY 11385

#### hereinafter referred to as the "Principal", and

Travelers Casualty and Surety Company of America, One Tower Square, Hartford, CT 06183

hereinafter referred to as the "Surety" are held and firmly bound to THE CITY OF NEW YORK, hereinafter referred to as the "CITY", or to its successors and assigns in the penal sum of \_\_\_\_\_\_

#### Fifteen Thousand and 00/100 Dollars

(\$<u>15,000.00</u>), Dollars lawful money of the United States, for the payment of which said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

Whereas, the Principal is about to submit (or has submitted) to the City the accompanying proposal, hereby made a part hereof, to enter into a contract in writing for

Job Order Contracts for Electric/Plumbing/HVAC - Agency Wide JOC2013E-2 DDC PIN 8502016RQ0007C / E-PIN: 85016B0036

#### Boroughs of Brooklyn and Staten Island

NOW, THEREFORE, the conditions of this obligation are such that if the Principal shall not withdraw said Proposal without the consent of the City for a period of forty-five (45) days after the opening of bids and in the event of acceptance of the Principal's Proposal by the City, if the Principal shall:

(a) Within ten (10) days after notification by the City, execute in quadruplicate and deliver to the City all the executed counterparts of the Contract in the form set forth in the Contract Documents, in accordance with the proposal as accepted, and

(b) Furnish a performance bond and separate payment bond, as may be required by the City, for the faithful performance and proper fulfillment of such Contract, which bonds shall be satisfactory in all respects to the City and shall be executed by good and sufficient sureties, and

(c) In all respects perform the agreement created by the acceptance of said Proposal as provided in the Information for Bidders, bound herewith and made a part hereof, or if the City shall reject the aforesaid Proposal, then this obligation shall be null and void; otherwise to remain in full force and effect.

#### BID BOND 2

In the event that the Proposal of the Principal shall be accepted and the Contract be awarded to him the Surety hereunder agrees subject only to the payment by the Principal of the premium therefore, if requested by the City, to write the aforementioned performance and payment bonds in the form set forth in the Contract Documents.

It is expressly understood and agreed that the liability of the Surety for any and all claims hereunder shall in no event exceed the penal amount of this obligation as herein stated.

There shall be no liability under this bond if, in the event of the acceptance of the Principal's Proposal by the City, either a performance bond or payment bond, or both, shall not be required by the City on or before the 30th day after the date on which the City signs the Contract.

The surety, for the value received, hereby stipulates and agrees that the obligations of the Surety and its bond shall in no way be impaired or affected by any postponements of the date upon which the City will receive or open bids, or by any extensions of the time within which the City may accept the Principal's Proposal, or by any waiver by the City of any of the requirements of the Information for Bidders, and the Surety hereby waives notice of any such postponements, extensions, or waivers.

IN WITNESS WHEREOF, the Principal and the Surety have hereunto set their hands and seals and such of them as are corporations have caused their corporate seals to be hereto affixed and these presents to be signed by their proper officers the <u>13th</u> day of <u>November</u>, <u>2015</u>.

(Seal)


(Seal)

Arcadia Electrical Co., Inc.	(L.S.)
Principal	
ву:/Х/сши	
Stephen Gianotti, President	
Λ	
Travelers Casualty and Surety Company of America	
Surety	
By: Ruslin Lumbi	
Susan Lupski, Attorney-In-Fact	

Tax ID #:	11-2958700	÷			APT E- PIN #:	85016B0036
			BID	BOND 3		
		<b></b>				
		OWLEDGI	MENT OF PE	RINCIPAL, IF	A CORPORATIC	<u>DN</u>
State of		County of _	Queens		SS:	
On this _		ay of _	to me know	who heing	2015, before	e me personally can n, did depose and say th
he resides a	at 216-15 31st Rd.					
that he is the	e		of Arc	adia Electrical	Co., Inc.	e knows the seal of sa
corporation,	that one of the sea said corporation, ar	en anixed	to said instri	iment is such	seal that it was	so affixed by order of t
	J, Nota		UDEMANN <sup>B</sup> of New York	10.0	aulle 1	An Anna in
	Con	mission No. 0	LU6193824	A M	otary Public	and
	Commi	alified in Quee sion Expires (	ns County //		-	
				RINCIPAL, IF	A PARTNERSHI	2
State of	C	ounty of		: S	is:	
On this	day	of			, before m	ne personally appeare
of						f the members of the firr the foregoing instrumen
and he ackno	owledged to me that	the execu	ted the same	as and for th	e act and deed o	f said firm.
					<i>.</i> .	
				No	tary Public	
	ACKN	OWI EDGN				
State of		of		St	S: before m	e personally appeared
		1	lo me knowr	) and known '	<u>n ma in na ina i</u>	nofenn daerrihad in and
ho executed	the foregoing instr	ument and	acknowledg	ed that he exc	ecuted the same.	
				Not	ary Public	
	AFFIX ACKN	OWLEDG	MENTS AND	D JUSTIFICAT	TION OF SURET	IES
	•					

.

1 · · · ·



#### ACKNOWLEDGMENT OF SURETY COMPANY

STATE OF ... New. York COUNTY OF ... Nassau } ss

 On this
 November 13, 2015

 On this
 Susan Lupski

 to me known, who, being by me duly sworn, did depose and say; that he/she resides in Nassau County

 Nassau County
 State of ... New York....., that he/she is the Attorney-In-Fact of the Travelers Casualty and Surety Company of America

 Travelers Casualty and Surety Company of America
 the corporation described in which executed the

above instrument; that he/she knows the seal of said corporation; that the seal affixed to said instrument is such corporate seal; that is was so affixed by the Board of Directors of said corporation; and that he/she signed his/her name thereto by like order; and the affiant did further depose and say that the Superintendent of insurance of the State of New York, has, pursuant to Section 1111 of the Insurance Law of the State of New York, issued to Travelers. Casualty and Surety Company of America... (Surety) his/her certificate of qualification evidencing the qualification of said Company and its sufficiency under any law of the State of New York as surety and guarantor, and the propriety of accepting and approving it as such; and that such certificate has not been revoked.

VI

**Notary Public** 

NY acknowledgement

LAURAJEAN MURTAGH Notary Public, State of New York No. 01MU6319758 Qualified in Nassau County Commission Expires 02/23/2019

#### TRAVELERS CASUALTY AND SURETY COMPANY OF AMERICA

#### HARTFORD, CONNECTICUT 06183

#### FINANCIAL STATEMENT AS OF DECEMBER 31, 2014

CAPITAL STOCK \$ 6,480,000

ASSETS		LIABILITIES & SURPLUS	
CASH AND INVESTED CASH BONDS STOCK6 INVESTMENT INCOME DUE AND ACURUED OTHER INVESTED ASSETS PREMIUM BALANCES NET DEFERRED TAX ASSET REINSURANCE RECOVERABLE SECURITIES LENDING REINVESTED COLLATERAL ASSETS RECEIVABLES FROM PARENT, SUBSIDIARIES AND AFFILIATES OTHER ASSETS	\$ 127,187,283 3,411,436,937 326,931,878 45,277,103 4,019,416 209,982,904 62,639,084 17,397,751 6,224,694 9,057,199 3,078,655	UNEARNED PREMIUMS LOSSES LOSS ADJUSTMENT EXPENSES COMMISSIONS TAXES, LICENSES AND FEES OTHER EXPENSES CURRENT FEDERAL AND FOREIGN INCOME TAXES REMITTANCES AND ITEMS NOT ALLOCATED AMOUNTS WITHHELD / RETAINED BY COMPANY FOR OTHERS RETROACTIVE REINSURANCE RESERVE ASSUMED POLICYHOLDER DIVIDENDS PROVISION FOR REINSURANCE ADVANCE PREMIUM PAYABLE FOR SECURITIES PAYABLE FOR SECURITIES PAYABLE FOR SECURITIES ESCHEAT LIABILITY OTHER ACCRUED EXPENSES AND LIABILITIES TOTAL LIABILITIES	\$ 855,349,712 G80,180,443 356,911,823 34,142,246 11,534,866 40,097,405 24,133,560 11,062,082 41,744,986 853,430 7,376,698 3,416,505 1,327,118 4,559,700 6,224,694 28,084,142 1,138,046 421,157 \$ 2,110,576,190
		CAPITAL STOCK PAID IN SURPLUS OTHER SURPLUS TOTAL SURPLUS TO POLICYHOLDERS	\$ 6,480,000 433,803,760 <u>1,674,373,715</u> \$ 2,114,657,475
TOTAL ASSETS	\$_4,225,233,665	TOTAL LIABILITIES & SURPLUS	\$ 4,225,233,665

S OF CONNECTICUT	)
COUNTY OF HARTFORD	) SS.
CITY OF HARTFORD	}

MICHAEL J. DOODY, BEING DULY SWORN, SAYS THAT HE IS SECOND VICE PRESIDENT, OF TRAVELERS CASUALTY AND SURETY COMPANY OF AMERICA, AND THAT TO THE BEST OF HIS KNOWLEDGE AND BELIEF, THE FOREGOING IS A TRUE AND CORRECT STATEMENT OF THE FINANCIAL CONDITION OF SAID COMPANY AS OF THE 31ST DAY OF DECEMBER, 2014.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 19TH DAY OF MARCH, 2015



a SECOND VICE PRESIDE

SUSAN M. WEISSLEDER Notary Public My Commission Expires November 30, 2017

NOTARY PUBLIC

### SAFETY QUESTIONNAIRE

The bidder must include, with its bid, all information requested on this Safety Questionnaire. Failure to provide a completed and signed Safety Questionnaire at the time of bid opening may result in disqualification of the bid as non-responsive.

### 1. Bidder Information:

Company Name: Arcadia Electrical Co., Inc.

DDC Project Number: JOC2013E-2

Company Size: \_\_\_\_\_ Ten (10) employees or less

X Greater than ten (10) employees

X Company has previously worked for DDC

### 2. Type(s) of Construction Work

TYPE OF WORK	LAST 3 YEARS	THIS PROJECT
General Building Construction		
Residential Building Construction		······
Nonresidential Building Construction		
Heavy Construction, except building		
Highway and Street Construction	. <u> </u>	
Heavy Construction, except highways		**************************************
Plumbing, Heating, HVAC	-	
Painting and Paper Hanging		
Electrical Work	X	×
Masonry, Stonework and Plastering		
Carpentry and Floor Work	and the second sec	
Roofing, Siding, and Sheet Metal		<del>antanan ina 1997 - 1997 - 1997 - 19</del> 9
Concrete Work	•••••••••••••••••••••••••••••••••••••••	
Specialty Trade Contracting		
Asbestos Abatement	·	
Other (specify)		

### 3. Experience Modification Rate:

The Experience Modification Rate (EMR) is a rating generated by the National Council of Compensation Insurance (NCCI). This rating is used to determine the contractor's premium for worker's compensation insurance. The contractor may obtain its EMR by contacting its insurance broker or the NCCI. If the contractor cannot obtain its EMR, it must submit a written explanation as to why.

The Contractor must indicate its intrastate and interstate EMR for the past three years. [Note: For contractors with less than three years of experience, the EMR will be considered to be 1.00].

YEAR	INTRASTATE RATE	INTERSTATE RATE
-	N/A Please See Attached	······································
	an a	
******************************	and the second	- Andrew Manager Miles St.

If the Intrastate and/or Interstate EMR for any of the past three years is greater than 1.00, the contractor must attach, to this questionnaire, a written explanation for the rating and identify what corrective action was taken to correct the situation resulting in that rating.

### 4. OSHA Information:

<u>N/A</u>

Contractor has received a willful violation issued by OSHA or New York City Department of Buildings (NYCDOB) within the last three years.

<u>\_\_\_\_N/A\_\_</u>

Contractor has had an incident requiring OSHA notification within 8 hours (i.e., fatality, or hospitalization of three or more employees).

The Occupational Safety and Health Act (OSHA) of 1970 requires employers with ten or more employees, on a yearly basis to complete and maintain on file the form entitled "Log of Work-related Injuries and Illnesses". This form is commonly referred to as the OSHA 300 Log (OSHA 200 Log for 2001 and earlier).

The OSHA 300 Log must be submitted for the last three years for contractors with more than ten employees.

The Contractor must indicate the total number of hours worked by its employees, as reflected in payroll records for the past three years.

The contractor must submit the incident Rate for Lost Time Injuries (the incident Rate) for the past three years. The incident Rate is calculated in accordance with the formula set forth below. For each given year, the total number of incidents is the total number of non-fatal injuries and illnesses reported on the OSHA 300 Log. The 200,000 hours represents the equivalent of 100 employees working forty hours a week, fifty weeks per year.

### Incident Rate =

Total Number of Incidents X 200,000 Total Number of Hours Worked by Employees

YEAR

### TOTAL NUMBERS OF HOURS WORKED BY EMPLOYEES

INCIDENT RATE

2014	149,543	6.69
2013	102,316	7.82
2012	97,174	4.12

If the contractor's incident Rate for any of the past three years is one point higher than the incident Rate for the type of construction it performs (listed below), the contractor must attach, to this questionnaire, a written explanation for the relatively high rate.

General Building Construction	8.5
Residential Building Construction	7.0
Nonresidential Building Construction	10.2
Heavy Construction, except building	8.7
Highway and Street Construction	9.7
Heavy Construction, except highways	8.3
Plumbing, Heating, HVAC	11.3
Painting and Paper Hanging	6.9
Electrical Work	9.5
Masonry, Stonework and Plastering	10.5
Carpentry and Floor Work	12.2
Roofing, Siding, and Sheet Metal	10.3
Concrete Work	8.6
Specialty Trade Contracting	8.6

### 5. Safety Performance on Previous DDC Project(s)

<u>N/A</u>

Contractor previously audited by the DDC Office of Site Safety.

DDC Project Number(s): \_\_\_\_

\_\_\_\_\_N/A\_\_\_\_Accident on previous DDC Project(s).

N/A Fatality or Life-altering Injury on DDC Project(s) within the last three years. [Examples of a life-altering injury include loss of limb, loss of a sense (e.g., sight, hearing), or loss of neurological function].

Date: 11/13/15

By: Signature of Owner, Partner, Corporate Officer)

Title: President

Page 32

	U.S. Postal Service				
	CERTIFIED MAIL RECEIPT				
	(Domestic Mail Only: No Useurance Coverage Provided)				
an a					
	I OFFICIAL USE				
	ŋ				
a di Antonio 🗖	Postmark				
	Return Receipt Fee (Endorsement Required)				
en de la construction de la constru La construction de la construction d	Bestricted Delivery Fee 4				
<b>1</b> <b>1</b>	Total Postage & Fees \$				
	Sent To				
CITY OF NEW	Street, Apt. No.;				
7	City, State, ZiP+4				
	· · · · · · · · · · · · · · · · · · ·				
	PS Form 3800, August 2006 Sec Reverse for Instructions				
<b>DIVISION OF LABOR</b>	RSERVICES				

## **CONSTRUCTION EMPLOYMENT REPORT**

### The City of New York Department of Small Business Services Division of Labor Services Contract Compliance Unit 110 William Street, New York, New York 10038 Phone: (212) 513 – 6323 Fax: (212) 618-8879 CONSTRUCTION EMPLOYMENT REPORT

### **GENERAL INFORMATION**

1.	Your contractual relationship in this contract is:	Prime contractor X Subcontractor
1a,	Are M/WBE goals attached to this project? Yes_	
2.	Please check one of the following if your firm wou City of New York as a:	Id like information on how to certify with the
	<ul> <li>Minority Owned Business Enterprise</li> <li>Women Owned Business Enterprise</li> <li>Disadvantaged Business Enterprise</li> </ul>	Locally Based Business Enterprise Emerging Business Enterprise
2a.	If you are certified as an MBE, WBE, LBE, EBE c certified with?	r DBE, what city/state agency are you Are you DBE certified? YesNo
3.	Please indicate if you would like assistance from S contracting opportunities: Yes_X_ No	
4.	is this project subject to a project labor agreement	Yes <u>x</u> No
5.	Are you a Union contractor? Yes X No withIBEW Local 3	
6. DAD	Are you a Veteran owned company? Yes No	
	TI: CONTRACTOR/SUBCONTRACTOR INFORMA	TION
7.	11-2958700	and was a second a s
	Employer Identification Number or Federal Tax I.D.	Email Address
8.	Arcadia Electrical Co., Inc.	
	Company Name	
9.	1005 Whickoff Avenue Ridgewood NV 44005	
<b>.</b>	<u>1005 Wyckoff Avenue, Ridgewood, NY 11385</u> Company Address and Zip Code	· · · · · · · · · · · · · · · · · · ·
10.	Stephen Gianotti	718-418-0106
	Chief Operating Officer	Telephone Number
11.		
• • •	Gregory Choquette Designated Equal Opportunity Compliance Officer	718-4180-0106
	(If same as Item #10, write "same")	Telephone Number
12.	Arcadia Electrical Co. Inc. Stanks. Ci.	
	Arcadia Electrical Co., Inc. Stephen Gianotti Name of Prime Contractor and Contact Person	
	(If same as Item #8, write "same")	

13,	Number of employees in your company: 97	
14	Contract information:	
	(a) <u>NYC DDC</u> Contracting Agency (City Agency)	(b) <u>NTE \$8,000,000.00</u> Contract Amount
	(c) <u>8502016RQ0007C</u> Procurement Identification Number (PIN)	(d) Contract Registration Number (CT#)
	(e) <u>Unknown</u> Projected Commencement Date	(f) Unknown Projected Completion Date
	(g) Description and location of proposed contract: Job_Order For Electric - Agencywide	

15. Has your firm been reviewed by the Division of Labor Services (DLS) within the past 36 months and issued a Certificate of Approval? Yes X No....

If yes, attach a copy of certificate.

16. Has DLS within the past month reviewed an Employment Report submission for your company and issued a Conditional Certificate of Approval? Yes <u>No X</u>

If yes, attach a copy of certificate.

NOTE: DLS WILL NOT ISSUE A CONTINUED CERTIFICATE OF APPROVAL IN CONNECTION WITH THIS CONTRACT UNLESS THE REQUIRED CORRECTIVE ACTIONS IN PRIOR CONDITIONAL CERTIFICATES OF APPROVAL HAVE BEEN TAKEN.

17. Has an Employment Report already been submitted for a different contract (not covered by this Employment Report) for which you have not yet received compliance certificate? Yes No X If yes,

Date submitted:	
Agency to which submitted:	
Name of Agency Person:	
Contract No:	
Telephone:	

18. Has your company in the past 36 months been audited by the United States Department of Labor, Office of Federal Contract Compliance Programs (OFCCP)? Yes\_\_\_\_ No\_X

.

If yes,

Page 2 Revised 8/13 FOR OFFICIAL USE ONLY: File No.

- (a) Name and address of OFCCP office.
- (b) Was a Certificate of Equal Employment Compliance issued within the past 36 months? Yes\_\_\_\_No\_\_\_\_

If yes, attach a copy of such certificate.

(c) Were any corrective actions required or agreed to? Yes\_\_\_\_ No\_\_\_\_

If yes, attach a copy of such requirements or agreements.

(d) Were any deficiencies found? Yes\_\_\_\_ No\_\_\_\_

If yes, attach a copy of such findings.

19. Is your company or its affiliates a member or members of an employers' trade association which is responsible for negotiating collective bargaining agreements (CBA) which affect construction site hiring? Yes X No.

If yes, attach a list of such associations and all applicable CBA's. IBEW Local #3

### PART II: DOCUMENTS REQUIRED

- 20. For the following policies or practices, attach the relevant documents (e.g., printed booklets, brochures, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a full explanation of the practices. See instructions.
  - Yes (a) Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)
  - Yes (b) Disability, life, other insurance coverage/description
  - Yes(c) Employee Policy/Handbook
  - Yes(d) Personnel Policy/Manual
  - Yes(e) Supervisor's Policy/Manual
  - Yes(f) Pension plan or 401k coverage/description for all management, nonunion and union employees, whether company or union administered
  - Yes(g) Collective bargaining agreement(s).
  - Yes(h) Employment Application(s)
  - Yes(i) Employee evaluation policy/form(s).
  - Yes(j) Does your firm have medical and/or non-medical (i.e. education, military, personal, pregnancy, child care) leave policy?

21. To comply with the Immigration Reform and Control Act of 1986 when and of whom does your firm require the completion of an I-9 Form?

(a) Prior to job offer	Yes <u>No x</u>
(b) After a conditional job offer	Yes No X
(c) After a job offer	Yes X No
(d) Within the first three days on the job	Yes X No
(e) To some applicants	Yes No X
(f) To all applicants	Yes No X
(g) To some employees	
(h) To all employees	
(h) To all employees	Yes No_X_ Yes_X_No

22. Explain where and how completed I-9 Forms, with their supportive documentation, are maintained and made accessible.

Each employees I-9 form are kept at our office located at 1005 Wyckoff Avenue, Ridgewood, NY 11385 and are kept in the employees indivdual file.

23. Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes X No\_\_\_\_\_ The medical exams are administered through the IBEW Local #3 not Arcadia Electrical Company, Inc.

If yes, is the medical examination given:

(a) Prior to a job offer	Yes No X
(b) After a conditional job offer	Yes X No
(c) After a job offer	Yes No X
(d) To all applicants	Yes No X
(d) To all applicants (e) Only to some applicants	Yes No X

If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations. We neither administer or retain any medical exam records that are administered by the IBEW Local #3.

24. Do you have a written equal employment opportunity (EEO) policy? Yes\_X\_ No\_\_\_\_

If yes, list the document(s) and page number(s) where these written policies are located. These polocies are provided through the IBEW Local 3 and are retained at their office.

25. Does the company have a current affirmative action plan(s) (AAP)

X\_Minorities and Women

- X\_Individuals with handicaps
  - Other. Please specify
- 26. Does your firm or collective bargaining agreement(s) have an internal grievance procedure with respect to EEO complaints? Yes X No\_\_\_\_

If yes, please attach a copy of this policy.

All polocies and procedures are retained at the IBEW Local 3 office.

If no, attach a report detailing your firm's unwritten procedure for handling EEO complaints.

27. Has any employee, within the past three years, filed a complaint pursuant to an internal grievance procedure or with any official of your firm with respect to equal employment opportunity? Yes\_\_\_\_No\_X

If yes, attach an internal complaint log. See instructions,

28. Has your firm, within the past three years, been named as a defendant (or respondent) in any administrative or judicial action where the complainant (plaintiff) alleged violation of any anti-discrimination or affirmative action laws? Yes No. X.

If yes, attach a log. See instructions.

29. Are there any jobs for which there are physical qualifications? Yes\_\_\_\_No X\_\_\_

If yes; list the job(s), submit a job description and state the reason(s) for the qualification(s).

30. Are there any jobs for which there are age, race, color, national origin, sex, creed, disability, marital status, sexual orientation, or citizenship gualifications? Yes No X

If yes, list the job(s), submit a job description and state the reason(s) for the qualification(s),



### SIGNATURE PAGE

I, (print name of authorized official signing) <u>Stephen Gianotti</u> hereby certify that the information submitted herewith is true and complete to the best of my knowledge and belief and submitted with the understanding that compliance with New York City's equal employment requirements, as contained in Chapter 56 of the City Charter, Executive Order No. 50 (1980), as amended, and the implementing Rules and Regulations, is a contractual obligation. I also agree on behalf of the company to submit a certified copy of payroll records to the Division of Labor Services on a monthly basis.

<u>Arcadia Electrical Co., Inc.</u> Contractor's Name

Jacqueline Ludemann	Adminaturation	
Name of person who prepared this Employment Report	Adminstrator Title	
Stephen Gianotti	President	. *
Name of official authorized to sign on behalf of the contractor	Title	
718-418-0106		
Telephone Number		
Signature of authorized official	11/17/15	
Alaria an antimitzed official	Date	, <u>, , , , , , , , , , , , , , , , , , </u>

If contractors are found to be underutilizing minorities and females in any given trade based on Chapter 56 Section 3H, the Division of Labor Services reserves the right to request the contractor's workforce data and to implement an employment program.

Contractors who fail to comply with the above mentioned requirements or are found to be in noncompliance may be subject to the withholding of final payment.

Willful or fraudulent falsifications of any data or information submitted herewith may result in the termination of the contract between the City and the bidder or contractor and in disapproval of future contracts for a period of up to five years. Further, such falsification may result in civil and/and or criminal prosecution.

To the extent permitted by law and consistent with the proper discharge of DLS' responsibilities under Charter Chapter 56 of the City Charter and Executive Order No. 50 (1980) and the implementing Rules and Regulations, all information provided by a contractor to DLS shall be confidential.

### Only original signatures accepted.

Sworn to before me this

\_\_\_\_ day of <u>November</u> 20 15

\_\_\_\_\_11/17/15

uler Kudeman Authorized Signature JACQUELINE LUDEMANN

17th

ACOULLINE LUDEMANN Notary Public, State of New York Commission No. 01LU6193834 Qualified in Queens County Commission Expires Oct. 14, 20

Page 6 Revised 8/13 FOR OFFICIAL USE ONLY: File No.



#215CY245

Maria Torres-Springer Commissioner

July 13, 2015

Mr. Stephen Gianotti Arcadia Electrical Company, Inc. 1005 Wyckoff Avenue Ridgewood, NY 11385

RE: NYC Department of Design & Construction Contract (DDC); Pin No. 8502015ED0001C; Contract No. E12-0037; Energy Conservation measures at 3 department of sanitation sites; Boroughs of the Brooklyn, Queens, and Staten Island; Contract Value: \$4,551,162.00; Continued Certificate of Approval.

Dear Mr. Gianotti:

Please be advised that Arcadia Electrical Company, Inc. has already received notice of its approval status for the three (3) year period indicated in the Department of Small Business Services/Division of Labor Services' (DLS') Certificate of Approval February 1, 2013 for File # 212CY300.

As your organization continues to meet the equal employment opportunity requirements of the City of New York, DLS approves the awarding of the above-referenced contract. This approval does not extend the initial 3 year approval (February 1, 2013 – January 31, 2016) referred to above.

If you have any questions, please call Mr. Jacques St. Cloud at (212) 513-9233 or by email <u>JSt.Cloud@sbs.nyc.gov</u>.

Very truly yours,

Helen Wilson Assistant Commissioner Division of Labor Services

cc: Lorraine Holley (DDC) Jacques St. Cloud File

> 110 William Street, New York, NY 10038 Tel 212.513.6300 \*Fax 212.618.8991\*TDD 212.513.6306 WWW.nyc.gov/sbs

# FORM A.

# CONTRACT BID INFORMATION: USE OF SUBCONTRACTORS/TRADES

- Unknown Do you plan to subcontractor work on this contract? Yes No <del>. .</del>
  - If yes, complete the chart below. N

NOTE: All proposed subcontractors with a subcontract in excess of \$750,000 must complete an Employment Report for review and

SI IRCONTRACTORI IS

	÷					
SUBCONTRACTOR						
PERFORMED BY SUBCONTRACTOR						
LETTERS BELOW)						
	LETTERS BELOW) SUBCONTRACTOR SUBCONTRACTOR SUBCONTRACTOR	LETTERS BELOW)	LETTERS BELOW) SUBCONTRACTOR SUBCONTRACTOR SUBCONTRACTOR	LETTERS BELOW) BY LETTERS BELOW) SUBCONTRACTOR SUBCONTRACTOR SUBCONTRACTOR	LETTERS BELOW) PERFORMED BY USE BY US	LETTERS BELOW) BY LETTERS BELOW) SUBCONTRACTOR SUBCONTRACTOR SUBCONTRACTOR

\*If subcontractor is presently unknown, please enter the trade (craft name).

OWNERSHIP CODES

- W: White
- B: Black H: Hispanic
- A: Asian N: Native American F: Female

Revised 8/13 FOR OFFICIAL USE ONLY: File No.\_ Page 8

FORM B: PROJECTED WORKFORCE

Unknown at time of bid as it is a Job Order Contract TRADE CLASSIFICATION CODES

(J) Journeylevel Workers (H) Helper (TOT) Total by Column


(A) Apprentice (TRN) Trainee

For each trade to be engaged by your company for this project, enter the projected workforce for Males and Females by trade classification on the charts below.

Trade:			M	MALES					FEMALES			
Liectrical		(1) White	Black (2)	(3)	(4)	(2)	(6) White	(7) Black	(8)	(6)	(10)	
Local 3		Non Hisp.	Non Hisp,	Hisp.	Asian	Native Amer.	Non Hisp.	Non Hisp.	Hisp.	Aslan	Native Amer.	
Total (Col, #1-10):	<u>,</u>							eleeilanginging				
Total Minority, Male & Female	I											
(00. #2,3,4,5,7,8,9, & 10):	¥											
Total Female (Col. #6 – 10):	TRN											
	тот						- - -					
,	-											
What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?	ces for you	projected	hires (i.e.	, unions,	governme	nt employm	ient office, job	tap center	, commun	ity outread	c(ha	
IBEW Local 3										i	×	

Revised 8-13 FOR OFFICIAL USE ONLY: File No.\_ Page 9

FORM B: PROJECTED WORKFORCE



Page 10 Revised 8/13 FOR OFFICIAL USE ONLY: File No.\_\_\_

FORM C: CURRENT WORKFORCE

TRADE CLASSIFICATION CODES

(J) Journeylevel Workers (H) Helper (TOT) Total by Column

(A) Apprentice (TRN) Trainee

For each trade currently engaged by your company for all work performed in New York City, enter the current workforce for Males and Females by trade classification on the charts below.

Trade:			2	MALES	,				FEMAI ES			
Electrical		(1) White	(2) Black	(2)	(4)	(2)	(9)		(8)	(6)	(10)	
Union Affiliation, if applicable IBEW Local 3		Non Hisp.	Non Hisp.	Hisp.	Asian	Native Amer.	vville Non Hisp.	Diack Non Hisp.	Hisp.	Asian	Native Amer.	
Total (Col. #1-10): 76	<b>.</b>	40	2	9	2							
Total Minority, Male & Female	I					<u>.</u>		• • • •				
(001. #4.3,4,3,7,0,3, & 10): 31	A	LC,	c.	5	-			-				
Total Female (Col. #6 – 10); 2	TRN		>	)	-			-	-			
:	TOT	45	10	11	œ	0	0	-		c	c	
	•											


What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?

 $\hat{a}$ 

Revised 8/13 Page 11

FOR OFFICIAL USE ONLY: File No.

FORM C: CURRENT WORKFORCE



Page 12 Revised 8:13 FOR OFFICIAL USE ONLY: File No.\_\_



RRY VAN ARSDALE JR.

. GERALD FINKEL airman, Joint Industry Board he Electrical Industry

BERT McCORMICK, JR.

'O V. MUNDO unsei

ecutive Committee RO J. LUPO alman ISTINE DeNAPOLI s-Chairperson A GRUNTHER sasurer SEPH BARBARO oretary

)BERT AMABILE MINISHI CAULO ITHEWT CAULO HN EREMITA AN S. FISHBONE ITHONY E. MANN HN MANNINO HN MEDINA NDRA MILAD-GIBSON M PACE EX SAMILENKO IL SOKOLOFF IRRY SULLIVAN JDY WEISSBERG

LIX HIRSCH wirmen Emeritüs

### ELECTRICAL EMPLOYERS SELF INSURANCE SAFETY PLAN 158-11 HARRY VAN ARSDALE JR. AVENUE • FLUSHING, N.Y. 11365 TEL: (718) 591-2800 • FAX: (718) 591-0533

March 20, 2015

JEAN L'ALLIER Director

Arcadia Electrical Co., Inc. 1005 Wyckoff Ave. Ridgewood, NY 11385

> Re: Arcadia Electrical Co., Inc. Effective: 01/01/09 Policy #: 148

### To Whom It May Concern:

This letter will serve as confirmation that the above referenced company is a participant in Electrical Employers Self Insurance Safety Plan. This Plan provides both workers' compensation and disability coverage in accordance with the statutory requirements of New York State.

As a participant in this self-insured group plan, the firm is afforded, in addition to the usual worker's compensation insurance coverage "A", the benefit of unlimited coverage under coverage "B", employer's liability.

Very truly yours,

L'Allier

Jean L'Allier Director JL:dc

### SAFETY IS NO ACCIDENT



RY VAN ARSDALE JR. Ider

GERALD FINKEL rman, Joint Industry Board e Electrical Industry

ERT McCORMICK, JR. ty Director

) V. MUNDO Isei

cutive Committee D.J. LUPO irman STINE DeNAPOLI -Chairperson GRUNTHER isurer EPH BARBARO refary

JERT AMABILE LAS BHIRO HONY CAULO IN EREMITA N S. FISHBONE HONY E. MANN IN MANNINO IN MEDINA IDRA MILAD-GIBSON A PACE X SAMILENKO .SOKOLOFF IRY SULLIVAN Y WEISSBERG

IX HIRSCH Irman Emeritus

5/14

ELECTRICAL EMPLOYERS SELF INSURANCE SAFETY PLAN 158-11 HARRY VAN ARSDALE JR. AVENUE • FLUSHING, N.Y. 11365 TEL: (718) 591-2800 • FAX: (718) 591-0533

> JEAN L'ALLIER Director

March 20, 2015

Arcadia Electrical Co., Inc. 1005 Wyckoff Ave. Ridgewood, NY 11385

To Whom It May Concern:

Arcadia Electrical Co., Inc. is insured by Electrical Employers Self Insurance Safety Plan for Workers' Compensation and Disability, and has been since 01/01/09.

Electrical Employers Self Insurance Safety Plan does not and never has Experienced Rated any of its affiliated Electrical Contractors. Premiums are based on a flat rate exclusively.

Very truly yours,

Jean L'Allier Director

JL:dc

SAFETY IS NO ACCIDENT

PROJECT REFERENCES – SIMILAR CONTRACTS COMPLETED BY THE BIDDER Ā.

List all contracts substantially completed within the last 4 years similar to the contract being awarded, up to a maximum of 10, in descending order of date of substantial completion.

& LocationContract AmountDateArchitect/Engineer& LocationContract(\$000)Completed& Tel. No.TypeType	ting Prime \$374,893.99 6/1/2012 DSNY DDC Narendra Patel (718)391-1954	Subcontractor \$3,274,687.00 6/2015 NYC DOC 5	Prime \$1,110,700.00 8/12/14 NYC SCA Shaul - 718-472-8000	Ave Prime \$848,000.00 6/21/15 NYC SCA 848,000.00 5/21/15 Shaul - 718-472-8000 N/A	Prime \$1,922,417.52 6/2015 R	Prime \$123,768.84 5/27/2015 DSNY	Prime \$938,000.00 8/20/15 20/15
Project & Location	DSNY Lighting Varick Avenue Brooklyn NY	Rosie M Singer Center 1818 Hazen Street Queens, NY	PS 116 107-25 Wren Place Queens, NY	PS 156 229-02 137th Ave Queens,NY 11413	DOT Asphalt Plant 30-01Harper Street Queens NY	DSNY Manhattan Communinty Garage. 650 W. 57th St New York	PS 243K 1580 Dean St Brooklvn NY 11213

CITY OF NEW YORK DDC

BID BOOKLET December 2013

26

PROJECT REFERENCES - CONTRACTS CURRENTLY UNDER CONSTRUCTION BY THE BIDDER

B.

List all contracts currently under construction even if they are not similar to the contract being

Project & LocationContractContractSubcontracted to AmountUncompleted PortionDate Scheduled toCorner Reference & Reference & Refe				where the second s	ilar to the contract	t being awarded		
ademy         subcontractor         \$3.343.389.00         \$0.00         \$3,171,685.22         122017         DASNY           aldenoc         Prime         \$1.872,936.00         \$0.00         \$3,171,685.22         122017         DASNY           aldenoce         Prime         \$1.872,936.00         \$0.00         \$3,171,685.22         122017         DASNY           aldenoce         Prime         \$1.872,936.00         \$0.00         \$1.443,512.75         4/2016         DOHSLeroy James           als Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Servin Andalcio.           als Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Servin Andalcio.           brary         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Servin Andalcio.           brary         Prime         \$3,235,13         Not to Exceed         \$3,773,62         3/2016         NYPL           Prime         \$8,235,325,13         \$2,000,000.00         \$8,199,566.95         12/2016         Selvin Andalcio.           Prime-JOCS         \$67,143.00         \$0.00         \$19,868.55         3/2016         NYPL	ocation	Contract Type	Contract Amount (\$000)	Subcontracted to Others (\$000)	Uncompleted Portion (\$000)	Date Scheduled to Complete		Architect/En gineer Reference &
ace         Subcontractor         \$3,343,389.00         \$0.00         \$3,171,685.22         122017         DASNY           sidence         Prime         \$1,872,386.00         \$0.00         \$1,443,512.75         42016         DOHSLeroy James           las Blvd         Prime         \$1,872,386.00         \$0.00         \$1,443,512.75         42016         DOHSLeroy James           las Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Selwin Andalcio.           las Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Selwin Andalcio.           las Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Selwin Andalcio.           las Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Selwin Andalcio.           brany         Prime         \$3,737.62         3/2016         NYPL         2/2036.2936           Prime         \$8,235,325.13         \$2,000,000.00         \$8,199,566.95         12/2016         Selwin Andalcio.           Prime-JOCS         \$67,143.00         \$0.00         \$1,93,688.55         3/2016         NYPL	Academv							if different
bitence         Prime         \$1,872,936.00         \$0.00         \$1,443,512.75         4/2016         DOHSLeroy James           las Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         \$212-361-8166           las Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         \$61win Andalcio.           las Blvd         Prime         \$3,737.62         \$3,737.62         \$12016         \$81mandalcio.           brary         JoCCS         \$92,015.11         Not to Exceed         \$3,737.62         \$12016         NYPL           Prime         \$8,235,325.13         \$2,000,000.00         \$8,199,566.95         12/2016         \$elwin Andalcio.           Prime-JOCS         \$67,143.00         \$0.00         \$19,566.95         \$12/2016         \$elwin Andalcio.           Prime-JOCS         \$67,143.00         \$0.00         \$19,566.95         \$12/2016         \$elwin Andalcio.	Place		\$3,343,389.00	\$0.00	\$3,171,685.22	12/2017	DASNY	from owner WDF
Prime         \$1,872,936.00         \$0.00         \$1,43,512.75         4/2016         DOHSLeroy James           las Blvd         Prime         \$1,872,936.00         \$0.00         \$1,43,512.75         4/2016         DOHSLeroy James           las Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         NYCHA           brary         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         NYCHA           brary         Prime         \$3,737.62         \$3,737.62         \$1/2016         Setwin Andalcio.           Prime         \$92,015.11         Not to Exceed         \$3,737.62         \$1/2016         NYPL           Prime         \$8,235,325.13         \$2,000,000.00         \$8,199,566.95         \$12/2016         NYCHA           Prime         \$8,233,325.13         \$2,000,000.00         \$8,199,566.95         \$12/2016         Setwin Andalcio.           Prime-JOCS         \$67,143.00         \$0.00         \$19,868.55         \$12/2016         NYPL	esidence							914-629-9096
Ias Blvd         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Selwin Andalcio.           brary         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Selwin Andalcio.           brary         Prime         \$3,737.62         \$3,737.62         \$12016         NYPL           Prime         \$8,235,325.13         \$2,000,000.00         \$8,199,566.95         12/2016         Selwin Andalcio.           Prime-JOCS         \$67,143.00         \$0.00         \$19,566.95         12/2016         Selwin Andalcio.			\$1,872,936.00	<b>\$</b> 0.00	\$1,443,512.75	4/2016	DOHSLeroy James	N/A
Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         NYCHA           brary         Prime         \$3,550,199.66         799,479.00         \$2,189,61649         2/2016         Selwin Andalcio.           brary         Prime         \$32,015.11         Not to Exceed         \$3,737.62         3/2016         NYPL           Prime         \$8,235,325.13         \$2,000,000.00         \$8,199,566.95         12/2016         NYCHA           Prime-JOCS         \$67,143.00         \$00         \$19,566.95         3/2016         Selwin Andalcio.	Iolas Rlvd						0010-100-212	
brary JOCS         S92,015.11         Not to Exceed         \$3,737.62         3/2016         (212)306-2936           Prime         \$8,235,325.13         \$2,000,000.00         \$8,199,566.95         12/2016         NYCHA           Prime-JOCS         \$67,143.00         \$0.00         \$19,868.55         3/2016         NYPL			\$3,550,199.66	799,479.00	\$2,189,61649	2/2016	NYCHA Selwin Andalcio	NIA
JOUS         \$92,015.11         Not to Exceed         \$3,737.62         3/2016         NYPL           Prime         \$8,235,325.13         \$2,000,000.00         \$8,199,566.95         12/2016         NYCHA           Prime-JOCS         \$67,143.00         \$0.00         \$19,\$66.95         3/2016         NYCHA           Prime-JOCS         \$67,143.00         \$0.00         \$19,\$66.55         3/2016         NYPL	Library						(212)306-2936	A/VI
Prime         \$8,235,325.13         \$2,000,000.00         \$8,199,566.95         \$12/2016         NYCHA           Prime-JOCS         \$67,143.00         \$0.00         \$19,868.55         \$3/2016         \$NYPL		JOCS	\$92,015.11	Not to Exceed	\$3,737.62	3/2016		DDC
\$8,235,325.13         \$2,000,000.00         \$8,199,566.95         \$12/2016         NYCHA           Prime-JOCS         \$67,143.00         \$0.00         \$19,868.55         \$3/2016         \$12336-2936           NYPL         \$19,868.55         \$3/2016         NYPL		Prime						arios Kodriguez 18-391-1232
Prime-JOCS         \$67,143.00         \$0.00         \$19,868.55         3/2016         (212)306-2936           NYPL			\$8,235,325.13	\$2,000,000.00	\$8,199,566.95		NYCHA	
\$19,868.55 3/2016 NYPL		Prime-JOCS	\$67,143.00				251 Mai Andalcio. (212)306-2936	N/A
718-391-1069	<u>е</u>				\$19,868.55			Mario Garrovillas DDC
								718-391-1069

CITY OF NEW YORK DDC

27

BID BOOKLET December 2013 PROJECT REFERENCES - PENDING CONTRACTS NOT YET STARTED BY THE BIDDER ن

List all contracts awarded to or won by the bidder but not yet started.

		Contract			
Project & Location	Contract Type	Amount (\$000)	Date Scheduled to Start	Owner Reference & Tel No	Architect/Engineer Reference & Tel. No. if different from
Huguenot Library 830 Huguenot Ave. Staten Island NY	DDC-JOCS	\$77,780.19	2/2016	TAPL	DDC Hanan Benjamin 718.201.1106
Soundview Library 660 Soundview Ave Bronx NY	DDC-JOCS	\$73,019.11	2/2016	TAYN	DDC DDC Richard Prunesti 718-391-1011
Energy Conservation at 3 Dept. Sanitation Sites Queens, Brooklyn, Staten Island	Prime	\$4,354,715.00	3/2016	ANSQ	DDC Wadie Mikhail
Staten Island Technical High School 485 Clawson Street Staten Island NY	Prime	\$1,323,000.00	4/2016	NYC SCA Natalie Youssef	N/A
PreK 780K 7401 Fort Hamilton PKY Brooklyn NY	Subcontractor	\$1,405,000.00	3/2016	NYC SCA	Technico Construction Services, Inc. Ody Tsoutsos 118-037-3800
Ingersoll Houses 102 Monument Walk Brooklyn NY	Prime	\$5,325,804.61	2/2016	NYCHA Selwin Andalcio .(212)306-2936	N/A

CITY OF NEW YORK DDC

BID BOOKLET December 2013

28

.

APT E-PIN #:

# BID BOOKLET PART A

### Tax ID #: \_\_\_

APT E-PIN #: \_\_\_\_\_

### PROJECT ID: JOCS\_DDC

### CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF PUBLIC BUILDINGS

### **BID BOOKLET**

### TABLE OF CONTENTS

### PARTA

### PAGE

1.	Special Notice to Bidders	1
<b>2</b> .	M/WBE Utilization Plan	4
3.	Bid Form	13
4.	Affirmation	19
5.	Bidder's Identification of Subcontractors	20-R
<b>6.</b>	Bid Bond	25
7.	Attachment 1 - Bid Information	28

### PART B

8.	Safety Questionnaire	30
9.	Pre-award Process	33
10.	Project Reference Form	35
11.	Contract Certificate	38
12.	Confirmation of Vendex Compliance	39
13.	Attachment 2 – Construction Employment Report	42

APT E-PIN #:

### CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF PUBLIC BUILDINGS

### SPECIAL NOTICE TO BIDDERS

### **BID SUBMISSION REQUIREMENTS**

### THE BID SHALL CONSIST OF TWO (2) SEPARATE, SEALED ENVELOPES. THE DOCUMENTS THAT MUST BE COMPLETED AND INCLUDED IN EACH SEPARATE ENVELOPE ARE LISTED BELOW.

**BID ENVELOPE #1:** Bid Envelope #1 shall contain the following items:

Bid Form, including Affirmation

\_\_\_\_\_

- Bid Security (if required, see page 28)
- Schedule B: M/WBE Participation Requirements

BID ENVELOPE #2: Bid Envelope #2 shall contain ONLY the following item:

Bidder's Identification of Subcontractors

### FAILURE TO SUBMIT THE FOUR ITEMS ABOVE WILL RESULT IN THE DISQUALIFICATION OF THE BID

BID ENVELOPE #1: In addition to the items listed above, Bid Envelope #1 shall also contain the following items: DO NOT include the items listed below in Bid Envelope #2.

- Safety Questionnaire
- Construction Employment Report (if bid is \$1,000,000 or more)
- Contract Certificate (if bid is less than \$1,000,000)
- Confirmation of Vendex Compliance
- Bidder's Certification of Compliance with Iran Divestment Act
- Special Experience Requirements Qualification Form (if required, see pages 2, 3)
- Any Addenda issued prior to the receipt of bids

### FAILURE TO SUBMIT THE EIGHT ITEMS LISTED MAY RESULT IN THE DISQUALIFICATION OF THE BID

APT E-PIN #:

### SPECIAL EXPERIENCE REQUIREMENTS

Bidders are advised that the special experience requirements set forth below apply to each contract for which a check mark is indicated before the word "Yes". Compliance with these special experience requirements will be determined solely by the City. Failure to meet these special experience requirements will result in the rejection of the bid as non-responsive.

General Construction	XYES	NO
Plumbing Work	XYES	NO
HVAC Work	XYES	NO
Electrical Work	XYES	NO

- (A) <u>EXPERIENCE REQUIREMENTS FOR THE BIDDER (PRIME CONTRACTOR)</u>: The special experience requirements set forth below apply to the bidder. Compliance with such special experience requirements will be evaluated at the time of the bid.
  - (1) The bidder must, within the last five (5) consecutive years prior to the bid opening, have successfully completed in a timely fashion at least three (3) projects similar in scope and type to the required work.
- (B) <u>QUALIFICATION FORM</u>: For each project submitted to meet the experience requirements set forth above, the bidder must complete and submit with its bid the Qualification Form set forth in this Bid Booklet. All information on the Qualification Form must be provided.
- (C) <u>CONDITIONS</u>: The City may, in determining compliance with the special experience requirements set forth above, consider prior projects completed by principal(s) or other employees of the bidder while affiliated with another entity, subject to the conditions set forth below.
  - (1) Any principal or other employee on whose prior experience the bidder is relying to demonstrate compliance with this special experience requirement must have held the following: (a) a significant management role in the prior entity with which he/she was affiliated, and (b) a significant management role in the entity submitting the bid for a period of six months or from the inception of the bidding entity.
  - (2) The bidder may not rely on the experience of its principals or other employees to demonstrate compliance with any other requirements, including without limitation, financial requirements or requirements for a specified minimum amount of annual gross revenues.
- (D) <u>JOINT VENTURES</u>: In the event the bidder is a joint venture, at least one firm in the joint venture must meet the above described experience requirements.
- (E) <u>COMPLIANCE</u>: Compliance with the experience requirements set forth herein will be determined solely by the City. The bidder is advised that failure to meet the above described experience will result in the rejection of the bid as non-responsive.

Tax	ID	#:
-----	----	----

APT E-PIN #:

### **Qualification Form**

List previous projects completed to meet the special experience requirements for this contract. Please photocopy this form for submission of all required projects.

Name of Contractor:
Name of Project:
Location of Project:
Owner or Owner's representative (Architect or Engineer) who is familiar with the work performed:
Name:
Title: Phone Number:
Brief description of work completed:
Was the work was performed as a prime or a subcontractor:
Amount of Contract:
Date of Completion:
************************
Name of Contractor:
Name of Project:
Location of Project:
Owner or Owner's representative (Architect or Engineer) who is familiar with the work performed:
Name:
Title: Phone Number:
Brief description of work completed:
Was the work was performed as a prime or a subcontractor:
Amount of Contract:
Date of Completion:

APT E-PIN #:

### M/WBE PROGRAM M/WBE PARTICIPATION REQUIREMENTS

<u>M/WBE Program Requirements</u>: The requirements for the M/WBE Program are set forth on the following pages of this Bid Booklet, in the section entitled "Notice to All Prospective Contractors".

<u>Schedule B: M/WBE Participation Requirements</u>: Schedule B: M/WBE Participation Requirements is set forth in this Bid Booklet on the pages following the section entitled "Notice to All Prospective Contractors".

**Rejection of the Bid:** The bidder must complete Schedule B: M/WBE Participation Requirements (Part II) set forth in this Bid Booklet on the pages following the section entitled "Notice to All Prospective Contractors". A Schedule B submitted by the bidder which does not include the Vendor Certification and Required Affirmations (See Section V of Part II) will be deemed to be non-responsive. In the event that the City determines that the bidder has submitted a Schedule B where the Vendor Certification and Required Affirmations are completed but other aspects of the Schedule B are not complete, or contain a copy or computation error that is at odds with the Vendor Certification and Required Affirmations, the bidder will be notified by the Agency and will be given four (4) calendar days from receipt of notification to cure the specified deficiencies and return a completed Schedule B to the Agency. Failure to do so will result in a determination that the Bid is non-responsive. Receipt of notification is defined as the date notice is emailed or faxed (if the bidder has provided an email address or fax number), or no later than five (5) calendar days from the date of mailing or upon delivery, if delivered.

**Participation Goals:** Participation Goals will be established for each individual Task Order issued pursuant to this Contract. Prior to issuance and registration of the Task Order, the contractor will be required to submit a Schedule B: M/WBE Utilization Plan.

**Impact on LBE Requirements:** If for a particular Task Order, Participation Goals are established for the participation of M/WBEs, the contractor is not required to comply with the Locally Based Enterprise Program ("LBE"). The LBE Program is set forth in Article 67of the Contract.

APT E-PIN #:

### NOTICE TO ALL PROSPECTIVE CONTRACTORS

### PARTICIPATION BY MINORITY-OWNED AND WOMEN-OWNED BUSINESS ENTERPRISES IN CITY PROCUREMENT

### ARTICLE I. M/WBE PROGRAM

Local Law No. 129 of 2005 added and Local Law 1 of 2013 amended Section 6-129 of the Administrative Code of the City of New York (hereinafter "Section 6-129"). Section 6-129 establishes the program for participation in City procurement ("M/WBE Program") by minority- owned business enterprises ("MBEs") and women-owned business enterprises ("WBEs"), certified in accordance with Section 1304 of the New York City Charter. As stated in Section 6-129, the intent of the program is to address the impact of discrimination on the City's procurement process, and to promote the public interest in avoiding fraud and favoritism in the procurement process, increasing competition for City business, and lowering contract costs. The contract provisions contained herein are pursuant to Section 6-129, and the rules of the Department of Small Business Services ("DSBS") promulgated thereunder.

If this Contract is subject to the M/WBE Program established by Section 6-129, the specific requirements of MBE and/or WBE participation for this Contract are set forth in Schedule B of the Contract (entitled the "M/WBE Utilization Plan"), and are detailed below. The Contractor must comply with all applicable MBE and WBE requirements for this Contract.

All provisions of Section 6-129 are hereby incorporated in the Contract by reference and all terms used herein that are not defined herein shall have the meanings given such terms in Section 6-129. Article I, Part A, below, sets forth provisions related to the participation goals for construction, standard and professional services contracts. Article I, Part B, below, sets forth miscellaneous provisions related to the M/WBE Program.

### PART A

### PARTICIPATION GOALS FOR CONSTRUCTION, STANDARD AND PROFESSIONAL SERVICES CONTRACTS OR TASK ORDERS

1. The **MBE** and/or **WBE** Participation Goals established for this Contract or Task Orders issued pursuant to this Contract, ("Participation Goals"), as applicable, are set forth on Schedule B, Part I to this Contract (see Page 1, line 1 Total Participation Goals) or will be set forth on Schedule B, Part I to Task Orders issued pursuant to this Contract, as applicable.

The **Participation Goals** represent a percentage of the total dollar value of the Contract or Task Order, as applicable, that may be achieved by awarding subcontracts to firms certified with New York City Department of Small Business Services as MBEs and/or WBEs, and/or by crediting the participation of prime contractors and/or qualified joint ventures as provided in Section 3 below, unless the goals have been waived or modified by Agency in accordance with Section 6-129 and Part A, Sections 10 and 11 below, respectively.

2. If **Participation Goals** have been established for this Contract or Task Orders issued pursuant to this Contract, Contractor agrees or shall agree as a material term of the Contract that Contractor shall be subject to the **Participation Goals**, unless the goals are waived or modified by Agency in accordance with Section 6-129 and Part A, Sections 10 and 11 below, respectively.

3. If **Participation Goals** have been established for this Contract or Task Order issued pursuant to this Contract, a Contractor that is an MBE and/or WBE shall be permitted to count its own participation toward fulfillment of the relevant **Participation Goal**, provided that in accordance with Section 6-129 the value of Contractor's participation shall be contractor pays to direct subcontractors (as defined in Section 6-129(c)(13)), and provided further that a Contractor that is certified as both an MBE and a WBE may count its own participation either toward the goal for MBEs or the goal for MBEs.

Contractor that is a qualified joint venture (as defined in Section 6-129(c)(30)) shall be permitted to count a percentage of its own participation toward fulfillment of the relevant **Participation Goal**. In accordance with Section 6-129, the value of its own participation toward fulfillment of the relevant **Participation Goal**.

BID BOOKLET SEPTEMBER 2008

APT E-PIN #:

of Contractor's participation shall be determined by subtracting from the total value of the Contract or Task Order, as applicable, any amounts that Contractor pays to direct subcontractors, and then multiplying the remainder by the percentage to be applied to total profit to determine the amount to which an MBE or WBE is entitled pursuant to the joint venture agreement, provided that where a participant in a joint venture is certified as both an MBE and a WBE, such amount shall be counted either toward the goal for MBEs or the goal for WBEs, but not both.

A. If Participation Goals have been established for this Contract, a prospective contractor shall be required to 4. submit with its bid or proposal, as applicable, a completed Schedule B, M/WBE Utilization Plan, Part II (see Pages12) indicating: (a) whether the contractor is an MBE or WBE, or qualified joint venture; (b) the percentage of work it intends to award to direct subcontractors; and (c) in cases where the contractor intends to award direct subcontracts, a description of the type and dollar value of work designated for participation by MBEs and/or WBEs, and the time frames in which such work is scheduled to begin and end. In the event that this M/WBE Utilization Plan indicates that the bidder or proposer, as applicable, does not intend to meet the Participation Goals, the bid or proposal, as applicable, shall be deemed nonresponsive, unless Agency has granted the bidder or proposer, as applicable, a pre- award waiver of the Participation Goals in accordance with Section 6-129 and Part A, Section 10 below.

B. (i) If this Contract is for a master services agreement or other requirements type contract that will result in the issuance of Task Orders that will be individually registered ("Master Services Agreement") and is subject to MWBE Participation Goals, a prospective contractor shall be required to submit with its bid or proposal, as applicable, a completed Schedule B, M/WBE Participation Requirements for Master Services Agreements That Will Require Individually Registered Task Orders, Part II (page 12) indicating the prospective contractor's certification and required affirmations to make all reasonable good faith efforts to meet participation goals established on each individual Task Order issued pursuant to this Contract, or if a partial waiver is obtained or such goals are modified by the Agency, to meet the modified Participation Goals by soliciting and obtaining the participation of certified MBE and/or WBE firms. In the event that the Schedule B indicates that the bidder or proposer, as applicable, does not intend to meet the Participation Goals that may be established on Task Orders issued pursuant to this Contract, the bid or proposal, as applicable, shall be deemed nonresponsive.

(ii) Participation Goals on a Master Services Agreement will be established for individual Task Orders issued after the Master Services Agreement is awarded. If Participation Goals have been established on a Task Order, a contractor shall be required to submit a Schedule B - M/WBE Utilization Plan For Independently Registered Task Orders That Are Issued Pursuant to Master Services Agreements, Part II (see Pages 12) indicating: (a) whether the contractor is an MBE or WBE, or qualified joint venture; (b) the percentage of work it intends to award to direct subcontractors; and (c) in cases where the contractor intends to award direct subcontracts, a description of the type and dollar value of work designated for participation by MBEs and/or WBEs, and the time frames in which such work is scheduled to begin and end. The contractor must engage in good faith efforts to meet the Participation Goals as established for the Task Order unless Agency has granted the contractor a pre-award waiver of the Participation Goals in accordance with Section 6-129 and Part A, Section 10 below.

THE BIDDER/PROPOSER MUST COMPLETE THE SCHEDULE B INCLUDED HEREIN (SCHEDULE B, PART II). A SCHEDULE C. B SUBMITTED BY THE BIDDER/PROPOSER WHICH DOES NOT INCLUDE THE VENDOR CERTIFICATION AND REQUIRED AFFIRMATIONS (SEE SECTION V OF PART II) WILL BE DEEMED TO BE NON-RESPONSIVE, UNLESS A FULL WAIVER OF THE PARTICIPATION GOALS IS GRANTED (SCHEDULE B, PART III). IN THE EVENT THAT THE CITY DETERMINES THAT THE BIDDER/PROPOSER HAS SUBMITTED A SCHEDULE B WHERE THE VENDOR CERTIFICATION AND REQUIRED AFFIRMATIONS ARE COMPLETED BUT OTHER ASPECTS OF THE SCHEDULE B ARE NOT COMPLETE, OR CONTAIN A COPY OR COMPUTATION ERROR THAT IS AT ODDS WITH THE VENDOR CERTIFICATION AND AFFIRMATIONS, THE BIDDER/PROPOSER WILL BE NOTIFIED BY THE AGENCY AND WILL BE GIVEN FOUR (4) CALENDAR DAYS FROM RECEIPT OF NOTIFICATION TO CURE THE SPECIFIED DEFICIENCIES AND RETURN A COMPLETED SCHEDULE B TO THE AGENCY. FAILURE TO DO SO WILL RESULT IN A DETERMINATION THAT THE BID/PROPOSAL IS NON-RESPONSIVE. RECEIPT OF NOTIFICATION IS DEFINED AS THE DATE NOTICE IS E-MAILED OR FAXED (IF THE BIDDER/PROPOSER HAS PROVIDED AN E-MAIL ADDRESS OR FAX NUMBER), OR NO LATER THAN FIVE (5) CALENDAR DAYS FROM THE DATE OF MAILING OR UPON DELIVERY, IF DELIVERED.

Where an M/WBE Utilization Plan has been submitted, the Contractor shall, within 30 days of issuance by Agency 5. of a notice to proceed, submit a list of proposed persons or entities to which it intends to award subcontracts within the subsequent 12 months. In the case of multiyear contracts, such list shall also be submitted every year thereafter. The Agency may also require the Contractor to report periodically about the contracts awarded by its direct subcontractors to indirect subcontractors (as defined in Section 6-129(c)(22)). PLEASE NOTE: If this Contract is a public works project subject to GML §101(5) (i.e., a contract valued at or below \$3M for projects in New York City) or if the Contract is subject to a project labor agreement in accordance with Labor Law §222, and the bidder is required to identify at the time of bid submission its intended subcontractors for the Wicks trades (plumbing and gas fitting; steam heating, hot water heating, ventilating and air conditioning (HVAC); and electric wiring), the Contractor must identify all those to which it intends to award construction subcontracts for any portion of the Wicks trade work **BID BOOKLET** CITY OF NEW YORK

SEPTEMBER 2008



at the time of bid submission, regardless of what point in the life of the contract such subcontracts will occur. In identifying intended subcontractors in the bid submission, bidders may satisfy any Participation Goals established for this Contract by proposing one or more subcontractors that are MBEs and/or WBEs for any portion of the Wicks trade work. In the event that the Contractor's selection of a subcontractor is disapproved, the Contractor shall have a reasonable time to propose alternate subcontractors.

6. MBE and WBE firms must be certified by DSBS in order for the Contractor to credit such firms' participation toward the attainment of the **Participation Goals**. Such certification must occur prior to the firms' commencement of work. A list of MBE and WBE firms may be obtained from the DSBS website at www.nyc.gov/buycertified, by emailing DSBS at buyer@sbs.nyc.gov, by calling (212) 513-6356, or by visiting or writing DSBS at 110 William St., New York, New York, 10038, 7th floor. Eligible firms that have not yet been certified may contact DSBS in order to seek certification by visiting www.nyc.gov/getcertified, emailing MWBE@sbs.nyc.gov, or calling the DSBS certification helpline at (212) 513-6311. A firm that is certified as both an MBE and a WBE may be counted either toward the goal for MBEs or the goal for WBEs, but not both. No credit shall be given for participation by a graduate MBE or graduate WBE, as defined in Section 6-129(c)(20).

7. Where an **M/WBE** Utilization Plan has been submitted, the Contractor shall, with each voucher for payment, and/or periodically as Agency may require, submit statements, certified under penalty of perjury, which shall include, but not be limited to,: the total amount the Contractor paid to its direct subcontractors, and, where applicable pursuant to Section 6-129(j), the total amount direct subcontractors paid to indirect subcontractors; the names, addresses and contact numbers of each MBE or WBE hired as a subcontractor by the Contractor, and, where applicable, hired by any of the Contractor's direct subcontractors; and the dates and amounts paid to each MBE or WBE. The Contractor shall also submit, along with its voucher for final payment: the total amount it paid to subcontractors, and, where applicable pursuant to Section 6-129(j), the total amount its direct subcontractors paid directly to their indirect subcontractors; and a final list, certified under penalty of perjury, which shall include the name, address and contact information of each subcontractor that is an MBE or WBE, the work performed by, and the dates and amounts paid to each.

8. If payments made to, or work performed by, MBEs or WBEs are less than the amount specified in the Contractor's **M/WBE** Utilization Plan, Agency shall take appropriate action, in accordance with Section 6-129 and Article II below, unless the Contractor has obtained a modification of its **M/WBE** Utilization Plan in accordance with Section 6-129 and Part A, Section 11 below.

9. Where an **M/WBE** Utilization Plan has been submitted, and the Contractor requests a change order the value of which exceeds the greater of 10 percent of the Contract or Task Order, as applicable, or \$500,000, Agency shall review the scope of work for the Contract or Task Order, as applicable, and the scale and types of work involved in the change order, and determine whether the **Participation Goals** should be modified.

10. Pre-award waiver of the **Participation Goals**. (a) A bidder or proposer, or contractor with respect to a Task Order, may seek a pre-award full or partial waiver of the **Participation Goals** in accordance with Section 6-129, which requests that Agency change one or more **Participation Goals** on the grounds that the **Participation Goals** are unreasonable in light of the availability of certified firms to perform the services required, or by demonstrating that it has legitimate business reasons for proposing a lower level of subcontracting in its M/WBE Utilization Plan.

(b) To apply for a full or partial waiver of the **Participation Goals**, a bidder, proposer, or contractor, as applicable, must complete Part III (Page 12) of Schedule B and submit such request no later than seven (7) calendar days prior to the date and time the bids, proposals, or Task Orders are due, in writing to the Agency by email at <u>poped@ddc.nyc.gov</u> or via facsimile at (718) 391-1886. Bidders, proposers, or contractors, as applicable, who have submitted requests will receive an Agency response by no later than two (2) calendar days prior to the due date for bids, proposals, or Task Orders; provided, however, that if that date would fall on a weekend or holiday, an Agency response will be provided by close-of-business on the business day before such weekend or holiday date.

(c) If the Agency determines that the **Participation Goals** are unreasonable in light of the availability of certified firms to perform the services required, it shall revise the solicitation and extend the deadline for bids and proposals, or revise the Task Order, as applicable.

(d) Agency may grant a full or partial waiver of the **Participation Goals** to a bidder, proposer or contractor, as applicable, who demonstrates—before submission of the bid, proposal or Task Order, as applicable—that it has legitimate usiness reasons for proposing the level of subcontracting in its **M/WBE** Utilization Plan. In making its determination, Agency shall consider factors that shall include, but not be limited to, whether the bidder, proposer or contractor, as

applicable, has the capacity and the bona fide intention to perform the Contract without any subcontracting, or to perform the Contract without awarding the amount of subcontracts represented by the **Participation Goals**. In making such determination, Agency may consider whether the **M/WBE** Utilization Plan is consistent with past subcontracting practices of the bidder, proposer or contractor, as applicable, whether the bidder, proposer or contractor, as applicable, has made efforts to form a joint venture with a certified firm, and whether the bidder, proposer, or contractor, as applicable, has made good faith efforts to identify other portions of the Contract that it intends to subcontract.

11. Modification of M/WBE Utilization Plan. (a) A Contractor may request a modification of its M/WBE Utilization Plan after award of this Contract. PLEASE NOTE: If this Contract is a public works project subject to GML §101(5) (i.e., a contract valued at or below \$3M for projects in New York City) or if the Contract is subject to a project labor agreement in accordance with Labor Law §222, and the bidder is required to identify at the time of bid submission its intended subcontractors for the Wicks trades (plumbing and gas fitting; steam heating, hot water heating, ventilating and air conditioning (HVAC); and electric wiring), the Contractor may request a Modification of its M/WBE Utilization Plan as part of its bid submission. The Agency may grant a request for Modification of a Contractor's M/WBE Utilization Plan if it determines that the Contractor has established, with appropriate documentary and other evidence, that it made reasonable, good faith efforts to meet the Participation Goals. In making such determination, Agency shall consider evidence of the following efforts, as applicable, along with any other relevant factors:

- The Contractor advertised opportunities to participate in the Contract, where appropriate, in general circulation media, trade and professional association publications and small business media, and publications of minority and women's business organizations;
- (ii) The Contractor provided notice of specific opportunities to participate in the Contract, in a timely manner, to minority and women's business organizations;
- (iii) The Contractor sent written notices, by certified mail or facsimile, in a timely manner, to advise MBEs or WBEs that their interest in the Contract was solicited;
- (iv) The Contractor made efforts to identify portions of the work that could be substituted for portions originally designated for participation by MBEs and/or WBEs in the M/WBE Utilization Plan, and for which the Contractor claims an inability to retain MBEs or WBEs;
- (v) The Contractor held meetings with MBEs and/or WBEs prior to the date their bids or proposals were due, for the purpose of explaining in detail the scope and requirements of the work for which their bids or proposals were solicited;
- (vi) The Contractor made efforts to negotiate with MBEs and/or WBEs as relevant to perform specific subcontracts, or act as suppliers or service providers;
- (vii) Timely written requests for assistance made by the Contractor to Agency's M/WBE liaison officer and to DSBS;
- (viii) Description of how recommendations made by DSBS and Agency were acted upon and an explanation of why action upon such recommendations did not lead to the desired level of participation of MBEs and/or WBEs.

Agency's M/WBE officer shall provide written notice to the Contractor of the determination.

(b) The Agency may modify the **Participation Goals** when the scope of the work has been changed by the Agency in a manner that affects the scale and types of work that the Contractor indicated in its **M/WBE** Utilization Plan would be awarded to subcontractors.

12. If this Contract is for an indefinite quantity of construction, standard or professional services or is a requirements type contract and the Contractor has submitted an **M/WBE** Utilization Plan and has committed to subcontract work to MBEs and/or WBEs in order to meet the **Participation Goals**, the Contractor will not be deemed in violation of the M/WBE Program requirements for this Contract with regard to any work which was intended to be subcontracted to an MBE and/or WBE to the extent that the Agency has determined that such work is not needed.

13. If **Participation Goals** have been established for this Contract or a Task Order issued pursuant to this Contract, at least once annually during the term of the Contract or Task Order, as applicable, Agency shall review the Contractor's progress toward attainment of its M/WBE Utilization Plan, including but not limited to, by reviewing the percentage of work the Contractor has actually awarded to MBE and/or WBE subcontractors and the payments the Contractor made to such subcontractors.

14. If **Participation Goals** have been established for this Contract or a Task Order issued pursuant to this Contract, Agency shall evaluate and assess the Contractor's performance in meeting those goals, and such evaluation and assessment shall become part of the Contractor's overall contract performance evaluation

APT E-PIN #:

### PART B: MISCELLANEOUS

1. The Contractor shall take notice that, if this solicitation requires the establishment of an **M/WBE** Utilization Plan, the resulting contract may be audited by DSBS to determine compliance with Section 6-129. See §6-129(e)(10). Furthermore, such resulting contract may also be examined by the City's Comptroller to assess compliance with the **M/WBE** Utilization Plan.

2. Pursuant to DSBS rules, construction contracts that include a requirement for an **M/WBE** Utilization Plan shall not be subject to the law governing Locally Based Enterprises set forth in Section 6-108.1 of the Administrative Code of the City of New York.

3. DSBS is available to assist contractors and potential contractors in determining the availability of MBEs and/or WBEs to participate as subcontractors, and in identifying opportunities that are appropriate for participation by MBEs and/or WBEs in contracts.

4. Prospective contractors are encouraged to enter into qualified joint venture agreements with MBEs and/or WBEs as defined by Section 6-129(c)(30).

5. By submitting a bid or proposal the Contractor hereby acknowledges its understanding of the M/WBE Program requirements set forth herein and the pertinent provisions of Section 6-129, and any rules promulgated thereunder, and if awarded this Contract, the Contractor hereby agrees to comply with the M/WBE Program requirements of this Contract and pertinent provisions of Section 6-129, and any rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract. The Contractor hereby agrees to make all reasonable, good faith efforts to solicit and obtain the participation of MBEs and/or WBEs to meet the required **Participation Goals**.

### ARTICLE II. ENFORCEMENT

1. If Agency determines that a bidder or proposer, as applicable, has, in relation to this procurement, violated Section 6-129 or the DSBS rules promulgated pursuant to Section 6-129, Agency may disqualify such bidder or proposer, as applicable, from competing for this Contract and the Agency may revoke such bidder's or proposer's prequalification status, if applicable.

2. Whenever Agency believes that the Contractor or a subcontractor is not in compliance with Section 6-129 or the DSBS rules promulgated pursuant to Section 6-129, or any provision of this Contract that implements Section 6-129, including, but not limited to any **M/WBE** Utilization Plan, Agency shall send a written notice to the Contractor describing the alleged noncompliance and offering the Contractor an opportunity to be heard. Agency shall then conduct an investigation to determine whether such Contractor or subcontractor is in compliance.

3. In the event that the Contractor has been found to have violated Section 6-129, the DSBS rules promulgated pursuant to Section 6-129, or any provision of this Contract that implements Section 6-129, including, but not limited to, any **M/WBE** Utilization Plan, Agency may determine that one of the following actions should be taken:

- (a) entering into an agreement with the Contractor allowing the Contractor to cure the violation;
- (b) revoking the Contractor's pre-qualification to bid or make proposals for future contracts;
- (c) making a finding that the Contractor is in default of the Contract;
- (d) terminating the Contract;
- (e) declaring the Contractor to be in breach of Contract;
- (f) withholding payment or reimbursement;
- (g) determining not to renew the Contract;
- (h) assessing actual and consequential damages;
- (i) assessing liquidated damages or reducing fees, provided that liquidated damages may be based on amounts representing costs of delays in carrying out the purposes of the M/WBE Program, or in meeting the purposes of the Contract, the costs of meeting utilization goals through additional procurements, the administrative costs of investigation and enforcement, or other factors set forth in the Contract;
- (j) exercising rights under the Contract to procure goods, services or construction from another contractor and charge the cost of such contract to the Contractor that has been found to be in noncompliance; or
- (k) taking any other appropriate remedy.

4. If an M/WBE Utilization Plan has been submitted, and pursuant to this Article II, Section 3, the Contractor has been found to have failed to fulfill its Participation Goals contained in its M/WBE Utilization Plan or the Participation Goals as modified by Agency pursuant to Article I, Part A, Section 11, Agency may assess liquidated damages in the amount of ten percent (10%) of the difference between the dollar amount of work required to be awarded to MBE and/or WBE firms to meet the Participation Goals and the dollar amount the Contractor actually awarded and paid, and/or credited, to MBE and/or WBE firms. In view of the difficulty of accurately ascertaining the loss which the City will suffer by reason of Contractor's failure to meet the Participation Goals, the foregoing amount is hereby fixed and agreed as the liquidated damages that the City will suffer by reason of such failure, and not as a penalty. Agency may deduct and retain out of any monies which may become due under this Contract the amount of any such liquidated damages; and in case the amount which may become due under this Contract shall be less than the amount of liquidated damages suffered by the City, the Contractor shall be liable to pay the difference.

5. Whenever Agency has reason to believe that an MBE and/or WBE is not qualified for certification, or is participating in a contract in a manner that does not serve a commercially useful function (as defined in Section 6-129(c)(8)), or has violated any provision of Section 6- 129, Agency shall notify the Commissioner of DSBS who shall determine whether the certification of such business enterprise should be revoked.

6. Statements made in any instrument submitted to Agency pursuant to Section 6-129 shall be submitted under penalty of perjury and any false or misleading statement or omission shall be grounds for the application of any applicable criminal and/or civil penalties for perjury. The making of a false or fraudulent statement by an MBE and/or WBE in any instrument submitted pursuant to Section 6-129 shall, in addition, be grounds for revocation of its certification.

7. The Contractor's record in implementing its **M/WBE** Utilization Plan shall be a factor in the evaluation of its performance. Whenever Agency determines that a Contractor's compliance with an **M/WBE** Utilization Plan has been unsatisfactory, Agency shall, after consultation with the City Chief Procurement Officer, file an advice of caution form for inclusion in VENDEX as caution data.

# SCHEDULE B – M/WBE Participation Requirements for Master Service Agreements That Will Require Individually Registered Task Orders

### Part I: M/WBE Participation Goals

Part I to be completed by contracting agency

Contract Overview								
APT E- Pin #	Various		FMS Pr	oject ID#: _	JOCS_D	DC		
Project Title/ Agency PIN #	Job Order Contract							
Bid/Proposal Response Date	WEDNESDAY, NOV	VEMBER	R 18, 2015					-,,,,,,,,,,,,,-
<b>Contracting Agency</b>	Department of Design and	l Constructi	on				****	
Agency Address	30-30 Thomas Ave	City	Long Islan	d	State	NY	Zip Code	11101
Contact Person	Donna Pope	Wee With Later and a second	Title	Director of	the Office	of Co	ntract Oppor	rtunity
Telephone #	(718) 391-1556		Email	poped@dd	c.nyc.gov	t		
Project Description (atte	ach additional pages if necessary)							

### **JOC's Contracts**

### M/WBE Participation Requirements for Construction, Professional and Standard Services Master Services Agreements That Will Require Individually Registered Task Orders

The Master Services Agreement awarded pursuant to this solicitation is subject to Minority and Women-Owned Business Enterprises (M/WBE) participation requirements established in Section 6-129 of the New York City Administrative Code. Depending on the scope of work and the availability of M/WBEs to perform such work, agencies may set M/WBE participation goals on each individual task order issued pursuant to such agreement. If M/WBE participation goals are established for an individual task order, Prime Contractors will be required to submit a completed Schedule B – M/WBE Utilization Plan unless a full waiver is obtained. If Prime contractors submit a Schedule B, they will be required to fulfill the M/WBE participation goals on each individual task order, except to the extent that a full or partial waiver is obtained or such goals are modified by the agency. Please refer to the Notice for Prospective Contractors for more information.

Prime Contract Industry CONSTRUCTION

Tax ID #:	APT E- PIN #:
	Subcontractor Participation Plan
Section I: Prime Contractor Co	ontact Information
Tax ID #	FMS Vendor ID #
<b>A</b> 1 11	Contact Person
Address	
Telephone #	Email
Section II: General Contract	Information
<ul> <li>Scopes of Subcontract Work</li> </ul>	Enter brief description of all the type(s) of subcontracts for all/any services you plan on subcontracting if         awarded this contract. Use additional sheets if necessary.         1

### Section V: Vendor Certification and Required Affirmations

### I hereby:

1) acknowledge my understanding of the M/WBE participation requirements as set forth herein and the pertinent provisions of Section 6-129 of the Administrative Code of the City of New York ('Section 6-129'), and the rules promulgated thereunder:

2) affirm that the information supplied in support of this Subcontractor Participation Plan is true and correct: 3) agree, if awarded this Contract, to comply with the M/WBE participation requirements of this Contract as established on each individual Task Order, the pertinent provisions of Section 6-129, and the rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract:

4) agree and affirm that it is a material term of this Contract that the Vendor will award to certified MBEs and/or WBEs the total dollar value of the M/WBE Participation Goals that are established on each individual Task Order issued pursuant to this Contract, unless a full waiver is obtained or such goals are modified by the Agency; and

5) agree and affirm, if awarded this Contract, to make all reasonable, good faithefforts to meet the M/WBE Participation Goals established on each individual Task Order issued pursuant to this Contract, or If a partial waiver is obtained or such goals are modified by the Agency, to meet the modified Participation Goalsby soliciting and obtaining the participation of certified MBE and/or WBE firms.

Signature	Date	
Print Name	 Title	

Tax	ID	#:	
-----	----	----	--

APT E-PIN #:

BID FORM
THE CITY OF NEW YORK
DEPARTMENT OF DESIGN AND CONSTRUCTION
DIVISION OF PUBLIC BUILDINGS

### BID FOR FURNISHING ALL LABOR AND MATERIAL NECESSARY AND REQUIRED FOR:

PROJECT ID: JOCS\_DDC

Name of Bidder:
Date of Bid Opening:
Bidder is: (Check one, whichever applies) Individual () Partnership () Corporation ()
Place of Business of Bidder:
Bidder's Telephone Number:
Residence of Bidder (If Individual):
If Bidder is a Partnership, fill in the following blanks:
Names of Partners Residence of Partners
If Bidder is a Corporation, fill in the following blanks: Organized under the laws of the State of
Name and Home Address of President:
Name and Home Address of Secretary:
Name and Home Address of Treasurer:

APT E-PIN #:

#### **BID FORM**

The above-named Bidder affirms and declares:

1. The said bidder is of lawful age and the only one interested in this bid; and no person, firm or corporation other than hereinbefore named has any interest in this bid, or in the Contract proposed to be taken.

2. By submission of this bid, each bidder and each person signing on behalf of any bidder certifies, and in the case of a joint bid each party thereto certifies as to its own organization, under penalty of perjury, that to the best of its knowledge and belief: (1) the prices in this bid have been arrived at independently without collusion, consultation, communication or agreement, for the purpose of restricting competition, as to any matter relating to such prices with any other bidder or with any competitor; (2) unless otherwise required by law, the prices quoted in this bid have not been knowingly disclosed by the bidder and will not knowingly be disclosed by the bidder prior to opening, directly or indirectly, to any other bidder or to any competitor; and (3) No attempt has been made or will be made by the bidder to induce any other person, partnership or corporation to submit or not to submit a bid for the purpose of restricting competition.

No councilman or other officer or employee or person whose salary is payable in whole or in part from 3. the City Treasury is directly or indirectly interested in this bid, or in the supplies, materials, equipment, work or labor to which it relates, or in any of the profits thereof.

4. The bidder is not in arrears to the City of New York upon debt or contract or taxes, and is not a defaulter, as surety or otherwise, upon any obligation of the City of New York, and has not been declared not responsible, or disqualified, by any agency of the City of New York or State of New York. nor is there any proceeding pending relating to the responsibility or qualification of the bidder to receive public contracts except as set forth on the Affirmation included as page 9 of this Bid Booklet.

The bidder hereby affirms that it has paid all applicable City income, excise and other taxes for all years it has conducted business activities in New York City.

5. The bidder, as an individual, or as a member, partner, director or officer of the bidder, if the same be a firm, partnership or corporation, executes this document expressly warranting and representing that should this bid be accepted by the City and the Contract awarded to him, he and his subcontractors engaged in the performance: (1) will comply with the provisions of Section 6-108 of the Administrative Code of the City of New York and the non-discrimination provisions of Section 220a of the New York State Labor Law, as more expressly and in detail set forth in the Agreement; (2) will comply with Section 6-109 of the Administrative Code of the City of New York in relation to minimum wages and other stipulations as more expressly and in detail set forth in the Agreement; (3) have complied with the provisions of the aforesaid laws since their respective effective dates, and (4) will post notices to be furnished by the City, setting forth the requirements of the aforesaid laws in prominent and conspicuous places in each and every plant, factory, building and structure where employees engaged in the performance of the Contract can readily view it, and will continue to keep such notices posted until the supplies, materials and equipment, or work labor and services required to be furnished or rendered by the Contractor have been finally accepted by the City. In the event of any breach or violation of the foregoing, the Contractor may be subject to damages, liquidated or otherwise, cancellation of the Contract and suspension as a bidder for a period of three years. (The words, "the bidder", "he", "his", and "him" where used herein shall mean the individual bidder, firm, partnership or corporation executing this bid).

#### 6. **Compliance Report**

The bidder, as an individual, or as a member, partner, director, or officer of the bidder, if the same be a firm, partnership, or corporation, (1) represents that his attention has been specifically drawn to Executive CITY OF NEW YORK BID BOOKLET Department of Design and Construction Page 14 SEPTEMBER 2008

Tax ID #:

Order No. 50, dated, April 25, 1980, on Equal Employment Compliance of the contract, and (2) warrants that he will comply with the provisions of Executive Order No. 50. The Employment Report must be submitted as part of the bid.

The bidder, as an individual, or as a member, partner, director, or officer of the bidder, if the same be a firm, partnership, or corporation, executes this document expressly warranting that he will comply with: (1) the provision of the contract on providing records, Chapter 8.

7. By submission of this bid, the bidder certifies that it now has and will continue to have the financial capability to fully perform the work required for this contract. Any award of this contract will be made in reliance upon such certification. Upon request therefor, the bidder will submit written verification of such financial capability in a form that is acceptable to the department.

8. In accordance with Section 165 of the State Finance Law, the bidder agrees that tropical hardwoods, as defined in Section 165 of the State Finance Law, shall not be utilized in the performance of this Contract, except as the same are permitted by the foregoing provision of law.

9. The bidder has visited and examined the site of the work and has carefully examined the Contract in the form approved by the Corporation Counsel, and will execute the Contract and perform all its items, covenants and conditions, and will provide, furnish and deliver all the work, materials, supplies, tools and appliances for all labor and materials necessary or required for the hereinafter named work, all in strict conformity with the Contract, for the prices set forth in its bid.

10. <u>M/WBE PARTICIPATION REQUIREMENTS</u>: By signing its bid, the bidder agrees to the Vendor Certification and Required Affirmations set forth below. The Vendor Certification and Required Affirmations will be deemed to satisfy the requirement to complete Section V of Part II of Schedule B: M/WBE Participation Requirements.

## Section V: Vendor Certification and Required Affirmations:

Ihereby:

- 1) acknowledge my understanding of the M/WBE participation requirements as set forth herein and the pertinent provisions of Section 6-129 of the Administrative Code of the City of New York and the rules promulgated thereunder;
- 2) affirm that the information supplied in support of this Subcontractor Participation Plan is true and correct;
- 3) agree, if awarded this Contract, to comply with the M/WBE participation requirements of this Contract as established on each individual Task Order, the pertinent provisions of Section 6-129, and the rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract;
- 4) agree and affirm that it is a material term of this Contract that the Vendor will award the total dollar value of the M/WBE Participation Goals that are established on each individual Task Order issued pursuant to this Contract, unless a full waiver is obtained or such goals are modified by the Agency; and
- 5) agree and affirm, if awarded this Contract, to make all reasonable, good faith efforts to meet the M/WBE Participation Goals established on each individual Task Order issued pursuant to this Contract, or if a partial waiver is obtained or such goals are modified by the Agency, to meet the modified Participation Goals by soliciting and obtaining the participation of certified MBE and/or WBE firms.

Tax ID #:

#### 3. SCHEDULE OF PRICES

The Contractor shall perform all Work required, necessary, and proper for or incidental to completing the Work called for in each individual Job Order issued pursuant to this Contract using the Construction Task Catalog® and Technical Specifications incorporated herein with the following Adjustment Factors:

1. Normal Working Hours: Contractor shall perform any or all items of work during Normal Working Hours called for in the individual Job Orders in accordance with the Contract Documents for the unit price specified in the Unit Price Book (UPB) multiplied by the adjustment factor of:



(Specify to four (4) decimal places)

2. Other Than Normal Working Hours: Contractor shall perform any or all items of work during Other Than Normal Working Hours called for in the individual Job Orders in accordance with the Contract Documents for the price specified in the Construction Task Catalog® multiplied by the adjustment factor. Other Than Normal Working Hours Adjustment Factor must be equal to or greater than the Normal Working Hours Adjustment Factor inserted above).



(Specify to four (4) decimal places)

3. Non-Prepriced Adjustment Factor: Contractor shall perform any or all items of work called for in the individual Job Orders in accordance with the Contract Documents for items not specified in the Construction Task Catalog® for the price as determined from Article 3B of the Contract multiplied by the Non-Pre-Priced Adjustment Factor of:



(Specify to four (4) decimal places)

4. Award Criteria Figure: Contractor shall include, in the space provided below, the Award Criteria Figure calculated on the page 18.



(Specify to four (4) decimal places)

NOTICE - The attention of Bidders is particularly called to the fact that, unless the Bid is made in strict conformity with the directions given, it will be considered non-responsive and may be rejected.

APT E-PIN #:

## BASIS OF CONTRACT AWARD

The following formula has been developed for the sole purpose of evaluating bids and awarding the Contract. Each bidder must complete the following Award Criteria Formula.

## AWARD CRITERIA FORMULA

Line 1.	Normal Working Hours Adjustment Factor	
Line 2.	Multiply Line 1 by 0 .85	
Line 3.	Other Than Normal Working Hours Adjustment Factor	······································
Line 4.	Multiply Line 3 by 0.05	
Line 5.	Non-Prepriced Adjustment Factor	••••••••••••••••••••••••••••••••••••••
Line 6.	Multiply Line 5 by 0.10	
Line 7.	Summation of lines 2, 4 and 6	
		(Award Figure)

The bidder shall complete the Award Criteria Formula and transfer the final Award Criteria Figure to the space provided on the Schedule of Prices. A contract will be awarded to the responsive and responsible bidder with the lowest Award Criteria Figure subject to the limitations appearing in the Contract Documents. The City reserves the right to revise all arithmetic errors in calculations for correctness.

Tax ID #:

APT E-PIN #:

## **BIDDER'S SIGNATURE AND AFFIDAVIT**

4

<u>WARNING!</u> If M/WBE goals have been established for this Contract, you MUST complete and submit the Affirmations on the 2nd page of the Subcontractor Utilization Plan (or a preapproved waiver) at the time you submit your bid. Failure to comply will result in the rejection of your bid.

Bidder: \_\_\_\_\_

By: \_\_\_

(Signature of Partner or corporate officer)

Attest: (Corporate Seal)

Secretary of Corporate Bidder

Affidavit on the following page should be subscribed and sworn to before a Notary Public

APT E-PIN #:

AFFIRMATION

The undersigned bidder affirms and declares that said bidder is not in arrears to the City of New York upon debt, contract or taxes and is not a defaulter, as surety or otherwise, upon obligation to the City of New York, and has not been declared not responsible, or disqualified, by any agency of the City of New York, nor is there any proceeding pending relating to the responsibility or qualification of the bidder to receive public contracts except\_\_\_\_\_\_

(If none, the bidder shall insert the word "None" in the space provided above.)

У	State	Zip Code
IECK ON	IE BOX AND INCLUDE APPROPRIATE NUM	
_/ A-	Individual or Sole Proprietorship* SOCIAL SECURITY NUMBER	
B/	Partnership, Joint Venture or other unincor EMPLOYER IDENTIFICATION NUMBER	porated organization
C-	Corporation EMPLOYER IDENTIFICATION NUMBER	• •
:		
Signa	ature	

If a corporation, place seal here

This affirmation must be signed by an officer or duly authorized representative.

\*Under the Federal Privacy Act the furnishing of Social Security Numbers by bidders on City contracts is voluntary. Failure to provide a Social Security Number will not result in a bidder's disqualification. Social Security Numbers will be used to identify bidders, proposers or vendors to ensure their compliance with laws, to assist the City in enforcement of laws, as well as to provide the City a means of identifying of businesses which seek City contracts.

Tax ID #:

#### BIDDER'S IDENTIFICATION OF SUBCONTRACTORS

#### NOTICE TO BIDDERS

SUBMISSION: The Bidder must at the time of the bid, submit the form on the next page ("BIDDER'S IDENTIFICATION OF SUBCONTRACTORS'). This form must be submitted in a separate, sealed envelope (BID ENVELOPE #2). Failure to do so will result in the disgualification of the bid as non-responsive.

NOTE: On the following pages, there are four (4) separate forms applicable to the various Contracts (Contract Nos. 1 through 4)

Please be advised that pursuant to GML § 101(5) the Bidder is required to submit with its bid the names of subcontractors it

intends to use to perform the following work on this contract, as well as the agreed-upon amount to be paid to each:

- plumbing and gas fitting;
- steam heating, hot water heating, ventilating and air conditioning apparatus; and
- electric wining and standard illuminating fixtures

# NOTE: This project may not involve all of the above listed subcontractors. Please see the form on the next page which indicates the subcontractors required for this Project.

The list of subcontractors is to be submitted in a separate sealed envelope by completing the form on the next page entitled "Bidder's Identification of Subcontractors". This form provides for the identification of any subcontractors intended to be used in any of the three trades listed above. If bidder intends to use its own forces for any of the above listed work, bidder should so indicate on the form.

Contractors should also clearly state the agreed upon amount to be paid to each subcontractor. The agreed upon amount is expressed as an adjustment factor indicated on the following page(s). Contactors are permitted to submit the names of more than one subcontractor for each of these trades. Note, however, that if more than one subcontractor is listed for any of the relevant trades, the agreed upon amount to be paid to each subcontractor must be stated.

Failure to submit the completed form on the next page ("Bidder's identification of Subcontractors") that includes the names of subcontractors and the agreed upon amounts to be paid to such subcontractors will render the bid non-responsive.

PLEASE NOTE: For any contract that is subject to M/WBE participation goals under Local Law 1 of 2013, if the bidder's intention to use its own forces to do any of the above-referenced work would result in Bidder's failure to attain the Target Subcontracting Percentage identified in the Subcontractor Utilization Plan, the bid will be non-responsive unless the bidder requests and obtains a Waiver of Target Subcontracting Percentage (Subcontractor Utilization Plan, Part III) in advance of bid submission

After the low bid is announced, the sealed list submitted by the low bidder will be opened and the names of the subcontractors will be announced. The sealed lists of subcontractors submitted by all other bidders shall be maintained by the Agency unopened unless such bidder shall become the low bidder (e.g., the initial low bidder is found non-responsive). All unopened lists of subcontractors shall be returned to the bidders unopened after contract award, unless the bidder has given the agency permission to shred the form.

After bid submission, any change of subcontractor or agreed-upon amount to be paid to each shall require approval of the Agency upon a showing of a legitimate construction need which shall include, but not be limited to, a change in project specifications, a change in project material costs, a change to subcontractor status as determined pursuant to §222 (2)(e) of the Labor Law, or if the subcontractor has become otherwise unwilling, unable or unavailable to perform the subcontract.

# BIDDER'S IDENTIFICATION OF SUBCONTRACTORS - CONTRACT #1: GENERAL CONSTRUCTION WORK

SUBMISSION: In addition to its Bid (Bid Envelope #1), the Bidder must, at the time of the bid, complete and submit this form in a separate sealed envelope (Bid Envelope #2) To complete this form, the Bidder must identify the subcontractors it intends to use for the work listed below, as well as the percent mark-ups to be paid to each subcontractor. Failure to complete this form and submit it in a separate, sealed envelope will result in the disqualification of the bid as non-responsive.

The Bidder intends to use the following subcontractors. If the Bidder intends to do any of the work referenced below with its own forces. the Bidder should complete this form using its own name. For Plumbing and Electrical Work, the contractor or sub-contractor performing the work must be accessed in the respective trade. If multiple subcontractors for any trade are proposed, Bidder may indicate multiple subcontractors on this form or if needed, submit multiple copies of this form

This contract is subject to MWBE participation goals under Local Law 1 of 2013. Trade work under this contract may be suitable for MWBE participation; therefore, if the trade work identified in this form is not targeted for MWBE participation, it is important that bidders consider how they intend to meet their MWBE subcontracting obligation outside of these work areas.

#### PLUMBING CONTRACTOR 1.

(Print Name) Agreed upon Adjustment Factors to be Paid to Subcontractor	
Charles about Holysement Lacrois in the Land ID 200000000000	Normal Working Hours:
	Non-Normal Working Hours:
PLUMBING CONTRACTOR	Non Pre-Priced Items.
(Print Name)	
Agreed upon Adjustment Factors to be Paid to Subcontractor.	Normal Working Hours
	Non-Normal Working Hours:
HVAC CONTRACTOR	Non Pre-Priced items
(Print Name)	
Agreed upon Adjustment Factors to be Paid to Subcontractor:	Normal Working Hours
	Non-Normal Working Hours
	Non Pre-Priced Items:
HVAC CONTRACTOR	
(Print Name)	
Agreed upon Adjustment Factors to be Paid to Subcontractor:	Normal Working Hours
· · · · · · · · · · · · · · · · · · ·	Non-Normal Working Hours
ELECTRICAL CONTRACTOR	Non Pre-Priced Items:
(Print Name)	
Agreed upon Adjustment Factors to be Paid to Subcontractor.	Normal Working Hours
	Non-Normal Working Hours
ELECTRICAL CONTRACTOR	Non Pre-Priced Items:
(Print Name) Agreed upon Adjustment Factors to be Paid to Subcontractor:	Normal Minikan Stram
(2) Some of the constraint of the second s second second s Second second secon second second sec	Normal Working Hours Non-Normal Working Hours:
	Man Oos Delevel House
R'S SIGNATURE: The Bidder must sign this form in the space provided	Non Pre-Priced Items:
Name of Bidder	
By	
By Signalure of Partner or Corporat	e Officer
Title	
DRIZATION TO SHRED: In the event an award of contract is not made to	

A 1d

## BIDDER'S IDENTIFICATION OF SUBCONTRACTORS

## CONTRACT #2: PLUMBING AND GAS FITTING WORK

SUBMISSION: In addition to its Bid (Bid Envelope #1), the Bidder must, at the time of the bid, complete and submit this form in a separate, sealed envelope (Bid Envelope #2). To complete this form, the Bidder must identify the subcontractors if intends to use for the work listed below, as well as the percent mark-ups to be paid to each subcontractor. Failure to complete this form and submit it in a separate, sealed envelope will result in the disgualification of the bid as non-responsive.

The Bidder intends to use the following subcontractors. If the Bidder intends to do any of the work referenced below with its own forces, the Bidder should complete this form using its own name. For Plumbing and Electrical Work, the contractor or sub-contractor performing the work must be licensed in the respective trade. If multiple subcontractors for any trade are proposed, Bidder may indicate multiple subcontractors on this form or if needed, submit multiple copies of this form.

This contract is subject to MWBE participation goals under Local Law 1 of 2013. Trade work under this contract may be suitable for MWBE participation; therefore, if the trade work identified in this form is not targeted for MWBE participation, it is important that bidders consider how they intend to meet their MWBE subcontracting obligation outside of these work areas.

#### 1 HVAC CONTRACTOR

(Print Agreed upon Adjustment Factors to be Paid to Subcont	
since apprendiation actions to be haid to applying	
	Non-Normal Working Hours:
HVAC CONTRACTOR	Non Pre-Pricod Items
(Peurit t	
Agreed upon Adjustment Factors to be Paid to Subconti	
	Non-Normal Working Hours
ELECTRICAL CONTRACTOR	Non Pre-Priced Items:
(Pont N	•
Agreed upon Adjustment Factors to be Paid to Subcontr	
	Non-Normal Working Hours
ELECTRICAL CONTRACTOR	Non Pre-Priced Items
(Print N	ame)
Agreed upon Adjustment Factors to be Paid to Subcontre	
	Non-Normal Working Hours
	Non Pre-Priced Items:
R'S SIGNATURE: The Bidder must sign this form in the space pr Name of Bidder:	
By"	n y y y y y y y y y y y y y y y y y y y
By:Signature of Partner or C Print Name	Corporate Officer
Title	

**BID BOOKLET** 

APT E-PIN #:

## BIDDER'S IDENTIFICATION OF SUBCONTRACTORS

## CONTRACT #3: HVAC WORK

SUBMISSION: In addition to its Bid (Bid Envelope #1), the Bidder must, at the time of the bid, complete and submit this form in a separate, sealed envelope (Bid Envelope #2). To complete this form, the Bidder must identify the subcontractors it intends to use for the work listed below, as well as the percent mark-ups to be paid to each subcontractor. Failure to complete this form and submit it in a separate, sealed envelope will result in the disqualification of the bid as non-responsive.

The Bidder intends to use the following subcontractors. If the Bidder intends to do any of the work referenced below with its own forces, the Bidder should complete this form using its own name. For Plumbing and Electrical Work, the contractor or sub-contractor performing the work must be licensed in the respective trade. If multiple subcontractors for any trade are proposed, Bidder may indicate multiple subcontractors on this form or if needed, submit multiple copies of this form

This contract is subject to MWBE participation goals under Local Law 1 of 2013. Trade work under this contract may be suitable for MWBE participation; therefore, if the trade work identified in this form is not targeted for MWBE participation, it is important that bidders consider how they intend to meet their MWBE subcontracting obligation outside of these work areas.

#### 1 PLUMBING AND GAS FITTING CONTRACTOR

	(Print Name) Agreed upon Adjustment Factors to be Paid to Subcontractor	
		Normal Working Hours: Non-Normal Working Hours
	PLUMBING AND GAS FITTING CONTRACTOR	Non Pre-Priced Items:
	(Print Name) Agreed upon Adjustment Factors to be Paid to Subcontractor:	Normal Working Hours: Non-Normal Working Hours:
2	ELECTRICAL CONTRACTOR	Non Pre-Priced Items.
	(Print Name) Agreed upon Adjustment Factors to be Paid to Subcontractor	Normal Working Hours: Non-Norinal Working Hours
	ELECTRICAL CONTRACTOR	Non Pre-Priced Items:
	(Pont Name) Agreed upon Adjustment Factors to be Paid to Subcontractor:	Normal Working Hours Non-Normal Working Hours
		Non Pre-Paced Items
BIDDE	R'S SIGNATURE: The Bidder must sign this form in the space provided Name of Bidder:	
	BySignature of Partner or Corporal Pent Name	
	Signature of Partner or Corporat Print Name.	e Officer
	Title.	
(UTHO hred Ih	RIZATION TO SHRED: In the event an award of contract is not made to is form entitled 'Biddur's Identification of Subcontractors'YI	the Bidder, the Bidder hereby authorizes the Agency to ESNO
EW YO	RK	BID BOOKI

CITY OF NEW Department of Design and Construction Tax ID #:

APT E-PIN #:

#### **BIDDER'S IDENTIFICATION OF SUBCONTRACTORS**

#### CONTRACT #4: ELECTRICAL WORK

SUBMISSION: In addition to its Bid (Bid Envelope #1), the Bidder must, at the time of the bid, complete and submit this form in a separate, sealed envelope (Bid Envelope #2). To complete this form, the Bidder must identify the subcontractors it intends to use for the work listed below, as well as the percent mark-ups to be paid to each subcontractor. Failure to complete this form and submit it in a separate, sealed envelope will result in the disqualification of the bid as non-responsive.

The Bidder intends to use the following subcontractors. If the Bidder intends to do any of the work referenced below with its own forces. the Bidder should complete this form using its own name. For Plumbing and Electrical Work, the contractor or sub-contractor performing the work must be licensed in the respective trade. If multiple subcontractors for any trade are proposed, Bidder may Indicate multiple subcontractors on this form or if needed, submit multiple copies of this form.

This contract is subject to MWBE participation goals under Local Law 1 of 2013. Trade work under this contract may be suitable for MWBE participation; therefore, if the trade work identified in this form is not targeted for MWBE participation, it is important that bidders consider how they intend to meet their MWBE subcontracting obligation outside of these work areas.

#### 1 PLUMBING AND GAS FITTING CONTRACTOR

and a density	(Print Name)	
	Agreed upon Adjustment Factors to be Paid to Subcontractor:	Normal Working Hours:
		Non-Normal Working Hours:
		Non Pre-Priced Items:
PLL	IMBING AND GAS FITTING CONTRACTOR	
<b>**</b>	(Pont Name)	
	Agreed upon Adjustment Factors to be Paid to Subcontractor	Normal Working Hours:
		Non-Normal Working Hours
HVA		Non Pre-Priced Items:
HVA	CCONTRACTOR	
	(Print Name)	
	Agreed upon Adjustment Factors to be Paid to Subcontractor:	Normal Working Hours:
		Non-Normal Working Hours:
		Non Pre-Priced Items:
HVA	CCONTRACTOR	
******	(Print Name)	
	Agreed upon Adjustment Factors to be Paid to Subcontractor:	Normal Working Hours
		Non-Normal Working Hours:
		Non Pre-Priced Items
)DER'S	SIGNATURE: The Bidder must sign this form in the space provided	
	Name of Bidder:	NY TANÀNA MANANA MAN
	By Signature of Partner or Corpora	Analysis with Samphoneses in Analysis Mary - Analysis Analysis and an analysis and analysis and analysis and a
	Signature of Partner or Corpora Print Name	le Officer
	Title:	
T: 100.7		
ed this to	ATION TO SHRED: In the event an award of contract is not made to rm entitled 'Bidder's Identification of Subcontractors'.	the Bidder, the Bidder hereby authorizes the Agency to //ESNO
NEW YO	RK	BID BOO

APT E-PIN #:

## BID BOND 1 FORM OF BID BOND

# KNOW ALL MEN BY THESE PRESENTS. That we, \_\_\_\_\_

hereinafter referred to as the "Principal", and \_\_\_\_\_

hereinafter referred to as the "Surety" are held and firmly bound to THE CITY OF NEW YORK, hereinafter referred to as the "CITY", or to its successors and assigns in the penal sum of \_\_\_\_\_\_

(\$\_\_\_\_\_), Dollars lawful money of the United States, for the payment of which said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

Whereas, the Principal is about to submit (or has submitted) to the City the accompanying proposal, hereby made a part hereof, to enter into a contract in writing for \_\_\_\_\_

NOW, THEREFORE, the conditions of this obligation are such that if the Principal shall not withdraw said Proposal without the consent of the City for a period of forty-five (45) days after the opening of bids and in the event of acceptance of the Principal's Proposal by the City, if the Principal shall:

(a) Within ten (10) days after notification by the City, execute in quadruplicate and deliver to the City all the executed counterparts of the Contract in the form set forth in the Contract Documents, in accordance with the proposal as accepted, and

(b) Furnish a performance bond and separate payment bond, as may be required by the City, for the faithful performance and proper fulfillment of such Contract, which bonds shall be satisfactory in all respects to the City and shall be executed by good and sufficient sureties, and

(c) In all respects perform the agreement created by the acceptance of said Proposal as provided in the Information for Bidders, bound herewith and made a part hereof, or if the City shall reject the aforesaid Proposal, then this obligation shall be null and void; otherwise to remain in full force and effect.

APT E-PIN #:

## BID BOND 2

In the event that the Proposal of the Principal shall be accepted and the Contract be awarded to him the Surety hereunder agrees subject only to the payment by the Principal of the premium therefore, if requested by the City, to write the aforementioned performance and payment bonds in the form set forth in the Contract Documents.

It is expressly understood and agreed that the liability of the Surety for any and all claims hereunder shall in no event exceed the penal amount of this obligation as herein stated.

There shall be no liability under this bond if, in the event of the acceptance of the Principal's Proposal by the City, either a performance bond or payment bond, or both, shall not be required by the City on or before the 30th day after the date on which the City signs the Contract.

The surety, for the value received, hereby stipulates and agrees that the obligations of the Surety and its bond shall in no way be impaired or affected by any postponements of the date upon which the City will receive or open bids, or by any extensions of the time within which the City may accept the Principal's Proposal, or by any waiver by the City of any of the requirements of the Information for Bidders, and the Surety hereby waives notice of any such postponements, extensions, or waivers.

IN WITNESS WHEREOF, the Principal and the Surety have hereunto set their hands and seals and such of them as are corporations have caused their corporate seals to be hereto affixed and these presents to be signed by their proper officers the \_\_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_.

(Seal)

Principal

(L.S.)

Ву:\_\_\_\_\_

(Seal)

Surety

By: \_\_\_\_

\_\_\_\_\_

APT E-PIN #: \_\_\_\_\_

## **BID BOND 3**

# ACKNOWLEDGMENT OF PRINCIPAL, IF A CORPORATION

State of	County of	
On this	day of	55.
	to me k	ss: , before me personally came known, who, being by me duly sworn, did depose and say that
ne resides at		
that he is the	of	
corporation; that one directors of said corp	eribed in and which executed e of the seals affixed to said i poration, and that he signed hi	d the foregoing instrument; that he knows the seal of said instrument is such seal; that it was so affixed by order of the is name thereto by like order.
		Notary Public
	ACKNOWLEDGMENT OF	F PRINCIPAL, IF A PARTNERSHIP
State of	County of	ss: ,, before me personally appeared nown and known to me to be one of the members of the firm
On this	County of	SS:
		, before me personally appeared
of		nown and known to me to be one of the members of the firm
and he acknowledge	to mo that he avecuted the	described in and who executed the foregoing instrument, same as and for the act and deed of said firm.
		Notary Public
	ACKNOWLEDGMENT OF	F PRINCIPAL, IF AN INDIVIDUAL
State of		
On this	County of	SS:
		, before me personally appeared
who executed the fore	going instrument and acknowl	ss: ,, before me personally appeared nown and known to me to be the person described in and ledged that he executed the same.
		Notary Public
AF	FIX ACKNOWLEDGMENTS	AND JUSTIFICATION OF SURETIES
9		and the second

### PLA PROJECT

## ATTACHMENT 1 – BID INFORMATION <u>PROJECT ID:</u> JOCS DDC

## **DESCRIPTION AND LOCATION OF WORK:**

Job Order Contracts for Electric/Plumbing/HVAC - Agency Wide JOC2013E-1 DDC PIN 8502016RQ0006C / E-PIN: 85016B0035 JOC2013E-2 DDC PIN 8502016RQ0007C / E-PIN: 85016B0036 JOC2013E-3 DDC PIN 8502016RQ0008C / E-PIN: 85016B0037 JOC2013P-1 DDC PIN 8502016RQ0009C / E-PIN: 85016B0038 JOC2013P-2 DCC PIN 8502016RQ0010C / E-PIN: 85016B0039 JOC2013H-1 DDC PIN 8502016RQ0011C / E-PIN: 85016B0040 JOC2013H-2 DDC PIN 8502016RQ0012C / E-PIN: 85016B0041 JOC2013H-3 DDC PIN 8502016RQ0013C / E-PIN: 85016B0042

#### **DOCUMENTS AVAILABLE AT:**

Department of Design and Construction, Contract Section 30-30 Thomson Avenue- First Floor, Long Island City, NY 11101

## SUBMISSION OF BIDS BEFORE BID OPENING: <u>TIME TO SUBMIT</u>: ON OR BEFORE WEDNESDAY, NOVEMBER 18, 2015 AT 2:00 P.M. BIDS MUST BE CLOCKED IN PRIOR TO BID OPENING.

#### PLACE TO SUBMIT:

Department of Design and Construction, Contract Section 30-30 Thomson Avenue-1<sup>st</sup> Floor Contract Unit, Long Island City, NY 11101

#### **BID OPENING:**

PLACE OF BID OPENING:	Department of Design and Construction, Contract Section, 1 <sup>st</sup> Floor Bid Room 30-30 Thomson Avenue Long Island City, NY 11101			
DATE AND HOUR:	WEDNESDAY, NOVEMBER 18, 2015 AT 2:00 P.M.			
	LATE BIDS WILL NOT BE ACCEPTED			

#### **BID SECURITY:**

Bid Security, in the amount of \$15,000, shall be required for each General Construction, Plumbing, HVAC and Electrical bid submitted. Bid Security may be in the form of a certified check or bid bond.

#### PERFORMANCE AND PAYMENT SECURITY:

Performance and Payment Bonds will not be required at contract award However, during the performance of the contract, the Contractor shall be required to provide Performance and Payment Bonds for each Job Order in excess of \$1,000,000 in an amount equal to 100% of the Job Order Price. Such security shall be in accordance with the requirements set forth in the Contract Documents. The City shall reimburse the Contractor the actual and reasonable cost of such security, with no mark-up for overhead and profit. The Contractor shall provide a copy of the cancelled check for the required security, as well as any other documentation required by the Commissioner.

## AGENCY CONTACT PERSON:

Lorraine Holley, 30-30 Thomson Avenue, 1<sup>st</sup> Floor, Long Island City, NY 11101 <u>Telephone</u>; (718) 391-3170 or (718) 391-1016 Fax: (718) 391-2615

## THIS PAGE INTENTIONALLY LEFT BLANK

# BID BOOKLET PART B

## SAFETY QUESTIONNAIRE

The bidder must include, with its bid, all information requested on this Safety Questionnaire. Failure to provide a completed and signed Safety Questionnaire at the time of bid opening may result in disqualification of the bid as non-responsive.

#### 1. Bidder Information:

Company Name: \_\_\_\_\_

DDC Project Number:

Company Size: \_\_\_\_\_ Ten (10) employees or less

Greater than ten (10) employees

Company has previously worked for DDC

#### 2. Type(s) of Construction Work

TYPE OF WORK	LAST 3 YEARS	THIS PROJECT
General Building Construction		
Residential Building Construction		
Nonresidential Building Construction		
Heavy Construction, except building		
Highway and Street Construction		
Heavy Construction, except highways		·
Plumbing, Heating, HVAC		
Painting and Paper Hanging		
Electrical Work		·
Masonry, Stonework and Plastering		
Carpentry and Floor Work		
Roofing, Siding, and Sheet Metal		
Concrete Work		
Specialty Trade Contracting		
Asbestos Abatement		
Other (specify)		

#### 3. Experience Modification Rate:

The Experience Modification Rate (EMR) is a rating generated by the National Council of Compensation Insurance (NCCI). This rating is used to determine the contractor's premium for worker's compensation insurance. The contractor may obtain its EMR by contacting its insurance broker or the NCCI. If the contractor cannot obtain its EMR, it must submit a written explanation as to why.

Page 30

The Contractor must indicate its <u>Intra</u>state and <u>Inter</u>state EMR for the past three years. [Note: For contractors with less than three years of experience, the EMR will be considered to be 1.00].

YEAR	INTRASTATE RATE	INTERSTATE RATE
#***····		

If the Intrastate and/or Interstate EMR for any of the past three years is greater than 1.00, the contractor must attach, to this questionnaire, a written explanation for the rating and identify what corrective action was taken to correct the situation resulting in that rating.

#### 4. OSHA Information:

Contractor has received a willful violation issued by OSHA or New York City Department of Buildings (NYCDOB) within the last three years.

\_

Contractor has had an incident requiring OSHA notification within 8 hours (i.e., fatality, or hospitalization of three or more employees).

The Occupational Safety and Health Act (OSHA) of 1970 requires employers with ten or more employees, on a yearly basis to complete and maintain on file the form entitled "Log of Work-related Injuries and Illnesses". This form is commonly referred to as the OSHA 300 Log (OSHA 200 Log for 2001 and earlier).

The OSHA 300 Log must be submitted for the last three years for contractors with more than ten employees.

The Contractor must indicate the total number of hours worked by its employees, as reflected in payroll records for the past three years.

The contractor must submit the incident Rate for Lost Time Injuries (the Incident Rate) for the past three years. The Incident Rate is calculated in accordance with the formula set forth below. For each given year, the total number of incidents is the total number of non-fatal injuries and illnesses reported on the OSHA 300 Log. The 200,000 hours represents the equivalent of 100 employees working forty hours a week, fifty weeks per year.

#### Incident Rate =

Total Number of Incidents X 200,000 Total Number of Hours Worked by Employees

YEAR

TOTAL NUMBERS OF HOURS WORKED BY EMPLOYEES

INCIDENT RATE

Page 31

BID BOOKLET SEPTEMBER 2008 If the contractor's Incident Rate for any of the past three years is one point higher than the Incident Rate for the type of construction it performs (listed below), the contractor must attach, to this questionnaire, a written explanation for the relatively high rate.

General Building Construction	8.5
Residential Building Construction	7.0
Nonresidential Building Construction	10.2
Heavy Construction, except building	8.7
Highway and Street Construction	9.7
Heavy Construction, except highways	8.3
Plumbing, Heating, HVAC	11.3
Painting and Paper Hanging	6.9
Electrical Work	9.5
Masonry, Stonework and Plastering	10.5
Carpentry and Floor Work	12.2
Roofing, Siding, and Sheet Metal	10.3
Concrete Work	8.6
Specialty Trade Contracting	8.6

## 5. Safety Performance on Previous DDC Project(s)

Contractor previously audited by the DDC Office of Site Safety.

DDC Project Number(s):

\_\_\_\_\_ Accident on previous DDC Project(s).

Fatality or Life-altering Injury on DDC Project(s) within the last three years. [Examples of a life-altering injury include loss of limb, loss of a sense (e.g., sight, hearing), or loss of neurological function].

Date: \_\_\_\_\_

(Signature of Owner, Partner, Corporate Officer)

Title:

By: \_\_\_



CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

Page 32

## THIS PAGE INTENTIONALLY LEFT BLANK

#### **Pre-Award Process**

The bidder is advised that as part of the pre-award review of its bid, it may be required to submit the information described in Sections (A) through (E) below. In the event the bidder fails to submit the required information within the specified time frame, its bid may be rejected as nonresponsive.

Sections (A) through (E): If required, the bidder must submit the information described in Sections

 (A) through (E) below within five (5) business days following receipt of notification from DDC that it is
 among the low bidders. Such notification from DDC will be by facsimile or in writing and will specify
 the types of information which must be submitted.

(A) **Contractor's Bid Breakdown**: If required, the bidder must complete and submit the Contractor's Bid Breakdown Form described on page 21 of this Bid Booklet.

\*

- (B) **Project Reference Form**: If required, the bidder must complete and submit the Project Reference Form set forth on pages 28 through 30 of this Bid Booklet. The Project Reference Form consists of 3 parts: (1) Similar Contracts Completed by the Bidder, (2) Contracts Currently Under Construction by the Bidder, and (3) Pending Contracts Not Yet Started by the Bidder.
- (C) Copy of License: If required, the bidder must submit a copy of the license under which the bidder will be performing the work. Such license must clearly show the following: (1) Name of the Licensee, (2) License Number, and (3) Expiration date of the License. A copy of the license will be required from bidders for the following contracts: Plumbing Work, Electrical Work and Asbestos Abatement.
- (D) **Financial Information**: If required, the bidder must submit the financial information described below:
  - (1) Audited Financial Statements: Financial statements (Balance Sheet and Income Statement) of the entity submitting the bid, as audited by an independent auditor licensed to practice as a certified public accountant (CPA). Audited financial statements for the three most recent fiscal years must be submitted. Each such financial statement must include the auditor's standard report.

If the bidder does not have audited financial statements, it must submit an affidavit attesting to the fact that the bidder does not have such statements. In addition, the bidder must submit the following documentation covering the three most recent fiscal years: signed federal tax returns, unaudited financial statements, and a "certified review letter" from a certified public accountant (CPA) verifying the unaudited financial statements.

Unless the most recent audited or unaudited financial statement was issued within ninety (90) days, the bidder must submit interim financial information that includes data on financial position and results of operation (income data) for the current fiscal year. Such information may be summarized on a monthly or quarterly basis or at other intervals.

(2) Schedule of Aged Accounts Receivable, including portion due within ninety (90) days.

(E) **Project Specific Information**: If required, the bidder must submit the project specific information described below:

- (1) Statement indicating the number of years of experience the bidder has had and in what type of construction.
- (2) Resumes of all key personnel to be involved in the project, including the proposed project superintendent.
- (3) List of significant pieces of equipment expected to be used for the contract, and whether such equipment is owned or leased.
- (4) Description of work expected to be subcontracted, and to what firms, if known.
- (5) List of key material suppliers.
- (6) Preliminary bar chart time schedule
- (7) Contractor's expected means of financing the project. This should be based on the assumption that the contractor is required to finance 2X average monthly billings throughout the contract period.
- (8) Any other issues the contractor sees as impacting his ability to complete the project according to the contract.

In addition to the information described in Sections (A) through (E) above, the bidder shall submit such additional information as the Commissioner may require, including without limitation, an explanation or justification for specific unit price items.

The bidder is further advised that it may be required to attend a pre-award meeting with DDC representatives. If such a meeting is convened, the bidder will be advised as to any additional material to be provided.

Page 34 of 37

BID BOOKLET SEPTEMBER 2008

# Ņ **PROJECT REFERENCES – SIMILAR CONTRACTS COMPLETED BY THE BIDDER**

List all contracts substantially completed within the last 4 years similar to the contract being awarded, up to a maximum of 10, in descending order of date of substantial completion.

r	7	 	 	<del>.</del>	
					Project & Location
			•		Contract Type
×					Contract Amount (\$000)
					Date Completed
					Owner Reference & Tel. No.
					Architect/Engineer Reference & Tel. No. if different from owner

CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

Page 35

BID BOOKLET SEPTEMBER 2008

BID BOOKLET SEPTEMBER 2008

CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

Page 36

r	 	 	-	
				Project & Location
				Contract Type
				Contract Amount (\$000)
in strangenetic second				Subcontracted to Others (\$000)
				Uncompleted Portion (\$000)
				Date Scheduled to Complete
				Owner Reference & Tel. No.
				Architect/E ngineer Reference & Tel. No. if different from owner

PROJECT REFERENCES - CONTRACTS CURRENTLY UNDER CONSTRUCTION BY THE BIDDER

œ

List all contracts currently under construction even if they are not similar to the contract being awarded.

ဂ PROJECT REFERENCES - PENDING CONTRACTS NOT YET STARTED BY THE BIDDER

List all contracts awarded to or won by the bidder but not yet started.

				Project & Location
				Contract Type
	•		-	Contract Amount (\$000)
		-		Date Scheduled to Start
				Owner Reference & Tel. No.
				Architect/Engineer Reference & Tel. No. if different from owner

Page 37

BID BOOKLET SEPTEMBER 2008

CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

#### OFFICE OF THE MAYOR BUREAU OF LABOR SERVICES CONTRACT CERTIFICATE

I, (fill in name of person signing)\_

hereby affirm that I am authorized by the above-named contractor to certify that said contractor's proposed contract with the above-named owner or city agency is less than \$1,000,000. This affirmation is made in accordance with Executive Order No. 50 (1980) as amended and its implementing regulations.

Date

Signature

WILLFUL OR FRAUDULENT FALSIFICATION OF ANY DATA OR INFORMATION SUBMITTED HEREWITH MAY RESULT IN THE TERMINATION OF ANY CONTRACT BETWEEN THE CITY AND THE BIDDER OR CONTRACTOR AND BAR THE BIDDER OR CONTRACTOR FROM PARTICIPATION IN ANY CITY CONTRACT FOR A PERIOD OF UP TO THREE YEARS. FURTHER, SUCH FALSIFICATION MAY RESULT IN CRIMINAL PROSECUTION.

CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

Page 38

BID BOOKLET SEPTEMBER 2008

## THIS PAGE INTENTIONALLY LEFT BLANK

## VENDEX COMPLIANCE

(A) <u>Vendex Fees</u>: Pursuant to Procurement Policy Board Rule 2-08(f)(2), the contractor will be charged a fee for the administration of the VENDEX system, including the Vendor Name Check process, if a Vendor Name Check review is required to be conducted by the Department of Investigation. The contractor shall also be required to pay the applicable required fees for any of its subcontractors for which Vendor Name Check reviews are required. The fee(s) will be deducted from payments made to the contractor under the contract. For contracts with an estimated value of less than or equal to \$1,000,000, the fee will be \$175 per Vendor Name Check review. For contracts with an estimated value of greater than \$1,000,000, the fee will be \$350 per Vendor Name Check review.

(B) <u>Confirmation of Vendex Compliance</u>: The Bidder shall submit this Confirmation of Vendex Compliance to the Department of Design and Construction, Contracts Section, 30-30 Thomson Avenue – First Floor, Long Island City, NY 11101.

Bid Information: The Bidder shall complete the bid information set forth below.

Name of Bidder:	
Bidder's Address:	
Bidder's Telephone Number:	
Bidder's Fax Number:	
Date of Bid Opening:	
Project ID:	·

<u>Vendex Compliance</u>: To demonstrate compliance with Vendex requirements, the Bidder shall complete either Section (1) or Section (2) below, whichever applies.

(1) Submission of Vendex Questionnaires to MOCS: By signing in the space provided below, the Bidder certifies that as of the date specified below, the Bidder has submitted Vendex Questionnaires to the Mayor's Office of Contract Services, Attn: VENDEX, 253 Broadway, 9<sup>th</sup> Floor, New York, New York 10007.

Date of Submission:

By: \_\_\_\_\_

(Signature of Partner or corporate officer)

Print Name:

(2) Submission of Certification of No Change to DDC: By signing in the space provided below, the Bidder certifies that it has read the instructions in a "Vendor's Guide to Vendex" and that such instructions do not require the Bidder to submit Vendex Questionnaires. The Bidder has completed TWO ORIGINALS of the Certification of No Change set forth on the next page of this Bid Booklet.

By: \_\_\_\_

(Signature of Partner or corporate officer)

Print Name: \_\_\_\_\_

CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

Page 39

BID BOOKLET SEPTEMBER 2008

# **Certificate of No Change Form**



- Please submit two completed forms. Copies will not be accepted.
- Please send both copies to the agency that requested it, unless you are advised to send it directly to the Mayor's Office of Contract Services (MOCS).
- A materially false statement willfully or fraudulently made in connection with this certification, and/or the failure to conduct appropriate due diligence in verifying the information that is the subject of this certification, may result in rendering the submitting entity non-responsible for the purpose of contract award.
- A materially false statement willfully or fraudulently made in connection with this certification may subject the person making the false statement to criminal charges

Enter Your Name

being duly sworn, state that I have read

and understand all the items contained in the vendor questionnaire and any submission of change as identified on page one of this form and certify that as of this date, these items have not changed. I further certify that, to the best of my knowledge, information and belief, those answers are full, complete, and accurate; and that, to the best of my knowledge, information, and belief, those answers continue to be full, complete, and accurate.

1,

In addition, I further certify on behalf of the submitting vendor that the information contained in the principal questionnaire(s) and any submission of change identified on page two of this form have not changed and have been verified and continue, to the best of my knowledge, to be full, complete and accurate.

I understand that the City of New York will rely on the information supplied in this certification as additional inducement to enter into a contract with the submitting entity.

# Vendor Questionnaire This section is required.

This refers to the vendor questionnaire(s) submitted for the vendor doing business with the City.

# **Principal Questionnaire**

This section refers to the most recent principal questionnaire submissions.



	Principal Name	Date of signature on last full Principal Questionnaire	Date(s) of signature on submission of change
1			
2			
3			
4	•		
5			
6			
Chec	k if additional changes were subm	nitted and attach a document with the	date of additional submissions.

# Certification This section is required.

This form must be signed and notarized. Please complete this twice. Copies will not be accepted.

## **Certified By:**

Name (Print)

Title

Name of Submitting Entity

Signature

Notarized By:

Notary Public

County License Issued

License Number

Date

Sworn to before me on: \_\_\_\_\_

Date

Mayor's Office of Contract Services 253 Broadway, 9th Floor New York, NY 10007 Phone: 212 788 0018 Fax: 212 788 0049

2

#### IRAN DIVESTMENT ACT COMPLIANCE RIDER

#### FOR NEW YORK CITY CONTRACTORS

The Iran Divestment Act of 2012, effective as of April 12, 2012, is codified at State Finance Law ("SFL") §165-a and General Municipal Law ("GML") §103-g. The Iran Divestment Act, with certain exceptions, prohibits municipalities, including the City, from entering into contracts with persons engaged in investment activities in the energy sector of Iran. Pursuant to the terms set forth in SFL §165-a and GML §103-g, a person engages in investment activities in the energy sector of Iran if:

- (a) The person provides goods or services of twenty million dollars or more in the energy sector of Iran, including a person that provides oil or liquefied natural gas tankers, or products used to construct or maintain pipelines used to transport oil or liquefied natural gas, for the energy sector of Iran; or
- (b) The person is a financial institution that extends twenty million dollars or more in credit to another person, for forty-five days or more, if that person will use the credit to provide goods or services in the energy sector in Iran and is identified on a list created pursuant to paragraph (b) of subdivision three of Section 165-a of the State Finance Law and maintained by the Commissioner of the Office of General Services.

A bid or proposal shall not be considered for award nor shall any award be made where the bidder or proposer fails to submit a signed and verified bidder's certification.

Each bidder or proposer must certify that it is not on the list of entities engaged in investment activities in Iran created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law. In any case where the bidder or proposer cannot certify that they are not on such list, the bidder or proposer shall so state and shall furnish with the bid or proposal a signed statement which sets forth in detail the reasons why such statement cannot be made. The City of New York may award a bid to a bidder who cannot make the certification on a case by case basis if:

- (1) The investment activities in Iran were made before the effective date of this section (i.e., April 12, 2012), the investment activities in Iran have not been expanded or renewed after the effective date of this section and the person has adopted, publicized and is implementing a formal plan to cease the investment activities in Iran and to refrain from engaging in any new investments in Iran: or
- (2) The City makes a determination that the goods or services are necessary for the City to perform its functions and that, absent such an exemption, the City would be unable to obtain the goods or services for which the contract is offered. Such determination shall be made in writing and shall be a public document.



## BIDDER'S CERTIFICATION OF COMPLIANCE WITH IRAN DIVESTMENT ACT

Pursuant to General Municipal Law §103-g, which generally prohibits the City from entering into contracts with persons engaged in investment activities in the energy sector of Iran, the bidder/proposer submits the following certification:

## [Please Check One]

#### **BIDDER'S CERTIFICATION**

- By submission of this bid or proposal, each bidder/proposer and each person signing on behalf of any bidder/proposer certifies, and in the case of a joint bid each party thereto certifies as to its own organization, under penalty of perjury, that to the best of its knowledge and belief, that each bidder/proposer is not on the list created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law.
- I am unable to certify that my name and the name of the bidder/proposer does not appear on the list created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law. I have attached a signed statement setting forth in detail why I cannot so certify.

Dated:

\_\_\_\_, New York

SIGNATURE

PRINTED NAME

Sworn to before me this \_\_\_\_\_ day of \_\_\_\_, 20

TITLE

Notary Public

Dated:

## **PROJECT ID: JOCS\_DDC**

## SCHEDULE A (FOR PUBLICLY BID PROJECTS)

## PART I. REQUIRED INFORMATION

Bid Booklet -Attachment 1 The Contractor shall obtain a bid security in the amount indicated to the right.	\$15,000.00
INFORMATION FOR BIDDERS PERFORMANCE AND PAYMENT BONDS The Contractor shall obtain performance and payment	See Bid Booklet- Attachment 1 - Bid information
bonds in the amount indicated to the right. CONTRACT ARTICLE 14.	_1095_consecutive calendar days
DATE FOR COMPLETION The Contractor shall complete the Work in the number of calendar days indicated to the right.	One 2 year (730 CCD) renewal option - See Article 1.3.3, subparagraph c of Contract
<u>CONTRACT ARTICLE 15.</u> <u>LIQUIDATED DAMAGES</u> If the Contractor fails to complete the Work within the time fixed for completion plus authorized time extensions or if the Contractor, in the sole determination of the Commissioner, has abandoned the Work, the Contractor shall pay to the City the amount indicated to the right.	<b>\$500</b> for each consecutive calendar day over completion time for each Job Order
CONTRACT ARTICLE 17. SUB-CONTRACTOR The Contractor shall not make subcontracts totaling an amount more than the percentage of the total Contract price indicated to the right.	Not to exceed85% of the Contract price
CONTRACT ARTICLE 21. RETAINAGE The Commissioner shall deduct and retain until the completion of the Work the percent value of the Work indicated to the right.	5% or10% of the value of the Work See Article 21

# PROJECT ID: JOCS\_DDC

See Schedule A – General Conditions Relating to Article 22 – Insurance.
_1_ % of Job Order price
1 Year(s)
See Article 74.1
Amount for which the Contract was awarded:
Not to Exceed \$_8,000,000.00

## **PROJECT ID: JOCS\_DDC**

## SCHEDULE A (FOR PUBLICLY BID PROJECTS)

## **Relating to Article 22 - Insurance**

## PART II. Types of Insurance, Minimum Limits and Special Conditions

<u>Note</u>: All certificate(s) of insurance submitted pursuant to Contract Article 22.3.3 must be accompanied by a Certification by Broker consistent with Part III below and include the following information:

- For each insurance policy, the name and NAIC number of issuing company, number of policy, and effective dates;
- Policy limits consistent with the requirements listed below;
- Additional insureds or loss payees consistent with the requirements listed below; and
- The number assigned to the Contract by the City (in the "Description of Operations" field).

## Insurance indicated by a blackened box (m) or by (X) in the to left will be required under this contract.

Types of Insurance (per Article 22 in its entirety, including listed paragraph)	Minimum Limits and Special Conditions		
■Commercial General Liability Art. 22.1.1	The minimum limits shall be \$1,000,000.00 per occurrence and \$2,000,000.00 per project aggregate applicable to this <b>Contract.</b>		
	Additional Insureds: 1. City of New York, including its officials and employees, with coverage at least as broad as ISO Forms CG 20 10 and CG 20 37, and		
	2. All person(s) or organization(s), if any, that Article 22.1.1(b) of the <b>Contract</b> requires to be named as Additional Insured(s),with coverage at least as broad as ISO Form CG 20 26. The Additional Insured endorsement shall either specify the entity's name, if known, or the entity's title (e.g., Project Manager).		
	3		
Workers' Compensation Art. 22.1.2	Workers' Compensation, Employers' Liability, and Disability Benefits Insurance: Statutory per New York State law without regard to jurisdiction.		
Disability Benefits Insurance Art. 22.1.2			
Employers' Liability Art. 22.1.2	Note: The following forms are acceptable: (1) New York State Workers' Compensation Board Form No. C-		
□ Jones Act Art. 22.1.3	105.2, (2) State Insurance Fund Form No. U-26.3, (3) New York State Workers' Compensation Board Form No. DB-120.1 and (3) Request for WC/DB Exemption		
<ul> <li>U.S. Longshoremen's and Harbor Workers Compensation Act Art. 22.1.3</li> </ul>	Form No. CE-200. The City will not accept an ACORD form as proof of Workers' Compensation or Disability Insurance.		
	Jones Act and U.S. Longshoremen's and Harbor Workers' Compensation Act: Statutory per U.S. law.		

# SCHEDULE A (FOR PUBLICLY BID PROJECTS)

#### **Relating to Article 22 - Insurance**

# PART II. Types of Insurance, Minimum Limits and Special Conditions

# Insurance indicated by a blackened box (=) or by (X) in the to left will be required under this contract.

Types of Insurance (per Article 22 in its entirety, including listed paragraph)	Minimum Limits and Special Conditions
■Builders' Risk Art. 22.1.4	100 % of total value of <b>Work</b>
	<b>Contractor</b> the Named Insured; the <b>City</b> both an Additional Insured and one of the loss payees as its interests may appear.
Art. 22.1.9	If the <b>Work</b> does not involve construction of a new building or gut renovation work, the <b>Contractor</b> may provide an installation floater in lieu of Builders Risk insurance.
	Note: Builders Risk Insurance may terminate upon Substantial Completion of the Work in its entirety
■Commercial Auto Liability Art. 22.1.5	\$1,000,000.00 per accident combined single limit If vehicles are used for transporting hazardous materials, the <b>Contractor</b> shall provide pollution liability broadened coverage for covered vehicles (endorsement CA 99 48) as well as proof of MCS 90
□ Contractor's Pollution Liability Art. 22.1.6	<pre>\$ per occurrence \$ aggregate Additional Insureds: 1. City of New York, including its officials and employees, and 2</pre>
Marine Protection and Indemnity Art. 22.1.7(a)	3 per occurrence \$ aggregate
	Additional Insureds: 1. City of New York, including its officials and employees, and 2 3

#### SCHEDULE A (FOR PUBLICLY BID PROJECTS) Relating to Article 22 - Insurance

#### PART II. Types of Insurance, Minimum Limits and Special Conditions (Continued)

### Insurance indicated by a blackened box (s) or by (X) in the to left will be required under this contract.

Types of Insurance (per Article 22 in its entirety, including listed paragraph)	Minimum Limits and Special Conditions
Hull and Machinery Insurance Art. 22.1.7(b)	per occurrence
	<ul> <li>\$aggregate</li> <li>Additional Insureds:</li> <li>1. City of New York, including its officials and employees, and</li> <li>2</li> <li>3</li> </ul>
□ Marine Pollution Liability Art. 22.1.7(c)	<pre>\$each occurrence Additional Insureds: 1. City of New York, including its officials and employees, and 2</pre>
[OTHER] Art. 22.1.8	\$each occurrence
[OTHER] Art. 22.1.8	\$ per occurrence
	<pre>\$aggregate Additional Insureds: 1. City of New York, including its officials and employees, and 2 3</pre>
[OTHER] Art. 22.1.8	\$ per occurrence
Railroad Protective Liability	\$aggregate
	Additional Insureds: 1. City of New York, including its officials and employees, and 2 3

SC-5

#### SCHEDULE A (FOR PUBLICLY BID PROJECTS) Relating to Article 22 - Insurance PART II. Types of Insurance, Minimum Limits and Special Conditions (Continued)

## Insurance indicated by a blackened box ( $\blacksquare$ ) or by (X) in the $\Box$ to left will be required under this contract.

[OTHER] Art. 22.1.8	Only required of the Contractor or Subcontractor performing any required asbestos removal.
Asbestos Liability	
	\$1,000,000 each occurrence,
	\$2,000,000 aggregate (Combined Single Limit); only required of the Contractor or Subcontractor performing any required asbestos removal.
	Additional Insureds: 1. City of New York, including its officials and employees, and
	2 3
[OTHER] Art. 22.1.8	
Boiler Insurance	\$200,000
[OTHER] Art. 22.1.8	\$1,000,000 per occurrence
■Professional Liability In the event any section of the Specifications requires the Contractor to engage a Professional Engineer to provide design and/or engineering services, the Engineer engaged by the Contractor, as well as any sub consultant(s) performing professional services, shall provide Professional Liability Insurance.	assumed by the Contractor under this Agreement arising out of the negligent performance of professional services or caused by an error, omission or negligent act of the
	Claims-made policies will be accepted for Professional Liability Insurance. All such policies shall have an extended reporting period option or automatic coverage of not less than two (2) years. If available as an option, the Contractor's Professional Engineer shall purchase extended reporting period coverage effective on cancellation or termination of such insurance unless a new policy is secured with a retroactive date, including at least the last policy year.

#### SCHEDULE A (FOR PUBLICLY BID PROJECTS) Relating to Article 22 - Insurance PART III. Broker's Certification

[Pursuant to Article 22.3.3 of the **Contract**, every Certificate of Insurance must be accompanied by either the following certification by the broker setting forth the following text and required information and signatures or certified copies of all policies referenced in the Certificate of Insurance.]

#### **CERTIFICATION BY BROKER**

The undersigned insurance broker represents to the City of New York that the attached Certificate of Insurance is accurate in all material respects, and that the described insurance is effective as of the date of this Certification.

[Name of broker (typewritten)]

[Address of broker (typewritten)]

[Email address of broker (typewritten)]

[Phone number/Fax number of broker (typewritten)]

[Signature of authorized official or broker]

[Name and title of authorized official (typewritten)]

State of .....) ) ss: County of .....)

Sworn to before me this

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_

NOTARY PUBLIC FOR THE STATE OF\_\_\_\_



#### SCHEDULE A (FOR PUBLICLY BID PROJECTS)

#### **Relating to Article 22 - Insurance**

#### PART IV. Address of Commissioner

Wherever reference is made in Article 7 or Article 22 to documents to be sent to the **Commissioner** (e.g., notices, filings, or submissions), such documents shall be sent to the address set forth below or, in the absence of such address, to the **Commissioner's** address as provided elsewhere in this **Contract**.

ACCO's Office, Insurance Unit

30-30 Thomson Avenue, 4<sup>th</sup> Floor

Long Island City, New York11101

ير . معري and a straight of the second secon Second second

en de Service de Carlos de Carl Carlos de C

and a second A second secon

PROJECT ID:	JOCS_DDC	and the
PROJECT NO.	JOC2013E-2	

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF PUBLIC BUILDINGS

30-30 THOMSON AVENUE TELEPHONE (718) 391-1000

LONG ISLAND CITY, NEW YORK 11101-3045 WEBSITE www.nyc.gov/buildnyc

Contract for Furnishing all Labor and Material Necessary and Required for:

# **JOB ORDER CONTRACT**

Contractor	
Dated	, 20
Aprroved as to Form Certified as to Legal Authority	
Acting Coporation Counsel	
Date	, 20
intered in the Comptroller's Office	
irst Assistant Bookkeeper	
ated	, 20
	6-02



PROJECT ID: PROJECT NO:

JOCS\_DDC JOC2013E-2

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF PUBLIC BUILDINGS

30-30 THOMSON AVENUE LONG ISLAND CITY, NEW YORK 11101-3045 TELEPHONE (718) 391-1000 WEBSITE www.nyc.gov/buildnyc

# VOLUME 2 OF 2 PROJECT LABOR AGREEMENT INFORMATION FOR BIDDERS CONTRACT PERFORMANCE AND PAYMENT BONDS SCHEDULE OF PREVAILING WAGES GENERAL CONDITIONS

FOR FURNISHING ALL LABOR AND MATERIALS NECESSARY AND REQUIRED FOR THE PROJECT

JOB ORDER CONTRACT - ELECTRICAL WORK -BOROUGH OF BROOKLYN & STATEN ISLAND (EXCEPT: COURTS, CORRECTION & JUVENILE DETENTION PROJECTS)

LOCATION: BOROUGH: CITY OF NEW YORK

CONTRACT: PIN NUMBER: Boro Wide Boro Wide

ELECTRIC WORK E-2 8502016RQ0007C



Date:

September 1, 2015

of the annualized value of the private benefit plans will be paid to workers as additional wages in compliance with Labor Law 220. At the time of contract award, the Contractor shall make available to the contracting Agency a complete set of plan documents for each private benefit plan into which contributions will be made and/or coverage provided. The Contractor shall also provide certification from a certified public accountant as to the annualized hourly value of such benefits consistent with the requirements of Section 220. See PLA Article 11, Section 2.

What happens if a Contractor or subcontractor fails to make a required payment to 11. **O.** a designated employee benefit fund?

The PLA sets forth a process for unions to address a contractor or a subcontractor's failure to make required payments. The process includes potentially the A. direct payment by the City to the benefit fund of monies owed and the corresponding withholding of payments to the Contractor. See PLA Article 11, Section 2.

Upon notification by a union or fringe benefit fund that a Contractor is delinquent in its payment of benefits and a determination by the Agency that the union or fund has submitted appropriate documentation of such delinquency, the Agency will thereafter require the Contractor to submit cancelled checks or other equivalent proof of payment of benefit contributions with certified payroll reports for work covered by this PLA on which the Contractor is engaged.

The City strongly advises Contractors to read these provisions carefully and to include appropriate provisions in subcontracts addressing these possibilities.

Does signing on to the PLA satisfy the Apprenticeship Requirements established 12. Q. for this bid?

Yes. By agreeing to perform the Work subject to the PLA, the bidder demonstrates compliance with the apprenticeship requirements imposed by this Invitation for Bids.

Who decides on the number of workers needed? 13. Q.

Except as expressly limited by a specific provision of the PLA, a Contractor retains full and exclusive authority for the management of their operations, including the determination as to the number of employees to be hired and the qualifications therefore and the promotion, transfer, and layoff of its employees. See PLA Article 6, Section 1.

May a contractor discharge a union referral for lack of productivity? 14. Q. Again, except as expressly limited by a specific provision of the PLA, a Contractor retains full and exclusive authority for the management of their operations, including the right to discipline or discharge for just cause its employees. See PLA Article 6, Section 1.

May a contractor assign a management person to site? 15. Q.

A. Yes. Managers are not subject to the provisions of the PLA, so there is no restriction on management and/or other non-trade personnel, as long as such personnel do not perform trade functions. See Article 3, Section 1.

- 16. Q. Does the PLA provide a standard work day across all the signatory trades? A. Yes, all signatory trades will work an eight (8) hour day. Monday through Friday with a day shift at straight time as the standard work week. The PLA also permits a Contractor to schedule a four day (within Monday through Friday) work week, ten (10) hours per day at straight time if announced at the commencement of the project. See PLA Article 12, Section 1. This is an example where the terms of the PLA override provisions of the Standard Construction Contract (compare with section 37.2 of the Standard Construction Contract). The standard work week may be reduced to 35 or 37 ½ hours of work in those limited circumstances where the City states in the bid documents that the Contractor will not be given access to the site to accommodate an 8 hour day. The 8 hour, 7 ½ hour or 7 hour work day must be established at the commencement of the project and may not be altered by the Contractor.
- Does the PLA create a common holiday schedule for all the signatory trades?
   A. Yes, the PLA recognizes nine (9) common holidays, including Veterans Day. See PLA Article 12, Section 4.
- 18. Q. Does the PLA provide for a standard policy for 'shift work' across all signatory trades?

A. Yes, second and third shifts may be worked with a standard 5% premium pay. In addition, a day shift does not have to be scheduled in order to work the second and third shifts at the 1.05 hourly pay rate. See PLA Article 12, Section 3.

19. Q. May the Contractor schedule overtime work, including work on a weekend?
A. Yes, the PLA permits the Contractor to schedule overtime work, including work on weekends. See PLA Article 12, Sections 2, 3, and 5. To the extent that the Agency's approval is required before a Contractor may schedule or be paid for overtime, that approval is still required notwithstanding the PLA language.

20. Q. Are overtime payments affected by the PLA?

A. Yes, all overtime pay incurred Monday through Saturday will be at time and one half  $(1 \frac{1}{2})$ . There will be no stacking or pyramiding of overtime pay under any circumstances. See PLA Article 12, Section 2. Sunday and holiday overtime will be paid according to each trade's CBA.

21. Q. Are there special provisions for Saturday work when a day is 'lost' during the week due to weather, power failure or other emergency?

A. Yes, when this occurs the Contractor may schedule Saturday work at weekday rates. See PLA Article 12, Section 5.

22. Q. Does the PLA contain special provisions for the manning of Temporary Services?



2015 Renovation PLA

- 7 -

**A.** Yes. Where temporary services are required by specific request of the Agency or construction manager, they shall be provided by the Contractor's existing employees during working hours in which a shift is scheduled for employees of the Contractor. The need for temporary services during non-working hours will be determined by the Agency or construction manager. There will be no stacking of trades on temporary services. See PLA Article 15.

23. Q. What do the workers get paid when work is terminated early in a day due to inclement weather or otherwise cut short of 8 hours?

A. The PLA provides that employees who report to work pursuant to regular schedule and not given work will be paid two hours of straight time. Work terminated early for severe weather or emergency conditions will be paid only for time actually worked. In other instances where work is terminated early, the worker will be paid for a full day. See PLA Article 12, Sections 6 and 8. The usual reporting pay requirement of two hours for employees who report to their work location pursuant to their regular schedule does not apply when the National Weather Service issues a Weather Advisory and the Contractor speaks to the employee at least four hours before their shift starting time. See PLA Article 12, Section 6.

24. Q. Should a local collective bargaining agreement of a signatory union expire during the project will a work stoppage occur on a project subject to the PLA?
A. No. All the signatory unions are bound by the 'no strike' agreement as to the PLA work. Work will continue under the PLA and the otherwise expired local CBA(s) until the new local CBA(s) are negotiated and in effect. See PLA Articles 7 and 19.

25. Q. May a Contractor working under the PLA be subject to a strike or other boycott activity by a signatory union at another site while the Contractor is a signatory to the PLA?

**A.** Yes. The PLA applies ONLY to work under the PLA and does not regulate labor relations at other sites even if those sites are in close proximity to PLA work.

26. Q. If a Contractor has worked under other PLAs in the New York City area, are the provisions in this PLA generally the same as the others?

A. While Project Labor Agreements often look similar to each other, and particular clauses are often used in multiple agreements, each PLA is a unique document and should be examined accordingly.

27. Q. What happens if a dispute occurs between the Contractor and an employee during the project?

A. The PLA contains a grievance and arbitration process to resolve disputes between the Contractor and the employees. See PLA Article 9.

28. Q. What happens if there is a dispute between locals as to which local gets to provide employees for a particular project or a particular aspect of a project?

**A.** The PLA provides for jurisdictional disputes to be resolved in accordance with the NY Plan. See PLA Article 10. A copy of the NY Plan is available upon request from the

2015 Renovation PLA

Department. The PLA provides that work is not to be disrupted or interrupted pending the resolution of any jurisdictional dispute. The work proceeds as assigned by the Contractor until the dispute is resolved. See PLA Article 10, Section 3.

29. Q. Does the 2015 Renovation PLA contain special provisions for JOCS or task order based Contracts?

A. The PLA does not apply to Task Orders or Work Orders that do not exceed \$10,000 issued under JOCS or Requirements Contracts otherwise subject to the PLA. See PLA Article 3, Section 1.

# **NYC Project Labor Agreements**

CONTACT INFORMATION FOR LOCAL UNIONS

### **BOILER MAKERS LOCAL NO. 5**

24 Van Siclen Avenue Floral Park, NY 11001 Phone: (516) 326-2500 Fax: (516) 326-3435 Business Manager: Steve Ludwigson

# **BLASTERS & DRILLERS LOCAL NO. 29**

43-12 Ditmars Blvd. Astoria, NY. 11105 Phone: (718) 278-5800 Business Manager: Thomas Russo

#### **BRICKLAYERS LOCAL NO. 1**

4 Court Square #1 Long Island City, NY 11101 Phone: (718) 392-0525 Business Manager: Jeramiah Sullivan

# CARPENTERS DISTRICT COUNCIL

395 Hudson Street, 9th Fl New York, New York 10014 Phone: (212) 366-7500 Fax: (212) 675-3140 Business Manager: Joe Geiger John Sheehy, D.C. Rep.

#### **CEMENT MASONS NO. 780**

150-50 14th Rd Suite 4 Whitestone, NY 11357 Phone: (718) 357-3750 Fax: (718) 357-2057 Business Manager: Gino Castingnoli

#### CONCRETE WORKERS **DISTRICT COUNCIL NO. 16**

29-18 35th Avenue Long Island City, NY 11106 Phone: (718) 392-5077 Fax: (718) 392-5087 Business Manager: Alex Castaldi

# DERRICKMEN AND RIGGERS LOCAL 197

35-53 24th Street Long Island City, NY 11101 Phone: (718) 361-6534 Fax: (718) 361-6584 William Hayes Bus. Manager Billhayes197@yahoo.com

## **DRYWALL TAPERS 1974**

265 West 14th Street New York, NY 10011 Phone: (212) 242-8500 Fax: (212) 242-2356 Business Manager: Sal Marsala

## **ELECTRICAL LOCAL NO. 3**

158-11 Harry Van Arsdale, Jr. Avenue Flushing, NY 11365 Phone: (718) 591-4000 Fax: (718) 380-8998 Business Manager: Chris Erickson Raymond Melville, Asst. Bus. Mgr. Construction

# **ELEVATOR CONSTRUCTORS NO. 1**

47-24 27th Avenue Long Island City, NY 11101 Phone: (718) 767-7004 Fax: (718) 767-6730 Business Manager: Lenny Legotte Ilegotte@localoneiuec.com

## **ENGINEERS LOCAL UNION NO. 14**

141-57 Northern Boulevard Flushing, NY 11354 Phone: (718) 939-0600 Fax: (718) 939-3131 Business Manager: Edwin Christian

# ENGINEERS NO. 15, 15A, 15B, 15C, 15D

265 West 14th Street New York, NY 10011 Phone: (212) 929-5327-8-9 Fax: (718) 729-3070 Business Manager: Tom Callahan

#### **ENGINEERS NO. 30**

115-06 Myrtle Avenue Richmond Hill, NY 11418 Phone: (718) 847-8484 Fax: (718) 850-0524 Business Manager: William Lynn

#### ENGINEERS No. 94

331-337 West 44th Street New York, NY 10036 Phone: (212) 245-7040 Fax: (212) 245-7886 Business Manager: Kuba Brown kubabrown@local94.com

#### **GLAZIERS NO. 1087**

45 West 14th Street New York, NY 10011 Phone: (212) 924-5200 Fax: (212) 255-1151 Business Manager: Joseph Azzopardi

#### HEAT & FROST INSULATORS AND ALLIED WORKERS LOCAL UNION NO. 12

35-53 24th Street Long Island City, NY 11101 Phone: (718) 784-3456 Fax: (718) 784-8357 Business Manager: Matty Aracich matty@insulatorslocal12.com

#### HEAT & FROST INSULATORS LOCAL UNION NO. 12A

1536 127th Street College Point. NY 11356 Phone: (718) 886-7226 Business Manager: Jaime Soto

#### **IRON WORKERS DISTRICT**

505 White Plains Road, Suite 200 Tarrytown, NY 10591 Phone: (914) 332-4430 Fax: (914) 332-4431 Business Manager: Edward Walsh iwnys@verizon.net

# IRON WORKERS NO. 40 (Manhattan, The Bronx & Staten Island)

451 Park Avenue South New York, NY 10016 Phone: (212) 889-1320 Fax: (212) 779-3267 Business Manager: Bob Walsh

# IRON WORKERS NO. 361 (Brooklyn & Queens)

89-19 97tH Avenue Ozone Park, NY 11416 Phone: (718) 322-1016-17 Fax: (718) 322-1053 Business Manager: Matthew Chartrand

### LABORERS LOCAL NO. 78 ASBESTOS & LEAD ABATEMENT

30 Cliff Street New York, New York 10038-2825 Phone: (212) 227-4803 Fax: (212) 406-1800 Business Manager: Edison Severino

#### LABORERS, CONSTRUCTION AND GENERAL BUILDING NO. 79 520 8th Avenue

New York, NY 10018 Phone: (212) 465-7900 Fax: (212- 465-7903 Business Manager: Michael Prohaska

#### LABORERS NO. 731

34-11 35th Avenue Astoria, NY 11106 (718) 706-0720 Business Manager: Joseph D'Amato

#### LATHERS METAL LOCAL NO. 46

1322 Third Avenue New York, NY 10021 Phone: (212) 737-0500 Fax: (212) 249-1226 Business Manager: Terrance Moore

#### MASON TENDERS DIST. COUNCIL

520 8th Avenue New York, NY 10018 Phone: (212) 452-9400 Fax: (212) 452-9499 Business Manager: Robert Bonanza

#### METAL POLISHERS

LOCAL UNION NO. 8A 36-18 33rd Street 2nd Fl. Long Island City, 11106 Phone: (718) 361-1770 Fax: (718) 361-1934 Business Manager: Hector Lopez

## MILLWRIGHT AND MACHINERY

ERECTORS LOCAL NO. 740 89-07 Atlantic Avenue Woodhavaen, NY 11412 Phone: (718) 849-3636 Fax: (718) 849-0070 Business Manager: Joseph Geiger

#### ORNAMENTAL IRON WORKERS NO. 580

501 West 42nd Street New York, NY 10036 Phone: (212) 594-1662 Fax: (212) 564-2748 Business Manager: Pete Myers

#### PAINTERS DISTRICT COUNCIL NO. 9

45 West 14th Street New York, NY 10011 Phone: (212) 255-2950 Fax: (212) 255-1151 Business Manager: Joseph Ramaglia

#### PAINTERS STRUCTURAL STEEL NO. 806

40 West 27th Street New York, New York 10001 Phone: (212) 447-1838/0149 Fax: (212) 545-8386 Business Manager: Angelo Serse

#### PAVERS & ROAD BUILDERS DISTRICT COUNCIL NO. 1

136-25 37m Avenue, Suite 502 Flushing, NY 11354 Phone: (718) 779-8850 Fax: (718) 779-8857 Business Manager: Keith Lozcalzo

#### PLASTERS LOCAL UNION NO. 262

2241 Conner Street Bronx, NY 10466 Phone: (718) 547-5440 Fax: (718) 547-5435 Business Manager: Michael Hubler

#### **PLUMBERS NO. 1**

158-29 Cross Bay Boulevard Howard Beach, NY 11414 Phone: (718) 738-7500 Fax: (718) 835-0896 Business Manager: John Murphy

#### PRIVATE SANITATION LOCAL NO. 813

45-18 Court Sq., Suite 600 Long Island City, NY 11101 Phone: (718) 937-7010 Fax: (718) 937-7003 Business Manager: Sean Campbell

## **ROOFERS & WATERPROOFERS NO. 8**

12-11 43<sup>rd</sup> Avenue Long Island City, NY 11101 Phone: (718) 361-1169 Fax (718) 361-8330 Business Manager: Nick Siciliano

#### SHEET METAL WORKERS LOCAL NO. 28

MANHATTAN OFFICE 500 Greenwich Street New York, NY 10013 Phone: (212) 941-7700 Fax: (212) 226-0304 Business Manager: Robert D'Orio

#### SHEET METAL WORKERS

LOCAL 137 21-42 44th Drive Long Island City, NY 11101 Phone: (718)) 937-4514 Fax: (718) 937-4113 Business Manager: Dante Dano

# STEAMFITTERS LOCAL UNION NO. 638

32-32 48th Avenue Long Island City, NY 11101 Phone: (718) 392-3420 Fax: (718) 784-7285 Business Manager: Richard Roberts

### **TEAMSTERS LOCAL UNION 282**

2500 Marcus Avenue Lake Success, NY 11042 Phone: (516) 488-2822 Fax: (516) 488-4895 Business Manager: Tom Gesauldi

## **TEAMSTERS LOCAL UNION 814**

21-42 44<sup>th</sup> Drive Long Island City, NY 11101 Phone: (718) 609-6407 Fax: (718) 361-9610 Business Manager: Jason Ide

### TILE, MARBLE & TERRAZO B.A.C. LOCAL UNION 7

45-34 Court Square Long Island City, NY 11101 Phone: (718) 786-7648 Fax: (718) 472-2370 Business Manager: Tom Lane

#### **TIMBERMEN LOCAL 1556**

395 Hudson Street New York, NY 10014 Phone: (212) 242-1320 Business Manager: Joseph Geiger

# PROJECT LABOR AGREEMENT

# **COVERING SPECIFIED**

# RENOVATION & REHABILITATION OF CITY OWNED BUILDINGS AND STRUCTURES

2015 - 2018



## TABLE OF CONTENTS

	Page
ARTICLE 1 - PREAMBLE	
SECTION 1. PARTIES TO THE AGREEMENT	2
ARTICLE 2 - GENERAL CONDITIONS	
SECTION 1. DEFINITIONS	3
SECTION 2. CONDITIONS FOR AGREEMENT TO BECOME EFFECTIVE	4
SECTION 3. ENTITIES BOUND & ADMINISTRATION OF AGREEMENT	4
SECTION 4. SUPREMACY CLAUSE	4
SECTION 5. LIABILITY	5
SECTION 6. THE AGENCY	6
SECTION 7. AVAILABILITY AND APPLICABILITY TO ALL SUCCESSFUL BIDDERS	6
SECTION 8. SUBCONTRACTING	
ARTICLE 3-SCOPE OF THE AGREEMENT	7
SECTION 1. WORK COVERED	7
SECTION 2. TIME LIMITATIONS	9
SECTION 3. EXCLUDED EMPLOYEES	9
SECTION 4. NON-APPLICATION TO CERTAIN ENTITIES	
ARTICLE 4- UNION RECOGNITION AND EMPLOYMENT	
SECTION 1. PRE-HIRE RECOGNITION	

SECTION 2. UNION REFERRAL 12
SECTION 3. NON-DISCRIMINATION IN REFERRALS
SECTION 4: MINORITY AND FEMALE REFERRALS
SECTION 5. CROSS AND QUALIFIED REFERRALS
SECTION 6. UNION DUES
SECTION 7. CRAFT FOREPERSONS AND GENERAL FOREPERSONS 16
SECTION 8. ON CALL REPAIR REFERRALS
ARTICLE 5- UNION REPRESENTATION
SECTION 1. LOCAL UNION REPRESENTATIVE
SECTION 2. STEWARDS
SECTION 3. LAYOFF OF A STEWARD
ARTICLE 6- MANAGEMENT'S RIGHTS
SECTION 1. RESERVATION OF RIGHTS
SECTION 2. MATERIALS, METHODS & EQUIPMENT
ARTICLE 7- WORK STOPPAGES AND LOCKOUTS
SECTION 1. NO STRIKES-NO LOCK OUT
SECTION 2. DISCHARGE FOR VIOLATION
SECTION 3. NOTIFICATION
SECTION 4. EXPEDITED ARBITRATION
SECTION 5. ARBITRATION OF DISCHARGES FOR VIOLATION
ARTICLE 8 - LABOR MANAGEMENT COMMITTEE

SECTION 1. SUBJECTS	. 25
SECTION 2. COMPOSITION	. 25
ARTICLE 9- GRIEVANCE & ARBITRATION PROCEDURE	. 26
SECTION 1. PROCEDURE FOR RESOLUTION OF GRIEVANCES	. 26
SECTION 2. LIMITATION AS TO RETROACTIVITY	. 29
SECTION 3. PARTICIPATION BY AGENCY AND/OR CONSTRUCTION MANAGER	. 29
ARTICLE 10 - JURISDICTIONAL DISPUTES	. 30
SECTION 1. NO DISRUPTIONS	. 30
SECTION 2. ASSIGNMENT	30
SECTION 3. NO INTERFERENCE WITH WORK	30
ARTICLE 11 - WAGES AND BENEFITS	31
SECTION 1. CLASSIFICATION AND BASE HOURLY RATE	31
SECTION 2. EMPLOYEE BENEFITS	31
ARTICLE 12- HOURS OF WORK, PREMIUM PAYMENTS,	37 37
SECTION 1. WORK WEEK AND WORK DAY	37
SECTION 2. OVERTIME	, 38
SECTION 3. SHIFTS	39
SECTION 4. HOLIDAYS	40
SECTION 5. SATURDAY MAKE-UP DAYS	40
SECTION 6. REPORTING PAY	41
SECTION 7. PAYMENT OF WAGES	42

SECTION 8. EMERGENCY WORK SUSPENSION
SECTION 9. INJURY/DISABILITY
SECTION 10. TIME KEEPING
SECTION 11. MEAL PERIOD
SECTION 12. BREAK PERIODS
ARTICLE 13 - APPRENTICES
SECTION 1. RATIOS
ARTICLE 14-SAFETY PROTECTION OF PERSON AND PROPERTY
SECTION 1. SAFETY REQUIREMENTS
SECTION 2. CONTRACTOR RULES
SECTION 3. INSPECTIONS
ARTICLE 15 - TEMPORARY SERVICES
ARTICLE 16 - NO DISCRIMINATION
SECTION 1. COOPERATIVE EFFORTS
SECTION 2. LANGUAGE OF AGREEMENT
ARTICLE 17- GENERAL TERMS
SECTION 1. PROJECT RULES
SECTION 2. TOOLS OF THE TRADE
SECTION 3. SUPERVISION
SECTION 4. TRAVEL ALLOWANCES
SECTION 5. FULL WORK DAY
40

Execution Copy 2015-2018

iv

SECTION 6. COOPERATION AND WAIVER	48
ARTICLE 18. SAVINGS AND SEPARABILITY	49
SECTION 1. THIS AGREEMENT	. 49
SECTION 2. THE BID SPECIFICATIONS	. 49
SECTION 3. NON-LIABILITY	. 50
SECTION 4. NON-WAIVER	. 50
ARTICLE 19 - FUTURE CHANGES IN SCHEDULE A AREA CONTRACTS	. 51
SECTION 1. CHANGES TO AREA CONTRACTS	., 51
SECTION 2. LABOR DISPUTES DURING AREA CONTRACT NEGOTIATIONS	51
ARTICLE 20 - WORKERS' COMPENSATION ADR	52
SECTION 1	52
ARTICLE 21 - HELMETS TO HARDHATS	52
SECTION 1.	52
SECTION 2.	52
Project Labor Agreement Letter of Assent	96
New York City Building And Construction Trades Council Standards of Excellence	98

### PROJECT LABOR AGREEMENT COVERING SPECIFIED RENOVATION & REHABILITATION OF NEW YORK CITY OWNED FACILITIES & STRUCTURES

#### ARTICLE 1 - PREAMBLE

WHEREAS, the City of New York desires to provide for the cost efficient,

safe, quality, and timely completion of certain rehabilitation and renovation work ("Program Work," as defined in Article 3) in a manner designed to afford the lowest costs to the Agencies covered by this Agreement, and the Public it represents, and the advancement of permissible statutory objectives;

WHEREAS, this Project Labor Agreement will foster the achievement of

these goals, inter alia, by:

(1) providing a mechanism for responding to the unique construction needs associated with this Program Work and achieving the most cost effective means of construction, including direct labor cost savings, by the Building and Construction Trades Council of Greater New York and Vicinity and the signatory Local Unions and their members waiving various shift and other hourly premiums and other work and pay practices which would otherwise apply to Program Work;

(2) expediting the construction process and otherwise minimizing the disruption to the covered Agencies' ongoing operations at the facilities that are the subject of the Agreement;

(3) avoiding the costly delays of potential strikes, slowdowns, walkouts, picketing and other disruptions arising from work disputes, reducing jobsite friction on common situs worksites, and promoting labor harmony and peace for the duration of the Program Work;

(4) standardizing the terms and conditions governing the employment of labor on Program Work;

(5) permitting wide flexibility in work scheduling and shift hours and times to allow maximum work to be done during off hours yet at affordable pay rates;

1

(6) permitting adjustments to work rules and staffing requirements from those which otherwise might obtain;

(7) providing comprehensive and standardized mechanisms for the settlement of work disputes, including those relating to jurisdiction;

- (8) ensuring a reliable source of skilled and experienced labor; and
- (9) securing applicable New York State Labor Law exemptions.

WHEREAS, the Building and Construction Trades Council of Greater New

York and Vicinity, its participating affiliated Local Unions and their members, desire to assist the City in meeting these operational needs and objectives as well as to provide for stability, security and work opportunities which are afforded by this Project Labor Agreement; and

WHEREAS, the Parties desire to maximize Program Work safety conditions for both workers and the community in the project area.

NOW, THEREFORE, the Parties enter into this Agreement:

#### SECTION 1. PARTIES TO THE AGREEMENT

This is a Project Labor Agreement ("Agreement") entered into by the City of New York, on behalf of itself and the Agencies covered herein, including in their capacity as construction manager of covered projects and/or on behalf of any third party construction manager which may be utilized, and the Building and Construction Trades Council of Greater New York and Vicinity ("Council") (on behalf of itself) and the signatory affiliated Local Union's ("Unions" or "Local Unions"). The Council and each signatory Local Union hereby warrants and represents that it has been duly authorized to enter into this Agreement.

2

# **ARTICLE 2 - GENERAL CONDITIONS**

## SECTION 1. DEFINITIONS

Throughout this Agreement, the various Union parties including the Building and Construction Trades Council of Greater New York and Vicinity and its participating affiliated Local Unions, are referred to singularly and collectively as "Union(s)" or "Local Unions"; the term "Contractor(s)" shall include any Construction Manager, General Contractor and all other contractors, and subcontractors of all tiers engaged in Program Work within the scope of this Agreement as defined in Article 3; "Agency" means the following New York City agencies: the Department for the Aging (DFTA), Administration for Children's Services (ACS). Department of Citywide Administrative Services (DCAS), Department of Correction (DOC). Department of Design and Construction (DDC), Fire Department (FDNY), Department of Homeless Services (DHS), Human Resources Administration (HRA). Department of Health and Mental Hygiene (DOHMH), Department of Parks and Recreation (DPR), Police Department (NYPD); Department of Sanitation (DSNY); the New York City Agency that awards a particular contract subject to this Agreement may be referred to hereafter as the "Agency"; when an Agency acts as Construction Manager, unless otherwise provided, it has the rights and obligations of a "Construction Manager" in addition to the rights and obligations of an Agency; the Building and Construction Trades Council of Greater New York and Vicinity is referred to as the ["BCTC" or "Council"]; and the work covered by this Agreement (as defined in Article 3) is referred to as "Program Work."

Execution Copy 2015-2018

3

# SECTION 2. CONDITIONS FOR AGREEMENT TO BECOME EFFECTIVE

This Agreement shall not become effective unless each of the following conditions are met: the Agreement is executed by (1) the Council, on behalf of itself, (2) the participating affiliated Local Unions; and (3) the mayor of the City of New York or his designee.

# SECTION 3. ENTITIES BOUND & ADMINISTRATION OF AGREEMENT

This Agreement shall be binding on all participating Unions and their affiliates, the Construction Manager (in its capacity as such) and all Contractors of all tiers performing Program Work, as defined in Article 3. The Contractors shall include in any subcontract that they let for performance during the term of this Agreement a requirement that their subcontractors, of all tiers, become signatory and bound by this Agreement with respect to that subcontracted work falling within the scope of Article 3 and all Contractors (including subcontractors) performing Program Work shall be required to sign a "Letter of Assent" in the form annexed hereto as Exhibit "A". This Agreement shall be administered by the applicable Agency or a Construction Manager or such other designee as may be named by the Agency or Construction Manager, on behalf of all Contractors.

## SECTION 4. SUPREMACY CLAUSE

This Agreement, together with the local Collective Bargaining Agreements appended hereto as Schedule A, represents the complete understanding of all signatories and supersedes any national agreement, local agreement or other collective bargaining agreement of any type which would otherwise apply to this Program Work, in whole or in part, except that Program Work which falls within the jurisdiction of the Operating

Engineers Locals 14 and 15 will be performed under the terms and conditions set out in the Schedule A agreements of Operating Engineers Locals 14 and 15. The Collective Bargaining Agreements of the affiliated local unions that cover the particular type of construction work to be performed by the contractor, and as set forth in the Schedule A list of Agreements, shall be deemed the Schedule A Collective Bargaining Agreements ("Schedule A CBA") under this Agreement. Where association and independent Collective Bargaining Agreements for a particular type of construction work are both set forth in Schedule A, association members shall treat the applicable association agreement as the Schedule A CBA and independent contractors shall treat the applicable independent agreement as the Schedule A CBA. Subject to the foregoing, where a subject covered by the provisions of this Agreement is also covered by a Schedule A Collective Bargaining Agreement, the provisions of this Agreement shall prevail. It is further understood that no Contractor shall be required to sign any other agreement as a condition of performing Program Work. No practice, understanding or agreement between a Contractor and a Local Union which is not set forth in this Agreement shall be binding on this Program Work unless endorsed in writing by the Construction Manager or such other designee as may be designated by the Agency.

#### SECTION 5. LIABILITY

The liability of any Contractor and the liability of any Union under this Agreement shall be several and not joint. The Construction Manager and any Contractor shall not be liable for any violations of this Agreement by any other Contractor; and the

Council and Local Unions shall not be liable for any violations of this Agreement by any other Union.

#### **SECTION 6. THE AGENCY**

The Agency (or Construction Manager where applicable) shall require in its bid specifications for all Program Work within the scope of Article 3 that all successful bidders, and their subcontractors of all tiers, become bound by, and signatory to, this Agreement. The Agency (or Construction Manager) shall not be liable for any violation of this Agreement by any Contractor. It is understood that nothing in this Agreement shall be construed as limiting the sole discretion of the Agency or Construction Manager in determining which Contractors shall be awarded contracts for Program Work. It is further understood that the Agency or Construction Manager has sole discretion at any time to terminate, delay or suspend the Program Work, in whole or part, on any Program.

#### SECTION 7. AVAILABILITY AND APPLICABILITY TO ALL SUCCESSFUL BIDDERS

The Unions agree that this Agreement will be made available to, and will fully apply to, any successful bidder for (or subcontractor of) Program Work who becomes signatory thereto, without regard to whether that successful bidder (or subcontractor) performs work at other sites on either a union or non-union basis and without regard to whether employees of such successful bidder (or subcontractor) are, or are not, members of any unions. This Agreement shall not apply to the work of any Contractor which is performed at any location other than the site of Program Work.

6

## **SECTION 8. SUBCONTRACTING**

Contractors will subcontract Program Work only to a person, firm or corporation who is or agrees to become party to this Agreement.

# **ARTICLE 3-SCOPE OF THE AGREEMENT**

#### **SECTION 1. WORK COVERED**

Program Work shall be limited to designated rehabilitation and renovation construction contracts bid and let by an Agency (or its Construction Manager where applicable) after the effective date of this Agreement with respect to rehabilitation and renovation work performed for an Agency on City-owned property under contracts let prior to December 31, 2018. Subject to the foregoing, and the exclusions below, such Program Work shall mean any and all contracts that predominantly involve the renovation, repair, alteration, rehabilitation or expansion of an existing City-owned building or structure within the five boroughs of New York City. Examples of Program Work include, but are not limited to, the renovation, repair, alteration and rehabilitation of an existing temporary or permanent structure, or an expansion of above ground structures located in the City on a City-owned building. This Program Work shall also include JOCS contracts, demolition work, site work, asbestos and lead abatement, painting services, carpentry services, and carpet removal and installation, to the extent incidental to such building rehabilitation of City-owned buildings or structures.

It is understood that, except where the City specifically applies this Project Labor Agreement to such work in its bid documents, Program Work does not include, and this Project Labor Agreement shall not apply to, any other work, including:

7

1. Contracts let and work performed in connection with projects carried over, recycled from, or performed under bids or rebids relating to work that were bid prior to the effective date of this Agreement or after December 31, 2018;

2. Contracts procured on an emergency basis;

3. Contracts that do not exceed \$250,000;

4. Contracts for work on streets and bridges and for the closing or environmental remediation of landfills;

5. Contracts with not-for-profit corporations where the City is not awarding or performing the work performed for that entity;

6. Contracts with governmental entities where the City is not awarding or performing the work performed for that entity;

7. Contracts with electric utilities, gas utilities, telephone companies, and railroads, except that it is understood and agreed that these entities may only install their work to a demarcation point, e.g. a telephone closet or utility vault, the location of which is determined prior to construction and employees of such entities shall not be used to replace employees performing Program Work pursuant to this agreement;

8. Contracts for installation of information technology that are not otherwise Program Work;

9. Task Orders or Work Orders issued under JOCS or Requirements Contracts that do not exceed \$10,000, and JOCS or Requirements Contracts where the monetary value of such contracts predominantly involves such Task Orders or Work

Orders: and

10. Contracts that do not exceed \$1 Million that are awarded pursuant to prequalified lists (PQLs) established by City agencies where entry on to the PQL is restricted to MWBEs, or a combination of MWBEs together with joint ventures which include at least one MWBE, or contractors who agree to subcontract at least 50% of the contract to MWBEs.

#### **SECTION 2. TIME LIMITATIONS**

In addition to falling within the scope of Article 3, Section 1, to be covered by this Agreement Program Work must be (1) advertised and let for bid after the effective date of this Agreement, and (2) let for bid prior to December 31, 2018, the expiration date of this Agreement. It is understood that this Agreement, together with all of its provisions, shall remain in effect for all such Program Work until completion, even if not completed by the expiration date of the Agreement. If Program Work otherwise falling within the scope of Article 3, Section 1 is not let for bid by the expiration date of this Agreement, this Agreement may be extended to that work by mutual agreement of the parties.

#### SECTION 3. EXCLUDED EMPLOYEES

The following persons are not subject to the provisions of this Agreement, even though performing Program Work:

A. Superintendents, supervisors (excluding general and forepersons specifically covered by a craft's Schedule A), engineers, professional engineers and/or licensed architects engaged in inspection and testing, quality control/assurance personnel, timekeepers, mail carriers, clerks, office workers, messengers, guards, technicians.

Q

non-manual employees, and all professional, engineering, administrative and management persons;

B. Employees of the Agency, New York City, or any other municipal or State agency, authority or entity, or employees of any other public employer, even though working on the Program site while covered Program Work is underway;

C. Employees and entities engaged in off-site manufacture, modifications, repair, maintenance, assembly, painting, handling or fabrication of project components, materials, equipment or machinery or involved in deliveries to and from the Program site, except to the extent they are lawfully included in the bargaining unit of a Schedule A agreement;

D. Employees of the Construction Manager (except that in the event the Agency engages a Contractor to serve as Construction Manager, then those employees of the Construction Manager performing manual, on site construction labor will be covered by this Agreement);

E. Employees engaged in on-site equipment warranty work unless employees are already working on the site and are certified to perform warranty work;

F. Employees engaged in geophysical testing other than boring for core samples:

G. Employees engaged in laboratory, specialty testing, or inspections, pursuant to a professional services agreement between the Agency, or any of the Agency's

10

other professional consultants, and such laboratory, testing, inspection or surveying firm; and

H. Employees engaged in on-site maintenance of installed equipment or systems which maintenance is awarded as part of a contract that includes Program Work but which maintenance occurs after installation of such equipment or system and is not directly related to construction services.

# SECTION 4. NON-APPLICATION TO CERTAIN ENTITIES

This Agreement shall not apply to those parents, affiliates, subsidiaries, or other joint or sole ventures of any Contractor which do not perform Program Work. It is agreed that this Agreement does not have the effect of creating any joint employment, single employer or alter ego status among the Agency (including in its capacity as Construction Manager) or any Contractor. The Agreement shall further not apply to any New York City or other municipal or State agency, authority, or entity other than a listed Agency and nothing contained herein shall be construed to prohibit or restrict the Agency or its employees, or any State, New York City or other municipal or State authority, agency or entity and its employees, from performing on or off-site work related to Program Work.

As the contracts involving Program Work are completed and accepted, the Agreement shall not have further force or effect on such items or areas except where inspections, additions, repairs, modifications, check-out and/or warranty work are assigned in writing (copy to Local Union involved) by the Agency (or Construction Manager) for performance under the terms of this Agreement.

11

# **ARTICLE 4- UNION RECOGNITION AND EMPLOYMENT**

# SECTION 1. PRE-HIRE RECOGNITION

The Contractors recognize the signatory Unions as the sole and exclusive bargaining representatives of all employees who are performing on-site Program Work, with respect to that work.

# **SECTION 2. UNION REFERRAL**

A. The Contractors agree to employ and hire craft employees for Program Work covered by this Agreement through the job referral systems and hiring halls established in the Local Unions area collective bargaining agreements. Notwithstanding this, Contractors shall have sole right to determine the competency of all referrals; to determine the number of employees required; to select employees for layoff (subject to Article 5, Section 3); and the sole right to reject any applicant referred by a Local Union, subject to the show-up payments. In the event that a Local Union is unable to fill any request for qualified employees within a 48 hour period after such requisition is made by a Contractor (Saturdays, Sundays and holidays excepted). a Contractor may employ qualified applicants from any other available source. In the event that the Local Union does not have a job referral system, the Contractor shall give the Local Union first preference to refer applicants, subject to the other provisions of this Article. The Contractor shall notify the Local Union of craft employees hired for Program Work within its jurisdiction from any source other than referral by the Union.

B. A Contractor may request by name, and the Local will honor, referral of persons who have applied to the Local for Program Work and who meet the following qualifications:

- (1) possess any license required by New York State law for the Program Work to be performed;
- (2) have worked a total of at least 1000 hours in the Construction field during the prior 3 years; and
- (3) were on the Contractor's active payroll for at least 60 out of the 180 calendar days prior to the contract award.

No more than twelve per centum (12%) of the employees covered by this Agreement, per Contractor by craft, shall be hired through the special provisions above. Under this provision, name referrals begin with the eighth employee needed and continue on that same basis.

C. Notwithstanding Section 2(B), above, certified MWBE contractors for which participation goals are set forth in New York City Administrative Code §6-129, that are not signatory to any Schedule A CBAs, with contracts valued at or under five hundred thousand (\$500,000), may request by name, and the Local will honor, referral of the second ( $2^{nd}$ ). fourth ( $4^{th}$ ), sixth ( $6^{th}$ ), and eighth ( $8^{th}$ ) employee, who have applied to the Local for Program Work and who meet the following qualifications:

- possess any license required by New York State law for the Program Work to be performed;
- (2) have worked a total of at least 1000 hours in the Construction field during the prior 3 years; and
- (3) were on the Contractor's active payroll for at least 60 out of the 180 work days prior to the contract award.

13

For such contracts valued at above \$500,000 but less than \$1 million, the Local will honor referrals by name of the second  $(2^{nd})$ , fifth  $(5^{th})$ , and eighth  $(8^{th})$  employee subject to the foregoing requirements. In both cases, name referrals will thereafter be in accordance with Section 2(B), above.

D. Where a certified MWBE Contractor voluntarily enters into a Collective Bargaining Agreement ("CBA") with a BCTC Union, the employees of such Contractor at the time the CBA is executed shall be allowed to join the Union for the applicable trade subject to satisfying the Union's basic standards of proficiency for admission.

# SECTION 3. NON-DISCRIMINATION IN REFERRALS

The Council represents that each Local Union hiring hall and referral system will be operated in a non-discriminatory manner and in full compliance with all applicable federal, state and local laws and regulations which require equal employment opportunities. Referrals shall not be affected in any way by the rules, regulations, bylaws, constitutional provisions or any other aspects or obligations of union membership, policies or requirements and shall be subject to such other conditions as are established in this Article. No employment applicant shall be discriminated against by any referral system or hiring hall because of the applicant's union membership, or lack thereof.

# SECTION 4: MINORITY, FEMALE, LOCAL AND SECTION 3 REFERRALS

In the event a Local Union either fails, or is unable to refer qualified minority or female applicants in percentages equaling the workforce participation goals adopted by the City and set forth in the Agency's (or, if applicable, Construction Manager's) bid

specifications, within 48 hours of the request for same, the Contractor may employ qualified minority or female applicants from any other available source.

In the event that the City or a City agency determines to adopt local workforce participation goals to be set forth in an Agency's (or, if applicable Construction Manager's) bid specifications, the City and BCTC will work together to seek agreement on appropriate goals to be set forth in applicable bid documents and to be subject to the provisions of this section.

For any Program Work that may become subject to requirements under Section 3 of the Housing and Urban Development Act of 1968, as amended by the Housing and Community Development Act of 1992, and any rules, including new or revised rules, that may be published thereunder, the Local Unions will acknowledge the Section 3 obligations of the Construction Manager or Contractor, as applicable, and agree to negotiate a method to implement this Article in a manner that would allow the Construction Manager or Contractor to meet its Section 3 obligations to the greatest extent feasible, and to post any required notices in the manner required by Section 3. The parties also acknowledge that the Construction Manager and Contractor may also fulfill its Section 3 requirements on Program Work by promoting opportunities for excluded employees, as defined by Article 3, Section 3 of this Agreement, on Program Work and, to the extent permitted by Section 3, by promoting opportunities for craft and other employees on non-Program Work.

# SECTION 5. CROSS AND QUALIFIED REFERRALS

The Local Unions shall not knowingly refer to a Contractor an employee then employed by another Contractor working under this Agreement. The Local Unions

15

will exert their utmost efforts to recruit sufficient numbers of skilled and qualified crafts employees to fulfill the requirements of the Contractor.

#### **SECTION 6. UNION DUES**

All employees covered by this Agreement shall be subject to the union security provisions contained in the applicable Schedule A local agreements, as amended from time to time, but only for the period of time during which they are performing on-site Program Work and only to the extent of tendering payment of the applicable union dues and assessments uniformly required for union membership in the Local Unions which represent the craft in which the employee is performing Program Work. No employee shall be discriminated against at any Program Work site because of the employee's union membership or lack thereof. In the case of unaffiliated employees, the dues payment will be received by the Local Unions as an agency shop fee.

# SECTION 7. CRAFT FOREPERSONS AND GENERAL FOREPERSONS

The selection of craft forepersons and/or general forepersons and the number of forepersons required shall be solely the responsibility of the Contractor except where otherwise provided by specific provisions of an applicable Schedule A, and provided that all craft forepersons shall be experienced and qualified journeypersons in their trade as determined by the appropriate Local Union. All forepersons shall take orders exclusively from the designated Contractor representatives. Craft forepersons shall be designated as working forepersons at the request of the Contractor, except when an existing local Collective Bargaining Agreement prohibits a foreperson from working when the craft persons he is leading exceed a specified number.

#### **SECTION 8. ON CALL REPAIR REFERRALS**

A. When an Agency awards a contract that requires the Contractor to have employees available on short notice to make time sensitive repairs with such contract requiring the Contractor to respond within as little as two hours from the time the Contractor is contacted by the Agency ("On Call, Repair Contract"), the Contractor will, within ten (10) days of being awarded an On Call, Repair Contract subject to this Agreement, notify the appropriate affiliated Union that it has been awarded such a contract and immediately enter into good faith negotiations with such relevant affiliated Union to establish a procedure to receive time sensitive referrals from such affiliated Union(s).

B. In the event the Contractor and the relevant affiliated Union(s) are unable to negotiate a specific, mutually agreeable procedure for on call repair referral procedure within twenty (20) days of commencement of negotiations or prior to commencement of performance of the contract, whichever is earlier, the Contractor and the relevant affiliated Unions will follow the following procedure:

1. Upon notification by a Contractor that it has been awarded an On Call Repair Contract pursuant to paragraph A above, each relevant affiliate Union shall provide the Contractor with the name and twenty four (24) hour contact information of an On Call, Repair Contract contact person for urgent on call repair referrals.

2. The relevant affiliated Unions shall prepare a list of individuals eligible and prepared for referral on an immediate basis to respond to the on call repair contractor. Such list shall be provided to and in the possession of the designated on call repair contact person for the affiliated Union and available for immediate reference.

Execution Copy 2015-2018

17

3. Individuals on such list must be able to comply with the Contractor's response time pursuant to contract requirements.

4. The Union's On Call, Repair Contract contact person shall respond to a contractor's request for referrals within a reasonable time of the request so that compliance with the contract shall be possible.

C. In the event that the Contractor makes a request for an on call referral that is compliant with this procedure and a Union is not able to respond to the request, that Union will be deemed to have waived the forty-eight (48) hour referral rule contained in Section 2 above and the Contractor may employ qualified applicants from any other available source that can meet contract requirements for that time sensitive on call repair work only; provided, however, that any work related to the repair work that is not of a time sensitive nature under the contract shall comply with Section 2. If a Union fails to timely refer a worker and the Contractor employs other workers, the Contractor will e-mail the agency within 72 hours and the agency will forward that e-mail to the designated Labor Management Committee contacts.

#### **ARTICLE 5- UNION REPRESENTATION**

#### SECTION 1. LOCAL UNION REPRESENTATIVE

Each Local Union representing on-site employees shall be entitled to designate in writing (copy to Contractor involved and Construction Manager) one representative, and/or the Business Manager, who shall be afforded access to the Program Work site during such time as bargaining unit work is occurring and subject to otherwise applicable policies pertaining to visitors to the site.

### **SECTION 2. STEWARDS**

A. Each Affiliated Union shall have the sole discretion to designate any journey person as a Steward and an alternate Steward. The Union shall notify the Owner and/or Construction Manager as well as the Contractor of the identity of the designated Steward (and alternate) prior to the assumption of such duties. Stewards shall not exercise supervisory functions and will receive the regular rate of pay for their craft classifications. All Stewards shall be working Stewards.

B. In addition to their work as an employee, the Steward shall have the right to receive complaints or grievances and to discuss and assist in their adjustment with the Contractor's appropriate supervisor. Each Steward shall be concerned with the employees of the Steward's trade and, if applicable, subcontractors of their Contractor, but not with the employees of any other trade Contractor. No Contractor shall discriminate against the Steward in the proper performance of Union duties.

C. The Stewards shall not have the right to determine when overtime shall be worked, or who shall work overtime except pursuant to a Schedule A provision providing procedures for the equitable distribution of overtime.

### **SECTION 3. LAYOFF OF A STEWARD**

Contractors agree to notify the appropriate Union 24 hours prior to the layoff of a Steward, except in cases of discipline or discharge for just cause. If a Steward is protected against layoff by a Schedule A provision, such provision shall be recognized to the extent the Steward possesses the necessary qualifications to perform the work required.

19

In any case in which a Steward is discharged or disciplined for just cause, the Local Union involved shall be notified immediately by the Contractor.

#### **ARTICLE 6- MANAGEMENT'S RIGHTS**

#### **SECTION 1. RESERVATION OF RIGHTS**

Except as expressly limited by a specific provision of this Agreement. Contractors retain full and exclusive authority for the management of their operations including, but not limited to, the right to: direct the work force, including determination as to the number of employees to be hired and the qualifications therefore; the promotion, transfer, layoff of its employees; require compliance with the directives of the Agency including standard restrictions related to security and access to the site that are equally applicable to Agency employees, guests, or vendors; or the discipline or discharge for just cause of its employees; assign and schedule work; promulgate reasonable Program Work rules that are not inconsistent with this Agreement or rules common in the industry and are reasonably related to the nature of work; and, the requirement, timing and number of employees to be utilized for overtime work. No rules, customs, or practices which limit or restrict productivity or efficiency of the individual, as determined by the Contractor. Agency and/or Construction Manager and/or joint working efforts with other employees shall be permitted or observed.

#### SECTION 2. MATERIALS, METHODS & EQUIPMENT

There shall be no limitation or restriction upon the Contractor's choice of materials, techniques, methods, technology or design, or, regardless of source or location, upon the use and installation of equipment, machinery, package units, pre-cast,

pre-fabricated, pre-finished, or pre-assembled materials or products, tools, or other labor-saving devices. Contractors may, without restriction, install or use materials, supplies or equipment regardless of their source; provided, however, that where there is a Schedule "A" that includes a lawful union standards and practices clauses, then such clause as set forth in Schedule A Agreements will be complied with, unless there is a lawful Agency specification (or specification issued by a Construction Manager which would be lawful if issued by the Agency directly) that would specifically limit or restrict the Contractor's choice of materials, techniques, methods, technology or design, or, regardless of source or location, upon the use and installation of equipment, machinery, package units, pre-cast, pre-fabricated, pre-finished, or pre-assembled materials or products, tools, or other labor-saving devices, and which would prevent compliance with such Schedule A clause. The on-site installation or application of such items shall be performed by the craft having jurisdiction over such work; provided, however, it is recognized that other personnel having special qualifications may participate, in a supervisory capacity, in the installation, check-off or testing of specialized or unusual equipment or facilities as designated by the Contractor. There shall be no restrictions as to work which is performed off-site for Program Work.

# **ARTICLE 7- WORK STOPPAGES AND LOCKOUTS**

# SECTION 1. NO STRIKES-NO LOCK OUT

There shall be no strikes, sympathy strikes, picketing, work stoppages, slowdowns, hand billing, demonstrations or other disruptive activity at the Program Work - site for any reason by any Union or employee against any Contractor or employer. There

shall be no other Union, or concerted or employee activity which disrupts or interferes with the operation of the Program Work or the objectives of the Agency at any Program Work site. In addition, failure of any Union or employee to cross any picket line established by any Union, signatory or non-signatory to this Agreement, or the picket or demonstration line of any other organization, at or in proximity to a Program Work site where the failure to cross disrupts or interferes with the operation of Program Work is a violation of this Article. Should any employees breach this provision, the Unions will use their best efforts to try to immediately end that breach and return all employees to work. There shall be no lockout at a Program Work site by any signatory Contractor, Agency or Construction Manager.

# SECTION 2. DISCHARGE FOR VIOLATION

A Contractor may discharge any employee violating Section 1, above, and any such employee will not be eligible thereafter for referral under this Agreement for a period of 100 days.

# SECTION 3. NOTIFICATION

If a Contractor contends that any Union has violated this Article, it will notify the Local Union involved advising of such fact, with copies of the notification to the Council. The Local Union shall instruct and order, the Council shall request, and each shall otherwise use their best efforts to cause, the employees (and where necessary the Council shall use its best efforts to cause the Local Union). to immediately cease and desist from any violation of this Article. If the Council complies with these obligations it shall not be liable for the unauthorized acts of a Local Union or its members. Similarly, a Local Union

and its members will not be liable for any unauthorized acts of the Council. Failure of a Contractor or the Construction Manager to give any notification set forth in this Article shall not excuse any violation of Section 1 of this Article.

### SECTION 4. EXPEDITED ARBITRATION

Any Contractor or Union alleging a violation of Section 1 of this Article may utilize the expedited procedure set forth below (in lieu of, or in addition to, any actions at law or equity) that may be brought.

A. A party invoking this procedure shall notify J.J. Pierson or Richard Adelman: who shall alternate (beginning with Arbitrator J.J. Pierson) as Arbitrator under this expedited arbitration procedure. If the Arbitrator next on the list is not available to hear the matter within 24 hours of notice, the next Arbitrator on the list shall be called. Copies of such notification will be simultaneously sent to the alleged violator and Council.

B. The Arbitrator shall thereupon, after notice as to time and place to the Contractor, the Local Union involved, the Council and the Construction Manager, hold a hearing within 48 hours of receipt of the notice invoking the procedure if it is contended that the violation still exists. The hearing will not, however, be scheduled for less than 24 hours after the notice required by Section 3, above.

C. All notices pursuant to this Article may be provided by telephone, telegraph, hand delivery, or fax, confirmed by overnight delivery, to the Arbitrator. Contractor, Construction Manager and Local Union involved. The hearing may be held on any day including Saturdays or Sundays. The hearing shall be completed in one session, which shall not exceed 8 hours duration (no more than 4 hours being allowed to either side

to present their case, and conduct their cross examination) unless otherwise agreed. A failure of any Union or Contractor to attend the hearing shall not delay the hearing of evidence by those present or the issuance of an award by the Arbitrator.

D. The sole issue at the hearing shall be whether a violation of Section 1, above, occurred. If a violation is found to have occurred, the Arbitrator shall issue a Cease and Desist Award restraining such violation and serve copies on the Contractor and Union involved. The Arbitrator shall have no authority to consider any matter in justification, explanation or mitigation of such violation or to award damages (any damages issue is reserved solely for court proceedings, if any.) The Award shall be issued in writing within 3 hours after the close of the hearing, and may be issued without an Opinion. If any involved party desires an Opinion, one shall be issued within 15 calendar days, but its issuance shall not delay compliance with, or enforcement of, the Award.

E. The Agency and Construction Manager (or such other designee of the Agency) may participate in full in all proceedings under this Article.

F. An Award issued under this procedure may be enforced by any court of competent jurisdiction upon the filing of this Agreement together with the Award. Notice of the filing of such enforcement proceedings shall be given to the Union or Contractor involved, and the Construction Manager.

G. Any rights created by statute or law governing arbitration proceedings which are inconsistent with the procedure set forth in this Article, or which interfere with compliance thereto, are hereby waived by the Contractors and Unions to whom they accrue.

24

H. The fees and expenses of the Arbitrator shall be equally divided between the involved Contractor and Union.

#### SECTION 5. ARBITRATION OF DISCHARGES FOR VIOLATION

Procedures contained in Article 9 shall not be applicable to any alleged violation of this Article, with the single exception that an employee discharged for violation of Section 1, above, may have recourse to the procedures of Article 9 to determine only if the employee did, in fact, violate the provisions of Section 1 of this Article; but not for the purpose of modifying the discipline imposed where a violation is found to have occurred.

#### **ARTICLE 8 - LABOR MANAGEMENT COMMITTEE**

#### **SECTION 1. SUBJECTS**

The Program Labor Management Committee will meet on a regular basis to: 1) promote harmonious relations among the Contractors and Unions; 2) enhance safety awareness, cost effectiveness and productivity of construction operations; 3) protect the public interests; 4) discuss matters relating to staffing and scheduling with safety and productivity as considerations; and 5) review efforts to meet applicable participation goals for MWBEs and workforce participation goals for minority and female employees.

#### **SECTION 2. COMPOSITION**

The Committee shall be jointly chaired by a designee of the Agency and the President of the Council. It may include representatives of the Local Unions and Contractors involved in the issues being discussed. The parties may mutually designate an

Execution Copy 2015-2018

25

MWBE representative to participate in appropriate Committee discussions. The Committee may conduct business through mutually agreed upon sub-committees.

#### **ARTICLE 9- GRIEVANCE & ARBITRATION PROCEDURE**

#### **SECTION 1. PROCEDURE FOR RESOLUTION OF GRIEVANCES**

Any question, dispute or claim arising out of, or involving the interpretation or application of this Agreement (other than jurisdictional disputes or alleged violations of Article 7, Section 1) shall be considered a grievance and shall be resolved pursuant to the exclusive procedure of the steps described below, provided, in all cases, that the question, dispute or claim arose during the term of this Agreement. Grievances shall include the City contract number and the Program Work address; such information is posted at the Program Work Site if already commenced, and is available in the City Record and Notice to Proceed for projects not already commenced.

Grievances as to whether a scope of work is included or excluded from this Agreement shall be submitted to the Labor Management Committee (LMC) in the first instance rather than Step 1 below. To be timely, such notice must be given no later than ten days prior to a bid opening if the grievance is challenging a determination by an Agency that the contract is not subject to this Agreement. For other grievances as to contractor scope of work issues, notice of such challenges shall be submitted to the LMC within 7 calendar days after the act, occurrence or event giving rise to the grievance. If the scope of work grievance is not resolved within 21 days of its submission to the LMC, then the grievance may proceed directly to Step 3 below.

Step 1:

26

(a)When any employee covered by this Agreement feels aggrieved by a claimed violation of this Agreement, the employee shall, through the Local Union business representative or job steward give notice of the claimed violation to the work site representative of the involved Contractor and the Construction Manager. To be timely, such notice of the grievance must be given within 7 calendar days after the act, occurrence or event giving rise to the grievance. The business representative of the Local Union or the job steward and the work site representative of the involved Contractor shall meet and endeavor to adjust the matter within 7 calendar days after timely notice has been given. If they fail to resolve the matter within the prescribed period, the grieving party, may, within 7 calendar days thereafter, pursue Step 2 of the grievance procedure by serving the involved Contractor with written copies of the grievance setting forth a description of the claimed violation, the date on which the grievance occurred, and the provisions of the Agreement alleged to have been violated. Grievances and disputes settled at Step 1 are non-precedential except as to the specific Local Union, employee and Contractor directly involved unless the settlement is accepted in writing by the Construction Manager (or designee) as creating a precedent.

(b) Should any signatory to this Agreement have a dispute (excepting jurisdictional disputes or alleged violations of Article 7, Section 1) with any other signatory to this Agreement and, if after conferring, a settlement is not reached within 7 calendar days, the dispute shall be reduced to writing and proceed to Step 2 in the same manner as outlined in subparagraph (a) for the adjustment of employee grievances.

Step 2:

27

A Step 2 grievance shall be filed with the Agency. the BCTC, the Contractor, and, if the grievance is against a subcontractor, the subcontractor. The Business Manager or designee of the involved Local Union. together with representatives of the involved Contractor, Council, the Construction Manager (or designee), and, if the grievance is against a subcontractor, the subcontractor, shall meet in Step 2 within 7 calendar days of service of the written grievance to arrive at a satisfactory settlement. The BCTC shall schedule the Step 2 meeting.

Step 3:

(a) If the grievance shall have been submitted but not resolved in Step 2, any of the participating Step 2 entities may, within 21 calendar days after the initial Step 2 meeting, submit the grievance in writing (copies to other participants, including the Construction Manager or designee) to the BCTC. In the event the matter is not resolved at Step 2, either J.J. Pierson or Richard Adelman, who shall act, alternately (beginning with Arbitrator J.J. Pierson), as the Arbitrator under this procedure, shall be designated at the Step 2 hearing and the BCTC will notify the arbitrator of his designation. After such notification by the BCTC, the local demanding arbitration shall within a reasonable time request the arbitrator to schedule the matter for an arbitration hearing date. The Labor Arbitration Rules of the American Arbitration Association shall govern the conduct of the arbitrator shall be final and binding on the involved Contractor, Local Union and employces and the fees and expenses of such arbitrations shall be borne equally by the involved Contractor and Local Union.

28


(b) Failure of the grieving party to adhere to the time limits set forth in this Article shall render the grievance null and void. These time limits may be extended only by written consent of the Construction Manager (or designee), involved Contractor and involved Local Union at the particular step where the extension is agreed upon. The Arbitrator shall have authority to make decisions only on the issues presented to him and shall not have the authority to change, add to, delete or modify any provision of this Agreement.

## SECTION 2. LIMITATION AS TO RETROACTIVITY

No arbitration decision or award, with the exception of those related to compliance with requirements to pay prevailing wages and supplements in accordance with federal or State law, may provide retroactivity of any kind exceeding 60 calendar days prior to the date of service of the written grievance on the Construction Manager and the involved Contractor or Local Union.

# SECTION 3. PARTICIPATION BY AGENCY AND/OR CONSTRUCTION MANAGER

The Agency and Construction Manager (or such other designee of the Agency) shall be notified by the involved Contractor of all actions at Steps 2 and 3 and, at its election, may participate in full in all proceedings at these Steps, including Step 3 arbitration.



29

# NYC AGENCY RENOVATION & REHAB CITY OWNED BUILDINGS/STRUCTURES PLA ARTICLE 10 - JURISDICTIONAL DISPUTES

#### SECTION I. NO DISRUPTIONS

There will be no strikes, sympathy strikes, work stoppages, slowdowns, picketing or other disruptive activity of any kind arising out of any jurisdictional dispute. Pending the resolution of the dispute, the work shall continue uninterrupted and as assigned by the Contractor. No jurisdictional dispute shall excuse a violation of Article 7.

#### **SECTION 2. ASSIGNMENT**

All Program Work assignments shall be made by the Contractor to unions affiliated with the BCTC consistent with the New York Plan for the Settlement of Jurisdictional Disputes ("New York Plan") and its Greenbook decisions, if any. Where there are no applicable Greenbook decisions, assignments shall be made in accordance with the provisions of the New York Plan and local industry practice.

# SECTION 3. NO INTERFERENCE WITH WORK

There shall be no interference or interruption of any kind with the Program Work while any jurisdictional dispute is being resolved. The work shall proceed as assigned by the Contractor until finally resolved under the applicable procedure of this Article. The award shall be confirmed in writing to the involved parties. There shall be no strike, work stoppage or interruption in protest of any such award.

#### **ARTICLE 11 - WAGES AND BENEFITS**

#### SECTION 1. CLASSIFICATION AND BASE HOURLY RATE

All employees covered by this Agreement shall be classified in accordance with the work performed and paid the hourly wage rates applicable for those classifications as required by the applicable prevailing wage laws.

#### **SECTION 2. EMPLOYEE BENEFITS**

A. The Contractors agree to pay on a timely basis contributions on behalf of all employees covered by this Agreement to those established jointly trusteed employee benefit funds designated in the applicable Collective Bargaining Agreements in Schedule A (in the appropriate Schedule A amounts), provided that such benefits are required to be paid on public works under any applicable prevailing wage law. Bona fide jointly trusteed fringe benefit plans established or negotiated through collective bargaining during the life of this Agreement may be added if similarly required under applicable prevailing wage law. Contractors, not otherwise contractually bound to do so, shall not be required to contribute to benefits, trusts or plans of any kind which are not required by the prevailing wage law provided, however, that this provision does not relieve Contractors signatory to local collective bargaining agreement with any affiliated union from complying with the fringe benefit requirements for all funds contained in the CBA.

B. 1. Notwithstanding Section 2 (A) above, and subject to 2 (B)(2) below, Contractors who designate employees pursuant to Article 4, Section 2 (B) and (C) ("core" employees) that are not signatory to a Schedule A Agreement and who maintain bona fide private benefit plans that satisfy the requirements of Section 220 of the Labor Law, may

31

satisfy the above benefit obligation with respect to those employees by providing those employees with coverage under their private benefit plans (to the extent consistent with Section 220). The total benefit payments to be made on behalf of each such employee must be equal to the total Section 220 supplement amount and any shortfall must be paid by cash supplement to the employee.

2. A contractor that will satisfy its Section 220 obligations in accordance with subsection 2(B)(1) above shall make available to the Agency at the time of contract award a complete set of plan documents for each non-Schedule A benefit plan into which contributions will be made and/or coverage provided pursuant to the provisions of Section 2(B)(l) above. The Contractor shall also provide certification from a certified public accountant as to the annualized hourly value of such benefits consistent with the requirements of Section 220.

3. The City shall verify that the alternate benefit plan(s), together with any cash supplement to the employee, is compliant with Section 220 prior to awarding the Contractor a contract covered by this Agreement. In the event the Contractor's alternate benefit plan(s), together with any cash supplement to the employee, is determined to be compliant with Section 220 and will be utilized by the Contractor on behalf of Article 4, Section 2(B) and (C) core employees, the Local Unions have no duty to enforce the Contractor's obligations on the alternate benefit plan(s) as they are not party to the alternate plan(s) or privy to the terms and conditions of the plan obligations. In the event the City determines the alternate benefit plan(s), together with any cash supplement to the employee, is not compliant with Section 220, the Contractor may, upon executing a Letter

32

of Assent, satisfy its obligations for all employees, including core employees, by contributing to the Schedule A benefit plans in accordance with the terms of the Schedule A Agreements.

C. The Contractors agree to be bound by the written terms of the legally established jointly trusteed Trust Agreements specifying the detailed basis on which payments are to be paid into, and benefits paid out of, such Trust Funds but only with regard to Program Work done under this Agreement and only for those employees to whom this Agreement requires such benefit payments.

D. 1. To the extent consistent with New York City's Procurement Policy Board Rules with respect to prompt payment, as published at <u>www.nyc.gov/ppb</u>, §4-06(e), and in consideration of the unions' waiver of their rights to withhold labor from a contractor or subcontractor delinquent in the payment of fringe benefits contributions ("Delinquent Contractor"); the Agency agrees that where any such union and/or fringe benefit fund shall notify the Agency, the General Contractor, and the Delinquent Contractor in writing with back-up documentation that the Delinquent Contractor has failed to make fringe benefit contributions to it as provided herein and the Delinquent Contractor shall fail, within ten (10) calendar days after receipt of such notice, to furnish either proof of such payment or notice that the amount claimed by the union and/or fringe benefit fund is in dispute, the Agency shall withhold from amounts then or thereafter becoming due and payable to the General Contractor an amount equal to that portion of such payment due to the General Contractor that relates solely to the work performed by

the Delinquent Contractor which the union or fringe benefit fund claims to be due it, and shall remit the amount when and so withheld to the fringe benefit fund and deduct such payment from the amounts then otherwise due and payable to the General Contractor, which payment shall, as between the General Contractor and the Agency, be deemed a payment by the Agency to the General Contractor; provided however, that in any month, such withholding shall not exceed the amount contained in the General Contractor's monthly invoice for work performed by the Delinquent Contractor. The union or its employee benefit funds shall include in its notification of delinquent payment of fringe benefits only such amount it asserts the Delinquent Contractor failed to pay on the specific project against which the claim is made and the union or its employee benefit funds may not include in such notification any amount such Delinquent Contractor may have failed to pay on any other City or non-City project.

2. In addition, where a union or employee benefit fund gives notice to the City that a Contractor is Delinquent as defined in subsection 2(D)(1) above and the City determines that the notice includes appropriate back-up documentation that the Contractor is delinquent, the City will promptly, but not later than twenty (20) days after receipt of the notice, provide a copy of said notice to City Agencies. In the event the City determines there is insufficient back-up documentation, it will notify the appropriate union and/or fringe benefit fund promptly, but not later than twenty (20) days after receipt of the Delinquency Notice, and shall include notice of what additional documentation is requested. Any determination by the City that there is insufficient back-up must be reasonable. This provision is intended to enhance compliance with the prevailing wage

34

law and the PLA with respect to the payment of fringe benefits, and is not intended as a substitute for the resolution of a disputed elaim pursuant to any applicable law or agreement.

The City and the relevant Agency(s) will thereafter require the Delinquent Contractor to provide cancelled checks or other equivalent proof of payment of benefit contributions that have come due, to be submitted with certified payroll reports for all Program Work covered by this Agreement on which the Delinquent Contractor is engaged, for at least a one-year period or such earlier period if the Contractor is ultimately determined not be a Delinquent Contractor. Such proof of payment when required is a condition of payment of the Delinquent Contractor's invoices by any entity, including, but not limited to, the City, the relevant Agency(s), Construction Manager, General Contractor, the prime or higher level subcontractor, as is appropriate under the Delinquent Contractor's engagement. The union and the funds shall upon request receive copies of the certified payrolls, cancelled checks, or other proof of payment from the City and/or the relevant Agency(s).

E. In the event the General Contractor or Delinquent Contractor shall notify the Agency as above provided that the claim of the union or fringe benefit fund is in dispute, the Agency shall withhold from amounts then or thereafter becoming due and payable to the General Contractor an amount equal to that portion of such payment due to the General Contractor that relates solely to the work performed by the Delinquent Contractor that the union and/or fringe benefit fund claims to be due it, pending resolution of the dispute pursuant to the union's Schedule A agreement, and the amount shall be paid to the party or parties ultimately determined to be entitled thereto, or held until the 35

Delinquent Contractor and union or employee benefit fund shall otherwise agree as to the disposition thereof: provided however, that such withholding shall not exceed the amount contained in the General Contractor's monthly invoice for work performed by the Delinquent Contractor. In the event the Agency shall be required to withhold amounts from a General Contractor for the benefit of more than one fringe benefit fund, the amounts so withheld in the manner and amount prescribed above shall be applied to or for such fund in the order in which the written notices of nonpayment have been received by the Agency, and if more than one such notice was received on the same day, proportionately based upon the amount of the union and/or fringe benefit fund claims received on such day. Nothing herein contained shall prevent the Agency from commencing an interpleader action to determine entitlement to a disputed payment in accordance with section one thousand six of the civil practice law and rules or any successor provision thereto.

F. Payment to a fringe benefit fund under this provision shall not relieve the General Contractor or Delinquent Contractor from responsibility for the work covered by the payment. Except as otherwise provided, nothing contained herein shall create any obligation on the part of the Agency to pay any union or fringe benefit fund, nor shall anything provided herein serve to create any relationship in contract or otherwise, implied or expressed, between the union/fund and/or fringe benefit and the Agency.

# NYC AGENCY RENOVATION & REHAB CITY OWNED BUILDINGS/STRUCTURES PLA ARTICLE 12- HOURS OF WORK, PREMIUM PAYMENTS,

# SHIFTS AND HOLIDAYS

#### SECTION 1. WORK WEEK AND WORK DAY

A. The standard work week shall consist of 40 hours of work at straight time rates. Monday through Friday, 8 hours per day, plus ½ hour unpaid lunch period. The standard work week may be reduced to 35 or 37 ½ hours of work at straight time rates, Monday to Friday, 7 or 7 ½ hours per day, plus ½ hour unpaid lunch period in those limited circumstances where the City states in the bid documents that the Contractor will not be given access to the site to accommodate an 8 hour day. The 8 hour, 7 ½ hour or 7 hour work day must be established at the commencement of the project and may not be altered by the Contractor.

B. In accordance with Program needs, there shall be flexible start times with advance notice from Contractor to the Union. The Day Shift shall commence between the hours of 6:00 a.m. and 9:00 a.m. and shall end between the hours of 2:30 p.m. and 5:30 p.m., for an 8 hour day, and up to 7:30 p.m. for a 10 hour day. The Evening Shift shall commence between the hours of 3:00 p.m. and 6:00 p.m., unless different times are necessitated by the Agency's phasing plans on specific projects. The Night Shift shall commence between the hours of 11:00 p.m. and 2:00 a.m., unless different times are necessitated by the Agency's phasing plans on specific projects. Subject to the foregoing, starting and quitting times shall occur at the Program Work site designated by the Contractor.

C. Scheduling — Except as provided above, Monday through Friday is the standard work week; 8 hours of work plus ½ hour unpaid lunch. Notwithstanding any other provision of this Agreement, a contractor may schedule a four day work week, 10 hours per day at straight time rates, plus a ½ hour unpaid lunch, at the commencement of the job.

D. Notice - Contractors shall provide not less than 5 days prior notice to the Local Union involved as to the work week and work hour schedules to be worked or such lesser notice as may be mutually agreed upon.

#### **SECTION 2. OVERTIME**

Overtime shall be paid for any work (i) over an employee's regularly scheduled work day, i.e., work over eight (8) hours in a day where 5/8s is scheduled, work over ten (10) hours in a day where 4/10s is scheduled, or work over seven (7) or seven and one half (7 ½) hours where such hours are scheduled pursuant to Article 12, section 1(A) and (ii) over forty (40) hours in a week, or over thirty five (35) or thirty seven and one-half (37 ½) where such hours are scheduled pursuant to Article 12, section 1(A). Overtime shall be paid at time and one half (1½) Monday through Saturday. All overtime work performed on Sunday and Holidays will be paid pursuant to the applicable Schedule A. There shall be no stacking or pyramiding of overtime pay under any circumstances. There will be no restriction upon the Contractor's scheduling of overtime or the nondiscriminatory designation of employees who shall be worked, including the use of employees, other than those who have worked the regular or scheduled work week, at straight time rates. The Contractor shall have the right to schedule work so as to minimize

38

overtime or schedule overtime as to some, but not all, of the crafts and whether or not of a continuous nature.

#### **SECTION 3. SHIFTS**

A. Flexible Schedules - Scheduling of shift work, including Saturday and Sunday work, shall be within the discretion of the Contractor in order to meet Program Work schedules and existing Program Work conditions including the minimization of interference with the mission of the Agency. It is not necessary to work a day shift in order to schedule a second or third shift, or a second shift in order to schedule a third shift, or to schedule all of the crafts when only certain crafts or employees are needed. Shifts must have prior approval of the Agency or Construction Manager, and must be scheduled with not less than five work days notice to the Local Union or such lesser notice as may be mutually agreed upon.

B. Second and/or Third Shifts/Saturday and/or Sunday Work - - The second shift shall start between 3 p.m. and 6 p.m. and the third shift shall start between 11 p.m. and 2 a.m., subject to different times necessitated by the Agency phasing plans on specific projects. There shall be no reduction in shift hour work. With respect to second and third shift work there shall be a 5% shift premium. No other premium or other payments for such work shall be required unless such work is in excess of the employee's regularly scheduled work week, i.e., 40 hours in the week or thirty five (35) or thirty seven and one half (37 ½) pursuant to Article 12, section 1(A). All employees within a classification performing Program Work will be paid at the same wage rate regardless of the shift or work scheduled work, subject only to the foregoing provisions.

Execution Copy 2015-2018

39

C. Flexible Starting Times - Shift starting times will be adjusted by the Contractor as necessary to fulfill Program Work requirements subject to the notice requirements of paragraph A.

#### **SECTION 4. HOLIDAYS**

A. Schedule - There shall be nine (9) recognized holidays on the

Project:

New Year's Day

Martin Luther King DayPresident's DayMemorial DayVeteran's DayLabor DayThanksgiving DayIndependence DayChristmas Day

All said holidays shall be observed on the calendar date except those holidays which occur on Saturday shall be observed on the previous Friday and those that occur on Sunday shall be observed on the following Monday.

B. Payment - Regular holiday pay, if any, for work performed on such a recognized holiday shall be in accordance with the applicable Schedule A.

C. Exclusivity - No holidays other than those listed in Section 4(A) above shall be recognized or observed.

#### **SECTION 5. SATURDAY MAKE-UP DAYS**

When severe weather, power failure, fire or natural disaster or other similar circumstances beyond the control of the Contractor prevent work from being performed on

40

a regularly scheduled weekday, the Contractor may schedule a Saturday make-up day and such time shall be scheduled and paid as if performed on a weekday. Any other Saturday work shall be paid at time and one-half  $(1\frac{1}{2})$ . The Contractor shall notify the Local Union on the missed day or as soon thereafter as practicable if such a make-up day is to be worked.

## SECTION 6. REPORTING PAY

Employees who report to the work location pursuant to their regular A. schedule and who are not provided with work shall be paid two hours reporting pay at straight time rates. An employee whose work is terminated early by a Contractor due to severe weather, power failure, fire or natural disaster of for similar circumstances beyond the Contractor's control, shall receive pay only for such time as is actually worked. In other instances in which an employee's work is terminated early (unless provided otherwise elsewhere in this Agreement), the employee shall be paid for his full shift. Contractors shall not be permitted to call, text or email or voicemail employees in advance of their regularly scheduled shift starting time to avoid reporting pay. Notwithstanding the above, in the event that the National Weather Service issues a weather advisory for the area in which the work location is situated, and the entire project is shut down as a result of the Weather Advisory, the contractor shall be permitted to speak to employees no less than four (4) hours in advance of their shift starting time, unless the Local Union consents to a shorter notice in writing, to advise them not to report to work due to the National Weather Service advisory, and employees who are so notified shall not receive two (2) hours reporting pay if they report to the work location. The contractor shall make every effort to

41

notify each employee directly and confirm that notification has been received. Voice, text, and email messages left for employees without confirmation of delivery and receipt by employee do not constitute sufficient notice under this provision.

B. When an employee, who has completed their scheduled shift and left the Program Work site, is "called out" to perform special work of a casual, incidental or irregular nature, the employee shall receive overtime pay at the rate of time and one-half of the employee's straight time rate for hours actually worked.

C. When an employee leaves the job or work location of their own volition or is discharged for cause or is not working as a result of the Contractor's invocation of Section 7 below, they shall be paid only for the actual time worked.

D. Except as specifically set forth in this Article there shall be no premiums, bonuses, hazardous duty, high time or other special premium payments or reduction in shift hours of any kind.

E. There shall be no pay for time not actually worked except as specifically set forth in this Article and except where an applicable Schedule A requires a full weeks' pay for forepersons.

# SECTION 7. PAYMENT OF WAGES

A. Termination- Employees who are laid off or discharged for cause shall be paid in full for that which is due them at the time of termination. The Contractor shall also provide the employee with a written statement setting forth the date of lay off or discharge.

# SECTION 8. EMERGENCY WORK SUSPENSION

A Contractor may, if considered necessary for the protection of life and/or safety of employees or others, suspend all or a portion of Program Work. In such instances, employees will be paid for actual time worked, except that when a Contractor requests that employees remain at the job site available for work, employees will be paid for that time at their hourly rate of pay.

# **SECTION 9. INJURY/DISABILITY**

An employee who, after commencing work, suffers a work-related injury or disability while performing work duties, shall receive no less than a full day's pay in accordance with the employee's regularly scheduled work day under Article 12, section (1)(A). Further, the employee shall be rehired at such time as able to return to duties provided there is still Program Work available for which the employee is qualified and able to perform.

# SECTION 10, TIME KEEPING

A Contractor may utilize brassing or other systems to check employees in and out. Each employee must check in and out. The Contractor will provide adequate facilities for checking in and out in an expeditious manner.

# SECTION 11. MEAL PERIOD

A Contractor shall schedule an unpaid period of not more than 1/2 hour duration at the work location between the 3rd and 5th hour of the scheduled shift. A Contractor may, for efficiency of operation, establish a schedule which coordinates the meal periods of two or more crafts or which provides for staggered lunch periods within a

43

craft or trade. If an employee is required to work through the meal period, the employee shall be compensated in a manner established in the applicable Schedule A.

# SECTION 12. BREAK PERIODS

There will be no rest periods, organized coffee breaks or other non-working time established during working hours. Individual coffee containers will be permitted at the employee's work location. Where 4/10s are being worked there shall be a morning and an afternoon coffee break.

# **ARTICLE 13 - APPRENTICES**

# SECTION 1. RATIOS

Recognizing the need to maintain continuing supportive programs designed to develop adequate numbers of competent workers in the construction industry and to provide craft entry opportunities for minorities, women and economically disadvantaged non-minority males, Contractors will employ apprentices in their respective crafts to perform such work as is within their capabilities and which is customarily performed by the craft in which they are indentured. Contractors may utilize apprentices and such other appropriate classifications in the maximum ratio permitted by the New York State Department of Labor or the maximum allowed per trade. Apprentices and such other classifications as are appropriate shall be employed in a manner consistent with the provisions of the appropriate Schedule A. The parties encourage, as an appropriate source of apprentice recruitment consistent with the rules and operations of the affiliated unions' apprentice-programs, the use of the Edward J. Malloy Initiative for Construction Skills, Non-Traditional Employment for Women and Helmets to Hardhats.

44

# ARTICLE 14-SAFETY PROTECTION OF PERSON AND PROPERTY

#### SECTION 1. SAFETY REQUIREMENTS

Each Contractor will ensure that applicable OSHA and safety requirements are at all times maintained on the Program Work site and the employees and Unions agree to cooperate fully with these efforts to the extent consistent with their rights and obligations under the law. Employees will cooperate with employer safety policies and will perform their work at all times in a safe manner and protect themselves and the property of the Contractor and Agency from injury or harm, to the extent consistent with their rights and obligations under the law. Failure to do so will be grounds for discipline, including discharge.

#### **SECTION 2. CONTRACTOR RULES**

Employees covered by this Agreement shall at all times be bound by the reasonable safety, security, and visitor rules as established by the Contractors and the Construction Manager for this Program Work. Such rules will be published and posted in conspicuous places throughout the Program Work sites. Any site security and access policies established by the Construction Manager or General Contractor intended for specific application to the construction workforce for Program Work and that are not established pursuant to an Agency directive shall be implemented only after notice to the BCTC and its affiliates and an opportunity for negotiation and resolution by the Labor Management Committee.

Execution Copy 2015-2018

45

#### **SECTION 3. INSPECTIONS**

The Contractors and Construction Manager retain the right to inspect incoming shipments of equipment, apparatus, machinery and construction materials of every kind.

#### ARTICLE 15 - TEMPORARY SERVICES

Temporary services, i.e. all temporary heat, climate control, water, power and light, shall only be required upon the determination of the Agency or Construction Manager, and when used shall be staffed and assigned to the appropriate trade(s) with jurisdiction. Temporary services shall be provided by the appropriate Contractors' existing employees during working hours in which a shift is scheduled for employees of this Contractor. The Agency or Construction Manager may determine the need for temporary services requirements during non-working hours, and when used shall be staffed and assigned to the appropriate trades(s). There shall be no stacking of trades on temporary services, provided this does not constitute a waiver of primary trade jurisdiction. In the event a temporary system component is claimed by multiple trades, the matter shall be resolved through the New York Plan for Jurisdictional Disputes.

#### **ARTICLE 16 - NO DISCRIMINATION**

#### SECTION 1. COOPERATIVE EFFORTS

The Contractors and Unions agree that they will not discriminate against any employee or applicant for employment because of creed, race, color, religion, sex, sexual orientation, national origin, marital status, citizenship status, disability, age or any other status provided by law, in any manner prohibited by law or regulation.

46

# **SECTION 2. LANGUAGE OF AGREEMENT**

The use of the masculine or feminine gender in this Agreement shall be construed as including both genders.

#### **ARTICLE 17- GENERAL TERMS**

#### SECTION 1. PROJECT RULES

A. The Construction Manager and the Contractors shall establish such reasonable Program Work rules that are not inconsistent with this Agreement or rules common in the industry and are reasonably related to the nature of work. These rules will be explained at the pre-job conference and posted at the Program Work sites and may be amended thereafter as necessary. Notice of amendments will be provided to the appropriate Local Union. Failure of an employee to observe these rules and regulations shall be grounds for discipline, including discharge. The fact that no order was posted prohibiting a certain type of misconduct shall not be a defense to an employee disciplined or discharged for such misconduct when the action taken is for cause.

B. The parties adopt and incorporate the BCTC's Standards of Excellence as annexed hereto as Exhibit "B".

## SECTION 2. TOOLS OF THE TRADE

The welding/cutting torch and chain fall are tools of the trade having jurisdiction over the work performed. Employees using these tools shall perform any of the work of the trade. There shall be no restrictions on the emergency use of any tools or equipment by any qualified employee or on the use of any tools or equipment for the performance of work within the employee's jurisdiction.

47

#### **SECTION 3. SUPERVISION**

Employees shall work under the supervision of the craft foreperson or general foreperson.

# SECTION 4. TRAVEL ALLOWANCES

There shall be no payments for travel expenses, travel time, subsistence allowance or other such reimbursements or special pay except as expressly set forth in this Agreement.

#### **SECTION 5. FULL WORK DAY**

Employees shall be at their work area at the starting time established by the Contractor, provided they are provided access to the work area. The signatories reaffirm their policy of a fair day's work for a fair day's wage.

# SECTION 6. COOPERATION AND WAIVER

The Construction Manager, Contractors and the Unions will cooperate in seeking any NYS Department of Labor, or any other government, approvals that may be needed for implementation of any terms of this Agreement. In addition, the Council, on their own behalf and on behalf of its participating affiliated Local Unions and their individual members, intend the provisions of this Agreement to control to the greatest extent permitted by law, notwithstanding contrary provisions of any applicable prevailing wage, or other, law and intend this Agreement to constitute a waiver of any such prevailing wage, or other, law to the greatest extent permissible only for work within the scope of this Agreement, including specifically, but not limited to those provisions relating to shift, night, and similar differentials and premiums. This Agreement does not, however,

48

constitute a waiver or modification of the prevailing wage schedules applicable to work not covered by this Agreement.

# ARTICLE 18. SAVINGS AND SEPARABILITY

## **SECTION 1. THIS AGREEMENT**

In the event that the application of any provision of this Agreement is enjoined, on either an interlocutory or permanent basis, or is otherwise determined to be in violation of law, or if such application may cause the loss of Program funding or any New York State Labor Law exemption for all or any part of the Program Work, the provision or provisions involved (and/or its application to particular Program Work, as necessary) shall be rendered, temporarily or permanently, null and void, but where practicable the remainder of the Agreement shall remain in full force and effect to the extent allowed by law (and to the extent no funding or exemption is lost), unless the part or parts so found to be in violation of law or to cause such loss are wholly inseparable from the remaining portions of the Agreement and/or are material to the purposes of the Agreement. In the event a court of competent jurisdiction finds any portion of the Agreement to trigger the foregoing, the parties will immediately enter into negotiations concerning the substance affected by such decision for the purpose of achieving conformity with the court determination and the intent of the parties hereto for contracts to be let in the future.

# SECTION 2. THE BID SPECIFICATIONS

In the event that the Agency's (or Construction Manager's) bid specifications, or other action, requiring that a successful bidder (and subcontractor) become signatory to this Agreement is enjoined, on either an interlocutory or permanent

basis. or is otherwise determined to be in violation of law. or may cause the loss of Program funding or any New York State Labor Law exemption for all or any part of the Program Work, such requirement (and/or its application to particular Program Work, as necessary) shall be rendered, temporarily or permanently, null and void, but where practicable the Agreement shall remain in full force and effect to the extent allowed by law and to the extent no funding or exemption is lost). In such event, the Agreement shall remain in effect for contracts already bid and awarded or in construction only where the Agency and Contractor voluntarily accepts the Agreement. The parties will enter into negotiations as to modifications to the Agreement to reflect the court or other action taken and the intent of the parties for contracts to be let in the future.

#### **SECTION 3. NON-LIABILITY**

In the event of an occurrence referenced in Section 1 or Section 2 of this Article, neither the Agency, the Construction Manager, any Contractor, nor any Union shall be liable, directly or indirectly, for any action taken, or not taken, to comply with any court order or injunction, other determination, or in order to maintain funding or a New York State Labor Law exemption for Program Work. Bid specifications will be issued in conformance with court orders then in effect and no retroactive payments or other action will be required if the original court determination is ultimately reversed.

#### **SECTION 4. NON-WAIVER**

Nothing in this Article shall be construed as waiving the prohibitions of Article 7 as to signatory Contractors and signatory Unions.

# **ARTICLE 19 - FUTURE CHANGES IN SCHEDULE A AREA CONTRACTS**

# SECTION 1. CHANGES TO AREA CONTRACTS


A. Schedule A to this Agreement shall continue in full force and effect until the Contractor and/or Union parties to the Area Collective Bargaining Agreements that are the basis for the Schedule A notify the Agency and Construction Manager in writing of the changes agreed to in that Area Collective Bargaining which are applicable to work covered by this Agreement and their effective dates.

B. It is agreed that any provisions negotiated into Schedule A collective bargaining agreements will not apply to work under this Agreement if such provisions are less favorable to those uniformly required of contractors for construction work normally covered by those agreements; nor shall any provision be recognized or applied on Program Work if it may be construed to apply exclusively, or predominantly, to work covered by this Agreement.

C. Any disagreement between signatories to this Agreement over the incorporation into Schedule A of provisions agreed upon in the renegotiation of Area Collective Bargaining Agreements shall be resolved in accordance with the procedure set forth in Article 9 of this Agreement.

# SECTION 2. LABOR DISPUTES DURING AREA CONTRACT NEGOTIATIONS

The Unions agree that there will be no strikes, work stoppages, sympathy actions, picketing, slowdowns or other disruptive activity or other violations of Article 7 affecting the Program Work by any Local Union involved in the renegotiation of Area



Local Collective Bargaining Agreements nor shall there be any lock-out on such Program Work affecting a Local Union during the course of such renegotiations.

#### **ARTICLE 20 - WORKERS' COMPENSATION ADR**

#### **SECTION 1.**

An ADR program may be negotiated and participation in the ADR Program

will be optional by trade.

#### **ARTICLE 21 - HELMETS TO HARDHATS**

#### **SECTION 1.**

The Contractors and the Unions recognize a desire to facilitate the entry into the building and construction trades of veterans who are interested in careers in the building and construction industry. The Contractors and Unions agree to utilize the services of the New York City Helmets to Hardhats Program to serve as a resource for preliminary orientation, assessment of construction aptitude, referral to apprenticeship programs or hiring halls, counseling and mentoring, support network, employment opportunities and other needs as identified by the parties.

#### SECTION 2.

The Unions and Contractors agree to coordinate with the Program to create and maintain an integrated database of veterans interested in working on this Project and of

apprenticeship and employment opportunities for this Project. To the extent permitted by law, the Unions will give credit to such veterans for bona fide, provable past experience.

IN WITNESS WHEREOF the parties have caused this Agreement to be executed and

effective as of the \_\_\_\_ day of \_\_\_\_\_

# FOR BUILDING AND CONSTRUCTION TRADES COUNCIL OF GREATER NEW YORK AND VICINITY

BY:

Gary LaBarbera President

# FOR NEW YORK CITY

BY:

Anthony Shorris First Deputy Mayor

APPROVED AS TO FORM:

# ACTING CORPORATION COUNSEL NEW YORK CITY

LIST OF SIGNATORY UNIONS	
Boiler Makers Local No. 5	
Carpenters District Council	
Cement Masons No. 780	
Concrete Workers, District Council No. 16	*******
Derrickmen and Riggers, Local Union No. 197	
Drywall Tapers 1974, District Council 9	****
Electrical Workers Local No. 3	*********
Glaziers Local Union No. 1087 District Council 9	*******
Heat & Frost Insulators, Local Union No. 12A	
Heat & Frost Insulators, Local Union No. 12	*******
Iron Workers District Council	
Iron Workers Local Union No. 40	
Iron Workers Local No. 361	
Laborers Local No. 78, Asbestos & Lead Abatement	*******
Laborers Local 1010 Pavers and Road Builders District Council	
Laborers 79 Construction and General Building Laborers	
Laborers Local No. 731 Excavators	
Mason Tenders District Council	
Metal Lathers Local No. 46	
Metal Polishers District Council 9	•••••••••••
Ornamental Iron Workers Local No. 580	*******
Painters District Council 9	
Plumbers Local No. 1	
Painters, Decorators & Wallcoverers District Council 9	
Painters Structural Steel No. 806	*******
Plasterers Local Union No. 262	
Roofers & Waterproofers Local 8	
Steamfitters Local Union No. 638	·····
Sheet Metal Workers Local No. 28	*******
Sheet Metal Workers Local No. 137	
Teamsters Local Union No. 282	******
Teamsters Local Union 814	
Teamsters Local No. 813 Private Sanitation	
Tile, Marble & Terrazzo B.A.C. Local Union No. 7	******



2015-2018

# SCHEDULE "A"

Union	Current Agreement w/
Architectural and Ornamental Iron Workers Local Union 580, AFL-CIO	Allied Building Metal Industries, Inc.
Building, Concrete, Excavating & Common Laborers Local 731	Independent
Building: Concrete, Excavating & Common Laborers Local 731	Members of the General Contractors Association of New York, Inc.
District Council No. 9, I.U.P.A.T Glaziers Local 1087	Window and Plate Glass Dealers Association
Drywall Tapers and Pointers Local 1974, affiliated with International Union of Painters & Allied Trades and Drywall Taping Contractor's Association & Association of Wall-Ceiling & Carpentry Industries NY. Inc.	Independent
Enterprise Association of Steamfitters and Apprentices Local 638	Mechanical Contractors Association of NY. Inc.
Enterprise Association of Steamfitters and Apprentices Local 638	Independent
Highway Road and Street Laborers Local Union 1010 of the District Council of Pavers and Road Builders of the Laborers' International Union of North America AFL-CIO	Independent
Highway Road and Street Laborers Local Union 1010 of the District Council of Pavers and Road Builders of the Laborers' International Union of North America AFL-CIO	Member of the General Contractors Association of New York. Inc.
International Association of Heat and Frost Insulators and Allied Workers Local No. 12 of New York City	Independent
International Association of Heat and Frost Insulators and Allied Workers Local No. 12 of New York City	The Insulation Contractors Association of New York City, Inc.
International Association of Heat and Frost Insulators and Allied Workers Local No. 12A of New York City	Independent

89

International Association of Heat and Frost Insulators and Allied Workers Local No. 12A of New York City	Environmental Contractors Association. Inc.
International Brotherhood of Boilermakers, Iron Ship Builders, Blacksmiths, Forgers and Helpers, AFL-CIO, Local Lodge No. 5	Boilermakers Association of Greater New York
Local Union No. 3 International Brotherhood of Electrical Workers, AFL-CIO	New York Electrical Contractors Association
International Brotherhood of Teamsters, Local 282, High Rise contract	Building Contractors Association & Independents
Local 46 Metallic Lathers Union and Reinforcing Iron Workers of NY and Vicinity of the International Association of Bridge, Structural, Ornamental and Reinforcing Iron Workers	Cement League
Local 46 Metallic Lathers Union and Reinforcing Iron Workers of NY and Vicinity of the International Association of Bridge, Structural, Ornamental and Reinforcing Iron Workers	Independent
Local 8 Roofers, Waterproofers & Allied Workers	Roofing and Waterproofing Contractors Association of New York and Vicinity
Local Union 1 of the United Association of Journeymen and Apprentices of the Pipe Fitting Industry of the United States and Canada	Association of Contracting Plumbers of the City of New York
Local Union Number 40 & 361 of Bridge. Structural Ornamental and Reinforcing Iron Workers AFL-CIO	Independent
Operative Plasterers' and Cement Masons' nternational Association Local No. 262	Independent
Painters and Allied Trades AFL-CIO. District Jouncil No. 9 (Painting and Protective Joatings CBA)	Independent

Execution Copy 2015-2018

Painters and Allied Trades AFL-CIO, District Council No. 9 (Painting and Protective Coatings CBA)	The Association of Master Painters & Decorators of NY. Inc. and The Association of Wall, Ceiling & Carpentry Industries of NY. Inc. and The Window and Plate Glass Dealers Association	
Sheet Metal Workers' International Association. Local 28	Sheet Metal & Air Conditioning Contractors Association of New York City, Inc.	
Sheet Metal Workers' International	The Greater New York Sign Association	
Association, Local 137		
n na maganang at ang		
Structural Steel and Bridge Painters Local 806, DC 9 International Union of Painters and Allied Trades, AFL-CIO	New York Structural Steel Painting Contractors Association	
AFICE HARCO, MAR STO		
Teamsters Local 813	Independent	
Teamsters Local 813	IESI NY Corporation	
Teamsters Local 814	Greater New York Movers and Warehousemen's Bargaining Group	
The Cement Masons' Union, Local 780	Cement League	
The District Council of Cement and Concrete Workers (comprised of Local 6A: Local 18A and Local 20)	Cement League	
The District Council of Cement and Concrete Workers (comprised of Local 6A: Local 18A and Local 20)	Independent	

91

The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Heavy Carpenters	GCA
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Dockbuilders Local No. 1556	Concrete Contractors of NY
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Dockbuilders Local 1556	Independent
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Millwright Local 740	Independent
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Timbermen Local 1556	Independent
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Timbermen Local 1556	GCA
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Heavy Carpenters	Independent
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Carpenters	Manufacturing Woodworkers Association of Greater New York Incorporated
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America	The Hoisting Trade Association of New York, Inc.
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America	The Test Boring Association



Execution Copy 2015-2018

The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America	Building Contractors Association
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America	The Association of Wall-Ceiling & Carpentry Industries of New York, Incorporated
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners	The Cement League
The District Council of NYC and Vicinity of the United Brotherhood of Carpenters and Joiners of America	New York City Millwright Association
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners	Greater New York Floor Covering Association
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Carpenters	Association of Architectural Metal & Glass
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Carpenters	Concrete Contractors of NY
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Building Construction Carpenters	Independent
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Local 2287	Independent
The District Council of New York City and Vicinity of the United Brotherhood of Carpenters and Joiners of America for Shop Carpenters	Independent
The Tile Setters and Tile Finishers Union of New York and New Jersey, Local 7 of the International Bricklayers and Allied Craftworkers	The Greater New York and New Jersey Contractors Association

Execution Copy 2015-2018

a napadag siyahan gerenyesansi ya Karan Ina ana a wila naman sena dadamin geneger kang senamanan wasananan nama

United Derrickmen & Riggers Association, Local 197 of NY, LI, Westchester & Vicinity	Contracting Stonesetters Association Inc.
United Derrickmen & Riggers Association L 197 of NY, LI, Westchester and Vicinity	Building Stone and Pre-cast Contractors Association
International Union of Operating Engineers Local 14-14B	Building Contractors Association
International Union of Operating Engineers Local 14-14B	Contractors Association of Greater NY
International Union of Operating Engineers Local 14-14B	GCA
International Union of Operating Engineers Local 14-14B	The Cement League
International Union of Operating Engineers Local 14-14B	Allied Building Metal Industries, Inc.
International Union of Operating Engineers Local 14-14B	Brick Association
International Union of Operating Engineers Local 14-14B	Independent
International Union of Operating Engineers Local 15	Allied Building Metal Industries, Inc.
International Union of Operating Engineers Local 15-15A	General Contractors Association
nternational Union of Operating Engineers Local 15D	General Contractors Association
nternational Union of Operating Engineers local 15D	Structural Steel Erectors

Execution Copy 2015-2018

International Union of Operating Engineers Local 15-15A	Building Contractors Association
International Union of Operating Engineers Local 15D	Building Contractors Association
International Union of Operating Engineers Local 15-15A	Contractors Association of Greater NY
International Union of Operating Engineers Local 15D	Contractors Association of Greater NY
International Union of Operating Engineers Local 15-15A	The Cement League
International Union of Operating Engineers Local 15D	The Cement League

95

# Project Labor Agreement - - Letter of Assent

#### Dear:

The undersigned party confirms that it agrees to be a party to and be bound by the New York Agency, Project Labor Agreement as such Agreement may, from time to time, be amended by the parties or interpreted pursuant to its terms. The terms of the Project Labor Agreement, its Schedules, Addenda and Exhibits are hereby incorporated by reference herein.

The undersigned, as a Contractor or Subcontractor (hereinafter Contractor) on the Project known as \_\_\_\_\_\_\_ and located at \_\_\_\_\_\_\_ (hereinafter PROJECT), for and in consideration of the award to it of a contract to perform work on said PROJECT, and in further consideration of the mutual promises made in the Project Labor Agreement, a copy of which was received and is acknowledged, hereby:

- (1) Accepts and agrees to be bound by the terms and conditions of the Agreement, together with any and all schedules; amendments and supplements now existing or which are later made thereto;
- (2) Agrees to be bound by the legally established collective bargaining agreements: local trust agreements for employee benefit funds; and trust documents for joint apprentice programs as well as apprentice program rules and procedures but only to the extent of Program Work and as required by the PLA.
- (3) Authorizes the parties to such local trust agreements to appoint trustees and successor trustees to administer the trust funds and hereby ratifies and accepts the trustees so appointed as if made by the Contractor but only to the extent of Program Work as required by the PLA.
- (4) Certifies that it has no commitments or agreements that would preclude its full and complete compliance with the terms and conditions of said Agreement. The Contractor agrees to employ labor that can work in harmony with all other labor on the Project and shall require labor harmony from every lower tier subcontractor it has engaged or may engage to work on the Project. Labor harmony disputes/issues shall be subject to the Labor Management Committee provisions.
- (5) Agrees to secure from any Contractor(s) (as defined in said Agreement) which is or becomes a Subcontractor (of any tier), to it, a duly executed Agreement to be Bound in from identical to this document.

Provide description of the Work, identify craft jurisdiction(s) and all contract numbers below:

Dated:

(Name of CM; GC; Contractor or Higher Level Subcontractor) (Name of Contractor or subcontractor)

(Authorized Officer & Title)

(Address)

#

(Phone) (Fax)

Contractor's State License

Sworn to before me this \_\_\_\_\_ day of \_\_\_\_\_\_,

Notary Public

97

# NEW YORK CITY BUILDING AND CONSTRUCTION TRADES COUNCIL STANDARDS OF EXCELLENCE

The purpose of this Standard of Excellence is to reinforce the pride of every construction worker and the commitment to be the most skilled, most productive and safest workforce available to construction employers and users in the City of New York. It is the commitment of every affiliated local union to use our training and skills to produce the highest quality work and to exercise safe and productive work practices.

The rank and file members represented by the affiliated local unions acknowledge and adopt the following standards:

- Provide a full days work for a full days pay;
- Safely work towards the timely completion of the job;
- > Arrive to work on time and work until the contractual quitting time;
- Adhere to contractual lunch and break times;
- > Promote a drug and alcohol free work site;
- > Work in accordance with all applicable safety rules and procedures;
- Allow union representatives to handle job site disputes and grievances without resort to slowdowns, or unlawful job disruptions;
- > Respect management directives that are safe, reasonable and legitimate;
- Respect the rights of co-workers;
- > Respect the property rights of the owner, management and contractors.

The Unions affiliated with the New York City Building and Construction Trades Council will expect the signatory contractors to safely and efficiently manage their jobs and the unions see this as a corresponding obligation of the contractors under this Standard of Excellence. The affiliated unions will expect the following from its signatory contractors:

- Management adherence to the collective bargaining agreements;
- > Communication and cooperation with the trade foremen and stewards;
- > Efficient, safe and sanitary management of the job site;
- > Efficient job scheduling to mitigate and minimize unproductive time;
- > Efficient and adequate staffing by properly trained employees by trade;
- Efficient delivery schedules and availability of equipment and tools to ensure efficient job progress;
- > Ensure proper blueprints, specifications and layout instructions and material are available in a timely manner
- > Promote job site dispute resolution and leadership skills to mitigate such disputes;
- > Treatment of all employees in a respectful and dignified manner acknowledging their contributions to a successful project.

The affiliated unions and their signatory contractors shall ensure that both the rank and file members and the management staff shall be properly trained in the obligations undertaken in the Standard of Excellence.





BuildSaleNVC establishes that all BTEA member companies and BCTC member unions establish minimum safety standards on all building construction projects in NYC as follows:

The workforce shell adhere to the minimum personal protective equipment (PPE) usage to include:

 ANSt compliant Hard Hats (with ratchet suspansion) at all times (supplied by employer)
 Construction-type Work Boots at all times

c. Long Pants and shirts with at least short sleeves at all times (no shorts or task tops)

L. Long rains and arrow work at least short servers at an writer (to shorts or team type) d. ANSI compliant Eye Protection in their possession and used as needed (supplied by employer) a, Adequate Hearing Protection in their possession and used as needed (supplied by employer) L High-vis traitile vents at street level and when around heavy equipment (supplied by employer)

CM and Subcontractor management shall implement a fail and consistent disciplinary policy for all size personnal regarding the adherence to size safety rules and requirements. Likewise, a joint labor / management team will periodically assess project wide implementation of these Codes.

3. CM firms shall maintain minimum standards for worklorce restroom, hygiens facilities and housekeeping, initially and throughout the duration of the project.

4. All personnel shall adhere to a strict policy equinst drug and alcohol possession and use on size and during hours of work.

5. All personnel shall attend a alta safety orientation prior to beginning work. Worker certifications of existy training for specific tasks such as line watch, flagmen, and salety attendant must be verified.

8. No coll phones, portable media devices, ratios, or other devices that limit hearing and attention shall be used while working on sites.

7. Ground Faux Circuit Interrupters (GFCI) will be used on all power tools and eidension cords.

8. Union trade representatives shall participate in a regularly scheduled site safety meeting on all projects regardless of size.

Extreme effort shall be made to isolate the public from all construction activity. Specifically, systems shall be put in place to control taking materials and pedestrian exposure. This should be a top priority for the entire project workforce.

10. Woders shall honor security access control systems to establish entry to sites by authorized personnel only, where applicable.

11 .Fall protection management shall be a top project priority. Workers shall maintain and use necessary fall protection systems and procedures where appropriate. Engineering controls and work methods which eliminate, guard, or otherwise control fall hezards shall take priority over personal fall errest system usage.

12. Where hazardous materials are present, projects shall implement efforts to communicate and control potential exposure to the worldorce.

With Full Support and Endorsement of:

Calatti Levers & Malon Prede AL COD BTEANYChin May W. Strag uncip 133 cifina: AL. 84 dans Alland 1-st Denne AVI TRANITASA A Doulodras

## INFORMATION FOR BIDDERS JOB ORDER CONTRACTS March 2013

#### 1. Overview of the Contract

A Job Order Contract (JOC) is a requirement contract for indefinite quantities pursuant to which the Contractor will perform a variety of projects at different locations. The bid documents include a Construction Task Catalog® (CTC) containing a series of construction tasks with preset unit prices. For all the JOC Contracts listed below, the contractor will bid two Adjustment Factors: (1) Normal Working Hours Adjustment Factor; and (2) Other Than Normal Working Hours Adjustment Factor. The Other Than Normal Working Hours Factor must be equal to or greater than the Normal Working Hours Adjustment Factor. The Non-Pre-Priced Adjustment Factor is for calculating the cost of

tasks not included in the CTC.

The Department intends to award 13 contracts as set forth in the table below.

Trade	Project #	Units	Not to Exceed
			Contract Value
General	JOC2013G-1	Manhattan(except: Courts, Corrections & Juvenile Detention projects)	\$8,000,000
General	JOC2013G-2	Queens(except: Courts, Corrections & Juvenile Detention projects)	
General	JOC2013G-3	Brooklyn & Staten Island(except: Courts, Corrections & Juvenile Detention projects)	\$8,000,000
General	JOC2013G-4	Bronx(except: Courts, Corrections & Juvenile Detention projects)	\$8,000,000
General	JOC2013G-5	Courts, Corrections & Juvenile Detention projects city wide	\$8,000,000
Electric	JOC2013E-1	Manhattan & Bronx(except: Courts, Corrections & Juvenile Detention projects)	\$8,000,000
Electric	JOC2013E-2	Brooklyn & Staten Island(execution Courts, Corrections & Juvenile Detention projects)	\$5,000,000
Electric	JOC2013E-3	Brooklyn & Staten Island(except: Courts, Corrections & Juvenile Detention projects)	\$5,000,000
Plumbing	JOC2013P-1	Queens(including Courts, Corrections & Juvenile Detention projects city wide)	\$5,000,000
Plumbing	JOC2013P-2	Queens & Bronx(including Courts, Corrections & Juvenile Detention projects)	\$3,000,000
- Kannoning	3002013F-2	Manhattan, Brooklyn & Staten Island (except: Courts, Corrections & Juvenile Detention projects)	\$3,000,000
HVAC	JOC2013H-1	Manhattan & Bronx(except: Courts, Corrections & Juvenile Detention projects)	<u> </u>
HVAC	JOC2013H-2	Brooklyn& Staten Island/except: Courts, Corrections & Juvenile Detention projects)	\$5,000,000
HVAC	JOC2013H-3	Brooklyn& Staten Island(except: Courts, Corrections & Juvenile Detention projects)	\$5,000,000
	1	Queens(including Courts, Corrections & Juvenile Detention projects city wide)	\$5,000,000

As individual projects are identified, the Contractor will participate in a Joint Scope Meeting at the site and discuss, among other things, the scope of the work and the schedule for completion. After the Joint Scope Meeting, the Department will send the Contractor a draft Detailed Scope of Work which the Contractor will review. Once the Detailed Scope of Work is finalized, the Department will send to the Contractor a Request for Proposal and the Detailed Scope of Work. The Contractor will then develop a Proposal, including a Price Proposal, based on the preset unit prices and the appropriate Adjustment Factors. If the Proposal is acceptable to the Department, a Job Order may be issued. The Job Order will require the Contractor to perform the Detailed Scope of Work, within the Job Order Completion Time, for the lump sum Job Order Price.

#### 2. Time and Place for Receipt of Bids

Sealed bids shall be received on or before the date and hour specified in Attachment 1, at which time they will be publicly opened and read aloud in the presence of the Commissioner or his or her representative, and any bidders who may desire to be present.



CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

INFORMATION FOR BIDDERS MARCH 2013

#### 3. **Definitions**

The definitions set forth in the Procurement Policy Board Rules shall apply to this Invitation For Bids.

#### Invitation For Bids and Contract Documents 4.

(A) Except for titles, sub-titles, headings, running headlines, tables of contents and indices (all of which are printed herein merely for convenience) the following, except for such portions thereof as may be specifically excluded, shall be deemed to be part of the Contract and the Invitation for Bids.

All provisions required by law to be inserted in this Contract, whether actually inserted (1)

or not

The Construction Task Catalog and Specifications (2)

The General Conditions, the General Requirements and the Special Conditions, if (3)

any

The Contract (4)

- The Information for Bidders; Request for Proposals; Notice of Solicitation and (5) Proposal For Bids; Bid or Proposal, and, if used, the Bid Booklet
- All Addenda issued prior to the receipt of the bids; the Notice of Award; Performance (6)and Payment Bonds, if required; and the Notice to Proceed with the Work.

(B) For particulars as to this procurement, including quantity and quality of the purchase, extent of the work or labor to be performed, delivery and performance schedule, and any other special instructions, prospective bidders are referred to the Invitation For Bids Documents. A copy of such documents can be obtained at the location set forth in Attachment 1.

(C) Deposit for Copy of Invitation For Bids Documents: Prospective bidders may obtain a copy of the Invitation For Bids Documents by complying with the conditions set forth in the Notice of Solicitation. The deposit must be in the form of a check or money order made payable to the City of New York, and drawn upon a state or national bank or trust company, or a check of such bank or trust company signed by a duly authorized officer thereof.

(D) Return of Invitation For Bids Documents: All Invitation For Bids Documents must be returned to the Department upon request. If the bidder elects not to submit a bid thereunder, the Invitation For Bids Documents shall be returned to the Department, along with a statement that no bid will be submitted.

(E) Return of Deposit: Such deposit will be returned within 30 days after the award of the contract or the rejection of all bids as set forth in the advertisement, provided the Invitation For Bids Documents are returned to the location specified in Attachment 1, in physical condition satisfactory to the Commissioner.

(F) Additional Copies: Additional copies of the Invitation For Bids Documents may be obtained, subject to the conditions set forth in the advertisement for bids.

#### Pre-Bid Conference 5.

A pre-bid conference shall be held as set forth in Attachment 1. Nothing stated at the pre-bid conference shall change the terms or conditions of the Invitation For Bids Documents, unless a change is made by written amendment as provided in Section 9 below. Failure to attend a mandatory pre-bid conference shall constitute grounds for the rejection of the bid.

#### Agency Contact 6.

Any questions or correspondence relating to this bid solicitation shall be addressed to the Agency Contact person specified in Attachment 1.

#### **Bidder's Oath** 7.

(A) The bid shall be properly signed by an authorized representative of the bidder and the bid shall be verified by the written oath of the authorized representative who signed the bid, that the several matters stated and information furnished therein are in all aspects true.

(B) A materially false statement willfully or fraudulently made in connection with the bid or any of the forms completed and submitted with the bid may result in the termination of any Contract between the City and the Bidder. As a result, the Bidder may be barred from participating in future City contracts as well as be subject to possible criminal prosecution.

#### 8. Not Used.

## 9. Examination of Proposed Contract

(A) <u>Request for Interpretation or Correction</u>: Prospective bidders must examine the Contract Documents carefully and before bidding must request the Commissioner in writing for an interpretation or correction of every patent ambiguity, inconsistency or error therein which should have been discovered by a reasonably prudent bidder. Such interpretation or correction, as well as any additional contract provisions the Commissioner may decide to include, will be issued in writing by the Commissioner as an addendum to the Contract, which will be transmitted to each person recorded as having received a copy of the Contract Documents from the Department. Transmission of such addendum will be by mail, e-mail, facsimile or hand delivery. Such addendum will also be posted at the place where the Contract Documents are available for the inspection of prospective bidders. Upon transmission as provided for herein, such addendum shall become a part of the Contract Documents, and binding on all bidders, whether or not actual notice of such addendum is shown.

(B) <u>Only Commissioner's Interpretation or Correction Binding</u>: Only the written interpretation or correction so given by the Commissioner shall be binding, and prospective bidders are warned that no other officer, agent or employee of the City is authorized to give information concerning, or to explain or interpret, the Contract.

(C) Documents given to a subcontractor for the purpose of soliciting the subcontractor's bid shall include either a copy of the bid cover sheet or a separate information sheet setting forth the project name, the Contract number (if available), the contracting agency and the Project's location.

#### 10. Form of Bid

Each bid must be submitted upon the prescribed form and must contain: a) the name, residence and place of business of the person or persons making the same; b) the names of all persons interested therein, and if no other person is so interested, such fact must be distinctly stated; c) a statement to the effect that it is made without any connection with any other person making a bid for the same purpose and that it is in all respects fair and without collusion or fraud; d) a statement that no Council member or other officer or employee or person whose salary is payable in whole or part from the City Treasury is directly or indirectly interested therein or in the supplies, materials or equipment and work or labor to which it relates, or in any portion of the profits thereof; e) a statement that the bidder is not in arrears to the City or to any agency upon a debt or contract or taxes, and is not a defaulter as surety or otherwise upon any obligation to the City to any agency thereof, except as set forth in the bid.

THE BID SHALL BE TYPEWRITTEN OR WRITTEN LEGIBLY IN INK. THE BID SHALL BE SIGNED IN INK. ERASURES OR ALTERATIONS SHALL BE INITIALED BY THE SIGNER IN INK. FAILURE TO CONFORM TO THE REQUIREMENTS OF THIS SECTION 10 SHALL RESULT IN THE REJECTION OF THE BID.

#### 11. Irrevocability of Bid

The prices set forth in the bid cannot be revoked and shall be effective until the award of the Contract, unless the bid is withdrawn as provided for in Sections 15 and 18 below.

#### 12. Acknowledgment of Addendum

The receipt of any addendum to the Contract Documents shall be acknowledged by the bidder in its bid submission.

CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

Page 3 of 11

#### 13. Bid Samples and Descriptive Literature

Bid samples and descriptive literature shall not be submitted by the bidder, unless expressly requested elsewhere in the Contract or Contract Documents. Any unsolicited bid samples or descriptive literature which are submitted shall not be examined or tested and shall not be deemed to vary any of the provisions of this Contract.

#### 14. Proprietary Information/Trade Secrets

(A) The bidder shall identify those portions of the bid which it deems to be confidential, proprietary information or trade secrets, and provide justification why such materials shall not be disclosed by the City. All such materials shall be clearly indicated by stamping the pages on which such information appears, at the top and bottom thereof with the word "Confidential". Such materials stamped "Confidential" must be easily separable from the non-confidential sections of the bid.

(B) All such materials so indicated shall be reviewed by the Agency and any decision not to honor a request for confidentiality shall be communicated in writing to the bidder. For those bids which are unsuccessful, all such confidential materials shall be returned to the bidder. Prices, makes and model or catalog numbers of the items offered, deliveries, and terms of payment shall be publicly available after bid opening, regardless of any designation of confidentiality made by the bidder.

#### 15. Pre-Opening Modification or Withdrawal of Bids

Bids may be modified or withdrawn by written notice received in the office designated in Attachment 1, before the time and date set for the bid opening. If a bid is withdrawn in accordance with this Section, the bid security, if any, shall be returned to the bidder.

#### 16. Bid Evaluation and Award

In accordance with the New York City Charter, the Procurement Policy Board Rules and the terms and conditions of this Invitation For Bids, this Contract shall be awarded, if at all, to the responsible bidder whose bid meets the requirements and evaluation criteria set forth in the Invitation For Bids, and whose bid price is either the most favorable bid price or, if the Invitation For Bids so states, the most favorable evaluated bid price. A bid may not be evaluated for any requirement or criterion that is not disclosed in the Invitation For Bids. Provided, however, that this solicitation is for a series of similar contracts and if a bidder bids on more than one contract, or already has an active contract in the series, the award of any contract in the series will be in the overall best interest of the Department.

If a Contractor is the apparent low bidder on more than one contract, then the Contractor will be required to demonstrate that it has the capacity to perform each of the contracts for which it is the apparent low bidder, including the bidder's ability to coordinate and perform work at multiple sites with multiple crews simultaneously. If the Contractor is unable to provide documentary or other proof that it has the capacity to perform all such contracts, the Contractor will be found non-responsive to the extent it does not have capacity. If the Department determines that the Contractor does not have the capacity for all such contracts, then the Department will determine which contracts to award to such Contractor based on the overall best interest of the City.

<u>Restriction:</u> No negotiations with any bidder shall be allowed to take place except under the circumstances and in the manner set forth herein. Nothing in this Section shall be deemed to permit a contract award to a bidder submitting a higher quality item than that designated in the Invitation For Bids, if that bid is not also the most favorable bid.

#### 17. Late Bids, Late Withdrawals and Late Modifications

Any bid received at the place designated in the solicitation after the time and date set for receipt of bids is late and shall not be considered. Any request for withdrawal or modification received at the place designated in the solicitation after the time and date set for receipt of bids is late and shall not be considered. The exception to this provision is that a late modification of a successful bid that makes the bid terms more favorable to the City shall be considered at any time it is received.

#### 18. Withdrawal of Bids.

Except as provided for in Section 15, above, a bidder may not withdraw its bid before the expiration of forty-five (45) days after the date of the opening of bids; thereafter, a bidder may withdraw its bid only in writing and in advance of an actual award. If within sixty (60) days after the execution of the Contract, the Commissioner fails to fix the date for commencement of work by written notice to the bidder, the bidder, at his option, may ask to be relieved of his obligation to perform the work called for by written notice to the Commissioner. If such notice is given to the Commissioner, and the request to withdraw is granted, the bidder waives all claims in connection with this Contract.

19. <u>Mistake in Bids</u>

(A) <u>Mistake Discovered Before Bid Opening:</u> A bidder may correct mistakes discovered before the time and date set for bid opening by withdrawing or correcting the bid as provided in Section 15 above.

#### (B) Mistakes Discovered Before Award

(1) In accordance with General Municipal Law (Section 103, subdivision 11), where a unilateral error or mistake is discovered in a bid, such bid may be withdrawn upon written approval of the Agency Chief Contracting Officer if the following conditions are met:

- (a) The mistake is known or made known to the agency prior to the awarding of the Contract or within 3 days after the opening of the bid, whichever period is shorter; and
- (b) The price bid was based upon an error of such magnitude that enforcement would be unconscionable; and
- (c) The bid was submitted in good faith and the bidder submits credible evidence that the mistake was a clerical error as opposed to a judgment error; and
- (d) The error in the bid is actually due to an unintentional and substantial arithmetic error or an unintentional omission of a substantial quantity of work, labor, material or services made directly in the compilation of the bid, which unintentional arithmetic error pr unintentional omission can be clearly shown by objective evidence drawn from inspection of the original work paper, documents, or materials used in the preparation of the bid sought to be withdrawn; and
- (e) It is possible to place the agency in the same position as existed prior to the bid.

(2) Unless otherwise required by law, the sole remedy for a bid mistake in accordance with this Article shall be withdrawal of the bid, and the return of the bid bond or other security, if any, to the bidder. Thereafter, the agency may, in its discretion, award the Contract to the next lowest bidder or rebid the Contract. Any amendment to or reformation of a bid or a Contract to rectify such an error or mistake therein is strictly prohibited.

(3) If the mistake and the intended correct bid are clearly evident on the face of the bid document, the bid shall be corrected to the intended correct bid and may not be withdrawn. Examples of mistakes that may be corrected are typographical errors, errors in extending unit prices, transposition errors and arithmetical errors.

#### 20. Low Tie Bids

(A) When two or more low responsive bids from responsible bidders are identical in price, meeting all the requirements and criteria set forth in the Invitation For Bids, the Agency Chief Contracting Officer will break the tie in the following manner and order of priority:

(B) If two or more bidders still remain equally eligible after application of paragraph (A) above, award shall be made by a drawing by lot limited to those bidders. The bidders involved shall be invited to attend the drawing. A witness shall be present to verify the drawing and shall certify the results on the bid tabulation sheet.

- 21. <u>Rejection of Bids</u>
  - (A) <u>Rejection of Individual Bids:</u> The Agency may reject a bid if:

CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION

- (1) The bidder fails to furnish any of the information required pursuant to Section 24 or 28 hereof; or if
- (2) The bidder is determined to be not responsible pursuant to the Procurement Policy Board Rules; or if
- (3) The bid is determined to be non-responsive pursuant to the Procurement Policy Board Rules; or if
- (4) The bid, in the opinion of the Agency Chief Contracting Officer, contains unbalanced bid prices and is thus non-responsive, unless the bidder can show that the prices are not unbalanced for the probable required quantity of items, or if the imbalance is corrected pursuant to Section 15.

(B) <u>Rejection of All Bids</u>: The Agency, upon written approval by the Agency Chief Contracting Officer, may reject all bids and may elect to resolicit bids if in its sole opinion it shall deem it in the best interest of the City so to do.

(C) <u>Rejection of All Bids and Negotiation With All Responsible Bidders:</u> The Agency Head may determine that it is appropriate to cancel the Invitation For Bids after bid opening and before award and to complete the acquisition by negotiation. This determination shall be based on one of the following reasons:

- (1) All otherwise acceptable bids received are at unreasonable prices, or only one bid is received and the Agency Chief Contracting Officer cannot determine the reasonableness of the bid price, or no responsive bid has been received from a responsible bidder; or
- (2) In the judgment of the Agency Chief Contracting Officer, the bids were not independently arrived at in open competition, were collusive, or were submitted in bad faith.

(D) When the Agency has determined that the Invitation for Bids is to be canceled and that use of negotiation is appropriate to complete the acquisition, the contracting officer may negotiate and award the Contract without issuing a new solicitation, subject to the following conditions:

- prior to notice of the intention to negotiate and a reasonable opportunity to negotiate have been given by the contracting officer to each responsible bidder that submitted a bid in response to the Invitation to Bids;
- (2) the negotiated price is the lowest negotiated price offered by a responsible bidder; and
- (3) the negotiated price is lower than the lowest rejected bid price of a responsible bidder that submitted a bid in response to the Invitation for Bids.

22. <u>Right to Appeal Determinations of Non-Responsiveness or Non-Responsibility and Right to</u> <u>Protest Solicitations and Award</u>

The bidder has the right to appeal a determination of non-responsiveness or non-responsibility and has the right to protest a solicitation and award. For further information concerning these rights, the bidder is directed to the Procurement Policy Board Rules.

# 23. Affirmative Action and Equal Employment Opportunity

This Invitation For Bids is subject to applicable provisions of Federal, State and Local Laws and executive orders requiring affirmative action and equal employment opportunity.

#### 24. VENDEX Questionnaires

(A) <u>Requirement:</u> Pursuant to Administrative Code Section 6-116.2 and the PPB Rules, bidders may be obligated to complete and submit VENDEX Questionnaires. Generally, if this bid is \$100,000 or more, or if this bid when added to the sum total of all contracts, concessions and franchises the bidder has received from the City and any subcontracts received from City contractors over the past twelve months, equals or exceeds \$100,000, Vendex Questionnaires must be completed. If required, Vendex Questionnaires must be completed and submitted before any award of contract may be made or before approval is given for a proposed subcontractor. Non-compliance with these submission requirements may result in the disqualification of the bid, disapproval of a subcontractor, subsequent withdrawal of approval for the use of an approved subcontractor, or the cancellation of the contract after its award.

(B) <u>Submission</u>: Vendex Questionnaires must be submitted directly to the Mayor's Office of Contract Services, ATTN: Vendex, 253 Broadway, 9<sup>th</sup> Floor, New York, New York 10007. In addition, the bidder must submit a Confirmation of Vendex Compliance to the agency. A form for this confirmation is set forth in the Bid Booklet.

(C) <u>Obtaining Forms:</u> Vendex Questionnaires, as well as detailed instructions, may be obtained at <u>www.nyc.gov/vendex</u>. The bidder may also obtain Vendex forms and instructions by contacting the Agency Chief Contracting Officer or the contact person for this contract.

#### 25. <u>Complaints About the Bid Process</u>

The New York City Comptroller is charged with the audit of contracts in New York City. Any vendor who believes that there has been unfairness, favoritism or impropriety in the bid process should inform the Comptroller, Office of Contract Administration, One Centre Street, Room 835, New York, New York; telephone number (212)669-2797.

#### 26. Bid, Performance and Payment Security

(A) <u>Bid Security</u>: Each bid must be accompanied by bid security in an amount and type specified in Attachment 1. The bid security shall assure the City of New York of the adherence of the bidder to its proposal, the execution of the Contract, and the furnishing of Performance and Payment Bonds by the bidder, if required in Attachment 1. Bid security shall be returned to the bidder as follows:

- (1) Within ten (10) days after the bid opening, the Comptroller will be notified to return the deposits of all but the three (3) lowest bidders. Within five (5) days after the award, the Comptroller will be notified to return the deposits of the remaining two unsuccessful bidders.
- (2) Within five (5) days after the execution of the Contract and acceptance of the Contractor's bonds, the Comptroller will be notified to return the bid security of the successful bidder or, if performance and payment bonds are not required, only after the sum retained under Article 21 of the Contract equals the amount of the bid security.
- (3) Where all bids are rejected, the Comptroller will be notified to return the deposit of the three (3) lowest bidders at the time of rejection.

(B) <u>Performance and Payment Security</u>: Performance and Payment Security must be provided in an amount and type specified in Attachment 1.

(C) <u>Acceptable Types of Security:</u> Acceptable types of security for bids, performance, and payment shall be limited to the following:

- (1) a one-time bond in a form satisfactory to the City;
- (2) a bank certified check or money order;
- (3) obligations of the City of New York; or
- (4) other financial instruments as determined by the Office of Construction in consultation with the Comptroller.



Whenever the successful bidder deposits obligations of the City of New York as performance and payment security, the Comptroller may sell and use the proceeds thereof for any purpose for which the principal or surety on such bond would be liable under the terms of the Contract. If the money is deposited with the Comptroller, the successful bidder shall not be entitled to receive interest on such money from the City.

(D) Form of Bonds: Security provided in the form of bonds must be prepared on the form of bonds authorized by the City of New York. Forms for bid, performance, and payment bonds are included in the Invitation for Bids Documents. Such bonds must have as surety thereunder such surety company or companies as are: (1) approved by the City of New York; (2) authorized to do business in the State of New York, and (3) approved by the Department of the Treasury of the United States. Premiums for any required bid bonds must be included in the base bid.

The bidder is advised that submission of a bid bond where the surety on such bond fails to meet the criteria set forth herein, shall result in the rejection of the bid as non-responsive.

The Department of the Treasury of the United States advises that information concerning approved surety companies may be obtained as follows: (1) from the Government Printing Office at 202-512-1800; (2) through the Internet at <u>http://www.fms.treas.gov/c570/index.html</u>, and (3) through a computerized public bulletin board, which can be accessed by using your computer modem and dialing 202-874-6887.

(E) <u>Power of Attorney:</u> Attorneys in fact who sign bid, performance, or payment bonds must file with each bond a certified copy of their power of attorney to sign said bonds.

#### 27. Failure to Execute Contract

In the event of failure of the successful bidder to execute the Contract and furnish the required security within ten (10) days after notice of the award of the Contract, the deposit of the successful bidder or so much thereof as shall be applicable to the amount of the award made shall be retained by the City, and the successful bidder shall be liable for and hereby agrees to pay on demand the difference between the price bid and the price for which such Contract shall be subsequently awarded, including the cost of any required releting and less the amount of such deposit. No plea of mistake in such accepted bid shall be available to the bidder for the recovery of the deposit or as a defense to any action based upon such accepted bid. Further, should the bidder's failure to comply with this Section cause any funding agency, body or group (Federal, State, City, Public, Private, etc.) to terminate, cancel or reduce the funding on this project, the bidder in such event shall be liable also to the City for the amount of actual funding withdrawn by such agency on this project, less the amount of the forfeited deposit.

#### 28. Bidder Responsibilities and Qualifications

(A) NO TEXT

(B) The Agency may require any bidder or prospective bidder to furnish all books of account, records, vouchers, statements or other information concerning the bidder's financial status for examination as may be required by the Agency to ascertain the bidder's responsibility and capability to perform the Contract. If required, a bidder must also submit a sworn statement setting forth such information as the Agency may require concerning present and proposed plant and equipment, the personnel and qualifications of his working organizations, prior experience and performance record.

(C) <u>Oral Examination on Qualifications:</u> In addition thereto, and when directed by the Agency, the bidder, or a responsible officer, agent or employee of the bidder, must submit to an oral examination to be conducted by the Agency in relation to his proposed tentative plan and schedule of operations, and such other matters as the Agency may deem necessary in order to determine the bidder's ability and responsibility to perform the work in accordance with the Contract. Each person so examined must sign and verify a stenographic transcript of such examination noting thereon such corrections as such person may desire to make.

(D) If the bidder fails or refuses to supply any of the documents or information set forth in

Page 8 of 11

paragraph (B) hereof or fails to comply with any of the requirements thereof, the Agency may reject the bid.

#### 29. Employment Report

In accordance with Executive Order No. 50 (1980) as modified by Executive Order 108 (1986), the filing of a completed Employment Report (ER) is a requirement of doing business with the City of New York for construction contractors with contracts of \$1,000,000 or more and subcontractors with construction subcontracts of \$750,000 or more. The required forms and information are included in the Bid Booklet.

#### 30. Labor Law Requirements

(A) <u>General:</u> The successful bidder will be required to comply strictly with all Federal, State and local labor laws and regulations.

(B) <u>New York State Labor Law:</u> This Contract is subject to New York State Labor Law Section 220, which requires that construction workers on the site be paid prevailing wages and supplements. The Contractor is reminded that all wage provisions of this Contract will be enforced strictly and failure to comply will be considered when evaluating performance. Noncompliance may result in the contractor being debarred by the City from future contracts. Complaints filed with the Comptroller may result in decisions which may debar a contractor from bidding contracts with any state governmental entity and other political subdivisions.

(C) <u>Records:</u> The Contractor is expected to submit accurate payroll reports and other required documents and verify attendance and job classifications being utilized in compliance with the law, Contract provisions and agency procedures.

#### 31. Insurance

(A) Bidders are advised that the insurance requirements contained herein are regarded as material terms of the Contract. As required by Article 22 of the Contract, the contractor must effect and maintain with companies licensed and authorized to do business in the State of New York, the types of insurance set forth therein, when required by and in the amounts set forth in Schedule A of the General Conditions. Such required insurance must be provided from the date the contractor is ordered to commence work and up to the date of final acceptance of all required work.

(B) The contractor must, within ten days of receipt of the notice of award, submit the following insurance documentation: (a) original certificate of insurance for general liability in the amount required by Schedule A of the General Conditions, and (b) original certificates of insurance or other proof of coverage for workers' compensation and disability benefits, as required by Section 57 of the New York State Workers' Compensation Law and Section 220 of the Disability Benefits Law.

- 32. Not Used.
- 33. Not Used.
- 34. Excise Tax

35.

Bidders are referred to the Specifications for information on Federal Excise Tax exemptions. Licenses and Permits

The successful bidder will be required to obtain all necessary licenses and permits necessary to perform the work.

36. Not Used.

#### 37. Locally Based Enterprise Requirements (LBE)

This Contract is subject to the requirements of Administrative Code, Section 6-108.1, and the regulations promulgated thereunder. No construction contract will be awarded unless and until these requirements have been complied with in their entirety. The bidder is advised of the provisions set forth



below, as well as the provisions with respect to the Locally Based Enterprise Program contained in Article 67 of the Contract. The contractor is advised that:

(A) If any portion of the Contract is subcontracted, not less than ten percent of the total dollar amount of the contract shall be awarded to locally based enterprises ("LBEs"); except, where less than ten percent of the total dollar amount of the Contract is subcontracted, such lesser percentage shall be so awarded.

(B) No contractor shall require performance and payment bonds from LBE subcontractors.

(C) No Contract shall be awarded unless the contractor first identifies in its bid:

(1) the percentage, dollar amount and type of work to be subcontracted; and

(2) the percentage, dollar amount and type of work to be subcontracted to LBEs.

(D) Within ten calendar days after notification of low bid, the apparent low bidder shall submit an "LBE Participation Schedule" to the contracting agency. If such schedule does not identify sufficient LBE subcontractors to meet the requirements of Administrative Code Section 6-108.1, the apparent low bidder shall submit documentation of its good faith efforts to meet such requirements.

(1) The "LBE Participation Schedule" shall include:

(a) the name and address of each LBE that will be given a subcontract,

(b) the percentage, dollar amount and type of work to be subcontracted to the LBE, and

(c) the dates when the LBE subcontract work will commence and end.

- (2) The following documents shall be attached to the "LBE Participation Schedule":
  - (a) verification letters from each subcontractor listed in the "LBE Participation Schedule" stating that the LBE will enter into a formal agreement for work,
  - (b) certification documents of any proposed LBE subcontractor which is not on the LBE
    - certified list, and
  - (c) copies of the certification letter of any proposed subcontractor which is an LBE.
- (3) Documentation of good faith efforts to achieve the required LBE percentage shall include as appropriate but not limited to the following:
  - (a) attendance at prebid meetings, when scheduled by the agency, to advise bidders of contract requirements;
  - (b) advertisement where appropriate in general circulation media, trade association publications and small business media of the specific subcontracts that would be at least equal to the percentage goal for LBE utilization specified by the contractor;
  - written notification to association of small, minority and women contractors soliciting specific subcontractors;
  - (d) written notification by certified mail to LBE firms that their interest in the contract is

solicited for specific work items and their estimated values;

- (e) demonstration of efforts made to select portions of the work for performance by LBE firms in order to increase the likelihood of achieving the stated goal;
- (f) documented efforts to negotiate with LBE firms for specific subcontracts, including at a minimum:

(i) The names, address and telephone numbers of LBE firms that are contacted:

(ii) A description of the information provided to LBE firms regarding the plans and specifications for portions of the work to be performed; (iii)

Page 10 of 11

Documentation showing that no reasonable price can be obtained from LBE firms; (iv) A statement of why agreements with LBE firms were not reached;

- (g) a statement of the reason for rejecting any LBE firm which the contractor deemed to be unqualified; and
- (h) documentation of efforts made to assist the LBE firms contacted that needed assistance in obtaining required insurance.

(E) Unless otherwise waived by the Commissioner with the approval of the Office of Economic and Financial Opportunity, failure of a proposed contractor to provide the information required by paragraphs (C) and (D) above may render the bid non-responsive and the Contract may not be awarded to the bidder. If the contractor states that it will subcontract a specific portion of the work, but can demonstrate despite good faith efforts it cannot achieve its required LBE percentage for subcontracted work until after award of Contract, the Contract may be awarded, subject to a letter of compliance from the contractor stating that it will comply with Administrative Code Section 6-108.1 and subject to approval by the Commissioner. If the contractor has not met its required LBE percentage prior to award, the contractor shall demonstrate that a good faith effort has been made subsequent to award to obtain LBEs on each subcontract until its meets the required percentage.

(F) When a bidder indicates prior to award that no work will be subcontracted, no work may be subcontracted without the prior written approval of the Commissioner, which shall be granted only if the contractor in good faith seeks LBE subcontractors at least six weeks prior to the start of work.

(G) The contractor may not substitute or change any LBE which was identified prior to award of the contract without the written permission of the Commissioner. The contractor shall make a written application to the Commissioner for permission to make such substitution or change, explaining why the contractor needs to change its LBE subcontractor and how the contractor will meet its LBE subcontracting requirement. Copies of such application must be served on the originally identified LBE by certified mail return receipt requested, as well as the proposed substitute LBE. The Commissioner shall determine whether or not to grant the contractor's request for substitution.

#### 38. Bid Submission Requirements

The Bid Submission Requirements are set forth on page 2 of the Bid Booklet.

#### 39. <u>Comptroller's Certificate</u>

This Contract shall not be binding or of any force unless it is registered by the Comptroller in accordance with Section 328 of the City Charter and the Procurement Policy Board Rules. This Contract shall continue in force only after annual appropriation of funds by the City of New York and certification as hereinabove set forth.

#### 40. Procurement Policy Board Rules

This Invitation For Bids is subject to the Rules of the Procurement Policy Board of the City of New York. In the event of a conflict between said Rules and a provision of this Invitation For Bids, the Rules shall take precedence.

# **CITY OF NEW YORK**

# STANDARD CONSTRUCTION CONTRACT AS AMENDED FOR DDC JOB ORDER CONTRACTS

January, 2015





### CITY OF NEW YORK STANDARD CONSTRUCTION CONTRACT

## TABLE OF CONTENTS

### CHAPTER I THE CONTRACT AND DEFINITIONS

ARTICLE 1.	THE CONTRACT	1
ARTICLE 2.	DEFINITIONS	4

CHAPTER II

# THE WORK AND ITS PERFORMANCE

ARTICLE 3.	CHARACTER OF THE WORK	8
ARTICLE 3A.	SELF PERFORMANCE REQUIREMENTS	8
ARTICLE 3B.	DEVELOPING THE JOB ORDER	8
ARTICLE 4.	MEANS AND METHODS OF CONSTRUCTION	11
ARTICLE 4A.	CONTRACTOR'S STAFF	12
ARTICLE 5.	COMPLIANCE WITH LAWS	12
ARTICLE 6.	INSPECTION	18
ARTICLE 7.	PROTECTION OF WORK AND OF PERSONS AND	
	PROPERTY; NOTICES AND INDEMNIFICATION	<sup>-</sup> 19

#### CHAPTER III TIME PROVISIONS

ARTICLE 8.	COMMENCEMENT AND PROSECUTION OF THE WORK	20
ARTICLE 9.	PROGRESS SCHEDULES	21
ARTICLE 10.	<b>REQUESTS FOR INFORMATION OR APPROVAL</b>	21
ARTICLE 11.	NOTICE OF CONDITIONS CAUSING DELAY AND	
	DOCUMENTATION OF DAMAGES CAUSED BY DELAY	22
ARTICLE 12.	COORDINATION WITH OTHER CONTRACTORS	23
ARTICLE 13.	<b>EXTENSION OF TIME FOR PERFORMANCE OF THE CONTRACT</b>	25
ARTICLE 13A.	EXTENSION OF TIME FOR PERFORMANCE OF A JOB ORDER	27
ARTICLE 14.	COMPLETION AND FINAL ACCEPTANCE OF THE WORK	28
ARTICLE 15.	LIQUIDATED DAMAGES	29
ARTICLE 16.	OCCUPATION OR USE PRIOR TO COMPLETION	30

i

### CHAPTER IV SUBCONTRACTS AND ASSIGNMENTS

# ARTICLE 17. SUBCONTRACTS



#### ARTICLE 18. ASSIGNMENTS

#### Contract

33

# CHAPTER V

# **CONTRACTOR'S SECURITY AND GUARANTY**

ARTICLE 19.	SECURITY DEPOSIT	33
ARTICLE 20.	PAYMENT GUARANTEE	34
ARTICLE 21.	RETAINED PERCENTAGE	36
ARTICLE 22.	INSURANCE	37
ARTICLE 23.	MONEY RETAINED AGAINST CLAIMS	43
ARTICLE 24.	MAINTENANCE AND GUARANTY	44

#### **CHAPTER VI**

# CHANGES, EXTRA WORK AND DOCUMENTATION OF CLAIM

ARTICLE 25.	CHANGES TO THE CONTRACT	45
ARTICLE 25A,	CHANGES TO A JOB ORDER	45
ARTICLE 26.	NOT USED	46
ARTICLE 27.	<b>RESOLUTION OF DISPUTES</b>	46
ARTICLE 28.	RECORD KEEPING FOR EXTRA OR DISPUTED WORK OR	
	WORK ON A TIME & MATERIALS BASIS	50
ARTICLE 29.	OMITTED WORK	51
ARTICLE 30.	NOTICE AND DOCUMENTATION OF COSTS ANDDAMAGES;	
	PRODUCTION OF FINANCIAL RECORDS	51

# CHAPTER VII

## POWERS OF THE RESIDENT ENGINEER, THE ENGINEER OR ARCHITECT AND THE COMMISSIONER

ARTICLE 31.	THE RESIDENT ENGINEER	53
ARTICLE 32.	THE ENGINEER OR ARCHITECT OR PROJECT MANAGER	53
ARTICLE 33.	THE COMMISSIONER	54
ARTICLE 34.	NO ESTOPPEL	54

#### CHAPTER VIII LABOR PROVISIONS

ARTICLE 35.	EMPLOYEES	54
ARTICLE 36.	NO DISCRIMINATION	56
ARTICLE 37.	LABOR LAW REQUIREMENTS	59
ARTICLE 38.	PAYROLL REPORTS	64
ARTICLE 39.	DUST HAZARDS	65





# CHAPTER IX PARTIAL AND FINAL PAYMENTS

ARTICLE 40.	JOB ORDER	65
ARTICLE 41.	NOT USED	65
ARTICLE 42.	PARTIAL PAYMENTS ON JOB ORDERS	65
ARTICLE 42A.	NOT USED	66
ARTICLE 42B.	SUBMISSION OF JOB ORDER PAYMENT REQUEST AND	
	REQUEST FOR PAYMENT	66
ARTICLE 42C.	PARTIAL PAYMENTS FOR MATERIALS IN ADVANCE OF	
	THEIR INCORPORATION IN THE WORK	66
ARTICLE 42D.	AUDIT BY THE DEPARTMENT'S ENGINEERING AUDIT	
	<b>OFFICER (EAO) AND THE COMPTROLLER OF THE CITY</b>	
	OF NEW YORK	68
ARTICLE 42E.	CONSTRUCTION CONTRACTOR EVALUATION PROVISION	69
ARTICLE 43.	PROMPT PAYMENT	69
ARTICLE 44.	NOT USED	70
ARTICLE 45.	FINAL PAYMENT ON JOB ORDERS	70
ARTICLE 45A.	FINAL PAYMENT ON THE CONTRACT	71
ARTICLE 46.	ACCEPTANCE OF FINAL PAYMENT	71
ARTICLE 47.	APPROVAL BY PUBLIC DESIGN COMMISSION	72

Contract

# CHAPTER X

**CONTRACTOR'S DEFAULT** 

ARTICLE 48.	COMMISSIONER'S RIGHT TO DECLARE CONTRACTOR	
	IN DEFAULT	72
ARTICLE 49.	EXERCISE OF THE RIGHT TO DECLARE DEFAULT	73
ARTICLE 50.	QUITTING THE SITE	74
ARTICLE 51.	COMPLETION OF THE WORK	74
ARTICLE 52.	PARTIAL DEFAULT	74
ARTICLE 53.	PERFORMANCE OF UNCOMPLETED WORK	75
ARTICLE 54.	OTHER REMEDIES	75

## CHAPTER XI MISCELLANEOUS PROVISIONS

ARTICLE 55.	CONTRACTOR'S WARRANTIES	76
ARTICLE 56.	CLAIMS AND ACTIONS THEREON	76
ARTICLE 57.	INFRINGEMENT	76
ARTICLE 58.	NO CLAIM AGAINST OFFICERS, AGENTS OR	
	EMPLOYEES	77
ARTICLE 59.	SERVICE OF NOTICES	77
ARTICLE 60.	UNLAWFUL PROVISIONS DEEMED STRICKEN	
	FROM CONTRACT	77
ARTICLE 61.	ALL LEGAL PROVISIONS DEEMED INCLUDED	77
ARTICLE 62.	TAX EXEMPTION	78

		•
	1	
		WE'R YORK OT'T DEPARTMENT OF
-		DESIGN + CONSTRUCTION

	Contract
INVESTIGATION(S) CLAUSE	79
TERMINATION BY THE CITY	81
CHOICE OF LAW, CONSENT TO JURISDICTION	
AND VENUE	83
PARTICIPATION IN AN INTERNATIONAL BOYCOTT	83
LOCALLY BASED ENTERPRISE PROGRAM	84
ANTITRUST	85
MACBRIDE PRINCIPLES PROVISIONS	85
ELECTRONIC FILING/NYC DEVELOPMENT HUB	87
PROHIBITION OF TROPICAL HARDWOODS	87
CONFLICTS OF INTEREST	87
MERGER CLAUSE	88
STATEMENT OF WORK	88
COMPENSATION TO BE PAID TO CONTRACTOR	88
	88
	89
	TERMINATION BY THE CITY CHOICE OF LAW, CONSENT TO JURISDICTION AND VENUE PARTICIPATION IN AN INTERNATIONAL BOYCOTT LOCALLY BASED ENTERPRISE PROGRAM ANTITRUST MACBRIDE PRINCIPLES PROVISIONS ELECTRONIC FILING/NYC DEVELOPMENT HUB PROHIBITION OF TROPICAL HARDWOODS CONFLICTS OF INTEREST MERGER CLAUSE







## WITNESSETH:

The parties, in consideration of the mutual agreements contained herein, agree as follows:

## CHAPTER I THE CONTRACT AND DEFINITIONS

## **ARTICLE 1. THE CONTRACT**

1.1 Except for titles, subtitles, headings, running headlines, tables of contents and indices (all of which are printed herein merely for convenience), the following, except for such portions thereof as may be specifically excluded, shall be deemed to be part of this Contract:

1.1.1All provisions required by law to be inserted in this Contract, whether actually inserted or not;

1.1.2 The General Conditions and Special Conditions, if any;

1.1.3 The Technical Specifications;

1.1.4 The Unit Price Book;

1.1.5 The Contract;

1.1.6The Information for Bidders; Request for Proposals; Notice of Solicitation and Proposal For Bids; Bid or Proposal, and, if used, the Bid Booklet;

1.1.7All Addenda issued prior to the receipt of the bids; the Notice of Award; Performance and Payment Bonds, if required; the Notice to Proceed or the Order to Work; and **Job Orders** issued pursuant to the **Contract**.

1.2 Should any conflict occur in or between the **Detailed Scope of Work** and Specifications, the Contractor shall be deemed to have estimated the most expensive way of doing the Work, unless the Contractor shall have asked for and obtained a decision in writing from the Commissioner of the Agency that is entering into this Contract, before the submission of its bid, as to what shall govern.

1

1.3 Overview of the Contract

1.3.1 Work to be Performed

- a. The Contractor shall perform the Work described in the **Detailed Scope of Work** referenced in each **Job Order**. The Contractor will be required to perform Work at any facility at any location within the City.
- b. The price of each Job Order shall be:
  - (1) The sum of the following calculation for each prepriced task: the unit price multiplied by the quantity multiplied by the appropriate adjustment factor; plus



- (2) The sum of the following calculation for each non-prepriced task: The lowest of three
   (3) independent subcontractors' price quotes multiplied by the non-prepriced adjustment factor.
- (3) Any additional insurance required in the Detailed Scope of Work. Compensation for such insurance will be paid based on actual reasonable costs with no provision for overhead or profit.
  - c. The Contractor shall make the necessary arrangements for and obtain all filings and permits required for the Work, including the preparation of all drawings, sketches, calculations and other documents and information that may be required therefor. If the Contractor is required to pay an application fee for filing a Project, a fee to obtain a building permit, or any other permit fee to the City of New York or some other governmental or regulatory agency, then the amount of such fee(s) paid by the Contractor for which a receipt is obtained shall be treated as a Non-Prepriced Task to be paid without mark-up.
- d. The Contractor shall obtain all final approvals for the Work, in the form of such certificates that are required by all governmental agencies having jurisdiction over the Work.
- e. The Contractor shall provide incidental engineering and architectural services required in connection with a particular **Job Order**, including drawings required for filing.
- 1.3.2 Guaranteed Minimum and Not to Exceed Values
  - a. The **Guaranteed Minimum**. Guaranteed Minimum: In the event the Contractor is not issued any Job Orders hereunder and the Contractor has, throughout the term of the Contract, submitted reasonable Proposals for specific Projects, the City agrees to pay, and the Contractor agrees to accept, a minimum fee of \$ 5,000 for the General Contractor and \$2,500 for Plumbing, Electrical and HVAC contractors. The Contractor further agrees that under such circumstances, it has no action for damages or for loss of profits against the City.

Trade	Term	Not to Exceed Contract Value
General	3 Years	\$8,000,000
Electric	3 Years	\$5,000,000
HVAC	3 Years	\$5,000,000
Plumbing	3 Years	\$3,000,000

b. The Not to Exceed Values are:

The Contractor will not be issued **Job Orders** exceeding the Not to Exceed Value during any Contract period. The Contractor is not guaranteed to receive this volume of Work. The Department has no obligation to issue **Job Orders** in excess of the Guaranteed Minimum.



#### 1.3.3 Contract Term

- a. The term of the Contract shall be as indicated in the chart above or when an amount equal to the Not to Exceed Value has been ordered, whichever occurs first.
- b. In the event that Work on a Job Order or Job Orders is not complete when the Term ends, the Contractor shall continue Work on the Job Order and all terms of this Contract shall apply.
- c. At the Commissioner's sole option, the term of this contract may be renewed for a period of two years.

#### 1.3.4 Adjustment Factors

- a. There are three adjustment factors for this Contract. When preparing a proposal, the Contractor shall select the appropriate Adjustment Factor for each task.
- b. The adjustment factors will be applied as follows:
  - (i) Normal Working Hours: Monday to Friday 7:00 a.m. to 4:00 p.m., except holidays;
  - (ii) Other Than Normal Working Hours: Monday to Friday 4:00 p.m. to 7:00 a.m. and all day Saturdays, Sundays and holidays;
  - (iii) Non-Prepriced adjustment factor.
- c. The Normal Working Hours and Other Than Normal Working Hours adjustment factors will be adjusted on the first anniversary of the bid date, and each 12 (twelve) months thereafter, in accordance with the Construction Cost Index as published in Engineering News-Record (ENR), pursuant to subsections (i)-(vi) set forth below. These subsections provide a means to update the base year adjustment factors to the subsequent year adjustment factors by using actual escalation/de-escalation as measured by the Construction Cost Index (CCI) published in the ENR.
  - (i) The originally bid adjustment factors are valid for the first 12 (twelve) months following the bid date.
  - (ii) CCI indices are published monthly. The "base year" for the purposes of this clause is the 12 (twelve) months prior to the bid date. The "base year index" is determined by adding the monthly CCI indices for each of the 12 (twelve) months of the "base year" and dividing by 12 (twelve). The result is the average CCI for the "base year."



- (iii) The "first adjustment period" for the purposes of the clause is the 12 (twelve) months following the bid date. The "first period extension index" is determined by adding the monthly CCI indices for the first year and dividing by 12 (twelve). The result is the average CCI for the "first adjustment period."
- (iv) The update percentage for the "first adjustment period" is determined by dividing the "first period extension index" by the "base year index." The new adjustment factors are determined by multiplying the update percentage by the original adjustment factors.
- (v) The update for subsequent periods is determined by the same procedure as described above. The "base year" shall be used for all subsequent years.
- (vi) All the above computations shall be carried to five (5) decimal places and then rounded to the fourth (4<sup>th</sup>) decimal place. Rounding of numbers shall be accomplished by increasing the fourth decimal place if the fifth decimal is equal to five or greater. If the fifth decimal place is equal to four or less, the fourth decimal shall remain unchanged.
- d. The Non-Prepriced adjustment factor shall not be adjusted for the duration of the Contract.
- e. The current adjustment factors shall be used for all Proposals being submitted.
- 1.3.5 Work for Program Units
  - a. The **Contractor** will perform work as the primary contractor for its trade in the assigned Borough for the Program Unit(s) as set forth in Paragraph 1 of the Information for Bidders. In the event that one of the other contractors, in the Contractor's trade, is unable to perform its assigned work, the Department may require the **Contractor** to perform such work, as a secondary contractor using the **Contractor's Own Adjustment Factor**. The Secondary's Department will select secondary contractors, from the available contractors in that trade, in the order of lowest to highest **Adjustment Factors**. JOC contractor shall not have the right to refuse projects. The decision to bypass JOC Contractor shall be made in writing. The determination as to whether a contractor is unable to perform will be based on Interim Evaluations that will be performed on every project measuring the Contractor's performance. The evaluation criteria will be:
  - b.
- (i) Job Order Development
  - 1. Timeliness of Proposal
  - 2. Quality of Proposal
- (ii) Ability to meet Construction Schedules
- (iii) Consistent high Quality of Work
- (iv) Cooperativeness
- (v) Record Keeping
- c. If the Corrections Program Unit is not one of the Contractor's primary Program Units, and the contractor is required to perform work for the Corrections Program Unit, its current Adjustment Factors will be increased by 10% for such job including Courts, Corrections & Juvenile Detention projects.



d. If the Contractor receives an unsatisfactory evaluation on any Interim Evaluation. The contractor must submit a Corrective Action Plan (CAP) for consideration and approval. The Department may elect not to assign that Contractor any additional projects for a period of three months until an approved CAP is in place

## ARTICLE 2. DEFINITIONS

- 2.1 The following words and expressions, or pronouns used in their stead, shall, wherever they appear in this Contract, be construed as follows, unless a different meaning is clear from the context:
  - 2.1.1 "Addendum" or "Addenda" shall mean the additional Contract provisions and/or technical clarifications issued in writing by the Commissioner prior to the receipt of bids.
  - 2.1.2 "Agency" shall mean a city, county, borough or other office, position, department, division, bureau, board or commission, or a corporation, institution or agency of government, the expenses of which are paid in whole or in part from the City treasury.
  - 2.1.3 "Agency Chief Contracting Officer" (ACCO) shall mean a person delegated authority by the Commissioner to organize and supervise the procurement activity of subordinate Agency staff in conjunction with the CCPO, or his/her duly authorized representative.
  - 2.1.4 "Allowance" shall mean a sum of money which the Agency may include in the total amount of the Contract for such specific contingencies as the Agency believes may be necessary to complete the Work, *e.g.*, lead or asbestos remediation, and for which the Contractor will be paid on the basis of stipulated unit prices ora formula set forth in the Contract or negotiated between the parties provided, however, that if the Contractor is not directed to use the Allowance, the Contractor shall have no right to such money and it shall be deducted from the total amount of the Contract.
  - 2.1.5 "City" shall mean the City of New York.
  - 2.1.6 "City Chief Procurement Officer" (CCPO) shall mean a person delegated authority by the Mayor to coordinate and oversee the procurement activity of Mayoral agency staff, including the ACCO and any offices which have oversight responsibility for the procurement of construction, or his/her duly authorized representative.
  - 2.1.7 "**Commissioner**" shall mean the head of the Agency that has entered into this Contract, or his/her duly authorized representative.
  - 2.1.8 "Comptroller" shall mean the Comptroller of the City of New York.
  - 2.1.9 "Contract" or "Contract Documents" shall mean each of the various parts of the contract referred to in Article 1 hereof, both as a whole and severally.
  - 2.1.10 "Contract Drawings" shall mean only those drawings specifically entitled as such and listed in the Specifications or in any Addendum, or referenced in the Detailed Scope of Work, or any drawings furnished by the Commissioner, pertaining or supplemental thereto.



- 2.1.11 "Contract Work" shall mean everything required to be furnished and done by the Contractor by any one or more of the parts of the Contract referred to in Article 1 and any Job Order, except Extra Work as hereinafter defined.
- 2.1.12 "**Contractor**" shall mean the entity which executed this Contract, whether a corporation, firm, partnership, joint venture, individual, or any combination thereof, and its, their, his/her successors, personal representatives, executors, administrators, and assigns, and any person, firm, partnership, joint venture, individual, or corporation which shall at any time be substituted in the place of the Contractor under this Contract.
- 2.1.13 "Days" shall mean calendar days, except where otherwise specified.
- 2.1.14 "Detailed Scope of Work "is the document that sets forth the obligations of the Contractor with respect to a Job Order.
- 2.1.15"Engineer" or "Architect" or "Project Manager" shall mean the person so designated in writing by the Commissioner to act as such in relation to a Job Order, including a private Architect or Engineer or Project Manager, as the case may be. Subject to written approval by the Commissioner, the Engineer, Architect or Project Manager may designate an authorized representative.
- 2.1.16"Engineering Audit Officer"(EAO) shall mean the person so designated by the Commissioner to perform responsible auditing functions hereunder.
- 2.1.17 "Extra Work" shall mean Work other than that required by the Job Order at the time it is issued which is authorized by the Commissioner pursuant to Chapter VI of this Contract.
- 2.1.18"Federal-Aid Contract" shall mean a contract in which the United States (federal) Government provides financial funding as so designated in the Information for Bidders.
- 2.1.19"**Final Acceptance**" shall mean final written acceptance of all the Work by the Commissioner, a copy of which shall be sent to the Contractor.
- 2.1.20 "Final Approved Punch List" shall mean a list, approved pursuant to Article 14, specifying those items of the Detailed Scope of Work to be completed by the Contractor and dates for the completion of each item of the Detailed Scope of Work.
- 2.1.21"Job Order" is the document that sets forth the Detailed Scope of Work, the Job Order Completion Time, and the price to be paid therefor.
- 2.1.22"Job Order Completion Time" shall mean the period of time allotted for the Contractor to complete the Detailed Scope of Work.
- 2.1.23"Job Order Payment Request" shall mean the documents required to be submitted to the Project Engineer when requesting payment approval of an individual Job Order.
- 2.1.24"Law" or "Laws" shall mean the Constitution of the State of New York, the New York City Charter, the New York City Administrative Code, a statute of the United States or of



the State of New York, a local law of the City of New York, any ordinance, rule or regulation having the force of law, or common law.

- 2.1.25" Materialman" shall mean any corporation, firm, partnership, joint venture, or individual, other than employees of the Contractor, who or which contracts with the Contractor or any Subcontractor, to fabricate or deliver, or who actually fabricates or delivers, plant, materials or equipment to be incorporated in the Work.
- 2.1.26"Means and Methods of Construction" shall mean the labor, materials, temporary structures, tools, plant, and construction equipment, and the manner and time of their use, necessary to accomplish the result intended by this Contract.
- 2.1.27 "Notice to Proceed" or "Order to Work" shall mean the written notice issued by the Commissioner specifying the time for commencement of the Work and the Engineer, Architect or Project Manager.
- 2.1.28"Other Contractor(s)" shall mean any contractor (other than the entity which executed this Contract or its Subcontractors) who or which has a contract with the City for work on or adjacent to the building or Site of the Work.
- 2.1.29"Payroll Taxes" shall mean State Unemployment Insurance (SUI), Federal Unemployment Insurance (FUI), and payments pursuant to the Federal Insurance Contributions Act (FICA).
- 2.1.30"**Project**" shall mean the public improvement to which a Job Order or a series of Job Orders relates.
- 2.1.31"Procurement Policy Board" (PPB) shall mean the Agency of the City of New York whose function is to establish comprehensive and consistent procurement policies and rules which shall have broad application throughout the City.
- 2.1.32"**Required Quantity**" in a unit price Contract shall mean the actual quantity of any item of Work or materials which is required to be performed or furnished in order to comply with the Contract.
- 2.1.33"**Resident Engineer**" shall mean the representative of the Commissioner duly designated by the Commissioner to be his/her representative at the site of the Work.
- 2.1.34"Site" shall mean the area upon or in which the Contractor's operations are carried on, and such other areas adjacent thereto as may be designated as such by the Engineer.
- 2.1.35"Small Tools" shall mean items that are ordinarily required for a worker's job function, including but not limited to, equipment that ordinarily has no licensing, insurance or substantive storage costs associated with it; such as circular and chain saws, impact drills, threaders, benders, wrenches, socket tools, etc.
- 2.1.36"Specifications" shall mean all of the directions, requirements, and standards of performance applying to the Work as hereinafter detailed and designated under the Specifications.



- 2.1.37"**Subcontractor**" shall mean any person, firm or corporation, other than employees of the Contractor, who or which contracts with the Contractor or with its subcontractors to furnish, or actually furnishes labor, or labor and materials, or labor and equipment, or superintendence, supervision and/or management at the Site. Wherever the word Subcontractor appears, it shall also mean sub-Subcontractor.
- 2.1.38"Supplemental Job Order" shall mean a Job Order issued to add or delete work from an existing, related Job Order.
- 2.1.39"Work" shall mean all services required to complete the Detailed Scope of Work in accordance with a Job Order and the Contract Documents, including without limitation, labor, material, superintendence, management, administration, equipment, and incidentals, and obtaining any and all permits, certifications and licenses as may be necessary and required to complete the Work, and shall include both Contract Work and Extra Work.
- 2.1.40 "Project Labor Agreement" shall mean a collective bargaining agreement with one or more labor organizations that establishes the terms and conditions of employment, i.e. wage rates and benefits, for a specific construction projects.

### CHAPTER II THE WORK AND ITS PERFORMANCE

## **ARTICLE 3. CHARACTER OF THE WORK**

3.1 Unless otherwise expressly provided in the **Detailed Scope of Work**, **Specifications**, and **Addenda**, the **Work** shall be performed in accordance with the best modern practice, utilizing, unless otherwise specified in writing, new and unused materials of standard first grade quality and workmanship and design of the highest quality, to the satisfaction of the **Commissioner**.

## **ARTICLE 3A.SELF PERFORMANCE REQUIREMENTS**

3A.1 The General Construction Contractor shall perform at least 15%, and the Electrical, HVAC, Plumbing Contractors shall perform at least 50% of the Work with its own forces and not by Subcontractors. Materials purchased but not installed with the Contractor's own forces and the supervision of Subcontractors shall not count towards this self-performance goal.

### **ARTICLE 3B.DEVELOPING THE JOB ORDER**

3B.1 Initiation of a Job Order

8



3B.1.1 As the need exists for performance by the **Contractor** under the terms of this **Contract**, the **Department** will notify the **Contractor** of a Project by issuing a Notice of Joint Scope Meeting.

## 3B.1.2 The Contractor shall attend the Joint Scope Meeting and discuss, at a minimum:

- a. the general scope of the Work
- b. methods and alternatives for accomplishing the Work
- c. access to the site and protocol for admission
- d. hours of operation
- e. staging area
- f. requirements for catalog cuts, technical data, samples and shop drawings
- g. requirements for design services including sketches, drawings, and specifications
- h. construction duration
- i. liquidated damages
- j. specific quality requirements for equipment and material
- k. the presence of hazardous materials
- 1. safety issues (e.g., submission and adherence to Safety Plan, Confined Space Entry Permits and Procedures, gas monitoring, etc.)
- m. Prevailing wage requirements (e.g., daily sign-in sheets, payroll reports, etc.)
- n. LBE or M/WBE requirements
- o. date on which Proposal is due
- 3B.1.3 Upon completion of the joint scoping process, the **Department** or the **Contractor**(if directed by the **Engineer**) will prepare a draft **Detailed Scope of Work** referencing any sketches, drawings, photographs, and specifications required to document accurately the work to be accomplished. The **Contractor**shall review the **Detailed Scope of Work** and request any required changes or modifications thereto. When an acceptable **Detailed Scope of Work** has been prepared, the **Department** will issue a Request for Proposal (RFP) which will require the **Contractor** to prepare a Proposal for the Work under consideration. The **Detailed Scope of Work**, unless modified by both the **Contractor** and the **Department** will be the basis on which the **Contractor**will develop its Proposal and the **Department** will evaluate the Proposal. The **Contractor**does not have the right to refuse to perform any unit price task item or any work in connection with a particular project.
- 3B.2 Preparation of the Proposal

The Contractor will prepare Proposals in accordance with the following:

- 3B.2.1 Prepriced Tasks: For Prepriced Tasks, the **Contractor**shall identify the task and guantities required from the Unit Price Book.
- 3B.2.2 Non-Prepriced Tasks: Non-Prepriced Tasks shall be separately identified and submitted in the Proposal. Information submitted in support of Non-Prepriced Tasks shall include, but not be limited to, the following:
  - a. Catalog cuts, specifications, technical data, drawings, or other information, as required, to evaluate the proposed item.



- b. If the **Contractor** will perform the **Work** with its own forces, it shall submit three independent quotes for all material and equipment to be installed.
- c. If the Work is to be subcontracted, the Contractor must submit three independent bids from Subcontractors. If three quotes or bids cannot be obtained, the Contractor will provide the reason in writing for the Department's approval. The Contractor shall not submit a quote or bid from any supplier or Subcontractor that the Contractor is not prepared to use. The Department may require additional quotes and bids if the suppliers or Subcontractors are not acceptable or if the prices are not reasonable.
- d. The final price submitted for Non-Prepriced Tasks shall be according to the following formula:

A = Labor from the Unit Price Book

*B*= *Direct Material Costs (supported by three quotes)* 

C = Direct Equipment Costs from the Unit Price Book or for Equipment not in the Unit Price Book supported by equipment amortization data

D = Subcontractor Costs (supported by three quotes)

Total Cost of Non Pre-Priced (NPP) Task=

(A \* Contractor's Normal or Other Than Normal Adjustment Factor)

+ (B \* Contractor's NPP Adjustment Factor)

+ (C \* Contractor's NPP Adjustment Factor)

+ (D \* Contractor's NPP Adjustment Factor)

- e. After a Non-Prepriced Task is developed by any JOC Contractor and incorporated into a Price Proposal approved by the Department, such Task shall, at the sole discretion of the Department, be added to the Construction Task Catalog then in use by all the Contractors in the pool of the trades, and shall be, from then on, deemed to be a Prepriced Task.
- f. The **Department**'s determination as to whether an item is a Prepriced Task or a Non-Prepriced Task shall be final, binding and conclusive as to the **Contractor**.
- g. The **Contractor** shall make the necessary arrangements for and obtain all filings and permits required for the Work, including the preparation of all drawings, sketches, calculations and other documents and information that may be required therefor. If the **Contractor** is required to pay an application fee for filing a Project, a fee to obtain a building permit, or any other permit fee to the City of New York or some other governmental or regulatory agency, then the amount of such fee paid by the **Contractor** for which a receipt is obtained shall be treated as a Non-Prepriced Task to be paid without mark-up. However, the cost of expediting services or equipment use fees is not reimbursable.
- h. The **Contractor** shall obtain all final approvals for the **Work**, in the form of such certificates that are required by all governmental agencies having jurisdiction over the **Work**.
- i. The **Contractor** shall provide incidental engineering and architectural services required in connection with a particular **Job Order** including drawings and information required for filing at no further markup.



3B.2.3 The Contractor's Proposal shall include, at a minimum:

- a. Price Proposal;
- b. Required architectural or engineering drawings or sketches;
- c. Required Catalog cuts, technical data or samples;
- d. List of anticipated Subcontractors and Materialmen indicating M/WBE and LBE status and anticipated price;
- e. Required Construction schedule;
- f. Sample warranties or guarantees for materials, equipment or systems proposed;
- g. Any additional insurance as required in the Detailed Scope of Work.
- 3B.2.4 The **Contractor**'s Proposal shall be submitted by the date indicated on the RFP. All incomplete Proposals shall be rejected. The time allowed for preparation of the Contractor's Proposal will be between two (2) and fourteen (14) days. On complex Job **Orders**, the time allowed may be greater than fourteen (14) days, as approved by the Engineer. In emergency situations and minor maintenance and repair Job **Orders** requiring immediate completion, the Proposal may be required quickly and the due date will be so indicated on the RFP or, as described below, the **Contractor** may be directed to begin work immediately with the paperwork to follow.
- 3B.3 Review of the Proposal and Issuance of a Job Order
  - 3B.3.1 The **Department** will evaluate the entire Proposal and proposed tasks and compare these with the **Department's** cost estimate of the **Detailed Scope of Work** to determine the reasonableness of approach, including the nature and quantity of tasks proposed.
  - 3B.3.2 The **Department** reserves the right to reject a Proposal or cancel a project for any reason. The **Department** also reserves the right not to issue a **Job Order** if that is determined to be in the best interests of the **Department**. The **Department** may pursue the performance of such **Work** by other means. The **Contractor** shall not recover any costs arising out of or related to the development of the **Job Order**, including, but not limited to, the costs to attend the Joint Scope Meeting, review the **Detailed Scope of Work**, prepare a Proposal (including incidental architectural and engineering services), **Subcontractor** costs, and the costs to review the Proposal with the **Department**.
  - 3B.3.3By submitting a Proposal to the **Department**, the **Contractor** agrees to accomplish the **Detailed Scope of Work** in accordance with RFP at the price submitted. It is the **Contractor's** responsibility to include the necessary tasks and quantities in the Price Proposal prior to delivering it to the **Department**.
  - 3B.3.4 Each Job Order provided to the Contractor shall reference the Detailed Scope of Work and set forth the price to be paid and the Job Order Completion Time. All clauses of this Contract shall be applicable to each Job Order. The Job Order, signed by the Department and delivered to the Contractor, constitutes the Department's acceptance of the Contractor's Proposal. A signed copy will be provided to the Contractor.
  - 3B.3.5 In the event that emergency response is necessary the **Contractor** shall be required to follow alternative procedures as established by the **Department**. The **Contractor** shall begin work as directed notwithstanding the absence of a fully developed RFP, **Detailed Scope of Work**, or **Job Order**. The **Contractor** shall be compensated in accordance



with the Unit Price Book and Non-Prepriced Tasks as if the Work had been ordered under the standard procedures. An emergency shall be as it is defined in Section 3-06 of the PPB rules.

3B.3.6 It is the **Contractor**'s responsibility to include in the Proposal those unit price tasks and quantities necessary to accomplish the **Detailed Scope of Work**. The risk associated with missing tasks and quantities from the Proposal shall be borne by the **Contractor**.

3B.4 Additions, deletions and changes to the **Detailed Scope of Work** shall be handled as a **Supplemental Job Order** and developed in accordance with this Article.

## **ARTICLE 4. MEANS AND METHODS OF CONSTRUCTION**

4.1 Unless otherwise expressly provided in the Detailed Scope of Work, Specifications, and Addenda, the Means and Methods of Construction shall be such as the Contractor may choose; subject, however, to the Engineer's right to reject the Means and Methods of Construction proposed by the Contractor which in the opinion of the Engineer:

4.1.1 Will constitute or create a hazard to the Work, or to persons or property; or

4.1.2 Will not produce finished Work in accordance with the terms of the Contract; or

4.1.3 Will be detrimental to the overall progress of the **Project**.

4.2 The Engineer's approval of the Contractor's Means and Methods of Construction, or his/her failure to exercise his/her right to reject such means or methods, shall not relieve the Contractor of its obligation to complete the Work as provided in this Contract; nor shall the exercise of such right to reject create a cause of action for damages.

## **ARTICLE 4A.CONTRACTOR'S STAFF**

4A.1 At a minimum, the **Contractor** shall have at all times a Project Manager, Estimator, Office Manager and Superintendent assigned to this **Contract**. Additional staff may be assigned depending on the volume of **Work**. The **Contractor** shall be responsible for managing, supervising and directing his/her **Subcontractors**. For each **Job Order** issued, the **Contractor** shall identify the Superintendent responsible for that work. The Superintendent shall be reachable 24 hours a day, seven days a week. If the named Superintendent is not available because of illness or vacation or the like, the **Contractor** shall notify the **Department** of a substitute Superintendent. At all times, the **Contractor** shall provide at least one Superintendent for every six **Job Orders**. The **Contractor** shall implement a quality control program. Whenever, in the sole discretion of the **Department**, the **Contractor** is not providing a sufficient level of supervision or control, the **Department** may direct the **Contractor** to increase the level of supervision and management effort for any or all projects, including, but not limited to, the right to direct the **Contractor** to: assign a full time, dedicated Superintendent for any project; submit daily management, inspection, activity, and planning reports; substitute **Subcontractors**; submit daily photographs of the **Work** in place and the **Work** areas prepared for the next **Day's Work**; and develop a site specific quality control program; all at no additional cost to the **Department**.

## **ARTICLE 5. COMPLIANCE WITH LAWS**

5.1 The **Contractor** shall comply with all **Laws** applicable to this **Contract** and to the **Work** to be done hereunder.

5.2 Procurement Policy Board Rules: This **Contract** is subject to the Rules of the **PPB** ("**PPB** Rules") in effect at the time of the bid opening for this **Contract**. In the event of a conflict between the **PPB** Rules and a provision of this **Contract**, the **PPB** Rules shall take precedence.

5.3 Noise Control Code provisions.

W YORK CITY DEP ESIGN + CONS

- 5.3.1 In accordance with the provisions of Section 24-216(b) of the Administrative Code of the City ("Administrative Code"), Noise Abatement Contract Compliance, devices and activities which will be operated, conducted, constructed or manufactured pursuant to this Contract and which are subject to the provisions of the City Noise Control Code shall be operated, conducted, constructed, or manufactured without causing a violation of the Administrative Code. Such devices and activities shall incorporate advances in the art of noise control development for the kind and level of noise emitted or produced by such devices and activities, in accordance with regulations issued by the Commissioner of the City Department of Design and Construction.
- 5.3.2 The Contractor agrees to comply with Section 24-219 of the Administrative Code and implementing rules codified at 15 Rules of the City of New York ("RCNY") Section 28-100 et seq. In accordance with such provisions, the Contractor, if the Contractor is the responsible party under such regulations, shall prepare and post a Construction Noise Mitigation Plan at each Site, in which the Contractor shall certify that all construction tools and equipment have been maintained so that they operate at normal manufacturers operating specifications. If the Contractor cannot make this certification, it must have in place an Alternative Noise Mitigation Plan approved by the City Department of Design and Construction. In addition, the Contractor's certified Construction Noise Mitigation Plan is subject inspection by the City Department of Design and Construction in accordance with Section 28-101 of Title 15 of RCNY. No Contract Work may take place at a Site unless there is a Construction Noise Mitigation Plan or approved Alternative Noise Mitigation Plan in place. In addition, the Contractor shall create and implement a noise mitigation training program. Failure to comply with these requirements may result in fines and other penalties pursuant to the applicable provisions of the Administrative Code and RCNY.

5.4 Ultra Low Sulfur Diesel Fuel: In accordance with the provisions of Section 24-163.3 of the Administrative Code, the **Contractor** specifically agrees as follows:

- 5.4.1 Definitions. For purposes of this Article 5.4, the following definitions apply:
  - 5.4.1(a) "Contractor" means any person or entity that enters into a Public Works Contract with a **City Agency**, or any person or entity that enters into an agreement with such person or entity, to perform work or provide labor or services related to such Public Works Contract.
  - 5.4.1(b) "Motor Vehicle" means any self-propelled vehicle designed for transporting persons or property on a street or highway.



- 5.4.1(c) "Nonroad Engine" means an internal combustion engine (including the fuel system) that is not used in a Motor Vehicle or a vehicle used solely for competition, or that is not subject to standards promulgated under Section 7411 or Section 7521 of Title 42 of the United States Code, except that this term shall apply to internal combustion engines used to power generators, compressors or similar equipment used in any construction program or project.
- 5.4.1(d) "Nonroad Vehicle" means a vehicle that is powered by a Nonroad Engine, fifty (50) horsepower and greater, and that is not a Motor Vehicle or a vehicle used solely for competition, which shall include, but not be limited to, excavators, backhoes, cranes, compressors, generators, bulldozers, and similar equipment, except that this term shall not apply to horticultural maintenance vehicles used for landscaping purposes that are powered by a Nonroad Engine of sixty-five (65) horsepower or less and that are not used in any construction program or project.
- 5.4.1(e) "Public Works Contract" means a contract with a **City Agency** for a construction program or project involving the construction, demolition, restoration, rehabilitation, repair, renovation, or abatement of any building, structure, tunnel, excavation, roadway, park or bridge; a contract with a **City Agency** for the preparation for any construction program or project involving the construction, demolition, restoration, rehabilitation, repair, renovation, repair, renovation, or abatement of any building, structure, tunnel, excavation, roadway, park or bridge; or a contract with a **City Agency** for any final work involved in the completion of any construction program or project involving the construction, repair, renovation, rehabilitation, repair, renovation, or abatement of any building, structure, tunnel, excavation, demolition, restoration, rehabilitation, repair, renovation, or abatement of any building, structure, tunnel, excavation, repair, renovation, or abatement of any building, structure, tunnel, excavation, repair, renovation, or abatement of any building, structure, tunnel, excavation, repair, renovation, or abatement of any building, structure, tunnel, excavation, repair, renovation, or abatement of any building, structure, tunnel, excavation, repair, renovation, or abatement of any building, structure, tunnel, excavation, repair, renovation, or abatement of any building, structure, tunnel, excavation, roadway, park or bridge.
- 5.4.1(f) "Ultra Low Sulfur Diesel Fuel" means diesel fuel that has a sulfur content of no more than fifteen parts per million (15 ppm).
- 5.4.2 Ultra Low Sulfur Diesel Fuel
  - 5.4.2(a) All **Contractors** shall use Ultra Low Sulfur Diesel Fuel in diesel-powered Nonroad Vehicles in the performance of this **Contract**.
  - 5.4.2(b) Notwithstanding the requirements of Article 5.4.2(a), **Contractors** may use diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm) to fulfill the requirements of this Article 5.4.2, where the Commissioner of the **City** Department of Design and Construction ("DDC Commissioner") has issued a determination that a sufficient quantity of Ultra Low Sulfur Diesel Fuel is not available to meet the needs of **Agencies** and **Contractors**. Any such determination shall expire after six (6) months unless renewed.
  - 5.4.2(c) Contractors shall not be required to comply with this Article 5.4.2 where the City Agency letting this Contract makes a written finding, which is approved, in writing, by the DDC Commissioner, that a sufficient quantity of Ultra Low Sulfur Diesel Fuel, or diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm) is not available to meet the requirements of Section 24-163.3 of the Administrative Code, provided that such Contractor in its fulfillment of the requirements of this Contract, to the extent practicable, shall use whatever quantity

of Ultra Low Sulfur Diesel Fuel or diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm) is available. Any finding made pursuant to this Article 5.4.2(c) shall expire after sixty (60) **Days**, at which time the requirements of this Article 5.4.2 shall be in full force and effect unless the **City Agency** renews the finding in writing and such renewal is approved by the DDC Commissioner.

- 5.4.2(d) **Contractors** may check on determinations and approvals issued by the DDC Commissioner pursuant to Section 24-163.3 of the Administrative Code, if any, at <u>www.ddd.nyc.gov</u> or by contacting the **City Agency** letting this **Contract**.
- 5.4.2(e) The requirements of this Article 5.4.2 do not apply where they are precluded by federal or State funding requirements or where the **Contract** is an emergency procurement.
- 5.4.3 Best Available Technology
  - 5.4.3(a) All **Contractors** shall utilize the best available technology for reducing the emission of pollutants for diesel-powered Nonroad Vehicles in the performance of this **Contract**. For determinations of best available technology for each type of diesel-powered Nonroad Vehicle, **Contractors** shall comply with the regulations of the **City** Department of Design and Construction, as and when adopted, Chapter 14 of Title 15 of the Rules of the City of New York (RCNY). The **Contractor** shall fully document all steps in the best available technology selection process and shall furnish such documentation to the **City Agency** or the DDC Commissioner upon request. The **Contractor** shall retain all documentation generated in the best available technology selected best available technology is in use.
  - 5.4.3(b) No Contractor shall be required to replace best available technology for reducing the emission of pollutants or other authorized technology utilized for a diesel-powered Nonroad Vehicle in accordance with the provisions of this Article 5.4.3 within three (3) years of having first utilized such technology for such vehicle.
  - 5.4.3(c) This Article 5.4.3 shall not apply to any vehicle used to satisfy the requirements of a specific Public Works Contract for fewer than twenty (20) Days.
  - 5.4.3(d) The **Contractor** shall not be required to comply with this Article 5.4.3 with respect to a diesel-powered Nonroad Vehicle under the following circumstances:
    - 5.4.3(d)(i) Where the **City Agency** makes a written finding, which is approved, in writing, by the DDC Commissioner, that the best available technology for reducing the emission of pollutants as required by this Article 5.4.3 is unavailable for such vehicle, the **Contractor** shall use whatever technology for reducing the emission of pollutants, if any, is available and appropriate for such vehicle.
    - 5.4.3(d)(ii)Where the DDC Commissioner has issued a written waiver based upon the **Contractor** having demonstrated to the DDC Commissioner that the use of the best available technology for reducing the emission of pollutants might endanger the operator of such vehicle or those working near



such vehicle, due to engine malfunction, the **Contractor** shall use whatever technology for reducing the emission of pollutants, if any, is available and appropriate for such vehicle, which would not endanger the operator of such vehicle or those working near such vehicle.

- 5.4.3(d)(iii) In determining which technology to use for the purposes of Articles 5.4.3(d)(i) and 5.4.3(d)(ii) above, the **Contractor** shall primarily consider the reduction in emissions of particulate matter and secondarily consider the reduction in emissions of nitrogen oxides associated with the use of such technology, which shall in no event result in an increase in the emissions of either such pollutant.
- 5.4.3(d)(iv) The **Contractor** shall submit requests for a finding or a waiver pursuant to this Article 5.4.3(d) in writing to the DDC Commissioner, with a copy to the **ACCO** of the **City Agency** letting this **Contract**. Any finding or waiver made or issued pursuant to Articles 5.4.3(d)(i) and 5.4.3(d)(ii) above shall expire after one hundred eighty (180) **Days**, at which time the requirements of Article 5.4.3(a) shall be in full force and effect unless the **City Agency** renews the finding, in writing, and the DDC Commissioner approves such finding, in writing, or the DDC Commissioner renews the waiver, in writing.

5.4.3(e) The requirements of this Article 5.4.3 do not apply where they are precluded by federal or State funding requirements or where Contract is an emergency procurement.

- 5.4.4 Section 24-163 of the Administrative Code. The **Contractor** shall comply with Section 24-163 of the Administrative Code related to the idling of the engines of motor vehicles while parking.
- 5.4.5 Compliance
  - 5.4.5(a) The **Contractor's** compliance with Article 5.4 may be independently monitored. If it is determined that the **Contractor** has failed to comply with any provision of Article 5.4, any costs associated with any independent monitoring incurred by the **City** shall be reimbursed by the **Contractor**.
  - 5.4.5(b)Any **Contractor** who violates any provision of Article 5.4, except as provided in Article 5.4.5(c) below, shall be liable for a civil penalty between the amounts of one thousand (\$1,000) and ten thousand (\$10,000) dollars, in addition to twice the amount of money saved by such **Contractor** for failure to comply with Article 5.4.
  - 5.4.5(c) No Contractor shall make a false claim with respect to the provisions of Article 5.4 to a City Agency. Where a Contractor has been found to have done so, such Contractor shall be liable for a civil penalty of twenty thousand (\$20,000) dollars, in addition to twice the amount of money saved by such Contractor in association with having made such false claim.

#### 5.4.6 Reporting



5.4.6(a)For all Public Works Contracts covered by this Article 5.4, the **Contractor** shall report to the **City Agency** the following information:

- 5.4.6(a)(i) The total number of diesel-powered Nonroad Vehicles used to fulfill the requirements of this Public Works Contract;
- 5.4.6(a)(ii) The number of such Nonroad Vehicles that were powered by Ultra Low Sulfur Diesel Fuel;
- 5.4.6(a)(iii)The number of such Nonroad Vehicles that utilized the best available technology for reducing the emission of pollutants, including a breakdown by vehicle model and the type of technology;
- 5.4.6(a)(iv) The number of such Nonroad Vehicles that utilized such other authorized technology in accordance with Article 5.4.3, including a breakdown by vehicle model and the type of technology used for each such vehicle;
- 5.4.6(a)(v) The locations where such Nonroad Vehicles were used; and
- 5.4.6(a)(vi) Where a determination is in effect pursuant to Article 5.4.2(b) or 5.4.2(c), detailed information concerning the **Contractor's** efforts to obtain Ultra Low Sulfur Diesel Fuel or diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm).

5.4.6(b) The **Contractor** shall submit the information required by Article 5.4.6(a) at the completion of **Work** under the Public Works Contract and on a yearly basis no later than August 1 throughout the term of the Public Works Contract. The yearly report shall cover **Work** performed during the preceding fiscal year (July 1 - June 30).

5.5Ultra Low Sulfur Diesel Fuel. In accordance with the Coordinated Construction Act for Lower Manhattan, as amended:

5.5.1Definitions. For purposes of this Article 5.5, the following definitions apply:

- 5.5.1(a) "Lower Manhattan" means the area to the south of and within the following lines: a line beginning at a point where the United States pierhead line in the Hudson River as it exists now or may be extended would intersect with the southerly line of West Houston Street in the Borough of Manhattan extended, thence easterly along the southerly side of West Houston Street to the southerly side of Houston Street, thence easterly along the southerly side of Houston Street, to the southerly side of East Houston Street, thence northeasterly along the southerly side of East Houston Street is would intersect with the United States pierhead line in the East River as it exists now or may be extended, including tax lots within or immediately adjacent thereto.
- 5.5.1(b) "Lower Manhattan Redevelopment Project" means any project in Lower Manhattan that is funded in whole or in part with federal or State funding, or any project intended to improve transportation between Lower Manhattan and the two air terminals in the City known as LaGuardia Airport and John F. Kennedy International



Airport, or between Lower Manhattan and the air terminal in Newark known as Newark Liberty International Airport, and that is funded in whole or in part with federal funding.

- 5.5.1(c) "Nonroad Engine" means an internal combustion engine (including the fuel system) that is not used in a Motor Vehicle or a vehicle used solely for competition, or that is not subject to standards promulgated under Section 7411 or Section 7521 of Title 42 of the United States Code, except that this term shall apply to internal combustion engines used to power generators, compressors or similar equipment used in any construction program or project.
- 5.5.1(d) "Nonroad Vehicle" means a vehicle that is powered by a Nonroad Engine, fifty (50) horsepower (HP) and greater, and that is not a Motor Vehicle or a vehicle used solely for competition, which shall include, but not be limited to, excavators, backhoes, cranes, compressors, generators, bulldozers, and similar equipment, except that this terms shall not apply to horticultural maintenance vehicles used for landscaping purposes that are powered by a Nonroad Engine of sixty-five (65) HP or less and that are not used in any construction program or project.
- 5.5.1(e) "Ultra Low Sulfur Diesel Fuel" means diesel fuel that has a sulfur content of no more than fifteen parts per million (15 ppm).
- 5.5.2 Requirements: **Contractors** and **Subcontractors** are required to use only Ultra Low Sulfur Diesel Fuel to power the diesel-powered Nonroad Vehicles with engine HP rating of fifty (50) HP and above used on a Lower Manhattan Redevelopment Project and, where practicable, to reduce the emission of pollutants by retrofitting such Nonroad Vehicles with oxidation catalysts, particulate filters, or technology that achieves lowest particulate matter emissions.

5.6 Pesticides. In accordance with Section 17-1209 of the Administrative Code, to the extent that the **Contractor** or any **Subcontractor** applies pesticides to any property owned or leased by the **City**, the **Contractor**, and any **Subcontractor** shall comply with Chapter 12 of the Administrative Code.

5.7 Waste Treatment, Storage, and Disposal Facilities and Transporters. In connection with the **Work**, the **Contractor** and any **Subcontractor** shall use only those waste treatment, storage, and disposal facilities and waste transporters that possess the requisite license, permit or other governmental approval necessary to treat, store, dispose, or transport the waste, materials or hazardous substances.

5.8 Environmentally Preferable Purchasing. The **Contractor** shall ensure that products purchased or leased by the **Contractor** or any **Subcontractor** for the **Work** that are not specified by the **City** or are submitted as equivalents to a product specified by the **City** comply with the requirements of the New York City Environmentally Preferable Purchasing Program contained in Chapter 11 of Title 43 of the RCNY, pursuant to Chapter 3 of Title 6 of the Administrative Code.

## **ARTICLE 6. INSPECTION**

6.1 During the progress of the **Work** and up to the date of **Final Acceptance**, the **Contractor** shall at all times afford the representatives of the **City** every reasonable, safe, and proper facility for inspecting all **Work** done or being done at the **Site** and also for inspecting the manufacture or preparation of materials and equipment at the place of such manufacture or preparation.





6.2 The **Contractor's** obligation hereunder shall include the uncovering or taking down of finished **Work** and its restoration thereafter; provided, however, that the order to uncover, take down and restore shall be in writing, and further provided that if **Work** thus exposed proves satisfactory, and if the **Contractor** has complied with Article 6.1, such uncovering or taking down and restoration shall be considered an item of **Extra Work** to be paid for in accordance with the provisions of this Contractor. If the **Work** thus exposed proves unsatisfactory, the **City** has no obligation to compensate the **Contractor** for the uncovering, taking down or restoration.

6.3 Inspection and approval by the Commissioner, the Engineer, Project Manager, or Resident Engineer, of finished Work or of Work being performed, or of materials and equipment at the place of manufacture or preparation, shall not relieve the Contractor of its obligation to perform the Work in strict accordance with the Contract. Finished or unfinished Work not found to be in strict accordance with the Contract shall be replaced as directed by the Engineer, even though such Work may have been previously approved and paid for. Such corrective Work is Contract Work and shall not be deemed Extra Work.

6.4 Rejected **Work** and materials shall be promptly taken down and removed from the **Site**, which must at all times be kept in a reasonably clean and neat condition.

## ARTICLE 7. PROTECTION OF WORK AND OF PERSONS AND PROPERTY; NOTICES AND INDEMNIFICATION

7.1 During the performance of the Work and up to the date of Final Acceptance, the Contractor shall be under an absolute obligation to protect the finished and unfinished Work against any damage, loss, injury, theft and/or vandalism and in the event of such damage, loss, injury, theft and/or vandalism, it shall promptly replace and/or repair such Work at the Contractor's sole cost and expense, as directed by the Resident Engineer. The obligation to deliver finished Work in strict accordance with the Contract prior to Final Acceptance shall be absolute and shall not be affected by the Resident Engineer's approval of, or failure to prohibit, the Means and Methods of Construction used by the Contractor.

7.2 During the performance of the Work and up to the date of Final Acceptance, the Contractor shall take all reasonable precautions to protect all persons and the property of the City and of others from damage, loss or injury resulting from the Contractor's, and/or its Subcontractors' operations under this Contract. The Contractor's obligation to protect shall include the duty to provide, place or replace, and adequately maintain at or about the Site suitable and sufficient protection such as lights, barricades, and enclosures.

7.3 The **Contractor** shall comply with the notification requirements set forth below in the event of any loss, damage or injury to **Work**, persons or property, or any accidents arising out of the operations of the **Contractor** and/or its **Subcontractors** under this **Contract**.

- 7.3.1 The Contractor shall make a full and complete report in writing to the Resident Engineer within three (3) Days after the occurrence.
- 7.3.2 The **Contractor** shall also send written notice of any such event to all insurance carriers that issued potentially responsive policies (including commercial general liability

insurance carriers for events relating to the **Contractor**'s own employees) no later than twenty (20) days after such event and again no later than twenty (20) days after the initiation of any claim and/or action resulting there from. Such notice shall contain the following information: the number of the insurance policy, the name of the Named Insured, the date and location of the incident, and the identity of the persons injured or property damaged. For any policy on which the **City** and/or the **Engineer**, **Architect**, or **Project Manager** are Additional Insureds, such notice shall expressly specify that "this notice is being given on behalf of the City of New York as Additional Insured, such other Additional Insureds, as well as the Named Insured."

7.3.2(a) Whenever such notice is sent under a policy on which the City is an Additional Insured, the Contractor shall provide copies of the notice to the Comptroller, the Commissioner and the City Corporation Counsel. The copy to the Comptroller shall be sent to the Insurance Unit, NYC Comptroller's Office, 1 Centre Street – Room 1222, New York, New York, 10007. The copy to the Commissioner shall be sent to the address set forth in Schedule A of the General Conditions. The copy to the City Corporation Counsel shall be sent to Insurance Claims Specialist, Affirmative Litigation Division, New York City Law Department, 100 Church Street, New York, New York 10007.

7.3.2(b) If the **Contractor** fails to provide any of the foregoing notices to any appropriate insurance carrier(s) in a timely and complete manner, the **Contractor** shall indemnify the **City** for all losses, judgments, settlements, and expenses, including reasonable attorneys' fees, arising from an insurer's disclaimer of coverage citing late notice by or on behalf of the **City**.

7.4 To the fullest extent permitted by law, the Contractor shall defend, indemnify, and hold the City, its employees, and officials (the "Indemnitees") harmless against any and all claims (including but not limited to claims asserted by any employee of the Contractor and/or its Subcontractors) and costs and expenses of whatever kind (including but not limited to payment or reimbursement of attorneys' fees and disbursements) allegedly arising out of or in any way related to the operations of the Contractor and/or its Subcontractors in the performance of this Contract or from the Contractor's and/or its Subcontractors' failure to comply with any of the provisions of this Contractor of the Law. Such costs and expenses shall include all those incurred in defending the underlying claim and those incurred in connection with the enforcement of this Article 7.4 by way of cross-claim, third-party claim, declaratory action or otherwise. The parties expressly agree that the indemnification obligation hereunder contemplates (1) full indemnity in the event of liability imposed against the Indemnitees without negligence and solely by reason of statute, operation of Law or otherwise; and (2) partial indemnity in the event of any actual negligence on the part of the Indemnitees either causing or contributing to the underlying claim (in which case, indemnification will be limited to any liability imposed over and above that percentage attributable to actual fault whether by statute, by operation of Law, or otherwise). Where partial indemnity is provided hereunder, all costs and expenses shall be indemnified on a pro rata basis.

7.4.1Indemnification under Article 7.4 or any other provision of the **Contract** shall operate whether or not **Contractor** or its **Subcontractors** have placed and maintained the insurance specified under Article 22.

7.5 The provisions of this Article 7 shall not be deemed to create any new right of action in favor of third parties against the **Contractor** or the **City**.



## CHAPTER III TIME PROVISIONS

## **ARTICLE 8. COMMENCEMENT AND PROSECUTION OF THE WORK**

8.1 The Contractor shall commence the Work on the date specified in the Notice to Proceed or the Order to Work. The time for performance of the Detailed Scope of Work shall be the duration set forth in the Job Order. TIME BEING OF THE ESSENCE to the City, the Contractor shall thereafter prosecute the Work diligently, using such Means and Methods of Construction as are in accord with Article 4 herein and as will assure its completion within the Job Order Completion Time, or on the date to which the time for completion may be extended.

#### **ARTICLE 9. PROGRESS SCHEDULES**

9.1 To enable the Work to be performed in an orderly and expeditious manner, the Contractor, within fifteen (15) Days after the Notice to Proceed or Order to Work, unless otherwise directed by the Engineer, shall submit to the Engineer a proposed progress schedule based on the Critical Path Method in the form of a bar graph or in such other form as specified by the Engineer, and monthly cash flow requirements, showing:

9.1.1 The anticipated time of commencement and completion of each of the various operations to be performed under the **Job Order**; and

9.1.2 The sequence and interrelation of each of these operations with the others and with those of other related contracts; and

9.1.3 The estimated time required for fabrication or delivery, or both, of all materials and equipment required for the **Work**, including the anticipated time for obtaining required approvals pursuant to Article 10; and

9.1.4 The estimated amount in dollars the **Contractor** will claim on a monthly basis.

9.2 The proposed schedule shall be revised as directed by the **Engineer**, until finally approved by the **Engineer**, and after such approval, subject to the provisions of Article 11, shall be strictly adhered to by the **Contractor**.

9.3 If the **Contractor** shall fail to adhere to the approved progress schedule, or to the schedule as revised pursuant to Article 11, it shall promptly adopt such other or additional **Means and Methods of Construction**, at its sole cost and expense, as will make up for the time lost and will assure completion in accordance with the approved progress schedule. The approval by the **City** of a progress schedule which is shorter than the time allotted under the **Contract** shall not create any liability for the **City** if the approved progress schedule is not met.

9.4 The **Contractor** will not receive **a Job Order** or any payments thereunder until the proposed progress schedule is submitted.

## ARTICLE 10. REQUESTS FOR INFORMATION OR APPROVAL



10.1 From time to time as the **Work** progresses and in the sequence indicated by the approved progress schedule, the **Contractor** shall submit to the **Engineer** a specific request in writing for each item of information or approval required by the **Contractor**. These requests shall state the latest date upon which the information or approval is actually required by the **Contractor**, and shall be submitted in a reasonable time in advance thereof to provide the **Engineer** a sufficient time to act upon such submissions, or any necessary re-submissions thereof.

10.2 The **Contractor** shall not have any right to an extension of time on account of delays due to the **Contractor's** failure to submit requests for the required information or the required approval in accordance with the above requirements.

## ARTICLE 11. NOTICE OF CONDITIONS CAUSING DELAY AND DOCUMENTATION OF DAMAGES CAUSED BY DELAY

11.1 After the commencement of any condition which is causing or may cause a delay in completion of the **Work**, including conditions for which the **Contractor** may be entitled to an extension of time, the following notifications and submittals are required:

- 11.1.1 Within seven (7) **Days** after the commencement of such condition, the **Contractor** must notify the **Engineer** in writing of the existence, nature and effect of such condition upon the approved progress schedule and the **Work**, and must state why and in what respects, if any, the condition is causing or may cause a delay.
- 11.1.2 If the **Contractor** shall claim to be sustaining damages for delay as provided for in this Article 11, within forty-five (45) **Days** from the time such damages are first incurred, and every thirty (30) **Days** thereafter for as long as such damages are being incurred, the **Contractor** shall submit to the **Commissioner** verified written statements of the details and the amounts of such damages, together with documentary evidence of such damages. The **Contractor** may submit any of the above statements within such additional time as may be granted by the **Commissioner** in writing upon written request therefor. On failure of the **Contractor** to strictly comply with all of the foregoing provisions, such claims shall be deemed waived and no right to recover on such claims shall exist. Damages that the **Contractor** may claim in any action arising under or by reason of this **Contract** shall not be different from or in excess of the statements made and documentation provided pursuant to this Article 11.

11.2 Failure of the **Contractor** to strictly comply with the requirements of Article 11.1.1 may, in the discretion of the **Commissioner**, be deemed sufficient cause to deny any extension of time on account of delay arising out of such condition. Failure of the **Contractor** to strictly comply with the requirements of Articles 11.1.1 and 11.1.2 shall be deemed a conclusive waiver by the **Contractor** of any and all claims for damages for delay arising from such condition and no right to recover on such claims shall exist.

11.3 When appropriate and directed by the **Engineer**, the progress schedule shall be revised by the **Contractor** untill finally approved by the **Engineer**. The revised progress schedule must be strictly adhered to by the **Contractor**.

11.4 Not Used

22



- 11.5 Not Used
- 11.6 Not Used
- 11.7 Not Used
- 11.8 Not Used
- 11.9 Not Used

#### ARTICLE 12. COORDINATION WITH OTHER CONTRACTORS

12.1 During the progress of the Work, Other Contractors may be engaged in performing other work or may be awarded other contracts for additional work on this **Project**. In that event, the Contractor shall coordinate the Work to be done hereunder with the work of such Other Contractors and the Contractor shall fully cooperate with such Other Contractors and carefully fit its own Work to that provided under other contracts as may be directed by the Engineer. The Contractor shall not commit or permit any act which will interfere with the performance of work by any Other Contractors.

12.2 If the Engineer determines that the Contractor is failing to coordinate its Work with the work of Other Contractors as the Engineer has directed, then the Commissioner shall have the right to withhold any payments otherwise due hereunder until the Contractor completely complies with the Engineer's directions.

12.3 The Contractor shall notify the Engineer in writing if any Other Contractor on this Project is failing to coordinate its work with the Work of this Contract. If the Engineer finds such charges to be true, the Engineer shall promptly issue such directions to the Other Contractor with respect thereto as the situation may require. The City shall not, however, be liable for any damages suffered by any Other Contractor's failure to coordinate its work with the Work of this Contract or by reason of the Other Contractor's failure to promptly comply with the directions so issued by the Engineer, or by reason of any Other Contractor's default in performance, it being understood that the City does not guarantee the responsibility or continued efficiency of any contractor. The Contractor agrees to make no claim against the City for any damages relating to or arising out of any directions issued by the Engineer pursuant to this Article 12 (including but not limited to the failure of any Other Contractor to comply or promptly comply with such directions), or the failure of the Engineer to issue any directions, or the failure of any Other Contractor.

12.4 The Contractor shall indemnify and hold the **City** harmless from any and all claims or judgments for damages and from costs and expenses to which the **City** may be subjected or which it may suffer or incur by reason of the **Contractor's** failure to comply with the **Engineer's** directions promptly; and the **Comptroller** shall have the right to exercise the powers reserved in Article 23 with respect to any claims which may be made for damages due to the **Contractor's** failure to comply with the **Engineer's** directions promptly. Insofar as the facts and **Law** relating to any claim would preclude the **City** from being completely indemnified by the **Contractor**, the **City** shall be partially indemnified by the **Contractor** to the fullest extent provided by **Law**.

12.5 Should the **Contractor** sustain any damage through any act or omission of any **Other Contractor** having a contract with the **City** for the performance of work upon the **Site** or of work which may be



necessary to be performed for the proper prosecution of the Work to be performed hereunder, or through any act or omission of a subcontractor of such Other Contractor, the Contractor shall have no claim against the City for such damage, but shall have a right to recover such damage from the Other Contractorunder the provision similar to the following provisions which apply to this Contract and have been or will be inserted in the contracts with such Other Contractors:

12.5.1 Should any Other Contractor having or who shall hereafter have a contract with the City for the performance of work upon the Site sustain any damage through any act or omission of the Contractor hereunder or through any act or omission of any Subcontractor of the Contractor, the Contractor agrees to reimburse such Other Contractor for all such damages and to defend at its own expense any action based upon such claim and if any judgment or claim (even if the allegations of the action are without merit) against the City shall be allowed the Contractor shall pay or satisfy such judgment or claim and pay all costs and expenses in connection therewith and agrees to indemnify and hold the City harmless from all such claims. Insofar as the facts and Law relating to any claim would preclude the City from being completely indemnified by the Contractor, the City shall be partially indemnified by the Contractor to the fullest extent provided by Law.

12.6 The **City's** right to indemnification hereunder shall in no way be diminished, waived or discharged by its recourse to assessment of liquidated damages as provided in Article 15, or by the exercise of any other remedy provided for by **Contract** or by **Law**.





# ARTICLE 13. EXTENSION OF TIME FOR PERFORMANCE FOR THE CONTRACT

· 13.1 Not Used

13.2 Not Used

13.3 Not Used

13.3.1 Not Used

13.3.2 Not Used

13.3.3 Not used

13.3.4 Not Used

13.4 Not Used

13.5 Not Used

13.6 Not Used.

13.7 Not Used

13.8 Not Used

13.8.1 Not Used:

13.8.1(a) Not Used;

13.8.1(b) Not Used;

13.8.1(c)Not Used

13.8.1(d) Not Used

13.8.1(e) Not Used

13.8.1(f) Not Used.

13.8.2 Not Used

# NEW YORK DITY DEPARTMENT OF DESIGN + CONSTRUCTION

Contract

13.8.2(a) Not Used

13.8.2(b) Not Used

13.8.2(c) Not Used

13.8.2(d) Not Used

## 13.9 Not Used

13.9.1 Not Used

13.9.1(a) Not Used

13.9.1(b) Not Used

13.9.1(c) Not Used

13.9.1(d) Not Used.

13.9.2 Not Used

13.9.3 Not Used

13.9.4 Not Used

13.10 Not Used

## ARTICLE 13A. EXTENSION OF TIME FOR PERFORMANCE OF A JOB ORDER

13A.1 Not Used

13A.2 Not Used

13A.3 Not Used

13A.3.1 Not Used

13A.3.2 Not Used

13A.3.3 Not Used

13A.4 Not Used

13A.5 Not Used

13A.5.1. Not Used

13A.6 Not Used

13A.7 Not Used

13A.8 Not Used

13A.9 Not Used



## ARTICLE 14. COMPLETION AND FINAL ACCEPTANCE OF THE WORK

14.1 Not Used

14.2 Not Used

14.3 Not Used

14.4 Determining the Date of **Final Acceptance** of a **Job Order**: The **Detailed Scope of Work** will be accepted as final and complete as of the date of the **Engineer's** inspection if, upon such inspection, the **Engineer** finds that all items on the **Final Approved Punch List** are complete and no further **Work** on the **Job Order** remains to be done. The **Commissioner** will then issue a written determination of **Final Acceptance**.

14.5 Request for Inspection: Inspection of the Work by the Engineer for the purpose of Final Acceptance shall be made within ten (10) Days after receipt of the Contractor's written request therefor.

14.6 Request for Re-inspection: If upon inspection for the purpose of Final Acceptance, the Engineer determines that there are items of Work still to be performed, the Contractor shall promptly perform them and then request a re-inspection. If upon re-inspection, the Engineer determines that the Work is finally accepted, the date of such re-inspection shall be the date of Final Acceptance. Re-inspection by the Engineer shall be made within ten (10) Days after receipt of the Contractor's written request therefor.

14.7 Initiation of Inspection by the Engineer: If the Contractor does not request inspection or reinspection of the Work for the purpose of Final Acceptance, the Engineer may initiate such inspection or re-inspection.

#### ARTICLE 15. LIQUIDATED DAMAGES

15.1 In the event the Contractor fails to complete the Detailed Scope of Work for a Job Order within the Job Order Completion Time, plus authorized time extensions, or if the Contractor, in the sole determination of the Commissioner, has abandoned the Work, the Contractor shall pay to the City Five Hundred Dollars (\$500.00) for each and every Day that the time consumed in completing the Work exceeds the time allowed therefor; which said sum, in view of the difficulty of accurately ascertaining the loss which the City will suffer by reason of delay in the completion of the Work hereunder, is hereby fixed and agreed as the liquidated damages that the City will suffer by reason of such delay, and not as a penalty. This Article 15 shall also apply to the Contractor whether or not the Contractor is defaulted pursuant to Chapter X of this Contract. Neither the failure to assess liquidated damages nor the granting of any time extension shall operate as a waiver or release of any claim the City may have against the Contractor for either actual or liquidated damages.

15.2 Liquidated damages received hereunder are not intended to be nor shall they be treated as either a partial or full waiver or discharge of the **City's** right to indemnification, or the **Contractor's** obligation to indemnify the **City**, or to any other remedy provided for in this **Contract** or by **Law**.



28



15.3 The **Commissioner** may deduct and retain out of the monies which may become due hereunder, the amount of any such liquidated damages; and in case the amount which may become due hereunder shall be less than the amount of liquidated damages suffered by the **City**, the **Contractor** shall be liable to pay the difference.

## ARTICLE 16. OCCUPATION OR USE PRIOR TO COMPLETION

16.1 Unless otherwise provided for in the Specifications, the Commissioner may take over, use, occupy or operate any part of the Work at any time prior to Final Acceptance, upon written notification to the Contractor. The Engineer shall inspect the part of the Work to be taken over, used, occupied, or operated, and will furnish the Contractor with a written statement of the Work, if any, which remains to be performed on such part. The Contractor shall not object to, nor interfere with, the Commissioner's decision to exercise the rights granted by Article 16. In the event the Commissioner takes over, uses, occupies, or operates any part of the Work:

16.1.1 the **Engineer** shall issue a written determination of completion with respect to such part of the **Work**;

16.1.2 the **Contractor** shall be relieved of its absolute obligation to protect such part of the unfinished **Work** in accordance with Article 7;

16.1.3 the **Contractor's** guarantee on such part of the **Work** shall begin on the date of such use by the **City**; and;

16.1.4 the **Contractor** shall be entitled to a return of so much of the amount retained in accordance with Article 21 as it relates to such part of the **Work**, except so much thereof as may be retained under Articles 24 and 44.

### CHAPTER IV SUBCONTRACTS AND ASSIGNMENTS

## **ARTICLE 17. SUBCONTRACTS**

17.1 The Electrical, HVAC and Plumbing **Contractor** shall perform with its own forces at least 50% of the **Work** within its own trade, and the General **Contractor** shall perform with its own forces at least 15% of all **Work**, unless prior written permission is obtained from the **Commissioner**. The percentage goals shall apply to the total of all **Job Orders**, and not to each individual **Job Order**. The purchase of materials not installed with the **Contractor's** own forces will not count towards meeting the goal.

All subcontracts made by the **Contractor** shall be in writing. No **Work** may be performed by a **Subcontractor** prior to the **Contractor** entering into a written subcontract with the **Subcontractor** and complying with the provisions of this Article 17.

17.2 Before making any subcontracts, the **Contractor** shall submit a written statement to the **Commissioner** giving the name and address of the proposed **Subcontractor**; the portion of the **Work** 





and materials which it is to perform and furnish; the cost of the subcontract; the VENDEX questionnaire if required; the proposed subcontract if requested by the **Commissioner**; and any other information tending to prove that the proposed **Subcontractor** has the necessary facilities, skill, integrity, past experience, and financial resources to perform the **Work** in accordance with the terms and conditions of this **Contract**.

17.5 The **Commissioner** will notify the **Contractor** in writing whether the proposed **Subcontractor** is approved. If the proposed **Subcontractor** is not approved, the **Contractor** may submit another proposed **Subcontractor** unless the **Contractor** decides to do the **Work**. No **Subcontractor** shall be permitted to enter or perform any work on the **Site** unless approved.

17.3 In addition to the requirements in Article 17.2, **Contractor** is required to list the **Subcontractor** in the web based Subcontractor Reporting System through the City's Payee Information Portal (PIP), available at <u>www.nyc.gov/pip.</u><sup>1</sup> For each **Subcontractor** listed, **Contractor** is required to provide the following information: Not to Exceed value, description of **Subcontractor's** Work, start and end date of thesubcontract and identification of the **Subcontractor's** industry.Thereafter, **Contractor** will be required to report in the system the payments made to each **Subcontractor** within 30 days of making the payment. If any of the required information changes throughout the Term of the **Contract, Contractor** will be required to revise the information in the system.

Failure of the **Contractor** to list a **Subcontractor** and/or to report **Subcontractor** payments in a timely fashion may result in the **Commissioner** declaring the **Contractor** in default of the **Contract** and will subject **Contractor** to liquidated damages in the amount of \$100 per day for each day that the **Contractor** fails to identify a **Subcontractor** along with the required information about the **Subcontractor** and/or fails to report payments to a **Subcontractor**, beyond the time frames set forth herein or in the notice from the **City**. Article 15 shall govern the issue of liquidated damages.

17.4 If an approved **Subcontractor** elects to subcontract any portion of its subcontract, the proposed subsubcontract shall be submitted in the same manner as directed above.

17.6 Before entering into any subcontract hereunder, the **Contractor** shall provide the proposed **Subcontractor** with a complete copy of this document and inform the proposed **Subcontractor** fully and completely of all provisions and requirements of this **Contract** relating either directly or indirectly to the **Work** to be performed and the materials to be furnished under such subcontract, and every such **Subcontractor** shall expressly stipulate that all labor performed and materials furnished by the **Subcontractor** shall strictly comply with the requirements of this **Contract**.

17.7 Documents given to a prospective Subcontractor for the purpose of soliciting the Subcontractor's bid shall include either a copy of the Detailed Scope of Work or a separate information sheet setting forth the Project name, the Contract number (if available), the Agency (as noted in Article 2.1.6), and the Project's location.

17.8 The**Commissioner's** approval of a **Subcontractor** shall not relieve the **Contractor** of any of its responsibilities, duties, and liabilities hereunder. The **Contractor** shall be solely responsible to the **City** 





<sup>&</sup>lt;sup>1</sup>In order to use the new system, a PIP account will be required. Detailed instructions on creating a PIP account and using the new system are also available at <u>www.nyc.gov/pip</u>. Additional assistance with PIP may be obtained by emailing the Financial Information Services Agency Help Desk at <u>pip@fisa.nyc.gov</u>.



for the acts or defaults of its **Subcontractor** and of such **Subcontractor's** officers, agents, and employees, each of whom shall, for this purpose, be deemed to be the agent or employee of the **Contractor** to the extent of its subcontract.

17.9 If the Subcontractor fails to maintain the necessary facilities, skill, integrity, past experience, and financial resources (other than due to the Contractor's failure to make payments where required) to perform the Work in accordance with the terms and conditions of this Contract, the Contractor shallpromptly notify the Commissionerand replace such Subcontractor with a newly approved Subcontractorin accordance with this Article 17.

17.10 The **Contractor** shall be responsible for ensuring that all **Subcontractors** performing **Work** at the **Site** maintain all insurance required by **Law**.

17.11 The **Contractor** shall promptly, upon request, file with the **Engineer** a conformed copy of the subcontract and its cost. The subcontract shall provide the following:

17.11.1Payment to Subcontractors: The agreement between the Contractor and its Subcontractor shall contain the same terms and conditions as to method of payment for Work, labor, and materials, and as to retained percentages, as are contained in this Contract.

17.11.2Prevailing Rate of Wages: The agreement between the **Contractor** and its **Subcontractor** shall include the prevailing wage rates and supplemental benefits to be paid in accordance with Labor Law Section 220.

17.11.3 Section 6-123 of the Administrative Code: Pursuant to the requirements of Section 6-123 of the Administrative Code, every agreement between the **Contractor** a **Subcontractor** in excess of fifty thousand dollars (\$50,000) shall include a provision that the **Subcontractor** shall not engage in any unlawful discriminatory practice as defined in Title VIII of the Administrative Code (Section 8-101 *et seq.*).

17.11.4 All requirements required pursuant to federal and/or state grant agreement(s), if applicable to the Work.

17.12 The Commissioner may deduct from the amounts certified under this Contract to be due to the Contractor, the sum or sums due and owing from the Contractor to the Subcontractors according to the terms of the said subcontracts, and in case of dispute between the Contractor and its Subcontractor, or Subcontractors, as to the amount due and owing, the Commissioner may deduct and withhold from the amounts certified under this Contract to be due to the Contractor such sum or sums as may be claimed by such Subcontractor, or Subcon

17.13 OnContracts where performance bonds and payment bonds are executed, the Contractor shall include on each requisition for payment the following data: Subcontractor's name, value of the subcontract, total amount previously paid to Subcontractor for Work previously requisitioned, and the amount, including retainage, to be paid to the Subcontractor for Work included in the requisition.

17.14OnContracts where performance bonds and payment bonds are not executed, the Contractor shall include with each requisition for payment submitted hereunder, a signed statement from each and every Subcontractor and/or Materialman for whom payment is requested in such requisition. Such signed statement shall be on the letterhead of the Subcontractor and/or Materialman for whom payment



is requested and shall (i) verify that such **Subcontractor** and/or **Materialman** has been paid in full for all **Work** performed and/or material supplied to date, exclusive of any amount retained and any amount included on the current requisition, and (ii) state the total amount of retainage to date, exclusive of any amount retained on the current requisition.

#### **ARTICLE 18. ASSIGNMENTS**

18.1 The **Contractor** shall not assign, transfer, convey or otherwise dispose of this **Contract**, or the right to execute it, or the right, title or interest in or to it or any part thereof, or assign, by power of attorney or otherwise any of the monies due or to become due under this **Contract**, unless the previous written consent of the **Commissioner** shall first be obtained thereto, and the giving of any such consent to a particular assignment shall not dispense with the necessity of such consent to any further or other assignments.

18.2 Such assignment, transfer, conveyance or other disposition of this **Contract** shall not be valid until filed in the office of the **Commissioner** and the **Comptroller**, with the written consent of the **Commissioner** endorsed thereon or attached thereto.

18.3 Failure to obtain the previous written consent of the **Commissioner** to such an assignment, transfer, conveyance or other disposition, may result in the revocation and annulment of this **Contract**. The **City** shall thereupon be relieved and discharged from any further liability to the **Contractor**, its assignees, transferees or sublessees, who shall forfeit and lose all monies therefor earned under the **Contract**, except so much as may be required to pay the **Contractor's** employees.

18.4 The provisions of this clause shall not hinder, prevent, or affect an assignment by the **Contractor** for the benefit of its creditors made pursuant to the **Laws** of the State of New York.

18.5 This**Contract** may be assigned by the **City** to any corporation, agency or instrumentality having authority to accept such assignment.

## CHAPTER V

## **CONTRACTOR'S SECURITY AND GUARANTEE**

#### **ARTICLE 19. SECURITY DEPOSIT**

19.1 If performance and payment bonds are required, the City shall retain the bid security to ensure that the successful bidder executes the **Contract** and furnishes the required payment and performance security within ten (10) **Days** after notice of the award of the **Contract**. If the successful bidder fails to execute the **Contract** and furnish the required payment and performance security, the **City** shall retain such bid security as set forth in the Information for Bidders. If the successful bidder executes the **Contract** and furnishes the required payment and performance security, the **City** shall return the bid security within a reasonable time after the furnishing of such bonds and execution of the **Contract** by the **City**.

19.2 If performance and payment bonds are not required, the bid security shall be retained by the City as security for the Contractor's faithful performance of the Contract. If partial payments are provided, the bid security will be returned to the Contractor after the sum retained under Article 21

32



equals the amount of the bid security, subject to other provisions of this **Contract**. If partial payments are not provided, the bid security will be released when final payment is certified by the **City** for payment.

19.3 If the **Contractor** is declared in default under Article 48 prior to the return of the deposit, or if any claim is made such as referred to in Article 23, the amount of such deposit, or so much thereof as the **Comptroller** may deem necessary, may be retained and then applied by the **Comptroller**:

19.3.1 To compensate the **City** for any expense, loss or damage suffered or incurred by reason of or resulting from such default, including the cost of re-letting and liquidated damages; or

19.3.2 To indemnify the City against any and all claims.

## **ARTICLE 20. PAYMENT GUARANTEE**

20.1 On**Contracts** where one hundred (100%) percent performance bonds and payment bonds are executed, this Article 20 does not apply.

20.2 In the event the terms of this **Contract** do not require the **Contractor** to provide a payment bond or where the **Contract** does not require a payment bond for one hundred (100%) percent of the **Contract** price, the **City** shall, in accordance with the terms of this Article 20, guarantee payment of all lawful claims for:

20.2.1 Wages and compensation for labor performed and/or services rendered; and

20.2.2 Materials, equipment, and supplies provided, whether incorporated into the Work or not, when demands have been filed with the City as provided hereinafter by any person, firm, or corporation which furnished labor, material, equipment, supplies, or any combination thereof, in connection with the Work performed hereunder (hereinafter referred to as the "beneficiary") at the direction of the City or the Contractor.

20.3 The provisions of Article 20.2 are subject to the following limitations and conditions:

20.3.1 If the **Contractor** provides a payment bond for a value that is less than one hundred (100%) percent of the value of the **Contract Work**, the payment bond provided by the **Contractor** shall be primary (and non-contributing) to the payment guarantee provided under this Article 20.

20.3.2 The guarantee is made for the benefit of all beneficiaries as defined in Article 20.2 provided that those beneficiaries strictly adhere to the terms and conditions of Article 20.3.4 and 20.3.5.

20.3.3 Nothing in this Article 20 shall prevent a beneficiary providing labor, services or material for the **Work** from suing the **Contractor** for any amounts due and owing the beneficiary by the **Contractor**.

20.3.4 Every person who has furnished labor or material, to the **Contractor** or to a **Subcontractor** of the **Contractor**, in the prosecution of the **Work** and who has not been paid in full therefor before the expiration of a period of ninety (90) **Days** after the date on which the last of the labor was performed or material was furnished by him/her for which the claim is made,



shall have the right to sue on this payment guarantee in his/her own name for the amount, or the balance thereof, unpaid at the time of commencement of the action; provided, however, that a person having a direct contractual relationship with a **Subcontractor** of the **Contractor** but no contractual relationship express or implied with the **Contractor** shall not have a right of action upon the guarantee unless he/she shall have given written notice to the **Contractor** within one hundred twenty (120) **Days** from the date on which the last of the labor was performed or the last of the material was furnished, for which his/her claim is made, stating with substantial accuracy the amount claimed and the name of the party to whom the material was furnished or for whom the labor was performed. The notice shall be served by delivering the same personally to the **Contractor** at any place where it maintains an office or conducts its business; provided, however, that where such notice is actually received by the **Contractor** by other means, such notice shall be deemed sufficient.

20.3.5 Except as provided in Labor Law Section 220-g, no action on this payment guarantee shall be commenced after the expiration of the one-year limitations period set forth in Section 137(4)(b) of the State Finance Law.

20.3.6 The **Contractor** shall promptly forward to the **City** any notice or demand received pursuant to Article 20.3.4. The **Contractor** shall inform the **City** of any defenses to the notice or demand and shall forward to the **City** any documents the **City** requests concerning the notice or demand.

20.3.7 All demands made against the **City** by a beneficiary of this payment guarantee shall be presented to the Engineer along with all written documentation concerning the demand which the Engineer deems reasonably appropriate or necessary, which may include, but shall not be limited to: the subcontract; any invoices presented to the **Contractor** for payment; the notarized statement of the beneficiary that the demand is due and payable, that a request for payment has been made of the **Contractor** and that the demand has not been paid by the **Contractor** within the time allowed for such payment by the subcontract; and copies of any correspondence between the beneficiary and the **Contractor** concerning such demand. The **City** shall notify the **Contractor** that a demand has been made. The **Contractor** shall inform the **City** of any defenses to the demand and shall forward to the **City** any documents the **City** requests concerning the demand.

20.3.8 The City shall make payment only if, after considering all defenses presented by the Contractor, it determines that the payment is due and owing to the beneficiary making the demand.

20.3.9 No beneficiary shall be entitled to interest from the **City**, or to any other costs, including, but not limited to, attorneys' fees, except to the extent required by State Finance Law Section 137.

20.4 Upon the receipt by the **City** of a demand pursuant to this Article 20, the **City** may withhold from any payment otherwise due and owing to the **Contractor** under this **Contract** an amount sufficient to satisfy the demand.

20.4.1 In the event the **City** determines that the demand is valid, the **City** shall notify the **Contractor** of such determination and the amount thereof and direct the **Contractor** to immediately pay such amount to the beneficiary. In the event the **Contractor**, within

seven (7) **Days** of receipt of such notification from the **City**, fails to pay the beneficiary, such failure shall constitute an automatic and irrevocable assignment of payment by the **Contractor** to the beneficiary for the amount of the demand determined by the **City** to be valid. The **Contractor**, without further notification or other process, hereby gives its unconditional consent to such assignment of payment to the beneficiary and authorizes the **City**, on its behalf, to take all necessary actions to implement such assignment of payment, including without limitation the execution of any instrument or documentation necessary to effectuate such assignment.

20.4.2 In the event that the amount otherwise due and owing to the **Contractor** by the **City** is insufficient to satisfy such demand, the **City** may, at its option, require payment from the **Contractor** of an amount sufficient to cover such demand and exercise any other right to require or recover payment which the **City** may have under **Law** or **Contract**.

20.4.3 In the event the **City** determines that the demand is invalid, any amount withheld pending the **City's** review of such demand shall be paid to the **Contractor**; provided, however, no lien has been filed. In the event a claim or an action has been filed, the terms and conditions set forth in Article 23 shall apply. In the event a lien has been filed, the parties will be governed by the provisions of the Lien Law of the State of New York.

20.5 The provisions of this Article 20 shall not prevent the **City** and the **Contractor** from resolving disputes in accordance with the **PPB**Rules, where applicable.

20.6 In the event the **City** determines that the beneficiary is entitled to payment pursuant to this Article 20, such determination and any defenses and counterclaims raised by the **Contractor** shall be taken into account in evaluating the **Contractor's** performance.

20.7 Nothing in this Article 20 shall relieve the **Contractor** of the obligation to pay the claims of all persons with valid and lawful claims against the **Contractor** relating to the **Work**.

20.8 The **Contractor** shall not require any performance, payment or other bonds of any Subcontractor if this **Contract** does not require such bonds of the **Contractor**.

20.9 The payment guarantee made pursuant to this Article 20 shall be construed in a manner consistent with Section 137 of the State Finance Law and shall afford to persons furnishing labor or materials to the **Contractor** or its **Subcontractors** in the prosecution of the **Work** under this **Contract** all of the rights and remedies afforded to such persons by such section, including but not limited to, the right to commence an action against the **City** on the payment guarantee provided by this Article 20 within the one-year limitations period set forth in Section 137(4)(b).

#### **ARTICLE 21. RETAINED PERCENTAGE**

- 21.1 If the Contractor is required to provide a 100% performance and payment security for a Job Order, then as further security for the faithful performance of the Job Order the Commissioner shall deduct, and retain until the substantial completion of the Work, five (5%) percent of the value of Work certified for payment in each partial payment voucher.
- 21.2 If the Contractor is not required to provide 100% performance and payment security, then as further security for the faithful performance of this Contract, the Commissioner shall deduct, and



retain until the substantial completion of the Work, ten (10%) percent of the value of Work certified for payment in each partial payment voucher.

## **ARTICLE 22. INSURANCE**

22.1 Types of Insurance: The Contractor shall procure and maintain the following types of insurance if, and as indicated, in Schedule A of the General Conditions (with the minimum limits and special conditions specified in Schedule A). Such insurance shall be maintained from the date the Contractor is required to provide Proof of Insurance pursuant to Article 22.3.1 through the date of completion of all required Work(including punch list work as certified in writing by the Resident Engineer), except for insurance required pursuant to Article 22.1.4, which may terminate upon Final Acceptance of all Job Orders awarded under this Contract. All insurance shall meet the requirements set forth in this Article 22. Wherever this Article requires that insurance coverage be "at least as broad" as a specified form (including all ISO forms), there is no obligation that the form itself be used, provided that the Contractor can demonstrate that the alternative form or endorsement contained in its policy provides coverage at least as broad as the specified form.

22.1.1 Commercial General Liability Insurance: The **Contractor** shall provide Commercial General Liability Insurance covering claims for property damage and/or bodily injury, including death, which may arise from any of the operations under this **Contract**. Coverage under this insurance shall be at least as broad as that provided by the latest edition of Insurance Services Office ("ISO") Form CG 0001. Such insurance shall be "occurrence" based rather than "claims-made" and include, without limitation, the following types of coverage: premises operations; products and completed operations; contractual liability (including the tort liability of another assumed in a contract); broad form property damage; independent contractors; explosion, collapse and underground (XCU); construction means and methods; and incidental malpractice. Such insurance shall contain a "per project" aggregate limit, as specified in Schedule A, that applies separately to operations under this **Contract**.

22.1.1(a) Such Commercial General Liability Insurance shall name the City as an Additional Insured. Coverage for the City shall specifically include the City's officials and employees, be at least as broad as the latest edition of ISO Form CG 20 10 and provide completed operations coverage at least as broad as the latest edition of ISO Form CG 20 37.

22.1.1(b) Such Commercial General Liability Insurance shall name all other entities designated as additional insureds in Schedule A but only for claims arising from the **Contractor's** operations under this **Contract**, with coverage at least as broad as the latest edition of ISO Form CG 20 26.

22.1.1(c) If the Work requires a permit from the Department of Buildings pursuant to 1RCNY Section 101-08, at <u>http://www.nyc.gov/html/dob/downloads/rules/1\_RCNY\_101-08.pdf</u>, the **Contractor** shall provide Commercial General Liability Insurance with limits of at least those required by 1 RCNY section 101-08. If the Work does not require such a permit, the minimum limits shall be those provided for in Schedule A.

22.1.1(d) If any of the Work includes repair of a waterborne vessel owned by or to be delivered to the City, such Commercial General Liability shall include, or be endorsed to include, Ship Repairer's Legal Liability Coverage to protect against,

without limitation, liability arising from navigation of such vessels prior to delivery to and acceptance by the **City**.

22.1.2 Workers' Compensation Insurance, Employers' Liability Insurance, and Disability Benefits Insurance: The **Contractor** shall provide, and shall cause its **Subcontractors** to provide, Workers Compensation Insurance, Employers' Liability Insurance, and Disability Benefits Insurance in accordance with the **Laws** of the State of New York on behalf of all employees providing services under this **Contract**(except for those employees, if any, for which the **Laws** require insurance only pursuant to Article 22.1.3).

22.1.3 United States Longshoremen's and Harbor Workers Act and/or Jones Act Insurance: If specified in Schedule A of the General Conditions or if required by Law, the Contractor shall provide insurance in accordance with the United States Longshoremen's and Harbor Workers Act and/or the Jones Act, on behalf of all qualifying employees providing services under this Contract.

22.1.4 Builders Risk Insurance: If specified in Schedule A of the General Conditions or a Detailed Scope of Work, the **Contractor** shall provide Builders Risk Insurance on a completed value form for the total value of the **Work** through Final Acceptance of the **Work** in its entirety. Such insurance shall be provided on an All Risk basis and include coverage, without limitation, for windstorm (including named windstorm), storm surge, flood and earth movement. Unless waived by the **Commissioner**, it shall include coverage for ordinance and law, demolition and increased costs of construction, debris removal, pollutant clean up and removal, and expediting costs. Such insurance shall cover, without limitation, (a) all buildings and/or structures involved in the **Work**, as well as temporary structures at the **Site**, and (b) any property that is intended to become a permanent part of such building or structure, whether such property is on the **Site**, in transit or in temporary storage. Policies shall name the **Contractor** as Named Insured and list the **City** as both an Additional Insured and a Loss Payee as its interest may appear.

22.1.4(a) Policies of such insurance shall specify that, in the event a loss occurs at an occupied facility, occupancy of such facility is permitted without the consent of the issuing insurance company.

22.1.4(b) Such insurance may be provided through an Installation Floater, at the **Contractor's** option, if it otherwise conforms with the requirements of this Article 22.1.4.

22.1.5 Commercial Automobile Liability Insurance: The **Contractor** shall provide Commercial Automobile Liability Insurance for liability arising out of ownership, maintenance or use of any owned (if any), non-owned and hired vehicles to be used in connection with this **Contract**. Coverage shall be at least as broad as the latest edition of ISO Form CA0001. If vehicles are used for transporting hazardous materials, the Automobile Liability Insurance shall be endorsed to provide pollution liability broadened coverage for covered vehicles (endorsement CA 99 48) as well as proof of MCS 90.

22.1.6 **Contractors** Pollution Liability Insurance: If specified in Schedule A of the General Conditions or a Detailed Scope of Work, the **Contractor** shall maintain, or cause the **Subcontractor** doing such **Work** to maintain, **Contractors** Pollution Liability Insurance covering bodily injury and property damage. Such insurance shall provide



coverage for actual, alleged or threatened emission, discharge, dispersal, seepage, release or escape of pollutants (including asbestos), including any loss, cost or expense incurred as a result of any cleanup of pollutants (including asbestos) or in the investigation, settlement or defense of any claim, action, or proceedings arising from the operations under this **Contract**. Such insurance shall be in the **Contractor's** name and list the **City** as an Additional Insured and any other entity specified in Schedule A. Coverage shall include, without limitation, (a) loss of use of damaged property or of property that has not been physically injured, (b) transportation, and (c) non-owned disposal sites.

22.1.6(a) Coverage for the **City** as Additional Insured shall specifically include the **City's** officials and employees and be at least as broad as provided to the **Contractor** for this **Project**.

22.1.6(b) If such insurance is written on a claims-made policy, such policy shall have a retroactive date on or before the effective date of this **Contract**, and continuous coverage shall be maintained, or an extended discovery period exercised, for a period of not less than three (3) years from the time the **Work** under this **Contract** is completed.

## 22.1.7 Marine Insurance:

22.1.7(a) Marine Protection and Indemnity Insurance: If specified in Schedule A of the General Conditions or if the **Contractor** engages in marine operations in the execution of any part of the **Work**, the **Contractor** shall maintain, or cause the **Subcontractor** doing such **Work** to maintain, Marine Protection and Indemnity Insurance with coverage at least as broad as Form SP-23. The insurance shall provide coverage for the **Contractor** or**Subcontractor** (whichever is doing this **Work**) and for the **City** (together with its officials and employees) and any other entity specified in Schedule A as an Additional Insured for bodily injury and property damage arising from marine operations under this **Contract**. Coverage shall include, without limitation, injury or death of crew members (if not fully provided through other insurance), removal of wreck, damage to piers, wharves and other fixed or floating objects and loss of or damage to any other vessel or craft, or to property on such other vessel or craft.

22.1.7(b) Hull and Machinery Insurance: If specified in Schedule A of the General Conditions or if the **Contractor** engages in marine operations in the execution of any part of the **Work**, the **Contractor** shall maintain, or cause the **Subcontractor** doing such **Work** to maintain, Hull and Machinery Insurance with coverage for the **Contractor** or **Subcontractor** (whichever is doing this **Work**) and for the **City** (together with its officials and employees) as Additional Insured at least as broad as the latest edition of American Institute Tug Form for all tugs used under this **Contract** and Collision Liability at least as broad as the latest edition of American Institute Hull Clauses.

22.1.7(c) Marine Pollution Liability Insurance: If specified in Schedule A of the General Conditions or if the **Contractor** engages in marine operations in the execution of any part of the **Work**, the **Contractor** shallmaintain, or cause the **Subcontractor** doing such **Work** to maintain, Marine Pollution Liability Insurance covering itself (or the Subcontractor doing such **Work**) as Named Insured and the



**City** (together with its officials and employees) and any other entity specified in Schedule A as an Additional Insured. Coverage shall be at least as broad as that provided by the latest edition of Water Quality Insurance Syndicate Form and include, without limitation, liability arising from the discharge or substantial threat of a discharge of oil, or from the release or threatened release of a hazardous substance including injury to, or economic losses resulting from, the destruction of or damage to real property, personal property or natural resources.

22.1.8 The **Contractor** shall provide such other types of insurance, at such minimum limits and with such conditions, as are specified in Schedule A of the General Conditions and/or a Detailed Scope of Work.

22.1.9 Installation Floater: The Contractor shall provide an Installation Floater policy covering materials, machinery and equipment during transit, installation and testing at the project sites with limits of not less than \$300,000.00 per location

22.2 General Requirements for Insurance Coverage and Policies:

22.2.1 All required insurance policies shall be maintained with companies that may lawfully issue the required policy and have an A.M. Best rating of at least A-/VII or a Standard and Poor's rating of at least A, unless prior written approval is obtained from the **City** Corporation Counsel.

22.2.2 The **Contractor** shall be solely responsible for the payment of all premiums for all required policies and all deductibles and self-insured retentions to which such policies are subject, whether or not the **City** is an insured under the policy.

22.2.3 In his/her sole discretion, the **Commissioner** may, subject to the approval of the **Comptroller** and the **City** Corporation Counsel, accept Letters of Credit and/or custodial accounts in lieu of required insurance.

22.2.4 The **City's** limits of coverage for all types of insurance required pursuant to Schedule A of the General Conditions shall be the greater of (i) the minimum limits set forth in Schedule A or (ii) the limits provided to the **Contractor** as Named Insured under all primary, excess, and umbrella policies of that type of coverage.

22.2.5 The **Contractor** may satisfy its insurance obligations under this Article 22 through primary policies or a combination of primary and excess/umbrella policies, so long as all policies provide the scope of coverage required herein.

22.2.6 Policies of insurance provided pursuant to this Article 22 shall be primary and non-contributing to any insurance or self-insurance maintained by the **City**.

#### 22.3 Proof of Insurance:

22.3.1 For all types of insurance required by Article 22.1 and Schedule A, except for insurance required by Articles 22.1.4 and 22.1.7,the **Contractor** shall file proof of insurance in accordance with this Article 22.3 within ten (10) **Days** of award. For insurance provided pursuant to Articles 22.1.4 and 22.1.7, proof shall be filed by a date



specified by the **Commissioner** or ten (10) **Days** prior to the commencement of the portion of the **Work** covered by such policy, whichever is earlier.

22.3.2For Workers' Compensation Insurance provided pursuant to Article 22.1.2, the **Contractor** shall submit one of the following forms: C-105.2 Certificate of Workers' Compensation Insurance; U-26.3 - State Insurance Fund Certificate of Workers' Compensation Insurance; Request for WC/DB Exemption (Form CE-200); equivalent or successor forms used by the New York State Workers' Compensation Board; or other proof of insurance in a form acceptable to the **Commissioner**. For Disability Benefits Insurance provided pursuant to Article 22.1.2, the **Contractor** shall submit DB-120.1 - Certificate Of Insurance Coverage Under The NYS Disability Benefits Law, Request for WC/DB Exemption (Form CE-200); equivalent or successor forms used by the New York State Workers' Compensation Board; or other provided pursuant to Article 22.1.2, the **Contractor** shall submit DB-120.1 - Certificate Of Insurance Coverage Under The NYS Disability Benefits Law, Request for WC/DB Exemption (Form CE-200); equivalent or successor forms used by the New York State Workers' Compensation Board; or other proof of insurance in a form Acceptable to the commissioner. For Disability Benefits Law, Request for WC/DB Exemption (Form CE-200); equivalent or successor forms used by the New York State Workers' Compensation Board; or other proof of insurance in a form acceptable to the **Commissioner**. ACORD forms are not acceptable.

22.3.3For policies provided pursuant to all of Article 22.1 other than Article 22.1.2, the Contractor shall submit one or more Certificates of Insurance on forms acceptable to the Commissioner. All such Certificates of Insurance shall certify (a) the issuance and effectiveness of such policies of insurance, each with the specified minimum limits (b) for insurance secured pursuant to Article 22.1.1 that the City and any other entity specified in Schedule A is an Additional Insured with coverage at least as broad as the most recent edition of ISO Forms CG 20 10, CG 20 37, and CG 20 26, as applicable; (c) in the event insurance is required pursuant to Article 22.1.6 and/or Article 22.1.7, that the City is an Additional Insured thereunder; (d) the company code issued to the insurance company by the National Association of Insurance Commissioners (the NAIC number); and (e) the number assigned to the Contract by the City. All such Certificates of Insurance shall be accompanied by either a duly executed "Certification by Broker" in the form contained in Part III of Schedule A or copies of all policies referenced in such Certificate of Insurance as certified by an authorized representative of the issuing insurance carrier. If any policy is not available at the time of submission, certified binders may be submitted until such time as the policy is available, at which time a certified copy of the policy shall be submitted.

22.3.4 Documentation confirming renewals of insurance shall be submitted to the **Commissioner** prior to the expiration date of coverage of policies required under this **Contract**. Such proofs of insurance shall comply with the requirements of Articles 22.3.2 and 22.3.3.

22.3.5 The **Contractor** shall be obligated to provide the City with a copy of any policy of insurance provided pursuant to this Article 22 upon the demand for such policy by the **Commissioner** or the **City** Corporation Counsel.

## 22.4 Operations of the Contractor:

22.4.1 The **Contractor** shall not commence the **Work** unless and until all required certificates have been submitted to and accepted by the **Commissioner**. Acceptance by the **Commissioner** of a certificate does not excuse the **Contractor** from securing insurance consistent with all provisions of this Article 22 or of any liability arising from its failure to do so.

22.4.2 The **Contractor** shall be responsible for providing continuous insurance coverage in the manner, form, and limits required by this **Contract** and shall be authorized to perform **Work** only during the effective period of all required coverage.

22.4.3 In the event that any of the required insurance policies lapse, are revoked, suspended or otherwise terminated, for whatever cause, the **Contractor** shall immediately stop all **Work**, and shall not recommence **Work** until authorized in writing to do so by the **Commissioner**. Upon quitting the **Site**, except as otherwise directed by the **Commissioner**, the **Contractor** shall leave all plant, materials, equipment, tools, and supplies on the Site. **Contract** time shall continue to run during such periods and no extensions of time will be granted. The **Commissioner** may also declare the **Contractor** in default for failure to maintain required insurance.

22.4.4 In the event the **Contractor** receives notice, from an insurance company or other person, that any insurance policy required under this Article 22 shall be cancelled or terminated (or has been cancelled or terminated) for any reason, the **Contractor** shall immediately forward a copy of such notice to both the **Commissioner** and the New York City Comptroller, attn: Office of Contract Administration, Municipal Building, One Centre Street, room 1005, New York, New York 10007. Notwithstanding the foregoing, the **Contractor** shall ensure that there is no interruption in any of the insurance coverage required under this Article 22.

22.4.5 Where notice of loss, damage, occurrence, accident, claim or suit is required under an insurance policy maintained in accordance with this Article 22, the **Contractor** shall notify in writing all insurance carriers that issued potentially responsive policies of any such event relating to any operations under this **Contract** (including notice to Commercial General Liability insurance carriers for events relating to the **Contractor's** own employees) no later than 20 days after such event. For any policy where the **City** is an Additional Insured, such notice shall expressly specify that "this notice is being given on behalf of the City of New York as Insured as well as the Named Insured." Such notice shall also contain the following information: the number of the insurance policy, the name of the named insured, the date and location of the damage, occurrence, or accident, and the identity of the persons or things injured, damaged or lost. The **Contractor** shall simultaneously send a copy of such notice to the City of New York c/o Insurance Claims Specialist, Affirmative Litigation Division, New York City Law Department, 100 Church Street, New York, New York 10007.

22.4.6 In the event of any loss, accident, claim, action, or other event that does or can give rise to a claim under any insurance policy required under this Article 22, the **Contractor** shall at all times fully cooperate with the **City** with regard to such potential or actual claim.

22.5 Subcontractor Insurance: In the event the Contractor requires any Subcontractor to procure insurance with regard to any operations under this Contract and requires such Subcontractor to name the Contractor as an Additional Insured thereunder, the Contractor shall ensure that the Subcontractor name the City, including its officials and employees, as an Additional Insured with coverage at least as broad as the most recent edition of ISO Form CG 20 26.

22.6 Wherever reference is made in Article 7 or this Article 22 to documents to be sent to the **Commissioner** (e.g., notices, filings, or submissions), such documents shall be sent to the address set



forth in Schedule A of the General Conditions. In the event no address is set forth in Schedule A, such documents are to be sent to the **Commissioner's** address as provided elsewhere in this Contract.

22.7 Apart from damages or losses covered by insurance provided pursuant to Articles 22.1.2, 22.1.3, or 22.1.5, the **Contractor** waives all rights against the **City**, including its officials and employees, for any damages or losses that are covered under any insurance required under this Article 22 (whether or not such insurance is actually procured or claims are paid thereunder) or any other insurance applicable to the operations of the **Contractor** and/or its employees, agents, or **Subcontractors**.

22.8 In the event the **Contractor** utilizes a self-insurance program to satisfy any of the requirements of this Article 22, the **Contractor** shall ensure that any such self-insurance program provides the **City** with all rights that would be provided by traditional insurance under this Article 22, including but not limited to the defense and indemnification obligations that insurers are required to undertake in liability policies.

22.9 Materiality/Non-Waiver: The **Contractor's** failure to secure policies in complete conformity with this Article 22, or to give an insurance company timely notice of any sort required in this **Contract** or to do anything else required by this Article 22 shall constitute a material breach of this **Contract**. Such breach shall not be waived or otherwise excused by any action or inaction by the **City** at any time.

22.10 Pursuant to General Municipal Law Section 108, this **Contract** shall be void and of no effect unless **Contractor** maintains Workers' Compensation Insurance for the term of this **Contract** to the extent required and in compliance with the New York State Workers' Compensation Law.

22.11 Other Remedies: Insurance coverage provided pursuant to this Article 22 or otherwise shall not relieve the **Contractor** of any liability under this **Contract**, nor shall it preclude the **City** from exercising any rights or taking such other actions available to it under any other provisions of this **Contract** or **Law**.

## ARTICLE 23. MONEY RETAINED AGAINST CLAIMS

23.1 If any claim shall be made by any person or entity (including **Other Contractors** with the **City** on this **Project**) against the **City** or against the **Contractor** and the **City** for any of the following:

(a) An alleged loss, damage, injury, theft or vandalism of any of the kinds referred to in Articles 7 and 12, plus the reasonable costs of defending the **City**, which in the opinion of the **Comptroller** may not be paid by an insurance company (for any reason whatsoever); or

(b) An infringement of copyrights, patents or use of patented articles, tools, etc., as referred to in Article 57; or

(c) Damage claimed to have been caused directly or indirectly by the failure of the **Contractor** to perform the **Work** in strict accordance with this **Contract**,

the amount of such claim, or so much thereof as the **Comptroller** may deem necessary, may be withheld by the **Comptroller**, as security against such claim, from any money due hereunder. The **Comptroller**, in his/her discretion, may permit the **Contractor** to substitute other satisfactory security in lieu of the monies so withheld.





NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

23.2 If an action on such claim is timely commenced and the liability of the **City**, or the **Contractor**, or both, shall have been established therein by a final judgment of a court of competent jurisdiction, or if such claim shall have been admitted by the **Contractor** to be valid, the **Comptroller** shall pay such judgment or admitted claim out of the monies retained by the **Comptroller** under the provisions of this Article 23, and return the balance, if any, without interest, to the **Contractor**.

## ARTICLE 24. MAINTENANCE AND GUARANTY

24.1 The **Contractor** shall promptly repair, replace, restore or rebuild, as the **Commissioner** may determine, any finished **Work** in which defects of materials or workmanship may appear or to which damage may occur because of such defects, during the one (1) year period subsequent to the date of **Final** Acceptance of the Job Order(or use and occupancy in accordance with Article 16), except where other periods of maintenance and guaranty are provided for in Schedule A.

24.2 As security for the faithful performance of its obligations hereunder, the **Contractor**, upon filing its requisition for **final** payment for a **Job Order**, shall deposit with the **Commissioner** a sum equal to one (1%) percent of the **Job Order** value in cash or certified check upon a state or national bank and trust company or a check of such bank and trust company signed by a duly authorized officer thereof and drawn to the order of the **Comptroller**, or obligations of the **City**, which the **Comptroller** may approve as of equal value with the sum so required.

24.3 In lieu of the above, the **Contractor** may make such security payment to the **City** by authorizing the **Commissioner** in writing to deduct the amount from the final payment for a **Job Order** which shall be deemed the deposit required above.

24.4 If the Contractor has faithfully performed all of its obligations hereunder the Commissioner shall so certify to the Comptroller within five (5) Days after the expiration of one (1) year from the date of Final Acceptance of the JobOrder or within thirty (30) Days after the expiration of the guarantee period fixed in the Specifications. The security payment shall be repaid to the Contractor without interest within thirty (30) Days after certification by the Commissioner to the Comptroller that the Contractor has faithfully performed all of its obligations in connection with such Job Order.

24.5 Notice by the **Commissioner** to the **Contractor** to repair, replace, rebuild or restore such defective or damaged **Work** shall be timely, pursuant to this article, if given not later than ten (10) **Days** subsequent to the expiration of the one (1) year period or other periods provided for herein.

24.6 If the **Contractor** shall fail to repair, replace, rebuild or restore such defective or damaged **Work** promptly after receiving such notice, the **Commissioner** shall have the right to have the **Work** done by others in the same manner as provided for in the completion of a defaulted **Contract**, under Article 51.

24.7 If the security payment so deposited is insufficient to cover the cost of such Work, the **Contractor** shall be liable to pay such deficiency on demand by the **Commissioner**.

24.8 The **Engineer's** certificate setting forth the fair and reasonable cost of repairing, replacing, rebuilding or restoring any damaged or defective **Work** when performed by one other than the **Contractor**, shall be binding and conclusive upon the **Contractor** as to the amount thereof.



24.9 The Contractor shall obtain all manufacturers' warranties and guaranties of all equipment and materials required by a Detailed Scope of Work or the Specifications in the name of the City and shall deliver same to the Commissioner. All of the City's rights and title and interest in and to said manufacturers' warranties and guaranties may be assigned by the City to any subsequent purchasers of such equipment and materials or lessees of the premises into which the equipment and materials have been installed.

## CHAPTER VI CHANGES, EXTRA WORK, AND DOCUMENTATION OF CLAIM

#### **ARTICLE 25. CHANGES TO THE CONTRACT**

25.1 Changes may be made to this **Contract** only as duly authorized in writing by the **Commissioner** in accordance with the **Law** andthis **Contract**. All such changes, modifications, and amendments will become a part of the **Contract**. Work so ordered shall be performed by the **Contractor**.

25.2 Contract changes will be made only for Work necessary to complete the Work included in the original scope of the Contract and/or for non-material changes to the scope of the Contract. Changes are not permitted for any material alteration in the scope of Work in the Contract.

25.3 The **Contractor** shall be entitled to a subsequent **Job Order** for **Extra Work**. All **Extra Work** shall be paid for at the unit prices set forth in the Construction Task Catalog or as Non-Prepriced Tasks in accordance with the procedure for developing a **Job Order**. Credits for deleted work shall be priced in the same manner.

25.4 All payments for change orders are subject to pre-audit by the **Engineering Audit Officer** and may be post-audited by the **Comptroller** and/or the **Agency**.

#### **ARTICLE 25A. CHANGES TO A JOB ORDER**

25A.1 The Department may make alterations, deletions or additions to any Job Order and Detailed Scope of Work. Such changes shall be priced in accordance with the procedure for developing a Job Order.

25A.2 The **Contractor** shall be entitled to a Supplemental Job Order for **Extra Work**. All **Extra Work** shall be paid for at the unit prices set forth in the Unit Price Book or as Non-Prepriced Tasks in accordance with the procedure for developing a **Job Order**. Credits for deleted work shall be priced in the same manner.

#### **ARTICLE 26.**

#### NOT USED

# ARTICLE 27. RESOLUTION OF DISPUTES

27.1 All disputes between the **City** and the **Contractor** of the kind delineated in this Article 27.1 that arise under, or by virtue of, this **Contract** shall be finally resolved in accordance with the provisions of this Article 27 and the **PPB** Rules. This procedure for resolving all disputes of the kind delineated herein shall be the exclusive means of resolving any such disputes.

27.1.1 This Article 27 shall not apply to disputes concerning matters dealt with in other sections of the **PPB**Rules, or to disputes involving patents, copyrights, trademarks, or trade secrets (as interpreted by the courts of New York State) relating to proprietary rights in computer software.

27.1.2 This Article 27 shall apply only to disputes about the scope of Work delineated by the Contract, the interpretation of Contract documents, the amount to be paid for Extra Work or disputed work performed in connection with the Contract, the conformity of the Contractor's Work to the Contract, and the acceptability and quality of the Contractor's Work; such disputes arise when the Engineer, ResidentEngineer, Engineering Audit Officer, or other designee of the Commissioner makes a determination with which the Contractor disagrees.

27.2 All determinations required by this Article 27 shall be made in writing clearly stated, with a reasoned explanation for the determination based on the information and evidence presented to the party making the determination. Failure to make such determination within the time required by this Article 27 shall be deemed a non-determination without prejudice that will allow application to the next level.

27.3 During such time as any dispute is being presented, heard, and considered pursuant to this Article 27, the **Contract** terms shall remain in force and the **Contractor** shall continue to perform **Work** as directed by the **ACCO** or the **Engineer**. Failure of the **Contractor** to continue **Work** as directed shall constitute a waiver by the **Contractor** of its claim.

27.4 Presentation of Disputes to Commissioner.

Notice of Dispute and Agency Response. The Contractor shall present its dispute in writing ("Notice of Dispute") to the Commissioner within thirty (30) Days of receiving written notice of the determination or action that is the subject of the dispute. This notice requirement shall not be read to replace any other notice requirements contained in the Contract. The Notice of Dispute shall include all the facts, evidence, documents, or other basis upon which the Contractor relies in support of its position, as well as a detailed computation demonstrating how any amount of money claimed by the Contractor in the dispute was arrived at. Within thirty (30) Days after receipt of the detailed written submission comprising the complete Notice of Dispute, the Engineer, ResidentEngineer, EngineeringAudit Officer, or other designee of the Commissioner shall submit to the Commissioner all materials he or she deems pertinent to the dispute. Following initial submissions to the Commissioner, either party may demand of the other the production of any document or other material the demanding party believes may be relevant to the dispute. The requested party shall produce all relevant materials that are not otherwise protected by a legal privilege recognized by the courts of New York State. Any question of relevancy shall be determined by the Commissioner whose decision shall be final. Willful failure of the Contractor to produce any requested material whose relevancy the Contractor has not disputed, or whose relevancy has been affirmatively determined, shall constitute a waiver by the Contractor of its claim.



27.4.1 Commissioner Inquiry. The Commissioner shall examine the material and may, in his or her discretion, convene an informal conference with the Contractor, the ACCO, and the Engineer, ResidentEngineer, Engineering Audit Officer, or other designee of the Commissioner toresolve the issue by mutual consent prior to reaching a determination. The Commissioner may seek such technical or other expertise as he or she shall deem appropriate, including the use of neutral mediators, and require any such additional material from either or both parties as he or she deems fit. The Commissioner's ability to render, and the effect of, a decision hereunder shall not be impaired by any negotiations in connection with the dispute presented, whether or not the Commissioner participated therein. The Commissioner may or, at the request of any party to the dispute, shall compel the participation of any Other Contractor with a contract related to the Work of this Contract, and that Contractor shall be bound by the decision of the Commissioner. Any Other Contractor thus brought into the dispute resolution proceeding shall have the same rights and obligations under this Article 27 as the Contractor initiating the dispute.

27.4.2 Commissioner Determination. Within thirty (30) Days after the receipt of all materials and information, or such longer time as may be agreed to by the parties, the Commissioner shall make his or her determination and shall deliver or send a copy of such determination to the Contractor, theACCO, and Engineer, Resident Engineer, Engineering Audit Officer, or other designee of the Commissioner, as applicable, together with a statement concerning how the decision may be appealed.

27.4.3 Finality of **Commissioner's** Decision. The **Commissioner's** decision shall be final and binding on all parties, unless presented to the Contract Dispute Resolution Board pursuant to this Article 27. The **City** may not take a petition to the Contract Dispute Resolution Board. However, should the **Contractor** take such a petition, the **City** may seek, and the Contract Dispute Resolution Board may render, a determination less favorable to the **Contractor** and more favorable to the **City** than the decision of the **Commissioner**.

27.5 Presentation of Dispute to the **Comptroller**. Before any dispute may be brought by the **Contractor** to the Contract Dispute Resolution Board, the **Contractor** must first present its claim to the **Comptroller** for his or her review, investigation, and possible adjustment.

27.5.1 Time, Form, and Content of Notice. Within thirty (30) **Days** of its receipt of a decision by the **Commissioner**, the **Contractor** shall submit to the **Comptroller** and to the **Commissioner** a Notice of Claim regarding its dispute with the **Agency**. The Notice of Claim shall consist of (i) a brief written statement of the substance of the dispute, the amount of money, if any, claimed and the reason(s) the **Contractor** contends the dispute was wrongly decided by the **Commissioner**; (ii) a copy of the written decision of the **Commissioner**; and (iii) a copy of all materials submitted by the **Contractor** to the **Agency**, including the Notice of Dispute. The **Contractor** may not present to the **Comptroller** any material not presented to the **Commissioner**, except at the request of the **Comptroller**.

27.5.2 Response. Within thirty (30) **Days** of receipt of the Notice of Claim, the **Agency** shall make available to the **Comptroller** a copy of all material submitted by the **Agency** to the **Commissioner** in connection with the dispute. The **Agency** may not present to the **Comptroller** any material not presented to the **Commissioner** except at the request of the **Comptroller**.

27.5.3 **Comptroller** Investigation. The **Comptroller** may investigate the claim in dispute and, in the course of such investigation, may exercise all powers provided in Sections 7-201 and 7-203



of the Administrative Code. In addition, the **Comptroller** may demand of either party, and such party shall provide, whatever additional material the **Comptroller** deems pertinent to the claim, including original business records of the **Contractor**. Willful failure of the **Contractor** to produce within fifteen (15) **Days** any material requested by the **Comptroller** shall constitute a waiver by the **Contractor** of its claim. The **Comptroller** may also schedule an informal conference to be attended by the **Contractor**, Agency representatives, and any other personnel desired by the **Comptroller**.

27.5.4 Opportunity of **Comptroller** to Compromise or Adjust Claim. The **Comptroller**shall have forty-five (45) **Days** from his or her receipt of all materials referred to in Article 27.5.3 to investigate the disputed claim. The period for investigation and compromise may be further extended by agreement between the **Contractor** and the **Comptroller**, to a maximum of ninety (90) **Days** from the **Comptroller's** receipt of all materials. The **Contractor** may not present its petition to the Contract Dispute Resolution Board until the period for investigation and compromise delineated in this Article 27.5.4 has expired. In compromising or adjusting any claim hereunder, the **Comptroller** may not revise or disregard the terms of the **Contract** between the parties.

27.6 Contract Dispute Resolution Board. There shall be a Contract Dispute Resolution Board composed of:

27.6.1 The chief administrative law judge of the Office of Administrative Trials and Hearings (OATH) or his/her designated OATH administrative law judge, who shall act as chairperson, and may adopt operational procedures and issue such orders consistent with this Article 27 as may be necessary in the execution of the Contract Dispute Resolution Board's functions, including, but not limited to, granting extensions of time to present or respond to submissions;

27.6.2 The **CCPO** or his/her designee; any designee shall have the requisite background to consider and resolve the merits of the dispute and shall not have participated personally and substantially in the particular matter that is the subject of the dispute or report to anyone who so participated; and

27.6.3 A person with appropriate expertise who is not an employee of the City. This person shall be selected by the presiding administrative law judge from a prequalified panel of individuals, established and administered by OATH with appropriate background to act as decision-makers in a dispute. Such individual may not have a contract or dispute with the City or be an officer or employee of any company or organization that does, or regularly represents persons, companies, or organizations having disputes with the City.

27.7 Petition to the Contract Dispute Resolution Board. In the event the claim has not been settled or adjusted by the **Comptroller** within the period provided in this Article 27, the **Contractor**, within thirty (30) **Days** thereafter, may petition the Contract Dispute Resolution Board to review the **Commissioner's** determination.

.7.1 Form and Content of Petition by **Contractor**. The **Contractor** shall present its dispute to the Contract Dispute Resolution Board in the form of a petition, which shall include (i) a brief written statement of the substance of the dispute, the amount of money, if any, claimed, and the reason(s) the **Contractor** contends the dispute was wrongly decided by the **Commissioner**; (ii) a copy of the written Decision of the **Commissioner**, (iii) copies of all materials submitted by the NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

**Contractor** to the Agency; (iv) a copy of the written decision of the **Comptroller**, if any, and (v) copies of all correspondence with, or written material submitted by the **Contractor**, to the **Comptroller**. The **Contractor** shall concurrently submit four (4) complete sets of the Petition: one set to the **City**CorporationCounsel (Attn: Commercial and Real Estate Litigation Division) and three (3) sets to the Contract Dispute Resolution Board at OATH's offices with proof of service on the City Corporation Counsel. In addition, the **Contractor** shall submit a copy of the written statement of the substance of the dispute, cited in (i) above, to both the **Commissioner** and the **Comptroller**.

27.7.2Agency Response. Within thirty (30) Days of its receipt of the Petition by the City Corporation Counsel, the Agency shall respond to the brief written statement of the Contractor and make available to the Contract Dispute Resolution Board all material it submitted to the Commissioner and Comptroller. Three (3) complete copies of the Agency response shall be provided to the Contract Dispute Resolution Board and one to the Contractor. Extensions of time for submittal of the Agency response shall be given as necessary upon a showing of good cause or, upon consent of the parties, for an initial period of up to thirty (30) Days.

- 27.7.3 Further Proceedings. The Contract Dispute Resolution Board shall permit the **Contractor** to present its case by submission of memoranda, briefs, and oral argument. The Contract Dispute Resolution Board shall also permit the **Agency** to present its case in response to the **Contractor** by submission of memoranda, briefs, and oral argument. If requested by the **City** Corporation Counsel, the **Comptroller** shall provide reasonable assistance in the preparation of the **Agency's** case. Neither the **Contractor** nor the **Agency** may support its case with any documentation or other material that was not considered by the **Comptroller**, unless requested by the Contract Dispute Resolution Board. The Contract Dispute Resolution Board, in its discretion, may seek such technical or other expert advice as it shall deem appropriate and may seek, on its own or upon application of a party, any such additional material from any party as it deems fit. The Contract Dispute Resolution Board, in its discretion, may combine more than one dispute between the parties for concurrent resolution.
- 27.7.4 Contract Dispute Resolution Board Determination. Within forty-five (45) **Days** of the conclusion of all written submissions and oral arguments, the Contract Dispute Resolution Board shall render a written decision resolving the dispute. In an unusually complex case, the Contract Dispute Resolution Board may render its decision in a longer period, not to exceed ninety (90) **Days**, and shall so advise the parties at the commencement of this period. The Contract Dispute Resolution Board's decision must be consistent with the terms of the **Contract**. Decisions of the Contract Dispute Resolution Board and shall not have precedential effect with respect to matters not before the Contract Dispute Resolution Board.

27.7.5 Notification of Contract Dispute Resolution Board Decision. The Contract Dispute Resolution Board shall send a copy of its decision to the **Contractor**, the **ACCO**, the **Engineer**, the **Comptroller**, the **City** Corporation Counsel, the **CCPO**, and the **PPB**. A decision in favor of the **Contractor** shall be subject to the prompt payment provisions of the **PPB**Rules. The Required Payment Date shall be thirty (30) **Days** after the date the parties are formally notified of the Contract Dispute Resolution Board's decision.

27.7.6 Finality of Contract Dispute Resolution Board Decision. The Contract Dispute Resolution Board's decision shall be final and binding on all parties. Any party may seek review of the Contract Dispute Resolution Board's decision solely in the form of a challenge, filed



within four (4) months of the date of the Contract Dispute Resolution Board's decision, in a court of competent jurisdiction of the State of New York, County of New York pursuant to Article 78 of the Civil Practice Law and Rules. Such review by the court shall be limited to the question of whether or not the Contract Dispute Resolution Board's decision was made in violation of lawful procedure, was affected by an error of Law, or was arbitrary and capricious or an abuse of discretion. No evidence or information shall be introduced or relied upon in such proceeding that was not presented to the Contract Dispute Resolution Board in accordance with this Article 27.

27.8 Any termination, cancellation, or alleged breach of the **Contract** prior to or during the pendency of any proceedings pursuant to this Article 27 shall not affect or impair the ability of the **Commissioner** or Contract Dispute Resolution Board to make a binding and final decision pursuant to this Article 27.

## ARTICLE 28. RECORD KEEPING FOR EXTRA OR DISPUTED WORK

28.1 While the **Contractor** or any of its **Subcontractors** is performing **Extra Work** or is performing disputed **Work**, or complying with a determination or order under protest in accordance with Articles 11, 27, and 30, in each such case the **Contractor** shall furnish the **Resident Engineer** daily with three (3) copies of written statements signed by the **Contractor's** representative at the **Site** showing:

28.1.1 The name, trade, and number of each worker employed on such **Work** or engaged in complying with such determination or order, the number of hours employed, and the character of the **Work** each is doing; and

28.1.2 The nature and quantity of any materials, plant and equipment furnished or used in connection with the performance of such **Work** or compliance with such determination or order, and from whom purchased or rented.

28.2 A copy of such statement will be countersigned by the **Resident Engineer**, noting thereon any items not agreed to or questioned, and will be returned to the **Contractor** within two (2) **Days** after submission.

28.3 The **Contractor** and its **Subcontractors**, when required by the **Commissioner**, or the **Comptroller**, shall also produce for inspection, at the office of the **Contractor** or **Subcontractor**, any and all of its books, bid documents, financial statements, vouchers, records, daily job diaries and reports, and cancelled checks, and any other documents relating to showing the nature and quantity of the labor, materials, plant and equipment actually used in the performance of such **Work**, or in complying with such determination or order, and the amounts expended therefor, and shall permit the **Commissioner** and the **Comptroller** to make such extracts there from, or copies thereof, as they or either of them may desire.

28.4 In connection with the examination provided for herein, the **Commissioner**, upon demand therefor, will produce for inspection by the **Contractor** such records as the **Agency** may have with respect to such **Extra Work** or disputed **Work** performed under protest pursuant to order of the **Commissioner**, except those records and reports which may have been prepared for the purpose of determining the accuracy and validity of the **Contractor's** claim.

28.5 Failure to comply strictly with these requirements shall constitute a waiver of any claim for extra compensation or damages on account of the performance of such **Work** or compliance with such determination or order.



## **ARTICLE 29. OMITTED WORK**

29.1 Not Used

29.2 Not Used

29.3 For units that have been ordered but are only partially completed, the unit price shall be reduced by a pro rata portion of the unit price bid based upon the percentage of **Work** omitted subject to Article 29.4.

29.4 In the event the **Contractor**, with respect to any omitted **Work**, has purchased any noncancelable material and/or equipment that is not capable of use except in the performance of this **Contract** and has been specifically fabricated for the sole purpose of this **Contract**, but not yet incorporated into the **Work**, the **Contractor** shall be paid for such material and/or equipment in accordance with Article 64.2.1(b); provided, however, such payment is contingent upon the **Contractor's** delivery of such material and/or equipment in acceptable condition to a location designated by the **City**.

29.5 The Contractor agrees to make no claim for damages or for loss of overhead and profit with regard to any omitted Work.

## ARTICLE 30. NOTICE AND DOCUMENTATION OF COSTS AND DAMAGES; PRODUCTION OF FINANCIAL RECORDS

30.1 If the **Contractor** shall claim to be sustaining damages by reason of any act or omission of the **City** or its agents, it shall submit to the **Commissioner** within forty-five (45) **Days** from the time such damages are first incurred, and every thirty (30) **Days** thereafter for as long as such damages are incurred, verified statements of the details and the amounts of such damages, together with documentary evidence of such damages. The **Contractor** may submit any of the above statements within such additional time as may be granted by the **Commissioner** in writing upon written request therefor. Failure of the **Commissioner** to respond in writing to a written request for additional time within thirty (30) **Days** shall be deemed a denial of the request. On failure of the **Contractor** to strictly comply with the foregoing provisions, such claims shall be deemed waived and no right to recover on such claims shall exist. Damages that the **Contractor** may claim in any action or dispute resolution procedure arising under or by reason of this **Contract** shall not be different from or in excess of the statements and documentation made pursuant to this Article 30.

30.2 In addition to the foregoing statements, the **Contractor** shall, upon notice from the **Commissioner**, produce for examination at the **Contractor's** office, by the **Engineer**, **Architect** or **Project Manager**, all of its books of account, bills, invoices, payrolls, subcontracts, time books, daily reports, bank deposit books, bank statements, check books, and cancelled checks, showing all of its acts and transactions in connection with or relating to or arising by reason of this **Contract**, and submit itself and persons in its employment, for examination under oath by any person designated by the **Commissioner** or **Comptroller** to investigate claims made or disputes against the **City** under this **Contract**. At such examination, a duly authorized representative of the **Contractor** may be present.

30.3 In addition to the statements required under Article 28 and this Article 30, the Contractor and/or its Subcontractor shall, within thirty (30) Days upon notice from the Commissioner or



**Comptroller**, produce for examination at the **Contractor's** and/or **Subcontractor's** office, by a representative of either the **Commissioner** or **Comptroller**, all of its books of account, bid documents, financial statements, accountant workpapers, bills, invoices, payrolls, subcontracts, time books, daily reports, bank deposit books, bank statements, check books, and cancelled checks, showing all of its acts and transactions in connection with or relating to or arising by reason of this **Contract**. Further, the **Contractor** and/or its **Subcontractor** shall submit any person in its employment, for examination under oath by any person designated by the **Commissioner** or **Comptroller** to investigate claims made or disputes against the **City** under this **Contract**. At such examination, a duly authorized representative of the **Contractor** may be present.

30.4 Unless the information and examination required under Article 30.3 is provided by the **Contractor** and/or its **Subcontractor** upon thirty (30) **Days'** notice from the **Commissioner** or **Comptroller**, or upon the **Commissioner's** or **Comptroller's** written authorization to extend the time to comply, the **City** shall be released from all claims arising under, relating to or by reason of this **Contract**, except for sums certified by the **Commissioner** to be due under the provisions of this **Contract**. It is further stipulated and agreed that no person has the power to waive any of the foregoing provisions and that in any action or dispute resolution procedure against the **City** to recover any sum in excess of the sums certified by the **Commissioner** to be due under or by reason of this **Contract**, the **Contractor** must allege in its complaint and prove, at trial or during such dispute resolution procedure, compliance with the provisions of this Article 30.

30.5 In addition, after the commencement of any action or dispute resolution procedure by the **Contractor** arising under or by reason of this **Contract**, the **City** shall have the right to require the **Contractor** to produce for examination under oath, up until the trial of the action or hearing before the Contract Dispute Resolution Board, the books and documents described in Article 30.3 and submit itself and all persons in its employ for examination under oath. If this Article 30 is not complied with as required, then the **Contractor** hereby consents to the dismissal of the action or dispute resolution procedure.

## CHAPTER VII POWERS OF THE RESIDENT ENGINEER, THE ENGINEER OR ARCHITECT AND THE COMMISSIONER

#### **ARTICLE 31. THE RESIDENT ENGINEER**

31.1 The **Resident Engineer** shall have the power to inspect, supervise, and control the performance of the Work, subject to review by the **Commissioner**. The **Resident Engineer** shall not, however, have the power to issue an **Extra Work** order, except as specifically designated in writing by the **Commissioner**.

# **ARTICLE 32. THE ENGINEER OR ARCHITECT OR PROJECT MANAGER**

32.1 The Engineer or Architect or Project Manager, in addition to those matters elsewhere herein delegated to the Engineer and expressly made subject to his/her determination, direction or approval, shall have the power, subject to review by the Commissioner:



32.1.1 To determine the amount, quality, and location of the Work to be paid for hereunder; and

32.1.2 To determine all questions in relation to the Work, to interpret the Job Order, Detailed Scope of Work, Drawings, Specifications, and Addenda, and to resolve all patent inconsistencies or ambiguities therein; and

32.1.3 To determine how the Work of this Contract shall be coordinated with Work of Other Contractors engaged simultaneously on this **Project**, including the power to suspend any part of the Work, but not the whole thereof; and

32.1.4 To make minor changes in the Work as he/she deems necessary, provided such changes do not result in a net change in the cost to the **City** or to the **Contractor** of the **Work** to be done under the **Contract**; and

32.1.5 To amplify the Job Order, Detailed Scope of Work, Drawings, add explanatory information and furnish additional Specifications and drawings, consistent with the Job Order.

32.2 The foregoing enumeration shall not imply any limitation upon the power of the Engineer or Architect or Project Manager, for it is the intent of this Contract that all of the Work shall generally be subject to his/her determination, direction, and approval, except where the determination, direction or approval of someone other than the Engineer or Architect or Project Manager is expressly called for herein.

32.3 The Engineer or Architect or Project Manager shall not, however, have the power to issue an Extra Work order, except as specifically designated in writing by the Commissioner.

## **ARTICLE 33. THE COMMISSIONER**

33.1 The **Commissioner**, in addition to those matters elsewhere herein expressly made subject to his/her determination, direction or approval, shall have the power:

33.1.1 To review and make determinations on any and all questions in relation to this **Contract** and its performance; and

33.1.2 To modify or change this **Contract** and/or **Job Order** so as to require the performance of **Extra Work**(subject, however, to the limitations specified in Article 25) or the omission of **Work**; and

33.1.3 To suspend the whole or any part or all **Job Orders** whenever in his/her judgment such suspension is required:

33.1.3(a) In the interest of the City generally; or

33.1.3(b) To coordinate the **Work** of the various contractors engaged on this **Project** pursuant to the provisions of Article 12; or





33.1.3(c) To expedite the completion of the entire **Project** even though the completion of this particular **Contract** may thereby be delayed.

## ARTICLE 34. NO ESTOPPEL

34.1 Neither the **City** nor any **Agency**, official, agent or employee thereof, shall be bound, precluded or estopped by any determination, decision, approval, order, letter, payment or certificate made or given under or in connection with this **Contract** by the **City**, the **Commissioner**, the **Engineer**, the **Resident Engineer**, or any other official, agent or employee of the **City**, either before or after the final completion and acceptance of the **Work** and payment therefor:

34.1.1 From showing the true and correct classification, amount, quality or character of the **Work** actually done; or that any such determination, decision, order, letter, payment or certificate was untrue, incorrect or improperly made in any particular, or that the **Work**, or any part thereof, does not in fact conform to the requirements of this **Contract**; and

34.1.2 From demanding and recovering from the **Contractor** any overpayment made to it, or such damages as the **City** may sustain by reason of the **Contractor's** failure to perform each and every part of its **Contract**.

## CHAPTER VIII LABOR PROVISIONS

#### ARTICLE 35. EMPLOYEES

#### 35.1 The **Contractor** and its **Subcontractors** shall not employ on the **Work**:

35.1.1 Anyone who is not competent, faithful and skilled in the Work for which he/she shall be employed; and whenever the **Commissioner** shall inform the **Contractor**, in writing, that any employee is, in his/her opinion, incompetent, unfaithful or disobedient, that employee shall be discharged from the **Work** forthwith, and shall not again be employed upon it; or

35.1.2 Any labor, materials or means whose employment, or utilization during the course of this **Contract**, may tend to or in any way cause or result in strikes, work stoppages, delays, suspension of **Work** or similar troubles by workers employed by the **Contractor** or its **Subcontractors**, or by any of the trades working in or about the buildings and premises where **Work** is being performed under this **Contract**, or by **Other Contractors** or their **Subcontractors** pursuant to other contracts, or on any other building or premises owned or operated by the **City**, its **Agencies**, departments, boards or authorities. Any violation by the **Contractor** of this requirement may, upon certification of the **Commissioner**, be considered as proper and sufficient cause for declaring the **Contractor** to be in default, and for the **City** to take action against it as set forth in Chapter X of this **Contract**, or such other article of this **Contract** as the **Commissioner** may deem proper; or

35.1.3 In accordance with Section 220.3-e of the Labor Law of the State of New York (hereinafter "Labor Law"), the **Contractor** and its **Subcontractors** shall not employ on the **Work** any apprentice, unless he/she is a registered individual, under a bona fide program registered with the New York State Department of Labor. The allowable ratio of apprentices to



journey-level workers in any craft classification shall not be greater than the ratio permitted to the **Contractor** as to its work force on any job under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered as above, shall be paid the wage rate determined by the **Comptroller** of the **City** for the classification of **Work** actually performed. The **Contractor** or **Subcontractor** will be required to furnish written evidence of the registration of its program and apprentices as well as all the appropriate ratios and wage rates, for the area of the construction prior to using any apprentices on the **Contract Work**.

35.2 If the total cost of the Work under this Contract is at least two hundred fifty thousand (\$250,000) dollars, all laborers, workers, and mechanics employed in the performance of the Contract on the public work site, either by the Contractor, Subcontractor or other person doing or contracting to do the whole or a part of the Work contemplated by the Contract, shall be certified prior to performing any Work as having successfully completed a course in construction safety and health approved by the United States Department of Labor's Occupational Safety and Health Administration that is at least ten (10) hours in duration.

35.3 In accordance with Local Law Nos. 30-2012 and 33-2012, codified at sections 6-132 and 12-113 of the Administrative Code, respectively,

35.3.1 The **Contractor** shall not take an adverse personnel action with respect to an officer or employee in retaliation for such officer or employee making a report of information concerning conduct which such officer or employee knows or reasonably believes to involve corruption, criminal activity, conflict of interest, gross mismanagement or abuse of authority by any officer or employee relating to this **Contract** to (a) the Commissioner of the Department of Investigation, (b) a member of the New York City Council, the Public Advocate, or the **Comptroller**, or (c) the **CCPO**, **ACCO**, **Agency** head, or **Commissioner**.

35.3.2 If any of the **Contractor's** officers or employees believes that he or she has been the subject of an adverse personnel action in violation of Article 35.3.1, he or she shall be entitled to bring a cause of action against the **Contractor** to recover all relief necessary to make him or her whole. Such relief may include but is not limited to: (a) an injunction to restrain continued retaliation, (b) reinstatement to the position such employee would have had but for the retaliation or to an equivalent position, (c) reinstatement of full fringe benefits and seniority rights, (d) payment of two times back pay, plus interest, and (e) compensation for any special damages sustained as a result of the retaliation, including litigation costs and reasonable attorney's fees.

35.3.3 The **Contractor** shall post a notice provided by the **City** in a prominent and accessible place on any site where work pursuant to the **Contract** is performed that contains information about:

35.3.3(a) how its employees can report to the New York City Department of Investigation allegations of fraud, false claims, criminality or corruption arising out of or in connection with the **Contract**; and

35.3.3(b)the rights and remedies afforded to its employees under Administrative Code sections 7-805 (the New York City False Claims Act) and 12-113 (the Whistleblower Protection Expansion Act) for lawful acts taken in



connection with the reporting of allegations of fraud, false claims, criminality or corruption in connection with the **Contract**.

35.3.4 For the purposes of this Article 35.3, "adverse personnel action" includes dismissal, demotion, suspension, disciplinary action, negative performance evaluation, any action resulting in loss of staff, office space, equipment or other benefit, failure to appoint, failure to promote, or any transfer or assignment or failure to transfer or assign against the wishes of the affected officer or employee.

35.3.5 This Article 35.3 is applicable to all of the **Contractor's Subcontractors** having subcontracts with a value in excess of \$100,000; accordingly, the **Contractor** shall include this rider in all subcontracts with a value a value in excess of \$100,000.

Article 35.3 is not applicable to this **Contract** if it is valued at \$100,000 or less. Articles 35.3.1, 35.3.2, 35.3.4, and 35.3.5 are not applicable to this **Contract** if it was solicited pursuant to a finding of an emergency.

## **ARTICLE 36. NO DISCRIMINATION**

36.1 The Contractor specifically agrees, as required by Labor Law Section 220-e, as amended, that:

36.1.1 In the hiring of employees for the performance of Work under this Contract or any subcontract hereunder, neither the Contractor, Subcontractor, nor any person acting on behalf of such Contractor or Subcontractor, shall by reason of race, creed, color or national origin discriminate against any citizen of the State of New York who is qualified and available to perform the Work to which the employment relates;

36.1.2 Neither the **Contractor**, **Subcontractor**, nor any person on its behalf shall, in any manner, discriminate against or intimidate any employee hired for the performance of **Work** under this **Contract** on account of race, creed, color or national origin;

36.1.3 There may be deducted from the amount payable to the **Contractor** by the **City** under this **Contract** a penalty of fifty (\$50.00) dollars for each person for each **Day** during which such person was discriminated against or intimidated in violation of the provisions of this **Contract**; and

36.1.4 This **Contract**, and any **Job Order** may be cancelled or terminated by the **City** and all moneys due or to become due hereunder may be forfeited, for a second or any subsequent violation of the terms or conditions of this Article 36.

36.1.5 This Article 36 covers all construction, alteration and repair of any public building or public work occurring in the State of New York and the manufacture, sale, and distribution of materials, equipment, and supplies to the extent that such operations are performed within the State of New York pursuant to this **Contract**.

36.2 The **Contractor** specifically agrees, as required by Section 6-108 of the Administrative Code, as amended, that:



36.2.1 It shall be unlawful for any person engaged in the construction, alteration or repair of buildings or engaged in the construction or repair of streets or highways pursuant to a **Contract** with the **City** or engaged in the manufacture, sale or distribution of materials, equipment or supplies pursuant to a **Contract** with the **City** to refuse to employ or to refuse to continue in any employment any person on account of the race, color or creed of such person.

36.2.2 It shall be unlawful for any person or any servant, agent or employee of any person, described in Article 36.1.2, to ask, indicate or transmit, orally or in writing, directly or indirectly, the race, color or creed or religious affiliation of any person employed or seeking employment from such person, firm or corporation.

36.2.3 Breach of the foregoing provisions shall be deemed a violation of a material provision of this **Contract**.

36.2.4 Any person, or the employee, manager or owner of or officer of such firm or corporation who shall violate any of the provisions of this Article 36.2 shall, upon conviction thereof, be punished by a fine of not more than one hundred (\$100.00) dollars or by imprisonment for not more than thirty (30) **Days**, or both.

36.3 This **Contract** is subject to the requirements of Executive Order No. 50 (1980) ("E.O. 50"), as revised, and the rules and regulations promulgated thereunder. No contract will be awarded unless and until these requirements have been complied with in their entirety. By signing this **Contract**, the **Contractor** agrees that it:

- 36.3.1 Will not engage in any unlawful discrimination against any employee or applicant for employment because of race, creed, color, national origin, sex, age, disability, marital status or sexual orientation with respect to all employment decisions including, but not limited to, recruitment, hiring, upgrading, demotion, downgrading, transfer, training, rates of pay or other forms of compensation, layoff, termination, and all other terms and conditions of employment; and
- 36.3.2 Will not engage in any unlawful discrimination in the selection of **Subcontractors** on the basis of the owner's race, color, creed, national origin, sex, age, disability, marital status or sexual orientation; and
- 36.3.3 Will state in all solicitations or advertisements for employees placed by or on behalf of the **Contractor** that all qualified applicants will receive consideration for employment without unlawful discrimination based on race, creed, color, national origin, sex, age, citizens status, disability, marital status, sexual orientation, or that it is an equal employment opportunity employer; and
- 36.3.4 Will send to each labor organization or representative of workers with which it has a collective bargaining agreement or other contract or memorandum of understanding, written notification of its equal employment opportunity commitments under E.O. 50 and the rules and regulations promulgated thereunder; and
- 36.3.5 Will furnish, before the award of the **Contract**, all information and reports, including an employment report, that are required by E.O. 50, the rules and regulations promulgated thereunder, and orders of the **City** Department of Business Services, Division of Labor



Services (**DLS**) and will permit access to its books, records, and accounts by the **DLS** for the purposes of investigation to ascertain compliance with such rules, regulations, and orders.

36.4 The **Contractor** understands that in the event of its noncompliance with the nondiscrimination clauses of this **Contract** or with any of such rules, regulations, or orders, such noncompliance shall constitute a material breach of this **Contract** and noncompliance with E.O. 50 and the rules and regulations promulgated thereunder. After a hearing held pursuant to the rules of the **DLS**, the Director of the **DLS** may direct the **Commissioner** to impose any or all of the following sanctions:

36.4.1 Disapproval of the Contractor; and/or

- 36.4.2 Suspension or termination of the Contract; and/or
- 36.4.3 Declaring the Contractor in default; and/or
- 36.4.4 In lieu of any of the foregoing sanctions, the Director of the **DLS** may impose an employment program.

In addition to any actions taken under this **Contract**, failure to comply with E.O. 50 and the rules and regulations promulgated thereunder, in one or more instances, may result in a **City Agency** declaring the **Contractor** to be non-responsible in future procurements. The **Contractor** further agrees that it will refrain from entering into any **Contract** or **Contract** modification subject to E.O. 50 and the rules and regulations promulgated thereunder with a **Subcontractor** who is not in compliance with the requirements of E.O. 50 and the rules and regulations promulgated thereunder.

36.5 The Contractor specifically agrees, as required by Section 6-123 of the Administrative Code, that:

36.5.1 The **Contractor** will not engage in any unlawful discriminatory practice in violation of Title 8 of the Administrative Code; and

36.5.2 Any failure to comply with this Article 36.5 may subject the **Contractor** to the remedies set forth in Section 6-123 of the Administrative Code, including, where appropriate, sanctions such as withholding of payment, imposition of an employment program, finding the **Contractor** to be in default, cancellation of the **Contract**, or any other sanction or remedy provided by **Law** or **Contract**.

## ARTICLE 37. LABOR LAW REQUIREMENTS

37.1 The **Contractor** shall strictly comply with all applicable provisions of the Labor Law, as amended. Such compliance is a material term of this **Contract**.

37.2 The **Contractor** specifically agrees, as required by Labor Law Sections 220 and 220-d, as amended, that:

37.2.1 Hours of Work: No laborer, worker, or mechanic in the employ of the **Contractor**, **Subcontractor** or other person doing or contracting to do the whole or a part of the **Work** contemplated by this **Contract** shall be permitted or required to work more than eight (8) hours in any one (1) **Day**, or more than five (5) **Days** in any one (1)



week, except as provided in the Labor Law and in cases of extraordinary emergency including fire, flood, or danger to life or property, or in the case of national emergency when so proclaimed by the President of the United States of America.

37.2.2 In situations in which there are not sufficient laborers, workers, and mechanics who may be employed to carry on expeditiously the Work contemplated by this **Contract** as a result of such restrictions upon the number of hours and **Days** of labor, and the immediate commencement or prosecution or completion without undue delay of the **Work** is necessary for the preservation of the **Site** and/or for the protection of the life and limb of the persons using the same, such laborers, workers, and mechanics shall be permitted or required to work more than eight (8) hours in any one (1) **Day**; or five (5) **Days** in any one (1) week; provided, however, that upon application of any **Contractor**, the **Commissioner** shall have first certified to the Commissioner of Labor of the State of New York (hereinafter "Commissioner of Labor") that such public **Work** is of an important nature and that a delay in carrying it to completion would result in serious disadvantage to the public; and provided, further, that such Commissioner of Labor shall have determined that such an emergency does in fact exist as provided in Labor Law Section 220.2.

37.2.3 Failure of the **Commissioner** to make such a certification to the Commissioner of Labor shall not entitle the **Contractor** to damages for delay or for any cause whatsoever.

37.2.4 Prevailing Rate of Wages: The wages to be paid for a legal day's **Work** to laborers, workers, or mechanics employed upon the **Work** contemplated by this **Contract** or upon any materials to be used thereon shall not be less than the "prevailing rate of wage" as defined in Labor Law Section 220, and as fixed by the **Comptroller** in the attached Schedule of Wage Rates and in updated schedules thereof. The prevailing wage rates and supplemental benefits to be paid are those in effect at the time the **Work** is being performed.

37.2.5 Requests for interpretation or correction in the Information for Bidders includes all requests for clarification of the classification of trades to be employed in the performance of the **Work** under this **Contract**. In the event that a trade not listed in the **Contract** is in fact employed during the performance of this **Contract**, the **Contractor** shall be required to obtain from the **Agency** the prevailing wage rates and supplementary benefits for the trades used and to complete the performance of this **Contract** at the price at which the **Contract** was awarded.

37.2.6 Minimum Wages: Except for employees whose wage is required to be fixed pursuant to Labor Law Section 220, all persons employed by the **Contractor** and any **Subcontractor** in the manufacture or furnishing of the supplies, materials, or equipment, or the furnishing of work, labor, or services, used in the performance of this **Contract**, shall be paid, without subsequent deduction or rebate unless expressly authorized by **Law**, not less than the sum mandated by Law.

37.3 Working Conditions: No part of the Work, labor or services shall be performed or rendered by the **Contractor** in any plants, factories, buildings or surroundings or under working conditions which are unsanitary or hazardous or dangerous to the health and safety of employees engaged in the performance of this **Contract**. Compliance with the safety, sanitary, and factory inspection **Laws** of the state in which the **Work** is to be performed shall be prima facie evidence of compliance with this Article 37.3.



37.4 Prevailing Wage Enforcement: The Contractor agrees to pay for all costs incurred by the City in enforcing prevailing wage requirements, including the cost of any investigation conducted by or on behalf of the Agency or the Comptroller, where the City discovers a failure to comply with any of the requirements of this Article 37 by the Contractor or its Subcontractor(s). The Contractor also agrees that, should it fail or refuse to pay for any such investigation, the Agency is hereby authorized to deduct from a Contractor's account an amount equal to the cost of such investigation.

37.4.1 The Labor Law Section 220 and Section 220-d, as amended, provide that this **Contract** shall be forfeited and no sum paid for any **Work** done hereunder on a second conviction for willfully paying less than:

37.4.1(a) The stipulated prevailing wage scale as provided in Labor Law section 220, as amended, or

37.4.1(b) The stipulated minimum hourly wage scale as provided in Labor Law section 220-d, as amended.

37.4.2 For any breach or violation of either working conditions (Article 37.3) or minimum wages (Article 37.2.6) provisions, the party responsible therefor shall be liable to the City for liquidated damages, which may be withheld from any amounts due on any contracts with the City of such party responsible, or may be recovered in actions brought by the City Corporation Counsel in the name of the City, in addition to damages for any other breach of this Contract, for a sum equal to the amount of any underpayment of wages due to any employee engaged in the performance of this Contract. In addition, the Commissioner shall have the right to cancel contracts and enter into other contracts for the completion of the original contract, with or without public letting, and the original Contractor shall be liable for any additional cost. All sums withheld or recovered as deductions, rebates, refunds, or underpayment of wages hereunder, shall be held in a special deposit account and shall be paid without interest, on order of the Comptroller, directly to the employees who have been paid less than minimum rates of pay as set forth herein and on whose account such sums were withheld or recovered, provided that no claims by employees for such payments shall be entertained unless made within two (2) years from the date of actual notice to the Contractor of the withholding or recovery of such sums by the City.

37.4.3 A determination by the **Comptroller** that a **Contractor** and/or its **Subcontractor** willfully violated Labor Law Section 220 will be forwarded to the **City's** five District Attorneys for review.

37.4.4 The **Contractor's** or **Subcontractor's** noncompliance with this Article 37.4 and Labor Law Section 220 may result in an unsatisfactory performance evaluation and the **Comptroller** may also find and determine that the **Contractor** or **Subcontractor** willfully violated the New York Labor Law.

37.4.4(a) An unsatisfactory performance evaluation for noncompliance with this Article 37.4 may result in a determination that the **Contractor** is a non-responsible bidder on subsequent procurements with the **City** and thus a rejection of a future award of a contract with the **City**, as well as any other sanctions provided for by **Law**.



37.4.4(b) Labor Law Section 220-b, as amended, provides that when two (2) final determinations have been rendered against a **Contractor** or **Subcontractor** within any consecutive six (6) year period determining that such **Contractor** or **Subcontractor** has willfully failed to pay the prevailing rate of wages or to provide supplements in accordance with the Labor Law and this Article 37.4, whether such failures were concurrent or consecutive and whether or not such final determinations concerning separate public works projects are rendered simultaneously, such **Contractor** or **Subcontractor** shall be ineligible to submit a bid on or be awarded any public works contract with the **City** for a period of five (5) years from the second final determination. If the final determination involves the falsification of payroll records or the kickback of wages or supplements, the **Contractor** or **Subcontractor** shall be ineligible to submit a bid on or be awarded any public works contract with the **City** for a period of five (5) years from the second final determination. If the final determination involves the falsification of payroll records or the kickback of wages or supplements, the **Contractor** or **Subcontractor** shall be ineligible to submit a bid on or be awarded any public works contract with

37.4.4(c) Labor Law Section 220, as amended, provides that the **Contractor** or **Subcontractor** found to have violated this Article 37.4 may be directed to make payment of wages or supplements including interest found to be due, and the **Contractor** or **Subcontractor** may be directed to make payment of a further sum as a civil penalty in an amount not exceeding twenty-five (25%) percent of the total amount found to be due.

37.5 The **Contractor** and its **Subcontractors** shall within ten (10) **Days** after mailing of a Notice of Award or written order, post in prominent and conspicuous places in each and every plant, factory, building, and structure where employees of the **Contractor** and its **Subcontractors** engaged in the performance of this **Contract** are employed, notices furnished by the **City**, in relation to prevailing wages and supplements, minimum wages, and other stipulations contained in Sections 220 and 220-h of the Labor Law, and the **Contractor** and its **Subcontractors** shall continue to keep such notices posted in such prominent and conspicuous places until **Final Acceptance** of the supplies, materials, equipment, or **Work**, labor, or services required to be furnished or rendered under this **Contract**.

37.6 The **Contractor** shall strictly comply with all of the provisions of Articles 37.6.1 through 37.6.5, and provide for all workers, laborers or mechanics in its employ, the following:

37.6.1 Notices Posted At Site: Post, in a location designated by the City, schedules of prevailing wages and supplements for this **Project**, a copy of all re-determinations of such schedules for the **Project**, the Workers' Compensation Law Section 51 notice, all other notices required by Law to be posted at the Site, the City notice that this **Project** is a public works project on which each worker is entitled to receive the prevailing wages and supplements for the occupation at which he or she is working, and all other notices which the City directs the Contractor to post. The Contractor shall provide a surface for such notices in a legible manner and shall replace any notice or schedule which is damaged, defaced, illegible or removed for any reason. The Contractor shall maintain such notices until all Work on the Site is complete; and

37.6.2 Daily Site Sign-in Sheets: Maintain daily Site sign-in sheets, and require that **Subcontractors** maintain daily Site sign-in sheets for its employees, which include blank spaces for an employee's name to be both printed and signed, job title, date started and

Social Security number, the time the employee began work and the time the employee left work, until **Final Acceptance** of the supplies, materials, equipment, or **Work**, labor, or services to be furnished or rendered under this **Contract** unless exception is granted by the **Comptroller** upon application by the **Agency**. In the alternative, subject to the approval of the **CCPO**, the **Contractor** and **Subcontractor** may maintain an electronic or biometric sign-in system, which provides the information required by this Article 37.6.2; and

ESSGN + CO

37.6.3 Individual Employee Information Notices: Distribute a notice to each worker, laborer or mechanic employed under this Contract, in a form provided by the Agency, that this Project is a public works project on which each worker, laborer or mechanic is entitled to receive the prevailing rate of wages and supplements for the occupation at which he or she is working. If the total cost of the Work under this Contract is at least two hundred fifty thousand (\$250,000) dollars, such notice shall also include a statement that each worker, laborer or mechanic must be certified prior to performing any Work as having successfully completed a course in construction safety and health approved by the United States Department of Labor's Occupational Safety and Health Administration that is at least ten (10) hours in duration. Such notice shall be distributed to each worker before he or she starts performing any Work of this Contract and with the first paycheck after July first of each year. "Worker, laborer or mechanic" includes employees of the Contractor and all Subcontractors and all employees of suppliers entering the Site. At the time of distribution, the Contractor shall have each worker, laborer or mechanic sign a statement, in a form provided by the Agency, certifying that the worker has received the notice required by this Article 37.6.3, which signed statement shall be maintained with the payroll records required by this Contract; and

37.6.3(a) The **Contractor** and each **Subcontractor** shall notify each worker, laborer or mechanic employed under this**Contract**in writing of the prevailing rate of wages for their particular job classification. Such notification shall be given to every worker, laborer, and mechanic on their first pay stub and with every pay stub thereafter; and

37.6.4 Site Laminated Identification Badges: The **Contractor** shall provide laminated identification badges which include a photograph of the worker's, laborer's or mechanic's face and indicate the worker's, laborer's or mechanic's name, trade, employer's name, and employment starting date (month/day/year). Further, the **Contractor** shall require as a condition of employment on the **Site**, that each and every worker, laborer or mechanic wear the laminated identification badge at all times and that it may be seen by any representative of the **City**. The **Commissioner** may grant a written waiver from the requirement that the laminated identification badge include a photograph if the **Contractor** demonstrates that the identity of an individual wearing a laminated identification badge can be easily verified by another method; and

37.6.5 Language Other Than English Used On Site: Provide the ACCO notice when three (3) or more employees (worker and/or laborer and/or mechanic) on the Site, at any time, speak a language other than English. The ACCO will then provide the Contractor the notices described in Article 37.6.1 in that language or languages as may be required. The Contractor is responsible for all distributions under this Article 37; and



37.6.6 Provision of Records: The **Contractor** and **Subcontractor(s)**shall produce within five (5) **Days** on the **Site** of the **Work** and upon a written order of the **Engineer**, the **Commissioner**, the **ACCO**, the **Agency EAO**, or the **Comptroller**, such records as are required to be kept by this Article 37.6; and

37.6.7 The **Contractor** and **Subcontractor(s)** shall pay employees by check or direct deposit. If this **Contract** is for an amount greater than one million (\$1,000,000) dollars, checks issued by the **Contractor** to covered employees shall be generated by a payroll service or automated payroll system (an in-house system may be used if approved by the **Agency**). For any subcontract for an amount greater than seven hundred fifty thousand (\$750,000) dollars, checks issued by a **Subcontractor** to covered employees shall be generated by a payroll service or automated payroll system (an in-house system (an in-house system may be used if approved by the generated by a payroll service or automated payroll system (an in-house system may be used if approved by the **Agency**); and

37.6.8 The failure of the **Contractor** or **Subcontractor(s)** to comply with the provisions of Articles 37.6.1 through 37.6.7 may result in the **Commissioner** declaring the **Contractor** in default and/or the withholding of payments otherwise due under the **Contract**.

37.7 The **Contractor** and its **Subcontractors** shall keep such employment and payroll records as are required by Section 220 of the Labor Law. The failure of the **Contractor** or **Subcontractor(s)** to comply with the provisions of this Article 37.7 may result in the **Commissioner** declaring the **Contractor** in default and/or the withholding of payments otherwise due under the **Contract**.

37.8 At the time the **Contractor** makes application for each partial payment and for final payment, the **Contractor** shall submit to the **Commissioner** a written payroll certification, in the form provided by this **Contract**, of compliance with the prevailing wage, minimum wage, and other provisions and stipulations required by Labor Law Section 220 and of compliance with the training requirements of Labor Law Section 220-h set forth in Article 35.2. This certification of compliance shall be a condition precedent to payment and no payment shall be made to the **Contractor** unless and until each such certification shall have been submitted to and received by the **Commissioner**.

37.9 This **Contract** is executed by the **Contractor** with the express warranty and representation that the **Contractor** is not disqualified under the provisions of Section 220 of the Labor Law from the award of the **Contract**.

37.10 Any breach or violation of any of the foregoing shall be deemed a breach or violation of a material provision of this **Contract**, and grounds for cancellation thereof by the **City**.

## **ARTICLE 38. PAYROLL REPORTS**

38.1 The **Contractor** and its **Subcontractor(s)** shall maintain on the **Site** during the performance of the **Work** the original payrolls or transcripts thereof which the **Contractor** and its **Subcontractor(s)** are required to maintain and shall submit such original payrolls or transcripts, subscribed and affirmed by it as true, within thirty (30) **Days** after issuance of its first payroll, and every thirty (30) **Days** thereafter, pursuant to Labor Law Section 220(3-a)(a)(iii). The **Contractor** and **Subcontractor(s)** shall submit such original payrolls or transcripts along with each and every payment requisition. If payment requisitions are not submitted at least once a month, the **Contractor** and its **Subcontractor(s)** shall submit original



payrolls and transcripts both along with its payment requisitions and independently of its payment requisitions.

38.2 The **Contractor** shall maintain payrolls or transcripts thereof for six (6) years from the date of completion of the **Work** on this **Contract**. If such payrolls and transcripts are maintained outside of New York City after the completion of the **Work** and their production is required pursuant to this Article 38, the **Contractor** shall produce such records in New York City upon request by the **City**.

38.3The Contractor and Subcontractor(s) shall comply with any written order, direction, or request made by the Engineer, the Commissioner, the ACCO, the Agency EAO, the Agency Labor Law Investigator(s), or the Comptroller, to provide to the requesting party any of the following information and/or records within five (5) Days of such written order, direction, or request:

38.3.1 Such original payrolls or transcripts thereof subscribed and affirmed by it as true and the statements signed by each worker pursuant to this Chapter VIII; and/or

38.3.2 Attendance sheets for each **Day** on which any employee of the **Contractor** and/or any of the **Subcontractor(s)** performed **Work** on the **Site**, which attendance sheet shall be in a form acceptable to the **Agency** and shall provide information acceptable to the **Agency** to identify each such employee; and/or

38.3.3 Any other information to satisfy the Engineer, the Commissioner, the ACCO, the Agency EAO, the Agency Labor Law Investigator(s) or the Comptroller, that this Chapter VIII and the Labor Law, as to the hours of employment and prevailing rates of wages and/or supplemental benefits, are being observed.

38.4 The failure of the **Contractor** or **Subcontractor(s)**to comply with the provisions of Articles 38.1 and/or 38.2 may result in the **Commissioner** declaring the **Contractor** in default and/or the withholding of payments otherwise due under the **Contract**.

# ARTICLE 39, DUST HAZARDS

39.1 Should a harmful dust hazard be created in performing the Work of this Contract, for the elimination of which appliances or methods have been approved by the Board of Standards and Appeals of the City of New York, such appliances and methods shall be installed, maintained, and effectively operated during the continuance of such harmful dust hazard. Failure to comply with this provision after notice shall make this Contract voidable at the sole discretion of the City.

## CHAPTER IX PARTIAL AND FINAL PAYMENTS

## **ARTICLE 40.JOB ORDER**

40.1 The City shall pay, and the Contractor agrees to accept, in full consideration for the Contractor's performance of the Work subject to the terms and conditions hereof, the lump sum price or unit prices for which this Contract was awarded, plus the amount required to be paid for any Extra



Work ordered by the Commissioner under Article 25, less credit for any Work omitted pursuant to Article 29.

## ARTICLE 41.

## NOT USED

## **ARTICLE 42. PARTIAL PAYMENTS ON JOB ORDERS**

42.1For all **Job Orders** of twenty five thousand (\$25,000) dollars or less, or with a **Job Order Completion Time** of 45 Days or less, there will be only one payment. For all other **Job Orders**, as the **Detailed Scope of Work** progresses satisfactorily, but not more often than once a month, beginning on the 46<sup>th</sup> day, the **Contractor** may submit to the **Engineer** a requisition for a partial payment in the prescribed form, which shall contain an estimate of the quantity and the fair value of the **Work** done during the payment period. Requisitions shall be submitted on a **Job Order** basis.

## ARTICLE 42A. PARTIAL PAYMENTS ON CONTRACT

#### NOT USED

## ARTICLE 42B.SUBMISSION OF JOB ORDER PAYMENT REQUEST AND REQUEST FOR PAYMENT

42B.1Upon completion of a Job Order, or when a Job Order is eligible for a partial payment, the **Contractor** shall submit a Job Order Payment Request to the **Project Engineer**. The **Contractor** shall submit a maximum of one Job Order Payment Request per Job Order per month (30 Day period).

42B.2Contractorshall include with each Job Order Payment Request the following data:

- Detailed Scope of Work
- Request for Proposal
- Proposal Summary
- Price Proposal
- Job Order
- Final Inspection Form (final payments only)
- Certification of Contractor to the Comptroller
- Certification of Subcontractor(s) to the Comptroller
- Verification of Payment to Subcontractor(s)
- LBE Program Compliance Report
- Daily Sign-In Sheets for Contractor and any Subcontractors
- Prevailing Wage Reports for Contractor and any Subcontractors

42B.3TheContractor shall submit a maximum of one Request for Payment per month (30 Day period). The Request for Payment shall consist of the individual Job Order Payment Requests that have been approved and not previously submitted.





42B.4TheContractor shall include with each Request for Payment the following data:

- Payment Approval and Tracking Sheet (Form 214B) for MBE/WBE
  - Estimate for Partial Payment
  - Certification for Estimate for Partial Payment

## ARTICLE 42C. PARTIAL PAYMENTS FOR MATERIALS IN ADVANCE OF THEIR INCORPORATION IN THE WORK

In order to better insure the availability of materials, fixtures and equipment when needed for the **Work**, the **Commissioner** may authorize partial payment for certain materials, fixtures and equipment, prior to their incorporation in the work, but only in strict accordance with and subject to all the terms and conditions set forth in the following Subdivisions numbered 1 to 15 inclusive, unless another method of payment is elsewhere provided in the **Specifications** for specified materials, fixtures or equipment.

42C.1 The **Contractor** shall submit to the **Commissioner** a written request, in quadruplicate, for payment for materials purchased or to be purchased for which he or she desires to be paid prior to their actual incorporation in the **Work**. The request shall be accompanied by a schedule of the types and quantities of materials, and shall state whether such materials are to be stored on or off the **Site**.

42C.2 Where the materials are to be stored off the Site, they shall be stored at a place other than the **Contractor's** premises (except with the written consent of the **Commissioner**) and under the conditions prescribed or approved by the **Commissioner**. The **Contractor** shall set apart and separately store at the place or places of storage all materials and shall clearly mark same "Property of the City of New York", and further shall not at any time move any of said materials to another off-site place of storage without the prior written consent of the **Commissioner**. Materials may be removed from their place of storage off the **Site** for incorporation in the work upon approval of the **Resident Engineer**.

42C.3 Where materials are to be stored at the Site, they shall be stored at such locations as shall be designated by the **Resident Engineer** and only in such quantities as, in the opinion of the **Resident Engineer**, will not interfere with the proper performance of the **Work** by the **Contractor** or by **Other Contractors** then engaged in performing on the Site. Such materials shall not be removed from their place of storage on the Site except for incorporation in the **Work**, without the approval of the **Resident Engineer**.

42C.4All costs, charges and expenses arising out of the storage of such materials shall be paid by the **Contractor** and the **City** hereby reserve the right to retain out of any partial or final payment made under the **Contractor** an amount sufficient to cover such costs, charges and expenses. There shall be no increase in the **Contractor** price for such costs, charges and expenses and the **Contractor** shall not make any claim or demand for compensation therefor.

42C.5 The **Contractor** shall pay any and all costs of handling and delivery of materials to the place of storage and from the place of storage to the **Site** of the **Work** and the **City** shall have the right to retain from any partial or final payment an amount sufficient to cover the cost of such handling and delivery.

42C.6 In the event that the whole or any part of these materials are lost, damaged or destroyed in advance of their satisfactory incorporation in the Work, the Contractor, at its own cost, shall promptly replace such lost, damaged or destroyed materials with materials of the same character and quality. The Contractor shall also promptly replace at its expense Work accepted under this Contract pursuant to



Article 16 of the Agreement which is lost or damaged by its negligence or carelessness or the negligence or carelessness of his/hers Subcontractors, agents or employees or by failure to comply with the provisions of this Contract. Until such time as the materials are replaced, the City will deduct from the value of the stored materials or from any money due under the Contract the amount paid to the Contractor for such lost, damaged or destroyed materials.

42C.7 Should any of the materials paid for by the **City** hereunder be subsequently rejected or incorporated in the **Work** in a manner or by a method not in accordance with the **Contract** and **Specifications**, the **Contractor** shall remove and replace such defective or improperly incorporated material with materials complying with the **Contract** and **Specifications**. Until such materials are replaced, the **City** will deduct from the value of the stored materials or from any other money due to the **Contractor**, the amount paid by the **City** for such rejected or improperly incorporated materials

42C.8 Payment for the cost of materials made hereunder shall not be deemed to be an acceptance of such materials as being in accordance with the **Contract Documents**, and the **Contractor** always retains and must comply with his/her duty to deliver to the **Site** and properly incorporate in the **Work** only materials which comply with the **Contract Documents**.

42C.9 The **Contractor** shall retain any and all risks in connection with the damage, destruction or loss of the materials paid for hereunder to the time of delivery of the same to the site of the **Work** and their proper incorporation in the **Work** in accordance with the **Contract Documents**.

42C.10 The **Contractor** shall comply with all **Law** and the regulations of any governmental body or agency pertaining to the priority purchase, allocation and use of materials.

42C.11When requesting payment for such materials, the **Contractor** shall submit with the partial estimate duly authenticated documents of title, such as bills of sale, invoices or warehouse receipts, all in quadruplicate. The executed bills of sale shall transfer title to the materials from the **Contractor** to the **City**(in the event that the invoices state that the materials has been purchased by a **Subcontractor**, bills of sale in quadruplicate will also be required transferring title to the materials from **Subcontractor** to the **Contractor**).

42C.12 Where the **Contractor**, with the approval of the **Commissioner**, has purchased unusually large quantities of materials in order to assure their availability for the **Work**, the **Commissioner**, at his/her option, may waive the requirements of Subdivision"11" provided the **Contractor** furnishes evidence in the form of an affidavit of the **Contractor** in quadruplicate and such other proof as the **Commissioner** may require that it is the sole owner of such materials and has purchased them free and clear of all liens and other encumbrances. In such event, the **Contractor** shall pay for such materials and submit proof thereof, in the same manner as provided in Subdivision"11" hereof, within seven (7) **Days** after receipt of payment therefore from the **Comptroller**. Failure on the part of the **Contractor** to submit satisfactory evidence that it has paid in full for all such materials shall preclude it from any payments under the **Contract**.

42C.13 The **Contractor** shall include in such succeeding partial estimate requisition a summary of materials stored which shall set forth the quantity and value of materials in storage, on or off the **Site**, at the end of each preceding estimate period; the amount removed for incorporation in the **Work**; the quantity and value of materials delivered during the current period and the total value of materials on hand for which payment thereof will be included in the current payment estimate.



66



42C.14 Upon proof to the satisfaction of the **Commissioner** of the actual cost of such materials and upon submission of proper proof of title as required under Subdivision "11" or "12" hereof, payment will be made therefor to the extent of Eighty Five (85%) percent therefore provided, however, that the cost so verified, established and approved shall not exceed the estimated cost of such materials included in the approved detailed breakdown estimate submitted in accordance with Article 42 of the Agreement; if it does, the City will pay only Eighty Five (85%) percent of such approved estimate cost.

42C.15Upon the incorporation in the **Work** of any such materials, which have been paid for in advance of such incorporation in accordance with the foregoing provisions, payment will be made for such materials incorporated in the **Work** pursuant to Article 42 or Article 43 of the **Agreement**, less any sums paid pursuant to Subdivision"14" herein.

## ARTICLE 42D.AUDIT BY THE DEPARTMENT'S ENGINEERING AUDIT OFFICER (EAO) AND THE COMPTROLLER OF THE CITY OF NEW YORK

42D.1. All vouchers or invoices presented for payment to be made hereunder, and the books, records and accounts upon which said vouchers or invoices are based, are subject to audit by the AgencyEAO and by the Comptroller of the City of New York pursuant to the powers and responsibilities as conferred upon said EAO and said Comptroller by the New York City Charter and Administrative Code of the City of New York, as well as all orders and regulations promulgated pursuant thereto. The Contractor is advised that all change orders (including negotiated ones) are also subject to the EAO's audit.

42D.2. The **Contractor** shall submit any and all documentation and justification in support of expenditures or fees under this **Contract** as may be required by the **AgencyEAO** and said **Comptroller** so that they may evaluate the reasonableness of the charges and shall make its records available to the **AgencyEAO** and the **Comptroller** as they consider necessary.

42D.3 All books, vouchers, records, reports, canceled checks and any and all similar material may also be subject to periodic inspection, review and audit by the State of New York, Federal Government and other persons duly authorized by the **City**.

42D.4 The **Contractor** shall not be entitled to final payment for a **Job Order** until all requirements have been satisfactorily met.

## ARTICLE 42E.CONSTRUCTION CONTRACTOR EVALUATION PROVISION

42E.1 For each **Contract** with an original or amended term of greater than 12 months, the **Contractor's** performance shall be evaluated by the **City** no later than 120 **Days** after the last day of each 12 month period following the issuance of the first **Job Order** ("interim evaluation"). The **Contractor's** performance shall additionally be evaluated within no later than 120 **Days** after the **Contractor's** expiration, completion, or termination date ("final evaluation"). Where the interim and final evaluations are to be performed within the same 120 **Day** period, only the final evaluation need be performed. A copy of each evaluation will be sent to the **Contractor** not later than 15 **Days** after the evaluation had been prepared, and the **Contractor** may respond in writing to the performance evaluation. Such responses shall be submitted to the evaluator not later than 15 **Days** after a copy of the evaluation is sent to the **Contractor's** performance to respond to a less than satisfactory evaluation may result in review of **Contractor's** performance when a bid is evaluated, without the benefit of **Contractor's** response to the evaluation.



## **ARTICLE 43. PROMPT PAYMENT**

43.1 The Prompt Payment provisions of the **PPB**Rules in effect at the time of the bid will be applicable to payments made under this **Contract**. The provisions require the payment to the **Contractor** of interest on payments made after the required payment date, except as set forth in the **PPB**Rules.

43.2 The **Contractor** shall submit a proper invoice to receive payment, except where the **Contract** provides that the **Contractor** will be paid at predetermined intervals without having to submit an invoice for each scheduled payment.

43.3 Determination of interest due will be made in accordance with the **PPB**Rules.

43.4 If the **Contractor** is paid interest, the proportionate share(s) of that interest shall be forwarded by the **Contractor** to its **Subcontractor(s)**.

43.5 The Contractor shall pay each Subcontractor or Materialman not later than seven (7) Days after receipt of payment out of amounts paid to the Contractor by the City for Work performed by the Subcontractor or Materialman under this Contract.

43.5.1 If **Contractor** fails to make any payment to any **Subcontractor** or **Materialman** within seven (7) **Days** after receipt of payment by the **City** pursuant to this Article 43.5, then the **Contractor** shall pay interest on amounts due to such **Subcontractor** or **Materialman** at the rate of interest in effect on the date such payment is made by the **Contractor** computed in accordance with Section 756-b(1)(b) of the New York General Business Law. Accrual of interest shall commence on the day immediately following the expiration of the seventh **Day** following receipt of payment by the **Contractor** from the **City** and shall end on the date on which payment is made.

43.6 The **Contractor** shall include in each of its **Subcontracts** a provision requiring each **Subcontractor** to make payment to each of its **Subcontractors** or **Materialmen** for **Work** performed under this **Contract** in the same manner and within the same time period set forth above.

## <u>ARTICLE 44.</u>

## NOT USED

#### **ARTICLE 45. FINAL PAYMENT ON JOB ORDERS**

45.1 After completion and Final Acceptance of the Detailed Scope of Work for a Job Order, the Contractor shall submit all required certificates and documents, together with a requisition for the balance claimed to be due under the Job Order, less the amount authorized to be retained for maintenance under Article 24. Such submission shall be within 90 Days of the date of the Commissioner's written determination of Final Acceptance, or within such additional time as may be granted by the Commissioner in writing. If the Contractor fails to submit all required certificates and documents within the time allowed, no payment of the balance claimed shall be made to the Contractor and the Contractor shall be deemed to have forfeited its right to payment of any balance claimed. A





verified statement similar to that required in connection with applications for partial payments shall also be submitted to the **Commissioner**.

45.2 Amended Verified Statement of Claims: The Contractor shall also submit with the final requisition any amendments to the final verified statement of any pending dispute resolution procedures in accordance with the PPBRules and this Contract and any and all alleged claims against the City, in any way connected with or arising out of this Contract (including those as to which details may have been furnished pursuant to Articles 11, 27, 28, and 30) that have occurred subsequent to Final Acceptance, setting forth with respect to each such claim the total amount thereof, the various items of labor and materials included therein, and the alleged value of each such item; and if the alleged claim be one for delay, the alleged cause of each such delay, the period or periods of time, giving the dates when the Contractor claims the performance of the Work or a particular part thereof was delayed, and an itemized statement and breakdown of the amount claimed for each such delay. With reference to each such claim, the Commissioner, the Comptroller and, in the event of litigation, the City Corporation Counsel shall have the same right to inspect, and to make extracts or copies of, the Contractor's books, vouchers, records, etc., as is referred to in Articles 11, 27, 28, and 30. Nothing contained in this Article45.2, is intended to or shall relieve the Contractor from the obligation of complying strictly with Articles 11, 27, 28, and 30. The Contractor is warned that unless such claims are completely set forth as herein required, the Contractor, upon acceptance of the Final Payment pursuant to Article 46, will have waived any such claims.

#### ARTICLE 45A. FINAL PAYMENT ON THE CONTRACT

45A.1 Preparation of Final Voucher: Upon determining the balance due hereunder other than on account of claims, the **Engineer** will prepare and certify, for the **Commissioner's** approval, a voucher for final payment in that amount less any and all deductions authorized to be made by the **Commissioner** under this **Contract** or by **Law**. In the case of a lump sum **Contract**, the **Commissioner** shall certify the voucher for final payment within thirty (30) **Days** from the date of completion and acceptance of the **Work**, provided all requests for extensions of time have been acted upon.

- 45A.1.1 All prior certificates and vouchers upon which partial and final payments were made for individual Job Orders, being merely estimates made to enable the Contractor to prosecute the Work more advantageously, shall be subject to correction in the final voucher, and the certification of the Engineer thereon and the approval of the Commissioner thereof, shall be conditions precedent to the right of the Contractor to receive any money hereunder. Such final voucher shall be binding and conclusive upon the Contractor.
- 45A.1.2 Payment pursuant to such final voucher, less any deductions authorized to be made by the **Commissioner** under this **Contract** or by **Law**, shall constitute the final payment, and shall be made by the **Comptroller** within thirty (30) **Days** after the filing of such voucher in his/her office.

45A.2The **Contractor** acknowledges that nothing contained in this Article 45A is intended to or shall in any way diminish the force and effect of Article 13.

## ARTICLE 46. ACCEPTANCE OF FINAL PAYMENT



46.1 The acceptance by the **Contractor**, or by anyone claiming by or through it, of the final payment, whether such payment be made pursuant to any judgment of any court, or otherwise, shall constitute and operate as a release of the **City** from any and all claims of and liability to the **Contractor** for anything heretofore done or furnished for the **Contractor** relating to or arising out of this **Contract** and the **Work** done hereunder, and for any prior act, neglect or default on the part of the **City** or any of its officials, agents or employees, excepting only a claim against the **City** for the amounts deducted or retained in accordance with the terms and provisions of this **Contract** or by **Law**, and excepting any claims, not otherwise waived, or any pending dispute resolution procedures which are contained in the verified statement filed with the **Contractor's** substantial and final requisitions pursuant to Articles 44 and 45.

46.2 The **Contractor** is warned that the execution by it of a release, in connection with the acceptance of the final payment, containing language purporting to reserve claims other than those herein specifically excepted from the operation of this Article 46, or those for amounts deducted by the **Commissioner** from the final requisition or from the final payment as certified by the **Engineer** and approved by the **Commissioner**, shall not be effective to reserve such claims, anything stated to the **Contractor** orally or in writing by any official, agent or employee of the **City** to the contrary notwithstanding.

46.3 Should the **Contractor** refuse to accept the final payment as tendered by the **Comptroller**, it shall constitute a waiver of any right to interest thereon.

46.4 The **Contractor**, however, shall not be barred by this Article 46 from commencing an action for breach of **Contract** to the extent permitted by **Law** and by the terms of the **Contract** for any claims that are contained in the verified statement filed with the **Contractor's** substantial and final requisitions pursuant to Articles 44 and 45 or that arose after submission of the final payment requisition, provided that a detailed and verified statement of claim is served upon the contracting **Agency** and **Comptroller** not later than forty (40) **Days** after the making of such final payment by electronic funds transfer (EFT) or the mailing of such final payment. The statement shall specify the items upon which the claim will be based and any such claim shall be limited to such items.

## **ARTICLE 47. APPROVAL BY PUBLIC DESIGN COMMISSION**

47.1 All works of art, including paintings, mural decorations, stained glass, statues, bas-reliefs, and other sculptures, monuments, fountains, arches, and other structures of a permanent character intended for ornament or commemoration, and every design of the same to be used in the performance of this **Contract**, and the design of all bridges, approaches, buildings, gates, fences, lamps, or structures to be erected, pursuant to the terms of this **Contract**, shall be submitted to the Art Commission, d/b/a the Public Design Commission of the City of New York, and shall be approved by the Public Design Commission prior to the erection or placing in position of the same. The final payment shall not become due or payable under this **Contract** unless and until the Public Design Commission shall certify that the design for the **Work** herein contracted for has been approved by the said Public Design Commission, and that the same has been executed in substantial accordance with the design so approved, pursuant to the provisions of Chapter 37, Section 854 of the **City** Charter, as amended.

## CHAPTER X CONTRACTOR'S DEFAULT

# ARTICLE 48. COMMISSIONER'S RIGHT TO DECLARE CONTRACTOR IN DEFAULT



48.1 In addition to those instances specifically referred to in other Articles herein, the **Commissioner** shall have the right to declare the **Contractor** in default of this **Contract** if:

48.1.1 The Contractor fails to commence Work when notified to do so by the Commissioner; or if

48.1.2 The Contractor shall abandon the Work; or if

48.1.3 The **Contractor** shall refuse to proceed with the **Work** when and as directed by the **Commissioner**; or if

48.1.4 The **Contractor** shall, without just cause, reduce its working force to a number which, if maintained, would be insufficient, in the opinion of the **Commissioner**, to complete the **Work** in accordance with the progress schedule; or if

48.1.5 The **Contractor** shall fail or refuse to increase sufficiently such working force when ordered to do so by the **Commissioner**; or if

48.1.6 The **Contractor** shall sublet, assign, transfer, convert or otherwise dispose of this **Contract** other than as herein specified; or sell or assign a majority interest in the **Contractor**; or if

48.1.7 The Contractor fails to secure and maintain all required insurance; or if

48.1.8 A receiver or receivers are appointed to take charge of the **Contractor's** property or affairs; or if

48.1.9 The **Commissioner** shall be of the opinion that the **Contractor** is or has been unnecessarily or unreasonably or willfully delaying the performance and completion of the **Work**, or the award of necessary subcontracts, or the placing of necessary material and equipment orders; or if

48.1.10 The **Commissioner** shall be of the opinion that the **Contractor** is or has been willfully or in bad faith violating any of the provisions of this **Contract**; or if

48.1.11 The **Commissioner** shall be of the opinion that the **Work** cannot be completed within the time herein provided therefor or within the time to which such completion may have been extended; provided, however, that the impossibility of timely completion is, in the **Commissioner's** opinion, attributable to conditions within the **Contractor's** control; or if

48.1.12 The Work is not completed within the time herein provided therefor or within the time to which the **Contractor** may be entitled to have such completion extended; or if

48.1.13 Any statement or representation of the **Contractor** in the **Contract** or in any document submitted by the **Contractor** with respect to the **Work**, A **Job Order**, or the **Contract** (or for purposes of securing the **Contract**) was untrue or incorrect when made; or if



48.1.14 The **Contractor** or any of its officers, directors, partners, five (5%) percent shareholders, principals, or other persons substantially involved in its activities, commits any of the acts or omissions specified as the grounds for debarment in the **PPB**Rules.

48.2 Before the **Commissioner** shall exercise his/her right to declare the **Contractor** in default, the **Commissioner** shall give the **Contractor** an opportunity to be heard, upon not less than two (2) **Days** notice.

## **ARTICLE 49. EXERCISE OF THE RIGHT TO DECLARE DEFAULT**

49.1 The right to declare the **Contractor** in default for any of the grounds specified or referred to in Article 48 shall be exercised by sending the **Contractor** a notice, signed by the **Commissioner**, setting forth the ground or grounds upon which such default is declared (hereinafter referred to as a "Notice of Default").

49.2 The **Commissioner's** determination that the **Contractor** is in default shall be conclusive, final, and binding on the parties and such a finding shall preclude the **Contractor** from commencing a plenary action for any damages relating to the **Contract**. If the **Contractor** protests the determination of the **Commissioner**, the **Contractor** may commence an action in a court of competent jurisdiction of the State of New York under Article 78 of the New York Civil Practice Law and Rules.

## **ARTICLE 50. QUITTING THE SITE**

50.1 Upon receipt of such notice the **Contractor** shall immediately discontinue all further operations under this **Contract** and shall immediately quit the **Site**, leaving untouched all plant, materials, equipment, tools, and supplies then on the **Site**.

#### ARTICLE 51. COMPLETION OF THE WORK

51.1 The **Commissioner**, after declaring the **Contractor** in default, may then have the **Work** completed by such means and in such manner, by contract with or without public letting, or otherwise, as he/she may deem advisable, utilizing for such purpose such of the **Contractor's** plant, materials, equipment, tools, and supplies remaining on the **Site**, and also such **Subcontractors**, as he/she may deem advisable.

51.2 After such completion, the **Commissioner** shall make a certificate stating the expense incurred in such completion, which shall include the cost of re-letting and also the total amount of liquidated damages (at the rate provided for in the **Contract**) from the date when the **Work** should have been completed by the **Contractor** in accordance with the terms hereof to the date of actual completion of the **Work**. Such certificate shall be binding and conclusive upon the **Contractor**, its sureties, and any person claiming under the **Contractor**, as to the amount thereof.

51.3 The expense of such completion, including any and all related and incidental costs, as so certified by the **Commissioner**, and any liquidated damages assessed against the **Contractor**, shall be charged against and deducted out of monies which are earned by the **Contractor** prior to the date of default. Should the expense of such completion, as certified by the **Commissioner**, exceed the total sum

72

#### Contract



which would have been payable under the **Contract** if it had been completed by the **Contractor**, any excess shall be paid by the **Contractor**.

#### ARTICLE 52. PARTIAL DEFAULT

52.1 In case the **Commissioner** shall declare the **Contractor** in default as to a part of the **Work** only, the **Contractor** shall discontinue such part, shall continue performing the remainder of the **Work** in strict conformity with the terms of this **Contract**, and shall in no way hinder or interfere with any **Other Contractor(s)** or persons whom the **Commissioner** may engage to complete the **Work** as to which the **Contractor** was declared in default.

52.2 The provisions of this Chapter relating to declaring the **Contractor** in default as to the entire **Work** shall be equally applicable to a declaration of partial default for a **Job Order** or any portion thereof, except that the **Commissioner** shall be entitled to utilize for completion of the part of the **Work** as to which the **Contractor** was declared in default only such plant, materials, equipment, tools, and supplies as had been previously used by the **Contractor** on such part.

## ARTICLE 53. PERFORMANCE OF UNCOMPLETED WORK

53.1 In completing the whole or any part of the **Work** under the provisions of this Chapter X, the **Commissioner** shall have the power to depart from or change or vary the terms and provisions of this **Contract**, provided, however, that such departure, change or variation is made for the purpose of reducing the time or expense of such completion. Such departure, change or variation, even to the extent of accepting a lesser or different performance, shall not affect the conclusiveness of the **Commissioner's** certificate of the cost of completion referred to in Article 51, nor shall it constitute a defense to an action to recover the amount by which such certificate exceeds the amount which would have been payable to the **Contractor** hereunder but for its default.

#### **ARTICLE 54. OTHER REMEDIES**

54.1 In addition to the right to declare the **Contractor** in default pursuant to this Chapter X, the **Commissioner** shall have the absolute right, in his/her sole discretion and without a hearing, to complete or cause to be completed in the same manner as described in Articles 51 and 53, any or all unsatisfactory or uncompleted punch list **Work** that remains after the completion date specified in the **Final Approved Punch List**. A written notice of the exercise of this right shall be sent to the **Contractor** who shall immediately quit the **Site** in accordance with the provisions of Article 50.

54.2 The expense of completion permitted under Article 54.1, including any and all related and incidental costs, as so certified by the **Commissioner**, shall be charged against and deducted out of monies which have been earned by the **Contractor** prior to the date of the exercise of the right set forth in Article 54.1; the balance of such monies, if any, subject to the other provisions of this **Contract**, to be paid to the **Contractor** without interest after such completion. Should the expense of such completion, as certified by the **Contractor**, any exceed the total sum which would have been payable under the **Contract** if it had been completed by the **Contractor**, any excess shall be paid by the **Contractor**.



54.3 The previous provisions of this Chapter X shall be in addition to any and all other remedies available under Law or in equity.

54.4 The exercise by the **City** of any remedy set forth herein shall not be deemed a waiver by the **City** of any other legal or equitable remedy contained in this **Contract** or provided under **Law**.

#### CHAPTER XI MISCELLANEOUS PROVISIONS

#### ARTICLE 55. CONTRACTOR'S WARRANTIES

55.1 In consideration of, and to induce, the award of this **Contract** to the **Contractor**, the **Contractor** represents and warrants:

55.1.1 That it is financially solvent, sufficiently experienced and competent to perform the Work; and

55.1.2 That the facts stated in its bid and the information given by it pursuant to the Information for Bidders is true and correct in all respects; and

55.1.3 That it has read and complied with all requirements set forth in the Contract.

#### ARTICLE 56. CLAIMS AND ACTIONS THEREON

56.1 Any claim, that is not subject to dispute resolution under the **PPB**Rules or this **Contract**, against the **City** for damages for breach of **Contract** shall not be made or asserted in any action, unless the **Contractor** shall have strictly complied with all requirements relating to the giving of notice and of information with respect to such claims, as herein before provided.

56.2 Nor shall any action be instituted or maintained on any such claims unless such action is commenced within six (6) months after **Final Acceptance** of the **Job Order** from which the lawsuit or claim arose; except that:

- 56.2.1 Any claims for monies deducted, retained or withheld under the provisions of this **Contract** shall be asserted within six (6) months after the date when such monies otherwise become due and payable hereunder; and
- 56.2.2 If the **Commissioner** exercises his/her right to terminate the **Contract** pursuant to Article 64, any such action shall be commenced within six (6) months of the date the **Commissioner** exercises said right.

#### **ARTICLE 57. INFRINGEMENT**

#### Contract



57.1 The **Contractor** shall be solely responsible for and shall defend, indemnify, and hold the **City** harmless from any and all claims (even if the allegations of the lawsuit are without merit) and judgments for damages and from costs and expenses to which the **City** may be subject to or which it may suffer or incur allegedly arising out of or in connection with any infringement by the **Contractor** of any copyright, trade secrets, trademark or patent rights or any other property or personal right of any third party by the **Contractor** and/or its **Subcontractors** in the performance or completion of the **Work**. Insofar as the facts or **Law** relating to any claim would preclude the **City** from being completely indemnified by the **Contractor**, the **City** shall be partially indemnified by the **Contractor** to the fullest extent permitted by **Law**.

#### ARTICLE 58. NO CLAIM AGAINST OFFICIALS, AGENTS OR EMPLOYEES

58.1 No claim whatsoever shall be made by the **Contractor** against any official, agent or employee of the **City** for, or on account of, anything done or omitted to be done in connection with this **Contract**.

#### **ARTICLE 59. SERVICE OF NOTICES**

59.1 The **Contractor** hereby designates the business address, fax number, and email address specified in its bid, as the place where all notices, directions or other communications to the **Contractor** may be delivered, or to which they may be mailed. Any notice, direction, or communication from either party to the other shall be in writing and shall be deemed to have been given when (i) delivered personally; (ii) sent by certified mail, return receipt requested; (iii) delivered by overnight or same day courier service in a properly addressed envelope with confirmation; or (iv) sent by fax or email and, unless receipt of the fax or e-mail is acknowledged by the recipient by fax or e-mail, deposited in a post office box regularly maintained by the United States Postal Service in a properly addressed, postage prepaid envelope.

59.2 Contractor's notice address, email address, or fax number may be changed at any time by an instrument in writing, executed and acknowledged by the Contractor, and delivered to the Commissioner.

59.3 Nothing herein contained shall, however, be deemed to preclude or render inoperative the service of any notice, direction or other communication upon the **Contractor** personally, or, if the **Contractor** is a corporation, upon any officer thereof.

## ARTICLE 60. UNLAWFUL PROVISIONS DEEMED STRICKEN FROM CONTRACT

60.1 If this **Contract** contains any unlawful provision not an essential part of the **Contract** and which shall not appear to have been a controlling or material inducement to the making thereof, the same shall be deemed of no effect and shall, upon notice by either party, be deemed stricken from the **Contract** without affecting the binding force of the remainder.

#### **ARTICLE 61. ALL LEGAL PROVISIONS DEEMED INCLUDED**

61.1 It is the intent and understanding of the parties to this **Contract** that each and every provision of **Law** required to be inserted in this **Contract** shall be and is inserted herein. Furthermore, it is hereby

#### Contract



stipulated that every such provision is to be deemed to be inserted herein, and if, through mistake or otherwise, any such provision is not inserted, or is not inserted in correct form, then this **Contract** shall forthwith upon the application of either party be amended by such insertion so as to comply strictly with the **Law** and without prejudice to the rights of either party hereunder.

#### **ARTICLE 62. TAX EXEMPTION**

62.1 The City is exempt from payment of Federal, State, and local taxes, including sales and compensating use taxes of the State of New York and its cities and counties on all tangible personal property sold to the City pursuant to the provisions of this **Contract**. These taxes are not to be included in bids. However, this exemption does not apply to tools, machinery, equipment or other property leased by or to the **Contractor**, **Subcontractor** or **Materialman** or to tangible personal property which, even though it is consumed, is not incorporated into the completed **Work** (consumable supplies) and tangible personal property that the **Contractor** is required to remove from the **Site** during or upon completion of the **Work**. The **Contractor** and its **Subcontractors** and **Materialmen** shall be responsible for and pay any and all applicable taxes, including sales and compensating use taxes, on such leased tools, machinery, equipment or other property and upon all such consumable supplies and tangible personal property that the **Contractor** from the **Site** during or upon completion of the **Work**.

62.2 The **Contractor** agrees to sell and the **City** agrees to purchase all tangible personal property, other than consumable supplies and other tangible personal property that the **Contractor** is required to remove from the **Site** during or upon completion of the **Work**, that is required, necessary or proper for or incidental to the construction of the **Work** covered by this **Contract**. The sum paid under this **Contract** for such tangible personal property shall be in full payment and consideration for the sale of such tangible personal property.

62.2.1 The Contractor agrees to perform the Detailed Scope of Work for each Job Order and to perform all Work, labor and services rendered, necessary, proper or incidental thereto for the sum shown in such Job Order and the sum so paid pursuant to this Contract for such Work, labor, and services, shall be in full consideration for the performance by the Contractor of all its duties and obligations under this Contract in connection with said Detailed Scope of Work.

62.3 20 NYCRR Section 541.3(d) provides that a **Contractor's** purchases of tangible personal property that is either incorporated into real property owned by a governmental entity or purchased for and sold to a governmental entity are exempt from sales and use tax. The **City** shall not pay sales tax for any such tangible personal property that it purchases from the **Contractor** pursuant to the **Contract**. With respect to such tangible personal property, the **Contractor**, at the request of the **City**, shall furnish to the **City** such bills of sale and other instruments as may be required by the **City**, properly executed, acknowledged and delivered assuring to the **City** title to such tangible personal property, free of liens and/or encumbrances, and the **Contractor** shall mark or otherwise identify all such tangible personal property of the **City**.

62.4 Title to all tangible personal property to be sold by the **Contractor** to the **City** pursuant to the provisions of the **Contract** shall immediately vest in and become the sole property of the **City** upon delivery of such tangible personal property to the **Site**. Notwithstanding such transfer of title, the



**Contractor** shall have the full and continuing responsibility to install such tangible personal property in accordance with the provisions of this **Contract**, protect it, maintain it in a proper condition and forthwith repair, replace and make good any damage thereto, theft or disappearance thereof, and furnish additional tangible personal property in place of any that may be lost, stolen or rendered unusable, without cost to the **City**, until such time as the **Work** covered by the **Contract** is fully accepted by the **City**. Such transfer of title shall in no way affect any of the **Contractor's** obligations hereunder. In the event that, after title has passed to the **City**, any of the tangible personal property is rejected as being defective or otherwise unsatisfactory, title to all such tangible personal property shall be deemed to have been transferred back to the **Contractor**.

62.5 The purchase by **Subcontractors** or **Materialmen** of tangible personal property to be sold hereunder shall be a purchase or procurement for resale to the **Contractor** (either directly or through other **Subcontractors**) and therefore not subject to the aforesaid sales and compensating use taxes, provided that the subcontracts and purchase agreements provide for the resale of such tangible personal property and that such subcontracts and purchase agreements are in a form similar to this **Contract** with respect to the separation of the sale of consumable supplies and tangible personal property that the **Contractor** is required to remove from the **Site** during or upon completion of the **Work** from the **Work** and labor, services, and any other matters to be provided, and provided further that the subcontracts and purchase agreements provide separate prices for tangible personal property and all other services and matters. Such separation shall actually be followed in practice, including the separation of payments for tangible personal property from the payments for other **Work** and labor and other things to be provided.

62.6 The **Contractor** and its **Subcontractors** and **Materialmen** shall furnish a **Contractor** Exempt Purchase Certificate to all persons, firms or corporations from which they purchase tangible personal property for the performance of the **Work** covered by this **Contract**.

62.7 In the event any of the provisions of this Article 62 shall be deemed to be in conflict with any other provisions of this **Contract** or create any ambiguity, then the provisions of this Article 62 shall control.

#### **ARTICLE 63. INVESTIGATION(S) CLAUSE**

63.1 The parties to this **Contract** agree to cooperate fully and faithfully with any investigation, audit or inquiry conducted by a United States, a State of New York (State) or a **City** governmental agency or authority that is empowered directly or by designation to compel the attendance of witnesses and to examine witnesses under oath, or conducted by the Inspector General of a governmental agency that is a party in interest to the transaction, submitted bid, submitted proposal, contract, lease, permit or license that is the subject of the investigation, audit or inquiry.

63.2 If any person who has been advised that his/her statement, and any information from such statement, will not be used against him/her in any subsequent criminal proceeding refuses to testify before a grand jury or other governmental agency or authority empowered directly or by designation to compel the attendance of witnesses and to examine witnesses under oath concerning the award of or performance under any transaction, agreement, lease, permit, contract, or license entered into with the **City**, the State, or any political subdivision or public authority thereof, or the Port Authority of New York and New Jersey, or any local development corporation within the **City**, or any public benefit corporation organized under the **Laws** of the State of New York, or;



63.3 If any person refuses to testify for a reason other than the assertion of his/her privilege against self incrimination in an investigation, audit or inquiry conducted by a **City** or State governmental agency or authority empowered directly or by designation to compel the attendance of witnesses and to take testimony under oath, or by the Inspector General of the governmental agency that is a party in interest in, and is seeking testimony concerning the award of, or performance under any transaction, agreement, lease, permit, contract, or license entered into with the **City**, the State, or any political subdivision thereof or any local development corporation within the **City**, then;

63.4 The **Commissioner** whose **Agency** is a party in interest to the transaction, submitted bid, submitted proposal, contract, lease, permit, or license shall convene a hearing, upon not less than five (5) **Days'** written notice to the parties involved to determine if any penalties should attach for the failure of a person to testify.

63.5 If any non-governmental party to the hearing requests an adjournment, the **Commissioner** who convened the hearing may, upon granting the adjournment, suspend any contract, lease, permit, or license, pending the final determination pursuant to Article 63.7 without the **City** incurring any penalty or damages for delay or otherwise.

63.6 The penalties which may attach after a final determination by the **Commissioner** may include but shall not exceed:

63.6.1 The disqualification for a period not to exceed five (5) years from the date of an adverse determination for any person, or any entity of which such person was a member at the time the testimony was sought, from submitting bids for, or transacting business with, or entering into or obtaining any contract, lease, permit or license with or from the **City**; and/or

63.6.2 The cancellation or termination of any and all such existing **City** contracts, leases, permits or licenses that the refusal to testify concerns and that have not been assigned as permitted under this **Contract**, nor the proceeds of which pledged, to an unaffiliated and unrelated institutional lender for fair value prior to the issuance of the notice scheduling the hearing, without the **City** incurring any penalty or damages on account of such cancellation or termination; monies lawfully due for goods delivered, work done, rentals, or fees accrued prior to the cancellation or termination shall be paid by the **City**.

63.7 The **Commissioner** shall consider and address in reaching his/her determination and in assessing an appropriate penalty the factors in Articles 63.7.1 and 63.7.2. The **Commissioner** may also consider, if relevant and appropriate, the criteria established in Articles 63.7.3 and 63.7.4, in addition to any other information which may be relevant and appropriate:

63.7.1 The party's good faith endeavors or lack thereof to cooperate fully and faithfully with any governmental investigation or audit, including but not limited to the discipline, discharge, or disassociation of any person failing to testify, the production of accurate and complete books and records, and the forthcoming testimony of all other members, agents, assignees or fiduciaries whose testimony is sought.

63.7.2 The relationship of the person who refused to testify to any entity that is a party to the hearing, including but not limited to, whether the person whose testimony is sought has an ownership interest in the entity and/or the degree of authority and responsibility the person has within the entity.



Contract



63.7.3 The nexus of the testimony sought to the subject entity and its contracts, leases, permits or licenses with the City.

63.7.4 The effect a penalty may have on an unaffiliated and unrelated party or entity that has a significant interest in an entity subject to penalties under Article 63.6, provided that the party or entity has given actual notice to the **Commissioner** upon the acquisition of the interest, or at the hearing called for in Article 63.4, gives notice and proves that such interest was previously acquired. Under either circumstance the party or entity shall present evidence at the hearing demonstrating the potential adverse impact a penalty will have on such person or entity.

#### 63.8 Definitions:

63.8.1 The term "license" or "permit" as used in this Article 63 shall be defined as a license, permit, franchise or concession not granted as a matter of right.

63.8.2 The term "person" as used in this Article 63 shall be defined as any natural person doing business alone or associated with another person or entity as a partner, director, officer, principal or employee.

63.8.3 The term "entity" as used in this Article 63 shall be defined as any firm, partnership, corporation, association, joint venture, or person that receives monies, benefits, licenses, leases, or permits from or through the **City** or otherwise transacts business with the **City**.

63.8.4 The term "member" as used in this Article 63 shall be defined as any person associated with another person or entity as a partner, director, officer, principal or employee.

63.9 In addition to and notwithstanding any other provision of this **Contract**, the **Commissioner** may in his/her sole discretion terminate this **Contract** upon not less than three (3) **Days'** written notice in the event the **Contractor** fails to promptly report in writing to the **Commissioner** of the Department of Investigations ("DOI") of the **City** any solicitation of money, goods, requests for future employment or other benefit or thing of value, by or on behalf of any employee of the **City** or other person, firm, corporation or entity for any purpose which may be related to the procurement or obtaining of this **Contract**.

#### **ARTICLE 64. TERMINATION BY THE CITY**

64.1 In addition to termination pursuant to any other article of this **Contract**, the **Commissioner** may, at any time, terminate this **Contract**, a **Job Order**, or a portion of a **Job Order**, by written notice to the **Contractor**. In the event of termination, the **Contractor** shall, upon receipt of such notice, unless otherwise directed by the **Commissioner**:

64.1.1 Stop Work on the date specified in the notice;

- 64.1.2 Take such action as may be necessary for the protection and preservation of the **City's** materials and property;
- 64.1.3 Cancel all cancelable orders for material and equipment;



64.1.4 Assign to the **City** and deliver to the **Site** or another location designated by the **Commissioner**, any non-cancelable orders for material and equipment that is not capable of use except in the performance of this **Contract** and has been specifically fabricated for the sole purpose of this **Contract** and not incorporated in the **Work**;

64.1.5 Take no action which will increase the amounts payable by the City under this Contract.

64.2 In the event of termination by the **City** pursuant to this Article 64, payment to the **Contractor** shall be in accordance with Articles 64.2.1, 64.2.2 or 64.2.3, to the extent that each respective article applies.

64.2.1 For non-cancelable material and equipment that is not capable of use except in the performance of this **Contract** and has been specifically fabricated for the sole purpose of this **Contract**, but not yet incorporated in the **Work**, the **Contractor** shall be paid the lesser of the following, less salvage value:

64.2.1(a)(i) The Direct Cost, as defined in Article 64.2.3; or

64.2.1(a.)(ii) The fair and reasonable value, if less than Direct Cost, of such material and equipment, plus necessary and reasonable delivery costs.

64.2.1(a)(iii) In addition, the **Contractor** shall be paid five (5%) percent of the amount described in Article 64.2.1(a)(i) or Article 64.2.1(a)(ii), whichever applies.

64.2.2 Unit Price Contracts or Items: On all unit price **Contracts**, or on unit price items in a **Contract**, the **City** will pay the **Contractor** the sum of the amounts described in Articles 64.2.2(a) and 64.2.2(b), less all payments previously made pursuant to this **Contract**:

64.2.2(a) For all completed units, the unit price stated in the Contract, and

64.2.2(b) For units that have been ordered but are only partially completed, the **Contractor** will be paid:

64.2.2(b)(i) A pro rata portion of the unit price stated in the **Contract** based upon the percent completion of the unit and

64.2.2(b)(ii) For non-cancelable material and equipment, payment will be made pursuant to Article 64.2.1.

64.3 In no event shall any payments under this Article 64 exceed the Contract price for such items.

64.4 All payments pursuant to Article 64 shall be in the nature of liquidated damages and shall be accepted by the **Contractor** in full satisfaction of all claims against the **City**.

64.5 The City may deduct or set off against any sums due and payable pursuant to this Article 64, any deductions authorized by this Contract or by Law (including but not limited to liquidated damages) and any claims it may have against the Contractor. The City's exercise of the right to terminate the Contract pursuant to this Article 64 shall not impair or otherwise effect the City's right to assert any claims it may have against the Contractor.

Contract



#### **ARTICLE 65. CHOICE OF LAW, CONSENT TO JURISDICTION AND VENUE**

65.1 This **Contract** shall be deemed to be executed in the **City** regardless of the domicile of the **Contractor**, and shall be governed by and construed in accordance with the **Laws** of the State of New York and the **Laws** of the United States, where applicable.

65.2 The parties agree that any and all claims asserted against the **City** arising under this **Contract**or related thereto shall be heard and determined in the courts of the State of New York ("New York State Courts") located in the **City** and County of New York. To effect this **Contract** and intent, the **Contractor** agrees:

65.2.1 If the City initiates any action against the Contractor in Federal court or in a New York State Court, service of process may be made on the Contractor either in person, wherever such Contractor may be found, or by registered mail addressed to the Contractor at its address as set forth in this Contract, or to such other address as the Contractor may provide to the City in writing; and

65.2.2 With respect to any action between the **City** and the **Contractor** in a New York State Court, the **Contractor** hereby expressly waives and relinquishes any rights it might otherwise have:

65.2.2(a) To move to dismiss on grounds of forum non conveniens;

65.2.2(b) To remove to Federal Court; and

65.2.2(c) To move for a change of venue to a New York State Court outside New York County.

65.2.3 With respect to any action brought by the **City** against the **Contractor** in a Federal Court located in the **City**, the **Contractor** expressly waives and relinquishes any right it might otherwise have to move to transfer the action to a Federal Court outside the **City**.

65.2.4 If the **Contractor** commences any action against the **City** in a court located other than in the **City** and County of New York, upon request of the **City**, the **Contractor** shall either consent to a transfer of the action to a New York State Court of competent jurisdiction located in the **City** and County of New York or, if the Court where the action is initially brought will not or cannot transfer the action, the **Contractor** shall consent to dismiss such action without prejudice and may thereafter reinstate the action in a New York State Court of competent jurisdiction in New York County.

65.3 If any provision(s) of this Article 65 is held unenforceable for any reason, each and all other provision(s) shall nevertheless remain in full force and effect.

#### ARTICLE 66. PARTICIPATION IN AN INTERNATIONAL BOYCOTT



66.1 The **Contractor** agrees that neither the **Contractor** nor any substantially owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the Federal Export Administration Act of 1979, as amended, or the regulations of the United States Department of Commerce (Commerce Department) promulgated thereunder.

66.2 Upon the final determination by the Commerce Department or any other agency of the United States as to, or conviction of the **Contractor** or a substantially owned affiliated company thereof for participation in an international boycott in violation of the provisions of the Export Administration Act of 1979, as amended, or the regulations promulgated thereunder, the **Comptroller** may, at his/her option, render forfeit and void this **Contract**.

66.3 The **Contractor** shall comply in all respects, with the provisions of Section 6-114 of the Administrative Code and the rules and regulations issued by the **Comptroller** thereunder.

#### ARTICLE 67. LOCALLY BASED ENTERPRISE PROGRAM

67.1 This **Contract** is subject to the requirements of Section 6-108.1 of the Administrative Code and regulations promulgated thereunder. No construction contractor **Job Order** shall be awarded unless and until these requirements have been complied with in their entirety. However, compliance with this Article 67 is not required if the Agency sets Subcontractor Participation Goals for Minority – and Women – Owned Business Enterprise (M/WBE's)

67.2 Unless specifically waived by the **Commissioner** with the approval of the Division of Economic and Financial Opportunity of the **City** Department of Business Services, if any portion of the **Contract** is subcontracted, not less than ten (10%) percent of the total dollar amount of the **Contract** shall be awarded to locally based enterprises (LBEs); except that where less than ten (10%) percent of the total dollar amount of the **Contract** is subcontracted, such lesser percentage shall be so awarded.

67.3 The Contractor shall not require performance and payment bonds from LBE Subcontractors.

67.4 If the **Contractor** has indicated prior to award of a **Job Order** that no **Work** will be subcontracted, no **Work** shall be subcontracted without the prior approval of the **Commissioner**, which shall be granted only if the **Contractor** makes a good faith effort beginning at least six (6) weeks before the **Work** is to be performed to obtain LBE **Subcontractors** to perform the **Work**.

67.5 If the **Contractor** has not identified sufficient LBE **Subcontractors** prior to award, it shall sign a letter of compliance stating that it complies with Section 6-108.1 of the Administrative Code, recognizes that achieving the LBE requirement is a condition of its **Contract**, and shall submit documentation demonstrating its good faith efforts to obtain LBEs. After award, the **Contractor** shall begin to solicit LBE's to perform subcontracted **Work** at least six (6) weeks before the date such **Work** is to be performed and shall demonstrate that a good faith effort has been made to obtain LBEs on each subcontract until it meets the required percentage.

67.6 Failure of the **Contractor** to comply with the requirements of Section 6-108.1 of the Administrative Code and the regulations promulgated thereunder shall constitute a material breach of this **Contract**. Remedy for such breach may include the imposition of any or all of the following sanctions:

82



67.6.1 Reducing the **Contractor's** compensation by an amount equal to the dollar value of the percentage of the LBE subcontracting requirement not complied with;

- 67.6.2 Declaring the Contractor in default;
- 67.6.3 If the **Contractor** is an LBE, de-certifying and declaring the **Contractor** ineligible to participate in the LBE program for a period of up to three (3) years.

#### ARTICLE 68. ANTITRUST

68.1 The **Contractor** hereby assigns, sells, and transfers to the **City** all right, title, and interest in and to any claims and causes of action arising under the antitrust **Laws** of New York State or of the United States relating to the particular goods or services purchased or procured by the **City** under this **Contract**.

#### ARTICLE 69.MacBRIDE PRINCIPLES PROVISIONS

#### 69.1 Notice To All Prospective Contractors:

69.1.1 Local Law No. 34 of 1991 became effective on September 10, 1991 and added Section 6-115.1 of the Administrative Code. The local Law provides for certain restrictions on City Contracts to express the opposition of the people of the City to employment discrimination practices in Northern Ireland to promote freedom of work-place opportunity.

69.1.2 Pursuant to Section 6-115.1, prospective **Contractors** for **Contracts** to provide goods or services involving an expenditure of an amount greater than ten thousand (\$10,000.) dollars, or for construction involving an amount greater than fifteen thousand (\$15,000.) dollars, are asked to sign a rider in which they covenant and represent, as a material condition of their **Contract**, that any business operations in Northern Ireland conducted by the **Contractor** and any individual or legal entity in which the **Contractor** holds a ten (10%) percent or greater ownership interest in the **Contractor** will be conducted in accordance with the MacBride Principles of nondiscrimination in employment.

69.1.3 Prospective **Contractors** are not required to agree to these conditions. However, in the case of **Contracts** let by competitive sealed bidding, whenever the lowest responsible bidder has not agreed to stipulate to the conditions set forth in this notice and another bidder who has agreed to stipulate to such conditions has submitted a bid within five (5%) percent of the lowest responsible bid for a **Contract** to supply goods, services or contraction of comparable quality, the **Agency** shall refer such bids to the Mayor, the Speaker or other officials, as appropriate, who may determine, in accordance with applicable **Law**, that it is in the best interest of the **City** that the **Contract** be awarded to other than the lowest responsible pursuant to Section 313(b)(2) of the **City** Charter.

69.1.4 In the case of **Contracts** let by other than competitive sealed bidding, if a prospective **Contractor** does not agree to these conditions, no **Agency**, elected official or the **City** Council shall award the **Contract** to that bidder unless the **Agency** seeking to use the goods, services or construction certifies in writing that the **Contract** is necessary for the **Agency** to



perform its functions and there is no other responsible **Contractor** who will supply goods, services or construction of comparable quality at a comparable price.

69.2 In accordance with Section 6-115.1 of the Administrative Code, the **Contractor** stipulates that such **Contractor** and any individual or legal entity in which the **Contractor** holds a ten (10%) percent or greater ownership interest in the **Contractor** either:

69.2.1 Have no business operations in Northern Ireland, or

69.2.2 Shall take lawful steps in good faith to conduct any business operations they have in Northern Ireland in accordance with the MacBride Principles, and shall permit independent monitoring of their compliance with such principles.

69.3 For purposes of this Article, the following terms shall have the following meanings:

69.3.1 "MacBride Principles" shall mean those principles relating to nondiscrimination in employment and freedom of work-place opportunity which require employers doing business in Northern Ireland to:

69.3.1(a) increase the representation of individuals from under-represented religious groups in the workforce, including managerial, supervisory, administrative, clerical and technical jobs;

69.3.1(b) take steps to promote adequate security for the protection of employees from under-represented religious groups both at the work-place and while traveling to and from **Work**;

69.3.1(c) ban provocative religious or political emblems from the workplace;

69.3.1(d) publicly advertise all job openings and make special recruitment efforts to attract applicants from under-represented religious groups;

69.3.1(e) establish layoff, recall, and termination procedures which do not in practice favor a particular religious group;

69.3.1(f) abolish all job reservations, apprenticeship restrictions and different employment criteria which discriminate on the basis of religion;

69.3.1(g) develop training programs that will prepare substantial numbers of current employees from under-represented religious groups for skilled jobs, including the expansion of existing programs and the creation of new programs to train, upgrade, and improve the skills of workers from under-represented religious groups;

69.3.1(h) establish procedures to asses, identify, and actively recruit employees from under-represented religious groups with potential for further advancement; and

69.3.1(i) appoint a senior management staff member to oversee affirmative action efforts and develop a timetable to ensure their full implementation.



Contract

69.4 The Contractor agrees that the covenants and representations in Article 69.2 are material conditions to this Contract. In the event the Agency receives information that the Contractor who made the stipulation required by this Article 69 is in violation thereof, the Agency shall review such information and give the Contractor an opportunity to respond. If the Agency finds that a violation has occurred, the Agency shall have the right to declare the Contractor in default in default and/or terminate this Contract for cause and procure supplies, services or Work from another source in the manner the Agency deems proper. In the event of such termination, the Contractor shall pay to the Agency, or the Agency in its sole discretion may withhold from any amounts otherwise payable to the Contractor, the difference between the Contract price for the uncompleted portion of this Contract and the cost to the Agency of completing performance of this Contract either itself or by engaging another Contractor or Contractors. In the case of a requirement Contract, the Contractor shall be liable for such difference in price for the entire amount of supplies required by the Agency for the uncompleted term of Contractor's Contract. In the case of a construction Contract, the Agency shall also have the right to hold the Contractor in partial or total default in accordance with the default provisions of this Contract, and/or may seek debarment or suspension of the Contractor. The rights and remedies of the Agency hereunder shall be in addition to, and not in lieu of, any rights and remedies the Agency has pursuant to this Contract or by operation of Law.

#### ARTICLE 70. ELECTRONIC FILING/NYC DEVELOPMENT HUB

70.1 The **Contractor** shall electronically file all alteration type-2 and alteration type-3 applications via the New York City Development Hub Web site, except applications for the following types of minor alterations: enlargements, curb cuts, legalizations, fire alarms, builders pavement plans, and jobs filed on Landmark Preservation Commission calendared properties. All such filings must be professionally certified. Information about electronic filing via the New York City Development Hub is available on the **City** Department of Buildings Web site at www.nyc.gov/buildings.

#### **ARTICLE 71. PROHIBITION OF TROPICAL HARDWOODS**

71.1 Tropical hardwoods, as defined in Section 165 of the New York State Finance Law (Finance Law), shall not be utilized in the performance of this **Contract** except as expressly permitted by Section 165 of the Finance Law.

#### ARTICLE 72. CONFLICTS OF INTEREST

72.1 Section 2604 of the City Charter and other related provisions of the City Charter, the Administrative Code, and the Penal Law are applicable under the terms of this Contract in relation to conflicts of interest and shall be extended to Subcontractors authorized to perform Work, labor and services pursuant to this Contract and further, it shall be the duty and responsibility of the Contractor to so inform its respective Subcontractors. Notice is hereby given that, under certain circumstances, penalties may be invoked against the donor as well as the recipient of any form of valuable gift.

#### ARTICLE 73. MERGER CLAUSE



73.1 The written **Contract** herein, contains all the terms and conditions agreed upon by the parties hereto, and no other agreement, oral or otherwise, regarding the subject matter of this Contract shall be deemed to exist or to bind any of the parties hereto, or to vary any of the terms contained herein.

#### **ARTICLE 74. STATEMENT OF WORK**

74.1 The Contractor shall furnish all labor and materials and perform all Work in strict accordance with the Detailed Scope of Work and terms of this Contract.

#### **ARTICLE 75. COMPENSATION TO BE PAID TO CONTRACTOR**

75.1 The City will pay and the Contractor will accept in full consideration for the performance of the **Detailed Scope of Work**, the **Job Order** price calculated in accordance with the following:

The **Contractor** shall perform all Work required, necessary, proper for or incidental to completing the Detailed Scope of Work called for in each individual Job Order issued pursuant to this Contract for the unit prices set forth in the Unit Price Book (UPB) and the following Adjustment Factors:

a) Normal Working Hours 7:00 a.m. to 4:00 p.m. Monday to Friday:

# (Specify to four (4) decimal places)

b) Other Than Normal Working Hours 4:00 p.m. to 7:00 a.m. Monday to Friday, and all day Saturday, Sunday, Holidays:

(Specify to four (4) decimal places)

c) Non-Prepriced:

.VS00 (Specify to four (4) decimal places)

## **ARTICLE 76. ELECTRONIC FUNDS TRANSFER**

76.1 In accordance with Section 6-107.1 of the Administrative Code, the **Contractor** agrees to accept payments under this Contract from the City by electronic funds transfer (EFT). An EFT is any transfer of funds, other than a transaction originated by check, draft or similar paper instrument, which is initiated through an electronic terminal, telephonic instrument or computer or magnetic tape so as to order, instruct or authorize a financial institution to debit or credit an account. Prior to the first payment made under this **Contract**, the **Contractor** shall designate one financial institution or other authorized payment agent and shall complete the attached "EFT Vendor Payment Enrollment Form" in order to provide the Commissioner of the City Department of Finance with information necessary for the **Contractor** to receive electronic funds transfer payments through a designated financial institution or authorized payment agent. The crediting of the amount of a payment to the appropriate account on the



books of a financial institution or other authorized payment agent designated by the **Contractor** shall constitute full satisfaction by the **City** for the amount of the payment under this **Contract**. The account information supplied by the **Contractor** to facilitate the electronic funds transfer shall remain confidential to the fullest extent provided by **Law**.

76.2 The **Commissioner** may waive the application of the requirements of this Article 76 to payments on contracts entered into pursuant to Section 315 of the **City** Charter. In addition, the Commissioner of the Department of Finance and the **Comptroller** may jointly issue standards pursuant to which the **Agency** may waive the requirements of this Article 76 for payments in the following circumstances: (i) for individuals or classes of individuals for whom compliance imposes a hardship; (ii) for classifications or types of checks; or (iii) in other circumstances as may be necessary in the interest of the **City**.

#### **ARTICLE 77. RECORDS RETENTION**

77.1 The **Contractor** agrees to retain all books, records, and other documents relevant to this **Contract** for six years after the final payment or termination of this **Contract**, whichever is later. **City**, state, and federal auditors and any other persons duly authorized by the **City** shall have full access to and the right to examine any such books, records, and other documents during the retention period.

#### **END OF ARTICLES**

#### SIGNATURES OF THE CONTRACT



Contract

IN WITNESS WHEREOF, the Commissioner, on behalf of the City of New York, and the Contractor, have executed FIVE COPIES of this Contract, three copies of which are to remain with the Commissioner, one other to be filed with the Comptroller of the City, and the fifth to be delivered to the Contractor.

**ØF NEW YORK** By: HSSociate Commissioner CONTRACTOR: By **OFFICER OF THE FIRM OR CORPORATION** AUTH (Where Contractor is a Corporation, add): Attest: (seal) SECRETARY

ACKNOWLEDGMENT BY CORPORATION State of N-CW OTH County of Over SS:

Contract

14:13: 13. 3 . S. .

On this 13 day of 144, 2016 before me personally came STephen Grano Tro

who affirms or being by me duly sworn, did depose and say that he/she resides in

the City of 1005 WfcKoFFACE: that he/she is the

of the <u>ARCALEA</u> <u>Elec</u> <u>Co</u> <u>Tric</u>the corporation described in and which executed the foregoing instrument; that s/he knows the seal of said corporation; that one of the seals affixed to said instrument is such seal; that it was so affixed by order of the directors of said corporation, and that s/he signed his name thereto by like order.

VICTORIAAYO-VAUGHAN Notary Public, State of New York Registration #01AY5014042 Qualified in Queens County Commission Expires July 15, <u>20</u> ACKNOWLEDGMENT BY COMMISSIONER

State of New York, County of Quee	ens ss:			
On this <u>B</u> day of <u>Ma</u>	N .2016	•		
before me personally came <u>Er</u>	<u>ic boc</u>	rstln		
to me known, and known to be Construction of The City of New executed the foregoing instrumen	e the Commission		1110 IIII4 4	
same as <b>Commissioner</b> for the p	urposes therein mentic	oned.		
VICTORIA AYO-VAUGHAN				
Notary Public, State of New York Registration #01AY5014042	Public or	Commissioner	of	Deeds
Qualified in Queens County D	89			

ACKNOWLEDGMENT BY PARTNERSHIP				
State of	County of	SS:		
On this day of				
before me personally came _		, to pre known		
	mber of he acknowledged to pose merein mention Public or Commission	50.	e firm described in and which executed the ubscribed the name of said firm thereto on Victoria AYO-VAUGHAN Netary Public, State of New York Registration #01AY5014042	
.[	ACKNOWLEDG	MENT BY IND	Commission Expires July 15, 2015	
State of	County of	ss:	00.000 A 00 A	
On this day of before me personally came	,_20	éno la	k jitav	
tome known and known to be he/she acknowledged to me th	to be the same personat he/she executed t	on described and the same for the pi	who executed the forgoing instrument and urposes therein mentioned.	

Notary Public or Commissioner of Deeds

## AUTHORITY

MAYOR'S CERTIFICATE NO:	CBX:_		DATED
RUDGET DIRECTOR'S CERTIFICAT	E NO:	CP/CAS:	DATED

BUDGET DIRECTOR'S CERTIFICATE NO:

#### APPROPRIATION

## COMMISSIONER'S CERTIFICATE

In conformity with the provisions of Section 6-101 of the Administrative Code of the City of New York, it is herby certified that the estimated cost of the work, materials and supplies required by the within Contract, accounting to:

000,000.00 Cran Five million GOLLAR) Is chargeable to the fund of the Department of Design and Construction Budget Code(s): I hereby certify that the specifications contained herein comply with the terms and conditions of the FY JOLO BUDGET HSSOcial Commissioner of the Department of Design and Construction COMPTROLLER'S CERTIFICATION The City of New York \_

In pursuance of the provisions of Section 6-101 of the Administrative Code of the City of New York, it is hereby certified that there remains unapplied and unexpended a balance of the above mentioned fund applicable to this Contract sufficient to pay the estimated expense of executing the same.

Comptroller

#### PERFORMANCE BOND

## KNOW ALL PERSONS BY THESE PRESENTS, That we,

hereinafter referred to as the "Principal", and \_\_\_\_\_\_

hereinafter referred to as the "Surety" ("Sureties") are held and firmly bound to THE CITY OF NEW YORK, hereinafter referred to as the "City" or to its successors and assigns, in the penal sum of

.

(\$\_\_\_\_\_) Dollars, lawful money of the United States, for the payment of which said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal is about to enter, or has entered, into a Contract in writing with the City for

a copy of which Contract is annexed to and hereby made a part of this bond as though herein set forth in full;

DEPARTMENT OF DESIGN AND CONSTRUCTION

FEBRUARY 2009

NOW, THEREFORE, the conditions of this obligation are such that if the Principal, his or its representatives or assigns, shall well and faithfully perform the said Contract and all modifications, amendments, additions and alterations thereto that may hereafter be made, according to its terms and its true intent and meaning, including repair and/or replacement of defective work and guarantees of maintenance for the periods stated in the Contract, and shall fully indemnify and save harmless the City from all cost and damage which it may suffer by reason of failure so to do, and shall fully reimburse and repay the City for all outlay and expense which the City may incur in making good any such default, and shall protect the said City of New York against, and pay any and all amounts, damages, costs and judgments which may or shall be recovered against said City or its officers or agents of which the said City of New York may be called upon to pay any person or corporation by reason of any damages arising or growing out of the doing of said work, or the repair or maintenance thereof, or the manner of doing the same, or the neglect of the said PRINCIPAL, or his (their, its) agents or servants, or the improper performance of the said work by the said PRINCIPAL, or his (their, its) agents or servants, or the infringement of any patent or patent rights by reason of the use of any materials furnished or work done as aforesaid or otherwise, then this obligation shall be null and void, otherwise to remain in full force and effect.

The Surety (Sureties), for value received, hereby stipulates and agrees, if requested to do so by the City, to fully perform and complete the Work to be performed under the Contract, pursuant to the terms, conditions, and covenants thereof, if the City determines that the Principal, for any cause, has failed or neglected to fully perform and complete such Work. The Surety (Sureties) further agrees to commence and diligently perform the Work specified in the Contract, including physical site work, within twenty-five (25) business days after written notice thereof from the City and to complete all Work within such time as the City may fix. The Surety and the City reserve all rights and defenses each may have against the other; provided, however, that the Surety expressly agrees that its reservation of rights shall not provide a basis for non-performance of its obligation to commence and to complete all Work as provided herein.

The Surety (Sureties), for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of said Surety (Sureties) and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition, or change in or to the said Contract or Work to be performed thereunder, or by any payment thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any Work to be performed or any moneys due or to become due thereunder, and said Surety (Sureties) does hereby waive notice of any and all of such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers, and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to said Surety (Sureties) as though done or omitted to be done by or in relation to said Principal.

DEPARTMENT OF DESIGN AND CONSTRUCTION

IN WITNESS WHEREOF, the Principal and the Surety (Sureties) have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereunto affixed and these presents to be signed by their proper officers, this \_\_\_\_\_\_ day of \_\_\_\_\_\_.

(Seal)				
			Principal	(L.S.)
•		Ву:		
(Seal)				
			Surety	
		Ву:		
(Seal)				
· ·		••••••••••••••••••••••••••••••••••••••	Surety	
•		Ву:		
(Seal)			ı	
		·····	Surety	
		Ву:		*****
Bond Premium Rate	and the second statement of the second			

Bond Premium Cost

If the Contractor (Principal) is a partnership, the bond should be signed by each of the individuals who are partners.

If the Contractor (Principal) is a corporation, the bond should be signed in its correct corporate name by a duly authorized officer, agent, or attorney-in-fact.

There should be executed an appropriate number of counterparts of the bond corresponding to the number of counterparts of the Contract.

of

#### ACKNOWLEDGMENT OF PRINCIPAL, IF A CORPORATION

State of \_\_\_\_\_ County of \_\_\_\_\_ ss:

On this \_\_\_\_\_ day of \_\_\_\_\_, before me personally came \_\_\_\_\_\_ to me known, who, being by me duly sworn did depose and say that he resides at \_\_\_\_\_\_

that he is the

the corporation described in and which executed the foregoing instrument; that he knows the seal of said corporation; that one of the seals affixed to said instrument is such seal; that it was so affixed by order of the directors of said corporation, and that he signed his name thereto by like order.

Notary Public or Commissioner of Deeds

#### ACKNOWLEDGMENT OF PRINCIPAL, IF A PARTNERSHIP

State of \_\_\_\_\_ County of \_\_\_\_\_ ss:

On this \_\_\_\_\_ day of \_\_\_\_\_, before me personally appeared \_\_\_\_\_

to me that he executed the same as and for the act and deed of said firm.

Notary Public or Commissioner of Deeds

#### ACKNOWLEDGMENT OF PRINCIPAL, IF AN INDIVIDUAL

State of \_\_\_\_\_\_ County of \_\_\_\_\_\_ ss:

On this \_\_\_\_\_\_ day of \_\_\_\_\_\_, before me personally appeared \_\_\_\_\_\_ to me known, and known to me to be the person described in and who executed the foregoing instrument; and acknowledged that he executed the same.

Notary Public or Commissioner of Deeds

Each executed bond should be accompanied by: (a) appropriate acknowledgments of the respective parties; (b) appropriate duly certified copy of Power of Attorney or other certificate of authority where bond is executed by agent, officer or other representative of Principal or Surety; (c) a duly certified extract from By-Laws or resolutions of Surety under which Power of Attorney or other certificate of authority of its agent, officer or representative was issued, and (d) certified copy of latest published financial statement of assets and liabilities of Surety.

Affix Acknowledgments and Justification of Sureties.

#### **PAYMENT BOND 1**

#### PAYMENT BOND

#### KNOW ALL MEN BY THESE PRESENTS, That we,

hereinafter referred to as the "Principal", and \_\_\_\_\_\_

hereinafter referred to as the "Surety" ("Sureties") are held and firmly bound to THE CITY OF NEW YORK, hereinafter referred to as the "City" or to its successors and assigns, in the penal sum of

.

(\$\_\_\_\_\_) Dollars, lawful money of the United States, for the payment of which said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

· · ·

WHEREAS, the Principal is about to enter, or has entered, into a Contract in writing with the City for

a copy of which Contract is annexed to and hereby made a part of this bond as though herein set forth in full;

.

DEPARTMENT OF DESIGN AND CONSTRUCTION

•,

#### PAYMENT BOND 2

NOW, THEREFORE, the conditions of this obligation are such that if the Principal, his or its representatives or assigns and other Subcontractors to whom Work under this Contract is sublet and his or their successors and assigns shall promptly pay or cause to be paid all lawful claims for

(a) Wages and compensation for labor performed and services rendered by all persons engaged in the prosecution of the Work under said Contract, and any amendment or extension thereof or addition thereto, whether such persons be agents servants or employees of the Principal or any such Subcontractor, including all persons so engaged who perform the work of laborers or mechanics at or in the vicinity of the site of the Project regardless of any contractual relationship between the Principal or such Subcontractors, or his or their successors or assigns, on the one hand and such laborers or mechanics on the other, but not including office employees not regularly stationed at the site of the project; and

(b) Materials and supplies (whether incorporated in the permanent structure or not), as well as teams, fuels, oils, implements or machinery furnished, used or consumed by said Principal or any subcontractor at or in the vicinity of the site of the Project in the prosecution of the Work under said Contract and any amendment or extension thereof or addition thereto; then this obligation shall be void, otherwise to remain in full force and effect.

This bond is subject to the following additional conditions, limitations and agreements:

(a) The Principal and Surety (Sureties) agree that this bond shall be for the benefit of any materialmen or laborer having a just claim, as well as the City itself.

(b) All persons who have performed labor, rendered services or furnished materials and supplies, as aforesaid, shall have a direct right of action against the Principal and his, its or their successors and assigns, and the Surety (Sureties) herein, or against either or both or any of them and their successors and assigns. Such persons may sue in their own name, and may prosecute the suit to judgment and execution without the necessity of joining with any other persons as party plaintiff.

(c) The Principal and Surety (Sureties) agree that neither of them will hold the City liable for any judgment for costs of otherwise, obtained by either or both of them against a laborer or materialman in a suit brought by either a laborer or materialman under this bond for moneys allegedly due for performing work or furnishing material.

99

(d) The Surety (Sureties) or its successors and assigns shall not be liable for any compensation recoverable by an employee or laborer under the Workmen's Compensation Law.

(e) In no event shall the Surety (Sureties), or its successors or assigns, be liable for a greater sum than the penalty of this bond or be subject to any suit, action or proceeding hereon that is instituted by any person, firm, or corporation hereunder later than two years after the complete performance of said Contract and final settlement thereof.

The Principal, for himself and his successors and assigns, and the Surety (Sureties), for itself and its successors and assigns, do hereby expressly waive any objection that might be interposed as to the right of the City to require a bond containing the foregoing provisions, and they do hereby further expressly waive any defense which they or either of them might interpose to an action brought hereon by any person, firm or corporation, including subcontractors, materialmen and third persons, for work, labor, services, supplies or material performed rendered, or furnished as aforesaid upon the ground that there is no law authorizing the City to require the foregoing provisions to be placed in this bond.

And the Surety (Sureties), for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of said Surety (Sureties), and its bonds shall be in no way impaired or affected by any extension of time, modification, omission, addition, or change in or of the said Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any part thereof, or of any Work to be performed, or any moneys due to become due thereunder and said Surety (Sureties) does hereby waive notice of any and all of such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers, and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, Subcontractors, and other transferees shall have the same effect as to said Surety (Sureties) as though done or omitted to be done or in relation to said Principal.

100

## PAYMENT BOND 4



IN WITNESS HEREOF, the Principal and the Surety (Sureties) have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereunto affixed and these presents to be signed by their proper officers, this \_\_\_\_\_\_ day of \_\_\_\_\_\_.

(Seal)	(L.S.)
	Principal
	Ву:
(Seal)	Surety
	Ву:
(Seal)	Surety
	Ву:
(Seal)	
	Surety
	Ву:
(Seal)	
	Surety
	Ву:

If the Contractor (Principal) is a partnership, the bond should be signed by each of the individuals who are partners.

If the Contractor (Principal) is a corporation, the bond should be signed in its correct corporate name by a duly authorized officer, agent, or attorney-in-fact.

There should be executed an appropriate number of counterparts of the bond corresponding to the number of counterparts of the Contract.

**PAYMENT BOND 5** 

of

## ACKNOWLEDGMENT OF PRINCIPAL, IF A CORPORATION

State of \_\_\_\_\_ County of \_\_\_\_\_ ss:

On this \_\_\_\_\_ day of \_\_\_\_\_, before me personally came \_\_\_\_\_

to me known, who, being by me duly sworn did depose and say that he resides at \_\_\_\_\_

that he is the

the corporation described in and which executed the foregoing instrument; that he knows the seal of said corporation; that one of the seals affixed to said instrument is such seal; that it was so affixed by order of the directors of said corporation, and that he signed his name thereto by like order.

Notary Public or Commissioner of Deeds

## ACKNOWLEDGMENT OF PRINCIPAL, IF A PARTNERSHIP

State of \_\_\_\_\_ County of \_\_\_\_\_ ss:

On this \_\_\_\_\_ day of \_\_\_\_\_, before me personally appeared \_\_\_\_\_

to me known, and known to me to be one of the members of the firm of

described in and who executed the foregoing instrument; and he acknowledged to me that he executed the same as and for the act and deed of said firm.

Notary Public or Commissioner of Deeds

## ACKNOWLEDGMENT OF PRINCIPAL, IF AN INDIVIDUAL

State of \_\_\_\_\_ County of \_\_\_\_\_ ss:

On this \_ day of \_\_\_\_\_, before me personally appeared to me known, and known to me to be the person described in and who executed the foregoing instrument; and acknowledged that he executed the same.

## Notary Public or Commissioner of Deeds

Each executed bond should be accompanied by: (a) appropriate acknowledgments of the respective parties; (b) appropriate duly certified copy of Power of Attorney or other certificate of authority where bond is executed by agent, officer or other representative of Principal or Surety; (c) a duly certified extract from By-Laws or resolutions of Surety under which Power of Attorney or other certificate of authority of its agent, officer or representative was issued, and (d) certified copy of latest published financial statement of assets and liabilities of Surety.

#### \* \* \* \* \* \* \* \*

Affix Acknowledgments and Justification of Sureties

DEPARTMENT OF DESIGN AND CONSTRUCTION

## This page intentionally left blank

#### LABOR LAW §220 PREVAILING WAGE SCHEDULE

Workers, Laborers and Mechanics employed on a public work project must receive not less than the prevailing rate of wage and benefits for the classification of work performed by each upon such public work. Pursuant to Labor Law §220 the Comptroller of the City of New York has promulgated this schedule solely for Workers, Laborers and Mechanics engaged by private contractors on New York City public work contracts.

This schedule is a compilation of separate determinations of the prevailing rate of wage and supplements made by the Comptroller for each trade classification listed herein pursuant to New York State Labor Law section 220 (5). The source of the wage and supplement rates, whether a collective bargaining agreement, survey data or other, is listed at the end of each classification.

Agency Chief Contracting Officers should contact the Bureau of Labor Law's Classification Unit with any questions concerning trade classifications, prevailing rates or prevailing practices with respect to procurement on New York City public works contracts. Contractors are advised to review the Comptroller's Prevailing Wage Schedule before bidding on public works contracts. Contractors with respect to public works concerning trade classifications, prevailing rates or prevailing practices with respect to public works contracts in the procurement stage must contact the contracting agency responsible for the procurement.

Any error as to compensation under the prevailing wage law or other information as to trade classification, made by the contracting agency in the contract documents or in any other communication, will not preclude a finding against the contractor of prevailing wage violation.

Any questions concerning trade classifications, prevailing rates or prevailing practices on New York City public works contracts that have already been awarded may be directed to the Bureau of Labor Law's Classification Unit by calling (212) 669-7974. All callers must have the agency name and contract registration number available when calling with questions on public works contracts. Please direct all other compliance issues to: Bureau of Labor Law, Attn: Wasyl Kinach, P.E., Office of the Comptroller, 1 Centre Street, Room 1122, New York, N.Y. 10007; Fax (212) 669-4002.

The appropriate schedule of prevailing wages and benefits must be posted at all public work sites pursuant to Labor Law §220 (3-a) (a).

This schedule is applicable to work performed during the effective period, unless otherwise noted. Changes to this schedule are published on our web site www.comptroller.nyc.gov. Contractors must pay the wages and supplements in effect when the worker, laborer, mechanic performs the work. Preliminary schedules for future one-year periods appear in the City Record on or about June 1 each succeeding year. Final schedules appear on or about July 1 in the City Record and on our web site www.comptroller.nyc.gov.

The Comptroller's Office has attempted to include all overtime, shift and night differential, Holiday, Saturday, Sunday or other premium time work. However, this schedule does not set forth every prevailing practice with respect to such rates with which employers must comply. All such practices are nevertheless part of the employer's prevailing wage obligation and contained in the collective bargaining agreements of the prevailing wage unions. These collective bargaining agreements are available for inspection by appointment. Requests for appointments may be made by calling (212) 669-4443, Monday through Friday between the hours of 9 a.m. and 5 p.m.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 1 of 86

Prevailing rates and ratios for apprentices are attached to this schedule in the Appendix. Pursuant to Labor Law §220 (3-e), only apprentices who are individually registered in a bona fide program to which the employer contractor is a participant, registered with the New York State Department of Labor, may be employed on a public work project. Workers who are not journey persons or not registered apprentices pursuant to Labor Law §220 (3-e) may not be substituted for apprentices and must be paid as journey persons.

Public Work construction, reconstruction, demolition, excavation, rehabilitation, repair, renovation, alteration, or improvement contracts awarded pursuant to a Project Labor Agreement ("PLA") in accordance with Labor Law section 222 may have different labor standards for shift, premium and overtime work. Please refer to the PLA's pre-negotiated labor agreements for wage and benefit rates applicable to work performed outside of the regular workday. More information is available at the Mayor's Office of Contract Services (MOCS) web page at http://www.nyc.gov/html/mocs/html/vendors/pla.shtml.

All the provisions of Labor Law section 220 remain applicable to PLA work including, but not limited to, the enforcement of prevailing wage requirements by the Comptroller; however, we will enforce shift, premium, overtime and other non-standard rates as they appear in a project's pre-negotiated labor agreement.

In order to meet their obligation to provide prevailing supplemental benefits to each covered employee, employers must either:

- 1) Provide bona-fide benefits which cost the employer no less than the prevailing supplemental benefits rate; or
- 2) Supplement the employee's hourly wage by an amount no less than the prevailing supplemental benefits rate; or
- 3) Provide a combination of bona-fide benefits and wage supplements which cost the employer no less than the prevailing supplemental benefits rate in total.

Particular attention should be given to the supplemental benefits requirement. Although in most instances the payment or provision for supplemental benefits is for each hour worked, some classifications require the payment or provision of supplemental benefits for each hour paid. Consequently, some prevailing practices require benefits to be purchased at the overtime, shift differential, Holiday, Saturday, Sunday or other premium time rate.

## Benefits are paid for <u>EACH HOUR WORKED</u> unless otherwise noted.

Wasyl Kinach, P.E. Director of Classifications Bureau of Labor Law

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 2 of 86

## TABLE OF CONTENTS

CLASSIFICATION	PAGE
ASBESTOS HANDLER	5
BLASTER	5
BOILERMAKER	7
BRICKLAYER	8
CARPENTER - BUILDING COMMERCIAL	
CARPENTER - HEAVY CONSTRUCTION WORK	
CARPENTER - SIDEWALK SHED, SCAFFOLD AND HOIST	
CEMENT & CONCRETE WORKER	
CEMENT MASON	
CORE DRILLER	
DERRICKPERSON AND RIGGER	
DIVER	15
DOCKBUILDER - PILE DRIVER	
DRIVER: TRUCK (TEAMSTER)	
ELECTRICIAN	
ELECTRICIAN - ALARM TECHNICIAN	
ELECTRICIAN-STREET LIGHTING WORKER	
ELEVATOR CONSTRUCTOR	24
ELEVATOR REPAIR & MAINTENANCE	
ENGINEER	
ENGINEER - CITY SURVEYOR AND CONSULTANT	
ENGINEER - FIELD (BUILDING CONSTRUCTION)	
ENGINEER - FIELD (HEAVY CONSTRUCTION)	
ENGINEER - FIELD (STEEL ERECTION)	
ENGINEER - OPERATING	
FLOOR COVERER	
GLAZIER	
GLAZIER - REPAIR & MAINTENANCE	
HEAT AND FROST INSULATOR	
HOUSE WRECKER	
IRON WORKER - ORNAMENTAL	
IRON WORKER - STRUCTURAL	
LABORER	
LANDSCAPING	50

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 3 of 86

MARBLE MECHANIC	
MASON TENDER	
MASON TENDER (INTERIOR DEMOLITION WORKER)	
METALLIC LATHER	55
MILLWRIGHT	
MOSAIC MECHANIC	
PAINTER	
PAINTER - SIGN	58
PAINTER - STRIPER	
PAINTER - STRUCTURAL STEEL	60
PAPERHANGER	
PAVER AND ROADBUILDER	
PLASTERER	64
PLASTERER - TENDER	65
PLUMBER	65
PLUMBER (MECHNICAL EQUIPMENT AND SERVICE)	67
PLUMBER (RESIDENTIAL RATES FOR 1, 2 AND 3 FAMILY HOME CONSTRUCTION)	67
PLUMBER: PUMP & TANK	68
POINTER - WATERPROOFER, CAULKER MECHANIC (EXTERIOR BUILDING RENOVATION)	
ROOFER	70
SANDBLASTER - STEAMBLASTER	
SHEET METAL WORKER	
SHEET METAL WORKER - SPECIALTY	
SHIPYARD WORKER	
SIGN ERECTOR	
STEAMFITTER	75
STEAMFITTER - REFRIGERATION AND AIR CONDITIONER	
STONE MASON - SETTER	
TAPER	
TELECOMMUNICATION WORKER	81
TILE FINISHER	82
TILE LAYER - SETTER	
TIMBERPERSON	
TUNNEL WORKER	
WELDER	

## **ASBESTOS HANDLER**

(Hazardous Material; Disturbs, removes, encapsulates, repairs, or encloses friable asbestos material)

## **Asbestos Handler**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$36.00 Supplemental Benefit Rate per Hour: \$15.95

## **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Sunday. Time and one half the regular hourly rate after 40 hours in any work week.

## **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day Good Friday Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day Easter

## **Paid Holidays**

None

(Local #78 and Local #12A)

## **BLASTER**

## **Blaster**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$46.89 Supplemental Benefit Rate per Hour: \$41.19

## **Blaster (Hydraulic)**

Effective Period: 7/1/2015 - 6/30/2016



Wage Rate per Hour: \$47.71 Supplemental Benefit Rate per Hour: \$41.19

#### **Blaster - Trac Drill Hydraulic**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$42.25 Supplemental Benefit Rate per Hour: \$41.19

## Blaster - Wagon: Air Trac: Quarry Bar: Drillrunners

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$41.46 Supplemental Benefit Rate per Hour: \$41.19

## **Blaster - Operators of Jack Hammers**

Chippers: Spaders: Concrete Breakers: and all other pneumatic tools of like usage: Walk Behind Self Propelled Hydraulic Asphalt and Concrete Breakers: Hydro (Water) Demolition

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$40.42 Supplemental Benefit Rate per Hour: \$41.19

#### **Blaster - Powder Carriers**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$36.53 Supplemental Benefit Rate per Hour: \$41.19

## Blaster - Hydraulic Trac Drill Chuck Tender

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$35.25 Supplemental Benefit Rate per Hour: \$41.19

#### Blaster - Chuck Tender & Nipper

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$34.50 Supplemental Benefit Rate per Hour: \$41.19

## Blaster - Magazine Keepers: (Watch Person)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$20.68 Supplemental Benefit Rate per Hour: \$41.19



Magazine Keepers:

Time and one half for work performed in excess of forty (40) hours per week and for work performed on Saturdays, Sundays and Holidays.

All Other Employees:

Time and one-half for the first eight hours of work on Saturday and for Make-up Time. Double time for all hours over eight Monday through Friday (except make-up hours) and for all hours worked on Sunday and Holidays.

## **Overtime**

Double time the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day

Paid Holidays

## Shift Rates

A single shift shall be 8 hours plus an unpaid lunch, starting at 8:00 A.M (or between 6:00 A.M. and 10:00 A.M. on weekdays). When two (2) shifts are employed, each shift shall be 8 hours plus  $\frac{1}{2}$  hour unpaid lunch. When three (3) shifts are employed, each shift will work seven and one-half (7  $\frac{1}{2}$ ) hours, but will be paid for eight (8) hours, since only one-half ( $\frac{1}{2}$ ) hour is allowed for mealtime. When two (2) or more shifts are employed, single time will be paid for each shift. The first 8 hours of any and all work performed Monday through Friday inclusive of any off-shift shall be at the single time rate.

(Local #29)

## BOILERMAKER

## **Boilermaker**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$51.56 Supplemental Benefit Rate per Hour: \$41.69 Supplemental Note: For time and one half overtime - \$61.94 For double overtime - \$82.18

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 7 of 86

### **Overtime Description**

For Repair and Maintenance work: Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. For New Construction work: Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Saturday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Columbus Day Election Day Veteran's Day Thanksgiving Day Christmas Day

Quadruple time the regular rate for work on the following holiday(s). Labor Day

### **Paid Holidays**

Good Friday Day after Thanksgiving Day before Christmas Day before New Year's Day

### **Shift Rates**

When shifts are required, the first shift shall work eight (8) hours at the regular straight-time hourly rate. The second shift shall work seven and one-half (7 ½) hours and receive eight hours at the regular straight time hourly rate plus twenty-five cents (\$0.25) per hour. The third shift shall work seven (7) hours and receive eight hours at the regular straight time hourly rate plus fifty cents (\$0.50) per hour. A thirty (30) minute lunch period shall not be considered as time worked. Work in excess of the above shall be paid overtime at the appropriate new construction work or repair work overtime wage and supplemental benefit hourly rate.

(Local #5)

## BRICKLAYER

### **Bricklayer**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$48.91

Supplemental Benefit Rate per Hour: \$28.03

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

## Paid Holidays

None

#### **Shift Rates**

Overtime rates to be paid outside the regular scheduled work day.

(Bricklayer District Council)

## **CARPENTER - BUILDING COMMERCIAL**

### **Building Commercial**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$50.50 Supplemental Benefit Rate per Hour: \$45.88

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Washington's Birthday Memorial Day

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 9 of 86

Independence Day Labor Day **Columbus Day Presidential Election Day Thanksgiving Day** Day after Thanksgiving Christmas Day

#### Paid Holidays None

#### Shift Rates

The second shift will receive one hour at the double time rate of pay for the last hour of the shift; eight hours pay for seven hours of work, nine hours pay for eight hours of work. There must be a first shift in order to work a second shift.

(Carpenters District Council)

## **CARPENTER - HEAVY CONSTRUCTION WORK**

(Construction of Engineering Structures and Building Foundations)

#### **Heavy Construction Work**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$50.50 Supplemental Benefit Rate per Hour: \$46.65

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day **President's Day Memorial Day** Independence Day Labor Day **Columbus Day Presidential Election Day Thanksgiving Day Christmas Day** 

PUBLISH DATE: 7/1/2015

Page 10 of 86 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016

### Paid Holidays

None

#### **Shift Rates**

Off shift work commencing between 5:00 P.M. and 11:00 P.M. shall work eight and one half hours allowing for one half hour for lunch. The wage rate shall be 113% of the straight time hourly wage rate.

(Carpenters District Council)

## **CARPENTER - SIDEWALK SHED, SCAFFOLD AND HOIST**

#### Carpenter - Hod Hoist

(Assisted by Mason Tender)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$49.60 Supplemental Benefit Rate per Hour: \$43.00



#### Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Day after Thanksgiving Christmas Day

Paid Holidays None

#### **Shift Rates**

The second shift will receive one hour at the double time rate of pay for the last hour of the shift; eight hours pay for seven hours of work, nine hours pay for eight hours of work. There must be a first shift in order to work a second shift.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 11 of 86

(Carpenters District Council)

## **CEMENT & CONCRETE WORKER**

#### Cement & Concrete Worker

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$42.48 Supplemental Benefit Rate per Hour: \$26.57 Supplemental Note: \$29.32 on Saturdays; \$32.07 on Sundays & Holidays

#### **Overtime Description**

Time and one half the regular rate after 7 hour day (time and one half the regular rate after an 8 hour day when working with Dockbuilders on pile cap forms and for work below street level to the top of the foundation wall, not to exceed 2 feet or 3 feet above the sidewalk-brick shelf, when working on the foundation and structure.)

#### **Overtime**

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day

#### **Paid Holidays**

1/2 day before Christmas Day 1/2 day before New Year's Day

#### **Shift Rates**

On shift work extending over a twenty-four hour period, all shifts are paid at straight time.

(Cement Concrete Workers District Council)

## **CEMENT MASON**

### **Cement Mason**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$38.88 Supplemental Benefit Rate per Hour: \$39.80 Supplemental Note: For time and one half overtime - \$49.05; For double overtime - \$58.30

#### **Overtime Description**

Time and one-half the regular rate after an 8 hour day, double time the regular rate after 10 hours. Time and onehalf the regular rate on Saturday, double time the regular rate after 10 hours. Double time the regular rate on Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day



Any worker who reports to work on Christmas Eve or New Year's Eve pursuant to his employer's instruction shall be entitled to three (3) hours afternoon pay without working.

#### **Shift Rates**

For an off shift day, (work at times other than the regular 7:00 A.M. to 3:30 P.M. work day) a cement mason shall be paid at the regular hourly rate plus a 25% per hour differential. Four Days a week at Ten (10)hour day.

(Local #780)

## **CORE DRILLER**

#### Core Driller

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$36.82 Supplemental Benefit Rate per Hour: \$22.69

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 13 of 86

#### **Core Driller Helper**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$29.44 Supplemental Benefit Rate per Hour: \$22.69

#### Core Driller Helper(Third year in the industry)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$26.50 Supplemental Benefit Rate per Hour: \$22.69

#### Core Driller Helper (Second year in the industry)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$23.55 Supplemental Benefit Rate per Hour: \$22.69

### Core Driller Helper (First year in the industry)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$20.61 Supplemental Benefit Rate per Hour: \$22.69

#### **Overtime Description**

Time and one half the regular rate for work on a holiday plus Holiday pay when worked.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Time and one half the regular rate for work on the following holiday(s).

#### Paid Holidays

New Year's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

#### Shift Rates

The shift day shall be the continuous eight and one-half ( $8\frac{1}{2}$ ) hours from 6:00 A.M. to 2:30 P.M. and from 2:30 P.M. to 11:00 P.M., including one-half ( $\frac{1}{2}$ ) hour of employees regular rate of pay for lunch. When two (2) or more shifts are employed, single time shall be paid for each shift, but those employees employed on a shift other than from 8:00 A.M. to 5:00 P.M. shall, in addition, receive seventy-five cents (\$0.75) per hour differential for each hour worked. When three (3) shifts are needed, each shift shall work seven and one-half ( $7\frac{1}{2}$ ) hours paid for eight (8) hours of labor and be permitted one-half ( $\frac{1}{2}$ ) hour for mealtime.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 14 of 86

(Carpenters District Council)

## DERRICKPERSON AND RIGGER

### Derrick Person & Rigger

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$44.84 Supplemental Benefit Rate per Hour: \$49.28 Supplemental Note: The above supplemental rate applies for work performed in Manhattan, Bronx, Brooklyn and Queens. \$50.70 - For work performed in Staten Island.

### **Overtime Description**

The first two hours of overtime on weekdays and the first seven hours of work on Saturdays are paid at time and one half for wages and supplemental benefits. All additional overtimes is paid at double time for wages and supplemental benefits. Deduct \$1.42 from the Staten Island hourly benefits rate before computing overtime.

#### **Overtime**

Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Washington's Birthday Good Friday Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

#### **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M.

(Local #197)

## DIVER

### Diver (Marine)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$63.82



Supplemental Benefit Rate per Hour: \$46.65

#### **Diver Tender (Marine)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$45.47 Supplemental Benefit Rate per Hour: \$46.65

#### Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day

### **Paid Holidays**

None

#### Shift Rates

When three shifts are utilized each shift shall work seven and one half-hours (7 1/2 hours) and paid for 8 hours, allowing for one half hour for lunch.

(Carpenters District Council)

## **DOCKBUILDER - PILE DRIVER**

#### **Dockbuilder - Pile Driver**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$50.50 Supplemental Benefit Rate per Hour: \$46.65

#### **Overtime**

Time and one half the regular rate after an 8 hour day.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 16 of 86

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day **President's Day** Memorial Day Independence Day Labor Day **Columbus Day Presidential Election Day** Thanksgiving Day **Christmas Day** 

# Paid Holidays

None

#### Shift Rates

Off shift work commencing between 5:00 P.M. and 11:00 P.M. shall work eight and one half hours allowing for one half hour for lunch. The wage rate shall be 113% of the straight time hourly wage rate.

(Carpenters District Council)

## DRIVER: TRUCK (TEAMSTER)

### **Driver - Dump Truck**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$39.53 Supplemental Benefit Rate per Hour: \$41.59 Supplemental Note: Over 40 hours worked: time and one half rate \$16.94, double time rate \$22.58

### **Driver - Tractor Trailer**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$39.50 Supplemental Benefit Rate per Hour: \$43.35 Supplemental Note: For over 40 hours worked: at time and one half - \$16.65; at double time - \$22.20

### Driver - Euclid & Turnapull Operator

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$40.06

**PUBLISH DATE: 7/1/2015** EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 17 of 86

Supplemental Benefit Rate per Hour: \$43.35

Supplemental Note: Over 40 hours worked: time and one half rate \$16.65 double time rate \$22.20

#### **Overtime Description**

For Paid Holidays: Holiday pay for all holidays shall be prorated based two hours per day for each day worked in the holiday week, not to exceed 8 hours of holiday pay. For Thanksgiving week, the prorated share shall be 5 1/3 hours of holiday pay for each day worked in Thanksgiving week.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

#### Paid Holidays

New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

#### **Shift Rates**

Off single shift work commencing between 6:00 P.M. and 5:00 A.M. shall work eight and one half hours allowing for one half hour for lunch and receive 9 hours pay for 8 hours of work.

#### Driver Redi-Mix (Sand & Gravel)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$36.30 Supplemental Benefit Rate per Hour: \$40.02 Supplemental Note: Over 40 hours worked: time and one half rate \$13.90, double time rate \$18.53

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 18 of 86

#### **Overtime Description**

For Paid Holidays: Employees working two (2) days in the calendar week in which the holiday falls are to paid for these holidays, provided they shape each remaining workday during that calendar week.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). President's Day Columbus Day Veteran's Day

Triple time the regular rate for work on the following holiday(s). New Year's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

#### **Paid Holidays**



New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Election Day Thanksgiving Day Christmas Day

(Local #282)

## ELECTRICIAN

(Including all low voltage cabling carrying data; video; and voice in combination with data and or video.)

#### Electrician "A" (Regular Day)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$54.00 Supplemental Benefit Rate per Hour: \$50.03



### Electrician "A" (Regular Day Overtime)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$81.00 Supplemental Benefit Rate per Hour: \$53.41

#### Electrician "A" (Day Shift)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$54.00 Supplemental Benefit Rate per Hour: \$50.03

#### Electrician "A" (Day Shift Overtime After 8 hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$81.00 Supplemental Benefit Rate per Hour: \$53.41

### Electrician "A" (Swing Shift)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$63.36 Supplemental Benefit Rate per Hour: \$56.94

## Electrician "A" (Swing Shift Overtime After 7.5 hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$95.04 Supplemental Benefit Rate per Hour: \$60.91

#### Electrician "A" (Graveyard Shift)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$70.97 Supplemental Benefit Rate per Hour: \$62.78

#### Electrician "A" (Graveyard Shift Overtime After 7 hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$106.46 Supplemental Benefit Rate per Hour: \$67.23

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### **Overtime Holidays**

Time and one half the regular rate for work on a holiday. New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

Paid Holidays

#### Shift Rates

When so elected by the Employer, one or more shifts of at least five days duration may be scheduled as follows: Day Shift: 8:00 am to 4:30 pm, Swing Shift 4:30 pm to 12:30 am, Graveyard Shift: 12:30 am to 8:00 am.

For multiple shifts of temporary light and/or power, the temporary light and/or power employee shall be paid for 8 hours at the straight time rate. For three or less workers performing 8 hours temporary light and/or power the supplemental benefit rate is \$24.39.



## Electrician "M" (First 8 hours)

"M" rated work shall be defined as jobbing: electrical work of limited duration and scope, also consisting of repairs and/or replacement of electrical and tele-data equipment. Includes all work necessary to retrofit, service, maintain and repair all kinds of lighting fixtures and local lighting controls and washing and cleaning of foregoing fixtures.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$27.50 Supplemental Benefit Rate per Hour: \$20.82 First and Second Year "M" Wage Rate Per Hour: \$23.00 First and Second Year "M" Supplemental Rate: \$18.56

### Electrician "M" (Overtime After First 8 hours)

"M" rated work shall be defined as jobbing: electrical work of limited duration and scope, also consisting of repairs and/or replacement of electrical and tele-data equipment. Includes all work necessary to retrofit, service, maintain and repair all kinds of lighting fixtures and local lighting controls and washing and cleaning of foregoing fixtures.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$41.25 Supplemental Benefit Rate per Hour: \$22.54 First and Second Year "M" Wage Rate Per Hour: \$34.50

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 21 of 86

First and Second Year "M" Supplemental Rate: \$20.00

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

#### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

Paid Holidays

(Local #3)

## **ELECTRICIAN - ALARM TECHNICIAN**

(Scope of Work - Inspect, test, repair, and replace defective, malfunctioning, or broken devices, components and controls of Fire, Burglar and Security Systems)

#### Alarm Technician

Effective Period: 7/1/2015 - 3/9/2016 Wage Rate per Hour: \$31.40 Supplemental Benefit Rate per Hour: \$14.76 Supplemental Note: \$13.26 only after 8 hours worked in a day

Effective Period: 3/10/2016 - 6/30/2016 Wage Rate per Hour: \$32.00 Supplemental Benefit Rate per Hour: \$15.47 Supplemental Note: \$13.97 only after 8 hours worked in a day

#### **Overtime Description**

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 22 of 86

Time and one half the regular rate for work on the following holidays: Columbus Day, Veterans Day, Day after Thanksgiving.

Double time the regular rate for work on the following holidays: New Year's day, Martin Luther King Jr. Day, President's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Christmas Day.

### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### **Paid Holidays**

New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

#### **Shift Rates**

Night Differential is based upon a ten percent (10%) differential between the hours of 4:00 P.M. and 12:30 A.M. and a fifteen percent (15%) differential for the hours 12:00 A.M. to 8:00 A.M.

### Vacation

At least 1 year of employment	ten (10) days
5 years or more of employment	
10 years of employment	
Plus one Personal Day per year	

#### Sick Days:

One day per Year. Up to 4 vacation days may be used as sick days.

(Local #3)

## **ELECTRICIAN-STREET LIGHTING WORKER**

### **Electrician - Electro Pole Electrician**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$54.00 Supplemental Benefit Rate per Hour: \$51.86

### **Electrician - Electro Pole Foundation Installer**

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 23 of 86

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$40.93 Supplemental Benefit Rate per Hour: \$39.46

#### Electrician - Electro Pole Maintainer

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$35.05 Supplemental Benefit Rate per Hour: \$35.51

#### **Overtime Description**

Electrician - Electro Pole Electrician: Time and one half the regular rate after a 7 hour day and after 5 consecutive days worked per week.

Electrician - Electro Pole Foundation Installer: Time and one half the regular rate after 8 hours within a 24 hour period and Saturday and Sunday.

Electrician - Electro Pole Maintainer: Time and one half the regular rate after a 7 hour day and after 5 consecutive days worked per week. Saturdays and Sundays may be used as a make-up day at straight time when a day is lost during the week to inclement weather.

#### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

Paid Holidays

(Local #3)

## **ELEVATOR CONSTRUCTOR**

#### **Elevator Constructor**

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate per Hour: \$59.55 Supplemental Benefit Rate per Hour: \$31.07

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 24 of 86

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate per Hour: \$60.96 Supplemental Benefit Rate per Hour: \$32.67

#### **Overtime Description**

For New Construction: work performed after 7 or 8 hour day, Saturday, Sunday or between 4:30pm and 7:00am shall be paid at double time rate.

Existing buildings: work performed after an 8 hour day, Saturday, Sunday or between 5:30pm and 7:00 am shall be paid time and one half.

#### **Overtime**

Double time the regular rate for work on the following holiday(s).

#### **Paid Holidays**

New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

#### Vacation

Employer contributes 8% of regular basic hourly rate as vacation pay for employees with more than 15 years of service, and 6% for employees with 5 to 15 years of service, and 4% for employees with less than 5 years of service.

(Local #1)

## **ELEVATOR REPAIR & MAINTENANCE**

#### **Elevator Service/Modernization Mechanic**

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate per Hour: **\$46.92** Supplemental Benefit Rate per Hour: **\$30.91** 

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate per Hour: \$47.91 Supplemental Benefit Rate per Hour: \$32.51

### **Overtime Description**

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 25 of 86

For Scheduled Service Work: Double time - work scheduled in advance by two or more workers performed on Sundays, Holidays, and between midnight and 7:00am.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday. Time and one half the regular rate for work on a holiday plus the day's pay.

#### **Paid Holidays**

New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

#### Shift Rates

Afternoon shift - regularly hourly rate plus a (15%) fifteen percent differential. Graveyard shift - time and one half the regular rate.

#### Vacation

Employer contributes 8% of regular basic hourly rate as vacation pay for employees with more than 15 years of service, and 6% for employees with 5 to 15 years of service, and 4% for employees with less than 5 years of service.

(Local #1)

## ENGINEER

### Engineer - Heavy Construction Operating Engineer I

Cherrypickers 20 tons and over and Loaders (rubber tired and/or tractor type with a manufacturer's minimum rated capacity of six cubic yards and over).

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$64.31 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$102.90

#### Engineer - Heavy Construction Operating Engineer II

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 26 of 86

Backhoes, Basin Machines, Groover, Mechanical Sweepers, Bobcat, Boom Truck, Barrier Transport (Barrier Mover) & machines of similar nature. Operation of Churn Drills and machines of a similar nature, Stetco Silent Hoist and machines of similar nature, Vac-Alls, Meyers Machines, John Beam and machines of a similar nature, Ross Carriers and Travel Lifts and machines of a similar nature, Bulldozers, Scrapers and Turn-a-Pulls: Tugger Hoists (Used exclusively for handling excavated material); Tractors with attachments, Hyster and Roustabout Cranes, Cherrypickers. Austin Western, Grove and machines of a similar nature, Scoopmobiles, Monorails, Conveyors, Trenchers: Loaders-Rubber Tired and Tractor: Barber Greene and Eimco Loaders and Eimco Backhoes; Mighty Midget and similar breakers and Tampers, Curb and Gutter Pavers and Motor Patrol, Motor Graders and all machines of a similar nature. Locomotives 10 Tons or under. Mini-Max, Break-Tech and machines of a similar nature; Shot blaster, skid steer machines and machines of a similar nature including bobcat, pile rig rubber-tired excavator (37,000 lbs. and under), 2 man auger.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$62.40 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$99.84

### Engineer - Heavy Construction Operating Engineer III

Minor Equipment such as Tractors, Post Hole Diggers, Ditch Witch (Walk Behind), Road Finishing Machines, Rollers five tons and under, Tugger Hoists, Dual Purpose Trucks, Fork Lifts, and Dempsey Dumpers, Fireperson.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$59.20 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$94.72

### Engineer - Heavy Construction Maintenance Engineer I

Installing, Repairing, Maintaining, Dismantling and Manning of all equipment including Steel Cutting, Bending and Heat Sealing Machines, Mechanical Heaters, Grout Pumps, Bentonite Pumps & Plants, Screening Machines, Fusion Coupling Machines, Tunnel Boring Machines Moles and Machines of a similar nature, Power Packs, Mechanical Hydraulic Jacks; all drill rigs including but not limited to Churn, Rotary Caisson, Raised Bore & Drills of a similar nature; Personnel, Inspection & Safety Boats or any boats used to perform functions of same, Mine Hoists, Whirlies, all Climbing Cranes, all Tower Cranes, including but not limited to Truck Mounted and Crawler Type and machines of similar nature; Maintaining Hydraulic Drills and machines of a similar nature; Well Point System-Installation and dismantling; Burning, Welding, all Pumps regardless of size and/or motor power, except River Cofferdam Pumps and Wells Point Pumps; Motorized Buggies (three or more); equipment used in the cleaning and televising of sewers, but not limited to jet-rodder/vacuum truck, vacall/vactor, closed circuit television inspection equipment; high powered water pumps, jet pumps; screed machines and concrete finishing machines of a similar nature; vermeers.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$62.11 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$99.38

### Engineer - Heavy Construction Maintenance Engineer II

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 27 of 86

On Base Mounted Tower Cranes

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$81.54 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$130.46

#### Engineer - Heavy Construction Maintenance Engineer III

On Generators, Light Towers

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$41.04 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$65.66

### Engineer - Heavy Construction Maintenance Engineer IV

On Pumps and Mixers including mud sucking

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$42.11 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$67.38

#### Engineer - Heavy Construction Oilers I

Gradalls, Cold Planer Grader, Concrete Pumps, Driving Truck Cranes, Driving and Operating Fuel and Grease Trucks.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$56.02 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$89.63

#### Engineer - Heavy Construction Oilers II

All gasoline, electric, diesel or air operated Shovels, Draglines, Backhoes, Keystones, Pavers, Gunite Machines, Battery of Compressors, Crawler Cranes, two-person Trenching Machines.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$38.79 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$62.06

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 28 of 86

### Engineer - Steel Erection Maintenance Engineers

Derrick, Travelers, Tower, Crawler Tower and Climbing Cranes

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$59.77 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$95.63

#### Engineer - Steel Erection Oiler I

**On a Truck Crane** 

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$55.95 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$89.52

### Engineer - Steel Erection Oiler II

**On a Crawler Crane** 

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$42.64 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime Shift Wage Rate: \$68.22

#### **Overtime Description**

On jobs of more than one shift, if the next shift employee fails to report for work through any cause over which the employer has no control, the employee on duty who works the next shift continues to work at the single time rate.

#### **Overtime**

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday. Double time the regular rate for work on the following holiday(s).

### **Paid Holidays**

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day



PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 29 of 86

Thanksgiving Day Day after Thanksgiving Christmas Day Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

#### Engineer - Building Work Maintenance Engineers I

Installing, repairing, maintaining, dismantling (of all equipment including: Steel Cutting and Bending Machines, Mechanical Heaters, Mine Hoists, Climbing Cranes, Tower Cranes, Linden Peine, Lorain, Liebherr, Mannes, or machines of a similar nature, Well Point Systems, Deep Well Pumps, Concrete Mixers with loading Device, Concrete Plants, Motor Generators when used for temporary power and lights), skid steer machines of a similar nature including bobcat.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$56.88 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime

### **Engineer - Building Work Maintenance Engineers II**

**On Pumps, Generators, Mixers and Heaters** 

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$44.22 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime

### Engineer - Building Work Oilers I

All gasoline, electric, diesel or air operated Gradealls: Concrete Pumps, Overhead Cranes in Power Houses: Their duties shall be to assist the Engineer in oiling, greasing and repairing of all machines; Driving Truck Cranes: Driving and Operating Fuel and Grease Trucks, Cherrypickers (hydraulic cranes) over 70,000 GVW, and machines of a similar nature.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$54.08 Supplemental Benefit Rate per Hour: \$34.25 Supplemental Note: \$61.60 on overtime

#### Engineer - Building Work Oilers II

Oilers on Crawler Cranes, Backhoes, Trenching Machines, Gunite Machines, Compressors (three or more in Battery).

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$40.21** Supplemental Benefit Rate per Hour: **\$34.25** Supplemental Note: **\$61.60** on overtime

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 30 of 86

### **Overtime Description**

On jobs of more than one shift, if an Employee fails to report for work through any cause over which the Employer has no control, the Employee on duty will continue to work at the rate of single time.

#### **Overtime**

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday. Double time the regular rate for work on the following holiday(s).

#### **Paid Holidays**

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Christmas Day Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

### **Shift Rates**

Off Shift: double time the regular hourly rate.

(Local #15)

## **ENGINEER - CITY SURVEYOR AND CONSULTANT**

### Party Chief

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$37.04 Supplemental Benefit Rate per Hour: \$18.60 Supplemental Note: Overtime Benefit Rate - \$25.45 per hour (time & one half) \$32.30 per hour (double time).

### Instrument Person

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$30.59 Supplemental Benefit Rate per Hour: \$18.60 Supplemental Note: Overtime Benefit Rate - \$25.45 per hour (time & one half) \$32.30 per hour (double time).

## <u>Rodperson</u>

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 31 of 86

Effective Period: 7/1/2015 - 6/30/2016

Wage Rate per Hour: \$26.52

Supplemental Benefit Rate per Hour: \$18.60

Supplemental Note: Overtime Benefit Rate - \$25.45 per hour (time & one half) \$32.30 per hour (double time).

#### **Overtime Description**

Time and one half the regular rate after an 8 hour day, Time and one half the regular rate for Saturday for the first eight hours worked, Double time the regular time rate for Saturday for work performed in excess of eight hours, Double time the regular rate for Sunday and Double time the regular rate for work on a holiday.

#### **Paid Holidays**

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

## ENGINEER - FIELD (BUILDING CONSTRUCTION)

(Construction of Building Projects, Concrete Superstructures, etc.)

### Field Engineer - BC Party Chief

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$60.77 Supplemental Benefit Rate per Hour: \$32.40 Supplemental Note: Overtime Benefit Rate - \$45.28 per hour (time & one half) \$58.15 per hour (double time).

### Field Engineer - BC Instrument Person

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$47.20** Supplemental Benefit Rate per Hour: **\$32.40** Supplemental Note: Overtime Benefit Rate - \$45.28 per hour (time & one half) \$58.15 per hour (double time).

### Field Engineer - BC Rodperson

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 32 of 86

Effective Period: 7/1/2015 - 6/30/2016

Wage Rate per Hour: \$30.49 Supplemental Benefit Rate per Hour: \$32.40 Supplemental Note: Overtime Benefit Rate - \$45.28 per hour (time & one half) \$58.15 per hour (double time).

#### **Overtime Description**

Time and one half the regular rate after a 7 hour work and time and one half the regular rate for Saturday for the first seven hours worked, Double time the regular time rate for Saturday for work performed in excess of seven hours, Double time the regular rate for Sunday and Double time the regular rate for work on a holiday.

#### **Paid Holidays**

New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Christmas Day Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

## **ENGINEER - FIELD (HEAVY CONSTRUCTION)**

(Construction of Roads, Tunnels, Bridges, Sewers, Building Foundations, Engineering Structures etc.)

### Field Engineer - HC Party Chief

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$66.43 Supplemental Benefit Rate per Hour: \$32.40 Supplemental Note: Overtime benefit rate - \$45.28 per hour (time & one half), \$58.15 per hour (double time).

#### Field Engineer - HC Instrument Person

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$48.82 Supplemental Benefit Rate per Hour: \$32.40 Supplemental Note: Overtime benefit rate - \$45.28 per hour (time & one half), \$58.15 per hour (double time).

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 33 of 86

#### Field Engineer - HC Rodperson

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$40.99 Supplemental Benefit Rate per Hour: \$32.40 Supplemental Note: Overtime benefit rate - \$45.28 per hour (time & one half), \$58.15 per hour (double time).

#### **Overtime Description**

Time and one half the regular rate after an 8 hour day, Time and one half the regular rate for Saturday for the first eight hours worked, Double time the regular time rate for Saturday for work performed in excess of eight hours, Double time the regular rate for Sunday and Double time the regular rate for work on a holiday.

#### **Paid Holidays**

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Veteran's Day Thanksgiving Day Christmas Day Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

## **ENGINEER - FIELD (STEEL ERECTION)**

### Field Engineer - Steel Erection Party Chief

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$62.26** Supplemental Benefit Rate per Hour: **\$32.40** Supplemental Note: Overtime benefit rate - \$45.28 per hour (time & one half), \$58.15 per hour (double time).

#### Field Engineer - Steel Erection Instrument Person

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$48.57** Supplemental Benefit Rate per Hour: **\$32.40** Supplemental Note: Overtime benefit rate - \$45.28 per hour (time & one half), \$58.15 per hour (double time).

### Field Engineer - Steel Erection Rodperson

Effective Period: 7/1/2015 - 6/30/2016

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 34 of 86

Wage Rate per Hour: \$32.61 Supplemental Benefit Rate per Hour: \$32.40 Supplemental Note: Overtime benefit rate - \$45.28 per hour (time & one half), \$58.15 per hour (double time).

#### **Overtime Description**

Time and one half the regular rate for Saturday for the first eight hours worked. Double time the regular rate for Saturday for work performed in excess of eight hours.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Double time the regular rate for Sunday. Double time the regular rate for work on the following holiday(s).

### **Paid Holidays**

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Christmas Day Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

## **ENGINEER - OPERATING**

### **Operating Engineer - Road & Heavy Construction I**

Back Filling Machines, Cranes, Mucking Machines and Dual Drum Paver.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$71.75 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$114.80

### **Operating Engineer - Road & Heavy Construction II**

Backhoes, Power Shovels, Hydraulic Clam Shells, Steel Erection, Moles and machines of a similar nature.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$74.29** 

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 35 of 86

Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$118.86

### **Operating Engineer - Road & Heavy Construction III**

Mine Hoists, Cranes, etc. (Used as Mine Hoists)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$76.67 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$122.67

### **Operating Engineer - Road & Heavy Construction IV**

Gradealls, Keystones, Cranes on land or water (with digging buckets), Bridge Cranes, Vermeer Cutter and machines of a similar nature, Trenching Machines.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$74.84 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$119.74

### **Operating Engineer - Road & Heavy Construction V**

Pile Drivers & Rigs (employing Dock Builder foreperson): Derrick Boats, Tunnel Shovels.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$73.36 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$117.38

### **Operating Engineer - Road & Heavy Construction VI**

Mixers (Concrete with loading attachment), Concrete Pavers, Cableways, Land Derricks, Power Houses (Low Air Pressure Units).

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$69.69 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$111.50

### **Operating Engineer - Road & Heavy Construction VII**

Barrier Movers , Barrier Transport and Machines of a Similar Nature.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$56.25 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$90.00

### **Operating Engineer - Road & Heavy Construction VIII**

**Utility Compressors** 

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$43.63 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$55.03

## **Operating Engineer - Road & Heavy Construction IX**

**Horizontal Boring Rig** 

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$66.26 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$106.02

### **Operating Engineer - Road & Heavy Construction X**

Elevators (manually operated as personnel hoist).

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$60.89 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$97.42

### **Operating Engineer - Road & Heavy Construction XI**

Compressors (Portable 3 or more in battery), Driving of Truck Mounted Compressors, Well-point Pumps, Tugger Machines Well Point Pumps, Churn Drill.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$47.28 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$75.65

### **Operating Engineer - Road & Heavy Construction XII**

All Drills and Machines of a similar nature.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 37 of 86

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$70.42 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$112.67

#### **Operating Engineer - Road & Heavy Construction XIII**

Concrete Pumps, Concrete Plant, Stone Crushers, Double Drum Hoist, Power Houses (other than above).

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$68.19 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$109.10

#### **Operating Engineer - Road & Heavy Construction XIV**

**Concrete Mixer** 

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$65.20 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$104.32

### **Operating Engineer - Road & Heavy Construction XV**

Compressors (Portable Single or two in Battery, not over 100 feet apart), Pumps (River Cofferdam) and Welding Machines, Push Button Machines, All Engines Irrespective of Power (Power-Pac) used to drive auxiliary equipment, Air, Hydraulic, etc.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$43.91 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$70.26

#### **Operating Engineer - Road & Heavy Construction XVI**

Concrete Breaking Machines, Hoists (Single Drum), Load Masters, Locomotives (over ten tons) and Dinkies over ten tons, Hydraulic Crane-Second Engineer.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$62.25 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$99.60

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 38 of 86

### **Operating Engineer - Road & Heavy Construction XVII**

On-Site concrete plant engineer, On-site Asphalt Plant Engineer, and Vibratory console.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$62.74 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$100.38

### **Operating Engineer - Road & Heavy Construction XVIII**

**Tower Crane** 

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$90.09 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$144.14

### **Operating Engineer - Paving I**

Asphalt Spreaders, Autogrades (C.M.I.), Roto/Mil

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$69.69 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$111.50

### **Operating Engineer - Paving II**

Asphalt Roller

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$67.87 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$108.59

### **Operating Engineer - Paving III**

Asphalt Plants

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$57.40 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$91.84



#### **Operating Engineer - Concrete I**

Cranes

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$74.51 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours

#### **Operating Engineer - Concrete II**

Compressors

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$44.25 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours

#### **Operating Engineer - Concrete III**

Micro-traps (Negative Air Machines), Vac-All Remediation System.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$59.51 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours

#### **Operating Engineer - Steel Erection I**

Three Drum Derricks

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$77.40 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$123.84

#### **Operating Engineer - Steel Erection II**

Cranes, 2 Drum Derricks, Hydraulic Cranes, Fork Lifts and Boom Trucks.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$74.37 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$118.99

#### **Operating Engineer - Steel Erection III**

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 40 of 86

Compressors, Welding Machines.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$44.09 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$70.54

### **Operating Engineer - Steel Erection IV**

Compressors - Not Combined with Welding Machine.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$41.98 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours Shift Wage Rate: \$67.17

### **Operating Engineer - Building Work I**

Forklifts, Plaster (Platform machine), Plaster Bucket, Concrete Pump and all other equipment used for hoisting material.



Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$61.27 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours

### **Operating Engineer - Building Work II**

Compressors, Welding Machines (Cutting Concrete-Tank Work), Paint Spraying, Sandblasting, Pumps (with the exclusion of Concrete Pumps), All Engines irrespective of Power (Power-Pac) used to drive Auxiliary Equipment, Air, Hydraulic, Jacking System, etc.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$45.85 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours

### **Operating Engineer - Building Work III**

Double Drum

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$69.76 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours

## **Operating Engineer - Building Work IV**

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 41 of 86

Stone Derrick, Cranes, Hydraulic Cranes Boom Trucks.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$73.91 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours

#### **Operating Engineer - Building Work V**

Dismantling and Erection of Cranes, Relief Engineer.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$68.09 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours

#### **Operating Engineer - Building Work VI**

4 Pole Hoist, Single Drum Hoists.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$67.37 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours

#### **Operating Engineer - Building Work VII**

**Rack & Pinion and House Cars** 

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$53.54 Supplemental Benefit Rate per Hour: \$30.40 Supplemental Note: \$55.10 overtime hours For New House Car projects Wage Rate per Hour \$42.70

#### **Overtime Description**

On jobs of more than one shift, if an Employee fails to report for work through any cause over which the Employer has no control, the Employee on duty will continue to work at the rate of single time.

For House Cars and Rack & Pinion only: Overtime paid at time and one-half for all hours in excess of eight hours in a day, Saturday, Sunday and Holidays worked.

#### Overtime

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday. Double time the regular rate for work on the following holiday(s).

### Paid Holidays

New Year's Day

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 42 of 86

Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

#### **Shift Rates**

For Steel Erection Only: Shifts may be worked at the single time rate at other than the regular working hours (8:00 A.M. to 4:30 P.M.) on the following work ONLY: Heavy construction jobs on work below the street level, over railroad tracks and on building jobs.

(Operating Engineer Local #14)

## FLOOR COVERER

(Interior vinyl composition tile, sheath vinyl linoleum and wood parquet tile including site preparation and synthetic turf not including site preparation)

### **Floor Coverer**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$50.50 Supplemental Benefit Rate per Hour: \$45.88

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Day after Thanksgiving Christmas Day

**PUBLISH DATE: 7/1/2015** 

EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 43 of 86

#### **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

#### Shift Rates

Two shifts may be utilized with the first shift working 8:00 A.M. to the end of the shift at the straight time of pay. The second shift will receive one hour at double time rate for the last hour of the shift. (eight for seven, nine for eight).

(Carpenters District Council)

# GLAZIER (New Construction, Remodeling, and Alteration)

#### **Glazier**

Effective Period: 7/1/2015 - 10/31/2015 Wage Rate per Hour: \$43.35 Supplemental Benefit Rate per Hour: \$36.59 Supplemental Note: Supplemental Benefit Overtime Rate: \$45.34

Effective Period: 11/1/2015 - 6/30/2016 Wage Rate per Hour: \$43.95 Supplemental Benefit Rate per Hour: \$36.84 Supplemental Note: Supplemental Benefit Overtime Rate: \$45.59

#### **Overtime Description**

An optional 8th hour can be worked at straight time rate. If 9th hour is worked, then both hours or more (8th & 9th or more) will be at the double time rate of pay.

#### **Overtime**

Double time the regular rate after a 7 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day Day after Thanksgiving

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 44 of 86

**Christmas Day** 

# Paid Holidays

#### Shift Rates

Shifts shall be any 7 hours beyond 4:00 P.M. for which the glazier shall receive 8 hours pay for 7 hours worked.

(Local #1281)

# **GLAZIER - REPAIR & MAINTENANCE**

(For the Installation of Glass - All repair and maintenance work on a particular building, whenever performed, where the total cumulative contract value is under \$105,000. Except where enumerated (i.e. plate glass windows) does not apply to non-residential buildings.)

## Craft Jurisdiction for repair, maintenance and fabrication

Plate glass replacement, Residential glass replacement, Residential mirrors and shower doors, Storm windows and storm doors, Residential replacement windows, Herculite door repairs, Door closer repairs, Retrofit apartment house (non commercial buildings), Glass tinting.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$23.68 Supplemental Benefit Rate per Hour: \$19.54

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Double time the regular rate for Sunday. Time and one half the regular hourly rate after 40 hours in any work week.

## **Paid Holidays**

New Year's Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day Day after Thanksgiving Christmas Day

(Local #1281)

# HEAT AND FROST INSULATOR

## **Heat & Frost Insulator**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$57.38 Supplemental Benefit Rate per Hour: \$37.41

#### **Overtime Description**

Double time shall be paid for supplemental benefits during overtime work. 8th hour paid at time and one half.

#### **Overtime**

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

Triple time the regular rate for work on the following holiday(s). Labor Day

#### Paid Holidays

None

## **Shift Rates**

The first shift shall work seven hours at the regular straight time rate. The second and third shift shall work seven hours the regular straight time hourly rate plus a fourteen percent wage and benefit premium. Off hour work in occupied or retail buildings may be worked on weekdays with an increment of \$1.00 per hour and eight hours pay for seven (7) hours worked. Double time will apply for over seven (7) hours worked on weekdays, weekends or holidays.

(Local #12)

# HOUSE WRECKER (TOTAL DEMOLITION)

# House Wrecker - Tier A

On all work sites the first, second, eleventh and every third House Wrecker thereafter will be Tier A House Wreckers (i.e. 1st, 2nd, 11th, 14th etc). Other House Wreckers may be Tier B House Wreckers.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$35.52 Supplemental Benefit Rate per Hour: \$26.86

## House Wrecker - Tier B

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$24.90 Supplemental Benefit Rate per Hour: \$19.88

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

Paid Holidays

(Mason Tenders District Council)

# **IRON WORKER - ORNAMENTAL**

## Iron Worker - Ornamental

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 47 of 86

Effective Period: 7/1/2015 - 6/30/2016

Wage Rate per Hour: \$43.20

Supplemental Benefit Rate per Hour: \$47.67

Supplemental Note: Supplemental benefits are to be paid at the applicable overtime rate when overtime is in effect.

## **Overtime Description**

Time and one half the regular rate after a 7 hour day for a maximum of two hours on any regular work day (the 8th and 9th hour) and double time shall be paid for all work on a regular work day thereafter, time and one half the regular rate for Saturday for the first seven hours of work and double time shall be paid for all work on a Saturday thereafter.

## Overtime

Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

**Paid Holidays** 

None

## **Shift Rates**

For off shift work - 8 hours pay for 7 hours of work. When two or three shifts are employed on a job, Monday through Friday, the workday for each shift shall be seven hours and paid for ten and one-half hours at the single time rate. When two or three shifts are worked on Saturday, Sunday or holidays, each shift shall be seven hours and paid fifteen and three-quarters hours.

(Local #580)

# **IRON WORKER - STRUCTURAL**

## Iron Worker - Structural

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$48.75 Supplemental Benefit Rate per Hour: \$67.34 Supplemental Note: Supplemental benefits are to be paid at the applicable overtime rate when overtime is in effect.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 48 of 86

#### **Overtime Description**

Monday through Friday- the first eight hours are paid at straight time, the 9th and 10th hours are paid at time and one-half the regular rate, all additional weekday overtime is paid at double the regular rate. Saturdays- the first eight hours are paid at time and one-half the regular rate, double time thereafter. Sunday-all shifts are paid at double time.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Good Friday Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

#### **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.



## Shift Rates

Monday through Friday - First Shift: First eight hours are paid at straight time, the 9th & 10th hours are paid at time and a half, double time paid thereafter. Second and third Shifts: First eight hours are paid at time and one-half, double time thereafter. Saturdays: All shifts, first eight hours paid at time and one-half, double time thereafter: Sunday all shifts are paid at double time.

(Local #40 & #361)

# LABORER (Foundation, Concrete, Excavating, Street Pipe Layer and Common)

#### <u>Laborer</u>

Excavation and foundation work for buildings, heavy construction, engineering work, and hazardous waste removal in connection with the above work. Landscaping tasks in connection with heavy construction work, engineering work and building projects. Projects include, but are not limited to pollution plants, sewers, parks, subways, bridges, highways, etc.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$40.50

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 49 of 86

Supplemental Benefit Rate per Hour: \$36.53

#### Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day

#### Paid Holidays

Labor Day Thanksgiving Day

#### **Shift Rates**

When two shifts are employed, single time rate shall be paid for each shift. When three shifts are found necessary, each shift shall work seven and one half hours (7  $\frac{1}{2}$ ), but shall be paid for eight (8) hours of labor, and be permitted one half hour for lunch.

(Local #731)

# LANDSCAPING

(Landscaping tasks, as well as tree pruning, tree removing, spraying and maintenance in connection with the planting of street trees and the planting of trees in city parks but not when such activities are performed as part of, or in connection with, other construction or reconstruction projects.)

## Landscaper (Above 6 years experience)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$27.00 Supplemental Benefit Rate per Hour: \$14.55

#### Landscaper (3 - 6 years experience)

Effective Period: 7/1/2015 - 6/30/2016

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 50 of 86

Wage Rate per Hour: \$26.00 Supplemental Benefit Rate per Hour: \$14.55

## Landscaper (up to 3 years experience)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$23.50 Supplemental Benefit Rate per Hour: \$14.55

## **Groundperson**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$23.50 Supplemental Benefit Rate per Hour: \$14.55

## Tree Remover / Pruner

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$32.00 Supplemental Benefit Rate per Hour: \$14.55

## Landscaper Sprayer (Pesticide Applicator)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$22.00 Supplemental Benefit Rate per Hour: \$14.55

## Watering - Plant Maintainer

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$17.00 Supplemental Benefit Rate per Hour: \$14.55

## **Overtime Description**

For all overtime work performed, supplemental benefits shall include an additional seventy-five (\$0.75) cents per hour.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Time and one half the regular rate for work on a holiday plus the day's pay.

## **Paid Holidays**

New Year's Day Memorial Day Independence Day Labor Day Thanksgiving Day



#### **Christmas Day**

#### Shift Rates

Work performed on a 4pm to 12am shift has a 15% differential. Work performed on a 12am to 8am shift has a 20% differential.

(Local #175)

# MARBLE MECHANIC

#### Marble Setter

Effective Period: 7/1/2015 - 12/31/2015 Wage Rate per Hour: \$51.53 Supplemental Benefit Rate per Hour: \$35.73

Effective Period: 1/1/2016 - 6/30/2016 Wage Rate per Hour: \$51.89 Supplemental Benefit Rate per Hour: \$36.62

#### Marble Finisher

Effective Period: 7/1/2015 - 12/31/2015 Wage Rate per Hour: \$40.53 Supplemental Benefit Rate per Hour: \$34.52

Effective Period: 1/1/2016 - 6/30/2016 Wage Rate per Hour: \$40.80 Supplemental Benefit Rate per Hour: \$35.15

#### Marble Polisher

Effective Period: 7/1/2015 - 12/31/2015 Wage Rate per Hour: \$36.65 Supplemental Benefit Rate per Hour: \$26.63

Effective Period: 1/1/2016 - 6/30/2016 Wage Rate per Hour: \$37.02 Supplemental Benefit Rate per Hour: \$27.01

#### **Overtime Description**

Supplemental Benefit contributions are to be made at the applicable overtime rates. Time and one half the regular rate after a 7 hour day or time and one half the regular rate after an 8 hour day - chosen by Employer at the start of the project and then would last for the full duration of the project.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 52 of 86

## **Overtime**

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

# Paid Holidays

None

(Local #7)

# **MASON TENDER**

## Mason Tender

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$36.67 Supplemental Benefit Rate per Hour: \$28.02

## **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

# **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day



## **Paid Holidays**

None

#### **Shift Rates**

The Employer may work two (2) shifts with the first shift at the straight time wage rate and the second shift receiving eight (8) hours paid for seven (7) hours work at the straight time wage rate.

(Local #79)

# MASON TENDER (INTERIOR DEMOLITION WORKER)

(The erection, building, moving, servicing and dismantling of enclosures, scaffolding, barricades, protection and site safety structures etc., on Interior Demolition jobs.)

## Mason Tender Tier A

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$35.46 Supplemental Benefit Rate per Hour: \$22.13

## Mason Tender Tier B

On Interior Demolition job sites 33 1/3 % of the employees shall be classified as Tier A Interior Demolition Workers and 66 2/3 % shall be classified as Tier B Interior Demolition Workers; provided that the employer may employ more than 33 1/3 % Tier A Interior Demolition Workers on the job site. Where the number of employees on a job site is not divisible by 3, the first additional employee (above the number of employees divisible by three) shall be a Tier B Interior Demolition Worker, and the second additional employee shall be a Tier A Interior Demolition Worker.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$24.65 Supplemental Benefit Rate per Hour: \$16.45

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Sunday.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day

PUBLISH DATE: 7/1/2015 EFFECTIV

EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 54 of 86

Labor Day Thanksgiving Day Christmas Day

# Paid Holidays

(Local #79)

# METALLIC LATHER

## Metallic Lather

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$43.63 Supplemental Benefit Rate per Hour: \$41.57 Supplemental Note: Supplemental benefits for overtime are paid at the appropriate overtime rate.

## **Overtime Description**

Overtime would be time and one half the regular rate after a seven (7) or eight (8) hours workday, which would be set at the start of the job.

## Overtime

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Washington's Birthday Good Friday Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day

## **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

## **Shift Rates**

There shall be either two (2) or three (3) shifts, each shift shall be eight (8) hours with nine (9) hours pay, including one half ( $\frac{1}{2}$ ) hour for lunch. Off-Hour Start shall commence after 3:30 P.M. and shall conclude by 6:00

A.M. The first consecutive seven (7) hours shall be at straight time with a differential of twelve dollars (\$12.00) per hour. Fringes shall be paid at the straight time rate.

(Local #46)

# MILLWRIGHT

#### **Millwright**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$49.50 Supplemental Benefit Rate per Hour: \$52.01

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day

## **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

## **Shift Rates**

The first shift shall receive the straight time rate of pay. The second shift receives the straight time rate of pay plus fifteen (15%) per cent. Members of the second shift shall be allowed one half hour to eat, with this time being included in the hours of the workday established. There must be a first shift to work a second shift. All additional hours worked shall be paid at the time and one-half rate of pay plus fifteen (15%) per cent for weekday hours.

(Local #740)

# **MOSAIC MECHANIC**

## Mosaic Mechanic - Mosaic & Terrazzo Mechanic

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$45.91 Supplemental Benefit Rate per Hour: \$38.15 Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$48.92 per hour.

## Mosaic Mechanic - Mosaic & Terrazzo Finisher

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$44.30 Supplemental Benefit Rate per Hour: \$38.14 Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$48.91 per hour.

# Mosaic Mechanic - Machine Operator Grinder

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$44.30 Supplemental Benefit Rate per Hour: \$38.14 Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$48.91 per hour.

## Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Washington's Birthday Good Friday Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

Paid Holidays

(Local #7)

# PAINTER

## Painter - Brush & Roller

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$41.00 Supplemental Benefit Rate per Hour: \$26.37 Supplemental Note: \$31.00 on overtime

## Spray & Scaffold / Decorative / Sandblast

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$44.00 Supplemental Benefit Rate per Hour: \$26.37 Supplemental Note: \$31.00 on overtime

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

#### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Thanksgiving Day Christmas Day

#### Paid Holidays None

(District Council of Painters #9)

# **PAINTER - SIGN**

**Designer** 

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 58 of 86

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$40.30 Supplemental Benefit Rate per Hour: \$7.22

#### <u>Journeyperson</u>

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$37.48 Supplemental Benefit Rate per Hour: \$7.22

## **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday. Double time the regular rate for work on the following holiday(s).

#### Paid Holidays

New Year's Day Martin Luther King Jr. Day Memorial Day Independence Day Labor Day Thanksgiving Day Day after Thanksgiving Christmas Day Two (2) additional holidays as floating holidays

(Local #8A-28A)

# **PAINTER - STRIPER**

## Striper (paint)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$35.00 Supplemental Benefit Rate per Hour: \$12.27 Supplemental Note: Overtime Supplemental Benefit rate - \$8.02 New Hire Rate (0-3 months) - \$0.00

#### Lineperson (thermoplastic)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$39.00 Supplemental Benefit Rate per Hour: \$12.27 Supplemental Note: Overtime Supplemental Benefit rate - \$8.02; New Hire Rate (0-3 months) - \$0.00

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 59 of 86

## Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Time and one half the regular rate for work on the following holiday(s).

## **Paid Holidays**

New Year's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Day after Thanksgiving Christmas Day

## **Shift Rates**

Employees hired before April 1, 2003: 15% night shift premium differential for work commenced at 9:00 PM or later.

#### Vacation

Employees with one to two years service shall accrue vacation based on hours worked: 250 hours worked - 1 day vacation; 500 hours worked - 2 days vacation; 750 hours worked - 3 days vacation; 900 hours worked - 4 days vacation; 1,000 hours worked - 5 days vacation. Employees with two to five years service receive two weeks vacation. Employees with five to twenty years service receive three weeks vacation. Employees with twenty to twenty-five years service receive four weeks vacation. Employees with 25 or more years service receive five weeks vacation. Vacation must be taken during winter months. 2 Personal Days except employees hired after 4/1/12 who do not have 2 years of service.

(Local #917)

# **PAINTER - STRUCTURAL STEEL**

## **Painters on Structural Steel**

Effective Period: 7/1/2015 - 9/30/2015 Wage Rate per Hour: \$48.00 Supplemental Benefit Rate per Hour: \$34.58

Effective Period: 10/1/2015 - 6/30/2016 Wage Rate per Hour: \$49.00 Supplemental Benefit Rate per Hour: \$36.08

## Painter - Power Tool

Effective Period: 7/1/2015 - 9/30/2015 Wage Rate per Hour: \$54.00 Supplemental Benefit Rate per Hour: \$34.58

Effective Period: 10/1/2015 - 6/30/2016 Wage Rate per Hour: \$55.00 Supplemental Benefit Rate per Hour: \$36.08

## **Overtime Description**

Supplemental Benefits shall be paid for each hour worked, up to forty (40) hours per week for the period of May 1st to November 15th or up to fifty (50) hours per week for the period of November 16th to April 30th.

## **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

## **Paid Holidays**

None

#### Shift Rates

Regular hourly rates plus a ten per cent (10%) differential

(Local #806)

# PAPERHANGER

## **Paperhanger**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$41.08 Supplemental Benefit Rate per Hour: \$29.23 Supplemental Note: Supplemental benefits are to be paid at the appropriate straight time and overtime rate.

## **Overtime**

Time and one half the regular rate after a 7 hour day.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 61 of 86

Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

#### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day Day after Thanksgiving Christmas Day

**Paid Holidays** 

None

#### **Shift Rates**

Evening shift - 4:30 P.M. to 12:00 Midnight (regular rate of pay); any work performed before 7:00 A.M. shall be at time and one half the regular base rate of pay.

(District Council of Painters #9)

# PAVER AND ROADBUILDER

## Paver & Roadbuilder - Formsetter

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$44.85 Supplemental Benefit Rate per Hour: \$36.92

## Paver & Roadbuilder - Laborer

Paving and road construction work, regardless of material used, including but not limited to preparation of job sites, removal of old surfaces, asphalt and/or concrete, by whatever method, including but not limited to milling; laying of concrete; laying of asphalt for temporary, patchwork, and utility paving (but not production paving); site preparation and incidental work before the installation of rubberized materials and similar surfaces; installation and repair of temporary construction fencing; slurry seal coating, maintenance of safety surfaces; play equipment installation, and other related work.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$40.98 Supplemental Benefit Rate per Hour: \$36.92

# Production Paver & Roadbuilder - Screed Person

(Production paving is asphalt paving when using a paving machine or on a project where a paving machine is traditionally used)

Adjustment of paving machinery on production paving jobs.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$45.45 Supplemental Benefit Rate per Hour: \$36.92

## Production Paver & Roadbuilder - Raker

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$44.85 Supplemental Benefit Rate per Hour: \$36.92

## Production Paver & Roadbuilder - Shoveler

General laborer (except removal of surfaces - see Paver and Roadbuilder-Laborer) including but not limited to tamper, AC paint and liquid tar work.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$41.56 Supplemental Benefit Rate per Hour: \$36.92



#### **Overtime Description**

Veteran's Day is a Paid Holiday for employees working on production paving.

If an employee works New Year's Day or Christmas Day, they receive the single time rate plus 25%.

Employees who work on a holiday listed below receive the straight time rate plus one day's pay for the holiday.

## **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### **Paid Holidays**

Memorial Day Independence Day Labor Day Presidential Election Day Thanksgiving Day

## **Shift Rates**

When two shifts are employed, the work period for each shift shall be a continuous eight (8) hours. When three shifts are employed, each shift will work seven and one half (7  $\frac{1}{2}$ ) hours but will be paid for eight (8) hours since only one half (1/2) hour is allowed for meal time.

When two or more shifts are employed, single time will be paid for each shift.

Night Work - On night work, the first eight (8) hours of work will be paid for at the single time rate, except that production paving work shall be paid at 15% over the single time rate for the screed person, rakers and

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 63 of 86

shovelers directly involved only. All other workers will be exempt. Hours worked over eight (8) hours during said shift shall be paid for at the time and one-half rate.

(Local #1010)

# PLASTERER

#### **Plasterer**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$43.43 Supplemental Benefit Rate per Hour: \$27.95

#### Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Martin Luther King Jr. Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day

# Paid Holidays

#### **Shift Rates**

When it is not possible to conduct alteration work during regular work hours, in a building occupied by tenants, said work shall proceed on a shift basis: however work over seven (7) hours in any twenty four (24) hour period, the time after seven (7) hours shall be considered overtime.

The second shift shall start at a time between 3:30 p.m. and 7:00 p.m. and shall consist of seven (7) working hours and shall receive eight (8) hours of wages and benefits at the straight time rate. The workers on the second shift shall be allowed one-half ( $\frac{1}{2}$ ) hour to eat with this time being included in the seven (7) hours of work.

(Local #530)

# **PLASTERER - TENDER**

## Plasterer - Tender

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$36.67 Supplemental Benefit Rate per Hour: \$28.02

## **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Washington's Birthday Memorial Day Independence Day Labor Day Presidential Election Day Thanksgiving Day Christmas Day

## **Paid Holidays**

None

## **Shift Rates**

When work commences outside regular work hours, workers receive an hour additional (differential) wage and supplement payment. Eight hours pay for seven hours work or nine hours pay for eight hours work.

(Mason Tenders District Council)

# **PLUMBER**

## **Plumber**

Effective Period: 7/1/2015 - 6/30/2016

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 65 of 86

Wage Rate per Hour: \$65.27 Supplemental Benefit Rate per Hour: \$28.38 Supplemental Note: Overtime supplemental benefit rate per hour: \$56.48

## **Plumber - Temporary Services**

Temporary Services - When there are no Plumbers on the job site, there may be three shifts designed to cover the entire twenty-four hour period, including weekends if necessary, at the following rate straight time.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$52.24 Supplemental Benefit Rate per Hour: \$22.28

#### **Overtime Description**

Double time the regular rate after a 7 hour day - unless for new construction site work where the plumbing contract price is \$1.5 million or less, the hours of labor can be 8 hours per day at the employers option. On Alteration jobs when other mechanical trades at the site are working an eighth hour at straight time, then the plumber shall also work an eighth hour at straight time.

#### **Overtime**

Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

#### Shift Rates

Shift work, when directly specified in public agency or authority documents where plumbing contract is \$8 million or less, will be permitted. 30% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shifts Monday to Friday. 50% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shift work performed on weekends. For shift work on holidays, double time wages and fringe benefits shall be paid.

(Plumbers Local #1)

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 66 of 86



# PLUMBER (MECHNICAL EQUIPMENT AND SERVICE)

(Mechanical Equipment and Service work shall include any repair and/or replacement of the present plumbing system.)

## Plumber

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$39.27 Supplemental Benefit Rate per Hour: \$13.34

## Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

## **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day **President's Day** Memorial Day **Independence Day** Thanksgiving Day Day after Thanksgiving **Christmas Day** 



(Plumbers Local # 1)

# PLUMBER (RESIDENTIAL RATES FOR 1, 2 AND 3 FAMILY HOME CONSTRUCTION)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$45.19 Supplemental Benefit Rate per Hour: \$20.62

## **Overtime**

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

# **Overtime Holidays**

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 67 of 86

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

# Paid Holidays

#### Shift Rates

30% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shifts Monday to Friday. 50% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shift work performed on weekends. For shift work on holidays, double time wages and fringe benefits shall be paid.

(Plumbers Local #1)

# PLUMBER: PUMP & TANK Oil Trades (Installation and Maintenance)

## Plumber - Pump & Tank

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$62.83 Supplemental Benefit Rate per Hour: \$21.37

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

#### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 68 of 86

Day after Thanksgiving Christmas Day

#### Paid Holidays

None

#### **Shift Rates**

All work outside the regular workday (8:00 A.M. to 3:30 P.M.) is to be paid at time and one half the regular hourly rate

(Plumbers Local #1)

# POINTER - WATERPROOFER, CAULKER MECHANIC (EXTERIOR BUILDING RENOVATION)

## Pointer - Waterproofer, Caulker Mechanic

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$47.41** Supplemental Benefit Rate per Hour: **\$24.40** 

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

#### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

Paid Holidays

## **Shift Rates**

All work outside the regular work day (an eight hour workday between the hours of 6:00 A.M. and 4:30 P.M.) is to be paid at time and one half the regular rate.



(Bricklayer District Council)

# ROOFER

## Roofer

Èffective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$40.70** Supplemental Benefit Rate per Hour: **\$30.17** 

## **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

#### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Presidential Election Day Thanksgiving Day Christmas Day

#### **Paid Holidays**

None

#### Shift Rates

Second shift - Regular hourly rate plus a 10% differential. Third shift - Regular hourly rate plus a 15% differential.

(Local #8)

# SANDBLASTER - STEAMBLASTER (Exterior Building Renovation)

## Sandblaster / Steamblaster

Effective Period: 7/1/2015 - 6/30/2016

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 70 of 86

Wage Rate per Hour: \$47.41 Supplemental Benefit Rate per Hour: \$24.40

# **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

# **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

# Paid Holidays

None



## **Shift Rates**

All work outside the regular work day (an eight hour workday between the hours of 6:00 A.M. and 4:30 P.M.) is to be paid at time and one half the regular rate.

(Bricklayer District Council)

# SHEET METAL WORKER

# **Sheet Metal Worker**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$46.96 Supplemental Benefit Rate per Hour: \$45.19 Supplemental Note: Supplemental benefit contributions are to be made at the applicable overtime rates.

# **Sheet Metal Worker - Fan Maintenance**

(The temporary operation of fans or blowers in new or existing buildings for heating and/or ventilation, and/or air conditioning prior to the completion of the project.)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$37.57

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 71 of 86

Supplemental Benefit Rate per Hour: \$45.19

#### Sheet Metal Worker - Duct Cleaner

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$12.90 Supplemental Benefit Rate per Hour: \$8.07

#### Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

**Paid Holidays** 

None

#### **Shift Rates**

Work that can only be performed outside regular working hours (seven hours of work between 7:30 A.M. and 3:30 P.M.) - First shift (work between 3:30 P.M. and 11:30 P.M.) - 10% differential above the established hourly rate. Second shift (work between 11:30 P.M. and 7:30 A.M.) - 15% differential above the established hourly rate.

For Fan Maintenance: On all full shifts of fan maintenance work the straight time hourly rate of pay will be paid for each shift, including nights, Saturdays, Sundays, and holidays.

(Local #28)

# SHEET METAL WORKER - SPECIALTY (Decking & Siding)

## **Sheet Metal Specialty Worker**

The first worker to perform this work must be paid at the rate of the Sheet Metal Worker. The second and third workers shall be paid the Specialty Worker Rate. The ratio of One Sheet Metal Worker, then Two Specialty Workers shall be utilized thereafter.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$42.64 Supplemental Benefit Rate per Hour: \$23.62 Supplemental Note: Supplemental benefit contributions are to be made at the applicable overtime rates.

## **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Christmas Day

Paid Holidays

(Local #28)


# SHIPYARD WORKER

## **Shipyard Mechanic - First Class**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$27.54 Supplemental Benefit Rate per Hour: \$3.01

## **Shipyard Mechanic - Second Class**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$20.22** Supplemental Benefit Rate per Hour: **\$2.73** 



## **Shipyard Laborer - First Class**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$20.90 Supplemental Benefit Rate per Hour: \$2.75

#### **Shipyard Laborer - Second Class**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$13.86 Supplemental Benefit Rate per Hour: \$2.48

#### **Shipyard Dockhand - First Class**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$23.61** Supplemental Benefit Rate per Hour: **\$2.86** 

#### Shipyard Dockhand - Second Class

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$15.94 Supplemental Benefit Rate per Hour: \$2.56

#### **Overtime Description**

Work performed on holiday is paid double time the regular hourly wage rate plus holiday pay.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Time and one half the regular hourly rate after 40 hours in any work week.

#### Paid Holidays

New Year's Day Martin Luther King Jr. Day President's Day Good Friday Memorial Day Independence Day Labor Day Thanksgiving Day Day after Thanksgiving Christmas Day

**Based on Survey Data** 

# SIGN ERECTOR (Sheet Metal, Plastic, Electric, and Neon)

## Sign Erector

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$45.60 Supplemental Benefit Rate per Hour: \$46.28

## **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday. Time and one half the regular rate for work on the following holiday(s).

## **Paid Holidays**

New Year's Day Washington's Birthday Memorial Day Independence Day Labor Day Columbus Day Election Day Thanksgiving Day Day after Thanksgiving Christmas Day

## Shift Rates

Time and one half the regular hourly rate is to be paid for all hours worked outside the regular workday either (7:00 A.M. through 2:30 P.M.) or (8:00 A.M. through 3:30 P.M.)

(Local #137)

# STEAMFITTER

## **Steamfitter I**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$55.00 Supplemental Benefit Rate per Hour: \$52.79 Supplemental Note: Overtime supplemental benefit rate: \$104.84

# **Steamfitter -Temporary Services**

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 75 of 86

The steamfitters shall not do any other work and shall not be permitted to work more than one shift in a twentyfour hour day. When steamfitters are present during the regular working day, no temporary services steamfitter will be required

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$41.80 Supplemental Benefit Rate per Hour: \$42.76 Supplemental Note: .

#### **Overtime**

Double time the regular rate after a 7 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

#### **Paid Holidays**

None

#### **Shift Rates**

Work performed between 3:30 P.M. and 7:00 A.M. and on Saturdays, Sundays and Holidays shall be at double time the regular hourly rate and paid at the overtime supplemental benefit rate above.

## Steamfitter II

For heating, ventilation, air conditioning and mechanical public works contracts with a dollar value not to exceed \$15,000,000 and for fire protection/sprinkler public works contracts not to exceed \$1,500,000.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$55.00 Supplemental Benefit Rate per Hour: \$52.79 Supplemental Note: Overtime supplemental benefit rate: \$104.84

#### Steamfitter -Temporary Services

The steamfitters shall not do any other work and shall not be permitted to work more than one shift in a twentyfour hour day. When steamfitters are present during the regular working day, no temporary services steamfitter will be required.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$41.80 Supplemental Benefit Rate per Hour: \$42.76

## **Overtime**

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day



Paid Holidays

## Shift Rates

May be performed outside of the regular workday except Saturday, Sunday and Holidays. A shift shall consist of eight working hours. All work performed in excess of eight hours shall be paid at double time. No shift shall commence after 7:00 P.M. on Friday or 7:00 P.M. the day before holidays. All work performed after 12:01 A.M. Saturday or 12:01 A.M. the day before a Holiday will be paid at double time. When shift work is performed the wage rate for regular time worked is a thirty percent premium together with fringe benefits.

On Transit Authority projects, where work is performed in the vicinity of tracks all shift work on weekends and holidays may be performed at the regular shift rates.

Local #638

# **STEAMFITTER - REFRIGERATION AND AIR CONDITIONER** (Maintenance and Installation Service Person)

# **Refrigeration and Air Conditioner Mechanic**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$39.25 Supplemental Benefit Rate per Hour: \$13.81

## Refrigeration and Air Conditioner Service Person V

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$32.25 Supplemental Benefit Rate per Hour: \$12.44

## **Refrigeration and Air Conditioner Service Person IV**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$26.72 Supplemental Benefit Rate per Hour: \$11.30

## **Refrigeration and Air Conditioner Service Person III**

Filter changing and maintenance thereof, oil and greasing, tower and coil cleaning, scraping and painting, general housekeeping, taking of water samples.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$22.93 Supplemental Benefit Rate per Hour: \$10.45

## **Refrigeration and Air Conditioner Service Person II**

Filter changing and maintenance thereof, oil and greasing, tower and coil cleaning, scraping and painting, general housekeeping, taking of water samples.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$19.02 Supplemental Benefit Rate per Hour: \$9.67

## **Refrigeration and Air Conditioner Service Person I**

Filter changing and maintenance thereof, oil and greasing, tower and coil cleaning, scraping and painting, general housekeeping, taking of water samples.

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$13.91 Supplemental Benefit Rate per Hour: \$8.78

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

# **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Independence Day Labor Day Veteran's Day Thanksgiving Day Christmas Day

Double time and one half the regular rate for work on the following holiday(s). Martin Luther King Jr. Day President's Day Memorial Day Columbus Day

#### Paid Holidays

New Year's Day Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Christmas Day

(Local #638B)

# **STONE MASON - SETTER**

#### **Stone Mason - Setters**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$47.20** Supplemental Benefit Rate per Hour: **\$37.15** 

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

## **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day Washington's Birthday Good Friday Memorial Day Independence Day



Labor Day Thanksgiving Day Christmas Day

#### Paid Holidays

1/2 day on Christmas Eve if work is performed in the A.M.

#### Shift Rates

For all work outside the regular workday (8:00 A.M. to 3:30 P.M. Monday through Friday), the pay shall be straight time plus a ten percent (10%) differential.

(Bricklayers District Council)

# TAPER

### **Drywall Taper**

Effective Period: 7/1/2015 - 12/29/2015 Wage Rate per Hour: \$46.32 Supplemental Benefit Rate per Hour: \$22.66

Effective Period: 12/30/2015 - 6/30/2016 Wage Rate per Hour: \$46.82 Supplemental Benefit Rate per Hour: \$22.66

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day Martin Luther King Jr. Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Thanksgiving Day Christmas Day

### **Paid Holidays**

Any worker who reports to work on Christmas Eve or New Year's Eve pursuant to his employer's instruction shall be entitled to three (3) hours afternoon pay without working.

### **Shift Rates**

Time and one half the regular rate outside the regular work hours (8:00 A.M. through 3:30 P.M.)

(Local #1974)

# TELECOMMUNICATION WORKER (Voice Installation Only)

## **Telecommunication Worker**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$40.35** Supplemental Benefit Rate per Hour: **\$13.19** Supplemental Note: The above rate applies for Manhattan, Bronx, Brooklyn, Queens. **\$12.64** for Staten Island only.

### Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

#### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day Lincoln's Birthday Washington's Birthday Memorial Day Independence Day Labor Day Columbus Day Election Day Veteran's Day Thanksgiving Day Christmas Day

### **Paid Holidays**

New Year's Day Lincoln's Birthday Washington's Birthday Memorial Day Independence Day Labor Day Columbus Day Election Day Veteran's Day

PUBLISH DATE: 7/1/2015

EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 81 of 86

**Thanksgiving Day** 

**Christmas Day** Employees have the option of observing either Martin Luther King's Birthday or the day after Thanksgiving instead of Lincoln's Birthday

### Shift Rates

For any workday that starts before 8A.M. or ends after 6P.M. there is a 10% differential for the applicable worker's hourly rate.

### Vacation

After 6 months.....one week. After 12 months but less than 7 years.....two weeks. After 7 or more but less than 15 years.....three weeks. After 15 years or more but less than 25 years.....four weeks.

(C.W.A.)

# TILE FINISHER

### **Tile Finisher**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$40.03 Supplemental Benefit Rate per Hour: \$29.71

#### Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

# **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day **President's Day Good Friday Memorial Day Independence** Day Labor Day **Columbus Day** Veteran's Day Thanksgiving Day Day after Thanksgiving **Christmas Day** 

**Paid Holidays** None



Off shift work day (work performed outside the regular 8:00 A.M. to 3:30 P.M. workday): shift differential of one and one quarter (1¼) times the regular straight time rate of pay for the seven hours of actual off-shift work.

(Local #7)

# TILE LAYER - SETTER

# **Tile Layer - Setter**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$51.61 Supplemental Benefit Rate per Hour: \$33.46

### Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

### **Shift Rates**

Off shift work day (work performed outside the regular 8:00 A.M. to 3:30 P.M. workday): shift differential of one and one quarter (1¼) times the regular straight time rate of pay for the seven hours of actual off-shift work.

(Local #7)

# TIMBERPERSON

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 83 of 86

### <u>Timberperson</u>

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$45.60 Supplemental Benefit Rate per Hour: \$46.67

### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather. Time and one half the regular hourly rate after 40 hours in any work week.

# Overtime Holidays

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day

**Paid Holidays** 

None

#### **Shift Rates**

Off shift work commencing between 5:00 P.M. and 11:00 P.M. shall work eight and one half hours allowing for one half hour for lunch. The wage rate shall be 113% of the straight time hourly wage rate.

(Local #1536)

# **TUNNEL WORKER**

Blasters, Mucking Machine Operators (Compressed Air Rates)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$59.17 Supplemental Benefit Rate per Hour: \$49.45

### **Tunnel Workers (Compressed Air Rates)**

Effective Period: 7/1/2015 - 6/30/2016

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 84 of 86

Wage Rate per Hour: \$57.12 Supplemental Benefit Rate per Hour: \$47.80

# **Top Nipper (Compressed Air Rates)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$56.07 Supplemental Benefit Rate per Hour: \$46.96

# Outside Lock Tender, Outside Gauge Tender, Muck Lock Tender (Compressed Air Rates)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$55.06 Supplemental Benefit Rate per Hour: \$46.07

# Bottom Bell & Top Bell Signal Person: Shaft Person (Compressed Air Rates)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$55.06 Supplemental Benefit Rate per Hour: \$46.07



# Changehouse Attendant: Powder Watchperson (Compressed Air Rates)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$48.16 Supplemental Benefit Rate per Hour: \$43.62

# **Blasters (Free Air Rates)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$56.47 Supplemental Benefit Rate per Hour: \$47.47

# **Tunnel Workers (Free Air Rates)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$54.04 Supplemental Benefit Rate per Hour: \$45.45

# All Others (Free Air Rates)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$49.93 Supplemental Benefit Rate per Hour: \$42.06

# Microtunneling (Free Air Rates)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$43.23 Supplemental Benefit Rate per Hour: \$36.36

### **Overtime Description**

For Repair-Maintenance Work on Existing Equipment and Facilities - Time and one half the regular rate after a 7 hour day, or for Saturday, or for Sunday. Double time the regular rate for work on a holiday. For Small-Bore Micro Tunneling Machines - Time and one-half the regular rate shall be paid for all overtime.

#### **Overtime**

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday. Double time the regular rate for work on the following holiday(s).

### **Paid Holidays**

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Election Day Veteran's Day Thanksgiving Day Christmas Day

(Local #147)

# WELDER TO BE PAID AT THE RATE OF THE JOURNEYPERSON IN THE TRADE PERFORMING THE WORK.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016

Page 86 of 86

# **OFFICE OF THE COMPTROLLER**

# **CITY OF NEW YORK**

# 220 APPRENTICESHIP PREVAILING WAGE SCHEDULE

# APPENDIX

Pursuant to Labor Law §220 (3-e), only apprentices who are individually registered in a bona fide program to which the employer contractor is a participant and registered with the New York State Department of Labor, may be employed on a public work project.

Any employee listed on a payroll at an apprentice wage rate, who is not registered as above, shall be paid the journey person wage rate for the classification of work he actually performed.

Apprentice ratios are established to ensure the proper safety, training and supervision of apprentices. A ratio establishes the number of journey workers required for each apprentice in a program and on a job site. Ratios are interpreted as follows: in the case of a 1:1, 1:4 ratio, there must be one journey worker for the first apprentice, and four additional journey workers for each subsequent apprentice.

# TABLE OF CONTENTS

CLASSIFICATION	PAGE
ASBESTOS HANDLER	
BOILERMAKER	3
BRICKLAYER	4
CARPENTER	5
CEMENT MASON	6
CEMENT AND CONCRETE WORKER	6
DERRICKPERSON & RIGGER (STONE)	7
DOCKBUILDER/PILE DRIVER	8
ELECTRICIAN	8
ELEVATOR CONSTRUCTOR	10
ELEVATOR REPAIR & MAINTENANCE	
ENGINEER	
ENGINEER - OPERATING	
FLOOR COVERER	
GLAZIER	
HEAT & FROST INSULATOR	15
HOUSE WRECKER	16
IRON WORKER - ORNAMENTAL	
IRON WORKER - STRUCTURAL	17
LABORER (FOUNDATION, CONCRETE, EXCAVATING, STREET PIPE LAYER & COMMON)	
MARBLE MECHANICS	19
MASON TENDER	20
METALLIC LATHER	21
MILLWRIGHT	
PAVER AND ROADBUILDER	
PAINTER	23
PAINTER - STRUCTURAL STEEL	
PLASTERER	
PLUMBER	25
POINTER - WATERPROOFER, CAULKER MECHANIC (EXTERIOR BUILDING RENOVATION)	
ROOFER	
SHEET METAL WORKER	
SIGN ERECTOR	
STEAMFITTER	
STONE MASON - SETTER	
TAPER	32
TILE LAYER - SETTER	32
TIMBERPERSON	33

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 2 of 34

,

# ASBESTOS HANDLER (Ratio of Apprentice Journeyperson: 1 to 1, 1 to 3)

# Asbestos Handler (First 1000 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 78% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$15.95

# Asbestos Handler (Second 1000 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$15.95

# Asbestos Handler (Third 1000 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 83% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$15.95

# Asbestos Handler (Fourth 1000 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 89% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$15.95

(Local #78)

**BOILERMAKER** (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

### **Boilermaker (First Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.00

### Boilermaker (Second Year: 1st Six Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 70% of Journeyperson's rate

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 3 of 34

Supplemental Benefit Rate Per Hour: \$31.66

#### Boilermaker (Second Year: 2nd Six Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.32

### Boilermaker (Third Year: 1st Six Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$35.00

### Boilermaker (Third Year: 2nd Six Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 85% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$36.67

### Boilermaker (Fourth Year: 1st Six Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 90% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$38.34

### Boilermaker (Fourth Year: 2nd Six Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 95% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$40.01

(Local #5)

# **BRICKLAYER** (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

#### Bricklayer (First 750 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$17.10

### Bricklayer (Second 750 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$17.10

# Bricklayer (Third 750 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$17.10

# Bricklayer (Fourth 750 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$17.10

# Bricklayer (Fifth 750 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 90% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$17.10

# Bricklayer (Sixth 750 Hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 95% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$17.10

(Bricklayer District Council)

# CARPENTER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# **Carpenter (First Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.14

# **Carpenter (Second Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.14

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 5 of 34

### **Carpenter (Third Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.14

# **Carpenter (Fourth Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.14

(Carpenters District Council)

# CEMENT MASON

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

## **Cement Mason (First Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 50% of Journeyperson's Rate

# Cement Mason (Second Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 60% of Journeyperson's Rate

### **Cement Mason (Third Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 70% of Journeyperson's Rate

(Local #780)

# CEMENT AND CONCRETE WORKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# Cement & Concrete Worker (First 1333 hours)

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 6 of 34

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.84

# Cement & Concrete Worker (Second 1333 hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$24.65

# Cement & Concrete Worker (Last 1334 hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$25.47

(Cement Concrete Workers District Council)

# **DERRICKPERSON & RIGGER (STONE)**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# Derrickperson & Rigger (stone) - First Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: 50% of Journeyperson's rate

# Derrickperson & Rigger (stone) - Second Year: 1st Six Months


Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

# Derrickperson & Rigger (stone) - Second Year: 2nd Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

# Derrickperson & Rigger (stone) - Third Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 90% of Journeyperson's rate Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate



(Local #197)

# DOCKBUILDER/PILE DRIVER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

## Dockbuilder/Pile Driver (First Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.52

### Dockbuilder/Pile Driver (Second Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.52

### Dockbuilder/Pile Driver (Third Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.52

### Dockbuilder/Pile Driver (Fourth Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.52

(Carpenters District Council)

# ELECTRICIAN (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

## Electrician (First Term: 0-6 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$13.00

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 8 of 34

Supplemental Benefit Rate per Hour: \$11.61 Overtime Supplemental Rate Per Hour: \$12.47

# Electrician (First Term: 7-12 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$14.00 Supplemental Benefit Rate per Hour: \$12.12 Overtime Supplemental Rate Per Hour: \$13.04

# Electrician (Second Term: 0-6 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$15.00 Supplemental Benefit Rate per Hour: \$12.63 Overtime Supplemental Rate Per Hour: \$13.62

# Electrician (Second Term: 7-12 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$16.00 Supplemental Benefit Rate per Hour: \$13.14 Overtime Supplemental Rate Per Hour: \$14.19

# Electrician (Third Term: 0-6 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$17.00 Supplemental Benefit Rate per Hour: \$13.65 Overtime Supplemental Rate Per Hour: \$14.77

# Electrician (Third Term: 7-12 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$18.00 Supplemental Benefit Rate per Hour: \$14.16 Overtime Supplemental Rate Per Hour: \$15.34

### Electrician (Fourth Term: 0-6 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$19.00 Supplemental Benefit Rate per Hour: \$14.67 Overtime Supplemental Rate Per Hour: \$15.92

# Electrician (Fourth Term: 7-12 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$21.00

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 9 of 34

Supplemental Benefit Rate per Hour: \$15.68 Overtime Supplemental Rate Per Hour: \$17.07

# Electrician (Fifth Term: 0-12 Months - Hired on or after 5/10/07)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$23.00 Supplemental Benefit Rate per Hour: \$18.56 Overtime Supplemental Rate Per Hour: \$20.00

# Electrician (Fifth Term: 13-18 Months - Hired on or after 5/10/07)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$27.50** Supplemental Benefit Rate per Hour: **\$20.82** Overtime Supplemental Rate Per Hour: **\$22.54** 

# Electrician (Fifth Term: 0-18 Months - Hired before 5/10/07)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$26.80 Supplemental Benefit Rate per Hour: \$20.46 Overtime Supplemental Rate Per Hour: \$22.14

#### **Overtime Description**

Overtime Wage paid at time and one half the regular rate For "A" rated Apprentices (work in excess of 7 hours per day) For "M" rated Apprentices (work in excess of 8 hours per day)

(Local #3)

# ELEVATOR CONSTRUCTOR (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

#### Elevator (Constructor) - First Year

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Rate Per Hour: \$26.94

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Rate Per Hour: \$28.41

# Elevator (Constructor) - Second Year

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate Per Hour: 55% of Journeyperson's rate Supplemental Rate Per Hour: \$27.35

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate Per Hour: 55% of Journeyperson's rate Supplemental Rate Per Hour: \$28.84

# Elevator (Constructor) - Third Year

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Rate Per Hour: \$28.17

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Rate Per Hour: \$29.69

# Elevator (Constructor) - Fourth Year

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Rate Per Hour: \$29.00

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Rate Per Hour: \$30.54

(Local #1)

# **ELEVATOR REPAIR & MAINTENANCE**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

# Elevator Service/Modernization Mechanic (First Year)

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Per Hour: \$26.87

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Per Hour: \$28.34

# Elevator Service/Modernization Mechanic (Second Year)

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 11 of 34

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate Per Hour: 55% of Journeyperson's rate Supplemental Benefit Per Hour: \$27.27

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate Per Hour: 55% of Journeyperson's rate Supplemental Benefit Per Hour: \$28.76

# Elevator Service/Modernization Mechanic (Third Year)

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Per Hour: \$28.08

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Per Hour: \$29.60

# Elevator Service/Modernization Mechanic (Fourth Year)

Effective Period: 7/1/2015 - 3/16/2016 Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Benefit Per Hour: \$28.89

Effective Period: 3/17/2016 - 6/30/2016 Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Benefit Per Hour: \$30.43

(Local #1)

ENGINEER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 5)

### **Engineer - First Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$23.68 Supplemental Benefit Rate per Hour: \$22.55

### Engineer - Second Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$29.60 Supplemental Benefit Rate per Hour: \$22.55

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 12 of 34

## **Engineer - Third Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$32.56 Supplemental Benefit Rate per Hour: \$22.55

# Engineer - Fourth Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$35.52 Supplemental Benefit Rate per Hour: \$22.55

(Local #15)

# **ENGINEER - OPERATING**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 5)

# **Operating Engineer - First Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour 40% of Journeyperson's Rate Supplemental Benefit Per Hour: \$20.15

# **Operating Engineer - Second Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's Rate Supplemental Benefit Per Hour: \$20.15

# **Operating Engineer - Third Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 60% of Journeyperson's Rate Supplemental Benefit Per Hour: \$20.15

(Local #14)

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 13 of 34

# FLOOR COVERER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

## Floor Coverer (First Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Rate Per Hour: \$31.14

#### Floor Coverer (Second Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Rate Per Hour: \$31.14

### Floor Coverer (Third Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Rate Per Hour: \$31.14

#### Floor Coverer (Fourth Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Rate Per Hour: \$31.14

(Carpenters District Council)

GLAZIER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

### **Glazier (First Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Rate Per Hour: \$13.64 Effective 11/1/2015 - Supplemental Rate Per Hour: \$13.79

#### **Glazier (Second Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 14 of 34

Supplemental Rate Per Hour: \$22.97 Effective 11/1/2015 - Supplemental Rate Per Hour: \$23.13

# **Glazier (Third Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Rate Per Hour: \$25.87 Effective 11/1/2015 - Supplemental Rate Per Hour: \$26.03

# **Glazier (Fourth Year)**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Rate Per Hour: \$31.04 Effective 11/1/2015 - Supplemental Rate Per Hour: \$31.29

(Local #1281)

# **HEAT & FROST INSULATOR**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# Heat & Frost Insulator (First Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

# Heat & Frost Insulator (Second Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

# Heat & Frost Insulator (Third Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 70% of Journeyperson's rate

# Heat & Frost Insulator (Fourth Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #12)

# HOUSE WRECKER (TOTAL DEMOLITION) (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# House Wrecker - First Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$21.17 Supplemental Benefit Rate per Hour: \$17.33

### House Wrecker - Second Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$22.32** Supplemental Benefit Rate per Hour: **\$17.33** 

# House Wrecker - Third Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$23.97 Supplemental Benefit Rate per Hour: \$17.33

# House Wrecker - Fourth Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$26.53** Supplemental Benefit Rate per Hour: **\$17.33** 

(Mason Tenders District Council)

# IRON WORKER - ORNAMENTAL

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# Iron Worker (Ornamental) - 1st Ten Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Rate Per Hour: \$36.50

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 16 of 34

# Iron Worker (Ornamental) - 11 -16 Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 55% of Journeyperson's rate Supplemental Rate Per Hour: \$37.62

# Iron Worker (Ornamental) - 17 - 22 Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Rate Per Hour: \$38.73

## Iron Worker (Ornamental) - 23 - 28 Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Rate Per Hour: \$40.97

# Iron Worker (Ornamental) - 29 - 36 Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Rate Per Hour: \$43.20

(Local #580)

# **IRON WORKER - STRUCTURAL**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

# Iron Worker (Structural) - 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$25.48 Supplemental Benefit Rate per Hour: \$46.83

# Iron Worker (Structural) - 7- 18 Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$26.08 Supplemental Benefit Rate per Hour: \$46.83

# Iron Worker (Structural) - 19 - 36 months

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 17 of 34

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$26.68 Supplemental Benefit Rate per Hour: \$46.83

(Local #40 and #361)

# LABORER (FOUNDATION, CONCRETE, EXCAVATING, STREET PIPE LAYER & COMMON)

(Ratio Apprentice to Journeyperson: 1 to 1, 1 to 3)

# Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) - First 1000 hours

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Rate Per Hour: \$36.53

# Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) -Second 1000 hours

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Rate Per Hour: \$36.53

# Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) -Third 1000 hours

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Rate Per Hour: \$36.53

# Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) -Fourth 1000 hours

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 90% of Journeyperson's rate Supplemental Rate Per Hour: \$36.53

(Local #731)

# MARBLE MECHANICS (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# Cutters & Setters - First 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

NO BENEFITS PAID DURING THE FIRST TWO MONTHS (PROBATIONARY PERIOD)

### Cutters & Setters - Second 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 55% of Journeyperson's rate

### Cutters & Setters - Third 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 65% of Journeyperson's rate

### Cutters & Setters - Fourth 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

## Cutters & Setters - Fifth 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 85% of Journeyperson's rate

### Cutters & Setters - Sixth 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 95% of Journeyperson's rate

### Polishers & Finishers - First 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

NO BENEFITS PAID DURING THE FIRST TWO MONTHS (PROBATIONARY PERIOD)

## Polishers & Finishers - Second 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

## Polishers & Finishers - Third 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

# Polishers & Finishers - Fourth 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 90% of Journeyperson's rate

(Local #7)

# MASON TENDER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

### Mason Tender - First Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$21.39** Supplemental Benefit Rate per Hour: **\$18.44** 

#### Mason Tender - Second Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$22.54 Supplemental Benefit Rate per Hour: \$18.44

## Mason Tender - Third Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$24.29** Supplemental Benefit Rate per Hour: **\$18.49** 

## Mason Tender - Fourth Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$26.95 Supplemental Benefit Rate per Hour: \$18.49

(Local #79)

# **METALLIC LATHER** (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# Metallic Lather (First Year -Called Prior to 6/29/11)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$29.41 Supplemental Benefit Rate per Hour: \$22.89

# Metallic Lather (Second Year - Called Prior to 6/29/11)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$34.01 Supplemental Benefit Rate per Hour: \$24.54

# Metallic Lather (Third Year - Called Prior to 6/29/11)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$39.07 Supplemental Benefit Rate per Hour: \$25.69

# Metallic Lather (First Year -Called On Or After 6/29/11)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$23.01 Supplemental Benefit Rate per Hour: \$17.95

# Metallic Lather (Second Year - Called On Or After 6/29/11)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$28.11 Supplemental Benefit Rate per Hour: \$17.95

# Metallic Lather (Third Year - Called On Or After 6/29/11)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$33.21 Supplemental Benefit Rate per Hour: \$17.95

(Local #46)

# MILLWRIGHT (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

## Millwright (First Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$27.23 Supplemental Benefit Rate per Hour: \$34.06

### Millwright (Second Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$32.18 Supplemental Benefit Rate per Hour: \$37.62

### Millwright (Third Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$37.13 Supplemental Benefit Rate per Hour: \$41.83

#### Millwright (Fourth Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$47.03 Supplemental Benefit Rate per Hour: \$48.31

(Local #740)

# PAVER AND ROADBUILDER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# Paver and Roadbuilder - First Year (Minimum 1000 hours)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$27.05 Supplemental Benefit Rate per Hour: \$17.12

# Paver and Roadbuilder - Second Year (Minimum 1000 hours)

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 22 of 34

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$28.69 Supplemental Benefit Rate per Hour: \$17.12

(Local #1010)

# PAINTER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

### Painter - Brush & Roller - First Year

Effective Period: 7/1/2015 - 10/31/2015 Wage Rate per Hour: \$15.80 Supplemental Benefit Rate per Hour: \$11.88

Effective Period: 11/1/2015 - 6/30/2016 Wage Rate per Hour: \$16.40 Supplemental Benefit Rate per Hour: \$12.13

### Painter - Brush & Roller - Second Year

Effective Period: 7/1/2015 - 10/31/2015 Wage Rate per Hour: \$19.75 Supplemental Benefit Rate per Hour: \$15.73

Effective Period: 11/1/2015 - 6/30/2016 Wage Rate per Hour: \$20.50 Supplemental Benefit Rate per Hour: \$15.98

### Painter - Brush & Roller - Third Year

Effective Period: 7/1/2015 - 10/31/2015 Wage Rate per Hour: \$23.70 Supplemental Benefit Rate per Hour: \$18.64

Effective Period: 11/1/2015 - 6/30/2016 Wage Rate per Hour: \$24.60 Supplemental Benefit Rate per Hour: \$18.89

### Painter - Brush & Roller - Fourth Year

Effective Period: 7/1/2015 - 10/31/2015 Wage Rate per Hour: \$31.60

Supplemental Benefit Rate per Hour: \$24.02

Effective Period: 11/1/2015 - 6/30/2016 Wage Rate per Hour: \$32.80 Supplemental Benefit Rate per Hour: \$24.27

(District Council of Painters)

# PAINTER - STRUCTURAL STEEL (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# Painters - Structural Steel (First Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

### Painters - Structural Steel (Second Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

### Painters - Structural Steel (Third Year)

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #806)

# PLASTERER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

#### Plasterer - First Year: 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Rate Per Hour: \$15.76

### Plasterer - First Year: 2nd Six Months

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 24 of 34

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 45% of Journeyperson's rate Supplemental Rate Per Hour: \$16.24

# Plasterer - Second Year: 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 55% of Journeyperson's rate Supplemental Rate Per Hour: \$18.21

# Plasterer - Second Year: 2nd Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Rate Per Hour: \$19.29

#### Plasterer - Third Year: 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Rate Per Hour: \$21.46

## Plasterer - Third Year: 2nd Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Rate Per Hour: \$22,54

(Local #530)

PLUMBER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

### Plumber - First Year: 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$14.00 Supplemental Benefit Rate per Hour: \$0.71

## Plumber - First Year: 2nd Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$14.00



Supplemental Benefit Rate per Hour: \$2.96

### Plumber - Second Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$23.87 Supplemental Benefit Rate per Hour: \$12.76

### Plumber - Third Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$25.97 Supplemental Benefit Rate per Hour: \$12.76

### Plumber - Fourth Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$28.82 Supplemental Benefit Rate per Hour: \$12.76

# Plumber - Fifth Year: 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$30.22 Supplemental Benefit Rate per Hour: \$12.76

### Plumber - Fifth Year: 2nd Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: **\$42.29** Supplemental Benefit Rate per Hour: **\$12.76** 

(Plumbers Local #1)

# POINTER - WATERPROOFER, CAULKER MECHANIC (EXTERIOR BUILDING RENOVATION)

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# Pointer - Waterproofer, Caulker Mechanic - First Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$25.01

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 26 of 34

Supplemental Benefit Rate per Hour: \$4.75

### Pointer - Waterproofer, Caulker Mechanic - Second Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$27.25 Supplemental Benefit Rate per Hour: \$9.70

### Pointer - Waterproofer, Caulker Mechanic - Third Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$32.24 Supplemental Benefit Rate per Hour: \$12.45

### Pointer - Waterproofer, Caulker Mechanic - Fourth Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate per Hour: \$38.66 Supplemental Benefit Rate per Hour: \$12.45

(Bricklayer District Council)



# **ROOFER** (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

### Roofer - First Year

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 35% of Journeyperson's Rate

### **Roofer - Second Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 50% of Journeyperson's Rate

### **Roofer - Third Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 60% of Journeyperson's Rate

### Roofer - Fourth Year

Effective Period: 7/1/2015 - 6/30/2016

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 27 of 34

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's Rate

(Local #8)

# SHEET METAL WORKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

### Sheet Metal Worker (0-6 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 25% of Journeyperson's rate Supplemental Rate Per Hour: \$6.24

## Sheet Metal Worker (7-18 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 35% of Journeyperson's rate Supplemental Rate Per Hour: \$16.71

### Sheet Metal Worker (19-30 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 45% of Journeyperson's rate Supplemental Rate Per Hour: \$23.00

#### Sheet Metal Worker (31-36 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 55% of Journeyperson's rate Supplemental Rate Per Hour: \$27.02

#### Sheet Metal Worker (37-42 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Rate Per Hour: \$29.06

#### Sheet Metal Worker (43-48 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Rate Per Hour: \$33.10

### Sheet Metal Worker (49-54 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Rate Per Hour: \$35.12

### Sheet Metal Worker (55-60 Months)

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Rate Per Hour: \$37.15

(Local #28)

# SIGN ERECTOR (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

### Sign Erector - First Year: 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 35% of Journeyperson's rate Supplemental Rate Per Hour: \$13.18

## Sign Erector - First Year: 2nd Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Rate Per Hour: \$14.95

### Sign Erector - Second Year: 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 45% of Journeyperson's rate Supplemental Rate Per Hour: \$16.74

# Sign Erector - Second Year: 2nd Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Rate Per Hour: \$18,52

# Sign Erector - Third Year: 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 55% of Journeyperson's rate Supplemental Rate Per Hour: \$24.94



# Sign Erector - Third Year: 2nd Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Rate Per Hour: \$26.87

# Sign Erector - Fourth Year: 1st Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Rate Per Hour: \$29.47

# Sign Erector - Fourth Year: 2nd Six Months

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Rate Per Hour: \$31.46

# Sign Erector - Fifth Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Rate Per Hour: \$33.43

## Sign Erector - Sixth Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Rate Per Hour: \$35.41

(Local #137)

# **STEAMFITTER** (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# Steamfitter - First Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate and Supplemental Per Hour: 40% of Journeyperson's rate

# **Steamfitter - Second Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate and Supplemental Rate Per Hour: 50% of Journeyperson's rate.

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 30 of 34

# **Steamfitter - Third Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate and Supplemental Rate per Hour: 65% of Journeyperson's rate.

# **Steamfitter - Fourth Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate and Supplemental Rate Per Hour: 80% of Journeyperson's rate.

# Steamfitter - Fifth Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate and Supplemental Rate Per Hour: 85% of Journeyperson's rate.

(Local #638)

# **STONE MASON - SETTER**

(Ratio Apprentice of Journeyperson: 1 to 1, 1 to 2)

# Stone Mason - Setters - First 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

# Stone Mason - Setters - Second 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Rate Per Hour: 50% of Journeyperson's rate

# Stone Mason - Setters - Third 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Rate Per Hour: 50% of Journeyperson's rate

# Stone Mason - Setters - Fourth 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Rate Per Hour: 50% of Journeyperson's rate

# Stone Mason - Setters - Fifth 750 Hours

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 31 of 34

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 90% of Journeyperson's rate Supplemental Rate Per Hour: 50% of Journeyperson's rate

## Stone Mason - Setters - Sixth 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 100% of Journeyperson's rate Supplemental Rate Per Hour: 50% of Journeyperson's rate

(Bricklayers District Council)

# TAPER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# **Drywall Taper - First Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

# Drywall Taper - Second Year

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

# **Drywall Taper - Third Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #1974)

# TILE LAYER - SETTER (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# Tile Layer - Setter - First 750 Hours

Effective Period: 7/1/2015 - 6/30/2016

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 32 of 34

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

# Tile Layer - Setter - Second 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 55% of Journeyperson's rate

# Tile Layer - Setter - Third 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 65% of Journeyperson's rate

# Tile Layer - Setter - Fourth 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

# Tile Layer - Setter - Fifth 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 85% of Journeyperson's rate

# Tile Layer - Setter - Sixth 750 Hours

Effective Period: 7/1/2015 - 6/30/2016 Wage and Supplemental Rate Per Hour: 95% of Journeyperson's rate

(Local #7)

# **TIMBERPERSON** (Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

# **Timberperson - First Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Rate Per Hour: \$31.54

# Timberperson - Second Year

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Rate Per Hour: \$31.54



PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 33 of 34

# **Timberperson - Third Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Rate Per Hour: \$31.54

# **Timberperson - Fourth Year**

Effective Period: 7/1/2015 - 6/30/2016 Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Rate Per Hour: \$31.54

(Local #1536)

PUBLISH DATE: 7/1/2015 EFFECTIVE PERIOD: JULY 1, 2015 THROUGH JUNE 30, 2016 Page 34 of 34

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

# DDC STANDARD GENERAL CONDITIONS FOR SINGLE CONTRACT PROJECTS



No Text

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

# DIVISION 01 – DDC STANDARD GENERAL CONDITIONS SINGLE CONTRACT PROJECTS TABLE OF CONTENTS

SECTION NO.	SECTION TITLE
01 10 00	SUMMARY
01 31 00	PROJECT MANAGEMENT AND COORDINATION
01 32 00	CONSTRUCTION PROGRESS DOCUMENTATION
01 32 33	PHOTOGRAPHIC DOCUMENTATION
01 33 00	SUBMITTAL PROCEDURES
01 35 03	GENERAL MECHANICAL REQUIREMENTS
01 35 06	GENERAL ELECTRICAL REQUIREMENTS
01 35 26	SAFETY REQUIREMENTS PROCEDURES
01 35 91	HISTORIC TREATMENT PROCEDURES
01 40 00	QUALITY REQUIREMENTS
01 42 00	REFERENCES
01 50 00	TEMPORARY FACILITIES, SERVICES AND CONTROLS
01 54 11	TEMPORARY ELEVATORS AND HOISTS
01 54 23	TEMPORARY SCAFFOLDING AND PLATFORMS
01 73 00	EXECUTION
01 74 19	CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
01 77 00	CLOSEOUT PROCEDURES
01 78 39	CONTRACT RECORD DOCUMENTS
01 79 00	DEMONSTRATION AND OWNERS PRE-ACCEPTANCE ORIENTATION
01 81 13	SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS
01 81 13.13	VOLATILE ORGANIC COMPOUND (VOC) LIMITS FOR ADHESIVES, SEALANTS, PAINTS AND COATINGS FOR LEED BUILDINGS
01 81 19	INDOOR AIR QUALITY REQUIREMENTS FOR LEED BUILDINGS
01 91 13	GENERAL COMMISSIONING REQUIREMENTS

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

No Text



### SECTION 01 10 00 SUMMARY

#### PARTI- GENERAL

#### 1.1 RELATED DOCUMENTS:

- A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].
- B. Addendum to the General Conditions: These General Conditions include and are supplemented by the Addendum to the General Conditions (the "Addendum"). The Addendum includes the following: (1) schedules referred to in these General Conditions (Schedule A through F), (2) information regarding the applicability of various articles, and (3) amended articles, if any.

#### 1.2 SUMMARY:

- A. This section includes the following:
  - 1. Scope and Intent
  - 2. Provisions Referenced in the Contract
  - 3. Performance of Work During Non-Regular Work Hours (Pursuant to a Change Order)
  - 4. Interruption of Services at Existing Facilities

#### 1.3 DEFINITIONS:

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.

#### 1.4 SCOPE AND INTENT:

A. Description of Project: Refer to the Addendum for a description of the project.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 1.4 B

B. LEED: The City of New York will seek U.S. Green Building Council (USGBC) LEED (Leadership in Energy and Environmental Design) certification for this Project as specified in Section 01 81 13, "SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS" and the Addendum to the General Conditions.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

NO TEXT



#### REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 1.4 C

- C. COMMISSIONING: The project will be commissioned by an independent third party under separate contract with the City of New York. Commissioning shall be in accordance with ASHRAE and USGBC LEED procedures, as described in Section 01 91 13, GENERAL COMMISSIONING REQUIREMENTS, and the Addendum to the General Conditions. The Contractor shall cooperate with the commissioning agent and provide whatever assistance is required.
- D. PROGRESS SCHEDULE: Refer to Section 01 32 00 CONSTRUCTION PROGRESS DOCUMENTATION for requirements of the project.
- E. COMPLETION OF WORK: Work to be done under the Contract is comprised of the furnishing of all labor, materials, equipment and other appurtenances, and obtaining all regulatory agency approvals necessary and required to complete the construction work in accordance with the Contract.
- F. OMISSION OF DETAILS: All work called for in the Specifications applicable to the Contract but not shown on the Contract Drawings in their present form, or vice versa, is required, and shall be performed by the Contractor as though it were originally delineated or described. The cost of such work shall be deemed included in the total Contract Price.
- G. WORK NOT IN SPECIFICATIONS OR CONTRACT DRAWINGS: Work not particularly specified in the Specifications nor detailed on the Contract Drawings but involved in carrying out their intent or in the complete and proper execution of the work, is required, and shall be performed by the Contractor. The cost of such work shall be deemed included in the total Contract Price.
- H. SILENCE OF THE SPECIFICATIONS: The apparent silence of the Specifications as to any detail, or the apparent omission from them of a detailed description concerning any work to be done and materials to be furnished, shall be regarded as meaning that only the best practice is to prevail and that only the best material and workmanship is to be used and interpretation of the Specifications shall be made upon that basis.
- I. CONFLICT BETWEEN CONTRACT DRAWINGS AND SPECIFICATIONS: Should any conflict occur in or between the Drawings and Specifications, the Contractor shall be deemed to have estimated the most expensive way of doing the work unless the Contractor shall have asked for and obtained a decision in writing from the Commissioner before the submission of the bid as to what shall govern.

### 1.5 CONTRACT DRAWINGS AND SPECIFICATIONS:

A. SCHEDULE C - The Contract Drawings are listed in Schedule C, which is set forth in the Addendum. Such drawings referred to in the Contract, and in the applicable Specifications for the Contract, bear the general title:

City of New York Department of Design and Construction Division of Public Buildings

- B. DOCUMENTS FURNISHED TO THE CONTRACTOR After the award of the Contract, the Contractor will be furnished with five (5) complete sets of paper prints of all Contract Drawings mentioned in Paragraph A above, as well as a copy of the Specifications.
- C. ADDITIONAL COPIES of Drawings and Specifications, when requested, will be furnished to the Contractor if available.



- D. SUPPLEMENTARY DRAWINGS When, in the opinion of the Commissioner, it becomes necessary to more fully explain the work to be done, or to illustrate the work further, or to show any changes which may be required, drawings known as Supplementary Drawings will be prepared by the Commissioner.
- E. COMPENSATION Where Supplementary Drawings entail extra work, compensation therefore to the Contractor shall be subject to the terms of the Contract. The Supplementary Drawings shall be binding upon the Contractor with the same force as the Contract Drawings.
- F. SUPPLEMENTARY DRAWING PRINTS Three (3) copies of prints of these Supplementary Drawings will be furnished to the Contractor.
- G. COPIES TO SUBCONTRACTORS The Contractor shall furnish each of its subcontractors and material suppliers such copies of Contract Drawings, Supplementary Drawings, or copies of the Specifications as may be required for its work.

### 1.6 COORDINATION:

- A. COORDINATION AND COOPERATION The Contractor shall consult and study the requirements of the Contract Drawings and Specifications for all required work, including all work to be performed by trade subcontractors, so that the Contractor may become acquainted with the work of the project as a whole in order to achieve the proper coordination and cooperation necessary for the efficient and timely performance of the work.
- B. CONTRACTOR TO CHECK DRAWINGS: The Contractor shall verify all dimensions, quantities and details shown on the Contract Drawings, Schedules, or other data received from the Commissioner, and shall notify the Commissioner of all errors, omissions, conflicts and discrepancies found therein. Notice of such errors shall be given before the Contractor proceeds with any work. Figures shall be used in preference to scale dimensions and large-scale drawings in preference to small-scale drawings.

#### 1.7 SHOP DRAWINGS AND RECORD DRAWINGS:

Refer to Division I Section 01 33 00 - SUBMITAL PROCEDURES and Section 01 78 39 - PROJECT RECORD DRAWINGS for requirements applicable to shop drawings and record drawings.

#### 1.8 TEMPORARY FACILITIES, SERVICES AND CONTROLS:

Refer to Division I Section 01 50 00 – TEMPORARY FACILITIES SERVICES AND CONTROLS for the responsibilities of the Contractor.

#### 1.9 DUST CONTROL:

The Contractor shall prepare, execute and manage a "Dust Control Plan" for the prevention of the emission of dust from construction related activities in compliance with 15 RCNY 13-01 et. seq.

#### 1.10 PROVISIONS REFERENCED IN THE CONTRACT:

A. SCHEDULE A - Various Articles of the Contract refer to requirements set forth in Schedule A of the General Conditions. Schedule A, which is included in the Addendum, sets forth (1) the referenced Articles of the Contract, and (2) the specific requirements applicable to the Contract.



- B. EXTENSION OF TIME Applications for Extensions of Time, as indicated in Article 13 of the Contract, shall be made in accordance with the Rules of the Procurement Policy Board.
- C. PARTIAL PAYMENTS FOR MATERIALS IN ADVANCE OF THEIR INCORPORATION IN THE WORK PURSUANT TO ARTICLE 42 OF THE CONTRACT In order to better insure the availability of materials, fixtures and equipment when needed for the work, the Commissioner may authorize partial payment for certain materials, fixtures and equipment, prior to their incorporation in the work, but only in strict accordance with, and subject to, all the terms and conditions set forth in the Specifications, unless an alternate method of payment is elsewhere provided in the Specifications for specified materials, fixtures or equipment.
  - 1. The Contractor shall submit to the Commissioner a written request, in quadruplicate, for payment for materials purchased or to be purchased for which the Contractor needs to be paid prior to their actual incorporation in the work. The request shall be accompanied by a schedule of the types and quantities of materials, and shall state whether such materials are to be stored on or off the site.
  - 2. Where the materials are to be stored off the site, they shall be stored at a place other than the Contractor's premises (except with the written consent of the Commissioner) and under the conditions prescribed or approved by the Commissioner. The Contractor shall set apart and separately store at the place or places of storage all materials and shall clearly mark same "PROPERTY OF THE CITY OF NEW YORK", and further, shall not at any time move any of said materials to another off-site place of storage without the prior written consent of the Commissioner. Materials may be removed from their place of storage off the site for incorporation in the work upon approval of the Resident Engineer.
  - 3. Where the materials are to be stored at the site, they shall be stored at such locations as shall be designated by the Resident Engineer and only in such quantities as, in the opinion of the Resident Engineer, will not interfere with the proper performance of the work by the Contractor or by other Contractors then engaged in performing work on the site. Such materials shall not be removed from their place of storage on the site except for incorporation in the work, without the approval of the Resident Engineer.
  - 4. INSURANCE
    - a. STORAGE OFF-SITE Where the materials are stored off the site and until such time as they are incorporated in the work, the Contractor shall fully insure such materials against any and all risks of destruction, damage or loss including but not limited to fire, theft, and any other casualty or happening. The policy of insurance shall be payable to the City of New York. It shall be in such terms and amounts as shall be approved by the Commissioner and shall be placed with a company duly licensed to do business in the State of New York. The Contractor shall deliver the original and one (1) copy of such policy or policies marked "Fully Paid" to the Commissioner.
    - b. STORAGE ON THE SITE Where the materials are stored at the site, the Contractor shall furnish satisfactory evidence to the Commissioner that they are properly insured against loss, by endorsements or otherwise, under the policy or policies of insurance obtained by the Contractor to cover losses to materials owned or installed by the Contractor. The policy of insurance shall cover fire and extended coverage against windstorm, hail, explosion and riot attending a strike, civil commotion, aircraft, vehicles and smoke.
  - 5. All costs, charges and expenses arising out of the storage of such materials, shall be paid by the Contractor and the City hereby reserves the right to retain out of any partial or final payment made under the Contract an amount sufficient to cover such costs, charges and expenses with the understanding that the City shall have and may exercise any and all other remedies at law for the recovery of such cost, charges and expenses. There shall be no

SUMMARY 01 10 00 -4 increase in the Contract price for such costs, charges and expenses and the Contractor shall not make any claim or demand for compensation therefore.

6. The Contractor shall pay any and all costs of handling and delivery of materials, to the place of storage and from the place of storage to the site of the work; and the City shall have the right to retain from any partial or final payment an amount sufficient to cover the cost of such handling and delivery.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- 7. In the event that the whole or any part of these materials are lost, damaged or destroyed in advance of their satisfactory incorporation in the work, the Contractor, at the Contractor's own cost, shall replace such lost, damaged or destroyed materials of the same character and quality. The City will reimburse the Contractor for the cost of the replaced materials to the extent, and only to the extent, of the funds actually received by the City under the policies of insurance hereinbefore referred to. Until such time as the materials are replaced, the City will deduct from the value of the stored materials or from any other money due under the Contract, the amount paid to the Contractor for such lost, damaged or destroyed materials.
- 8. Should any of the materials paid for the City hereunder be subsequently rejected or incorporated in the work in a manner or by a method not in accordance with the Contract Documents, the Contractor shall remove and replace, at Contractor's own cost, such defective or improperly incorporated material with materials complying with the Contract Documents. Until such materials are replaced, the City will deduct from the value of the stored materials or from any other money due the Contractor, the amount paid by the City for such rejected or improperly incorporated materials.
- 9. Payments for the cost of materials made hereunder shall not be deemed to be an acceptance of such materials as being in accordance with the Contract Documents, and the Contractor always retains and must comply with the Contractor's duty to deliver to the site and properly incorporate in the work only materials which comply with the Contract Documents.
- 10. The Contractor shall retain any and all risks in connection with the damage, destruction or loss of the materials paid for hereunder to the time of delivery of the same to the site of the work and their proper incorporation in the work in accordance with the Contract Documents.
- 11. The Contractor shall comply with all laws and the regulations of any governmental body or agency pertaining to the priority purchase, allocation and use of the materials.
- 12. When requesting payment for such materials, the Contractor shall submit with the partial estimate duly authenticated documents of title, such as bills of sale, invoices or warehouse receipts, all in quadruplicate. The executed bills of sale shall transfer title to the materials from the Contractor to the City. (In the event that the invoices state that the material has been purchased by a subcontractor, bills of sale in quadruplicate will also be required transferring title to the materials from subcontractor to the Contractor).
- 13. Where the Contractor, with the approval of the Commissioner, has purchased unusually large quantities of materials in order to assure their availability for the work, the Commissioner, at the Commissioner's option, may waive the requirements of Paragraph 12 provided the Contractor furnishes evidence in the form of an affidavit from the Contractor in quadruplicate, and such other proof as the Commissioner may require, that the Contractor is the sole owner of such materials and has purchased them free and clear of all liens and other encumbrances. In such event, the Contractor shall pay for such materials and submit proof thereof, in the same manner as provided in Paragraph 12 hereof, within seven (7) days after receipt of payment therefore from the Comptroller. Failure on the part of the Contractor to submit satisfactory evidence that all such materials have been paid for in full, shall preclude the Contractor from payments under the Contract.



SUMMARY 01 10 00 -5



- 14. The Contractor shall include in each succeeding partial estimate requisition a summary of materials stored which shall set forth the quantity and value of materials in storage, on or off the site, at the end of each preceding estimate period; the amount removed for incorporation in the work; the quantity and value of materials delivered during the current period and the total value of materials on hand for which payment thereof will be included in the current payment estimate.
- 15. Upon proof to the satisfaction of the Commissioner of the actual cost of such materials and upon submission of proper proof of title as required under Paragraph 12 or Paragraph 13 hereof, payment will be made therefore to the extent of 85%, provided however, that the cost so verified, established and approved shall not exceed the estimated cost of such materials included in the approved detailed breakdown estimate submitted in accordance with Article 41 of the Contract; if it does, the City will pay only 85% approved estimated cost.
- 16. Upon the incorporation in the work of any such materials, which have been paid for in advance of such incorporation in accordance with the foregoing provisions, payment will be made for such materials incorporated in the work pursuant to Article 42 of the Contract, less any sums paid pursuant to Paragraph 15 herein.
- D. MOBILIZATION PAYMENT A line item for mobilization shall be allowed on the Contractor's Detailed Bid Breakdown submitted in accordance with Article 41 of the Contract. The Mobilization Payment is intended to include the cost of required bonds, insurance coverage and/or any other expenses required for the initiation of the Contract Work. All costs for mobilization shall be deemed included in the total Contract Price. The Detailed Bid Breakdown shall reflect, and the Mobilization Payment shall be made, in accordance with the following schedule:

Contract Amou	Percent		N	lobilization	
Less than - \$	50,000	x	0	=	0
\$ 50,000 - \$	100,000	x		=	\$ 6,000
\$ 100,001 - \$	500,000	x	6	=	\$ 6,000 (min) - \$ 30,000 (max)
\$ 500,000 - \$	2,500,000	X	5	=	\$ 30,000 (min) - \$ 125,000 (max)
Over - \$	2,500,000	x	4	=	\$ 125,000 (min) - \$ 300,000 (max)

The Contractor may requisition for one-half (1/2) of the Mobilization Payment upon satisfactory completion of the following:

- 1. Installation of any required field office(s).
- 2. Submission of all required insurance certificates and bonds.
- 3. Approval by the Department of Design and Construction of the coordinated progress schedule for the project and the Contractor's Shop Drawing schedule.

The remaining balance of the Mobilization Payment may be requisitioned only after 10 percent (10%) of the Contract price, exclusive of the total amount of Mobilization Payments made or to be made hereunder, shall have been approved for payment.

E. ULTRA LOW SULFUR DIESEL FUEL AND BEST AVAILABLE TECHNOLOGY REPORTING: The Contractor shall submit reports to the Commissioner regarding the use of Ultra Low Sulfur Diesel Fuel in Non-Road Vehicles, and the implementation of Best Available Technology (BAT), as set forth in Article 5.4 of the Contract. Such reports shall be submitted in accordance with the schedule, format, directions and procedures established by the Commissioner.



## 1.11 PERFORMANCE OF WORK DURING NON-REGULAR WORK HOURS:

- A. NON-REGULAR WORK HOURS: The Commissioner may issue a change order in accordance with Article 25 of the Contract which (1) directs the Contractor to perform the Work, or specific components thereof, during other than regular work hours (i.e., evenings, weekends and holidays), and (2) provides compensation to the Contractor for costs in connection with the performance of Work during other than regular work hours. The Commissioner may issue a change order if a delay has occurred and such delay is not the fault of the Contractor, or if the work is of such an important nature that delay in completing such work would result in serious disadvantage to the public.
- B. PROCEDURE: The Contractor shall (1) obtain whatever permits may be required for performance of the work during other than regular business hours, and (2) pay all necessary fees in connection with such permits. In addition, if directed by the Commissioner, the Contractor shall make immediate application to the Commissioner of the Department of Labor, State of New York, for dispensation in accordance with Subdivision 2 of Section 220 of the Labor Law.

### 1.12 INTERRUPTION OF SERVICES AT EXISTING FACILITIES:

- A. EVENING AND WEEKEND WORK Where performance of the Work requires the temporary shutdown(s) of services, such shutdown(s) shall be made at night or on weekends or at such times that will cause no interference with the established routines and operations of the facility in question.
  - 1 Where weekend or evening work is required due to unavoidable service shutdowns, such work shall be performed at no extra cost to the City. Components of the Work that must be performed during other than regular work hours are indicated in the Drawings and/or the Specifications.

#### B. INTERRUPTION OF EXISTING FACILITIES:

- 1 The Contractor shall not interrupt any of the services of the facility nor interfere with such services in any way without the permission of the Commissioner. Such interruption or interferences shall be made as brief as possible, and only at such time stated.
- 2 Under no circumstances shall the Contractor, its subcontractors, or its workers, be permitted to use any part of the project as a shop, without the permission of the Commissioner.
- 3 Unnecessary noise shall be avoided at all times and necessary noise shall be reduced to a minimum.
- 4 Toilet facilities, water and electricity must be operational at all times (i.e. 24/7). No services of the facility can be interrupted in any way without the permission of the Commissioner. Careful coordination of all work with the Resident Engineer must be done to maintain the operational level of the project personnel at the facility.
- 5 The Contractor shall schedule the work to avoid noise interference that will affect the normal functions of the facility. In particular, construction operations producing noises that are objectionable to the functions of the facility must be scheduled at times of day or night, day of the week, or weekend, which will not interfere with personnel at the facility. Any additional cost resulting from this scheduling shall be borne by the Contractor.



- 6 The Contractor shall arrange to work continuously, including evening and weekend hours, if required, to assure that services will be shut down only during the time actually required to make the necessary connections to the existing facility.
- 7 The Contractor shall give ample written notice in advance to the Commissioner and personnel at the facility of any required shutdown.

PART II – PRODUCTS (Not Used) PART III – EXECUTION (Not Used) END OF SECTION 01 10 00



### SECTION 01 31 00 PROJECT MANAGEMENT AND COORDINATION

#### PART I - GENERAL

#### 1.1 RELATED DOCUMENTS:

- A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].
- B. LEED: Refer to the Addendum to identify whether this project is designed to comply with a Certification Level according to the U.S. Green Building Council's Leadership in Energy & Environmental Design (LEED) Rating System, as specified in Section 01 81 13, "SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS."
- C. COMMISSIONING: Refer to the Addendum to identify whether this project will be commissioned by an independent third party under separate contract with the City of New York. Commissioning shall be in accordance with ASHRAE and USGBC LEED-NC procedures, as described in Section 01 91 13, GENERAL COMMISSIONING REQUIREMENTS. The Contractor shall cooperate with the commissioning agent and provide whatever assistance is required.

#### 1.2 SUMMARY:

- A. This Section includes administrative provisions for coordinating construction operations on the Project including without limitation the following.
  - 1. Coordination Drawings.
  - 2. Administrative and supervisory personnel.
  - 3. Project meetings.
  - 4. Requests for Interpretation (RFIs).
- B. This section includes the following:
  - 1. Definitions
  - 2. Coordination
  - 3. Submittals
  - 4. Administrative and Supervisory Personnel
  - 5. Project Meetings
  - 6. Requests for Interpretation (RFI's)
  - 7. Correspondence
  - 8. Contractor's Daily Reports
  - 9. Alternate and Substitute Equipment
- C. RELATED SECTIONS: include without limitation the following:
  - 1. Section 01 10 00 SUMMARY
  - 2. Section 01 32 00 CONSTRUCTION PROGRESS DOCUMENTATION
  - 3. Section 01 33 00 SUBMITTALS
  - 4. Section 01 35 26 SAFETY REQUIREMENTS
  - 5. Section 01 73 00 EXECUTION REQUIREMENTS
  - 6. Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PROJECT MANAGEMENT AND COORDINATION 01 31 00 -1



### 7. Section 01 77 00 PROJECT CLOSEOUT PROCEDURES


NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

### **1.3 DEFINITIONS:**

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.

### 1.4 COORDINATION:

- A. Coordination: The Contractor shall coordinate its construction operations, including those of its subcontractors, with other entities to ensure the efficient and orderly installation of each part of the Work. The Contractor shall coordinate the various operations required by different Sections of the Specifications that depend on each other for proper installation, connection, and operation.
  - 1. Schedule construction operations in sequence in order to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
  - 2. Coordinate installation of different components to ensure maximum accessibility for required maintenance, service, and repair.
  - 3. Make adequate provisions to accommodate items scheduled for later installation.
  - 4. Where availability of space is limited, coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair of all components, including mechanical and electrical.
- B. The Contractor shall prepare memoranda for distribution to its subcontractors and other involved entities, outlining special procedures required for coordination. Such memoranda shall include required notices, reports, and meeting minutes as applicable.
- C. Administrative Procedures: The Contractor shall coordinate scheduling and timing of required administrative procedures with other construction activities and activities of its subcontractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include without limitation the following:
  - 1. Preparation of Contractor's Construction Schedule.
  - 2. Installation and removal of temporary facilities and controls.
  - 3. Delivery and processing of submittals.
  - 4. Progress meetings.
  - 5. Pre-installation conferences..
  - 6. Startup and adjustment of systems.
  - 7. Project closeout activities.
- D. Conservation: The Contractor shall coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials.



### 1.5 SUBMITTALS:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- A. Submit shop drawings, product data, samples etc. in compliance with Section 01 33 00, SUBMITTAL PROCEDURES.
- B. Coordination Drawings: The Contractor shall prepare applicable Coordination Drawings in compliance with the requirements for Coordination Drawings in Section 01 33 00, SUBMITTAL PROCEDURES.
- C. Safety Plan in compliance with Section 01 35 26, SAFETY REQUIREMENTS PROCEDURES.
- D. Waste Management Plan in compliance with Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
- E. Key Personnel Names: Within 15 days after the Notice to Proceed, the Contractor shall submit a list of key personnel assignments of the Contractor and its subcontractors, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home and office telephone numbers. Provide names, addresses, and telephone numbers of individuals assigned as standbys in case of the absence of individuals assigned to Project.
  - 1. Post copies of list in Project meeting room, in temporary field office, and by each temporary telephone. Keep list current at all times.
  - In addition to Project superintendent, provide other administrative and supervisory personnel as required for proper performance of the Work. Include special personnel required for coordinating all operations by its subcontractors.

#### 1.6 PROJECT MEETINGS:

- A. General: The Resident Engineer will hold regularly scheduled construction progress meetings at the site, at which time the Contractor and appropriate subcontractors shall have their representatives present to discuss all details relative to the execution of the work. The Resident Engineer shall preside over these meetings.
  - 1. Agenda: Prior to each meeting, the Resident Engineer will consult with the Contractor and will prepare an agenda of items to be discussed. In general, after informal discussion of any item on the agenda, the Resident Engineer will summarize the discussion in a brief written statement, and the Contractor will then dictate a brief statement for the record.
  - 2. Coordination: In addition to construction progress meetings called by the Resident Engineer, the Contractor shall hold regularly scheduled meetings for the purpose of coordinating; expediting and scheduling the work in accordance with the master coordinated Job Progress Chart. The Contractore and its subcontractors, material suppliers or vendors whose presence is necessary, are required to attend. These meetings may, at the discretion of the Contractor, be held at the same place and immediately following the project meetings held by the Resident Engineer. Minutes of these meetings shall be recorded, typed and printed by the Contractor and distributed to all parties concerned.

### B. PRECONSTRUCTION KICK-OFF MEETING:

1. The Resident Engineer will schedule a preconstruction kick-off meeting either at DDC's main office or at the Project site to review responsibilities and personnel assignments and clarify the

New YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

role of each participant. Unless otherwise directed the Design Consultant will record and distribute meeting minutes.

 Attendees: Authorized representative of the Client Agency; Design Consultant; the Contractor and its superintendents, subcontractor(s) and their superintendent(s); LEED sub-consultant and Commissioning Authority /Agent (CxA) as applicable and other concerned parties. All participants at the meeting shall be familiar with the Project and authorized to conclude matters relating to the Contract Work.

- 3. Agenda: Includes without limitation the following as applicable:
  - a. Establishing construction schedule
  - b. Schedule for regular construction meetings
  - c. Phasing
  - d. Critical work sequencing and long-lead items
  - e. Designation of key personnel and their duties
  - f. Reviewing Application for Payment and Change Order Procedures
  - g. Procedures for Requests for Information (RFIs.)
  - h. Review Permits and Approval requirements
  - i. Review all recent Administrative Code reporting requirements relating to the project, (i.e. LL 77, LL86 etc.)
  - j. Procedures for testing and inspecting
  - k. Reviewing special conditions at the Project site
  - I. Distribution of the Contract Documents
  - m. Submittal procedures
  - n. Safety Procedures
  - o. LEED requirements
  - p. Commissioning Requirements
  - q. Preparation of Record Documents
  - r. Historic Treatment requirements
  - s. Use of the premises
  - t. Work restrictions
  - u. Client Agency occupancy requirements
  - v. Responsibility for temporary facilities, services and controls
  - w. Construction Waste Management and Disposal
  - x. Indoor Air Quality Management Plan
  - y. Dust Mitigation Plan
  - z. Office, work, and storage areas
  - aa. Equipment deliveries and priorities
  - bb. Security
  - cc. Progress cleaning
  - dd. Working hours





### C. CONSTRUCTION PROGRESS MEETINGS:

- 1. The Resident Engineer will schedule and conduct construction progress meetings at bi-weekly intervals or as otherwise determined. All participants at the meeting shall be familiar with the Project and authorized to conclude matters relating to the Work. Unless otherwise directed the Design Consultant will record and distribute meeting minutes.
- 2. Attendees:
  - a. Design Consultant and applicable sub-consultants
  - b. Client Agency Representative
  - c. Representatives from the Contractor, sub-contractor(s), suppliers or other entities involved in the current progress, planning, coordination or future activities of the Work
  - d. Other appropriate DDC personnel, DDC consultants and concerned parties
- 3. Agenda: Includes without limitation the following:
  - a. Review the Construction Schedule and progress of the Work. Determine if the Work is on time, ahead of schedule or behind schedule. Determine actions to be taken to maintain or accelerate the schedule
  - b. Review and approve prior meeting minutes and follow up open issues
  - c. Coordinate work between each subcontractor
  - d. Sequence of Operations
  - e. Status of submittals, deliveries and off-site fabrication
  - f. Status of inspections and approvals by governing agencies
  - g. Temporary facilities and controls
  - h. Review Site Safety
  - i. Quality and work standards
  - j. Field observations
  - k. Status of correction of deficient items
  - I. RFI's
  - m. Pending changes
  - n. Status of outstanding Payments and Change Orders
  - o. LEED requirements including Construction Waste Management, Indoor Air Quality Plan, Dust Mitigation and Commissioning
  - p. Status of Administrative Code reporting requirements related to the project.

### 1.7 REQUESTS FOR INFORMATION (RFI):

- A. Procedure: Immediately on discovery of the need for information or interpretation of the Contract Documents, and if not possible to request interpretation at Project meeting, the Contractor shall prepare and submit an RFI in the form specified by the Resident Engineer.
  - 1. RFI shall originate with the Contractor. RFIs submitted by entities other than Contractor will be returned with no response.
  - 2. Coordinate and submit RFI in a prompt manner to the Resident Engineer so as to avoid delays in Contractor's work or work of its subcontractors.
  - 3. RFI Log: The Contractor shall prepare, maintain, and submit a tabular log of RFIs organized by the RFI number monthly to the Resident Engineer.



4. On receipt of responses and action to the RFI, the Contractor shall update the RFI log and immediately distribute the RFI response to affected parties. Review response(s) and notify the Resident Engineer immediately if the Contractor disagrees with response(s).

#### **1.8 CORRESPONDENCE:**

Copies of all correspondence to DDC shall be sent directly to the Resident Engineer at the job site.

### 1.9 CONTRACTOR'S DAILY REPORTS:

The Contractor shall prepare and submit Daily Construction Progress Reports as outlined in Section 01 32 00, CONSTRUCTION PROGRESS DOCUMENTATION.

PART II – PRODUCTS (Not Used) PART III – EXECUTION (Not Used) END OF SECTION 01 31 00



### SECTION 01 32 00 CONSTRUCTION PROGRESS DOCUMENTATION

#### PARTI - GENERAL

#### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

### 1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for establishing an effective base line schedule for the project and documenting the progress of construction during performance of the Work by developing, revising as necessary, various documents including but not limited to the following:
  - 1. Baseline Construction Schedule.
  - 2. Composite Schedule for entire project
  - 3. Recovery Composite Schedule
  - 4. Revised and/or updated Composite Schedule
  - 5. Submittals Schedule.
  - 6. Daily construction reports.
  - 7. Material location reports.
  - 8. Field condition reports.
  - 9. Special reports.
- B. RELATED SECTIONS: include without limitation the following:
  - 1. Section 01 10 00 SUMMARY
  - 2. Section 01 32 22 PHOTOGRAPHIC DOCUMENTATION
  - 3. Section 01 33 00 SUBMITTAL PROCEDURES
  - 4. Section 01 40 00 QUALITY REQUIREMENTS

### 1.3 **DEFINITIONS:**

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.



C. Baseline Construction Schedule:

A horizontal bar chart type schedule (Microsoft Project OR similar program) listing all the activities and their duration for entire contract duration OR construction period, including logical ties and interrelations between the activities necessary for the timely and successful completion of the project. Critical path activities shall be clearly marked. The Baseline construction schedule is a preliminary schedule that must be reviewed and approved by the Resident Engineer.

### D. Composite Schedule:

A composite horizontal bar chart type schedule (Microsoft Project OR similar program) listing all activities to be performed by the Contractor and its subcontractors, the duration of each activity including logical ties and interrelations between activities, and the sequence of each of necessary activities for the timely and successful completion of the project within the stipulated contract duration. Critical path activities shall be clearly marked. The Composite schedule must be signed and submitted by the Contractor within thirty (30) calendar days after the date established for commencement of the Contract, unless otherwise directed. The Composite Schedule must be reviewed and approved by the Resident Engineer.

E. Recovery Composite Schedule: A Recovery Composite Schedule is not required unless the City issues an Acceleration Change Order.

A Composite Schedule outlining and incorporating extraordinary efforts required to recover lost time with the aim of achieving completion of the project within the stipulated contract duration, plus authorized time extensions. In such case special attention must be given to keep the delays as minimum as possible and must establish the nature of efforts such as extended hours of work, weekend work, accelerated fabrication, required action(s) or effort(s) by the Contractor, its subcontractors, consultants, clients, end users and/or other concerned parties.

Such schedule must be prepared and submitted within Five (5) calendar days of request by the Resident Engineer. The Recovery Composite Schedule must be reviewed and approved by the Resident Engineer.

F. Revised and/or Updated Composite Schedule:

A Baseline construction schedule OR Composite Schedule OR Recovery Composite Schedule for the project that shows the actual duration of all the completed activities, including duration of and the reasons for delays, if any has occurred, AND revisions to all remaining activities of the Contractor and its subcontractors, including changes, if any, to logical ties, interrelations and the sequence of each of the outlined activities. Any such revisions should be shown on the row just below the approved schedule of the respective activity so that revisions can be compared.

The Revised and/or updated Composite Schedule must be reviewed and approved by the Resident Engineer.

- G. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.
- H. Event: The starting or ending point of an activity.
- I. Fragment: A part of the activity that breaks down activities into smaller activities for greater detail.
- J. Milestone: A key or critical point in time for reference or measurement.
- K. Network Diagram: A graphic diagram of a network schedule, showing activities and activity relationships.

CONSTRUCTION PROGRESS DOCUMENTATION 01 32 00 - 2



### PART II - PRODUCTS

**D** ] **D** ] •

### 2.1 BASELINE CONSTRUCTION SCHEDULE:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- A. The Contractor shall prepare a Baseline horizontal bar-chart-type construction schedule for the project. Submit the Baseline Construction Schedule to the Resident Engineer within (15) fifteen calendar days after the date established for commencement of the Contract, unless directed otherwise. The Baseline Schedule must be reviewed and approved by the Resident Engineer.
  - 1. Provide a separate time bar for each significant construction activity. Coordinate each activity on the schedule with other construction activities for proper interrelationship & sequence.
  - 2. Duration: The duration of each activity on the schedule besides installation must clearly show required duration of filing for permits, inspections, testing, approvals, shop drawings and materials submittals and approvals, fabrication, delivery, phasing for each construction activity.
  - 3. Schedule shall be time-scaled in not more than weekly increments, with the dates of the first day (Monday) of each week indicated.
  - Completion of all the project activities shall be indicated in advance of the date established for completion of the Contract, allowing time for required inspection and punch list work.
  - 5. Clearly show time bar for all the tasks, to be completed before start of physical work of scheduled activities, including but not limited to obtaining required permit, subcontractor approval, submission and approval of shop drawings, field verification, time for fabrication and delivery, testing of materials and/or samples, preparation and approval of mock-up sample, curing, pre-testing of soil, pre-testing of equipment including start up, testing & adjusting, filing for inspection by regulatory agencies, training, final use, etc. required to maintain orderly progress of the activity. A special consideration must be given to those activities requiring early approvals because of long lead-time for manufacture or fabrication.
  - 6. Phasing: Arrange all activities in proper sequence to reflect requirements for phased completion, work by other entities, work by the City, City furnished items, coordination with existing work, limitations arising due to continued occupancies, non-interruptible services, partial completion for occupancy, site restrictions, provisions for future work, seasonal variations, environmental control, and similar conditions of the project.
  - Arrange all activities and/or show interrelationship and logical sequence of all activities, determine and mark all critical path activities including any phasing reflecting actual project condition.
  - 8. Keep at least two blank horizontal bars between all activities for recording actual progress and submitting Revised Schedule as defined in Sub-Section 1.3 G
  - 9. If necessary a new revised schedule shall be prepared in the same manner as outlined above.

# 2.2 COMPOSITE SCHEDULE FOR THE PROJECT:

- A. The Contractor shall prepare a Composite Schedule based on the approved Baseline Schedule Such schedule shall indicate graphically and chronologically the start and completion of each and every activity, including all the pre-activity and post activity tasks. Keep at least two blank horizontal bars between all activities for recording actual progress and/or revisions.
  - 1. If necessary the Contractore shall meet with each subcontractor and with the Resident Engineer to review and make warranted adjustments and finalize the Composite Schedule. Once the schedule is finalized, the Contractor shall sign and date a reproducible form of the Composite Schedule. The Composite Schedule must be finalized and signed by the Contractor within (30) thirty calendar days after the date established for commencement of the Contract, unless directed otherwise. The Composite Schedule must be reviewed and approved by the Resident Engineer.



#### 2.3 RECOVERY COMPOSITE SCHEDULE:

A. A Recovery Composite Schedule is not required unless the City issues an Acceleration Change Order. A Recovery Composite Schedule outlining and incorporating extraordinary efforts required to recover lost time with the aim of achieving completion of the project within the stipulated contract duration, plus authorized time extensions, must be developed and submitted within (5) five calendar days of the request by the Resident Engineer. Such Recovery Composite Schedule shall include all information as defined in Article 1.3 F and shall be prepared in the same manner as outlined in Sub-Sections 2.1 and 2.2. The Recovery Composite Schedule must be reviewed and approved by the Resident Engineer.

### 2.4 REVISED AND/OR UPDATED COMPOSITE SCHEDULE:

- A. The Contractor shall revise and/or update the approved Composite Schedule as directed. The Revised schedule shall be prepared in the same manner as outlined above in Sub-Sections 2.1 and 2.2.
- B. The Contractor shall mark actual progress, delays, work stoppage etc. in the row just below the approved schedule for the respective activity so that revisions can be compared.
- C. Such schedule also shall indicate graphically and chronologically any revisions to the start and completion of the remaining activities including revisions to all the pre-activity and post activity tasks for all subcontractors.
- D. If necessary, the Contractor shall meet with each subcontractor and with the Resident Engineer to review and make warranted adjustments and finalize the Revised Composite Schedule. Once the schedule is finalized, the Contractor shall sign and date a reproducible form of the Schedule. Such schedule must be prepared and submitted by the Contractor within Five (5) calendar days of request by the Resident Engineer. The Revised Composite Schedule must be reviewed and approved by the Resident Engineer.

#### 2.5 SUBMITTALS SCHEDULE:

- A. Preparation: The Contractor shall submit a schedule of submittals, arranged in chronological order by dates required by the construction schedule. Include time required for review, re-submittal, ordering, manufacturing, fabrication, and delivery when establishing dates.
- B. SCHEDULE F: Schedule F sets forth all submittal requirements for shop drawings and material samples. Schedule F is included in the Addendum. At the kick-off meeting, the Contractor must review this Schedule with the Resident Engineer and the Design Consultant. Within 10 days after the kick-off meeting, the Contractor must complete information on Schedule F concerning the submission date, the required delivery date and the fabrication time. For all required submittals of shop drawings and material samples, the Schedule F provided by the Contractor must indicate a submission date which is at least 20 business days prior to the date of the manufacture of the item or materials to be installed. In addition, if so directed by the Commissioner, the Schedule F provided by the Contractor must indicate a submission date which is within 60 business days after the kick-off meeting. In the event of any conflict between the Specifications and Schedule F, Schedule F omits either a reference to or information concerning a submittal requirement which is set forth in the Specifications), such omission from Schedule F shall have no effect and the Contractor's submittal obligation, as set forth in the Specifications, shall remain in full force and effect.
- C. Review: The Resident Engineer will review the Schedule F submitted by Contractor. Upon acceptance, the Resident Engineer will date and sign the schedule as approved and transmit it to the Design Consultant, Contractor and others within DDC as he/she deems appropriate.



#### 2.6 REPORTS:

A. Daily Construction Reports: The Contractor shall submit to the Resident Engineer written Daily Construction Reports at the end of each work day, recording basic information such as the date, day, weather conditions, and contract days passed, remaining contract duration/days and the following information concerning the Project.

Information: The reports shall be prepared by the Contractor's Superintendent and shall bear the Contractor's Superintendents signature. Each report shall contain the following information:

- 1. List of name of Contractor, subcontractors, their work force in each category, and details of activities performed.
- 2. The type of materials and/or major equipment being installed by the Contractor and/or by each subcontractor.
- 3. The major construction equipment being used by the Contractor and/or subcontractors.
- 4. Material and Equipment deliveries.
- 5. High and low temperatures and general weather conditions.
- 6. Accidents.
- 7. Meetings and significant decisions.
- 8. Unusual events.
- 9. Stoppages, delays, shortages, and losses.
- 10. Meter readings and similar recordings
- 11. Emergency procedures.
- 12. Orders and/or requests of authorities having jurisdiction.
- 13. Approved Change Orders received and implemented.
- 14. Field Orders and Directives received and implemented.
- 15. Services connected and disconnected.
- 16. Equipment or system tests and startups.
- 17. Partial Completions and occupancies.
- 18. Substantial Completions authorized.

NOTE: If there is NO ACTIVITY at site, a daily report indicating so and the reason for no activity at the site must be submitted.

- B. Material Location Reports: The contractor shall submit a Material Location Report at weekly OR monthly intervals as determined and established by the Resident Engineer. Such report shall include a comprehensive list of materials delivered to and stored at Project site. List shall be cumulative, showing materials previously reported plus items recently delivered. Include with list a statement of progress on and delivery dates for materials or items of equipment fabricated or stored away from Project site.
- C. Field Condition Reports: Immediately on discovery of a difference between field conditions and the Contract Documents, prepare and submit a detailed report. Submit a Request For Information (RFI) form with a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

#### 2.7 SPECIAL REPORTS:

A. Accident report, incident report, special condition report for the conditions out of control of any party involved with the project effecting project progress, explaining impact on the project schedule and cost if any.

PART III – EXECUTION (Not Used) END OF SECTION 01 32 00



No Text

### CONSTRUCTION PROGRESS DOCUMENTATION 01 32 00 - 6



### SECTION 01 32 33 PHOTOGRAPHIC DOCUMENTATION

### REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SECTION 01 32 33

#### PARTI- GENERAL

#### **1.1 RELATED DOCUMENTS:**

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract]

### 1.2 SUMMARY:

- A. This Section includes the following:
  - 1. Photographic Media
  - 2. Construction Photographs
  - 3. Pre-construction Photographs
  - 4. Periodic Construction Progress Photographs
  - 5. Special Photographs
  - 6. DVD Recordings
  - 7. Final Completion Construction Photographs
- B. RELATED SECTIONS: include without limitation the following:
  - 1. Section 01 10 00 SUMMARY
  - 2. Section 01 33 00 SUBMITTAL PROCEDURES
  - 3. Section 01 35 91 HISTORIC TREATMENT PROCEDURES
  - 4. Section 01 78 39 CONTRACT RECORD DOCUMENTS
  - 5. Section 01 81 19 INDOOR AIR QUALITY REQUIREMENTS FOR LEED BUILDINGS
- C. PHOTOGRAPHER The Contractor shall employ and pay for the services of a professional photographer who shall take photographs showing the progress of the work for all Contracts.

#### 1.3 DEFINITIONS:

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.

#### 1.4 SUBMITTALS:

A. Qualification Data: For photographer.



- B. Key Plan: With each Progress Photograph Submittal include a key plan of Project site and building with notation of vantage points marked for location and direction of each image. Indicate location, elevation or story of construction. Include same label information as corresponding set of photographs.
- C. Construction Progress Photograph Prints: Take Progress Photographs bi-weekly and submit four color prints of each photographic view for each trade to the Resident Engineer. Such photographs shall be included in each monthly progress report or as otherwise directed by the Resident Engineer.
- D. Construction Photograph Negatives: Submit a complete set of photographic negatives in individually protected negative sleeves with each submittal of prints. Identify negatives with label matching photographic prints.
- E. Digital Images: If Digital Media is used, submit a complete set of digital color image electronic files on CD-ROM with each submittal of prints. Identify electronic media with date photographs were taken. Submit images that have same aspect ratio as the sensor, un-cropped.

### 1.5 QUALITY ASSURANCE:

A. Photographer Qualifications: An individual who has been regularly engaged as a professional photographer of construction projects for not less than three years.

#### 1.6 COORDINATION:

A. The Contractor and its subcontractor(s) shall cooperate with the photographer and provide auxiliary services requested, including access to Project site and use of temporary facilities, including temporary lighting required to produce clear, well-lit photographs without obscuring shadows.

#### 1.7 COPYRIGHT:

- A. The Contractor shall include the provisions set forth below in the agreement between the Contractor and the Photographer who will provide the construction photographs described in this section. The Contractor shall submit to the Resident Engineer a copy of its agreement with the Photographer.
- B. Any photographs, images and/or other materials produced pursuant to this Agreement, and any and all drafts and/or other preliminary materials in any format related to such items produced pursuant to this Agreement, shall upon their creation become the exclusive property of the City.
- C. Any photographs, images and/or other materials provided pursuant to this Agreement ("Copyrightable Materials") shall be considered "work-made-for-hire" within the meaning and purview of Section 101 of the United States Copyright Act, 17 U.S.C. § 101, and the City shall be the copyright owner thereof and of all aspects, elements and components thereof in which copyright protection might exist. To the extent that the Copyrightable Materials do not qualify as "work-made-for-hire," the Photographer hereby irrevocably transfers, assigns and conveys exclusive copyright ownership in and to the Copyrightable Materials to the City, free and clear of any liens, claims, or other encumbrances. The Photographer shall retain no copyright or intellectual property interest in the Copyrightable Materials. The Copyrightable Materials shall be used by the Photographer for no purpose other than in the performance of this Agreement without the prior written permission of the City. The Department may grant the Photographer a license to use the Copyrightable Materials on such terms as determined by the Department and set forth in the license.
- D. The Photographer acknowledges that the City may, in its sole discretion, register copyright in the Copyrightable Materials with the United States Copyright Office or any other government agency authorized to grant copyright registrations. The Photographer shall fully cooperate in this effort, and agrees to provide any and all documentation necessary to accomplish this.



E. The Photographer represents and warrants that the Copyrightable Materials: (i) are wholly original material not published elsewhere (except for material that is in the public domain); (ii) do not violate any copyright Law; (iii) do not constitute defamation or invasion of the right of privacy or publicity; and (iv) are not an infringement, of any kind, of the rights of any third party. To the extent that the Copyrightable Materials incorporate any non-original material, the Photographer has obtained all necessary permissions and clearances, in writing, for the use of such non-original material under this Agreement, copies of which shall be provided to the City.

#### PART II - PRODUCTS

#### 2.1 PHOTOGRAPHIC MEDIA:

- A. Photographic Film: Medium format, 2-1/4 by 2-1/4 inches (60 by 60 mm).
- B. Digital Images:
  - 1. Construction Progress Images: Color images in JPEG format with minimum sensor size of 1.3 megapixels.
  - 2. Presentation Quality Images: Provide Color images in uncompressed TIFF format, produced by a digital camera with minimum sensor size of 4.0 megapixels, and at an image resolution of not less than 1024 by 768 with 8"x10" original capture at 300 dpi or greater.
- C. Prints:
  - 1. Format: 8-by-10-inch (203-by-254-mm) smooth-surface matte color prints on single-weight commercial-grade stock paper, with 1inch wide margins and punched for standard 3-ring binder.
  - 2. Identification: On the front of each photograph affix a label in the margin with Project name and date photograph was taken. On the back of each print, provide an applied label or rubber-stamped impression with the following information:
    - a. Project Contract I.D. Number.
    - b. Project Contract Name.
    - c. Name of Contractor. (and Subcontractor Trade Represented)
    - d. Subject of Image Taken.
    - e. Date and time photograph was taken if not date stamped by camera.
    - f. Description of vantage point, indicating location, direction and other pertinent information.
    - g. Unique sequential identifier.
    - h. Name and address of photographer.

### PART III - EXECUTION

#### 3.1 CONSTRUCTION PHOTOGRAPHS:

- A. General: Take photographs using the maximum range of depth of field, and that are in focus, to clearly show the Work. Photographs with blurry or out-of-focus areas will not be accepted.
  - 1. Maintain key plan with each set of construction photographs that identifies each photographic location and direction of view.
- B. Film Images:
  - 1. Date Stamp: Unless otherwise indicated, date and time stamp each photograph as it is being taken so stamp is integral to photograph.



- 2. Field Office Prints: Retain one set of prints of progress photographs in the field office at Project site, available at all times for reference. Identify photographs same as for those submitted to Commissioner.
- C. Digital Images: Submit digital images exactly as originally recorded in the digital camera, without alteration, manipulation, editing, or modifications using image-editing software.
  - 1. Date and Time: Include date and time in filename for each image.
  - 2. Field Office Images: Maintain one set of images on CD-ROM in the field office at Project site, available at all times for reference. Identify images same as for those submitted to Commissioner.

### 3.2 PRE-CONSTRUCTION & PRE-DEMOLITION PHOTOGRAPHS:

- A. Before commencement of Contract work at the site, take color photographs of Project site and surrounding properties, including existing structures or items to remain during construction, from different vantage points, as directed by the Resident Engineer.
  - 1. Flag applicable excavation areas and construction limits before taking construction photographs.
  - 2. Take photographs of minimum eight (8) views to show existing conditions adjacent to property before starting the Work.
  - 3. Take applicable photographs of minimum eight (8) views of existing buildings either on or adjoining property to accurately record physical conditions at start of construction.
  - 4. Take additional photographs as required or directed by the Resident Engineer to record settlement or cracking of adjacent structures, pavements, and improvements.
- B. Demolition Operations: Take photographs as directed by the Resident Engineer of minimum of eight (8) views each before commencement of demolition operations, at mid-point of operations and at completion of operations.
- C. Pre-Demolition Photographs: Take archival quality color photographs, to include all exterior building facades, of all structures at the Project site designated to be fully demolished or removed in compliance with NYC Building Code requirements. Submit four (4) complete sets of pre-demolition photographs, in the format specified herein, to the Resident Engineer for submission to the Department of Buildings.

### 3.3 PERIODIC CONSTRUCTION PROGRESS PHOTOGRAPHS:

A. Take photographs of minimum eight (8) views bi-weekly as directed by the Resident Engineer of construction progress for each contract trade. Select vantage points to show status of construction and progress since last photographs were taken.

#### 3.4 SPECIAL PHOTOGRAPHS:

- A. The photographer shall take special photographs of subject matter or events as specified in other sections of the Project Specifications from vantage points specified or as otherwise directed by the Resident Engineer.
- B. Historical Elements: As required in Section 01 35 91, HISTORIC TREATMENT PROCEDURES, for Contract work at designated landmark structures or sites the photographer, as specified and required by individual sections of the Contract documents or at the direction of the Commissioner, shall take images of existing elements scheduled to be removed for replacement, repair or replication in quantities as directed, including post-construction photographs of completed work as directed by the Commissioner.



1. Take Presentation Quality Photographs of designated landmark structures as directed by the Commissioner for submission to the New York City Landmarks Preservation Commission. Provide a minimum of four color photographic prints of each view as directed.

### 3.5 DVD RECORDING:

A. When DVD Recording of Demonstration and Training sessions is required for Non-Commissioned projects the Contractor shall provide the services of a Videographer as indicated in Section 01 79 00, DEMONSTRATION AND OWNER'S PRE-ACCEPTANCE ORIENTATION.

### 3.6 FINAL COMPLETION CONSTRUCTION PHOTOGRAPHS:

A. Take color photographs of minimum eight (8) unobstructed views of the completed project or project and site, as directed by the Commissioner and after all scaffolding, hoists, shanties, field offices or other temporary work has been removed and final cleaning is done after date of Substantial Completion for submission as Project Record Documents. Submit four (4) sets of each view of Presentation Quality photographic prints including negatives and/or digital images electronic file

#### END OF SECTION 01 32 33



No Text

PHOTOGRAPHIC DOCUMENTATION 01 32 33 - 6



## SECTION 01 33 00 SUBMITTAL PROCEDURES

#### PARTI- GENERAL:

#### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

#### 1.2 SUMMARY:

- A. This Section includes administrative and procedural requirements for submitting Shop Drawings, Coordination Drawings, Catalogue Cuts, Material Samples and other submittals required by the Contract Documents.
- B. Review of submittals does not relieve the Contractor of responsibility for any Contractor's errors or omissions in such submittals, nor from responsibility for complying with the requirements of the Contract.
- C. Responsibility of the Contractor: The approval of Shop Drawings will be general and shall not relieve the Contractor of responsibility for the accuracy of such Shop Drawings, nor for the proper fitting and construction of the work, nor of the furnishing of materials or work required by the Contract and not indicated on the Shop Drawings. Approval of Shop Drawings shall not be construed as approving departures from the Contract Drawings, Supplementary Drawings or Specifications.
- D. This Section includes the following:
  - 1. Definitions
  - 2. Submission Procedures
  - 3. Coordination Drawings
  - 4. LEED Submittals
  - 5. Ultra Low Sulfur Diesel Fuel Reporting
  - 6. Construction Photographs and DVD Recordings
  - 7. As-Built Documents
- 1.3 RELATED SECTIONS: Include without limitation the following:
  - A. Section 01 10 00 SUMMARY
  - B. Section 01 31 00 PROJECT MANAGEMENT AND COORDINATION
  - C. Section 01 32 00 CONSTRUCTION PROGRESS DOCUMENTATION
  - D. Section 01 32 33 PHOTOGRAPHIC DOCUMENTATION
  - E. Section 01 77 00 CLOSEOUT PROCEDURES
  - F. Section 01 78 39 CONTRACT RECORD DOCUMENTS
  - G. Section 01 81 13 SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS

## 1.4 DEFINITIONS:

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or

SUBMITTAL PROCEDURES 01 33 00 - 1




combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.

- C. Submittals: Written and graphic information that requires responsive actions and includes without limitation all shop drawings, product data, letters of certification, tests and other information required for quality control and as required by the Contract Documents.
- D. Informational Submittals: Written information that does not require responsive action. Submittals may be rejected for non-compliance with the Contract.
- E. Shop Drawings: Include drawings, diagrams, illustrations, schedules, performance charts, brochures, and other data, except for coordination drawings, specifically prepared for the project by the Contractor or any subcontractor, manufacturer, supplier or distributor, which illustrates how specific portions of the work shall be fabricated and/or installed.
- F. Coordination Drawings: As required in Section 01 31 00 PROJECT MANAGEMENT AND COORDINATION.
- G. Product Data and Quality Assurance Submittals: Includes manufacturer's standard catalogs, pamphlets and other printed materials including without limitation the following:
  - 1. Catalogue and Product specifications
  - 2. Installation instructions
  - 3. Color charts
  - 4. Catalog cuts
  - 5. Rough-in diagrams and templates
  - 6. Wiring diagrams
  - 7. Performance curves
  - 8. Operational range diagrams
  - 9. Mill reports
  - 10. Design data and calculations
  - 11. Certification of compliance or conformance
  - 12. Manufacturer's instructions and field reports

#### 1.5 COORDINATION DRAWINGS:

- A. The Contractor shall provide reproducible Coordination Drawing(s) of the reflective ceiling showing the integration of all applicable contract work, including general construction work as well as trade work (Plumbing, HVAC, and Electrical) to be performed by subcontractors. The Coordination Drawing(s) shall include, without limitation, the following information:
  - 1. General Construction work showing the reflective ceiling plan including starting points, ceiling and beam soffits elevations, ceiling heights, roof openings, etc.
  - HVAC Contract work showing ductwork, heating and sprinkler piping, location of grilles, registers etc. and access doors in hung ceilings. Locations shall be fixed by elevations and dimensions from column centerlines and/or walls.
  - 3. Plumbing Contract work including piping, valves, cleanouts etc., indicating locations and elevations and shall indicate the necessary access doors.
  - 4. Electrical Contract work indicating fixtures, large conduit runs, clearances, pull boxes, junction boxes, sound system speakers, etc.
- B. The Contractor shall issue the completed Coordination Drawing(s) to the Resident Engineer for his/her review. The Resident Engineer may call as many meetings as necessary with the Contractor, including



- C. Upon resolution of any conflicts, the Contractor shall provide a final Coordination Drawing(s) which will become the Master Coordination Drawing(s). The Master Coordination Drawing(s) shall be signed and dated by the Contractor to indicate acceptance of the arrangement of the work.
- D. A reproducible copy of the Master Coordination Drawing(s) shall be provided by the Contractor to each of the appropriate subcontractor(s), the Resident Engineer and the Design Consultant for information.
- E. Shop Drawings shall not be submitted prior to acceptance of the final coordinated drawings and shall be prepared in accordance with the Master Coordination Drawing(s). No work will be permitted without accepted Shop Drawings. It is therefore essential that this procedure be instituted as quickly as possible.

#### 1.6 SUBMITTAL PROCEDURES:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- A. Refer to Section 01 35 03 GENERAL MECHANICAL REQUIREMENTS and Section 01 35 06 GENERAL ELECTRICAL REQUIREMENTS for additional submittal requirements involving electrical and mechanical work or equipment of any nature called for the project.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
  - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activities, with the Submittal Schedule specified in Section 01 32 00 CONSTRUCTION PROGRESS DOCUMENTATION.
  - 2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
  - 3. The Commissioner reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- C. Submittals Schedule: The Submittals Schedule is set forth in Schedule F, which is included in the Addendum.
- D. Identification: Place a permanent label or title block on each submittal for identification.
  - 1. Indicate name of firm or entity that prepared each submittal on label or title block.
  - 2. Provide a space approximately 6 by 8 inches on label or beside title block to record Contractor's review and approval markings and action taken by Design Consultant.
  - 3. Include the following minimum information on label for processing and recording action taken:
    - a. Project name, DDC Project Number and Contract Number
    - b. Date.
    - c. Name and address of Design Consultant.
    - d. Name and address of Contractor.
    - e. Name and address of subcontractor.
    - f. Name and address of supplier.
    - g. Name of manufacturer.
    - h. Submittal number or other unique identifier, including revision identifier.
    - i. Number and title of appropriate Specification Section.
    - j. Drawing number and detail references, as appropriate.
    - k. Location(s) where product is to be installed, as appropriate.
    - I. Other necessary identification.
- E. Transmittal:
  - 1. Package each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form in triplicate. Transmittals received from sources other than the







Contractor will be returned without review. Re-submission of the same drawings or product data shall bear the original number of the prior submission and the original titles.

- 2. Transmittal Form: Provide locations on form for the following information:
  - a. Project name, DDC Project number and Contract Number
  - b. Date.
  - c. Destination (To:).
  - d. Source (From:)
  - e. Names of Contractor, subcontractor, manufacturer, and supplier.
  - f. Category and type of submittal.
  - g. Submittal purpose and description.
  - h. Specification Section number and title.
  - i. Drawing number and detail references, as appropriate.
  - j. Transmittal number, numbered consecutively.
  - k. Submittal and transmittal distribution record.
  - I. Remarks.
  - m. Signature of transmitter.
- F. Shop Drawings:
  - 1. Procedures for Preparing, Forwarding, Checking and Returning all Shop Drawings shall be, generally, as follows:
    - a. The Contractor shall make available to its subcontractors the necessary Contract Documents and shall instruct such subcontractor to determine dimensions and conditions in the field, particularly with reference to coordination between the trade subcontractors. The Contractor shall direct its subcontractors to prepare Shop Drawings for submission to the Design Consultant in accordance with the requirements of these General Conditions. The Contractor shall also direct its subcontractors to "Ring Up" corrections made on all re-submissions for approval, so as to be readily seen, and that the symbol "sub" be used to identify the source of the correction or information that has been added.

The Contractor shall:

- 1. Review and be responsible to the Commissioner, for information shown on its subcontractor's Shop and Installation drawings and manufacturers' data, and also for conformity to Contract Documents.
- 2. "Ring Up" corrections made on all submissions for approval, so as to be readily seen, and that the symbol "GC", "PL", "HVAC" or "EL" be used to indicate that the correction and/or information added was made by the Contractor and/or its subcontractor(s).
- Clearly designate which entity is to perform the work when the term, "work by others" or other similar phrases are indicated on the Contract Drawings before submission to the Design Consultant.
- 4. Stamp submissions "Recommended for Acceptance", date and forward to the Design Consultant.
- 2. The Contractor shall promptly prepare and submit project specific layout detail and Shop Drawings of such parts of the work as are indicated in the Specifications, Schedule F of the Addendum or as required. These Shop Drawings shall be made in accordance with the Contract Drawings, Specifications and Supplementary Drawings, if any. The Shop Drawings shall be accurate and distinct and give all the dimensions required for the fabrication, erection and installation of the work.

3. Size of Drawings: The Shop Drawings, unless otherwise directed, shall be on sheets of the same size as the Contract Drawings, drawn accurately and of sufficient scale to be legible, with a one half (1/2) inch marginal space on each side and a two (2) inch marginal space for binding on the left side.



- 4. Scope of Drawings: Shop Drawings shall be numbered consecutively and shall accurately and distinctly represent all aspects of the work, including without limitation the following:
  - a. All working and erection dimensions.
  - b. Arrangements and sectional views.
  - c. Necessary details, including performance characteristics, and complete information for making necessary connections with other work.
  - d. Kinds of materials including thickness and finishes.
  - e. Identification of products.
  - f. Fabrication and installation drawings.
  - g. Roughing-in and setting diagrams.
  - h. Wiring diagrams showing field-installed wiring, including power, signal, and control wiring.
  - i. Shop work manufacturing instructions.
  - j. Templates and patterns.
  - k. Schedules.
  - I. Design calculations.
  - m. Compliance with specified standards.
  - n. Notation of coordination requirements.
  - o. Notation of dimensions established by field measurement.
  - p. Relationship to adjoining construction clearly indicated.
  - q. Seal and signature of professional engineer if specified.
  - r. Wiring Diagrams: Differentiate between manufacturer-installed and field-installed wiring.
  - s. All other information necessary for the work and/or required by the Commissioner.
- 5. Titles and Reference: Shop Drawings shall be dated and contain:
  - a. Name of the Project, DDC Project Number and Contract Number.
  - b. The descriptive names of equipment, or materials covered by the Contract Drawings and the classified item number or numbers, if any, under which it is, or they are required.
  - c. The locations or points and sequence at which materials, or equipment, are to be installed in the work.
  - d. Cross references to the section number, detail number and paragraph number of the Contract Specifications.
  - e. Cross references to the sheet number, detail number, etc., of the Contract Drawings.
- 6. Field Measurements: In addition to the above requirements, the Shop Drawings shall be signed by the Contractor and, if applicable, the subcontractor responsible for preparation of the Shop Drawings. Each Shop Drawing shall be stamped with the following wording:

FIELD MEASUREMENTS: The Contractor certifies that it has verified and supplemented the Contract Drawings by taking all required field measurements, which said measurements correctly reflect all field conditions and that this Shop Drawing incorporates said measurements.

7. Contractor's Statement with Submittal: Any Submittal by the Contractor for acceptance, including without limitation, all dimensional drawings of equipment, blueprints, catalogues, models, samples and other data relative to the equipment, the materials, the work or any part thereof, must be accompanied by a statement that the Submittal has been examined by the Contractor and that everything shown in the Submittal is in accordance with the requirements of the Contract Drawings and Specifications. If there is any discrepancy between what is shown in the Submittal and the requirements of the Contract Drawings and Specifications, the Contractor shall, in its statement, list and clearly describe each such discrepancy.

Acceptance will be given based upon the Contractor's representation that what is shown in the Submittal is in accordance with the requirements of the Contract Drawings and Specifications. If



NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

> the Contractor's statement indicates any discrepancy between what is shown in the Submittal and the requirements of the Contract Drawings and Specifications, such change is subject to review and prior written acceptance by the Design Consultant. In addition, such change may require a change order in accordance with Article 25 of the Contract. In the event any such change is approved, any additional expense or increased cost in connection with the change is the sole responsibility of the Contractor.

- 8. Submission of Shop Drawings:
  - a. Initial Submission: The Contractor shall submit seven (7) copies of each Shop Drawing to the Design Consultant for his/her review and acceptance. The Design Consultant will transmit Shop Drawings to appropriate sub-consultants for review and acceptance, including Commissioning Authority/Agent as applicable. A satisfactory Shop Drawing will be stamped "No Exceptions Taken", be dated and distributed by the Design Consultant as follows:
    - 1) Two (2) copies thereof will be returned to the Contractor by letter.
    - 2) Three (3) copies of the approved Shop Drawing and copy of the transmittal letter to the Contractor will be forwarded to DDC.
    - 3) One copy will be retained by the Design Consultant.
    - 4) One copy will be forwarded / retained by sub-consultant(s) as appropriate.

Should the Shop Drawing(s) be "Rejected" or noted "Revise and Resubmit" by the Design Consultant, the Design Consultant will return the Shop Drawings to the Contractor with the necessary corrections and changes to be made as indicated thereon.

- b. Revisions: The Contractor must make such corrections and changes and again submit seven (7) copies of each shop drawing to the Design Consultant. The Contractor shall revise and resubmit the Shop Drawing as required by the Design Consultant until the Shop Drawings are stamped "No Exceptions Taken". However, Shop Drawings which have been stamped "Make Corrections Noted" shall be considered an "Acceptable" Shop Drawing and NEED NOT be resubmitted.
- c. Commencement of Work: No work or fabrication called for by the Shop Drawings shall be done until the acceptance of the said drawings by the Design Consultant is given. In addition to the foregoing Shop Drawing transmissions, a copy of any Shop Drawing prepared by any of the Contractor's subcontractors which Shop Drawing indicated work related to, adjacent to, impinging upon, or affecting work to be done by other subcontractors shall be transmitted to the subcontractors so affected. [These accepted Shop Drawings shall be distributed to the affected subcontractors when required with a copy of the transmittal to the Resident Engineer.]
- d. Variations: If the Shop Drawings show variations from the Contract requirements because of standard shop practice or other reasons, the Contractor shall make specific mention of such variations in its letter of submittal. Acceptance of the Shop Drawings shall constitute acceptance of the subject matter thereof only and not of any structural apparatus shown or indicated.

#### G. Product Data:

- 1. General: Except as otherwise prescribed herein, the submission, review and acceptance of Product Data and Catalogue cuts shall conform to the procedures specified in Sub-Section 1.6 F, Shop Drawings.
- 2. If information must be specially prepared for submittal because standard printed data are not suitable for use, submit as Shop Drawings, not as Product Data.
- Mark each copy of each submittal to show which products and options are applicable.
- 4. Include the following information, as applicable:

- New York CITY DEPARTMENT OF DESIGN + CONSTRUCTION
  - a. Manufacturer's written recommendations.
  - b. Manufacturer's product specifications.
  - c. Manufacturer's installation instructions.
  - d. Standard color charts.
  - e. Manufacturer's catalog cuts.
  - f. Wiring diagrams showing factory-installed wiring.
  - g. Printed performance curves.
  - h. Operational range diagrams.
  - i. Mill reports.
  - j. Standard product operation and maintenance manuals.
  - k. Compliance with specified referenced standards.
  - I. Testing by recognized testing agency.
  - m. Application of testing agency labels and seals.
  - n. Notation of coordination requirements.
  - 5. Submit Product Data before or concurrent with Samples.
  - 6. Submission of Product Data:
    - a. Initial Submission: The Contractor shall submit seven (7) sets of Product Data to the Design Consultant for his/her review and acceptance. The Design Consultant will transmit Product Data to appropriate sub-consultants for review and acceptance, including Commissioning Authority/Agent as applicable. A satisfactory catalogue cut will be stamped "No Exception Taken", be dated and distributed as follows:
      - 1) Two (2) copies thereof will be returned to the Contractor by letter.
      - Three (3) copies of the Product Data and copy of the transmittal letter to the Contractor will be forwarded to DDC
      - 3) One copy will be retained by the Design Consultant.
      - 4) One copy will be forwarded / retained by sub-consultant(s) as appropriate.

Should the Product Data be "Rejected" or noted "Revise and Resubmit" by the Design Consultant, the Design Consultant will return one (1) set of such Product Data to the Contractor with the necessary corrections and changes to be made indicated and one (1) set to DDC.

- 7. Revisions: The Contractor must make such corrections and changes and again submit seven (7) copies of each Product Data for the review of the Design Consultant. The Contractor shall revise and resubmit the Product Data as required by the Design Consultant until the submission is stamped "No Exceptions Taken" by the Design Consultant. However, Product Data which has been stamped "Make Corrections Noted" shall be considered an "Accepted" Product Data and NEED NOT be resubmitted.
- H. Samples of Materials:
  - 1. For samples of materials involving electrical work of any nature, refer to Section 00 35 06 General Electrical Requirements.
  - 2. Samples shall be in triplicate, of sufficient size to show the quality, type, range of color, finish and texture of the material.
  - 3. Each of the samples shall be labeled as follows:
    - a. Name of the Project, DDC Project Number and Contract Number.
    - b. Name and quality of the material.
    - c. Date.



NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- d. Name of Contractor, subcontractor, manufacturer and supplier.
- e. Related Specification or Contract Drawing reference to the samples submitted.
- 4. A letter of transmittal, in triplicate, from the Contractor requesting acceptance must accompany all such samples.
- 5. Transportation charges to the Design Consultant's office must be prepaid on all samples forwarded.
- 6. Samples for testing purposes shall be as required in the Specifications.
- 7. Samples on Display: When samples are specified to be equal to approved product, they shall be carefully examined by the Contractor and by those whom the Contractor expects to employ for the furnishing of such materials.
- 8. Timely Submissions Log/Schedule: Samples shall be submitted in accordance with approved Shop Drawing log so as to permit proper consideration without delaying any operation under the project. Materials should not be ordered until acceptance is received, in writing, from the Design Consultant. All materials shall be furnished equal in every respect to the accepted samples.
- 9. The Acceptance of any samples will be given as promptly as possible, and shall be only for the characteristic color, texture, strength, or other feature of the material named in such approval, and no other. When this approval is issued by the Design Consultant, it is done with the distinct understanding that the materials to be furnished will fully and completely comply with the Specifications, the determination of which may be made at some later date by a laboratory test or by other procedure. Use of materials will be permitted only so long as the quality remains equal to the approved samples and complies in every respect with the Specifications, and the colors and textures of the samples on file in the office of the Design Consultant, for the project.
- 10. Acceptability of test Data: The Commissioner will be the final judge as to acceptability of laboratory test data and performance in service of materials submitted.
- 11. Valuable Samples: Valuable samples, such as hardware, plumbing and electrical fixtures, etc., not destroyed by inspection or test, will be returned to the Contractor and may be incorporated into the work after all questions of acceptability have been settled, providing suitable permanent records are made as to the location of the samples, their properties, etc.
- 12. Equivalent Quality: Any material, article and/or equipment which is designated in the Drawings and/or Specifications by a number in the catalogue of any manufacturer or by a manufacturer's grade or trade name is designated for the purpose of describing the material, article and/or equipment and fixing the standard of performance and/or function, as well as the quality and/or finish. Any material, article and/or equipment which is other than what is specified in the Drawings and/or Specifications will only be accepted if the Commissioner makes a written determination that such material, article and/or equipment is equivalent to that which is specified in the Drawings and/or Specifications.
- 13. The submission of any material, article and/or equipment as the equal of any material, article and/or equipment set forth in the Drawings and/or Specifications as a standard shall be accompanied by any and all information essential for determining whether such proposed material, article and/or equipment is equivalent to that which is specified. Such information shall include, without limitation, illustrations, drawings, descriptions, catalogues, records of tests, samples, as well as information regarding the finish, durability and satisfactory use of such proposed material, article and/or equipment under similar operating conditions.



#### 1.7 LEED SUBMITTALS:

**D**]**D**]•

- A. Comply with submittal requirements specified in Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL; Section 01 81 13, SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS; Section 01 81 13.13, VOLATILE ORGANIC COMPOUND (VOC) LIMITS FOR ADHESIVES, SEALANTS, PAINTS AND COATINGS FOR LEED BUILDINGS; Section 01 81 19, INDOOR AIR QUALITY REQUIREMENTS FOR LEED BUILDINGS and Section 01 91 13, GENERAL COMMISSIONING REQUIREMENTS.
- B. LEED Building submittal information shall be assembled into one package per each applicable specification section, separate from all other non-LEED submittals. Each submittal package shall have a separate transmittal and identification as described in Sub-Section 1.6 herein.
- C. Number of Copies: Submit FOUR (4) copies of LEED submittals, in accordance with procedure described in Sub-Section 1.6 herein, unless otherwise indicated.
  - 1. LEED Submittals shall be clearly marked "LEED".

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- D. Material Safety Data Sheets (MSDSs) for LEED Certification: Submit information necessary to show compliance with LEED certification requirements, which will be the limit of the Design Consultant's review for LEED compliance.
  - 1. Designated LEED submittals that include non-LEED MSDS data will not be reviewed. The entire submittal will be returned for re-submission.
- E. Product Cut Sheets and/or Shop Drawings for LEED Certification: Provide product cut sheets and/or shop drawings with the Contractor's or sub-contractor's stamp, confirming that the submitted products are the products installed in the Project. For detailed requirements refer to Sub-Section 1.6 of Section 01 81 13 SUSTAINABLE DESIGN REQUIREMENTS FOR LEED PROJECTS.
  - 1. Provide the quantity, length, area, volume, weight, and/or cost of each product submitted as required to satisfy LEED documentation requirements. Refer to Sub-Section 1.6 of Section 01 81 13 SUSTAINABLE DESIGN REQUIREMENTS FOR LEED PROJECTS.

### 1.8 ULTRA LOW SULFUR DIESEL FUEL AND BEST AVAILABLE TECHNOLOGY REPORTING:

A. In accordance with Section 01 10 00 Summary, Sub-Section 1.5 E, the Contractor shall submit reports to the Commissioner regarding the use of Ultra Low Sulfur Diesel Fuel and Best Available Technology (BAT) in Non road Vehicles. Submission of such reports shall be in accordance with the schedule, format, directions and procedures established by the Commissioner.

#### 1.9 CONSTRUCTION PHOTOGRAPHS AND DVD RECORDINGS:

A. Submit construction progress photographs and DVD recordings in accordance with requirements of Section 01 32 33, PHOTOGRAPHIC DOCUMENTATION

#### 1.10 AS-BUILT DOCUMENTS:

A. Submit all as-built documents in accordance with Section 01 78 39 CONTRACT RECORD DOCUMENTS.



PART II - PRODUCTS (Not Used) PART III - EXECUTION (Not Used) END OF SECTION 01 33 00

> SUBMITTAL PROCEDURES 01 33 00 - 10



## SECTION 01 35 03 GENERAL MECHANICAL REQUIREMENTS

## REFER TO THE ADDENDUM FOR APPLICABILITY OF THIS SECTION 01 35 03

#### PARTI- GENERAL

### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

#### 1.2 SUMMARY:

A. The General Mechanical Requirements contained herein shall be followed by the Contractor, as well as its subcontractor for HVAC work. This Section sets forth the General Requirements applicable to mechanical work for the Project. Such requirements are intended to be read in conjunction with the Specifications and Contract Drawings for the Project. In the event of any conflict between the requirements set forth in this Section and the requirements of the Specifications and/or the Contract Drawings, whichever requirement is the most stringent, as determined by the Commissioner, shall take precedence.

#### 1.3 RELATED SECTIONS: Include without limitation the following:

- A. Section 01 10 00 SUMMARY
- B. Section 01 33 00 SUBMITTAL PROCEDURES
- C. Section 01 35 06 GENERAL ELECTRICAL REQUIREMENTS
- D. Section 01 42 00 REFERENCES
- E. Section 01 77 00 CLOSEOUT PROCEDURES
- F. Section 01 78 39 CONTRACT RECORD DOCUMENTS

#### 1.4 **DEFINITIONS**:

A. CONCEALED PIPING AND DUCTS -: shall mean piping and ducts hidden from sight in masonry or other construction, in floor fill, trenches, partitions, hung ceilings, furred spaces, pipe shafts and in service tunnels not used for passage. Where piping and ducts run in areas that have hung ceilings, such piping and ducts shall be installed in the hung ceilings. For work on existing piping any insulation on such existing piping is to be tested for asbestos and abated, if found to be positive by a certified asbestos contractor. Such testing and abatement shall occur prior to the performance of any work on these pipes.

#### 1.5 SUBMITTALS:

- A. INTENT OF MECHANICAL CONTRACT DRAWINGS Mechanical Contract Drawings are in part diagrammatic and show the general arrangement of the equipment, ducts and piping included in the Contract and the approximate size and location of the equipment.
- B. The Contractor shall follow these Contract Drawings in laying out the work and verify the spaces in which it will be installed. The Contractore shall submit, as directed, Mechanical Shop Drawings, roughing drawings, manufacturer's Shop Drawings, field drawings, cuts, bulletins, etc., of all materials, equipment and methods of installation shown or specified in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.



- 1. Submit sheet metal shop standards. Submit manufacturer's product data including gauges, materials, types of joints, scaling materials and installations for metal ductwork materials and products.
- 2. Submit scaled layout drawing (3/8"=1') of metal ductwork and fittings including, but not limited to, duct sizes, locations, elevations, slopes of horizontal runs, wall and floor penetrations and connections. Show modifications of indicated requirements made to conform to local shop practice and how those modifications ensure that free area, materials and rigidity are not reduced. Layouts should include all the room plans, mechanical equipment rooms and penthouses. Method of attachment of duct hangers to building construction all with the support details. Coordinate shop drawings with related trades prior to submission.
- Indicate duct fittings, particulars such as gauges, sizes, welds and configuration prior to start of work for low-pressure systems.
- 4. Submit maintenance data and parts lists for metal ductwork materials and products. Include this data, product data and shop drawings in maintenance manual.

#### 1.6 ACCESSIBILITY:

All work shall be installed by the Contractor so as to be readily accessible for inspection, operation, maintenance and repair. Minor deviations from the arrangement indicated on the Contract Drawings may be made to accomplish this, but they shall not be made without approval by the Commissioner.

#### 1.7 CHANGES IN PIPING, DUCTS, AND EQUIPMENT:

Wherever field conditions are such that for proper execution of the work, reasonable changes in location of piping, ducts and equipment are necessary and required, the Contractor shall make such changes as directed and approved, without extra cost to the City.

## 1.8 CLEANING OF PIPING, DUCTS, AND EQUIPMENT:

Piping, ducts and equipment shall be thoroughly cleaned by the Contractor of all dirt, cuttings and other foreign substances. Should any pipe, duct or other part of the several systems be obstructed by any foreign matter, the Contractor will be required to pay for disconnecting, cleaning and reconnecting wherever necessary for the purpose of locating and removing obstructions. The Contractor shall pay for repairs to other work damaged in the course of removing obstructions. For work on existing piping, ducts and equipment the Contractor shall pay special attention during this task so as not to disturb the insulation on such piping, ducts or equipment.

## 1.9 STANDARDIZATION OF SIMILAR EQUIPMENT:


Unless otherwise particularly specified, all equipment of the same kind, type or classification, and used for identical purposes, shall be the product of one (1) manufacturer.

#### 1.10 SUPPORTING STRUCTURES DESIGNED BY THE CONTRACTOR:

Unless otherwise specified, supporting structures for equipment to be furnished by the Contractor shall be designed by an Engineer licensed in New York State retained by the Contractor. Supporting structures shall be built by the Contractor of sufficient strength to safely withstand all stresses to which they may be subjected, within permissible deflections, and shall meet the following standards:

A. Structural Steel - ASTM Standard Specifications, AISC and New York City Construction Codes.





- C. Steel reinforcement for concrete shall be of intermediate grade and shall meet the requirements of the Standard Specifications for Billet Steel-Concrete Reinforcement Bars, ASTM.
- D. Drawings and calculations shall be submitted for review and acceptance in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

#### 1.11 ELIMINATION OF NOISE:

- A. All systems and/or equipment provided under the Contract shall operate without objectionable noise or vibration.
- B. Should operation of any one or more of the several systems produce noise or vibration which is, in the opinion of the Commissioner, objectionable, the Contractor shall at its own expense make changes in piping, equipment, etc. and do all work necessary to eliminate objectionable noise or vibration.
- C. Should noise or vibration found objectionable by the Commissioner be transmitted by any pipe or portions of the structure from systems and/or equipment installed under the Contract, the Contractor shall at its own expense install such insulators and make such changes in or additions to the installations as may be necessary to prevent transmission of this noise or vibration.

## 1.12 PRELIMINARY FIELD TEST:

As soon as conditions permit, the Contractor shall furnish all necessary labor and materials for, and shall make, preliminary field tests of the equipment to ascertain compliance with the requirements of the Contract. If the preliminary field tests disclose equipment that does not comply with the Contract, the Contractor shall, prior to the acceptance test, make all changes, adjustments and replacements required.

#### 1.13 INSTRUCTIONS ON OPERATION:

At the time the equipment is placed in permanent operation by the City, the Contractor shall make all adjustments and tests required by the Commissioner to prove that such equipment is in proper and satisfactory operating condition. The Contractor shall instruct the City's operating personnel on the proper maintenance and operation of the equipment for the period of time called for in the Specifications.

#### **1.14 CERTIFICATES:**

On completion of the work, the Contractor shall obtain certificates of inspection, approval, acceptance and of compliance with all laws from all agencies and/or entities having jurisdiction over the work and shall deliver these certificates to the Commissioner in accordance with Section 01 77 00 CLOSEOUT PROCEDURES. The work shall not be deemed substantially complete until the certificates have been delivered.

PART II – PRODUCTS (Not Used) PART III – EXECUTION (Not Used) END OF SECTION 01 35 03



No Text

## GENERAL MECHANICAL REQUIREMENTS 01 35 03 - 4



## SECTION 01 35 06 GENERAL ELECTRICAL REQUIREMENTS

#### PARTI- GENERAL

#### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

#### 1.2 SUMMARY:

- A. This Section sets forth the General Requirements applicable to electrical work for the Project. Such requirements are intended to be read in conjunction with the Specifications and Contract Drawings for the Project. In the event of any conflict between the requirements set forth in this Section and the requirements of the Project Specifications and/or the Contract Drawings, whichever requirement is the most stringent, as determined by the Commissioner, shall take precedence.
- B. This Section includes the following:
  - 1. Procedure for Electrical Approval

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- 2. Submittals
- 3. Electrical Installation Procedures
- 4. Electrical Conduit System Including Boxes (Pull, Junction and Outlet)
- 5. Electrical Wiring Devices
- 6. Electrical Conductors and Terminations
- 7. Circuit Protective Devices
- 8. Distribution Centers
- 9. Motors
- 10. Motor Control Equipment
- 11. Schedule of Electrical Equipment

#### 1.3 RELATED SECTIONS: Include without limitation the following:

- A. Section 01 10 00 SUMMARY
- B. Section 01 33 00 SUBMITTAL PROCEDURES
- C. Section 01 35 03 GENERAL MECHANICAL REQUIREMENTS
- D. Section 01 42 00 REFERENCES
- E. Section 01 77 00 CLOSEOUT PROCEDURES
- F. Section 01 78 39 CONTRACT RECORD DOCUMENTS

## 1.4 **DEFINITIONS:**

- A. WIRING: means both wire and raceway (rigid steel, heavy wall conduit unless specifically indicated otherwise).
- B. POWER WIRING: means wiring from a panel board or other specified source to a starter (if required) then to a disconnect (if required), then to the final point of usage such as a motor, unit or device.
- C. CONTROL and/or INTERLOCK WIRING: means that wiring that signals the device to operate or shut down in response to a signal from a remote control device such as a temperature, smoke, pressure, float,

GENERAL ELECTRICAL REQUIREMENTS 01 35 06 - 1



etc. device (starters and disconnect switches are not included in this definition) regardless of the voltage required for the controlling device.

- D. RIGID STEEL CONDUIT: shall mean rigid steel, heavy wall conduit that is hot dipped galvanized inside and outside. The conduit shall meet the requirements of the latest edition, as amended, of the "Standard for Rigid Steel Conduit" of the Underwriters' Laboratories, Inc. Unless otherwise specified in the Specifications or indicated on the Contract Drawings, rigid steel conduit shall be used for all exposed work, for all underground conduits in contact with earth and for fire alarms systems, as required by the New York City Construction Codes:
- E. ELECTRICAL METALLIC TUBING (EMT): shall mean industry standard thin wall conduit of galvanized steel only. All elbows, bends, couplings and similar fittings which are installed as a part of the conduit system shall be compatible for use with electric metallic tubing. Couplings and terminating fittings shall be of the pressure type as approved by the Commissioner. Set screw fittings will not be acceptable. EMT shall meet the requirements of the latest edition, as amended, of the "Standard for Electrical Metallic Tubing of the Underwriters Laboratories Inc." EMT may only be used where specifically indicated. In no case will EMT be permitted in spaces other than hung ceilings and dry wall partitions.
- F. FLEXIBLE METALLIC CONDUIT (FMC): Shall mean a conduit made through the coiling of a selfinterlocking ribbed strip of aluminum or steel, forming a hollow tube through which wires can be pulled. For final connections to motors and motorized equipment, not more than a 4' - 0" length of flexible conduit may be used. For watertight installations, this conduit shall be of a watertight type, attached with watertight glands or fittings for final connections from outlet box to recessed lighting fixtures and in locations only where specifically permitted by the Specifications or Contract Drawings.

## 1.5 PROCEDURE FOR ELECTRICAL APPROVAL:

This Sub-Section sets forth General Electrical information, as well as required approvals for all electrical work required for the Project, including ancillary electrical work which may be included in the work of other trade subcontractors.

- A. ELECTRIC SERVICE: The electric service supply is subject to commercial and operating variation of the utility company. Proper provision shall be made to have all apparatus operate normally under these conditions.
- B. ACCEPTANCE: Acceptance and approval of the work will be contingent upon the inspection and test of the installation by the City regulatory agency.
- C. TESTS: The Contractor shall notify the Commissioner when the Contractor has completed the work and is ready to have it inspected and tested. Upon completion of the work tests shall be made as required by the Commissioner of all electrical materials, electrical and associated mechanical equipment, and of appliances installed hereunder. The Contractor shall furnish all labor and material for such tests. Should the tests show that any of the material, appliances or workmanship is not first class or not in compliance with the Contract, the Contractor on written notice shall remove and promptly replace them with other materials in conformity with the Contract.
- D. CERTIFICATE OF THE BUREAU OF ELECTRICAL CONTROL, OF THE DEPARTMENT OF BUILDINGS (B.E.C.): The Contractor must file prior to requesting a substantial completion inspection a Certificate of Inspection issued by B.E.C. On completion of the work the Contractor shall obtain certificates of inspection, approval, acceptance and compliance from all agencies and/or entities having jurisdiction over the work and shall deliver these certificates to the Commissioner in accordance with Section 01 77 00 CLOSEOUT PROCEDURES.
- E. RESPONSIBILITY FOR CARE AND PROTECTION OF EQUIPMENT:
  - 1. The Contractor furnishing any equipment shall be responsible for the equipment until it has been finally inspected, tested and accepted, in accordance with the requirements of the Contract.





- 2. After delivery and before and after installation, the Contractor shall protect all equipment against theft, injury or damage from all causes. The Contractor shall carefully store all equipment received for work, which is not immediately installed. If any equipment has been subject to possible injury by water, it shall be thoroughly dried out and put through a special dielectric test as directed by the Commissioner, at the expense of the Contractor or replaced by the Contractor without additional cost to the City.
- F. UNIFORMITY OF EQUIPMENT: Any two (2) or more pieces of equipment, apparatus or materials of the same kind, type or classification which are intended to be used for identical types of service, shall be made by the same manufacturer.

#### 1.6 SUBMITTALS:

- A. CONTRACTOR'S ELECTRICAL DRAWINGS AND SAMPLES FOR APPROVAL:
  - 1. The Contractor shall submit to the Commissioner for approval, in accordance with Section 01 33 00 SUBMITTAL PROCEDURES, complete dimensional drawings of all equipment, wiring diagrams, motor test data, details of control, installation layouts showing all details and locations and including all schedules, and descriptions and supplementary data to comprise complete working drawings and instructions for the performance of the work. A description of the operation of the equipment and controls shall be included. A letter, in triplicate, shall accompany each submittal.
  - 2. The Contractor shall submit in accordance with Section 01 33 00 SUBMITTAL PROCEDURES, duplicate samples of such materials and appliances as may be requested by the Commissioner for approval. These samples shall be properly tagged for identification and submitted for examination and test. After the samples are approved, one (1) sample will be returned to the Contractor and the other sample will be filed in the office of the Commissioner's representative for inspection use. After the Contract is completed, the second set of samples will be returned to the Contractor.
- B. TIMELINESS: All material shall be submitted in accordance with the submittal schedule in sufficient time for the progress of construction. Failure to promptly submit acceptable samples and dimensional drawings of equipment will not be accepted as grounds for an extension of time. The Commissioner may decline to consider submittals unless all related items are submitted at the same time.
- C. CONTRACTOR'S STATEMENT WITH SUBMITTALS: Contractor shall submit statement in accordance with Section 01 33 00, SUBMITTAL PROCEDURES.
- D. BULLETINS AND INSTRUCTIONS: The Contractor shall furnish and deliver to the Commissioner in accordance with Section 01 78 39, CONTRACT RECORD DOCUMENTS and Section 01 77 00, CLOSEOUT PROCEDURES, after acceptance of the work, four (4) complete sets of instructions, technical bulletins and any other printed matter (diagrams, prints, or drawings) required to provide complete information for the proper operation, maintenance and repair of the equipment and the ordering of spare parts.

PART II – PRODUCTS (Not Used)



## PART III - EXECUTION

## 3.1 ELECTRICAL INSTALLATION PROCEDURES:

This Sub-Section sets forth the General Installation Procedure that shall apply to all electrical work and electrical equipment appearing in the Contract.

(Refer to Sub-Section 1.4 DEFINITIONS for terms used in this section)

- A. INTENT OF CONTRACT DOCUMENTS: The Drawings and Specifications are to be interpreted as a means of conveying the scope and intent of the work without giving every minor electrical detail. It is intended, nevertheless, that the Contractor shall provide whatever labor and materials are found necessary, within the scope of the Contract, for the successful operation of the installation. Specific details of individual installations are to be finally decided upon when the Contractor submits Working or Shop Drawings for approval to DDC. Whenever there are two (2) or more methods to complete project work within the Contract scope, the Commissioner reserves the right to choose that method which, in the Commissioner's opinion, will afford the most satisfactory performance, lasting qualities, and accessibility for repairs, even though this selection is the most costly.
- B. SCHEMATIC PLANS APPROXIMATE LOCATIONS: Conduits and wiring are shown on the plans for diagrammatic purposes only. Therefore, conduit layouts may not necessarily give the actual physical route of the conduits. The Contractor who installs a conduit system will also be required, as part of the work, to furnish and install all hangers and pull-boxes, including any special pull-boxes found necessary to overcome interferences, and to facilitate the pulling of electrical cables. Similarly, the locations of equipment, appliances, outlets and other items shown on Contract Drawings are only approximate and are to be definitively established when equipment Shop Drawings are submitted and approved by DDC during construction.
- C. SLEEVES: required for conduits passing through walls or floors, shall be furnished and set by the Contractor installing the conduits. Sleeves in waterproofed floors shall be provided with flashing extending 12 inches in all directions from sleeve and secured to waterproofing. Flashing shall be turned down into space between pipe and sleeve and caulked watertight. Flashing shall be 20 oz. cold rolled copper. Sleeves shall be supplied with welded flanges similar to those supplied by the subcontractor for Plumbing Work and shall extend one (1) inch above finished floor.
- D. COORDINATION: The Contractor shall keep in close touch with the construction progress and obtain the necessary information for the accurate placement of its work in ample time before project construction operations obstruct its work. The Contractor is to consult all other Contract Drawings, as well as approved equipment Shop Drawings on file in the Resident Engineer's Field Office. This will aid in avoiding interferences, omissions and errors in the electrical installation.
- E. RESTORATION: If drilling or cutting is done on finished surfaces of equipment or the structure, any marring of the surface shall be repaired or replaced by the Contractor. The Contractor shall be held responsible for corrective restoration due to its cutting or drilling, and for any damage to the project or its contents caused by the Contractor or the Contractor's workers. If any piercing of waterproofing occurs because of the installation of the work, the Contractor shall restore the waterproofing, at its own expense, to the satisfaction of the Commissioner.
- F. ELECTRICAL WORK AT SITE: The Contractor furnishing equipment consisting of a number of related electrical devices or appliances, mounted in a single enclosure, or on a common base, shall furnish this unit complete with internal wiring, connections, terminal boxes with copper connectors and/or lugs and ample electrical leads, ready for connection and operation. The cost of any wiring, re-wiring or other work required to be done on this unit in the field, shall be borne by the Contractor, without additional cost to the City.
- G. COOPERATION AMONG SUBCONTRACTORS: Whenever an electrically operated unit or system involves the combined work of several subcontractors for its installation and successful operation, the



Contractor shall require each subcontractor to exercise the utmost diligence in cooperating with others to produce a complete, harmonious installation.

## REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.2

#### 3.2 ELECTRICAL CONDUIT SYSTEM INCLUDING BOXES (PULL, JUNCTION AND OUTLET):

This Sub-Section sets forth the requirements applying to the installation of electrical conduits, boxes or fittings. Rigid steel conduit shall be used throughout, unless otherwise directed by the Commissioner. Where the word 'conduit', without a modifier such as, rigid steel, EMT, etc., is specified to be used, it shall be interpreted to mean, rigid steel, heavy wall, threaded conduit.

(Refer to Sub-Section 1.4 DEFINITIONS for terms used in this section)

#### A. INSTALLATIONS AND APPLICATIONS:

- 1. Unless otherwise specified or indicated on the Contract Drawings, conduit runs shall be installed concealed in finished spaces.
- 2. CONDUIT SIZES: The sizes of conduit shall be as indicated on the Contract Drawings. Wherever conduit sizes are not indicated, the conduit shall meet the requirements of the New York City Electrical Code to accommodate the conductors to be installed therein.
- Conduits shall be rearned smooth after cutting. No running threads will be permitted. Universal type couplings shall be used where required. Conduit joints shall be screwed up to butt. Empty conduits after installation shall have all open ends temporarily plugged to prevent the entrance of water or other foreign matter.
- Conduits being installed in concrete or masonry shall be securely held in place during pouring and construction operations. A group of conduits terminating together shall be held in place by a template.
- 5. UNDERGROUND STEEL CONDUITS: Unless otherwise specified, all underground steel conduits in contact with earth shall be encased by the Contractor who installs them, in a covering of not less than two (2) inches of an approved concrete mixture. Concrete mix shall be one (1) part cement to four and one-half (4 1/2) parts of fine and coarse aggregate.
- 6. EXCAVATION RESTORATION PERMITS: When installing underground conduits, duct banks or manholes the Contractor shall perform the work of cutting pavement, excavation shoring, keeping trenches or holes pumped dry, backfilling, restoration of surfaces to original condition and removal of excess earth and rubbish from premises. During the work, the Contractor shall provide adequate crossovers, protective barriers, lamps, flags, etc., to safeguard traffic and the public. When the work is in a public highway or street, the Contractor shall secure and pay for all necessary permits and inspection fees and pay the cost of repaving.
- EXPOSED CONDUIT SUPPORTS: Exposed conduit shall be supported by Galvanized hangers with necessary inserts, beam clamps of approved design or attached to walls or ceilings by expansion bolts. Exposed conduits shall be supported or fastened at intervals not more than five (5) feet.
- Exposed conduit shall be installed parallel or at right angles to ceiling, walls and partitions. Where direction changes of exposed conduit cannot be made with neat bends, such as required around beams or columns, conduit type fitting shall be used.



9. The conduit shall be installed with an approved expansion joint:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- a. Wherever the conduit crosses a building expansion joint the Contractor will be held responsible for determining where the building expansion joints are located.
- b. Every 200 feet, when in straight runs of 200 feet or longer.
- 10. Conduit may only enter and leave a floating slab in the vertical direction, and then only in an approved manner. Horizontal entries into floating slabs are not permitted.
- 11. Conduit installed in pipe shafts shall be properly supported to carry the total weight of the raceway system complete with cable. In addition at least one (1) horizontal brace per 10 ft. section shall be provided to assure stability of the raceway system.
- 12. BUSHINGS AND LOCKNUTS: Approved bushings and locknuts shall be used wherever conduits enter outlet boxes, switch boxes, pull boxes, panel board cabinets, etc.
- 13. CONDUIT BENDS: shall be made without kinking conduit or appreciably reducing the internal diameter. All bends in conduit of two (2) inch in diameter or larger shall be made with an hydraulic or power pipe bender. The radius of the inner edge of any bend shall not be less than six (6) times the internal diameter of the conduit where rubber covered conductors are to be installed, and not less than 10 times the internal diameter of the conduit where rubber covered conductors are to be used. Long gradual sweeps will be required, rather than sharp bends, when changes of direction are necessary.

#### 14. EMPTY CONDUITS

▶】▶】●

- a. TESTS: All conduits and ducts required to be installed and left empty shall be tested for clear bore and correct installation by the Contractor using a ball mandrel and a brush and snake before the installation will be accepted. The ball shall be turned to approximately 85% of the internal diameter of the raceway to be tested. Two (2) short wire brushes shall be included in the mandrel assembly. Snaking of conduits, ducts, etc., shall be performed by the Contractor in the presence of the Resident Engineer. Any conduits or ducts which reject the mandrel shall be cleared at once with the Contractor bearing all costs, such as chopping concrete, to replace the defective conduit and restore the surface to its original condition.
- b. TAGS: Numbers or letters shall be assigned to the various conduit runs, and as they test clear they shall be identified by a fiber tag not less than 1-¼ inch width, attached by means of a nylon cord. All conduit terminations in panel, splice or pull boxes as well as those out of the floor or ceiling shall be tagged.
- c. TEST RECORDS: As the conduit runs clear, a record shall be kept under the heading of "Empty Conduit Tested, Left Clear, Tagged and Capped" showing conduit designation, diameter, location, date tested and by whom. When complete, this record shall be signed by the Resident Engineer and submitted in triplicate for approval. This record shall be entered on the Contract Record Drawings under Section 01 78 39, CONTRACT RECORD DOCUMENTS.
- d. CAPPING: All empty conduit and duct openings, after test, shall be capped or plugged by the Contractor as directed.
- e. DRAG LINES: A drag line shall be left in all empty conduit.
- B. BOXES:
  - The Contractor shall furnish and erect all pull boxes indicated on the plans or where required. Sides, top and bottom of pull boxes shall be Galvanized coated and shall be built of No. 12 USSG steel reinforced at corners by substantial angle irons and riveted or welded to plates. Bottom or side



of pull boxes shall be removable and held in place by corrosion resistant machine screws. Pull boxes in damp locations shall have threaded hubs and gaskets and be NEMA 4X. All pull boxes shall be suspended from ceiling or walls in the most substantial manner.

- 2. In centering outlets, the Contractor is cautioned to allow for overhead pipes, ducts and other obstructions, and for variations in arrangement and thickness of fireproofing, soundproofing and plastering. Precaution should be exercised regarding the location of window and door trims, paneling, etc. Mistakes resulting from failure to exercise precaution must be corrected by the Contractor at no additional cost to the City. Outlets in hung ceilings shall be supported from the black iron or structure.
- 3. The exact location of all outlets in finished rooms shall be as directed. When the interior finish has been applied, the Contractor shall make any necessary adjustment of its work to properly center the outlets. All outlet boxes for local switches near doors shall be located at the strike side of doors as finally hung, whether so indicated on the drawings or not.
- 4. Exposed wall outlet boxes shall be erected neatly and tight against the walls and securely anchored to same.
- 5. All wall outlets of each type shall be set accurately at the same level on each floor, except where otherwise specified or directed. Where special conditions occur, outlets shall be located as directed.
- 6. MOUNTING HEIGHTS: The following heights are standard heights and are subject to correction due to coordination with Contract Drawings. All such changes must be approved by the Resident Engineer. Heights given are from finished floor to center line of outlet or device on wall or partition, unless otherwise indicated.

a.	General Convenience Outlets	
	(mount vertical)	1'-6"
b.	Clock Outlets	8'-6"or 1'-6" below ceiling
c.	Wall Lighting Switches	4'-0"
d.	Motor Controllers	5'-0"
e.	Motor Push-button	4'-2"
f.	Telephone Outlets	As Directed
g.	Fire Alarm Bells	8'-6"or 1'-6" below ceiling
h.	Fire Alarm Stations	4'-0"
i.	Intercom Outlet	1'-6"

- j. Cooking and Refrigerator Unit As Directed
- 7. Outlet boxes shall be of approved design and construction; of form and dimensions suited and adapted to its specific location; the kind of fixture to be used and the number and arrangements of conduits, etc., connecting therewith. All ferrous outlet boxes shall meet the requirements for zinc coating as specified under Electrical Conduit Systems.
- 8. There shall be knockouts opened only for the insertion of conduit. Any outlet boxes with more openings than are necessary for conduit insertion shall be sealed by the Contractor without additional charge.
- All outlet boxes and junction boxes for exposed work shall be galvanized cast iron or cast aluminum with threaded openings. Outlet boxes for exposed inside work in damp locations shall be galvanized cast iron or cast aluminum with threaded hubs and neoprene gaskets.
- 10. Junction boxes shall not be less than 4 11/16" square and shall be equipped with zinc coated plates. Where plates are exposed they shall be finished to match the room decor.



- 11. FIXTURE SUPPORTS: Outlet boxes supporting lighting fixtures shall be equipped with fixture studs held by approved galvanized stove bolts or integral with the box. Cast iron or malleable boxes shall have four (4) tapped holes for mounting required cover or fixtures.
- 12. Outlet boxes exposed to the weather or indicated W.P. shall be cast iron or cast aluminum and the covers made watertight with neoprene gaskets. The boxes shall have external lugs for mounting. Drilling of the body of the fitting for mounting will not be permitted. The cover screws shall be appropriate in size, non-corrodible and not less than four (4) in number for each box opening.

## **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.3**

#### 3.3 ELECTRICAL WIRING DEVICES:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

▶】▶】◆

- A. WALL SWITCHES shall be of the best specification grade, quiet type, and shall have a rating of 20 Amperes at 277 volts, as manufactured by Bryant, Hubbell or approved equal. The mechanism shall be equipped with arc snuffers. They shall be of the tumbler type, single pole. Switches of the 3-way type shall have a similar rating.
- B. RECEPTACLES:
  - 1. CONVENIENCE OUTLETS: shall be of the best specification grade, duplex, two-pole, 3-wire, 20 Amperes at 125 volts. It shall have a grounding pole that shall be grounded to the conduit system. Receptacles shall be capable of both back and side wiring and shall have only one (1) grounding screw. Receptacles shall be Hubbell Cat. #5262 or approved equal.
  - 2. HEAVY DUTY RECEPTACLE OUTLETS: shall have the Ampere rating and the number of poles specified on the Contract Drawings and shall be Hubbell, Russell-Stoll, Bryant, AH & H or approved equal. Each outlet shall have a grounding pole, which shall be grounded to the conduit system.
  - 3. FLOOR RECEPTACLES: shall be Russell & Stoll #3040 or approved equal, to fit into floor box previously specified.
  - 4. NAMEPLATES: are required for all receptacles other than 120V.
- C. CLOCK HANGERS: Clock outlets for surface type clocks shall be equipped with a supporting hook and recessed faceplate to conceal the electrical cord.
- D. WATERTIGHT DEVICES: For installations exposed to weather or in damp locations, the devices shall be in a gasketed, cast iron enclosure.
- E. PLATES:
  - 1. Every convenience outlet and switch outlet shall be covered by means of a stainless steel No. 302 0.4" antimagnetic plate with an approved finish, unless provided otherwise in the detailed Specifications.
  - 2. Where two (2) or three (3) switches are grouped together, a single faceplate shall be used. Where more than three (3) switches are located at one (1) point, the faceplates may be made up in multiple units.

#### **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.4**

#### 3.4 ELECTRICAL CONDUCTORS AND TERMINATIONS:

A. CONDUCTORS FOR LIGHT AND POWER - All wire and cable shall be of annealed copper of 98% conductivity. Aluminum wire or cable will not be permitted. The insulation shall be flame retardant, moisture and heat resistant, thermoplastic, type THW or THWN rated for 600 volts at 75 degrees C. for

both wet and dry locations. Wires No. 8 or larger shall be stranded. Wires and cables shall also be subject to the requirements of the NYCEC. Cables for incoming service or wire in conduits contiguous with the earth or in concrete or other damp or wet locations shall be synthetic rubber insulated with neoprene jacket, heat and moisture resistant and shall be equal to UL Type USE and rated for 600 volts at 75 degrees C. for both wet and dry locations.

- B. FIXTURE WIRE: Lighting fixtures shall be wired with No. 14 gauge wire designated as AWM and rated at 105 degrees C.
- C. OTHER TYPES: Cables and wires for interior communication systems are described in applicable detailed Specifications.
- D. MINIMUM SIZE: Conductors smaller than No. 12 AWG shall not be used for light or power.
- E. COLOR CODE: Wires shall have a phase color code, and multiple conductor cables shall be color coded.
- F. CABLE DATA: The Contractor shall submit for approval the following information for each size and type of cable to be furnished.
  - 1. Manufacture of Cable Location of Plant.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- 2. Minimum insulation resistance at standard test temperature.
- 3. Days required for delivery to site of work after order to proceed with manufacture.
- G. ORIGINAL REELS: Cable and wire shall be delivered to the site of the work on original sealed factory reels.
- H. WIRE INSTALLATION:

- INSTALL WIRES AFTER PLASTERING Feeder and branch circuits wiring shall not be installed in conduit before the rough plastering work is completed. No conductors shall be pulled into floor conduits before floor is poured.
- 2. CONDUIT SECURED IN PLACE No conductor shall be pulled into any conduit run before all joints are made up tightly and the entire run rigidly secured in place.
- WIRE ENDS All wires shall be left with sufficiently long ends for proper connection and stowing.
- PULLING COMPOUNDS When required to ease the pulling-in of wires into conduit, only approved compounds as recommended by cable manufacturers shall be used.
- PRESSURE CONNECTORS for wires shall be of the cast copper or forged copper pressure plate type. Connectors shall be O.Z., Burndy, National Electric Products or approved equal.
- Splices and feeder taps in the gutters of panel boxes shall be made by means of pressure plate type connectors encased in composition covers as manufactured by O.Z., Burndy, National Electric Products or approved equal.
- 7. Splices in branch wiring for sound systems and fire systems, shall be first made mechanically secure, then soldered and taped.
- 8. In lieu of soldered splices (except for sound and Fire Systems, which must have soldered splices) the following alternates are acceptable for operating temperatures up to 105 degrees C., for fluorescent fixtures and for the splicing of branch circuit wiring up to No. 8 AWG wire:
  - a. Mechanical splices made with mechanical connectors as manufactured by the Minnesota Manufacturing Company "Scotchlock" or approved equal. Mechanical connectors requiring a special tool (pressure connectors, insulators and locking rings) by Buchanan or approved equal. The tool used for connector application shall be as approved by the connector manufacturer.





- b. For wire and cable No. 6 AWG and larger for branch circuit wiring the seamless tubular connector will only be accepted. Application of this connector shall be with a tool recommended by the connector manufacturer.
- 9. TAGS: All feeders and risers shall be tagged at both ends, and in all pull and junction boxes and gutter spaces through which they pass. Such tags shall be of fiber and have the feeder designation and size stamped thereon.
- 10. BRANCH CIRCUIT WIRING:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- a. The Contractor installing branch circuit wiring shall test the work for correct connections and leave all loop splices in the fixture outlet boxes properly spliced and taped. The Contractor shall provide wire ends long enough for convenient connection to device.
- b. NEUTRALS: No common neutrals shall be used except for lighting branch circuits. Each neutral wire shall be terminated separately on a neutral busbar in the panelboard. No common neutrals will be permitted for convenience receptacle branch circuits.

#### I. TERMINATIONS

- 1. LUGS: All lugs for all devices and all cable terminations shall be copper. AL/CU rated lugs will not be permitted. The only exception to this requirement is when the particular device is not manufactured with copper lugs by any manufacturer. Lugs for No. 6 AWG cable and larger shall be cast copper or forged copper pressure plate type. Lugs for 1/0 and larger shall be fastened with two (2) bolts.
- 2. All lugs shall be of the proper size to accept the cable connected to them. Any subcontractor furnishing a device containing lugs is to coordinate with the Contractor to insure that the device terminations are adequate for the wire or cable (whose size may be larger than expected due to voltage drop considerations) connected to the device.

# **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.5**

## 3.5 CIRCUIT PROTECTIVE DEVICES:

This Section sets forth the circuit protective devices such as circuit breakers and safety switches, used in connection with Motor Control Equipment, Distribution Centers, Panel boards and Service Entrance.

#### A. CIRCUIT BREAKERS:

- 1. CIRCUIT BREAKERS: shall be operable in any position and shall be of the quick-make, quick-break type on manual operation. The handle shall be trip free, preventing contacts from being held in closed position against abnormal overloads or short circuits. Positive visual indication of automatic tripped position of breaker shall be provided, in addition to the "On" and "Off" indication. All circuit breakers shall be of the bolted type.
- 2. TRIP RATING: Circuit breakers shall be provided with the required number of trip elements, calibrated at 40 degrees C., ambient temperature, in accordance with wire sizes or motor currents as shown on Contract Drawings or indicated in the Specifications.
- 3. POLE BARRIER: Multipole pole breakers shall be designed to break all poles simultaneously. They shall be provided with barriers between poles and arc suppressing devices.
- 4. ELEMENTS: Multipole circuit breakers shall have frames of not less than a 100 Ampere rating. Multipole circuit breakers for 480 volts AC operation shall have an NEMA interrupting rating of 18,000 Amperes, unless a higher rating is specified in the Specific Requirements or indicated on the Contract Drawings.







- 5. For circuit breakers with frame size up to and including 225 Amperes, the breakers may be provided with non-interchangeable trip elements. For frame ratings above 225 Amperes, the breakers shall be provided with interchangeable trip elements, which can be replaced readily.
- 6. Single pole circuit breakers for branch circuits shall have a frame size of no less than 100 Amperes, and shall be rated at 125 volt A.C. with a NEMA interrupting rating of 10,000 Amperes, unless a higher rating is specified in the Specifications or indicated on the Contract Drawings.
- 7. INVERSE TIME ACTION: The circuit breakers shall be dual element type, one (1) element with time limit characteristics, so that tripping will be prevented on momentary overloads, but will occur before dangerous values are reached and the other with instantaneous trip action. Inverse time delay action shall be effective between a minimum tripping point of 125% of rating of breaker and an instantaneous tripping point between 600% and 700% of rated current.
- 8. CONSTANCY OF CALIBRATION: The tripping elements shall insure constant calibration and be capable of withstanding excessive short circuit conditions without injury.
- 9. CONTACTS: shall be non-welding under operating conditions and of the silver to silver type.
- 10. TEMPERATURE RISE: Current carrying parts, except thermal elements, shall not rise in temperature in excess of 30 degrees C. while carrying rated current at rated frequency.
- 11. NUMBERING: Each circuit breaker shall be distinctly numbered when installed in a group with other breakers. The calibration of trip element shall be indicated on each breaker.
- B. SAFETY SWITCHES:

NEMA TYPE HD: When safety switches are permitted to be used for service entrance, motor disconnecting means or to control other types of electrical equipment, they shall be of the type HD of a rating not less than 30 Amperes. Enclosures shall be provided with means for locking. For ratings above 60 Amperes terminals shall have double studs.

## REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.6

#### 3.6 DISTRIBUTION CENTERS:

- This Section sets forth the construction and installation procedure for Switchboards, Panel boards and Cabinets.
- A. PANELBOARDS-GENERAL TYPE: The panel boards shall be of the automatic circuit breaker type with individual breakers for each circuit, removable without disturbing the other units. Circuit breakers shall be in accordance with the requirements outlined under "Circuit Protective Devices."
- B. NUMBER AND RATING OF CIRCUIT BREAKERS: The Contract Drawings show a layout of each panel, giving the number, frame, size and trip setting of circuit breakers and number of branch circuits and spare breakers. Each branch circuit shall be distinctly numbered.
- C. BUS-BAR CONSTRUCTION AND SUPPORT: Panel Boards shall be of the dead front type and shall have bus bars and branch circuits designed to suit the system and voltage. Current carrying parts, exclusive of circuit breakers shall be copper and based on a maximum density of 1,000 Amperes per square inch. Bus bars for the main switchboard shall be designed for the frame rating of the Service Breaker. Bus bars shall run up the center of the panel, unless otherwise indicated, and shall have connected thereto the various branch circuits. Unless otherwise specified, bus bars for each panel board shall be equipped with main lugs only and capacity as required on Contract Drawings. Where main protection is required, automatic circuit breakers shall be used. A neutral bus of at least the same capacity as a live bus bar shall be provided for the connection of all neutral conductors. Each terminal shall be identified. All current carrying parts, exclusive of circuit breakers, shall be of copper with a minimum number of joints. The bus bar structure shall be a self-supporting unit, firmly fastened to a ½



inch plastic board, extending the full length and width of assembly which shall serve to insulate the bus structure from the back of panel box. Other methods affording equally effective bus structure support and insulation will be given consideration. An insulating barrier shall separate neutral bus from other parts of panel.

- D. CIRCUIT BREAKER ASSEMBLY: The entire circuit breaker and bus bar assembly shall be mounted on an adjustable metal base or pan and secured to the back of panel box. The panel shall have edges flanged for rigidity.
- E. PANEL MOUNTING: The panel shall be centered in the panel box to line up with door openings and set level and plumb so that no live parts are exposed with the door open.
- F. PANEL CABINET:
  - 1. PANEL CABINET INSTALLATION: When installed surface mounted in panel closets they shall be mounted on Kindorf channel.
  - 2. Where cabinets cannot be set entirely flush due to shallow walls or partitions or where cabinet is extra deep, the protruding sides of cabinet shall be trimmed with a metal or hardwood return molding of approved design and fastened to cabinet so as to conceal the intersection between the wall and cabinet.
- G. NAMEPLATES: Nameplates where required, shall be made of engraved Lamicoid sheet, or approved equal. Letters and numbers shall be engraved white on a black background (except for Firehouse projects which shall have white letters on a red background). The Contractor shall submit an engraved sample for approval as to design and style of lettering before proceeding with the manufacture of the nameplate. Nameplates shall be of suitable size and shall also be provided at the top of the switchboard or section thereof and on the trim at the top of all lighting and power panels. Similar nameplates shall also be provided for each distribution circuit breaker giving the breaker number, the number of the feeder, and the name of the equipment fed.
- H. SHOP DRAWINGS: showing all details of boxes, panels, etc., shall be submitted for approval.
- I. DIRECTORIES: A directory shall be fastened with brass screws and consist of a noncorrosive metal frame with dimensions not less than five (5) inches x eight (8) inches and a transparent window of Plasticile, Plexiglass, Lucite, Polycarbonate or approved equal that is not less than 1/16 inch thick over cardboard or heavy paper. The directory shall be typewritten and show the number of each circuit, the name of circuit and lighting or equipment supplied. The size of riser feeder shall be as indicated on directory. The dimensions of directory shall be submitted for approval for each size of panel.
- J. CONSTRUCTION
  - 1. FINISH: Panel boxes, doors and trim for installation in dry locations, shall be zinc coated after fabrication by the hot-dip galvanizing or electroplate process on inside and outside surfaces. In damp locations, panel boards shall be enclosed and gasketed NEMA 3R type. Panel boards located outdoors or exposed to the weather shall be NEMA 3X type.
  - 2. PAINTING: Panel boxes, doors and trim shall receive a coat of approved priming paint and a second coat of approved paint in the field after installation. Paint shall be applied to the inside and outside of boxes and on both sides of trim. Panel trims and doors shall receive a third or finishing coat on the outside after installation. Approval as to texture and color must be obtained before the final coat is applied.

## **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.7**

#### 3.7 MOTORS:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

This Section sets forth the general design, construction and performance requirements, which shall apply to all motors furnished in the Contract.

- A. MOTOR DESIGN: All motors shall be designed to comply with the New York State Energy Conservation Construction Code and the New York City Energy Conservation Code. In the event of any conflict or inconsistency between such codes, the New York City Energy Conservation Code shall prevail. Motors shall have standard NEMA frames and shall have nameplate ratings adequate to meet the specified conditions of operation. Motor performance under variable conditions of voltage and frequency shall be within the limits set in NEMA standards, unless modified in the Specifications. Motors shall be expressly designed for the hazard duty load, voltage and frequency as specified in the Contract. All motor windings shall be copper. All motors intended to operate on a 208 volt system shall be designed and rated for 200 volts.
- B. STANDARDS OF COMPARISON: In the absence of specific motor specifications, in general, the best standard products of the leading motor manufacturers shall be considered as a standard for comparison. The requirements of the NEMA standards for motors and generators shall be deemed to contain the minimum requirements of performance and design.
- C. OBJECTIONABLE NOISES: Objectionable noises will not be tolerated and exceptionally quiet motors may be required for certain specified locations. Noise control tests as per the New York City Construction Codes may be performed as directed by the Commissioner. Such motors shall bear a nameplate lettered "Quiet Motor." Springs and slip rings shall be of approved non-ferrous material.
- D. BEARINGS:
  - Bearings, unless specified otherwise, shall be of the ball or roller type. Motors one (1) horsepower and larger that are equipped with ball roller bearings shall also have lubrication of the pressure-relief greasing type. The Contractor furnishing four (4) or more such motors shall also furnish, as part of the Contract, a pressure grease gun of rugged design, of approximately 10 ounce capacity, complete with necessary adapters. The Contractor shall also provide 10 pounds of approved gun grease.
  - 2. For any particular unit where sleeve bearings are deemed desirable, permission for their use may be granted by the Commissioner. Motors one (1) horsepower and larger that are equipped with sleeve type bearings shall in addition to having protected accessible fittings for oiling be provided with visible means for determining normal oil level. Lubrication shall be positive, automatic and continuous.
- E. MOTOR TERMINALS AND BOXES: Each motor shall be furnished with flexible leads of sufficient length to extend for a distance of not less than three (3) inches beyond the face of the conduit terminal box. This box shall be furnished of ample size to make and house motor connections. These requirements shall be met irrespective of any other standards or practices. Size of cable terminals and conduit terminal box holes shall be subject to approval. For motors five (5) horsepower. or larger, each terminal shall come with two (2) cast or forged copper pressure type connectors with bolts, nuts and washers. For motors of smaller ratings, connectors of other acceptable types may be furnished. For installations exposed to the weather or moist locations, terminal boxes shall be of cast iron with threaded hubs and gasketed covers. Cover screws shall be of non-corrosive material.
- F. MOTOR TEMPERATURE RISES: The motor nameplate temperature rises for the various types of motor enclosures shall be as listed below:

1.	Open Frame	40 degrees C.
2.	Totally enclosed and enclosed fan cooled	55 degrees C.

3. Explosion proof and submersible Partially enclosed and drip proof

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

55 degrees C. 40 degrees C.

The temperature of the various parts of a motor shall meet the requirements of NEMA standards for the size and type of the motors. Tests for heating shall be made by loading the motor to its rated horsepower and keeping it so loaded for the rated time interval or until the temperature becomes constant.

- SPECIAL CODE INSTALLATIONS: Electrical installations covered by special publications of NBFU and G. by special City rulings and regulations shall comply in design and safety features with such applicable codes, regulations and rulings, and shall be furnished and installed complete with all accessories and safety devices as therein specified.
- MOTORS ON LIGHTING PANELS: The largest A.C. motor permitted on branch circuits of lighting panels H. shall not exceed 1/4 horsepower.
- Ι. MOTORS RATED: 1/2 horsepower and larger shall be polyphase.

## **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.8**

#### MOTOR CONTROL EQUIPMENT: 3.8

₽】₽】●

4.

This Section sets forth the requirements for motor controllers and associated devices. Such requirements are applicable to all motor control equipment furnished or installed.

- MANUFACTURER: All control equipment furnished under the Contract shall be the product of a single Α. manufacturer. Exceptions to this rule may be granted in the case of controllers for fractional horsepower motors driving special equipment, the various units of which have been engineered to obtain specific performance.
- Β. CONTROL ITEMS REQUIRED: The Contractor furnishing motors shall also furnish therewith complete disconnecting, starting and control equipment as required by the detailed Specifications, the various code authorities and for the successful operation of the driven equipment. These items include circuit breaker, magnetic starter with overload protection and low voltage release or protection, push button stations, pilot lights and alarms, float, pressure, temperature and limit switches, load transfer switches, devices for manual operation and speed controllers, etc. The Contractor shall furnish as many of these items as are required for the successful operation of the driven unit.
  - Where a motor is to be located out of sight of the controller, the Contractor shall furnish an 1. approved disconnecting means to be mounted near motor.

#### C. **TYPES OF STARTERS:**

- SQUIRREL CAGE: A.C. motors of the squirrel cage type, rated from one (1) to 30 horsepower, 1. shall have magnetic across the line starters; motors rated above 30 horsepower shall be furnished with reduced voltage (autotransformer type) starter or part winding start with time delay to reduce inrush current. Size of starters shall be based on 200V operation.
- 2. SLIP RING: A.C. Motors of the slip-ring type shall be furnished with primary across the line starters interlocked with secondary starting and regulating equipment. The interlocking feature shall prevent starting of the motor when the secondary controller is off the initial starting point.
- MAGNETIC: For fractional horsepower motors, magnetic type starters are not required unless the 3. particular method of controlling the driven equipment makes them necessary. Where individual single phase fractional horsepower motors or the sum of fractional horsepower motors controlled by an automatic device are 1/2 horsepower or more, magnetic starters and circuit breakers shall be used. Single phase A.C. motors smaller than 1/2 horsepower or three-phase A.C. motors smaller than one (1) horsepower where manual control is specified may be furnished with starters of toggle



switch or push button type with inbuilt thermal protection. No additional disconnecting means is required to be furnished with this type of starter. This type of starter may also be used in series with automatic control devices such as thermostats, float and pressure switches, provided the individual motor or the sum of fractional horsepower motors is less than ½ horsepower. Means for manual operation shall be provided.

- D. DISCONNECTING BREAKER: All motor starters, unless otherwise specified, shall be provided with a disconnecting means in the form of a circuit breaker of the type specified under Article 3.5 CIRCUIT PROTECTIVE DEVICES. This disconnecting means shall be contained in the same housing with the starter and shall be operable from outside. Means shall be provided for locking the handle of the circuit breaker in the "OFF" position if it is desired to take the equipment out of service and prevent unauthorized starting.
- E. CONTROL CABINET: DRY LOCATIONS All starters shall be furnished with general purpose, NEMA Type 1, sheet metal enclosures with hinged covers and baked enamel finish.
- F. CONTROL CABINET WATERTIGHT: In wet locations, cast iron watertight enclosures with threaded hubs, galvanized and gasketed hinged covers shall be provided.
- G. 1. PANELS: Motor control devices and appliances shall be mounted on approved insulating slabs with all wiring and connections made on the back of the slabs.
  - 2. WIRING AND TERMINALS: Wiring connections for currents of 100 Amperes or less may be made with copper wire or cable with special flameproof insulating coverings. Such wires shall be installed in a neat workmanlike manner, flat against the slab, and held in place by clips. Connections shall be made with pressure connectors for No. 8 AWG and larger wires, and with grommets for small stranded wires. Except for incoming and outgoing main leads, all connections shall terminate on approved connector blocks, which may be installed on the face of the slab. For small, across the line starters, the above requirements may be modified if satisfactory connections are provided.
  - 3. COPPER BUS: For currents exceeding 100 Amperes, copper bus shall be used in place of wires. The bus shall be constructed of copper rods, tubing or flat strap, bent and shaped properly and securely attached to the slab in a neat and workmanlike manner. The cross section of copper shall provide sufficient areas to keep current density at not more than 1,000 Amperes per square inch.
- H. COOPERATION: The Contractor's subcontractor(s) who furnish electrically operated equipment shall give to the Contractor and the Contractor's electrical subcontractor full information relative to sizes and locations of apparatus furnished by them which require electrical connections.
- I. SPARE PARTS:
  - 1. FURNISH: The Contractor shall furnish the following spare parts pertaining to equipment furnished by each subcontractor.

One (1) set of contact fingers and springs and thermal elements for each three (3) (or fraction) of each size of magnetic contactor starter.

One (1) holding coil for each three (3) (or fraction) of each size of magnetic contactor starter.

2. WRAPPER MARKING: All parts shall be delivered to the Resident Engineer neatly wrapped and boxed and plainly tagged and marked for identification and reordering.

#### END OF SECTION 01 35 06

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

## Division 01 - DDC STANDARD GENERAL CONDITIONS SINGLE CONTRACT PROJECTS Issue Date - June 01, 2013

No Text

## GENERAL ELECTRICAL REQUIREMENTS 01 35 06 - 16



## SECTION 01 35 26 SAFETY REQUIREMENTS PROCEDURES

#### PART I - GENERAL

#### 1.1 RELATED DOCUMENTS:

- A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].
- B. The Contractor shall comply with the requirements of "The City of New York Department of Design and Construction Safety Requirements". This document is included in the Information for Bidders.

#### 1.2 SUMMARY:

- A. This Section includes administrative and general procedural requirements for Safety and Health Requirements, including:
  - 1. Definitions
  - 2. Required Safety Meeting
  - 3. Compliance with Regulations
  - 4. Submittals
  - 5. Personnel Protective Equipment
  - 6. Hazardous Materials
  - 7. Emergency Suspension of Work
  - 8. Protection of Personnel
  - 9. Environmental Protection

#### 1.3 **DEFINITIONS:**

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.

#### 1.4 REQUIRED SAFETY MEETINGS:

- A. Prior to commencing construction, the Resident Engineer will schedule and hold a preconstruction kick-off meeting either at DDC's main office or at the Project site with representatives of the Contractor, including the principal on-site project representative and one or more safety representatives, Commissioner's designated representatives and other concerned parties for the purpose of reviewing the Contract Safety requirements. The Contractor's safety requirements shall be reviewed, and implementation of safety provisions pertinent to the Work shall be discussed.
- B. The Contractor is responsible for conducting weekly documented jobsite safety meetings, given to all jobsite personnel including all subcontractors on the project, with the purpose of discussing safety topics and job specific requirements at the DDC worksite.



#### 1.5 COMPLIANCE WITH REGULATIONS:

- A. The Work, including contact with or handling of hazardous materials, disturbance or dismantling of structures containing hazardous materials, and disposal of hazardous materials, shall comply with the applicable requirement for CFR Parts 1910 and 1926, and 40 CFR, Parts 61, 261, 761 and 763.
- B. Work involving disturbance or dismantling of asbestos or asbestos containing materials, demolition of structures containing asbestos and removal of asbestos, shall comply with 40 CFR Part 61, Subparts A and M, and 40 CFR Part 763, as applicable.
- C. Work shall additionally comply with all applicable federal, state and local safety and health regulations.
- D. In case of a conflict between applicable regulations, the more stringent requirements shall apply.
- E. All workers working on the DDC project site are required by NYC Local Law 41 to complete the OSHA 10 -hour training course.

#### 1.6 SUBMITTALS:

- A. The Contractor shall submit, to the Resident Engineer, copies of the Safety Program, Site Safety Plan and other required documentation in accordance with the "New York City Department of Design and Construction Safety Requirements."
- B. Permits: If hazardous materials are disposed of off-site submit copies of shipping manifests and permits from applicable federal, state or local authorities and disposal facilities, and submit certificates that the material has been disposed of in accordance with regulations to the Resident Engineer.
- C. Accident Reporting: Submit a copy of each accident report to the Resident Engineer in accordance with the "New York City Department of Design and Construction Safety Requirements."
- D. All Asbestos and Lead project regulatory notifications are to be submitted to DDC's Bureau of Environmental and Geotechnical Services (BEGS) through the Resident Engineer.
- E. Request for Subcontractor Approval: Any subcontractor performing environmental work shall submit required documentation for approval to perform such work as required by DDC's BEGS.

## **PART II - PRODUCTS**

## 2.1 PERSONNEL PROTECTIVE EQUIPMENT:

Special facilities, devices, equipment and similar items used by the Contractor in execution of the Work shall comply with 29 CFR Part 1910, subpart I, Part 1926, subpart E and other applicable regulations.

#### 2.2 HAZARDOUS MATERIALS:

- A. The Contractor shall bring to the attention of the Commissioner, any material encountered during execution of the Work that the Contractor suspects to be hazardous.
- B. The Commissioner shall determine whether the Contractor shall perform tests to determine if the material is hazardous. A change to the Contract price may be provided, subject to the applicable provisions of the Contract.
- C. If the material is found to be hazardous, the Commissioner may direct the Contractor to remediate the hazard and a change to the Contract price may be provided, subject to the applicable provisions of the Contract.





#### 3.1 EMERGENCY SUSPENSION OF WORK:

- A. When the Contractor is notified by the Commissioner of noncompliance with the safety provisions of the Contract, the Contractor shall immediately, unless otherwise instructed, correct the unsafe condition, at no additional cost to the City.
- B. If the Contractor fails to comply promptly, all or part of the Work may be stopped by notice from the Commissioner.
- C. When, in the opinion of the Commissioner, the Contractor has taken satisfactory corrective action, the Commissioner shall provide written notice to the Contractor that work may resume.
- D. The Contractor shall not be allowed any extension of time or compensation for damages in connection with a work stoppage for an unsafe condition.

#### 3.2 PROTECTION OF PERSONNEL:

- A. The Contractor shall take all necessary precautions to prevent injury to the public, occupants, or damage to property of others. The public and occupants includes all persons not employed by the Contractor or a subcontractor.
- B. Whenever practical, the work area shall be fenced, barricaded or otherwise blocked off from the Public or occupants to prevent unauthorized entry into the work area, in compliance with the requirements of Section 01 50 00, TEMPORARY FACILITIES, SERVICES AND CONTROLS, and including, without limitation, the following:
  - 1. Provide traffic barricades and traffic control signage where construction activities occur in vehicular areas.
  - 2. Corridors, aisles, stairways, doors and exit ways shall not be obstructed or used in a manner to encroach upon routes of ingress or egress utilized by the public or occupants, or to present an unsafe condition to the public or occupants.
  - 3. Store, position and use equipment, tools, materials, scraps and trash in a manner that does not present a hazard to the public or occupant by accidental shifting, ignition or other hazardous activity.
  - 4. Store and transport refuse and debris in a manner to prevent unsafe and unhealthy conditions for the public and occupants. Cover refuse containers, and remove refuse on a frequent regular basis acceptable to the Resident Engineer. Use tarpaulins or other means to prevent loose transported materials from dropping from trucks or other vehicles.

#### 3.3 ENVIRONMENTAL PROTECTION:

- A. Dispose of solid, liquid and gaseous contaminants in accordance with local codes, laws, ordinances and regulations.
- B. Comply with applicable federal, state and local noise control laws, ordinances and regulations, including but not limited to 29 CFR 1910.95, 29 CFR 1926.52 and NYC Administrative Code Chapter 28 of Title 15.

END OF SECTION 01 35 26



No Text

## SAFETY REQUIREMENTS PROCEDURES 01 35 26 - 4





## SECTION 01 35 91 HISTORIC TREATMENT PROCEDURES

# REFER TO THE ADDENDUM FOR APPLICABILITY OF THIS SECTION 01 35 91

#### PART I - GENERAL

## 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

#### 1.2 SUMMARY:

- A. This Section includes administrative and procedural requirements for the treatment of Landmark Structures and Landmark Quality Structures, as identified in the Addendum. Specific requirements are indicated in other sections of the Specifications.
- B. This Section includes, without limitation, the following:
  - 1. Storage and protection of existing historic materials.
  - 2. Temporary protection of historic materials during construction.
  - 3. General Protection
  - 4. Protection during use of heat-generating equipment.
  - 5. Photographic Documentation
  - 6. NYC Landmarks Preservation Commission Final Approval signoffs.

# 1.3 RELATED SECTIONS: include without limitation the following:

- A. Section 01 10 00 SUMMARY
- B. Section 01 32 33 PHOTOGRAPHIC DOCUMENTATION
- C. Section 01 33 00 SUBMITTAL PROCEDURES
- D. Section 01 77 00 CLOSEOUT PROCEDURES
- E. Section 01 78 39 CONTRACT RECORD DOCUMENTS

#### 1.4 DEFINITIONS:

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.
- C. Landmark Structure or Site: Any building or site which has been designated as a landmark, or any building or site within a landmark district, as designated by the New York City Landmarks Preservation Commission or the New York State Historic Preservation Office.



- D. Landmark Quality Structure: Any building which has been determined by the City to be of landmark quality and/or historical significance
- E. Preservation: To apply measures necessary to sustain the existing form, integrity, and materials of a historic property. Work may include preliminary measures to protect and stabilize the property.
- F. Rehabilitation: To make possible a compatible use for a property through repair, alterations, and additions while preserving those portions or features that convey its historical, cultural, or architectural values.
- G. Restoration: To accurately depict the form, features, and character of a property as it appeared at a particular period of time by means of the removal of features from other periods in its history and the reconstruction of missing features from the restoration period.
- H. Reconstruction: To reproduce in the exact form and detail a building, structure, or artifact as it appeared at a specific period in time.
- I. Stabilize: To apply measures designed to reestablish a weather-resistant enclosure and the structural reinforcement of an item or portion of the building while maintaining the essential form as it exists at present.
- J. Protect and Maintain: To remove deteriorating corrosion, reapply protective coatings, and install protective measures such as temporary guards; to provide the least degree of intervention.
- K. Repair: To stabilize, consolidate, or conserve; to retain existing materials and features while employing as little new material as possible. Repair includes patching, piecing-in, splicing, consolidating, or otherwise reinforcing or upgrading materials. Within restoration, repair also includes limited replacement in kind, rehabilitation, and reconstruction, with compatible substitute materials for deteriorated or missing parts of features when there are surviving prototypes.
- L. Replace: To duplicate and replace entire features with new material in kind. Replacement includes the following conditions:
  - 1. Duplication: Includes replacing elements damaged beyond repair or missing. Original material is indicated as the pattern for creating new duplicated elements.
  - Replacement with New Materials: Includes replacement with new material when original material is not available as patterns for creating new duplicated elements.
  - Replacement with Substitute Materials: Includes replacement with compatible substitute materials. Substitute materials are not allowed, unless otherwise indicated.
- M. Remove: To detach items from existing construction and legally dispose of them off-site, unless indicated to be removed and salvaged or removed and reinstalled.
- N. Remove and Salvage: To detach items from existing construction and deliver them to the City ready for reuse.
- O. Remove and Reinstall: To detach items from existing construction, repair and clean them for reuse, and reinstall them where indicated.
- P. Existing to Remain or Retain: Existing items of construction that are not to be removed and that are not otherwise indicated to be removed and salvaged, or removed and reinstalled.



Q. Material in Kind: Material that matches existing materials, as much as possible, in species, cut, color, grain, and finish.

#### 1.5 SUBMITTALS:

- A. Historic Treatment Program: Submit a written plan for each phase or process, including protection of surrounding materials during operations. Describe in detail materials, methods, and equipment to be used for each phase of work.
- B. Alternative Methods and Materials: If alternative methods and materials to those indicated are proposed for any phase of work, submit for Commissioner's approval a written description including evidence of successful use on other comparable projects, and program of testing to demonstrate effectiveness for use on this Project.
- C. Qualification Data: For historic treatment specialists as specified and required by individual sections of the project specifications.
- Photographs for Designated Landmark Structures: Submit photographs in accordance with Section 01 32
   33, PHOTOGRAPHIC DOCUMENTATION and as described in this section.
- E. Record Documents: Include modifications to manufacturer's written instructions and procedures, as documented in the historic treatment preconstruction conference and as the Work progresses.

#### 1.6 QUALITY ASSURANCE:

- A. Special Experience Requirements: Special Experience Requirements may apply to the firm that will provide Historic Treatment Services. If applicable, such Special Experience Requirements are set forth in the Bid Booklet and the Addendum.
- B. Historic Treatment Preconstruction Conference: The Resident Engineer will schedule and hold a preconstruction meeting at the site in accordance with Section 01 31 00, PROJECT MANAGEMENT AND COORDINATION.
  - 1. Review manufacturer's written instructions for precautions and effects of products and procedures on building materials, components, and vegetation.
    - a. Record procedures established as a result of the review and distribute to affected parties.

# 1.7 STORAGE AND PROTECTION OF HISTORIC MATERIALS:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- A. Removed and Salvaged Historic Materials: As specified and required by individual sections of the project specifications.
- B. Removed and Reinstalled Historic Materials: As specified and required by individual sections of the project specifications.
- C. Existing Historic Materials to Remain: Protect construction indicated to remain against damage and soiling during historic treatment. When permitted by the Commissioner, items may be removed to a suitable, protected storage location during historic treatment and reinstalled in their original locations after historic treatment operations are complete.
- D. Storage and Protection: When removed from their existing location, store historic materials, at a location acceptable to the Commissioner, within a weather tight enclosure where they are protected from wetting by rain, snow, or ground water, and temperature variations. Secure stored materials to protect from theft.
  - 1. Identify removed items with an inconspicuous mark indicating their original location.





#### PART II - PRODUCTS (Not Used)

#### PART III - EXECUTION

# 3.1 PROTECTION, GENERAL:

- A. Comply with manufacturer's written instructions for precautions and effects of products and procedures on adjacent building materials, components, and vegetation.
- B. Ensure that supervisory personnel are present when work begins and during its progress.
- C. Temporary Protection of Historic Materials during Construction:
  - 1. Protect existing materials during installation of temporary protections and construction. Do not deface or remove existing materials.
  - 2. Attachments of temporary protection to existing construction shall be approved by the Commissioner prior to installation.
- D. Protect landscape work adjacent to or within work areas as follows:
  - 1. Provide barriers to protect tree trunks.
  - 2. Bind spreading shrubs.
  - 3. Use coverings that allow plants to breathe and remove coverings at the end of each day. Do not cover plant material with a waterproof membrane for more than 8 hours at a time.
  - 4. Set scaffolding and ladder legs away from plants.
- E. Existing Drains: Prior to the start of work or any cleaning operations, test drains and other water removal systems to ensure that drains and systems are functioning properly. Notify Commissioner immediately of drains or systems that are stopped or blocked. Do not begin Work of this Section until the drains are in working order.
  - 1. Provide a method to prevent solids, including stone or mortar residue, from entering the drains or drain lines. Clean out drains and drain lines that become blocked or filled by sand or any other solids because of work performed under this Contract.
  - 2. Protect storm drains from pollutants. Block drains or filter out sediments, allowing only clean water to pass.

# 3.2 PROTECTION DURING USE OF HEAT-GENERATING EQUIPMENT:

- A. No roofing work requiring the use of an open flame shall be permitted on any Landmark Structure or any Landmark Quality Structure, whose roof or wall structure is made of wood or primarily of wood.
- B. Comply with the following procedures while performing work with heat-generating equipment, including welding, cutting, soldering, brazing, paint removal with heat, and other operations where open flames or implements utilizing heat are used:
  - 1. Obtain Commissioner's approval for operations involving use of open-flame or welding equipment. Notification shall be given for each occurrence and location of work with heat-generating equipment.
  - 2. As far as practical, use heat-generating equipment in shop areas or outside the building.
  - 3. Before work with heat-generating equipment commences, furnish personnel to serve as a fire watch (or watches) for location(s) where work is to be performed.







- 4. Do not perform work with heat-generating equipment in or near rooms or in areas where flammable liquids or explosive vapors are present or thought to be present. Use a combustible gas indicator test to ensure that the area is safe.
- 5. Remove and keep the area free of combustibles, including, rubbish, paper, waste, etc., within area of operations.
- 6. If combustible material cannot be removed, provide fireproof blankets to cover such materials.
- 7. Where possible, furnish and use baffles of metal or gypsum board to prevent the spraying of sparks or hot slag into surrounding combustible material.
- 8. Prevent the extension of sparks and particles of hot metal through open windows, doors, holes, and cracks in floors, walls, ceilings, roofs, and other openings.
- 9. Inspect each location of the day's work not sooner than 30 minutes after completion of operations to detect hidden or smoldering fires and to ensure that proper housekeeping is maintained.
- C. Where sprinkler protection exists and is functional, maintain it without interruption while operations are being performed. If operations are performed close to automatic sprinkler heads, shield the individual heads temporarily with guards.

#### 3.3 PHOTOGRAPHIC DOCUMENTATION:

Photographs for Designated Landmark Structures: Show existing conditions prior to any historic treatments, including one overall photograph and two close-up photographs of all areas of work affected. Show one overall photograph and two close-up photographs of all areas of work after the successful execution of all historical treatments.

# 3.4 NEW YORK CITY LANDMARKS PRESERVATION COMMISSION FINAL APPROVALS SIGNOFF:

For all projects involving a Landmark Structure or Site, the Contractor, at the completion of the work, shall submit to the Commissioner, in accordance with Section 01 78 39, CONTRACT RECORD DOCUMENTS, all documentation concerning the successful execution of all historic treatments. This shall include, but not be limited to, copies of all before and after photographs of historic treatments, one copy of the Contractor's as-built drawings, copies of testing and analysis results, including cleaning, mortar analysis, pointing mortars and all other information pertaining to work performed under the New York City Landmarks Preservation Commission jurisdiction.

END OF SECTION 01 35 91



No Text

# HISTORIC TREATMENT PROCEDURES 01 35 91 - 6

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION Division 01 – DDC STANDARD GENERAL CONDITIONS SINGLE CONTRACT PROJECTS Issue Date - June 01, 2013

# SECTION 01 40 00 QUALITY REQUIREMENTS

#### PARTI- GENERAL

#### 1.1 RELATED DOCUMENTS:

A: The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

#### 1.2 SUMMARY:

- A. This Section includes the following:
  - a. Definitions
  - b. Conflicting Requirements
  - c. Quality Assurance
  - d. Quality Control
  - e. Approval of Materials
  - f. Special Inspections (Controlled Inspection)
  - g. Inspections by Other City Agencies
  - h. Certificates of Approval
  - i. Acceptance Tests
  - j. Repair and Protection
- B. This Section includes administrative and procedural requirements for quality control to assure compliance with quality requirements specified in the Contract Documents.
- C. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
- D. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and control procedures that facilitate compliance with the Contract Document requirements.
- E. Provisions of this Section do not limit requirements for the Contractor to provide quality-assurance and control services required by the Commissioner or authorities having jurisdiction.
- F. Specific test and inspection requirements are specified in the individual sections of the Specifications.
- G. LEED: Refer to the Addendum to identify whether this project is designed to comply with a Certification Level according to the U.S. Green Building Council's Leadership in Energy & Environmental Design (LEED) Rating System, as specified in Section 01 81 13, "SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS."
- H. COMMISSIONING: Refer to the Addendum to identify whether this project will be Commissioned by an independent third party under separate contract with the City of New York. Commissioning shall be in accordance with ASHRAE and USGBC LEED-NC procedures, as described in Section 01 91 13, GENERAL COMMISSIONING REQUIREMENTS. The Contractor shall cooperate with the commissioning agent and provide whatever assistance is required.

QUALITY REQUIREMENTS 01 40 00 - 1



# **1.3 RELATED SECTIONS:** Include without limitation the following:

- A. Section 01 10 00 SUMMARY
- B. Section 01 31 00 PROJECT MANAGEMENT AND COORDINATION
- C. Section 01 32 00 CONSTRUCTION PROGRESS DOCUMENTATION
- D. Section 01 33 00 SUBMITTAL PROCEDURES
- E. Section 01 77 00 CLOSEOUT PROCEDURES
- F. Section 01 78 39 CONTRACT RECORD DOCUMENTS

#### 1.4 **DEFINITIONS**:

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.
- C. Commissioning: A Total Quality Assurance process that includes checking the design and installation of equipment, as well as performing functional testing of the same to confirm that the installed equipment is operating and in conformance with the Contract Documents and the City's requirements.

#### 1.5 CONFLICTING REQUIREMENTS:

- A. General: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, the Contractor shall comply with the most stringent requirement as determined by the Commissioner. The Contractor shall refer any uncertainties and/or conflicting requirements to the Commissioner for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. The Contractor shall refer any uncertainties to the Commissioner for a decision before proceeding.

#### 1.6 QUALITY ASSURANCE:

- A. General: Qualifications paragraphs in this Sub-Section establish the minimum qualification levels required. Individual Specification Sections specify additional requirements.
- B. Installer Qualifications: Special Experience Requirements may apply to the firm that will install, erect or assemble specified work required for the Project. If applicable, such Special Experience Requirements are set forth in the Bid Booklet and the Addendum.
- C. Manufacturer Qualifications: Special Experience Requirements may apply to the firm that will manufacture equipment, products or systems specified for the Project. If applicable, such Special Experience Requirements are set forth in the Bid Booklet and the Addendum.



- D. Fabricator Qualifications: Special Experience Requirements may apply to the firm that will fabricate material, products or systems specified for the Project. If applicable, such Special Experience Requirements are set forth in the Bid Booklet and the Addendum
- E. Professional Engineer Qualifications: A professional engineer who is licensed to practice in the State of New York and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or products that are similar to those indicated for this Project in material, design, and extent.
- F. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- G. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:
  - 1. Build mockups in location and of size indicated or, if not indicated, as directed by the Resident Engineer.
  - 2. Notify Resident Engineer seven (7) days in advance of dates and times when mockups will be constructed.
  - 3. Demonstrate the proposed range of aesthetic effects and workmanship.
  - 4. Obtain Design Consultant's approval of mockups before starting work, fabrication, or construction.
  - 5. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
  - 6. Demolish and remove mockups when directed, unless otherwise directed or indicated.

#### 1.7 QUALITY CONTROL:

- A. City's Responsibilities: Where quality-control services are indicated as the City's responsibility in the Specifications, the City will engage a qualified testing agency to perform these services.
  - COST OF TESTS BORNE BY THE CITY: Where the City directs tests to be performed to determine compliance with the Specifications regarding materials or equipment, and where such compliance is ascertained as a result thereof, the City will bear the cost of such tests.
  - The City will furnish the Contractor with names, addresses, and telephone numbers of testing entities engaged and a description of the types of testing and inspecting they are engaged to perform.
  - 3. Costs for retesting and re-inspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to the Contractor.
- B. Contractor's Responsibility: Tests and inspections not explicitly assigned to the City are the Contractor's responsibility. Unless otherwise indicated, the Contractor shall provide quality-control services as set forth in the Specifications and those required by Authorities having jurisdiction. The Contractor shall provide quality-control services required by Authorities having jurisdiction, whether specified or not.
  - 1. COST OF TESTS BORNE BY CONTRACTOR In the case of tests which are specifically called for in the Specifications to be provided by the Contractor or tests which are required by any Authority having jurisdiction, but are not indicated as the responsibility of the City, the cost thereof shall be borne by the Contractor and shall be deemed to be included in the Contract price. The Contractor shall reimburse the City for expenditures incurred in providing tests on materials and equipment submitted by the Contractor as the equivalent of that specifically named in the Specifications and rejected for non-compliance.
  - 2. Where services are indicated as Contractor's responsibility, the Contractor shall engage a qualified testing agency to perform these quality-control services. Any testing agency engaged by the Contractor to perform quality control services is subject to prior approval by the Commissioner.

QUALITY REQUIREMENTS 01 40 00 - 3




- 3. The Contractor shall not employ same entity engaged by the City, unless agreed to in writing by the Commissioner.
- 4. The Contractor shall notify testing agencies and the Resident Engineer at least 72 hours in advance of the date and time for the performance of Work that requires testing or inspecting.
- 5. Where quality-control services are indicated as Contractor's responsibility, the Contractor shall submit a certified written report, in triplicate to the Commissioner, of each quality-control service.
- 6. Testing and inspecting requested by the Contractor and not required by the Contract Documents are Contractor's responsibility.
- 7. The Contractor shall submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Manufacturer's Field Services: Where indicated, the Contractor shall engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Results shall be submitted in writing as specified in Section 01 33 00 SUBMITTAL PROCEDURES.
- D. Retesting/Re-inspecting: Regardless of whether the original tests or inspections were the Contractor's responsibility, the Contractor shall provide quality-control services, including retesting and re-inspecting, for construction that replaced Work that failed to comply with the Contract Documents.
- E. Associated Services: The Contractor shall cooperate with entities performing required tests, inspections, and similar quality-control services, and shall provide reasonable auxiliary services as requested. The Contractor shall notify the testing agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
  - 1. Access to the Work.

▶】▶】●

- 2. Incidental labor and facilities necessary to facilitate tests and inspections.
- 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist testing entity in obtaining samples.
- 4. Facilities for storage and field curing of test samples.
- 5. Delivery of samples to testing entities.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- 6. Design mix proposed for use for material mixes that require control by the testing entity.
- 7. Security and protection for samples and for testing and inspecting equipment at the Project site.
- F. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
  - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.
  - 2. Coordinate and cooperate with the Commissioning Authority/Agent as applicable for start-up, inspection and functional testing in the implementation of the Commissioning Plan.
- G. Manufacturer's Directions: Where the Specifications provide that the manufacturer's directions are to be used, such printed directions shall be submitted to the Commissioner.
- H. Inspection of Material: In the event that the Specifications require the Contractor to engage the services of an entity to witness and inspect any material especially manufactured or prepared for use in or part of the permanent construction, such entity shall be subject to prior written approval by the Commissioner.
  - 1. NOTICE The Contractor shall give notice in writing to the Commissioner sufficiently in advance of its intention to commence the manufacture or preparation of materials especially manufactured or prepared for use in or as part of the permanent construction. Such notice shall contain a request for inspection, the date of commencement and the expected date of completion of the manufacture or preparation of materials. Upon receipt of such notice, the Commissioner will arrange to have a representative present at such times during the manufacture as may be necessary to inspect the materials, or the Commissioner will notify the Contractor that the inspection will be made at a point



other than the point of manufacture, or the Commissioner will notify the Contractor that inspection will be waived.

- I. No Shipping Before Inspection: The Contractor shall comply with the foregoing before shipping any material.
- J. Certificate of Manufacture: When the Commissioner so requires, the Contractor shall furnish to the Commissioner authoritative evidence in the form of Certificates of Manufacture that the materials to be used in the work have been manufactured and tested in conformity with the Specifications. These certificates shall include copies of the results of physical tests and chemical analyses where necessary, that have been made directly on the product, or on similar products being fabricated by the manufacturer. This may include such approvals as B.S.A., M.E.A., B.E.C. Advisory Board, etc.
- K. Acceptance: When materials or manufactured products shall comprise such quantity that it is not practical to make physical tests or chemical analyses directly on the product furnished, a certificate stating the results of such tests or analyses of similar materials which were concurrently produced may, at the discretion of the Commissioner, be considered as the basis for the acceptance of such material or manufactured product.
- L. Testing Compliance: The testing personnel shall make the necessary inspections and tests, and the reports thereof shall be in such form as will facilitate checking to determine compliance with the Specifications, indicating thereon all analyses and/or test data and interpreted results thereof.
- M. Reports: Six (6) copies of the reports shall be submitted and authoritative certification thereof must be furnished to the Commissioner as a prerequisite for the acceptance of any material or equipment.
- N. Rejections: If, in making any test, it is ascertained by the Commissioner that the material or equipment does not comply with the Specifications, the Contractor will be notified thereof, and will be directed to refrain from delivering said materials or equipment, or to promptly remove it from the site or from the work and replace it with acceptable material at no additional cost to the City.
- O. Furnish Designated Materials: Upon rejection of any material or equipment submitted as the equivalent of that specifically named in the Specifications, the Contractor shall immediately proceed to furnish the designated material or equipment.

#### 1.8 APPROVAL OF MATERIALS:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- A. Local Laws: All materials, appliances and types or methods of construction shall be in accordance with the Specifications and shall in no event be less than that necessary to conform to the requirements of the New York City Construction Codes, Administrative Code and Charter of the City of New York.
- B. Approval of Manufacturer: The names of proposed manufacturers, material suppliers, and dealers who are to furnish materials, fixtures, equipment, appliances or other fittings shall be submitted to the Commissioner for approval, as early as possible, to afford proper review and analysis. No manufacturer will be approved for any materials to be furnished under the Contract unless it shall have a plant of ample capacity and shall have successfully produced similar products. All approvals of materials or equipment that are legally required by the New York City Construction Codes and other governing Authorities must be obtained prior to installation.
- C. All Materials: Fixtures, fittings, supplies and equipment furnished under the Contract shall be new and unused, except as approved by the Commissioner, and of standard first-grade quality and of the best workmanship and design. The City of New York encourages the use of recycled products where practical.
- D. INFORMATION TO SUPPLIERS In asking for prices on materials under any item of the Contract, the Contractor shall provide the manufacturer or dealer with such complete information from the

QUALITY REQUIREMENTS 01 40 00 - 5



Specifications and Contract Drawings as may in any case be necessary, and in every case the Contractor shall inform the manufacturer or dealer of all the General Conditions and requirements herein contained.

#### 1.9 SPECIAL INSPECTIONS:

#### A. SPECIAL INSPECTIONS:

- 1. Inspection of selected materials, equipment, installation, fabrication, erection or placement of components and connections made during the progress of the Work to ensure compliance with the Contract Documents and provisions of the New York City Construction Codes, shall be made by a Special Inspector. The City of New York will retain the services of the Special Inspector and bear the costs for the performance of Special Inspections in compliance with NYC Construction Codes requirements or as additionally may be called for in the project specifications, except as noted below for Form TR-3: Technical Report for Concrete Design Mix. The Special Inspector shall be an entity compliant with the requirements of the New York City Construction Codes. The Contractor shall notify the relevant Special Inspector in writing at least 72 hours before the commencement of any work requiring special inspection.
- 2. Form TR3: Technical Report Concrete Design Mix: The contractor shall be responsible for, and bear all costs associated with the filing and securing of approvals, if any, for Form TR3: Technical Report Concrete Design Mix, including, but not limited to, engaging the services of a New York City licensed Concrete Testing Lab for the review and approval of concrete design mix, testing, signatures and professional seals, etc., compliant with NYC Department of Buildings requirements, for each concrete design mix.
- 3. The Contractor shall notify the relevant Special Inspector in writing at least 72 hours before the commencement of any work requiring Special Inspection. The contractor shall be responsible for, and bear related costs to assure that all construction or work shall remain accessible and exposed for inspection purposes until the required inspection is completed.
- 4. Inspections and tests performed under "Special Inspection" shall not relieve the Contractor of the responsibility to comply with the Contract Documents, and that there is no warranty given to the Contractor by the City of New York in connection with such inspection and tests or certifications made under "Special Inspections".
- 5. The contractor must coordinate with the Resident Engineer or DDC Project Manager to provide access and schedule the work for inspection by the Special Inspector.

#### 1.10 INSPECTIONS BY OTHER CITY AGENCIES:

- A. Letter of Completion: Just prior to substantial completion of this Project, the Commissioner will file with the Department of Buildings, an application for a Letter of Completion or a Certificate of Occupancy for the structure.
- B. Final Inspections: In connection with the above mentioned application for a Letter of Completion or a Certificate of Occupancy and before certificates of final payments are issued, the Contractor will be required to arrange for all final inspections by the inspection staff of the Department of Buildings, Fire Department or other Governmental Agencies having jurisdiction, and secure all reports, sign offs, certificates, etc., by such inspection staff or other governmental agencies, in order that a Letter of Completion or Certificate of Occupancy can be issued promptly.

### 1.11 CERTIFICATES OF APPROVAL:

- A. Responsibility: The Contractor shall be responsible for and shall obtain all final approvals for the work installed under the Contract in the form of such certificates that are required by all governmental agencies having jurisdiction over the work of the Contract.
- B. Transmittal: All such certificates shall be forwarded to the Commissioner through the Resident Engineer.





- A. Government Agencies: All equipment and appliances furnished and installed under the Contract shall conform to the requirements of the Specifications, and shall in no event be less than that necessary to comply with the minimum requirements of the law and all of the governmental agencies having jurisdiction.
- B. Notice of Tests: Whenever the Specifications and/or any governmental agency having jurisdiction requires the acceptance test, the Contractor shall give written notice to all concerned of the time when these tests will be conducted.
- C. Energy: The City will furnish all energy, fuel, water and light required for tests.
- D. Labor and Materials: The Contractor shall furnish labor and all other material and instruments necessary to conduct the acceptance tests at no additional cost to the City.
- E. Certificates: The final acceptance by the Commissioner shall be contingent upon the Contractor delivering to the Commissioner all necessary certificates evidencing compliance in every respect with the requirements of the regulatory agencies having jurisdiction.
- F. Results: If the results of tests and Special Inspections indicate that the material or procedures do not meet requirements as set forth on the Contract Drawings or in the Specifications or are otherwise unsatisfactory, the Contractor shall only proceed as directed by the Resident Engineer. Additional costs resulting from retesting, re-inspecting, replacing of material and/or damage to the work and any delay caused to the schedule shall be borne by the Contractor.

#### PART II – PRODUCTS (Not Used)

#### PART III - EXECUTION

#### 3.1 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, the Contractor shall repair damaged construction and restore substrates and finishes.
  - 1. Provide materials and comply with installation requirements specified in other Specification Sections. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible.







No Text

QUALITY REQUIREMENTS 01 40 00 - 8



#### SECTION 01 42 00 REFERENCES

#### PART I - GENERAL

#### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

#### 1.2 DEFINITIONS:

# REFER TO THE ADDENDUM, Article IX, FOR ADDITIONAL DEFINITIONS AND REVISIONS TO THE CONTRACT AND SPECIFICATIONS

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. "APPROVED," ETC. "Approved," "acceptable," "satisfactory," and words of similar import shall mean and intend approved, acceptable or satisfactory to the Commissioner.
- C. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.
- D. "DIRECTED," "REQUIRED," ETC.- Wherever reference is made in the Contract to the work or its performance, the terms "directed," "required," "permitted," "ordered," "designated," "prescribed," "determined," and words of similar import shall, unless expressed otherwise, imply the direction, requirements, permission, order, designation or prescription of the Commissioner.
- E. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Operations at Project site including unloading, temporarily storing, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- H. "Provide": Furnish and install, complete and ready for the intended use."
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings.

REFERENCES 01 42 00 -1





# 1.3 CODES, AGENCIES AND REGULATIONS:

A.D.A.A.G.	Americans with Disabilities Act (ADA) – Architectural Barriers Act (ABA)
B.G. & E.	Bureau of Gas and Electricity of the City of New York
B.S. & A.	New York City Board of Standards and Appeals
DOE	Department of Energy
E.C.C.C.N.Y.S.	Energy Conservation Construction Code of New York State
EPA	Environmental Protection Administration
N.Y.C.C.C.	New York City Construction Codes – includes:
	New York City Plumbing Code
	New York City Building Code
	New York City Mechanical Code
N.Y.S.D.O.L N.Y.C.D.E.P	New York City Fuel Gas Code New York State Department of Labor New York City Department of Environmental Protection
N.Y.C.E.C. N.Y.C.E.C.C N.Y.C.F.C	New York City Electrical Code New York City Energy Conservation Code New York City Fire Code
N.Y.SD.E.C.	New York State Department of Environmental Conservation
O.S.H.A.	Occupational Safety & Health Administration

#### 1.4 INDUSTRY STANDARDS:

- A. STANDARD REFERENCES Unless otherwise specifically indicated in the Contract Documents, whenever reference is made to the furnishing of materials or testing thereof that conforms to the standards of any technical society, organization or body, it shall be construed to mean the latest standard, code, specification adopted and published by that technical society, organization or body, as of the date of the bid opening, unless the provisions of the New York City Construction Codes adopt a different or earlier dated version of such standard.
- B. APPLICABILITY OF STANDARDS: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect, to the extent referenced, as if bound or copied directly into the Contract Documents. Such standards are made a part of the Contract Documents by reference.
- C. CONFLICTING REQUIREMENTS: Where compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantity or quality, comply with the most stringent requirements. Immediately refer uncertainties, and requirements that are different but apparently equal, to the Commissioner in writing for a decision before proceeding.
- D. STANDARD SPECIFICATIONS When no reference is made to a code, standard or specification, the Standard Specifications of the ASTM or the AIEE, as the case may be, shall govern.
- E. REFERENCES Reference to a technical society, organization or body may be made in the Specifications by abbreviations. Abbreviations and acronyms used in the Specifications and other Contract Documents mean the associated name. The following names are subject to change and are



believed, but are not assured, to be accurate and up-to-date as of the Issue Date of the Contract Documents.

AA	Aluminum Association, Inc. (The)
AAADM	American Association of Automatic Door Manufacturers
AABC	Associated Air Balance Council
AAMA	American Architectural Manufacturers Association
AASHTO	American Association of State Highway and Transportation Officials
AATCC	American Association of Textile Chemists and Colorists (The)
ABAA	Air Barrier Association of America
ABMA	American Bearing Manufacturers Association
ACI	ACI International (American Concrete Institute)
ACPA	American Concrete Pipe Association
AEIC	Association of Edison Illuminating Companies, Inc. (The)
AF&PA	American Forest & Paper Association
AGA	American Gas Association
AGC	Associated General Contractors of America (The)
AGMA	American Gear Manufacturer Association
AHA	American Hardboard Association (Now part of CPA)
AHAM	Association of Home Appliance Manufacturers
AI	Asphalt Institute
AIA	American Institute of Architects (The)
AIEE	American Institute of Electrical Engineers
AISC	American Institute of Steel Construction
AISI	American Iron and Steel Institute
AITC	American Institute of Timber Construction
ALCA	Associated Landscape Contractors of America (Now PLANET - Professional Landcare Network)

REFERENCES 01 42 00 -3

# DDD NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

ALSc	American Lumber Standard Committee, Incorporated
ALI	Automotive Lift Institute
AMCA	Air Movement and Control Association International, Inc.
ANSI	American National Standards Institute
AOSA	Association of Official Seed Analysts, Inc.
APA	APA - The Engineered Wood Association
APA	Architectural Precast Association
API	American Petroleum Institute
ARI	Air-Conditioning & Refrigeration Institute
ARMA	Asphalt Roofing Manufacturers Association
ASA	American Standards Association
ASAE	American Society of Agricultural Engineers
ASCE/SEI	American Society of Civil Engineers, Structural Engineering Institute
ASHRAE	American Society of Heating, Refrigerating and Air-Conditioning Engineers
ASME	American Society of Mechanical Engineers
ASSE	American Society of Sanitary Engineering
ASTM	ASTM International (American Society for Testing and Materials International)
AWCI	AWCI International (Association of the Wall and Ceiling Industry International)
AWCMA	American Window Covering Manufacturers Association (Now WCSC)
AWI	Architectural Woodwork Institute
AWPA	American Wood-Preservers' Association
AWSC	American Welding Society
AWWA	American Water Works Association
BHMA	Builders Hardware Manufacturers Association
BIA	Brick Industry Association (The)

REFERENCES 01 42 00 -4



BICSI	BICSI
BIFMA	BIFMA International (Business and Institutional Furniture Manufacturer's Association International)
BISSC	Baking Industry Sanitation Standards Committee
CIBSE	Charted Institute of Building Services Engineers
CCC	Carpet Cushion Council
CDA	Copper Development Association
CEA	Canadian Electricity Association
CFFA	Chemical Fabrics & Film Association, Inc.
CGA	Compressed Gas Association
CGSB	Canadian General Standards Board
CIMA	Cellulose Insulation Manufacturers Association
CIPRA	Cast Iron Pipe Research Association
CISCA	Ceilings & Interior Systems Construction Association
CISPI	Cast Iron Soil Pipe Institute
CLFMI	Chain Link Fence Manufacturers Institute
CPA	Composite Panel Association
СРРА	Corrugated Polyethylene Pipe Association
CPSC	Consumer Product Safety Commission
CRI	Carpet & Rug Institute (The)
CRSI	Concrete Reinforcing Steel Institute
CSA	Canadian Standards Association
CSI	Cast Stone Institute
CSI	Construction Specifications Institute (The)
CSSB	Cedar Shake & Shingle Bureau
СТІ	Cooling Technology Institute (Formerly: Cooling Tower Institute)

DDDD NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

DASMA	Door and Access Systems Manufacturer's Association International
DHI	Door and Hardware Institute
DOC	U.S. Department of Commerce – National Institute of Standards and Technology
EIA	Electronic Industries Alliance
DOJ	U.S. department of Justice
EIMA	EIFS Industry Members Association
DOL	U.S. Department of labor
EJCDC	Engineers Joint Contract Documents Committee
DOTn	U.S. Department of Transportation
EN	European Committee of Standards
EJMA	Expansion Joint Manufacturers Association, Inc.
ESD	ESD Association
EVO	Efficiency Valuation Organization
FEME	Federal Emergency Management Agency
FIBA	Federation Internationale de Basketball Amateur (The International Basketball Federation)
FIVB	Federation Internationale de Volleyball (The International Volleyball Federation)
FMG	FM Global (Formerly: FM - Factory Mutual System)
FMRC	Factory Mutual Research (Now FMG)
FRSA	Florida Roofing, Sheet Metal & Air Conditioning Contractors Association, Inc.
FSA	Fluid Sealing Association
FSC	Forest Stewardship Council
GA	Gypsum Association
GANA	Glass Association of North America
GRI	(Now GSI)
GS	Green Seal
GSI	Geosynthetic Institute



Н	Hydraulic Institute
н	Hydronics Institute
НММА	Hollow Metal Manufacturers Association (Part of NAAMM)
HPVA	Hardwood Plywood & Veneer Association
HPW	H. P. White Laboratory, Inc.
HUD	U.S. Department of Housing and Urban Development
IAPMO	International Association of Plumbing and Mechanical Officials
IAS	International Approval Services (Now CSA International)
IBF	International Badminton Federation
ICC	International Code Council, Inc.
ICEA	Insulated Cable Engineers Association, Inc.
ICRI	International Concrete Repair Institute, Inc.
IEC	International Electrotechnical Commission
IEEE	Institute of Electrical and Electronics Engineers, Inc. (The)
IESNA	Illuminating Engineering Society of North America
IEST	Institute of Environmental Sciences and Technology
IGCC	Insulating Glass Certification Council
IGMA	Insulating Glass Manufacturers Alliance
11.1	Indiana Limestone Institute of America, Inc.
ISO	International Organization for Standardization
ISSFA	International Solid Surface Fabricators Association
ITS	Intertek
ITU	International Telecommunication Union
KCMA	Kitchen Cabinet Manufacturers Association
LMA	Laminating Materials Association (Now part of CPA)
LPI	Lightning Protection Institute
MBMA	Metal Building Manufacturers Association

REFERENCES 01 42 00 -7

DDDD NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

MFMA	Maple Flooring Manufacturers Association, Inc.
MFMA	Metal Framing Manufacturers Association
МН	Material Handling (Now MHIA)
MHIA	Material Handling Industry of America
MIA	Marble Institute of America
MPI	Master Painters Institute
MSS	Manufacturers Standardization Society of The Valve and Fittings Industry Inc.
NAAMM	National Association of Architectural Metal Manufacturers
NACE	NACE International (National Association of Corrosion Engineers International)
NADCA	National Air Duct Cleaners Association
NAGWS	National Association for Girls and Women in Sport
NAIMA	North American Insulation Manufacturers Association
NBGQA	National Building Granite Quarries Association, Inc.
NCAA	National Collegiate Athletic Association (The)
NCMA	National Concrete Masonry Association
NCPI	National Clay Pipe Institute
NCTA	National Cable & Telecommunications Association
NEBB	National Environmental Balancing Bureau
NECA	National Electrical Contractors Association
NeLMA	Northeastern Lumber Manufacturers' Association
NEMA	National Electrical Manufacturers Association
NETA	InterNational Electrical Testing Association
NFHS	National Federation of State High School Associations
NFPA	NFPA (National Fire Protection Association)
NFRC	National Fenestration Rating Council

.

# DDDD

NGA	National Glass Association
NHLA	National Hardwood Lumber Association
NLGA	National Lumber Grades Authority
NIS	National Institute of Standards and Technology
NOFMA	NOFMA: The Wood Flooring Manufacturers Association (Formerly: National Oak Flooring Manufacturers Association)
NRCA	National Roofing Contractors Association
NRMCA	National Ready Mixed Concrete Association
NSF	NSF International (National Sanitation Foundation International)
NSSGA	National Stone, Sand & Gravel Association
NTMA	National Terrazzo & Mosaic Association, Inc. (The)
NTRMA	National Tile Roofing Manufacturers Association (Now TRI)
NWWDA	National Wood Window and Door Association (Now WDMA)
OPL	Omega Point Laboratories, Inc. (Acquired by ITS - Intertek)
PCI	Precast / Pre-stressed Concrete Institute
PDCA	Painting & Decorating Contractors of America
PDI	Plumbing & Drainage Institute
PGI	PVC Geomembrane Institute
PLANET	Professional Landcare Network (Formerly: ACLA - Associated Landscape Contractors of America)
PPS	Power Piping Society
PTI	Post-Tensioning Institute
RCSC	Research Council on Structural Connections
RFCI	Resilient Floor Covering Institute
RIS	Redwood Inspection Service
RMI	Rack Manufacturers Institute
RTI	(Formerly: NTRMA - National Tile Roofing Manufacturers Association) (Now TRI)



NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

SAE	SAE International
SCAQMD	South Coast Air Quality Management District
SCS	Scientific Certification System
SDI	Steel Deck Institute
SDI	Steel Door Institute
SEFA	Scientific Equipment and Furniture Association
SGCC	Safety Glazing Certification Council
SHBI	Steel Heating Boiler Institute
SIA	Security Industry Association
SIGMA	Sealed Insulating Glass Manufacturers Association (Now IGMA)
SJI	Steel Joist Institute
SMA	Screen Manufacturers Association
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
SMPTE	Society of Motion Picture and Television Engineers
SPFA	Spray Polyurethane Foam Alliance (Formerly: SPI/SPFD - The Society of the Plastics Industry, Inc.; Spray Polyurethane Foam Division)
SPIB	Southern Pine Inspection Bureau (The)
SPRI	Single Ply Roofing Industry
SSINA	Specialty Steel Industry of North America
SSPC	SSPC: The Society for Protective Coatings
STI	Steel Tank Institute
SWI	Steel Window Institute
SWRI	Sealant, Waterproofing, & Restoration Institute
TCA	Tile Council of America, Inc.
TIA/EIA	Telecommunications Industry Association/Electronic Industries Alliance
TMS	The Masonry Society

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

ТРІ	Truss Plate Institute, Inc.
ТРІ	Turfgrass Producers International
TRI	Tile Roofing Institute (Formerly: RTI - Roof Tile Institute)
UL	Underwriters Laboratories Inc.
ULC	Underwriters Laboratories of Canada
UNI	Uni-Bell PVC Pipe Association
USAV	USA Volleyball
USC	United States Code
USGBC	U.S. Green Building Council
USITT	United States Institute for Theatre Technology, Inc.
WASTEC	Waste Equipment Technology Association
WCLIB	West Coast Lumber Inspection Bureau
WCMA	Window Covering Manufacturers Association (Now WCSC)
WCSC	Window Covering Safety <b>Council</b> (Formerly: WCMA - Window Covering Manufacturers Association)
WDMA	Window & Door Manufacturers Association (Formerly: NWWDA - National Wood Window and Door Association)
WI	Woodwork Institute (Formerly: WIC - Woodwork Institute of California)
WIC	Woodwork Institute of California (Now WI)
WMMPA	Wood Moulding & Millwork Producers Association
WRI	Wire Reinforcement Institute, Inc.
USEPA	United States Environmental Protection Agency
WSRCA	Western States Roofing Contractors Association
WWPA	Western Wood Products Association

PART II - PRODUCTS (Not Used)

PART III - EXECUTION (Not Used)

END OF SECTION 01 42 00

REFERENCES 01 42 00 -11





#### REFERENCES 01 42 00 -12



#### SECTION 01 50 00 TEMPORARY FACILITIES, SERVICES AND CONTROLS

#### PARTI- GENERAL

#### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

#### 1.2 SUMMARY:

- A. This section includes the following:
  - a. Temporary Water System
  - b. Temporary Sanitary Facilities
  - c. Temporary Electric Power, Temporary Lighting System, And Site Security Lighting
  - d. Temporary Heat
  - e. Dewatering Facilities And Drains
  - f. Temporary Field Office for Contractor
  - g. Resident Engineer's Office
  - h. Material Sheds
  - i. Temporary Enclosures
  - j. Temporary Partitions
  - k. Temporary Fire Protection
  - I. Work Fence Enclosure
  - m. Rodent and Insect Control
  - n. Plant Pest Control Requirements
  - o. Project Identification Signage
  - p. Security Guards/Fire Guards on Site
  - q. Project Sign and Rendering
  - r. Safety
- 1.3 RELATED SECTIONS: include without limitation the following:
  - A. Section 01 10 00 SUMMARY
  - B. Section 01 42 00 REFERENCES
  - C. Section 01 54 11 TEMPORARY ELEVATORS AND HOISTS
  - D. Section 01 54 23 TEMPORARY SCAFFOLDS AND SWING STAGING
  - E. Section 01 77 00 CLOSE OUT PROCEDURES

#### 1.4 DEFINITIONS:

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Permanent Enclosure: As determined by Commissioner, permanent or temporary roofing that is complete, insulated, and weather tight; exterior walls which are insulated and weather tight; and all openings that are closed with permanent construction or substantial temporary closures.



C. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.

#### 1.5 SUBMITTALS:

- A. Site Plan: Show temporary facilities, utility hookups, staging areas, and parking areas for construction personnel.
- B. Reports: Submit reports of tests, inspections, meter readings and similar procedures for temporary use.

#### 1.6 PROJECT CONDITIONS:

- A. Temporary Use of Permanent Facilities and Services: The Contractor shall be responsible for the operation, maintenance, and protection of each permanently installed facility and service while in use during construction before Final Acceptance by the City, regardless of previously assigned responsibilities.
- B. Install, operate, maintain and protect temporary facilities, services and controls.
  - 1. Keep temporary services and facilities clean and neat in appearance.
  - Operate temporary services in a safe and efficient manner.
  - 3. Relocate temporary services and facilities as needed as Work progresses.
  - 4. Do not overload temporary services and facilities or permit them to interfere with progress.
  - 5. Provide necessary fire prevention measures.
  - 6. Do not allow hazardous, dangerous or unsanitary conditions, or public nuisances to develop or persist on-site

# 1.7 NON-REGULAR WORK HOURS (OVERTIME):

- A. The Contractor shall provide the temporary services, facilities and controls set forth in this Section during other than regular working hours if the Drawings and/or the Specifications indicate that the Work, or specific components thereof, must be performed during other than regular working hours. In such case, all costs for the provision of temporary services, facilities and controls during other than regular working hours shall be deemed included in the total Contract Price.
- B. The Contractor shall provide the temporary services, facilities and controls set forth in this Section during other than regular working hours if a change order is issued directing the Contractor to perform the Work, or specific components thereof, during other than regular working hours. In such case, compensation for the provision of temporary services, facilities and controls during other than regular working hours shall be provided through the change order.

# 1.8 SERVICES BEYOND COMPLETION DATE:

A. The Contractor shall provide the temporary services, facilities and controls set forth in this Section until the date on which it completes all required work at the site, including all punch list work, as certified in writing by the Resident Engineer, or earlier if so directed in writing by the Commissioner. The Contractor shall provide such temporary services, facilities and controls even if completion of all required work at the site occurs after the time fixed for such completion in Schedule A.





#### PART II - PRODUCTS

#### 2.1 MATERIALS:

- A. Provide undamaged materials in serviceable condition and suitable for use intended.
- B. Tarpaulins: Waterproof, fire-resistant UL labeled with flame spread rating of 15 or less. For temporary enclosures, provide translucent, nylon-reinforced, laminated polyethylene or polyvinyl chloride, fire-retardant tarpaulins.
- C. Water: Potable and in compliance with requirements of the Department of Environmental Protection.

#### 2.2 EQUIPMENT:

- A. Provide undamaged equipment in serviceable condition and suitable for use intended.
- B. Water Hoses: Heavy-duty abrasive-resistant flexible rubber hoses, 100 feet (30 m) long with pressure rating greater than the maximum pressure of the water distribution system. Provide adjustable shutoff nozzles at hose discharge.
- C. Electric Power Cords: Grounded extension cords.
  - 1. Provide hard-service cords where exposed to abrasion or traffic.
  - 2. Provide waterproof connectors to connect separate lengths of electric cords where single lengths will not reach areas of construction activity.
  - 3. Do not exceed safe length-voltage ratio.
- D. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.

#### PART III - EXECUTION:

#### 3.1 INSTALLATION, GENERAL:

- A. Locate facilities where they will serve the Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.
- B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities as approved by the Resident Engineer.

#### 3.2 TEMPORARY WATER SYSTEM:

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.2 A

- A. TEMPORARY WATER SYSTEM NEW FACILITIES: During construction, the Contractor shall furnish a Temporary Water System as set forth below.
  - 1. Immediately after the Commissioner has issued an order to start work, the Contractor shall file an application with the Dept. of Environmental Protection for the schedule of charges for water use during construction. The Contractor will be responsible for payment of water charges.
  - 2. Immediately after the Commissioner has issued an order to start work, the Contractor shall file an application with the Department of Environmental Protection's Bureau of Water Supply and obtain a permit to install the temporary water supply system. The system shall be installed and maintained for the use of the Contractor and its subcontractors. A copy of the above mentioned permit shall be filed with the Commissioner. The Contractor shall provide temporary water main, risers and waste stacks as directed and install on each floor, outlets with two (2) 3/4" hose valve connections over a barrel installed on a steel pan. The Contractor shall provide drains from the pans to the stack and house sewer and hose bibs to drain the water supply

TEMPORARY FACILITIES, SERVICES AND CONTROLS 01 50 00 -3



risers and mains. During winter months, the Contractor shall take the necessary precautions to prevent the temporary water system from freezing. The Contractor shall provide repairs to the temporary water supply system for the duration of the project until said temporary system is dismantled and removed.

3. Disposition of Temporary Water System: The Contractor shall be responsible for dismantling the temporary water system when no longer required for the construction operations, or when replaced by the permanent water system installed for the project, or as otherwise directed by the Resident Engineer. All repair work resulting from the dismantling of the temporary water system shall be the responsibility of the Contractor.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.2 B

- B. TEMPORARY WATER SYSTEM PROJECTS IN EXISTING FACILITIES:
  - When approved by the Commissioner, use of existing water system will be permitted for temporary water service during construction, as long as the system is cleaned and maintained in a condition acceptable to the Commissioner. At Substantial Completion, the Contractor shall restore the existing water system to conditions existing before initial use.
  - The Contractor shall be responsible for all repairs to the existing water system permitted to be used for temporary water service during construction. The Contractor shall be responsible to maintain the existing system in a clean condition on a daily basis, acceptable to the Commissioner.
  - 3. The Contractor will be responsible for payment of water charges as directed by the Commissioner. Billing will be in accordance with the Department of Environmental Protection schedule of charges for Building Purposes.
- C. WASH FACILITIES: The Contractor shall install wash facilities supplied with potable water at convenient locations for personnel involved in handling materials that require wash-up for a healthy and sanitary condition.
  - 1. Dispose of drainage properly.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- 2. Supply cleaning compounds appropriate for each condition.
- 3. Include safety showers, eyewash fountains and similar facilities for the convenience, safety and sanitation of personnel.
- D. DRINKING WATER FACILITIES: The Contractor shall provide drinking water fountains or containerized tap-dispenser bottled-drinking water units, complete with paper cup supplies. Where power is accessible, provide electric water coolers to maintain dispensed water temperature at 45 to 55 deg. F (7 to 13 deg. C).

#### 3.3 TEMPORARY SANITARY FACILITIES:

**⋗**】▶】●

A. The Contractor shall provide toilets, wash facilities and drinking water fixtures in compliance with regulations and health codes for type, number, location, operation and maintenance of fixtures and facilities. Provide toilet tissue, paper towels, paper cups and similar disposable materials as appropriate for each facility, and provide covered waste containers for used materials.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.3 B

B. SELF-CONTAINED TOILET UNITS:

- 1. The Contractor shall provide temporary single-occupant toilet units of the chemical, aerated recirculation, or combustion type for use by all construction personnel. Units shall be properly vented and fully enclosed with a glass-fiber-reinforced polyester shell or similar nonabsorbent material. Quantity of toilet units shall comply with the latest OSHA regulations.
- 2. Toilets: Install separate self-contained toilet units for male and female personnel. Shield toilets to ensure privacy.



# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.3 C

- C. EXISTING TOILETS:
  - 1. TOILET FACILITIES: When approved by the Commissioner, the Contractor shall arrange for the use of existing toilet facilities by all personnel during the execution of the work. The Contractor shall be responsible to clean and maintain facilities in a condition acceptable to the Resident Engineer and, at completion of construction, to restore facilities to their condition at the time of initial use.
  - 2. MAINTENANCE The Contractor shall maintain the temporary toilet facilities in a clean and sanitary manner and make all necessary repairs.
  - NUISANCES The Contractore shall not cause any sanitary nuisance to be committed by its employees or the employees of its subcontractors in or about the work, and shall enforce all sanitary regulations of the City and State Health Authorities.

# 3.4 TEMPORARY ELECTRIC POWER, TEMPORARY LIGHTING SYSTEM, AND SITE SECURITY LIGHTING:

- A. SCOPE: This Section sets forth the General Conditions and procedures relating to Temporary Electric Power, Temporary Lighting System and Site Security Lighting during the construction period.
   B. TEMPORARY ELECTRIC POWER:
  - The Contractor shall provide and maintain a Temporary Electric Power service and distribution system of sufficient size, capacity and power characteristics required for construction operations for all required work by the Contractor and its subcontractors, including but not limited to power for the Temporary Lighting System, Site Security Lighting, construction equipment, hoists, temporary elevators and all field offices. Temporary Electric Power shall be provided as follows:

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.4 B (1)

- 1. CONNECTION TO UTILITY LINES:
  - a. Temporary Electric Power Service for use during construction shall be provided as follows: The Contractor shall make all necessary arrangements with the Public Utility Company and pay all charges for the Temporary Electric Power system. The Contractor shall include in its total Contract Price any charges for Temporary Electric Power, including charges that may be made by the Public Utility Company for extending its electrical facilities, and for making final connections. The Contractor shall make payment directly to the Public Utility Company.
  - b. APPLICATIONS FOR METER: The Contractor shall make application to the Public Utility Company and sign all documents necessary for, and pay all charges incidental to, the installation of a watt hour meter or meters for Temporary Electric Power. The Contractor shall pay to the Public Utility Company, all bills for Temporary Electric energy used throughout the work, as they become due.
  - c. SERVICE AND METERING EQUIPMENT The Contractor shall furnish and install, at a suitable location on the site, approved service and metering equipment for the Temporary Electric Power System, ready for the installation of the Public Utility Company's metering devices. The temporary service mains to and from the metering location shall be not less than 100 Amperes, 3-phase, 4-wire and shall be of sufficient capacity to take care of all demands for all construction operations and shall meet all requirements of the NYCEC.



#### REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.4 B (2)

# 2. CONNECTION TO EXISTING ELECTRICAL POWER SERVICE:

- a. When approved by the Commissioner, electrical power service for the Temporary Lighting System and for the operation of small tools and equipment less than. <sup>1</sup>/<sub>4</sub> horsepower may be taken from the existing electric distribution system if the existing system is of adequate capacity for the temporary power load. The Contractor shall cooperate and coordinate with the facility custodian, so as not to interfere with the normal operation of the facility.
- b. There will be no charge to the Contractor for the electrical energy consumed.
- c. The Contractor shall provide, maintain and pay all costs for separate temporary electric power for any temporary power for equipment larger than 1/4 horsepower. When directed by the Commissioner, the Contractor shall remove its own temporary power system.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.4 B (3)

- 3. ELECTRICAL GENERATOR POWER SERVICE:
  - a. When connection to Utility Lines or existing facility electric service is not available or is not adequate to supply the electric power need for construction operations, the Contractor shall provide self-contained generators to provide power beyond that available.
  - b. Pay for all energy consumed in the progress of the Work, exclusive of that available from the existing facility or Utility Company.
  - c. Provide for control of noise from the generators.
  - d. Comply with the Ultra Low Sulfur Fuel in Non-Road Vehicles requirements as set forth in Article 5.4 of the Contract.

# C. USE OF COMPLETED PORTIONS OF THE ELECTRICAL WORK:

- 1. USE OF MAIN DISTRIBUTION PANEL: As soon as the permanent electric service feeders and equipment, metering equipment and main distribution panel are installed and ready for operation, the Contractor shall have the temporary lighting and power system changed over from the temporary service points to the main distribution panel.
- COST OF CHANGE OVER The Contractor shall be responsible for all costs due to this change over of service and it shall also make application to the Public Utility Company for a watt hour meter to be set on the permanent meter equipment.
- 3. The requirements for temporary electric power service specified herein shall be adhered to after change over of service until final acceptance of the project.
- 4. NO EXTRA COST The operation of the service and switchboard equipment shall be under the supervision of the Contractor, but this shall in no way be interpreted to mean the acceptance of such part of the installation or relieve the Contractor from its responsibility for the complete work or any part thereof. There shall be no additional charge for supervision by the Contractor.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.4 D

# D. TEMPORARY LIGHTING SYSTEM:

1.

The Contractor shall provide adequate service for the temporary lighting system, or a minimum of 100 Amperes, 3-phase, 4-wire service for the temporary lighting system, whichever is



greater, and make all necessary arrangements with the Public Utility Company and pay all charges by them for the Temporary Lighting System

- 2. The Contractor shall furnish and connect to the metered service point, a Temporary Lighting System to illuminate the entire area where work is being performed and points adjacent to the work, with separately fused circuits for stairways and bridges. Control switches for stairway circuits shall be located near entrance on ground floor.
- 3. ITEMS: The Temporary Lighting System provided by the Contractor shall consist of wiring, fixtures, left-hand double sockets, (one (1) double socket for every 400 square feet, with one (1) lamp and one (1) three-prong outlet) lamps, fuses, locked type guards, pigtails and any other incidental material. Additional details may be outlined in the detailed Specifications for the Electrical Work. Changes may be made, provided the full equivalent of those requirements is maintained.
- 4. The Temporary Lighting System shall be progressively installed as required for the advancement of the work under the Contract.
- RELOCATION: The cost for the relocation or extension of the original Temporary Lighting System, required by the Contractor or its subcontractors, that is not required due to the normal advancement of the work, as determined by the Resident Engineer, shall be borne by the Contractor.
- 6. PIGTAILS: shall be furnished with left-hand sockets with locked type guards and 40 feet of rubber covered cable. The Contractor shall furnish and distribute a minimum of three (3) complete pigtails to each subcontractor. See the detailed Electrical Specifications for possible additional pigtails required.
- 7. LAMPS: The Contractor shall furnish and install one (1) complete set of lamps, including those for the trailers. Broken and burned out lamps in the temporary lighting system, DDC field office and construction trailers, shall be replaced by the Contractor. All lamps shall be compact fluorescent
- 8. CIRCUIT PROTECTION: The Contractor shall furnish and install GFI protection for the Temporary Lighting and Site Security Lighting Systems.
- 9. MAINTENANCE OF TEMPORARY LIGHTING SYSTEM:
  - a. The Contractor shall maintain the Temporary Lighting System in good working order during the scheduled hours established.
  - b. The Contractor shall include in its total Contract Price all costs in connection with the Temporary Lighting System, including all costs for installation, maintenance and electric power.
- 10. REMOVAL OF TEMPORARY LIGHTING SYSTEM: The temporary lighting system shall be removed by the Contractor when authorized by the Commissioner.
- 11. HAND TOOLS: The temporary lighting system shall not be used for power purposes, except that light hand tools not larger than 1/4 horsepower may be operated from such system by the Contractor and its subcontractors.

#### **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.4 E**

E. SITE SECURITY LIGHTING (FOR NEW CONSTRUCTION ONLY):

- 1. The Contractor shall furnish, install and maintain a system of site security lighting, as herein specified, to illuminate the construction site of the project, and it shall be connected to and energized from the Temporary Lighting System. All costs in connection with site security lighting shall be deemed included in the total Contract Price.
- 2. It is essential that the site security lighting system be completely installed and operating, at the earliest possible date. The Contractor shall direct its subcontractors to cooperate, coordinate and exert every effort to accomplish an early complete installation of the site security lighting system. After the system is installed and in operation, if a part of the system interferes with the work of any trade, the Contractor shall be completely responsible for the expense of removing,



relocating and replacing all equipment necessary to reinstate the system to proper operating conditions.

- 3. The system shall consist of flood lighting by pole mounted guarded sealed-beam units. Floodlight units shall be mounted 16 feet above grade. Floodlights shall be spaced around the perimeter of the site to produce an illumination level of no less than one (1) foot candle around the perimeter of the site, as well as in any potentially hazardous area or any other area within the site that might be deemed by the Resident Engineer to require security illumination. The system shall be installed in a manner acceptable to the Resident Engineer. The first lighting unit in each circuit shall be provided with a photoelectric cell for automatic control. The photoelectric cell shall be installed as per manufacturer's recommendations.
- 4. All necessary poles shall be furnished and installed by the Contractor.
- 5. The site security lighting shall be kept illuminated at all times during the hours of darkness. The Contractor shall, at its own expense, shall keep the system in operation, and shall furnish and install all material necessary to replace all damaged or burned out parts.
- The Contractor shall be on telephone call alert for maintaining the system during the operating period stated above.
   All materials and equipment furnished under this partice abolt parts.
- 7. All materials and equipment furnished under this section shall remain the property of the Contractor and shall be removed and disposed of by the Contractor when authorized in writing by the Resident Engineer.

# **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.5**

# 3.5 TEMPORARY HEAT:

1.

» ] » ] ⊶

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- A. GENERAL:
  - Definition: The provision of Temporary Heat shall mean the provision of heat in order to permit construction to be performed in accordance with the Progress Schedule during all seasons of the year and to protect the work from the harmful effects of low temperature. In the event the building, or any portion thereof, is occupied during construction, the provision of Temporary Heat shall include the provision of heat to permit normal operations in such occupied areas.
    - a. The provision of Temporary Heat shall be in accordance with the temperature requirements set forth in Sub-Section 3.5 C herein.
    - b. The provision of Temporary Heat shall include the provision of: 1) all fuel necessary and required, 2) all equipment necessary and required, and 3) all operating labor necessary and required. Operating labor shall mean that minimum force required for the safe day to day operation of the system for the provision of Temporary Heat and shall include, without limitation, heating maintenance labor and/or Fire Watch as required by NYC Fire Department regulations. Operating labor may be required seven (7) days per week and during other than normal working hours, for the period of time required by seasonal weather conditions.
    - C. In the event the building, or any portion thereof, is occupied and the Project involves the replacement, modification and/or shut down of the permanent heating system, or any key component thereof; and such system is a combined system which furnishes domestic hot water for the building occupants, the provision of Temporary Heat shall include the provision of domestic hot water at the same temperature as the system which is being replaced. Domestic hot water shall be provided in accordance with the phasing requirements set forth in the Contract Documents.
  - 2. Responsibility: The Contractor's responsibility for the provision of Temporary Heat, including all expenses in connection therewith, shall be as set forth below:
    - a. Projects Involving Enclosure of the Building:

3

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- Prior to Enclosure Until the Commissioner determines that the building has been enclosed, as set forth in Sub-Section 3.5 B; the Contractor shall be responsible for the provision of Temporary Heat.
- 2) Post Enclosure Once the Commissioner determines that the building, or any portion thereof, has been enclosed, as set forth in Sub-Section 3.5 B, the Contractor shall be responsible for the provision of Temporary Heat by one or more of the following means: 1) by an existing heating system (if any), 2) by a permanent heating system which is being installed as part of the Project, or 3) by a temporary heating system(s).
- 3) The Contractor shall, within two (2) weeks of the kick-off meeting, submit to DDC for review its proposed plan to provide Temporary Heat. Such plan is subject to approval by the Resident Engineer. The Contractor shall provide Temporary Heat in accordance with the approved plan until written acceptance by the Commissioner of the work of all Contractors, including punch list work, unless directed otherwise in writing by the Commissioner. The responsibility of the Contractor provided for herein is subject to the exception set forth in Sub-Section 3.5 A.2 (b) herein.
- b. Projects not involving Enclosure of the Building:
  - If the Project involves the installation of a new permanent heating system if one did not exist previously, or the replacement, modification and/or shut down of the existing permanent heating system, or any key component thereof, the Contractor shall be responsible for the provision of Temporary Heat, except as otherwise provided in Sub-Section 3.5 H.3(b).2 herein.
  - 2) If the Project does not involve the installation of a new permanent heating system if one did not exist previously, or the replacement, modification and/or shut down of the existing permanent heating system, or any key component thereof; there is no Contractor responsibility of the provision of Temporary Heat, unless otherwise specified in the Contract Documents. However, if the Commissioner, pursuant to Sub-Section 3.5 H.3 (b).1 herein, determines that the provision of Temporary Heat is necessary due to special and/or unforeseen circumstances, the Contractor shall be responsible for the provision of Temporary Heat and shall be paid for the same in accordance with Sub-Section 3.5 H.3 (b).1 herein.
- B. ENCLOSURE OF STRUCTURES:
  - 1. Notification: The Contractor shall notify all its subcontractors and the Resident Engineer at least 30 days prior to the anticipated date that the building(s) will be enclosed.
  - 2. Commissioner Determination: The Commissioner shall determine whether the building, or any portion thereof, has been enclosed. As indicated in Sub-Section 3.5 A.2 above, once the building has been enclosed, the Contractor shall be responsible for the provision of Temporary Heat. The Commissioner's determination with respect to building enclosure shall be based upon all relevant facts and circumstances, including without limitation, 1) whether the building meets the criteria set forth in Paragraph 3 below, and 2) whether the openings in the building, such as doorways and windows, have been sufficiently covered so as to provide reasonable heat retention and protection from the elements
  - 3. Criteria for enclosure:
    - a. Roof Area:
      - 1) A building shall be considered to be roofed when the area to be roofed is covered by a permanent structure and all openings through the permanent structure are covered and protected by temporary covers as described in Paragraph (c) below.
      - 2) Intermediate floor structures of multi-floor buildings shall be considered to be roofed subject to the same requirements of the building roof.



- 3) The final roofing system need not be in place for the building or structure to be determined to be enclosed; provided, however, all openings through the permanent structure covering the roof must be covered and protected by temporary covers, as described in Paragraph (c) below.
- b. Walls: For the walls to be determined to be enclosed permanent exterior wall elements or facing material must be in place and all openings must be covered and protected by temporary covers, as described in Paragraph (c) below.
- C. Temporary Covers: In order to be acceptable, temporary covers must be securely fixed to prevent the entrance of rain, snow and direct wind. The minimum material requirements for temporary covers are as follows: 1) minimum10 mil. Plastic 2) minimum 12 ounce waterproof canvas tarpaulins, or 3) a minimum three-eighths (3/8) inch thickness exterior grade plywood.
- Temporary covers for openings shall be the responsibility of the Contractor and such work shall be deemed included in the Contract price.

## C. TEMPERATURE REQUIREMENTS:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- 1. Unoccupied Buildings: The temperature requirement for the provision of Temporary Heat in unoccupied buildings shall be the GREATER of the following: 1)50 degrees Fahrenheit, or 2) the temperature requirement for the particular type of work set forth in the Contract Documents.
- 2. Occupied Buildings: The temperature requirement for the provision of Temporary Heat in occupied buildings, or portions thereof, shall be the GREATER of the following: 68 degrees Fahrenheit or the temperature requirement for the particular type of work set forth in the Contract Documents.

#### D. DURATION:

▶】▶】●

- 1. The Contractor shall be required to provide Temporary Heat until the date on which it completes all required work at the site, including all punch list work, as certified in writing by the Resident Engineer, or earlier if so directed in writing by the Commissioner. The Contractor shall be responsible for the provision of Temporary Heat for the time specified herein, regardless of any delays in completion of the Project, including delays that result in the commencement of the provision of Temporary Heat during a season that is later than that which may have been originally anticipated. The Contractor shall include in its Total Contract Price all expenses in connection with the provision of Temporary Heat in accordance with the requirements specified herein.
- 2. The total Contract duration is set forth in consecutive calendar days in Schedule A of the Addendum. The Table set forth below indicates the number of full heating seasons that are deemed included in various contract durations, which are specified in consecutive calendar days (ccd)s. At a minimum, a full heating season shall extend from October 15<sup>th</sup> to April 15<sup>th</sup>.

Contract Duration up to 360 ccds 360 to 720 ccds more than 720 ccds

Full Heating Seasons Required 1 full heating season 2 full heating seasons 3 full heating seasons

# E. METHOD OF TEMPORARY HEAT:

- 1. The method of temporary heat shall be in conformance with the New York City Fire Code and with all applicable laws, rules and regulations. Prior to implementation, such method shall be subject to the written approval of the Commissioner.
- 2. The method of temporary heat shall:
  - a. Not cause the deposition of dirt or smudges upon any finished work or cause any defacement or discoloration to the finished work.
  - b. Not be injurious or harmful to people or materials.

- c. Portable fueled heating devises or equipment SHALL NOT BE ALLOWED for use as temporary heat other than construction-related curing or drying in conformance with the NYC Fire Code.
- 3. No open fires will be permitted.

#### F. TEMPORARY HEATING SYSTEM:

 The temporary system for the provision of Temporary Heat provided by the Contractor following enclosure of the building shall be complete including, subject to provisions of paragraph E above, boilers pumps, radiators, space heaters, water and heating piping, insulation and controls. The temporary system for the provision of Temporary Heat shall be capable of maintaining the minimum temperature requirements set forth in Paragraph C above.

#### G. COORDINATION:

1.

1. The Contractor, in the provision of Temporary Heat, shall coordinate its operations in order to insure sufficient and timely performance of all required work, including work performed by trade subcontractors. The Contractor shall supply and pay for all water required and used in the building for the operation of the heating system(s) for the purpose of Temporary Heat. The Contractor shall include all expenses in connection with the supply of water for Temporary Heat in its Total Contract Price. During the period in which Temporary Heat in an enclosed building is being furnished and maintained, the Contractor shall provide proper ventilating and drying, open and close the windows and other openings when necessary for the proper execution of the work and also when directed by DDC. The Contractor shall maintain all permanent or temporary enclosures at its own expense.

# H. USE OF PERMANENT HEATING SYSTEMS:

- Use of Permanent Heating System for Temporary Heat after Building Enclosure
  - a. The Contractor shall provide all labor and materials to promptly furnish and set all required equipment and convectors and/or radiators, piping, valves, fitting, etc., in ample time for their use for the provision of Temporary Heat after enclosure of the building.
  - b. New portions of the permanent heating system that are used for furnishing Temporary Heat shall be left in near perfect condition when delivered to the City for operation. Any repairs required, other than for ordinary wear and tear on the equipment, shall be made by the Contractor at his/her expense. The starting date for the warranty or guarantee period for such equipment shall be the date of Substantial Completion acceptance.
  - c. In the event that the Contractor does not advance the installation of the permanent heating system in sufficient time to permit its use for Temporary Heat as determined by DDC, the Contractor shall furnish and install a separate system for the provision of Temporary Heat as required to maintain the minimum temperature requirements set forth in Paragraph C above.
- 2. All equipment for the system for the provision of Temporary Heat shall be placed so as to comply with the requirements specified hereinbefore, and shall be connected, disconnected and suitably supported and located so as to permit construction work, including finish work such as wall plastering and painting, to proceed. The installation of the system for the provision of Temporary Heat by the Contractor, including the placing of ancillary system equipment, shall be coordinated with the operations of all trade subcontractors so as to insure sufficient and timely performance of the work. Once the permanent heating system is operating properly, the Contractor shall remove all portions of the system for Temporary Heat not part of the permanent heating system.

# 3. Temporary Heat Allowance for Special Conditions or and/or Unforeseen Circumstances.

a. The City may establish an allowance in the Contract for payment of costs and expenses in connection with the provision of Temporary Heat as set forth herein. If established, the City will include an amount for such allowance on the Bid Form, and the Contractor shall

> TEMPORARY FACILITIES, SERVICES AND CONTROLS 01 50 00 -11

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

• ] • ] •

h.

include such allowance amount in its Total Contract Price. The Contractor shall only be entitled to payment from this allowance under the conditions and in accordance with the requirements set forth below. In the event this allowance or any portion thereof remains unexpended at the conclusion of the Contract, such allowance shall remain the sole property of the City. Should the amount of the allowance be insufficient to provide payment for the expenses specified below, the City will increase the amount of the allowance.

- The allowance set forth herein may be utilized only under the conditions set forth below.
  - In the event the Project does not involve the installation of a new permanent heating system if one did not exist previously, or the replacement, modification and/or shut down of the existing permanent heating system, or any key component thereof, and the Commissioner determines that the provision of Temporary Heat is necessary due to special and/or unforeseen circumstances, the Contractor shall be responsible for the provision of Temporary Heat, as directed by the Commissioner. The City shall pay such Contractor for all costs for labor, material, and equipment necessary and required for the same. Payment shall be made in accordance with Article 26 of the Contract, except that the cost of fuel shall be as set forth in Paragraph (c) below.
  - 2. In the event the Commissioner determines that there is a need for maintenance of the permanent heating system by the Contractor after written acceptance by the Commissioner of the work, and that the need for such maintenance is not the fault of the Contractor, the Contractor shall provide the required maintenance of the permanent heating system for the period of time directed by the Commissioner. The City shall pay the Contractor for the cost of direct labor and fuel necessary and required in connection with such maintenance, excluding the cost of any foremen or other supervision. Payment shall be made in accordance with Article 26 of the Contract, except that the cost of fuel shall be as set forth in Paragraph (c) below.
- c. Payment for Fuel Costs Payment from the allowance set forth herein for the cost of fuel necessary and required to operate the system for the provision of Temporary Heat or to maintain the permanent heating system under the conditions set forth in Paragraph b above shall be limited to the direct cost of such fuel. The Contractor shall not be entitled to any overhead and/or profit for such fuel costs. In order to receive payment for such fuel costs, the Contractor must present original invoices for the same. DDC reserves the right to furnish the required fuel.

#### I. RELATED ELECTRICAL WORK:

- The Contractor shall be responsible for providing the items set forth below and shall include all expenses in connection with such items in its Total Contract Price. The Contractor shall provide such items promptly when required and shall in all respects coordinate its work with the work performed by trade subcontractors in order to facilitate the provision of Temporary Heat.
  - a. The Contractor shall provide all labor, materials, equipment and power necessary and required to furnish and maintain any temporary or permanent electrical connections to all equipment specified to be connected as part of the work of his Contract.
  - b. The Contractor shall supply and pay for all power necessary and required for the operation of the system for the provision of Temporary Heat and/or the permanent heating system used for Temporary Heat. Such power shall be provided by the Contractor for the duration the Contractor is required to provide Temporary Heat, as set forth in Sub-Section 3.5 D herein.
- In providing the items set forth in Paragraph 1 above, the Contractor is advised that labor may be required seven (7) days a week and/or during other than normal working hours for the period of time required by seasonal weather conditions.



### J. RELATED PLUMBING WORK:

- 1. The Contractor shall be responsible for providing all labor, materials and equipment necessary and required to furnish and maintain all temporary or permanent connections to all equipment or plumbing outlets specified to be provided as part of the work of this Contract. The Contractor shall include all expenses in connection with such items of work in its Total Contract Price. The Contractor shall provide such items of work promptly when required and shall in all respects coordinate its work with the work performed by trade subcontractors in order to facilitate the provision of Temporary Heat.
- 2. In the event portions of the permanent plumbing equipment furnished by the Contractor as part of the work of this Contract are used for the provision of Temporary Heat either during construction or prior to acceptance by the City of the complete plumbing system, the Contractor shall be responsible to provide such plumbing equipment to the City in near perfect condition and shall make any repairs required, other than for ordinary wear and tear on the equipment, at his expense. The starting date for warranty and/or guarantee period for such plumbing equipment shall be the date of Substantial Completion acceptance by the City.
- 3. For Projects requiring the installation of new and/or modified gas service, as well as associated meter installations, the Contractor shall promptly perform all required filings and coordination with the Utility Companies in order to expedite the installation, testing, and approval of the gas service and associated meter(s).

# 3.6 STORM WATER CONTROL, DEWATERING FACILITIES AND DRAINS:

#### A. PUMPING:

- 1. Comply with requirements of authorities having jurisdiction. Maintain Project site, excavations, and construction free of water. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of storm water from heavy rainfall.
- 2. Contractor shall furnish and install all necessary automatically operated pumps of adequate capacity with all required piping to run-off agencies, so as to maintain the excavation, cellar floor, pits and exterior depressions and excavations free from accumulated water during the entire period of construction and up to the date of final acceptance of work of the Contract.
- 3. All pumps shall be maintained at all times in proper working order.
- 4. Dispose of rainwater in a lawful manner that will not result in flooding Project or adjoining properties nor endanger permanent Work or temporary facilities.
- 5. Remove snow and ice as required to minimize accumulations.

# 3.7 TEMPORARY FIELD OFFICE FOR CONTRACTOR:

- A. The Contractor shall establish a temporary field office for its own use at the site during the period of construction, at which readily accessible copies of all Contract Documents shall be kept.
- B. The field office shall be located where it will not interfere with the progress of any part of the work or with visibility of traffic control devices.
- C. CONTRACTOR'S REPRESENTATIVE: In charge of the office there shall be a responsible and competent representative of the Contractor, duly authorized to receive orders and directions and to put them into effect.
- D. Arrangements shall be made by the Contractor whereby its representative may be readily accessible by telephone.
- E. All temporary structures shall be of substantial construction and neat appearance, and shall be painted a uniform gray unless otherwise directed by the Commissioner.
- F. CONTRACTOR'S SIGN The Contractor shall post and keep posted, on the outside of its field office, office or exterior fence or wall at site of work, a legible sign giving full name of the company, address of the company and telephone number(s) of responsible representative(s) of the firm who can be reached in event of an emergency at any time.





G. ADVERTISING PRIVILEGES - The City reserves the right to all advertising privileges. The Contractor shall not cause any signs of any kind to be displayed at the site unless specifically required herein or authorized by the Commissioner.

# 3.8 DDC FIELD OFFICE:

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.8 A

# A. OFFICE SPACE IN EXISTING BUILDING:

- 1. The Resident Engineer will arrange for office space for sole use in the building where work is in progress. The Contractor shall provide and install a lockset for the door to secure the equipment in the room. The Contractor shall provide two (2) keys to the Resident Engineer. After completion of the project the Contractor shall replace the original lockset on the door and ensure its proper operation.
- 2. In addition to equipment specified in Sub-Section 3.8 D, the Contractor shall provide, for exclusive use of the DDC Field Office, the following:
  - a. Two (2) single pedestal desks, 42" x 32"; two (2) swivel chairs with arms and three (3) side chairs without arms to match desk. Two metal (2) lockers, single units, 15" x 18" x 78" overall including 6" legs. Lockers to have flat key locks with two (2) keys each, General Steel products or approved equal. Two (2) full ball bearing suspension four (4) drawer vertical legal filing cabinets with locks, approximately 52"H x 28 ½"D x 18"W.
  - b. One (1) 9000 B.T.U air conditioner or as directed by Commissioner. Wiring for the air conditioner shall be minimum No. 12 AWG fed from individual circuits in the fuse box.
  - c. One (1) folding conference table, 96" x 30" and ten (10) folding chairs.
  - d. Two (2) metal wastebaskets.
  - e. One (1) fire extinguisher, one (1) quart vaporizing liquid type, brass, wall mounted by Pyrene No. C21 or approved equal.
  - f. One (1) Crystal Springs water cooler with bottled water, Model No. LP14058 or approved equal to be furnished for the duration of the project as required.
- 3. The Contractor shall provide one (1) telephone, where directed and shall pay all costs for telephone service for calls within the New York City limits for the duration of the project.
- 4. All furniture and equipment, except computer equipment specified in Sub-Section 3.8 D.3, shall remain the property of the Contractor.
- 5. Computer Workstation quantities shall be provided as specified in Sub-Section 3.8 B 3-a for DDC Managed Projects, or Sub-Section 3.8 B 3-b for CM Managed projects.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.8 B

- B. DDC FIELD OFFICE TRAILER:
  - 1. GENERAL: The Contractor shall, for the time frame specified herein, provide and maintain at its own cost and expense a DDC Construction Field Office and all related items as specified herein [hereinafter collectively referred to as the "DDC Field Office"] for the exclusive use of the Resident Engineer. The DDC Field Office shall be located at the Project site and shall be solely dedicated to the Project. Provision of the DDC Field Office shall commence within THIRTY (30) days from Notice to proceed and shall continue through forty-five (45) days after Substantial Completion of the required construction at the Project site. The Contractor shall remove the DDC Field Office forty-five (45) days after Substantial Completion of the required in writing by the Commissioner.
  - TRAILER: The Contractor shall provide at its own cost and expense a mobile office trailer for use as the DDC Field Office. The Contractor shall install and connect all utility services to the



trailer within thirty (30) days from Notice to Proceed. The trailer shall have equipment in compliance with the minimum requirements hereinafter specified. Any permits and fees required for the installation and use of said trailer shall be borne by the Contractor. The trailer including furniture and equipment therein, except computer equipment specified in Sub-Section 3.8D.3 herein, shall remain the property of the Contractor.

3. Trailer shall be an office type trailer of the size specified herein, with exterior stairs at entrance. Trailer construction shall be minimum 2 x 4 wall construction fully insulated with paneled interior walls, pre-finished gypsum board ceilings and vinyl tile floors.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.8.B.3a or SUB-SECTION 3.8.B.3b.

- a. <u>DDC Managed Project Trailer</u>: DDC Field Office Trailer Size, Layout and Computer Workstation:
  - 1) Overall length: 32 Feet Overall width: 10 Feet
  - 2) Interior Layout: Provide one (1) general office/conference room area and one (1) private office at one end of the trailer. Provide equipment and amenities as specified in Sub-Section 3.8.B herein.
  - Computer Workstation: Provide one (1) complete computer workstation, as specified in Sub-Section 3.8.D herein, in the private office area as directed by the Resident Engineer.
- b. <u>CM Managed Project Trailer</u>: DDC Field Office Trailer Size, Layout and Computer Workstation:
  - 1) Overall length: 50 Feet
  - Overall width: 10 Feet
  - 2) Interior Layout:
    - Provide one (1) large general office/conference room in the center of the trailer and two (2) private offices, one (1) each at either end of the trailer. Provide equipment and amenities as specified in Sub-Section 3.8.B herein.

 Computer Workstation: Provide three (3) complete computer workstations as specified in Sub-Section 3.8.D herein. Provide one (1) each complete computer workstation in each private office and one (1) complete computer workstation at the secretarial position as directed by the Resident Engineer.

4. The exterior of the trailer shall be lettered with black block lettering of the following heights with white borders:

CITY OF NEW YORK	2-1/2"
DEPARTMENT OF DESIGN AND CONSTRUCTION	3-3/4"
DIVISION OF PUBLIC BUILDINGS	3-1/2"
DDC FEILD OFFICE	2-1/2"

NOTE: In lieu of painting letters on trailer the Contractor may substitute a sign constructed of a good quality weatherproof material with the same type and size of lettering above.

- 5. All windows and doors shall have aluminum insect screens. Provide wire mesh protective guards at all windows.
- 6. The interior shall be divided by partitions into general and private office areas as specified herein. Provide a washroom located adjacent to the private office and a built-in wardrobe closet opposite the washroom. Provide a built-in desk in the private office(s) with fixed overhead shelf and clearance below for two (2) file cabinets.





- 7. Provide a built-in drafting or reference table, located in the general office/conference room, at least 60 inches long by 36 inches wide with cabinet below and wall type plan rack at least 42 inches wide.
- 8. The washroom shall be equipped with a flush toilet, wash basin with two (2) faucets, medicine cabinet, complete with supplies and a toilet roll tissue holder. Plumbing and fixtures shall be approved house type, with each appliance trapped and vented and a single discharge connection. Five (5) gallon capacity automatic electric heater for domestic hot water shall be furnished.
- 9. HVAC: The trailer shall be equipped with central heating and cooling adequate to maintain a temperature of 72 degrees during the heating season and 75 degrees during the cooling season when the outside temperature is 5 degrees F. winter and 89 degrees F. summer.
- 10. Lighting shall be provided via ceiling mounted fluorescent lighting fixtures to a minimum level of 50 foot candles in the open and private office(s) along with sufficient lighting in the washroom. Broken and burned out lamps shall be replaced by the Contractor. A minimum of four (4) duplex convenience outlets shall be provided in the open office and two (2) each in the private office(s). These outlets shall be in addition to special outlet requirements for computer stations, copiers, HVAC unit, etc.
- 11. Electrical service switch and panel shall be adequately sized for the entire trailer load. Provide dedicated circuits for HVAC units, hot water heater, copiers and other equipment as required. All wiring and installation shall conform to the New York City Electrical Code.
- 12. The following movable equipment shall be furnished:
  - a. Two (2) single pedestal desks, 42" x 32"; two (2) swivel chairs with arms and three (3) side chairs without arms to match desk. Two (2) full ball bearing suspension four (4) drawer vertical legal filing cabinets with locks and two (2) full ball bearing two (2) drawer vertical legal filing cabinets in each private office located below built-in desk.
  - b. One (1) folding conference table, 96" x 30" and ten (10) folding chairs.
  - c. Three (3) metal wastebaskets.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

DDD→

- d. One (1) fire extinguisher one (1) quart vaporizing liquid type, brass, wall mounted by Pyrene No. C21 or approved equal.
- e. One (1) Crystal Springs water cooler with bottled water, Model No. LP14058 or approved equal to be furnished for the duration of the Contract as required.
- 13. TRAILER TEMPORARY SERVICE: Plumbing and electrical work required for the trailer will be furnished and maintained as below.
  - a. PLUMBING WORK: The Contractor shall provide temporary water and drainage service connections to the DDC Field Office trailer for a complete installation. Provide all necessary soil, waste, vent and drainage piping.

Contractor to frost-proof all water pipes to prevent freezing.

- 1) REPAIRS, MAINTENANCE: The Contractor shall provide repairs for the duration of the project until the trailer is removed from the site.
- 2) DISPOSITION OF PLUMBING WORK: At the expiration of the time limit set forth in Article 3.8 A.14(c).4 herein, the temporary water and drainage connections and piping to the DDC Field Office trailer shall be removed by the Contractor and shall be plugged at the mains. All piping shall become the property of the Contractor for Plumbing Work and shall be removed from the site, all as directed. All repair work due to these removals shall be the responsibility of the Contractor.
- b. ELECTRICAL WORK:
  - 1) The Contractor shall furnish, install and maintain a temporary electric feeder to the DDC Field Office trailer immediately after it is placed at the job site.
  - 2) The temporary electrical feeder and service switch/fuse shall be adequately sized based on the trailer load and installed per the New York City Electrical Code and complying with utility requirements.


B NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- 3) Make all arrangements and pay all costs to provide electric service.
- 4) The Contractor shall pay all costs for current consumed and for maintenance of the system in operating condition, including the furnishing of the necessary bulb replacements lamps, etc., for the duration of the project and for a period of fortyfive (45) days after the date of Substantial Completion.
- 5) Disposition of Electric Work: At the expiration of the time limit set forth, the temporary feeder, safety switch, etc., shall be removed and disposed of as directed.
- 6) All repair work due to these removals shall be the responsibility of the Contractor.
- c. MAINTENANCE
  - The Contractor shall provide and pay all costs for regular weekly janitor service and furnish toilet paper, sanitary seat covers, cloth towels and soap and maintain the DDC Field Office in first-class condition, including all repairs, until the trailer is removed from the site.
  - 2) <u>Supplies</u>: The Contractor shall be responsible for providing (a) all office supplies, including without limitation, pens, pencils, stationery, filtered drinking water and sanitary supplies, and (b) all supplies in connection with required computers and printers, including without limitation, an adequate supply of blank CD's/DVD's, storage boxes for blank CDs/DVDs, and paper and toner cartridges for the printer.
  - 3) <u>Risk of Loss</u>: The entire risk of loss with respect to the DDC Field Office and equipment shall remain solely and completely with the Contractor. The Contractor shall be responsible for the cost of any insurance coverage determined by the Contractor to be necessary for the Field Office.
  - 4) At forty-five (45) days after the date of Substantial Completion, or sooner as directed by the Commissioner, the Contractors shall have all services disconnected and capped to the satisfaction of the Commissioner. All repair work due to these removals shall be the responsibility of the Contractor.
- d. TELEPHONE SERVICE: The Contractor shall provide and pay all costs for the following telephone services for the DDC Field Office trailer:
  - 1) Separate telephone lines for one (1) desk phone in each private office.
  - 2) One (1) wall phone (with six (6) foot extension cord) at plan table.
  - 3) Separate telephone lines for the fax machine and internet access in each private office. Telephone service shall include voice mail.
  - 4) A remote bell located on outside of trailer
  - 5) The telephone service shall continue until the trailer is removed from the site.
- e. PERMITS: The Contractor shall make the necessary arrangements and obtain all permits and pay all fees required for this work.
- C. RENTED SPACE: The Contractor has the option of providing, at its cost and expense, rented office or store space in lieu of trailer. Said space shall be in the immediate area of the Project and have adequate plumbing, heating and electrical facilities. Space chosen by the Contractor for the DDC Field Office must be approved by the Commissioner before the area is rented. All insurance, maintenance and equipment, including computer workstations specified in Sub-Section 3.8 D in quantities required as specified in Sub-Section 3.8 B 3 for the DDC Field Office trailer, shall also apply to rented spaces.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.8 D

- D. ADDITIONAL EQUIPMENT FOR THE DDC FIELD OFFICE:
  - 1. The Contractor shall provide a high volume copy machine (50 copies per minute) for paper sizes 8½ x 11, 8½ x 14 & 11 x 17. Copier shall remain at job site until the DDC Field office trailer is removed from the site.





- 2. The Contractor shall furnish a fax machine and a telephone answering machine at commencement of the project for the exclusive use of the DDC Field Office. All materials shall be new, sealed in manufacturer's original packaging and shall have manufacturers' warrantees. All items shall remain the property of the City of New York at the completion of the project.
- COMPUTER WORKSTATION: The Contractor shall provide a complete computer workstation as specified herein:
  - a. Hardware/Software Specification:

**▶** ] **▶** ] ←

- <u>Computer Equipment -</u> Computers shall be provided for all contracts that have a Total Consecutive Calendar Days for construction duration as set forth in Schedule "A" of 180 CCD's or greater. Contracts of lesser duration shall not require computers.
- 2) Computers furnished by the Contractor for use by City Personnel, for the duration of the contract, shall be in accordance with Specific Requirements, contained herein, shall remain the property of the City of New York at the completion of the project and shall meet the following minimum requirements:
- 3) Personal Computer(s) Each Workstation Configuration.

a) Make and Model:

b) Processor:

c) System RAM:

CD-RW:

- Dell; HP; Gateway; Acer; or, an approved equivalent. (Note: an approved equivalent requires written approval of the Assistant Commissioner of ITS.)
- i5-2400 (6MB Cache, 3.1GHz) or faster computer -Single Processor.
- Minimum of 4GB (Gigabytes) Dual Channel DDR3 SDRAM at 1333MHz – 2 DIMMSs
- d) Hard Disk Drive(s): 500 GB (Gigabytes) Serial ATA (7200RPM) w/DataBurst Cache, or larger.

Parallel Port, and three (3) USB Ports.

Internal CD-RW, 48x Speed or faster.

of RAM.

Monitor.

16xDVD+/-RW DVD Burner (with double layer write capability) 16x Speed or faster

(2) full size PCI Slots available.

Integrated 10/100/1000 Ethernet card.

g) I/O Ports:

e)

f)

- h) Video Display Card:
- i) Monitor:
- j) Available Exp. Slots:
- k) Network Interface:
- I) Other Peripherals: Optica

Optical scroll Mouse, 101 Key Keyboard, Mouse Pad and all necessary cables.

Must have at least one (1) Serial Port, one (1)

HD Graphics (VGA, HDMI) with a minimum of 64 MB

22" W, 23.0 Inch VIS, Widescreen, VGA/DVI LCD

System as configured above shall have at least two

m) Software Requirement: Microsoft Windows 7 Professional SP1, 32 bit; Microsoft Office Professional 2010 or 2013; Microsoft Project 2010; Adobe Acrobat reader; Anti-Virus software package with 2 year updates subscription; and, either Auto Cad LT or Microsoft

> TEMPORARY FACILITIES, SERVICES AND CONTROLS 01 50 00 -18



Visio Standard Edition, as directed by the Resident Engineer.

- 4) DDC Field Office Specs: DDC Field Offices requiring computers shall be provided with the following:
  - a) One (1) broad-band internet service account. Wideband Internet connectivity at a minimum throughput of 15 Mbps download and 5 Mbps upload is required at each field office location with 1-5 staffers. For larger field offices see table below for minimum required upload speeds. Telephone service should be bundled together with Internet connectivity. Because of throughput requirements Verizon FIOS is the preferred connectivity provider where available.

Office Personnel #	Upload Speeds (Minimum)
1-5	5 Mbps
6-10	10 Mbps
11 – 15	15 Mbps
16 – 20	20 Mbps

This account will be active for the life of the project. The e-mail name for the account shall be the DDC Field Office/project Id (e.g. <u>FLD K HWK666</u> <u>McGuinness@earthlink.com</u>).

- b) One (1) 600 DPI HP Laser Jet Printer (twelve (12) pages per minute or faster) with one (1) Extra Paper (Legal Size)
- c) All necessary cabling for equipment specified herein.
- d) Storage Boxes for Blank CD's
- e) Printer Table
- f) UPS/Surge Suppressor combo
- 5) All computers required for use in the Engineer's Field Office shall be delivered, installed, and setup in the Field Office by the Contractor.
- 6) All Computer Hardware shall come with a three (3) year warranty for on-site repair or replacement. Additionally, and notwithstanding any terms of the warranty to the contrary, the Contractor is responsible for rectifying all computer problems or equipment failures within one (1) business day.
- 7) An adequate supply of blank CDs/DVDs, and paper and toner cartridges for the printer shall be provided by the Contractor, and shall be replenished by the Contractor as required by the Resident Engineer.
- 8) It is the Contractor's responsibility to ensure that electrical service and phone connections are also available at all times; that is, the Field Office Computer(s) is to be powered and turned on twenty-four (24) hours each day.
- 9) Broadband connectivity is preferred at each field office location. Please take into consideration that an extra phone line dedicated to the modem must be ordered as part of the contract unless Internet broadband connectivity, via Cable or DSL, is available at the planned field office location. Any questions regarding this policy should be directed to the Assistant Commissioner of Information Technology Services at 718-391-1761.
- 10) <u>Ownership</u>: The equipment specified above shall, unless otherwise directed by the Commissioner, be the sole property of the City of New York upon delivery to the DDC Field Office. The Contractor shall prepare and maintain an accurate inventory of all equipment which it purchases for the DDC Field Office. Such inventory shall be provided to the City of New York. Upon completion of the

TEMPORARY FACILITIES, SERVICES AND CONTROLS 01 50 00 -19



required services, as directed by the Commissioner, the Contractor shall turn such equipment over to the City of New York.

HEAD PROTECTION (HARD HATS): E.

EW YORK CITY DEPARTMENT OF **DESIGN + CONSTRUCTION** 

- The Contractor shall provide a minimum of 10 standard protective helmets for the exclusive use 1 of Department of Design and Construction personnel and their visitors. Helmets shall be turned over to the Resident Engineer and kept in the DDC Field Office.
- Upon completion of the project, the helmets shall become the property of the Contractor. 2.

#### 3.9 MATERIAL SHEDS:

**D**]**D**]•

- Material sheds used by the Contractor for the storage of its materials shall be kept at locations which A. will not interfere at any time with the progress of any part of the work or with visibility of traffic control devices.
- B. Store combustible materials apart from the facility.

#### 3.10 TEMPORARY ENCLOSURES:

- Provide temporary enclosures for protection of construction, in progress and completed, from Α. exposure, foul weather, other construction operations, and similar activities. Provide temporary weather tight enclosure for building exterior.
- Where heating or cooling is needed and permanent enclosure is not complete, insulate temporary Β. enclosures.

# 3.11 TEMPORARY PARTITIONS:

- Provide floor-to-ceiling dustproof partitions to limit dust and dirt migration and to separate occupied A. tenant areas from fumes and noise.
  - 1. Construct dustproof partitions with gypsum wallboard with joints taped on occupied side, and fireretardant plywood on construction operations side.
  - Construct dustproof partitions with 2 layers of 3-mil (0.07-mm) polyethylene sheet on each side. 2. Cover floor with 2 layers of 3-mil (0.07-mm) polyethylene sheet, extending sheets 18 inches (460 mm) up the sidewalls. Overlap and tape full length of joints. Cover floor with fire-retardant plywood.
    - Construct vestibule and airlock at each entrance through temporary partition with not less a. than 48 inches (1219 mm) between doors. Maintain water-dampened foot mats in vestibule.
  - Insulate partitions to provide noise protection to occupied areas. 3. 1
  - Seal joints and perimeter. Equip partitions with dustproof doors and security locks. 5.
  - Protect air-handling equipment.
  - 6. Weather strip openings.
  - 7. Provide walk-off mats at each entrance through temporary partition.

# 3.12 TEMPORARY FIRE PROTECTION:

- Install and maintain temporary fire-protection facilities of types needed to protect against reasonably Α. predictable and controllable fire losses. Comply with NFPA 241.
- Β. Prohibit smoking in all areas.
- Supervise welding operations, combustion-type temporary heating units, and similar sources of fire C. ignition according to requirements of authorities having jurisdiction.





- D. Develop and supervise an overall fire-prevention and protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.
- E. Provide temporary standpipes and hoses for fire protection. Hang hoses with a warning sign stating that hoses are for fire-protection purposes only and are not to be removed. Match hose size with outlet size and equip with suitable nozzles.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.13

# 3.13 WORK FENCE ENCLOSURE:

- A. The Contractor shall furnish, erect and maintain a wood construction or chain-link fence to the extent shown on the drawings or required by the work enclosing the entire project on all sides. All materials used shall be new. Any permit required for the installation and use of said fence and costs shall be borne by the Contractor.
- B. WOOD FENCE shall be 7'-0" high with framing construction of yellow pine, using 4" x 4" approved preservative-treated posts on not more than 6'-0" centers, with three (3) rails of at least 2" x 4" size to which shall be secured minimum 1/2 inch thick exterior grade plywood. Posts shall be firmly fixed in the ground at least 30" and thoroughly braced. Top edge of fence shall be trimmed with a rabbeted edge mould. Provide on the street traffic sides of fence, observation openings as directed.
  - 1. GATES Provide an adequate number of double gates, complete with hardware, located as approved by the Resident Engineer. Double gates shall have a total clear opening of 14'-0" with two (2) 7'-0" hinged swinging sections. Hanging posts shall be 6" x 6" and shall extend high enough to receive and be provided with tension or sag rods for the swinging sections.
  - 2. PAINTING The fence and gates shall be entirely painted on the street and public sides with one (1) coat of exterior primer and one (1) top coat of exterior grade acrylic-latex emulsion paint. Black stenciled signs reading "POST NO BILLS" shall be painted on fence with three (3) inch high letters on 25 foot spacing for the entire length of fence on street traffic sides. Signs shall be stenciled five (5) feet above the sidewalk.
- C. CHAIN-LINK FENCING shall be minimum 2-inch thick, galvanized steel, chain-link fabric fencing; 8 feet high with galvanized steel pipe posts; minimum 2-3/8-inch OD line posts and 2-7/8-inch OD corner and pull posts, with 1-5/8-inch OD top and bottom rails. Fence shall be accurately aligned and plumb, adequately braced and complete with gates, locks and hardware as required. Under no condition shall fencing be attached or anchored to existing construction or trees.
- D. 1. It shall be the obligation of the Contractor to remove all posters, advertising signs, and markings, etc., immediately.
  - 2. Should the fencing be required to be relocated during the course of the Contract, it shall be done by the Contractor at no additional cost to the City.
  - 3. Where sidewalks are used for "drive over" purposes for Contractor vehicles, a suitable wood mat or pad shall be provided for protection of sidewalks and curbs.
  - 4. Where required, make provision for fire hydrants, lampposts, etc.
  - 5. REMOVAL When directed by the Resident Engineer, the fence shall be removed.

# 3.14 RODENT AND INSECT CONTROL:

A. DESCRIPTION: The Contractor shall provide all labor, materials, plant and equipment, and incidentals required to survey and monitor rodent activity and to control any infestation or outbreak of rodents, rats, mice, water beetles, roaches and fleas within the project area. Special attention should be paid to the following conditions or areas:

1. Wet areas within the project area, including all temporary structures.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- 2. All exterior and interior temporary toilet structures within the project area.
- 3. All Field Offices and shanties within the project area of all subcontractors and DDC.
- 4. Wherever there is evidence of food waste and/or discarded food or drink containers, in quantity, that would cause breeding of rodents or the insects herein specified.
- 5. Any other portion of the premises requiring such special attention.

#### B. MATERIALS:

1. All materials shall be approved by the New York State Department of Environmental Conservation and comply with the New York City Health Code, OSHA and the laws, ordinances and regulations of State and Federal agencies pertaining to such chemical and/or materials.

#### C. PERSONNEL:

1. All pest control personnel must be supervised by an exterminator licensed in categories 7A and 8.

#### D. METHODS:

- 1. Application and dosage of all materials shall be done in strict compliance with the manufacturer's recommendations.
- 2. Any unsanitary conditions, such as uncollected garbage or debris, resulting from all Contractor's activities, which will provide food and shelter to the resident rodent population shall be corrected by the Contractor immediately after notification of such condition by the Resident Engineer.

#### E. RODENT CONTROL WORK:

- 1. In wetlands, woodlands and areas adjacent to a stream, special precautions must be taken to protect water quality and to ensure the safety of other wildlife. To prevent poisoned bait from entering streams, no poisoned bait shall be used in areas within seventy-five (75) feet of all stream banks. Live traps must be used in these seventy-five (75) foot buffer zone areas and within wetland and woodland areas.
- In areas outside the seventy-five (75) foot zone of protection adjacent to streams, and in areas outside wetlands and woodlands, tamper proof bait stations with poisoned bait shall be placed during the period of construction and any consumed or decomposed bait shall be replenished as directed.
- 3. At least one month prior to initiation of the construction work, and periodically thereafter, live traps and/or rodenticide bait in tamper proof bait stations, as directed above, shall be placed at locations that are inaccessible to pets, human beings, children and other non-target species, particularly wildlife (for example-birds) in the project area.
- 4. The Contractor shall be responsible for collecting and disposing of all trapped and poisoned rodents found in live traps and tamper proof bait stations. The Contractor shall also be responsible for posting and maintaining signs announcing the baiting of each particular location.

The Contractor shall be responsible for the immediate collection and disposal of any visible rodent remains found on streets or sidewalks within the project area.

- 5. It is anticipated that public complaints will be addressed to the Commissioner. The Contractor, where directed by the Commissioner, shall take appropriate actions, like baiting, trapping, proofing, etc., to remedy the source of complaint within the next six (6) hours of normal working time which is defined herein for the purposes of this section as 7 A.M. to 6 P.M. on Mondays through Saturdays.
- 6. Emergency service during the regular workday hours (Monday through Friday) shall be rendered within 24 hours, if requested by the Commissioner, at no additional cost to the City.



#### F. EDUCATION & NOTICES:

- 1. The Contractor shall post notices on all Construction Bulletin Boards advising workers, employees, and residents to call the Engineer's Field Office to report any infestation or outbreak of rodents, rats, mice, water beetles, roaches and fleas within the project area. The Contractor shall provide and distribute literature pertaining to IPM techniques of rodent control to affected businesses and superintendents of nearby residential buildings to ensure their participation in maintaining their establishments free of unsanitary conditions, harborage removal and rodent proofing.
- Prior to application of any chemicals, the Contractor shall furnish to the Commissioner copies or sample labels for each pesticide, antidote information, and Material Data Safety Sheets (MSDS) for each chemical used.

#### G. RECORDS

- 1. The Contractor shall keep a record of all rodent and waterbug infestation surveys conducted by him/her and make available, upon request, to the Commissioner. The findings of each survey shall include, but not be limited to, recommended Integrated Pest Management (IPM) techniques, like baiting, trapping, proofing, etc., proposed for rodent and waterbug pest control.
- 2. The Contractor shall maintain records of all locations baited along with the type and quantity of rodenticide and insecticide bait used.

#### 3.15 PLANT PEST CONTROL REQUIREMENTS and TREE PROTECTION REQUIREMENTS:

- A. <u>Plant Pest Control Requirements</u>: The Contractor and its subcontractors, including the Certified Arborist described below, shall comply with all Federal and New York State laws and regulations concerning Asian Longhorned Beetle (ALB) management, including protocols for ALB eradication and containment promulgated by the New York State Department of Agriculture and Markets (NYSDAM). The Contractor is referred to: (1) Part 139 of Title 1 NYCRR, Agriculture and Markets Law, Sections 18, 164 and 167, as amended, and (2) State Administrative Procedure Act, Section 202, as amended.
  - 1. All tree work performed within the quarantine areas must be performed by New York State Department of Agriculture and Markets (NYSDAM) certified entities. Transportation of all host material, living, dead, cut or fallen, inclusive of nursery stock, logs, green lumber, stumps, roots, branches and debris of a half inch or more in diameter from the quarantine areas is prohibited unless the Contractor or its sub-contractor performing tree work has entered into a compliance agreement with NYSDAM. The terms of said compliance agreement shall be strictly complied with. Any host material so removed shall be delivered to a facility approved by NYSDAM. For the purpose of this contract host material shall be ALL species of trees.
  - 2. Any host material that is infested with the Asian Longhorned Beetle must be immediately reported to NYSDAM for inspection and subsequent removal by either State or City contracts, at no cost to the Contractor.
  - 3. Prior to commencement of tree work, the Contractor shall submit to the Commissioner a copy of a valid Asian Longhorned Beetle compliance agreement entered into with NYSDAM and the Contractor or its sub-contractor performing tree work. If any host material is transported from the quarantine area the Contractor shall immediately provide the Commissioner with a copy of the New York State 'Statement of Origin and Disposition' and a copy of the receipt issued by the NYSDAM approved facility to which the host materials are transported.
  - 4. Quarantine areas, for the purpose of this contract shall be defined as all five boroughs of the City of New York. In addition, prior to the start of any tree work, the Contractor shall contact the



NYC Department of Parks & Recreation's Director of Landscape Management at (718) 699-6724, to determine the limits of any additional quarantine areas that may be in effect at the time when tree work is to be performed. The quarantine area may be expanded by Federal and State authorities at any time and the Contractor is required to abide by any revisions to the quarantine legislation while working on this contract. For further information please contact: NYSDAM (631) 288-1751.

- B. <u>Tree Protection Requirements</u>: The Contractor shall retain a Certified Arborist, as defined by New York City Department of Parks and Recreation (NYCDPR) regulations, to provide the services described below.
  - <u>Surveys and Reports</u>: The Certified Arborist shall, at the times indicated below, conduct a survey and prepare a plant material assessment report which includes: (1) identification, by species and pertinent measurements, of all plant material located on the project site, or in proximity to the project site, as described below, including all trees, significant shrubs and/or planting masses; (2) identification and plan for the containment of plant pests and pathogens, including the ALB, as described in paragraph A above; (3) evaluation of the general health and condition of any infected plant material.
  - 2. <u>Frequency of Reports</u>: The Certified Arborist shall conduct a survey and provide a plant material assessment report at two (2) points in time: (1) prior to the commencement of construction work; and (2) at the time of substantial completion. In addition, for projects exceeding 24 months in duration, the Certified Arborist shall conduct a survey and prepare a report at the midpoint of construction. Copies of each plant material assessment report shall be submitted to the Resident Engineer within two (2) weeks of the survey.
  - 3. <u>Proximity to Project Site</u>: Off-site trees, significant shrubs and/or planting masses shall be considered to be located in proximity to the project site under the circumstances described below.
    - a. The tree trunk, significant shrub, or primary cluster of stems in a planting mass is within 50 (fifty) feet of the project's Contract Limit Lines (CLLs) or Property Lines (PLs).
    - b. Any part of the tree or shrub stands within 50 (fifty) feet of: (a) a path for site access for vehicles and/or construction equipment; or (b) scaffolding to be erected for construction activity, including façade remediation projects.
    - c. The Certified Arborist determines that the critical root zone (CRZ) of an off-site tree, significant shrub, or primary cluster of stems in a planting mass extends into the project site, whether or not that plant material is located within the 50-foot inclusionary perimeter as outlined above.
  - 4. <u>Tree Protection Plan</u>: The Certified Arborist shall prepare, and the Contractor shall implement, a Tree Protection Plan, for all trees that may be affected by any construction work, excavation or demolition activities, including without limitation, (1) on-site trees, (2) street trees, as defined below, (3) trees under NYCDPR jurisdiction as determined by the Department of Transportation, and (4) all trees that are located in proximity to the project site, as defined above. The Tree Protection Plan shall comply with the NYC DPR rules, regulations and specifications. The Contractor is referred to Chapter 5 of Title 56 of the Official Compilation of the Rules of the City of New York. Copies of the Tree Protection Plan shall be submitted to the Resident Engineer prior to the commencement of construction. Implementation of the Tree Protection Plan for street trees and trees under NYCDPR jurisdiction shall be in addition to any tree protection requirements specified or required for the project site. For the purpose of this article, a "street tree" means the following: (1) a tree that stands in a sidewalk, whether paved or unpaved, between the curb lines or lateral lines of a roadway and the adjacent property lines



of the project site, or (2) a tree that stands in a sidewalk and is located within 50 feet of the intersection of the project's site's property line with the street frontage property line.

C. <u>No Separate Payment</u>. No separate payment shall be made for compliance with Plant Pest Control Requirements or Tree Protection Requirements. The cost of compliance with Plant Pest Control Requirements and Tree Protection Requirements shall be deemed included in the Contractor's bid for the Project.

#### 3.16 PROJECT IDENTIFICATION SIGNAGE:

- A. The Contractor shall provide, install and maintain Project identification and other signs where indicated to inform public and individuals seeking entrance to the Project.
- B. In order to properly convey notice to persons entering upon a City construction site, the Contractor shall furnish and install a sign at the entrance (gates) as follows:

#### NO TRESPASSING

#### AUTHORIZED PERSONNEL ONLY

- C. If no construction fence exists at the site, this notice shall be conveyed by incorporating the above language into safety materials (barriers, tape, and signs).
- D. Provide temporary, directional signs for construction personnel and visitors.
- E. Maintain and touch up signs so that they are legible at all times.

#### 3.17 PROJECT CONSTRUCTION SIGN AND RENDERING:

#### A. PROJECT SIGN:

- 1 Responsibility: The Contractor shall produce and install one (1) project sign which shall be posted and maintained upon the site of the project at a place and in a position directed by the Commissioner. The Contractor shall protect the sign from damage during the continuance of work under the Contract and shall do all patching of lettering, painting and bracing thereof necessary to maintain the sign in first class condition and in proper position. Prior to fabrication, the Contractor shall submit an 8-1/2" x 11" color match print proof from the sign manufacturer of the completed sign for approval by the Commissioner.
- 2 Sign Quality: The Contractor shall provide all materials required for the production of the sign as specified herein. Workmanship shall be of the best quality, free from defects and shall be produced in a timely manner.
- 3 Schedule: Upon project mobilization, the Contractor shall commence production and installation of the sign.
- 4 Removal: At the completion of all work under the Contract, the Contractor shall remove and dispose of the project sign away from the site.
- 5 Sign construction:
  - a. Frame: The frame shall be from quality dressed 2"x2" pine, fire retardant, pressure treated lumber, that surrounds the inside back edge of the sign. The sign shall have one (1) intermediate vertical and two (2) diagonal supports, glued and screwed for rigidity. Frame shall be painted white with two (2) coats of exterior enamel paint, prior to mounting of sign panel.
  - b. Edging: U-shaped, 22 gauge aluminum edging, with a white enameled finish to match sign

TEMPORARY FACILITIES, SERVICES AND CONTROLS 01 50 00 -25

#### NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

background, shall run around entire edging of sign panel and frame. Corners shall be mitered for a tight fit. Channel dimensions shall be 1" inch (overlap to sign panel face) x 1 3/4" (or as required across frame depth) x 1" (back overlap).

- c. Sign Panel: 4' x 8' panel shall be constructed in one (1) piece of 14 gauge (.0785") 6061-T6 aluminum. This panel shall be pre-finished both sides with a glossy white baked-on enamel finish and be flush with edge of 2" x 2" wood frame. Samples must be submitted for approval.
- d. Fastening: Fasten sign panel to wood frame using cadmium plated no. 8 sheet metal screws at ½" below edge of panel and 8" on center. The U-shaped aluminum channel shall be applied over the wood frame edge and fastened with cadmium plated no. 8 sheet metal screws at 12" on center around the entire perimeter.
- 6 Sign Graphics:

- a. A digital file of the project sign will be provided to the Contractor by the Commissioner's representative for printing. The Commissioner's representative shall insert the project name and names and titles of personnel (3 or more) and any other required information associated with the project. All signs may include a second panel for a project rendering as described in Sub-Section 3.17.B herein.
- b. The digital file shall be reproduced at the Sign Panel size of 4' x 8' on 3M High Performance Vinyl or approved equal. The 3M High Performance Vinyl or equivalent shall be guaranteed for nine (9) years. Guarantee must cover fading, peeling, chipping or cracking. The sign manufacturer is required to maintain all specified Pantone Matching System (PMS) type and other composition elements represented in the digital file of the project sign.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SETION 3.17 B

- B. PROJECT RENDERING:
  - 1. Responsibility: In addition to the Project Sign, the Contractor shall furnish and install one (1) sign showing a rendering of the project. A digital file of the project rendering will be provided to the Contractor by the Commissioner's representative. From an approved image file provided by DDC, the Project Rendering is to be sized, printed, and mounted in an identical manner as described in Sub-Section 3.17.A above for the Project Sign. A color match print proof from the sign manufacturer of the Rendering Sign printed from the supplied file is to be submitted to DDC for approval before fabrication. The Rendering Sign is to be posted at the same height as the Project Sign. Where possible, the Rendering Sign shall be mounted with a perfect match of the short sides of the rectangle so that the Rendering Sign and the Project Sign together will create one long rectangle.
  - 2. Removal: At the completion of all work under the Contract, the Contractor shall remove and dispose of the project rendering away from the site.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.18

# 3.18 SECURITY GUARDS/FIRE GUARDS ON SITE:

- A. SECURITY GUARDS (WATCHMEN):
  - 1. The Contractor shall provide competent Security Guard Service on the site, beginning on the date on which the Contractor commences actual construction work, or on such earlier date on which there is activity at the site related to the work, including without limitation, delivery of

# NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

materials or construction set-up. The Contractor shall continue to provide such Security Guard Service until the date on which it completes all required work at the site, including all punch list work, as certified in writing by the Resident Engineer, or earlier if so directed in writing by the Commissioner. Throughout the specified time period, there shall be no less than one (1) Security Guard on duty every day, including Saturdays, Sunday and Holidays, 24 hours a day, except between the hours of 8:00 A.M. and 4:00 P.M. on any day which is a regular working day for a majority of the trade subcontractors. This exception during the working day shall not apply after the finishing painting of the plaster work is commenced; thereafter, not less than one (1) Security Guard shall be on duty continuously, 24 hours a day.

- Every Security Guard shall be required to hold a "Certificate of Fitness" issued by the Fire Department. Every Security Guard shall, during his/her tour of duty, perform the duties of Fire Guard in addition to his/her security obligations.
- 3. Should the Commissioner find that any Security Guard is unsatisfactory; such guard shall be replaced by the Contractor upon the written demand of the Commissioner.
- 4. Each Security Guard furnished by the Contractor shall be instructed by the Contractor to include in his/her duties the entire construction site including the Field Office, temporary structures, and equipment, materials, etc.
- 5. Should the Contractor or any other subcontractor consider the security requirements outlined above inadequate, the Contractor shall provide such additional security as it thinks necessary, after obtaining the written consent of the Commissioner. The additional cost of such approved increased protection will be paid by the Contractor.
- 6. Nothing contained in this Sub-Section shall diminish in any way the responsibility of the Contractor and each subcontractor for its own work, materials, tools, equipment, nor for any of the other risks and obligations outlined hereinbefore in this Article.
- B. COSTS The Contractor shall employ Security Guards/Fire Guards throughout the specified time period, except as otherwise modified by the detailed Specifications and as approved by the Commissioner, for the purpose of safeguarding and protecting the site. All costs for Security Guards/Fire Guards shall be borne by the Contractor.
- C. RESPONSIBILITY The Contractor and its subcontractors will be responsible for safeguarding and protecting their own work, materials, tools and equipment.

#### 3.19 SAFETY:

A. The Contractor, in compliance with requirements of Section 01 35 26, SAFETY REQUIREMENTS PROCEDURES, shall provide and maintain all necessary temporary closures, guard rails, and barricades to adequately protect all workers and the public from possible injury. Any removal of these items, during the progress of the work, shall be replaced by the Contractor at no additional cost to the City.

END OF SECTION 01 50 00



No Text

TEMPORARY FACILITIES, SERVICES AND CONTROLS 01 50 00 -28



# SECTION 01 54 11 TEMPORARY ELEVATORS AND HOISTS

#### PARTI- GENERAL

#### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

#### 1.2 SUMMARY:

- A. This section includes the following:
  - 1. Temporary Use, Operation and Maintenance of Elevators during Construction
    - a. For New Buildings up to 15 Stories
    - b. For New Buildings over 15 Stories
    - c. For Existing Buildings
  - 2. Temporary Construction Hoists and Hoist ways (For Material and Personnel)
- 1.3 RELATED SECTIONS: include without limitation the following:
  - A. Section 01 10 00 SUMMARY
  - B. Section 01 42 00 REFERENCES
  - C. Section 01 50 00 TEMPORARY FACILITIES AND CONTROLS
  - D. Section 01 54 23 TEMPORARY SCAFFOLDS AND SWING STAGING
  - E. Section 01 77 00 CLOSE OUT PROCEDURES

#### PART II - PRODUCTS (Not Used)

#### PART III - EXECUTION

REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.1

# 3.1 TEMPORARY USE, OPERATION AND MAINTENANCE OF ELEVATORS DURING CONSTRUCTION FOR NEW BUILDINGS UP TO AND INCLUDING 15 STORIES:

- A. INSTALLATION: The Contractor shall install, complete, operate, and maintain in good working order, as indicated herein, one (1) selected main elevator for the transport of employees of the Contractor and/or its subcontractors, and representatives of the DDC and other Governmental Agencies having jurisdiction of work at the project. The Contractor shall furnish, install, and maintain such elevator in good working order, including all necessary hoisting ropes, governor cables, traveling conductor cables, operating devices, temporary hand reset target annunciators, temporary signal devices, and all other permanent or temporary parts. The installation, operation and maintenance of the temporary elevator and all equipment and/or parts utilized in connection therewith shall be in accordance with the rules and regulations of all agencies and/or entities having jurisdiction over elevators in temporary use.
- B. RESPONSIBILITY: The Contractor shall be responsible for any injury to persons or damage to property arising out of the temporary elevator and all equipment and/or parts utilized in connection therewith.



- C. COSTS: The Contractor shall be responsible for all costs in connection with the temporary elevator, including without limitation: (1) installing and operating the temporary elevator, (2) maintaining the temporary elevator in clean, proper operating condition, including the cost of lubricants and/or parts for such maintenance, (3) performing all work in pits, shaft ways and machine rooms necessary for the operation of the temporary elevator, (4) replacing the temporary elevator or any equipment or parts utilized in connection therewith, if required, due to damage, destruction or excessive wear or corrosion, except for the replacement of hoisting ropes as set forth below, (5) performing all required electrical work in connection with the temporary elevator, (6) providing all electric power required to operate the temporary elevator, (7) providing all necessary conduit and wiring connections for the proper operation and signaling of the temporary elevator, and (8) providing all labor for the operation and maintenance of the temporary elevator, including on an overtime basis if necessary. The total Contract Price shall include all costs in connection with the temporary elevator, including without limitation, the costs specified herein.
- D. COMMENCEMENT OF SERVICE: The Contractor shall begin to provide temporary elevator service using the selected main passenger elevator no later than eight (8) weeks (40 working days) after the machine room roof slab, or that portion of it surrounding the elevator shaft, has been placed. No later than three (3) weeks (15 working days) after the machine room roof slab, or that portion of it surrounding the elevator shaft, has been placed the following work shall have been completed:
  - 1. The shaft shall have been completely enclosed by either the permanent or a temporary enclosure meeting the requirements of the law.
  - 2. The machine room shall have been made completely watertight either by permanent or temporary construction. Beams or other devices, either permanent or temporary shall be provided which will enable the safe and practicable hoisting of the elevator machinery for installation.
  - 3. There shall have been installed on all floors at the shaft way entrances to the elevator, solid substantial frames and either sliding or swing doors with substantial hardware and door locks and any necessary approved wire mesh barricades for adjacent shaft ways.
  - 4. There shall have been furnished and installed solid substantial enclosures at front, back, sides and top of car platform enclosure, with emergency exit at top of car, excepting that the portion of the front at the elevator entrance shall have been provided with a substantial temporary door or gate.
- E. ELECTRICAL INSTALLATION: The Contractor, not later than 20 calendar days after the machine room roof slab or that portion of its surrounding the elevator has been placed, shall have furnished and installed temporary or permanent power and light feeders as required for the elevator used for temporary service and shall have connected such feeders to the terminals on the starter panels or controllers in the machine room to the low voltage transformers and car light outlets in the center of shaft way and for the car control and signal traveling cables. The Contractor shall make all these required connections as soon as the equipment is declared ready for such connections by the Resident Engineer.
- F. REMOVAL: When elevators for permanent use have been installed and are in condition for service, and when directed by the Commissioner, the Contractor shall remove the temporary enclosures and all temporary elevator equipment and promptly proceed with the installation of the permanent equipment as required under the Contract.
- G. INSPECTION: Before temporary elevator equipment is removed, a joint inspection of the equipment shall be made by the Contractor and the Commissioner to determine the condition of this equipment upon the discontinuation of its temporary use. If this inspection deems it necessary, the Contractor shall furnish and install new governor and compensating ropes, new traveling cables and new controller parts, etc. The car and counterweight safeties shall be thoroughly cleaned of all dirt and all foreign matter, then properly lubricated and placed in good operating condition to the satisfaction of the Commissioner. If it is determined and ordered by the Commissioner that new hoist ropes are required, such ropes shall be installed and payment therefore will be made in accordance with Article 26 of the Contract.



- H. REPLACEMENT: The Contractor shall furnish and install new equipment or parts for any equipment or parts of the temporary elevator installation that have been damaged, destroyed, or that indicate excessive wear or corrosion, excepting the replacement of hoisting ropes. All shaft ways, pits, motor rooms and sheave spaces used for temporary operation of elevators shall be thoroughly cleaned. Where lubricated rails are used they shall be washed down. If roller guides are used, all rust, dirt, etc., must be moved from the rails. The full cost of parts replacement, cleaning, etc., shall be borne by the Contractor except for the replacement of hoisting ropes.
- I. LIMITATIONS ON USE: The temporary elevator shall not be used during its operation for the hoisting of materials or the removal of rubbish, but shall be limited only to the transportation of employees of the Contractor and/or its subcontractors, and representatives of DDC and other Governmental Agencies having jurisdiction of work at the project. However, the Resident Engineer may grant special permission at specified times to the Contractor and/or its subcontractors to hoist materials, which in the Resident Engineer's opinion will not overload or damage the elevator installation, but only after such times as all plastering has been completed from the second floor up. In the event of any damage to the temporary elevator, the Contractor shall notify the Resident Engineer within 24 hours after such damage has occurred. As indicated above, the Contractor shall be responsible for the replacement of any equipment or parts of the temporary elevator that have been damaged.
- J. LIQUIDATED DAMAGES: The Contractor will be charged at the rate of \$100 per day for each day it fails to provide the temporary elevator service described in this section beginning with the 41<sup>st</sup> working day after the machine room roof slab, or that portion of it surrounding the elevator shaft, has been placed and stripped. This charge will be deducted from any amount due and owing to the Contractor.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.2

# 3.2 TEMPORARY USE, OPERATION AND MAINTENANCE OF ELEVATORS DURING CONSTRUCTION FOR NEW BUILDING OVER 15 STORIES:

- A. INSTALLATION: The Contractor shall install, complete, operate, and maintain in good working order, as indicated herein, two (2) selected main elevators for the transport of employees of the Contractor and/or its subcontractors, and representatives of the DDC and other Governmental Agencies having jurisdiction of work at the project. The Contractor shall furnish, install, and maintain such elevators in good working order, including all necessary hoisting ropes, governor cables, traveling conductor cables, operating devices, temporary hand reset target annunciators, temporary signal devices, and all other permanent or temporary parts. The installation, operation and maintenance of the temporary elevators and all equipment and/or parts utilized in connection therewith shall be in accordance with the rules and regulations of all agencies and/or entities having jurisdiction over elevators in temporary use. The two (2) elevators shall not be operated simultaneously.
- B. RESPONSIBILITY: The Contractor shall be responsible for any injury to persons or damage to property arising out of the temporary elevators and all equipment and/or parts utilized in connection therewith.
- C. COSTS: The Contractor shall be responsible for all costs in connection with the temporary elevators, including without limitation: (1) installing and operating the temporary elevators, (2) maintaining the temporary elevators in clean, proper operating condition, including the cost of lubricants and/or parts for such maintenance, (3) performing all work in pits, shaft ways and machine rooms necessary for the operation of the temporary elevators, (4) replacing the temporary elevators or any equipment or parts utilized in connection therewith, if required due to damage, destruction or excessive wear or corrosion, except for the replacement of hoisting ropes as set forth below, (5) performing all required electrical work in connection with the temporary elevators, (6) providing all electric power required to operate the temporary elevators, (7) providing all necessary conduit and wiring connections for the proper operation and signaling of the temporary elevators, and (8) providing all labor for the operation and maintenance of the temporary elevators, including on an overtime basis if necessary. The total Contract Price shall








include all costs in connection with the temporary elevators, including without limitation, the costs specified herein.

- D. LOW RISE ELEVATOR: The Contractor shall begin to provide temporary elevator service using one (1) selected main passenger elevator no later than six (6) weeks (30 working days) after the 12th Floor slab, or that portion of it surrounding the elevator shaft, has been placed and stripped. No later than one (1) week, five (5) working days, after the 12th Floor slab, or that portion of it surrounding the elevator shaft, has been placed and stripped the following work shall have been completed:
  - 1. The shaft shall have been completely enclosed up to the 12th Floor by either the permanent or a temporary enclosure meeting the requirements of the law.
  - 2. A temporary machine room enclosure shall have been provided at the 11th Floor and shall have been made completely watertight either by permanent or temporary construction. Beams or other devices, either permanent or temporary, shall be provided which will enable the safe and practicable hoisting of the elevator machinery for installation.
  - 3. There shall have been installed on all floors up to and including the 9th Floor at the shaft entrances to the elevator, solid substantial wood frames and either sliding or swing doors with substantial hardware and door locks, also any necessary approved wire mesh barricades for adjacent shaft ways.
  - 4. There shall have been furnished and installed solid substantial enclosures at front, back, sides and top of car platform enclosure, with an emergency exit at top of car, excepting that the portion of the front at the elevator entrance shall have been provided with a substantial temporary door or gate.
- E. ELECTRICAL INSTALLATION: The Contractor not later than 10 calendar days after the 12th Floor slab or that portion of it surrounding the elevator, has been poured and stripped, shall have furnished and installed temporary or permanent power and light feeders as required for the elevator used for temporary service and shall have connected such feeders to the terminals on the starter panels or controllers in the temporary machine room, to the low voltage transformers and car light outlets in the center of the shaftway and for the car control and signal traveling cables. The Contractor shall make all these required connections as soon as the Equipment is declared ready for such connections by the Resident Engineer.
- F. HIGH RISE ELEVATOR: The Contractor shall begin to provide temporary elevator service to all floors, using a selected main passenger elevator, no later than eight (8) weeks (40 working days) after the machine room roof slab, or that portion of it surrounding the elevator shaft, has been placed. No later than three (3) weeks (15 working days) after the machine room roof slab, or that portion of it surrounding the elevator shaft, has been placed. No later the elevator shaft, has been placed, the following work shall have been completed:
  - 1. The shaft shall have been completely enclosed by either the permanent or temporary enclosure, meeting the requirements of the law.
  - 2. The machine room shall have been made completely watertight either by permanent or temporary construction. Beams or other devices, either permanent or temporary shall be provided which will enable the safe and practicable hoisting of the elevator machinery for installation.
  - 3. There shall have been installed on all floors at the shaft way entrances to the elevator, solid substantial frames and either sliding or swing doors with substantial hardware and door locks, also any necessary approved wire mesh barricades for adjacent shaft ways.
  - 4. There shall have been furnished and installed, solid substantial enclosures at front, back, sides and top of car platform enclosure, with an emergency exit at top of car, excepting that the portion of the front at the elevator entrance shall have been provided with a substantial temporary door or gate.
- G. ELECTRICAL INSTALLATION: The Contractor, not later than 20 calendar days after the machine room slab or that portion of it surrounding the elevator shaft has been placed, shall have furnished and installed temporary or permanent power and light feeders as required for the high rise elevator to be used for





H. When the high rise elevator is completed and ready for temporary operation, the low rise temporary elevator shall be shut down.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- I. REMOVAL: When one (1) or more elevators for permanent use have been installed and are in condition for service, and when directed by the Commissioner, the Contractor shall remove the temporary enclosures and all temporary elevator equipment, and promptly proceed with the installation of the permanent equipment as required under the Contract.
- J. INSPECTION: Before temporary elevator equipment is removed, a joint inspection of the equipment shall be made by the Contractor and the Commissioner to determine the condition of this equipment upon the discontinuation of its temporary use. If this inspection determines it necessary, the Contractor shall furnish and install new governor and compensating ropes, new traveling cables, new controller parts, etc. The car and counterweight safeties shall be thoroughly cleaned of all dirt and all foreign matter, then properly lubricated and placed in good operating condition to the satisfaction of the Commissioner. If it is determined and ordered by the Commissioner that new hoist ropes are required, such ropes shall be installed and payment therefore will be made in accordance with Article 26 of the Contract.
- K. REPLACEMENT: The Contractor shall furnish and install new equipment or parts for any equipment or parts of the temporary elevator installations that have been damaged, destroyed, or that indicate excessive wear or corrosion, excepting the replacement of hoisting ropes. All shaft ways, pits, motor rooms and sheaves spaces used for temporary operation of elevators shall be thoroughly cleaned down. Where lubricated rails are used they shall be washed down, if roller guides are used, all rust, dirt, etc., must be removed from the rails. The full cost of parts replacement cleaning, etc., shall be borne by the Contractor except for the replacement of hoisting ropes.
- L. LIMITATIONS ON USE: The temporary elevators shall not be used during their operation for the hoisting of materials or the removal of rubbish, but shall be limited only to the transportation of employees of the Contractor and/or its subcontractors, and representatives of DDC and other Governmental Agencies having jurisdiction of work at the project. However, the Resident Engineer may grant special permission at specified times to the Contractor and/or its subcontractors to hoist materials, which in the Resident Engineer's opinion will not overload or damage the elevator installation, but only after such times as all plastering has been completed from the second floor up. In the event of any damage to the temporary elevator, the Contractor shall notify the Resident Engineer within 24 hours after such damage has occurred. As indicated above, the Contractor shall be responsible for the replacement of any equipment or parts of the temporary elevator that have been damaged.
- M. LIQUIDATED DAMAGES: The Contractor will be charged at the rate of \$100 per day for each day it fails to provide the temporary elevator service described in this Section beginning with the 31st working day after the 12th Floor slab, or that portion of the 12th Floor slab surrounding the elevator shaft, has been placed and stripped. This charge will be deducted from any amount due and owing to the Contractor.

# **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.3**

# 3.3 TEMPORARY USE, OPERATION AND MAINTENANCE OF ELEVATORS DURING CONSTRUCTION FOR EXISTING BUILDINGS:

A. The Contractor may use, at the Commissioner's discretion, one (1) selected elevator in the building for temporary operation by the Contractor for the transportation of employees of the Contractor and/or its subcontractors, and representatives of DDC and other Governmental Agencies having jurisdiction over the work at the Project. The operation of the temporary elevator and all equipment and/or parts utilized in



connection therewith shall be in accordance with the rules and regulations of all agencies and/or entities having jurisdiction over elevators in temporary use.

- B. RESPONSIBILITY: The Contractor shall be responsible for any injury to persons or damage to property arising out of the temporary elevator and all equipment and/or parts utilized in connection therewith.
- C. REPLACEMENT: The Contractor shall furnish and install new equipment or parts for any equipment or parts of the elevator for temporary operation that have been damaged, destroyed, or that indicate excessive wear or corrosion, excepting the replacement of hoisting ropes. All shaft ways, pits, motor rooms and sheave spaces used for temporary operation of elevators shall be thoroughly cleaned down. Where lubricated rails are used they shall be washed down, if roller guides are used, all rust, dirt, etc., must be moved from the rails. The full cost of parts replacement, cleaning, etc., shall be borne by the Contractor except for the replacement of hoisting ropes. If it is determined and ordered by the Commissioner that new hoist ropes are required, such ropes shall be installed and payment therefore will be made in accordance with Article 26 of the Contract.
- D. LIMITATIONS ON USE: The temporary elevator shall not be used during its operation for the hoisting of materials or the removal of rubbish, but shall be limited only to the transportation of employees of the Contractor and/or its subcontractors, and representatives of DDC and other Governmental Agencies having jurisdiction of work at the project. However, the Resident Engineer may grant special permission at specified times to the Contractor and/or its subcontractors to hoist materials, which in the Resident Engineer's opinion will not overload or damage the elevator installation. In the event of any damage to the temporary elevator, the Contractor shall notify the Resident Engineer within 24 hours after such damage has occurred. As indicated above, the Contractor shall be responsible for the replacement of any equipment or parts of the temporary elevator that have been damaged.
- E. LIQUIDATED DAMAGES: The Contractor will be charged at the rate of \$100 per day for each day it fails to provide elevator services described in this section beginning with 15 consecutive calendar days from Notice to Proceed. This charge will be deducted from any amount due and owing to the Contractor.

# 3.4 TEMPORARY HOISTS AND HOISTWAYS (FOR MATERIAL AND PERSONNEL):

- A. RESPONSIBILITY: The Contractor shall provide adequate numbers of material hoists for the most expeditious performance of all parts of the work including the work of all its subcontractors.
- B. LOCATIONS: No hoists shall be constructed at such locations as will interfere with, or affect the construction of, floor arches, or the work of subcontractors. The hoists may be located at the exterior sides of the structure or in the courtyard and extend upward adjacent to the line of window openings. The hoists shall be located a sufficient distance from the exterior walls and be so protected as to prevent any of the permanent work from being damaged, stained or marred.
- C. ELEVATOR SHAFT: Wherever possible, one or more of the permanent elevator shafts may be used as temporary hoist ways, providing such use complies with the requirements of the Building Code of the City of New York and has been approved by the Commissioner, and providing further it entails no interference with the progress of the work.
- D. PROTECTION FOR INTERIOR HOISTS: All interior material hoist ways shall be enclosed on each floor and shall be adequately protected with appropriate safety guards. In no event shall the protection be less than that required by law.

#### END OF SECTION 01 54 11

DDD

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION



### SECTION 01 54 23 TEMPORARY SCAFFOLDING AND PLATFORMS

#### PARTI- GENERAL

#### 1.1 RELATED DOCUMENTS:

- A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].
- B. Section 01 35 26: Safety Requirements Procedures.
- C. The Contractor shall comply with the requirements of "The City of New York Department of Design and Construction Safety Requirements". This document is included in the Information for Bidders.

#### 1.2 SUMMARY:

- A. This Section includes administrative and general procedural requirements for Temporary Scaffolding and Platforms, including:
  - 1. Conformance
  - 2. Responsibility
  - 3. Jobsite Documentation and Submittals
  - 4. Inspections
- B. This Section governs ALL scaffold used on DDC project sites including, but not limited to, Suspended Scaffold, Supported Scaffold and Sidewalk Sheds.

#### 1.3 CONFORMANCE:

A. Unless otherwise indicated, the Contractor is responsible for providing, erecting, installing and maintaining all temporary scaffolding and platforms which shall comply with requirements of Chapter 33 (Safeguards During Construction or Demolition) of the NYC Building Code, NYC Local Law 52 of 2005, OSHA Construction Standard 1926 Subpart L, and furnishing the items and personnel set forth in this section.

#### 1.4 **RESPONSIBILITY**:

- A. Jobsite Safety Coordinator: The Contractor shall designate and employ a Jobsite Safety Coordinator, who shall be a competent person, who shall have a daily presence on the project site during scaffold use. This designee must possess and maintain a valid New York City Department of Buildings supported scaffold certificate of completion. An alternate shall also be designated, in the event that the Jobsite Safety Coordinator is absent. The Jobsite Safety Coordinator shall:
  - 1. Verify completeness of documentation and submittals (as described below).
  - 2. Verify that inspections are performed, including pull tests (see below), reports are filed and reported deficiencies are corrected.
  - 3. Monitor trades using scaffold.
  - 4. Limit access to scaffold areas that are tagged for non-use.
  - 5. Inform trades of scaffold load limitations.
  - 6. Monitor loading of decks.
  - 7. Verify that any ties that are temporarily removed are properly restored in the same shift.
  - 8. Verify that outriggers and planks that are moved are properly set up and secured.
  - 9. Verify that all scaffold decks in use have proper access/egress.
  - 10. Verify that all open sides of decks in excess of 14 inches have proper guardrails and toe-boards.

TEMPORARY SCAFFOLDING AND PLATFORMS 01 54 23 - 1



- 11. Notify appropriate parties, including but not limited to the Resident Engineer, site safety coordinator / monitor, site safety consultant, scaffold users, contractor and the scaffold engineer, of misuses, non-conformances, hazards and accidents.
- 12. Keep a log of significant actions and events connected with the scaffolding.
- B. The Contractor shall be responsible for erecting, maintaining and dismantling the scaffolding and/or sidewalk shed in conformance with requirements of the New York City Building Code, OSHA and the Contract documents, including the specifications. The Contractor shall also be guided by generally accepted standards of scaffold industry practice as promulgated by the Scaffold Industry Association.
- C. The Contractor shall require the subcontractor responsible for erecting the scaffolding to engage a Scaffold Engineer, licensed as a professional engineer by the State of New York. The Scaffold Engineer shall be responsible to ensure the following: (1) that the installation design is in compliance with requirements of the New York City Building Code and OSHA, (2) that the design comports with the capabilities of the components and the characteristics of the site, (3) that scaffold loads on the host building, including netting, have been properly considered, and (4) that the design documents provide accurate information for erectors and users.
- D. Scaffold users are trade contractors assigned to work on the scaffold. Training certificates from a New York City Department of Buildings approved training provider are mandatory. These users have the duty to become familiar with the New York City Building Code and OSHA requirements germane to users, to obey the instructions of the Jobsite Safety Coordinator and to inform the Jobsite Safety Coordinator of known hazards, non-conformances or violations.

### 1.5 JOBSITE DOCUMENTATION AND SUBMITTALS:

The Contractor shall prepare, obtain and submit the following to the Resident Engineer:

- A. NYC Department of Buildings permit(s) for scaffold and sidewalk sheds (as applicable) including filing applications signed and sealed by a Professional Engineer licensed in the State of New York;
- B. Site logistics plan / site safety plan;
- C. Installation drawing(s), design and product data to be provided for <u>all</u> scaffold(s) and shed(s) must include, at a minimum:
  - 1. Plan(s);
  - 2. Elevation(s);
  - 3. Duty load designation; "standard" (150 psf live load) or "heavy duty" (300 psf live load).
  - 4. Details including base support, anchors and ties;
  - 5. Notes and specifications including load limits, number of planked levels, tie spacing, netting, and sequence of installation and removal.
  - 6. Anchorage into sound material.
  - 7. Load limits based on pull tests;
  - 8. Specifications for pull test(s), method, proof load and the number of trials;
  - 9. Elevations, levels or heights, where anchorage is made into masonry;
  - 10. Specifications for frames, planks, screw jacks, anchors, and any other ancillary hardware;
  - 11. Samples for anchors, ties and netting;
  - 12. Sequence of operations for erection and demolition;
  - 13. Location plan, heights, widths, "jumps" over doorways and driveways;
  - 14. Specify size, maximum span and maximum spacing of headers and stringers;
  - 15. Specify legs, girts, braces, nailing and connections;
  - 16. All sidewalk sheds shall be designed, engineered, signed and sealed by a Professional Engineer licensed in the State of New York;
    - a. Generic (not job specific) engineering drawings are satisfactory for standard sheds and arrangements.





b. Special engineering is required for custom sheds, site-specific problems or non-standard arrangements.

#### 1.6 INSPECTIONS:

- A. Signed inspection reports shall be issued for each inspection and pull-test below, and shall be logged and maintained on site by the Jobsite Safety Coordinator for the duration of the project.
- B. Pull testing shall be required during design, and during or post erection, where anchorage is made into masonry. The Scaffold Engineer shall specify the test method, proof load and the number of trials.
- C. Sidewalk sheds shall be inspected after initial installation, major modification, or damage and thence every three months. Inspections shall be by a Scaffold Engineer for custom sheds and by a Competent Person employed by the Contractor for standard sheds.
- D. Scaffolds shall be inspected by the Scaffold Engineer during erection, post-erection and prior to use and thence every three months. The Scaffold Engineer shall repeat inspections after major alteration/modification, damage.
- E. A Qualified Person assigned by the Contractor shall inspect the progress of erection and dismantling, and the condition and integrity of the sidewalk sheds after high winds, major storms and at least once per month during usage.
- F. A Qualified Person assigned by the Contractor shall inspect the progress of erection and dismantling at least weekly, and the condition and integrity of the scaffold after high winds, major storms and at least once per month during usage.
- G. Scaffolds and Sidewalk Sheds shall be inspected daily by the Jobsite Safety Coordinator or alternate prior to use by scaffold users. The inspection results must be recorded in the maintenance log, and be available on-site at all times.
- H. At the completion of the project, submit all inspection documents as Miscellaneous Record Documents in accordance with Section 01 78 39, CONTRACT RECORD DOCUMENTS.

#### 1.7 LADDERS AND STAIRS:

A. The Contractor shall provide and maintain ladders or temporary stairs extending from the street to the first story, and to and from every floor and roof level of the project.

#### 1.8 ACCESS AND EXITS:

A. The ladders or temporary stairs shall be of acceptable size, number and location, so that proper and convenient access may be had by those required to proceed to and from all parts of the project.

PART II - PRODUCTS (Not Used)

PART III - EXECUTION (Not Used)

END OF SECTION 01 54 23

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION Division 01 – DDC STANDARD GENERAL CONDITION SINGLE CONTRACT PROJECTS Issue Date - June 01, 2013

No Text



### SECTION 01 73 00 EXECUTION

#### PARTI- GENERAL

#### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

#### 1.2 SUMMARY:

- A. This Section includes general procedural requirements governing execution of the Work including without limitation the following:
  - 1. Delivery of Materials
  - 2. Contractor's Superintendent
  - 3. Surveys
  - 4. Borings
  - 5. Examination
  - 6. Environmental Assessment
  - 7. Preparation
  - 8. Deferred Construction
  - 9. Installation
  - 10. Permits
  - 11. Transportation
  - 12. Sleeves and Hangers
  - 13. Sleeve and Hanger Drawings
  - 14. Cutting and Patching
  - 15. Location of Partitions
  - 16. Furniture and Equipment
  - 17. Removal of Rubbish and Surplus Material
  - 18. Cleaning
  - 19. Security And Protection of Work Site
  - 20. Maintenance of Site and Adjoining Property
  - 21. Maintenance of Project Site
  - 22. Safety Precautions for Control Circuits
  - 23. Obstructions in Drainage Lines
- 1.3 **RELATED SECTIONS:** Include without limitation the following:
  - A. Section 01 10 00 SUMMARY
  - B. Section 01 31 00 PROJECT MANAGEMENT AND COORDINATION
  - C. Section 01 33 00 SUBMITTAL PROCEDURES
  - D. Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT & DISPOSAL
  - E. Section 01 77 00 CLOSEOUT PROCEDURES
  - F. Section 01 78 39 CONTRACT RECORD DOCUMENTS

EXECUTION 01 73 00 - 1



#### 1.4 **DEFINITIONS:**

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.

### 1.5 QUALITY ASSURANCE:

A. Land Surveyor Qualifications: A professional land surveyor who is licensed in the State of New York and who is experienced in providing land-surveying services of the kind indicated.

#### PART II – PRODUCTS (Not Used)

#### PART III - EXECUTION

#### 3.1 DELIVERY OF MATERIALS:

- A. Material Orders: The Contractor shall furnish to the Commissioner a copy of each material order, indicating date of order and quantity of material, and shall also notify the Commissioner when materials have been delivered to the site and in what quantities.
- B. Ample Quantities: The Contractor shall deliver materials in ample quantities to insure the most prompt and uninterrupted progress of the work so as to complete the work within the Contract time.
- C. Containers: The manufacturer's containers shall be delivered with unbroken seals and shall bear proper labels.
- D. Deliveries: The Contractor shall coordinate deliveries in order to avoid delaying or impeding the progress of the work.
- E. Handling: The Contractor shall provide equipment and personnel to handle products by methods to prevent soiling or damage.
  - 1. Promptly inspect shipments to assure products comply with requirements, quantities are correct, and products are undamaged.
  - 2. Promptly return damaged shipments or incorrect orders to manufacturer.
  - 3. For materials or equipment to be reused or salvaged, use special care in removal, storage and reinstallation to insure proper function in completed work.
- F. Storage: Store products in accordance with provisions of Article 3.1, and periodically inspect to assure that stored products are undamaged and are maintained under required conditions.
- G. Stacking: All materials shall be properly stacked in convenient places adjacent to the site, or where directed, and protected in a satisfactory manner. Stacked materials shall be so arranged as to not interfere with visibility of traffic control devices.
- H. Overloading: If authority is given to store materials in any part of the project area, they shall be so stored as to cause no overloading.



I. No Interference: If it becomes necessary to remove and restack materials to avoid impeding the progress of any part of the work or interfering with the work to be done by any trade subcontractor, the Contractor shall remove and restack such materials at no additional cost to the City.

# 3.2 CONTRACTOR'S CONSTRUCTION SUPERINTENDENT:

- A. Contractor's Construction Superintendent: The Contractor shall devote its time and personal attention to the work and shall employ and retain at the project site, from the commencement until the entire completion of the work, a Contractor's Construction Superintendent. The Contractor's Construction Superintendent shall be registered with the New York City Department of Buildings in compliance with the Construction Superintendent Rule of the City of New York and shall be competent and capable of maintaining proper supervision and care of the work and shall be acceptable to the Commissioner. The Construction Superintendent shall, in the absence of the Contractor, and irrespective of any superintendent or foreman employed by any subcontractor, shall see that the instructions of the Commissioner are carried out.
- B. Replacement: The Contractor's Construction Superintendent on the job shall not be changed or removed without the consent of the Commissioner.

#### **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.3**

#### 3.3 SURVEYS:

- A. Line and Grade: The City will establish a baseline and bench mark near the site of the work for use of the Contractor in connection with the performance of the work.
- B. Responsibility: The Contractor shall establish all other lines and elevations required for its work and shall be solely responsible for the accuracy thereof.
- C. Safeguard All Points: The Contractor shall safeguard all points, stakes, grade marks and bench marks made or established by the Contractor on the work, shall re-establish same if disturbed and bear the entire expense of rectifying the work improperly installed due to not maintaining, not protecting or removing without authorization such established points, stakes, or marks.
- D. City Monuments and Markers: No work shall be performed near City monuments or marks so as to disturb them until the said monuments or marks have been referenced or reset or otherwise disposed of by the relevant Agency or party who installed them.
- E. Foundations: The Contractor shall furnish certification from a licensed Surveyor that all portions of the foundation work are located in accordance with the Contract Drawings and at the elevations required thereby. This certification shall show the actual locations and the actual elevations of all the work in relation to the locations and elevations shown on the Contract Drawings, including but not restricted to the following:
  - 1. The locations and elevations of all piles, if any.
  - 2. Elevations of tops of all spread footings, tops of pile caps, and tops of all foundation walls, elevator pit walls and ramp walls.
  - 3. Location of all footing centers and pier centers including those for exterior wall columns.
  - 4. Location of all foundation walls including wall columns, elevator pit walls and ramp walls.
- F. Wall Lines: After the first courses of masonry or stone have been laid, the Contractor shall establish the permanent lines of exterior walls. The Contractor shall furnish promptly, certification from a licensed Surveyor, in the form of signed original drawings showing the exact location of such wall lines, of all portions of all structures. Except at its own risk, the Contractor shall not proceed further with the erection of walls until the Surveyor's certification has been submitted and verified for correct location of wall lines.



- G. Surveyor: The Surveyor selected for any of the purposes mentioned in Paragraph E and Paragraph F above, and Paragraph I below, shall be a land Surveyor licensed in the State of New York and shall be subject to the approval of the Commissioner. The Surveyor shall not be a regular employee of the Contractor, nor shall the Surveyor have any interest in the Contract. The Surveyor shall not be employed by the Contractor in laying out any work, it being intended that the Surveyor's certification shall represent an independent and disinterested verification of such layout. The Surveyor shall report to the Department of Design and Construction's Resident Engineer each time upon arrival to and departure from the site and review with the Resident Engineer the data required for the project.
- H. Final Certification: Final certification shall be submitted upon completion of the work or upon completion of any subdivision of the work as directed by the Commissioner. Any exceptions or deviations from the drawings shall be noted on the final certificate and there shall be included any maps, plates, notes, pertinent documents and data necessary, in the opinion of the Commissioner, to constitute a full and complete report.
- I. Final Survey: The Contractor shall submit to DDC for submission to the Department of Buildings a final Survey by the licensed Surveyor showing the location of the new Structure, before completion of the Structure. This Survey shall show the location of the first tier of beams or of the first floor; the finish grades of the open spaces on the plot; the established curb level and the location of all other Structures on the plan, together with the location and boundaries of the lot or plot upon which the Structure is constructed, curb cuts, all yard dimensions, etc.



# **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.4**

#### 3.4 BORINGS:

- A. The work of this Sub-Section shall be the responsibility of the Contractor unless otherwise indicated.
- B. Reference Drawings: The Boring Drawings as listed on the title sheet are for information to the bidder and are to be used under the conditions as follows:
  - 1. Boring Logs: shown on the Boring Drawings, record information obtained under engineering supervision in the course of exploration carried out by or under the direction of forces of the Department of Design and Construction at the site.
  - 2. Soils and Rock Samples: All inferences are drawn from the indications observed as made by engineering and scientific personnel. All such inferences and all records of the work including soil samples and rock cores, if any, are available to bidders for inspection.
  - 3. Certification of Samples: The City certifies that the work was carried out as stated, and that the soil samples and rock cores, if any were referred to, were actually taken from the site at the times, places and in the manner indicated. The samples are available for inspection in the Department of Design and Construction Subsurface Exploration Section.
  - 4. Bidder's Responsibility: The bidder, however, is responsible for any conclusions to be drawn from the work. If the bidder accepts those of the City, it must do so at its own risk. If the bidder prefers not to assume such risk, the bidder is under the obligation of employing its own experts to analyze the available information, and must be responsible for any consequences of acting on their conclusions.
  - 5. Continuity Not Guarantee: The City does not guarantee continuity of conditions shown at actual boring locations over the entire site. Where possible, borings are located to avoid all obstructions and previous construction which can be found by inspection of the surface and the bidder is required to estimate the influence of such features from its own inspection of the site.





#### 3.5 EXAMINATION:

- A. Existing Conditions: The existence and location of site improvements, utilities, and other construction indicated as existing are not guaranteed. Before beginning work, investigate and verify the existence and location of mechanical and electrical systems and other construction affecting the Work.
  - 1. Before construction, verify the location and points of connection of utility services.
- B. Existing Utilities: The existence and location of underground utilities and other construction indicated as existing are not guaranteed. Before beginning site work, investigate and verify the existence and location of underground utilities and other construction affecting the Work.
  - 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; and underground electrical services.
  - 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- C. Acceptance of Conditions: Examine substrates, areas, and conditions, with the subcontractor responsible for installation or application present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
  - 1. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
  - 2. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
  - 3. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
  - Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

#### 3.6 ENVIRONMENTAL ASSESSMENTS:

- A. City Responsibilities: An Environmental Assessment and survey is performed by the NYC DDC and its findings are included in the Contract Documents. In accordance with the NYC Administrative Code Title 15 Chapter 1 an asbestos survey is required to be performed by an Asbestos Investigator certified by the NYC Department of Environmental Protection (DEP) to identify the presence of asbestos containing material (ACM) prior to any alteration, renovation or demoliition activity. The findings of such survey are required for the submission of approvals and permits issued by the NYC Department of Buildings (DOB). When the findings indicate that asbestos containing material is present and will be disturbed during the alteration, renovation or demolition activity then abatement design specifications will be incorporated into the contract documents. The Contractor shall comply with all federal, state and local asbestos regulations affecting the work for this Contract.
- B. Contractor Responsibility: The Contractor shall comply with all federal, state and local environmental regulations, including without limitation USEPA and OSHA regulations which require the Contractor to assess if lead based paint will be disturbed during the work in order to protect his/her workers and the building occupants from migration of lead dust into the air. The Contractor shall comply with all federal, state and local environmental waste disposal regulation which may be required during the work. The Contractor is required to hire licensed abatement and disposal companies for the requisite work.

#### 3.7 PREPARATION:

- A. Field Measurements: The Contractor shall verify all dimensions and conditions on the job so that all work will properly join the existing work.
- B. The Contractor, before commencing work, shall examine all adjoining work on which its work is in any way dependent on good workmanship in accordance to the intent of the Specifications and the Contract

Drawings. The Contractor shall report to the Commissioner any condition that will prevent it from performing work that conforms to the required standard.

- C. Existing Utility Information: Furnish information to the Commissioner that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.
- D. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.

### 3.8 DEFERRED CONSTRUCTION:

- A. Where necessity for deferred construction is certified by the Commissioner, in order to permit the installation of any item or items of equipment required to be furnished and installed concurrent with the time allowed for doing and completing the work of the Contract, the Contractor shall defer construction work limited to adequate areas as approved by the Commissioner.
- B. The Contractor shall confer with the affected trade subcontractors and ascertain arrangements, time and facilities necessary to be made by the Contractor in order to execute the provisions specified herein.

#### 3.9 INSTALLATION:


◗◗◗◗

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
  - 1. Make vertical work plumb and make horizontal work level.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
- 3. Conceal pipes, ducts, and wiring in finished areas, unless otherwise indicated.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- F. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work and work of trade subcontractors to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- G. Anchors and Fasteners: Provide anchors and fasteners as required to anchor each component securely in place, accurately located and aligned with other portions of the Work.
  - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by the Design Consultant.
  - 2. Allow for building movement, including thermal expansion and contraction.
  - 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.





I. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

#### 3.10 PERMITS:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

A. The Contractor shall comply with all local, state and federal laws, rules and regulations affecting the Work of this Project, including, without limitation, (1) obtaining all necessary permits for the performance of the Work prior to commencement thereof, and (2) complying with all requirements for the disposal of demolition and/or construction debris, waste, etc., including disposal in City landfills. The Contractor shall be responsible for all costs in connection with such regulatory compliance, unless otherwise specified in the Contract.

#### 3.11 TRANSPORTATION:

- A. Availability: It shall be the duty of the Contractor to determine the availability of transportation facilities and dockage for the use of its employees, equipment and material and the conditions under which such use will be permitted.
- B. Costs: If transportation facilities and dockage are available and are permitted to be used by the governmental agency having jurisdiction, the Contractor shall pay all necessary costs and expenses, and abide by all rules and regulations promulgated in connection therewith.
- C. Vehicles: With respect to the use of vehicles on highways and bridges, the Contractor's attention is directed to the limitations set forth in the Rules of the City of New York, Title 34, Chapter 4, Section 4-15.
- D. Continued Use: It is understood that the Commissioner makes no warranty as to the continued use by the Contractor of such facilities.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.12

#### 3.12 SLEEVES AND HANGERS:

- A. Coordinate with Progress Schedule: The Contractor shall promptly furnish and install conduits, outlets, piping sleeves, boxes, inserts and all other materials and equipment that is to be built into the work in conformity with the requirements of the project.
- B. Cooperation of Subcontractors: All subcontractors shall fully cooperate with each other in connection with the performance of the above work as "cutting in" new work is neither contemplated nor will it be tolerated.
- C. Timeliness: In the event that timely delivery of sleeves and other materials cannot be made, and to avoid delay, the Contractor may arrange to have boxes or other forms set at the locations where the piping or other material is to pass through or into the slabs, walls or other work. Upon the subsequent installation of the sleeves or other material, the Contractor shall fill around them with materials as required by the Contract. The necessary expenditures incurred for the boxing out and filling in shall be borne by the Contractor.
- D. Inserts: The Contractor is to install strip inserts four (4) feet on center and perpendicular to beams in ceiling slabs of boiler, machine and mechanical equipment rooms. Inserts are to be installed for strippable concrete slabs only.





### **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.13**

# 3.13 SLEEVE AND PENETRATION DRAWINGS:

A. As soon as practicable after the commencement of work and when the order in which concrete for the first slabs, walls, etc. to be poured is determined, the Contractor shall submit to the Resident Engineer a sketch indicating the location and size of all penetrations for sleeves, ducts, etc. which will be required to accommodate the mechanical trades, in order to determine if such penetrations will materially weaken the project's structure. The sketch shall be stamped and returned if approved and/or comments will be transmitted. The Contractor shall continue to submit sketches as the pouring schedule and the concrete work progresses and, until approvals for the penetration sketches have been given. The Contractor shall not predicate its layout work on unapproved sketches.

# 3.14 CUTTING AND PATCHING:

- A. Responsibility: The Contractor shall do all cutting, patching and restoration required by its work, unless otherwise particularly specified in the Specifications.
- B. Restore Work: The Contractor shall restore any work damaged during the performance of the work.
- C. Competent Workers: All restoration work shall be done to the satisfaction of the Commissioner by competent workers skilled in the trade required by such restoration. If, in the judgment of the Commissioner, workers engaged in restoration work are incompetent, they shall be replaced immediately by competent workers.
- D. Structural Elements: Do not cut and patch structural elements without the prior approval, in writing, of the Resident Engineer.
- E. Operational Elements: Do not cut and patch operating elements and related components.
- F. Visual Requirements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch construction exposed on the exterior or in occupied spaces in a manner that would, in Commissioner's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- G. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during cutting and patching operations, by methods and with materials so as not to void existing warranties.
- H. Removals: The Contractor must remove from the premises all demolished materials of every nature or description resulting from cutting, patching and restoration work, in accordance with the requirements hereinafter stipulated under Sub-Section 3.17 herein and as further required in Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL.

# **REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 3.15**

#### 3.15 LOCATION OF PARTITIONS:

A. Within three (3) weeks after the concrete slabs have been poured on each floor level, the Contractor shall immediately locate accurately all of the partitions, including the door openings, on the floor slabs in a manner approved by the Resident Engineer.



#### 3.16 FURNITURE AND EQUIPMENT:

- A. Responsibility: The Contractor is responsible for moving all loose furniture and/or equipment in all areas where the location of such furniture and/or equipment interferes with the proper performance of its work.
- B. Protection: All such furniture and/or equipment must be adequately protected with dust cloths and returned to their original locations when directed to do so by the Resident Engineer.

#### 3.17 REMOVAL OF RUBBISH AND SURPLUS MATERIALS:

- A. Of the waste that is generated during demolition, as many of the waste materials as economically feasible, and as stated here, shall be reused, salvaged, or recycled. Waste disposal in landfills shall be minimized. Comply with requirements of Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL.
- B. Rubbish: Rubbish shall not be thrown from the windows or other parts of the project. Mason's rubbish, dirt and other dust-producing material shall be wetted down periodically.
- C. Location: The Contractor shall clean Project site and work area daily and sweep up and deposit, at a location designated on each floor, all of its rubbish, debris and waste materials, as it accumulates and when directed by the Resident Engineer. Wood crating shall be broken up, neatly bundled, tied and stacked ready for removal and be deposited at a location designated on each floor.
  - 1. Comply with requirements in NYC Fire Department for removal of combustible waste materials and debris.
  - 2. Do not hold materials more than 7 days during normal weather or 3 days if the temperature is expected to rise above 80 degrees F (27 degrees C).
  - 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
- D. Laborers: The Contractor shall be responsible for the removal of all rubbish, etc., from the site. The Contractor shall remove from the designated locations all piles of rubbish, debris, waste material and wood crating as they accumulate and when directed by the Resident Engineer, and shall remove them from the site. The Contractor shall employ and keep engaged for this purpose an adequate number of laborers.
- E. Surplus Materials: The Contractor shall remove from the site all surplus materials when there is no further use for same.
- F. Tools And Materials: At the conclusion of the work, all erection plant, tools, temporary structures and materials belonging to the Contractor shall be promptly removed.
- G. Waste Disposal: Burying or burning waste materials on-site will not be permitted. Washing waste materials down sewers or into waterways will not be permitted.

### 3.18 CLEANING:

- A. The Contractor shall thoroughly clean all equipment and materials furnished and installed and shall deliver such materials and equipment undamaged in a clean and new appearing condition up to date of Final Acceptance.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- D. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.



- E. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration up to date of Final Acceptance.
- F. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration up to date of Final Acceptance.

# 3.19 SECURITY AND PROTECTION OF WORK SITE:

- A. Provide protection of installed work, including appropriate protective coverings and maintain conditions that ensure installed Work is without damage or deterioration up to date of Final Acceptance.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.
- C. Secure and protect work and work site against damage, loss, injury, theft and/or vandalism.
- D. Maintain daily sign-in sheets of workers and visitors and make the sheets available to the Commissioner

# 3.20 MAINTENANCE OF SITE AND ADJOINING PROPERTY:

- A. The Contractor shall take over and maintain the Project site, after order to start work.
- B. The Contractor shall be responsible for the safety of the adjoining property, including sidewalks, paving, fences, sewers, water, gas, electric and other mains, pipes and conduits etc. until the date of Final Acceptance. The Contractor shall, at its own expense, except as otherwise specified, protect same and maintain them in at least as good a condition as that in which the Contractor finds them.
- C. All pavements, sidewalks, roads and approaches to fire hydrants shall be kept clear at all times, maintained and repaired to serviceable condition with materials to match existing.
- D. Provide and keep in good repair all bridging and decking necessary to maintain vehicular and pedestrian traffic.
- E. The Contractor shall also remove all snow and ice as it accumulates on the sidewalks within the Contract Limits Lines.

#### 3.21 MAINTENANCE OF PROJECT SITE:

- A. The Contractor shall take over and maintain all project areas, after order to start work.
- B. Until the date of Final Acceptance, the Contractor shall be responsible for the safety of all project areas, including water, gas, electric and other mains and pipes and conduits and shall at the Contractor's own expense, except as otherwise specified, protect same and maintain them in at least as good condition as that in which the Contractor finds them.
- C. All pavements, sidewalks, roads and approaches to fire hydrants shall be kept clear at all times, maintained, and if damaged, repaired to serviceable conditions with materials to match existing.
- D. The Contractor shall keep the space for the Resident Engineer in a clean condition.

# 3.22 SAFETY PRECAUTIONS FOR CONTROL CIRCUITS:

A. Control circuits, the failure of which will cause a hazard to life and property, shall comply with the New York City 2011 Electrical Code requirements.

# 3.23 OBSTRUCTIONS IN DRAINAGE LINES:

A. The Contractor shall be responsible for all obstructions occurring in all drainage lines, fittings and fixtures after the installations and cleaning of these drainage lines, fittings and fixtures as certified by the Resident Engineer. Roof drains shall be kept clear of any and all debris. Any stoppage shall be repaired immediately at the expense of the Contractor.



END OF SECTION 01 73 00





# SECTION 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

### PART I - GENERAL

### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

### 1.2 SUMMARY:

- A. This section includes administrative and procedural requirements for the management and disposal of construction waste and includes the following requirements:
  - 1. Waste Management Goals
  - 2. Waste Management Plan
  - 3. Progress Reports
  - 4. Progress Meetings
  - 5. Management Plan Implementation
- B. This Section includes:
  - 1. Definitions
  - 2. Waste Management Performance Requirements
  - 3. Reference Resources
  - 4. Submittals
  - 5. Quality Assurance
  - 6. Waste Plan Implementation
  - 7. Additional Demolition and Salvage Requirements
  - 8. Disposal
- **1.3 RELATED SECTIONS:** Include without limitation the following:
  - A. Section 01 10 00 SUMMARY
  - B. Section 01 31 00 PROJECT MANAGEMENT AND COORDINATION
  - C. Section 01 32 00 CONSTRUCTION PROGRESS DOCUMENTATION
  - D: Section 01 73 00 EXECUTION
  - E. Section 01 77 00 CLOSEOUT PROCEDURES
  - F. Section 01 78 39 CONSTRUCTION RECORD DOCUMENTS
  - G Section 01 81 13 SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS

### 1.4 **DEFINITIONS**:

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.
- C. Clean: Untreated and unpainted; not contaminated with oils, solvents, caulk or the like.

CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL 01 74 19 - 1



- D. Construction and Demolition Waste: Solid wastes typically including building materials, trash debris and rubble resulting from remodeling, repair and demolition operations. Hazardous materials and land clearing waste are not included.
- E. Diversion from Landfill: To remove, or have removed, from the site for recycling, reuse or salvage, material that might otherwise be sent to a landfill.
- F. Recyclable: The ability of a product or material to be recovered at the end of its life cycle and remanufactured into a new product.
- G. Recycle (recycling): To sort, separate, process, treat or reconstitute solid waste and other discarded materials for the purpose of redirecting such materials into the manufacture of useful products. Recycling does not include burning, incinerating or thermally destroying waste.
- H. Return: To give back reusable items or unused products to vendors.
- I. Reuse: To reuse excess or discarded construction material in some manner on the Project site.
- J. Salvage: To remove a waste material from the Project site for resale or reuse.
- K. Waste: Extra material or material that has reached the end of its useful life in its intended use. Waste includes salvageable, returnable, recyclable and reusable material.
- L. Waste Management Plan: A project-related plan for the collection, transportation and disposal of waste generated at the construction site. The purpose of the plan is to ultimately reduce the amount of material becoming landfill.

# 1.5 WASTE MANAGEMENT PERFORMANCE REQUIREMENTS:

- A. The City of New York has established that this project shall generate the least amount of waste possible and that processes that ensure the generation of as little waste as possible due to error, inaccurate planning, breakage, mishandling, contamination, or other factors shall be employed.
- B. Of the waste that is generated during demolition, as many of the waste materials as economically feasible, and as stated here, shall be reused, salvaged, or recycled. Waste disposal in landfills shall be minimized.

# REFER TO THE ADDENDUM FOR THE APPLICABILITY OF SUB-SECTION 1.5 C

- C. LEED CERTIFICATION: The City of New York will seek LEED (Leadership in Energy and Environmental Design) certification for this Project as indicated in the Addendum to the General Conditions from the U.S. Green Building Council. The documentation required here will be used for this purpose. LEED awards points for a variety of sustainable design measures on a project, one of which is the reuse and recycling of project waste.
- D. DIVERSION REQUIREMENTS. A minimum of 75% of total Project demolition waste (by weight) shall be diverted from landfill. The following waste categories are likely candidates to be included in the diversion plan as applicable for this project:
  - 1. Concrete
  - 2. Bricks
  - 3. Concrete masonry units (CMU)
  - 4. Asphalt
  - 5. Metals (e.g. banding, stud trim, ceiling grid, ductwork, piping, rebar, roofing, other trim, steel, iron, galvanized, stainless steel, aluminum, copper, zinc, brass, bronze)





- 6. Clean dimensional wood
- Carpet and pad
- 8. Drywall
- 9. Ceiling tiles
- 10. Cardboard, paper, and packaging
- 11. Reuse items indicated on the Drawings and/or elsewhere in the Specification
- E. All fluorescent lamps, HID lamps and mercury-containing thermostats removed from the site shall be recycled.
- F. Recycling on the job, subject to the Commissioner's approval, is encouraged on the site itself, such as the crushing and reuse of removed sound concrete and stone. Include these categories in the Waste Management Plan.

### 1.6 REFERENCES, RESOURCES:

- A. DDC encourages its contractors to seek information from websites and experts in salvage or recycling in order to minimize disposal costs. There are numerous opportunities to sell, salvage, or to donate materials and accrue tax benefits (which would accrue to the contractor); also there are outlets that will pick up, and in some cases buy recyclable materials. Examples of information resources are as follows:
  - 1. DDC's Sustainable Design web site:

http://www.nyc.gov/html/ddc/html/design/sustainable home.shtml This includes a manual on Construction and Demolition Waste Reduction and Recycling, a Sample Waste Management Plan and sample C&D Waste Management log. A standard Construction and Demolition Waste Management Log form is included at the end of this section.

2. Web Resources

(Information only; no warranty or endorsement is implied.)

<u>www.wastematch.org</u> Site of New York Waste Match, a materials exchange database and service <u>www.bignyc.org</u> Site of Build It Green NYC, a non-profit outlet for salvaged and surplus building materials

<u>www.usgbc.org</u> Site of the United States Green Building Council, with a description of the LEED certification process and requirements for C&D waste recycling

www.epa.gov/epawaste/index.htm Site of the U.S. Environmental Protection Agency that discusses construction and demolition waste issues, and links to other resources.

### 1.7 SUBMITTALS:

- A. The Contractor shall be responsible for the development and implementation of a Waste Management Plan for the Project. The Contractor's subcontractors shall assist in the development of that Plan, and collect and deposit their waste and recyclable materials in accordance with the approved Plan.
- B. DRAFT WASTE MANAGEMENT PLAN. Within fifteen (15) days after receipt of 'Notice to Proceed', or prior to any waste removal, whichever occurs sooner, the Contractor shall submit to the Commissioner a Draft Waste Management Plan. Include separate sections for demolition and construction waste. The Plan shall demonstrate how the performance goals will be met, and contain the following:

- List of materials targeted for reuse, salvage, or recycling, and names, addresses, and phone numbers of receiving facilities/companies that will be purchasing or accepting each material.
- 2. Description of onsite and/or offsite sorting methods for all materials to be removed from site.
- If mixed construction and demolition waste is to be sorted off-site, provide a letter from the processor stating the average percentage of mixed construction and demolition waste they recycle.
- Landfill information: Names of landfills where non-recyclable/reusable/salvageable waste will be disposed, and list of applicable tipping fees.
- 5. Materials handling procedures: A description of the means by which any recyclable, salvaged, or reused materials will be protected from contamination, and collected in a manner that will meet the requirements for acceptance by the designated recycling processors.
- 6. Transportation: A description of the means of transportation and destination for recycled materials.
- 7. Meetings: Description of regular meetings to be held to address waste management.
- 8. Sample spreadsheet and description of how the implementation of the plan will be documented on a monthly basis.
- C. FINAL WASTE MANAGEMENT PLAN. Within fifteen (15) days of Commissioner's approval of the Draft Plan, the Contractor shall submit a Final Waste Management Plan.
- D. PROGRESS REPORTS. The Contractor shall submit monthly a Waste Management Progress Report, containing the following information:
  - 1. Project title, name of company completing report, and dates of period covered by the report
  - Report on the disposal of all jobsite waste. A DDC C&D Waste Management Log form is available on the DDC Sustainable Design website and included at the end of this section. For each shipment of material removed from the site, provide the following:
    - a. Date and ticket number of removal
    - b. Identity of material hauler

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

c. Material Category

•]•]•]•]

- d. Total quantity of waste, in tones/cubic yards, by type
- e. Quantity of waste salvaged, recycled and/or reused, by type
- f. Total quantity of waste diverted from landfill (recycled, salvaged, reused) as a percentage of total waste
- g. Recipient of each material type
- 3. Provide monthly and cumulative project totals of waste, quantity diverted, and percentage diverted.
- 4. Note that the unit of measure may be either tons or cubic yards, but must be consistent for all shipments and all materials throughout the project. Reports with inconsistent or mixed units will not be reviewed and will be returned for re-submission.
- 5. Include legible copies of on-site logs, weight tickets and receipts. Receipts shall be from charitable organizations, recycling and/or disposal site operators who can legally accept the materials for the purpose of reuse, recycling or disposal. Contractor shall save such original documents for the life of the project plus seven (7) years.
- E. LEED Submittal: For LEED designated projects submit LEED Letter Template for the applicable credit, signed by the Contractor, tabulating total waste material, quantities diverted and means by which it is diverted, and statement that requirements for the credit have been met.
- F. Refrigerant Recovery. Submit Qualification data for Refrigerant recovery technician and statement of refrigerant recovery, signed by the refrigerant recovery technician responsible for recovering refrigerant

stating that all refrigerant that was present was recovered and that recovery was performed according to EPA regulations. Include name and address of technician and date refrigerant was recovered.

### 1.8 **QUALITY ASSURANCE:**

•

- The Contractor shall designate a Waste Management Coordinator, to ensure compliance with this Α. section. Coordinator shall be present at Project site full time for the duration of the project.
- Refrigerant Recovery Technician Qualifications: Certified by EPA-approved certification program. Β.
- Regulatory Requirements: Comply with hauling and disposal regulations of authorities having jurisdiction. C.
- Waste management plans, documentation and implementation shall be discussed at the following D. meetings:
  - Pre-demolition kick-off meeting 1.
  - Pre-construction kick-off meeting 2.

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

- Regular job-site meetings 3.
- Contractor toolbox meetings 4.

### PART II - PRODUCTS (Not Used)

### PART III - EXECUTION

### WASTE PLAN IMPLEMENTATION: 3.1

- The Contractor shall implement the Waste Management Plan, coordinate the Plan with all affected trades, Α. and designate one individual as the Construction Waste Management Representative, who will be responsible for communicating the progress of the Plan with the Commissioner on a regular basis, and for assembling the required LEED documentation.
- The Contractor shall be responsible for the provision of containers and the removal of all waste, non-Β. returned surplus materials, and rubbish from the site in accordance with the approved Waste Management Plan. The Contractor shall oversee and document the results of the Plan. Monies received for salvaged materials shall remain with the Contractor, except the monies for those items specifically identified elsewhere in the specifications, or indicated on the drawings as belonging to others.
- Responsibilities of Subcontractors: Each subcontractor shall be responsible for collecting its waste, non-C. returned surplus materials, and rubbish, in accordance with the Waste Management Plan.
- Distribution. The Contractor shall distribute copies of the Waste Management Plan to each D. Subcontractor, Resident Engineer, Construction Manager, and Commissioner.
- Training. The Contractor shall provide on-site instruction of proper waste management procedures to be E. used by all parties in appropriate stages of the Project.
- Procedures. Conduct waste management operations to ensure minimum interference with site F. vegetation, roads, streets, walks and other adjacent occupied and used facilities.
  - Collect co-mingled waste and/or separate all recyclable waste in accordance with the Plan Specific 1. areas on the Project site are to be designated, and appropriate containers and bins clearly marked with acceptable and unacceptable materials.
  - Inspect containers and bins for contamination and remove contaminated materials if found. 2.



3. Comply with the General Conditions for controlling dust and dirt, environmental protection, and noise control.

# 3.2 ADDITIONAL DEMOLITION AND SALVAGE REQUIREMENTS:

A. Demolition and salvage of additional items indicated in other sections of the Project Specifications require special attention as part of the overall 75 % diversion from landfill. Specific requirements for special attention are designated in other sections of the Project Specifications.

### 3.3 DISPOSAL:

- A. General. Except for items or material to be salvaged, recycled or otherwise reused, remove waste material from the Project site and legally dispose of them in a manner acceptable to authorities having jurisdiction.
  - 1. Except as otherwise specified, do not allow waste materials that are to be disposed of to accumulate on site.
  - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
- B. Burning. Do not burn waste materials
- C. Disposal. Transport waste materials off Project Site and legally dispose of them.

### END OF SECTION 01 74 19

NEW YORK CITY DEARFMENT OF DESIGN + CONSTRUCTION

# CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT LOG

Project Name: \_

Contractor: For Month:

Project I.D.:			Material	Quantity (to	ns or cubic )	ards) <sup>1</sup>	
Ticket Hauling Company *Material Category <sup>2</sup> #	*Material Category <sup>2</sup>		*Total Weight	Excluded Material <sup>3</sup>	*Diverted Material <sup>4</sup>	"Lanonied Material	*Material Recipient
						na yr ywy a mae'n mae'n a mae'n a ar a	
							gana rena manga da akata ginan tangka tersebu na mandapa ga da da na aminga nana-mata anana da mataka tersebi
							ער האו אין איז
	n de van de fan de f	<u>}</u>					والمحافظ
	en relevant of each and the second	+	n je na je na je na politika u je politika na politika na na politika na politika na politika na politika na p				
	ni n	+					
	na mana na mana mana mana mana mana man	+	n januar ala ang kang kang kang kang kang kang kang	-			می به به این این می بود بود می می می می می می می می این این این این این این می بود. این این این این این این ای می این این این این این این این این این ای
	a name of a state of the	+	n den serie and an and a serie and a serie of the series o				والإفكار فالمرابعة محاملا والمحاملة الإفراقية والمحامل المحاملة المحاملة والمحامل والمحامل والمحاملة والمحامل
	ny menerana da kana da	<u> </u>	nd dava man jule daja jule njelo il. 1914 ili monovalje na dolo				وبو میکند. با این میرود با از این از این از این از این از این میکند. این میکند این از این از این از این از این
	and a second	÷				A Second S	والمحافظة والمحافظة والمحافظة والمحافظة والمحافظة والمحافظة والمحافظة والمحافظة والمحافظ والمحافظة والمحافظة
							ومعتقدان هاداراته محاصبات والمحاد والمحادية المحادية المحادية المحادية المحادية والمحادية والمحادية المحادية ال
		1					
				and the second	na da da se a manana na manana		
		+	*Total		*Diverted	*Landfilled	
Monthly Totals	Monthly Total	است. م					
% Diverted this Month	% Diverted this Month*	*					

1. Volume (cubic yards) may be used instead of weight if used for ALL amounts and ALL materials. Notes:

**Cumulative Totals** 

% Diverted to Date

- Includes concrete; bricks; concrete masonry units (CMU); asphalt; metals; clean dimensional wood; carpet and pad; drywall; ceiling tiles; cardboard, paper, and packaging; and any other reuse items indicated on the Drawings and/or elsewhere in the Specification. Excluded material includes soil or land clearing debris. N
- Diverted material includes recycled and reused material diverted from landfill. Recycled material is reprocessed into new products. Reused material is reclaimed, salvaged or otherwise used in its original form, either on-site or off-site.
  - These items must be listed in order to receive LEED credit. 4



CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT LOG

No Text



### SECTION 01 77 00 CLOSEOUT PROCEDURES

### PARTI- GENERAL

### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

### 1.2 SUMMARY:

- A. This Section includes administrative and general procedural requirements for Closeout Procedures, including without limitation the following:
  - 1. Definitions
  - 2. Substantial Completion
  - 3. Final Acceptance
  - 4. Warranties
  - 5. Final Cleaning
  - 6. Repair of the Work
- B. LEED: Refer to the Addendum to identify whether this project is designed to comply with a Certification Level according to the U.S. Green Building Council's Leadership in Energy & Environmental Design (LEED) Rating System, as specified in Section 01 81 13, "SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS."
- C. COMMISSIONING: Refer to the Addendum to identify whether this project will be commissioned by an independent third party under separate contract with the City of New York. Commissioning shall be in accordance with ASHRAE and USGBC LEED- NC procedures, as described in Section 01 91 13, GENERAL COMMISSIONING REQUIREMENTS. The Contractor shall cooperate with the commissioning agent and provide whatever assistance is required.
- 1.3 **RELATED SECTIONS:** include without limitation the following:
  - A. Section 01 10 00 SUMMARY
  - B. Section 01 33 00 SUBMITTAL PROCEDURES
  - C. Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT & DISPOSAL
  - D. Section 01 78 39 CONTRACT RECORD DOCUMENTS
  - E. Section 01 79 00 DEMONSTRATION AND OWNER'S PRE-ACCEPTANCE ORIENTATION

### 1.4 DEFINITIONS:

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or



combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.

- C. <u>Substantial Completion</u>: shall mean the written determination by the Commissioner that the Work required under the Contract is substantially, but not entirely, complete.
- D. <u>Final Acceptance</u>: shall mean final written acceptance of all the Work by the Commissioner, a copy of which shall be sent to the Contractor.

## **1.5 SUBSTANTIAL COMPLETION:**

- A. Preliminary Procedures: Before requesting inspection to determine the date of Substantial Completion, the Contractor shall complete and supply all items required by the contract specifications, General Conditions, Addendum to the General Conditions, change orders or other directives from the Commissioner's representatives. The required items will include all contract requirements for substantial completion, including but not limited to items related to releases, regulatory approvals, warranties and guarantees, record documents, testing, demonstration and orientation, final clean up and repairs, and all specific checklist of items by the Resident Engineer. (See Attachment "A" at the end of this section for sample requirements for Substantial Completion).
- B. Prepare and submit a list to the Resident Engineer of incomplete items, the value of incomplete construction, and reasons the work is not complete.
- C. Inspection: The Contractor shall submit to the Resident Engineer a written request for inspection for Substantial Completion. Within ten (10) days of receipt of the request, the Resident Engineer will either proceed with inspection or notify Contractor of unfulfilled requirements. The Resident Engineer may request the services, as required, of the Design Consultant, Client Agency Representative and/or other entities having involvement with the Work to assist in the inspection of the Work. If the Resident Engineer makes a determination that the work is substantially complete and approves the Final Punch List and the date for Final Acceptance, he/she will so advise the Commissioner and recommend issuance of the Certificate of Substantial Completion. If the Resident Engineer determines that the work is not substantially complete, he/she will notify the Contractor of those items that must be completed or corrected before the Certificate of Substantial Completion will be issued.
  - 1 Re-inspection: Contractor shall request re-inspection when the Work identified in previous inspections as incomplete is completed or corrected.
  - 2 Results of completed inspection will form the basis of requirements for Final Acceptance.

### 1.6 FINAL ACCEPTANCE:

- A. Preliminary Procedures: Before requesting final inspection for Final Acceptance of the Work, the Contractor shall complete the following. (Note that the following are to be completed, submitted as appropriate, and approved by the Commissioner, as applicable, prior to the final inspection and are not to be submitted for approval or otherwise at the final inspection unless specifically indicated). List
  - 1. Verify that all required submittals have been provided to the Commissioner including but not limited to the following:
    - a. Manufacturer's cleaning instructions
    - b. Posted instructions
    - c. As-built Record Documents (Drawings, specifications, and product data) as described in Section 01 78 39, CONTRACT RECORD DOCUMENTS, incorporating any changes required by the Commissioner as a result of the review of the submission prior to the pre-final inspection.
    - d. Operation and Maintenance Manuals, including Preventive Maintenance, Special Tools, Repair Requirements, Parts List, Spare Parts List, and Operating Instructions.



- e. Completion of required Demonstration and Orientation, as applicable, of designated personnel in operation and maintenance of systems, sub-systems and equipment.
- f. Applicable LEED Building submittals as described in Section 01 81 13, SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS.
- g. Construction progress photographs as described in Section 01 32 33, PHOTOGRAPHIC DOCUMENTATION.
- 2. Submit a certified copy of the final approved Punch List of items to be completed or corrected. The certified copy of the Punch List shall state that each item has been completed or otherwise resolved for acceptance, and shall be endorsed and dated by the Contractor.
- Submit pest-control final inspection report and survey as required in Section 01 50 00,
- TEMPORARY FACILITIES AND CONTROLS.
- 4. Submit record documents and similar final record information.
- Deliver tools, spare parts, extra stock and similar items.
- Complete final clean-up requirements including touch-up painting of marred surfaces.
- Submit final meter readings for utilities, as applicable, a measured record of stored fuel, and similar data as of the date when the City took possession of and assumed responsibility for corresponding elements of the work.
- B. Final Inspection: The Contractor shall submit to the Resident Engineer a written request for inspection for Final Acceptance of the Work. Within ten (10) days of receipt of the request, the Resident Engineer will either proceed with inspection or notify the Contractor of unfulfilled requirements. The Resident Engineer may request the services, as required, of the Design Consultant, Client Agency Representative and/or other entities having involvement with the Work to assist in the inspection of the Work. If the Resident Engineer finds that all items on the Final Approved Punch List are complete and no further work remains to be done, he/she will so advise the Commissioner and recommend the issuance of the determination of Final Acceptance. If the Resident Engineer determines that the work is not complete, he/she will notify the Contractor of those items that must be completed or corrected before the determination of Final Acceptance will be issued.
- C. Final Acceptance: The Work will be accepted as final and complete as of the date of the Resident Engineer's inspection if, upon such inspection, the Resident Engineer finds that all items on the Punch List are complete and no further Work remains to be done. The Commissioner will then issue a written determination of Final Acceptance.

### 1.7 WARRANTIES:

- A. The items of materials and/or equipment for which manufacturer warranties are required are listed in Schedule B of the Addendum. For each item of material and/or equipment listed in Schedule B, the Contractor shall obtain a written warranty from the manufacturer. Such warranty shall provide that the material or equipment is free from defects for the period set forth in Schedule B and will be replaced or repaired within such specified period. The contractor shall deliver all required warranties to the Commissioner.
- B. Unless indicated otherwise Warranties are to take effect on the date of Substantial Completion.
- C. Submittal Time: Submit written Warranties on request of the Commissioner for designated portions of the Work where commencement of Warranties other than date of Substantial Completion is indicated.
- D. Partial Occupancy: Submit properly executed Warranties to the Commissioner within 15 days of completion of designated portions of the Work that are completed and occupied or used by the City.
- E. Organize the Warranty documents into an orderly sequence based on the Project Specification Divisions and Section Numbers.





- 1. Bind Warranties in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
- Identify each binder on the front and spine with the typed or printed title "WARRANTIES;" name and location of Project; Capitol Budget Project Number (FMS ID); and Contractor's and applicable subcontractor's name and address.
- 3. Provide heavy paper dividers with plastic-covered tabs for each separate Warranty. Mark tab to identify the product or installation.
- 4. Provide a typed description of each product or installation being warranted, including the name of the product, and the name, address, and telephone number of the Installer.
- F. When warranted materials and/or equipment require operation and maintenance manuals, provide additional copies of each required Warranty in each required manual. Refer to Section 01 78 39, CONTRACT RECORD DOCUMENTS, for requirements of Operation and Maintenance Manuals.

### PART II – PRODUCTS

## 2.1 MATERIALS:

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

### **PART III - EXECUTION**

### 3.1 FINAL CLEANING:

- A. General: Provide final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
  - 1. Complete the following cleaning operations, as applicable, before requesting inspection for Final Acceptance of the Work for entire Project or for a portion of Project:
    - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
    - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
    - c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
    - d. Remove tools, construction equipment, machinery, and surplus material from Project site.
    - e. Remove snow and ice to provide safe access to building.
    - f. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
    - g. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
    - h. Sweep concrete floors broom clean in unoccupied spaces.
    - i. Vacuum carpet and similar soft surfaces, removing debris and excess nap; shampoo if visible soil or stains remain.



- j. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Replace chipped or broken glass and other damaged transparent materials. Polish mirrors and glass, taking care not to scratch surfaces.
- k. Remove labels that are not permanent.
- I. Touch up and otherwise repair and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.
  - 1) Do not paint over "UL" and similar labels, including mechanical and electrical nameplates.
- m. Wipe surfaces of mechanical and electrical equipment and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
- n. Replace parts subject to unusual operating conditions.
- Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
- p. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
- q. Clean ducts, blowers, and coils if units were operated without filters during construction.
- r. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency. Replace burned-out bulbs, and those noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.
- s. Leave Project clean and ready for occupancy.
- t. Construction Waste Disposal: Comply with waste disposal requirements in Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL.
- C. Pest Control: Engage an experienced, licensed exterminator to make a final inspection and rid Project of rodents, insects, and other pests, as required in Section 01 50 00, TEMPORARY FACILITIES, SERVICES AND CONTROLS. Prepare and submit a Pest Control report to the Commissioner.
- D. Comply with safety standards for cleaning. Do not burn waste materials. Do not bury debris or excess materials on City's property. Do not discharge volatile, harmful, or dangerous materials into drainage systems. Remove waste materials from Project site and dispose of lawfully.

### 3.2 REPAIR OF THE WORK:

- A. Subject to the terms of the Contract the Contractor shall complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Contractor shall repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.
  - 1. Remove and replace chipped, scratched, and broken glass, reflective surfaces, and other damaged transparent materials.
  - 2. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that that already show evidence of repair or restoration.
    - a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.





- 3. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
- Replace burned-out bulbs, bulbs noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.

# END OF SECTION 01 77 00

• •

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION



# SECTION 01 77 00

### ATTACHMENT 'A'

The following list is a general sample of Substantial Completion requirements, including but not limited to:

- 1. Prepare and submit a list to the Resident Engineer, of incomplete items, the value of incomplete construction, and reasons the work is not complete.
- Obtain and submit any necessary releases enabling the City unrestricted use of the project and access to services and utilities.
- Regulatory Approvals: Submit all required documentation from applicable Governing Authorities, including, but not limited to, Department of Buildings (DoB); Department of Transportation (DoT); Department of Environmental Protection (DEP); Fire Department (FDNY); etc. Documentation to include, but not limited to, the following:
  - a. Building Permits, Applications and Sign-offs.
  - b. Permits and Sign-off for construction fences; sidewalk bridges; scaffolds, cranes and derricks; utilities; etc.
  - c. Certificates of Inspections and Sign-offs.
  - d. Required Certificates and Use Permits.
  - e. Certificate of Occupancy (C.O.), Temporary Certificate of Occupancy (T.C.O.) or Letter of Completion as applicable.
- 4. Submit specific warranties required by the specifications, final certifications, and similar documents.
- 5. Prepare and submit Record Documents as described in Section 01 78 39, CONTRACT RECORD DOCUMENTS, including but not limited to; approved documentation from Governing Authorities; as-built record drawings and specifications; product data; operation and maintenance manuals; Final Completion construction photographs; damage or settlement surveys; final property surveys; and similar final record information. The Resident Engineer will review the submission and provide appropriate comments. If comments are significant the initial submission will be returned to the Contractor for correction and re-submission incorporating the comments prior to the Final Inspection.
- 6. Record Waste Management Progress Report: Submit C&D Waste Management logs, with legible copies of weight tickets and receipts required in accordance with Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL.
- 7. If applicable submit LEED Letter Template in accordance with the requirements of Section 01 81 13, SUSTAINABLE DESIGN REQUIREMENTS FOR LEED BUILDINGS.
- Schedule applicable Demonstration and Orientation required in other Sections of the Project Specifications and as described in Section 01 79 00, DEMONSTRATION AND OWNER'S PRE-ACCEPTANCE ORIENTATION.
- 9. Deliver tools, spare parts, extra materials, and similar items to location designated by Resident Engineer. Label with manufacturer's name and model number where applicable.
- 10. Make final changeover of permanent locks and deliver keys to the Resident Engineer. Advise Commissioner of changeover in security provisions.
- 11. Complete startup testing of systems as applicable.
- 12. Submit approved test/adjust/balance records.
- 13. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements as directed by the Resident Engineer.
- 14. If applicable complete Commissioning requirements as defined in Section 01 91 13, GENERAL COMMISSIONING REQUIREMENTS.
- 15. Complete final cleaning requirements, including touchup painting.
- 16. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.











### SECTION 01 78 39 CONTRACT RECORD DOCUMENTS

### PART I - GENERAL

### 1.1 RELATED DOCUMENTS:

A. The following documents apply to all required work for the Project: (1) the Contract Drawings, (2) the Specifications, (3) the General Conditions, (4) the Addendum, and (5) the Contract [City of New York Standard Construction Contract].

### 1.2 SUMMARY:

- A. This Section includes administrative and general procedural requirements for Contract Record Documents, including:
  - 1. As-built Contract Record Drawings.
  - 2. As-built marked-up copies of Record Specifications, addenda and Change Orders.
  - 3. As-built marked-up Product Data
  - 4. Record Samples
  - 5. Construction Record Photographs
  - 6. Operating and Maintenance Manuals
  - 7. Final Site Survey
  - 8. Guarantees and Warranties
  - 9. Waste Disposal Documentation
  - 10. LEED Materials and Matrix
  - 11. Miscellaneous Record Submittals
- B. The Department of Design and Construction, at the start of construction (kick-off meeting), will furnish to the Contractor at no cost a complete set of Contract Drawings Mylars (reproducible) pertaining to the work to be performed under the Contract. It is the responsibility of the Contractor to modify the Contract Drawings to indicate all changes and corrections, if any, occurring in the work as actually installed. The Contractor is required to furnish all other Mylar (reproducible) drawings, if necessary, such as Addenda Drawings and Supplementary Drawings as may be necessary to indicate all work in detail as actually completed. <u>All professional seals must be blocked out</u>. Title box complete with project title and Design Consultants' names will remain.
- C. Maintenance of Documents and Samples: The Contractor shall maintain, during the progress of the work, an accurate record of the work as actually installed, on Contract Record Drawings, on Mylar (reproducible), in ink. Store record documents and samples in the field office apart from the Contract Documents used for construction. Do not use Project Record Documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition. Make documents and samples available at all times for the Resident Engineer's inspections.

The Contractor's attention is particularly directed to the necessity of keeping accurate records of all subsurface and concealed work, so that the Contract Record Drawings contain this information in exact detail and location. Contract Record Drawings shall also show all connections, valves, gates, switches, cut-outs and similar operating equipment.

For projects designated to achieve a LEED rating the Contractor shall receive a copy of the project's LEED scorecard for the purpose of monitoring compliance with the target objectives and to facilitate coordination with the LEED Consultant. The Contractor shall receive periodic updates of this scorecard,



and is required to submit the final version of the Scorecard at Substantial Completion with other project Record Documents.

### 1.3 RELATED SECTIONS: include without limitation the following:

- A. Section 01 10 00 SUMMARY
- B. Section 01 32 00
- CONSTRUCTION PROGRESS DOCUMENTATION PHOTOGRAPHIC DOCUMENTATION
- C. Section 01 32 33 PHOTOGRA D. Section 01 33 00 SUBMITTAL
- D. Section 01 33 00

SUBMITTAL PROCEDURES

E. Section 01 77 00 PROJECT CLOSEOUT PROCEDURES

### 1.4 **DEFINITIONS:**

- A. Refer to Article 2 of the Contract for definition of terms, words and expressions used in the General Conditions not otherwise defined herein.
- B. Design Consultant: "Design Consultant" shall mean the entity responsible for providing design services for the Project, including without limitation, preparing the construction documents (drawings and specifications) and providing services in connection with such documents during construction. The entity serving as the "Design Consultant" may be a corporation, firm, partnership, joint venture, individual or combination thereof. Such entity may be either an employee(s) of the City or an entity engaged by the City to provide such services.

### 1.5 SUBMITTALS:

A. As-Built Contract Record Drawings: Comply with the following:

(Heating & Ventilating Inspector)

(Electrical Inspector)

- 1. Progress Submission: As directed by the Resident Engineer, submit progress As-Built Contract Record Drawings at the 50% Construction Completion stage.
- 2. Final Submission: Before substantial completion payment, the Contractor shall furnish to the Commissioner one (1) complete set of marked-up Mylar (reproducible) As-Built Contract Record Drawings, in ink indicating all of the work and locations as actually installed, plus one (1) set of paper prints which will be furnished to the sponsoring agency by DDC.
- 3. As-Built Contract Record Drawings shall be of the same size as that of the Contract Drawings, with a one (1) inch margin on three (3) sides and a two (2) inch margin on the left side for binding.
- 4. Each As-Built Contract Record Drawing shall bear the legend "AS-BUILT CONTRACT RECORD DRAWING" in heavy block lettering, one half (1/2) inch high, and contain the following data:

DDC

DDC

AS-BUILT CONTRACT I Contractor's Name Contractor's Address Subcontractor's Name (v Subcontractor's Address	vhere applicable)	
Made by:	Date	
Checked by:	Date	
Commissioner's Represe	entatives	
(Resident Engineer)	DDC	
(Plumbing Inspector)	DDC	

CONTRACT RECORD DOCUMENTS 01 78 39- 2



- Record Drawing Title Sheet: The Contractor shall prepare a title sheet, the same size as the Contract Record Drawings, which shall contain the following:
  - a. Heading:

The City of New York Department of Design and Construction Division of Public Buildings

- b. Capital Budget Project Number (FMS ID)
- c. Name and Location of Project
- d. Contractor's Name and Address
- e. Subcontractor's Name and Address (where applicable)
- f.. Record of changes (a caption description of work affected, and the date and number of Change Order or other authorization)
- g.. List of Record Drawings
- B. Record Specifications, Addenda and Change Order: Submit to the Commissioner two (2) copies each of marked-up Record Specifications, Addenda and Change Orders.
- C. Record Product Data: Submit to the Commissioner two (2) sets of Record Product Data.
- D. Record Construction Photographs: Submit to the Commissioner final as-built construction photographs and negatives of the completed work as described in Section 01 32 33, PHOTOGRAPHIC DOCUMENTATION.
- E. Operating and Maintenance Manuals:
  - Submit three (3) copies each of preliminary manuals to the Resident Engineer for review and approval. The Contractor shall make such corrections, changes and/or additions to the manual until deemed satisfactory by the Resident Engineer. Deliver three (3) copies of the final approved manuals to the Resident Engineer for distribution.
  - 2. Commissioning: Comply with the requirements of Section 01 91 13, GENERAL COMMISSIONING REQUIREMENTS, as well as the requirements set forth in sections of the Project Specifications, for projects designated for Commissioning. Submit four (4) copies each of data designated to be included in the Commissioning Operation and Maintenance Manual to the Resident Engineer. The Resident Engineer will forward such data to the Commissioning Authority/Agent (CxA) for review and comment. The Contractor shall make such corrections, changes and/or additions to the data until deemed satisfactory and deliver four (4) copies of the final data to the Resident Engineer for use by the Commissioning Authority/Agent (CxA) to prepare the Commissioning Operation and Maintenance Manual.
    - a. Non-Commissioning Data: All remaining data not designated for Commissioning and required as part of Maintenance and Operation Manual shall be prepared and assembled in accordance with the requirements of this section for Operating and Maintenance Manuals.
- F. Final Site Survey: Submit Final Site Survey as described in Section 01 73 00, EXECUTION, in quantities requested by the Commissioner, signed and sealed by a Land Surveyor licensed in the State of New York.
- G. Guarantees and Warranties.
- H. Waste Disposal Documents and Miscellaneous Record Documents.






### **PART II – PRODUCTS**

### 2.1 CONTRACT RECORD DRAWINGS:

- A. Record Prints: The Contractor shall maintain one set of blue- or black-line white prints as applicable of the Contract Drawings and Shop Drawings. If applicable, the Record Contract Drawings and Shop Drawings shall incorporate the arrangement of the work based on the accepted Master Coordination Drawing(s) as described in Section 01 33 00, SUBMITTAL PROCEDURES.
  - 1. Preparation: The Contractor shall mark Record Prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to prepare the marked-up Record Prints.
    - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
    - b. Accurately record information in an understandable drawing technique.
    - Record data as soon as possible after obtaining it. Record and check the markup before enclosing concealed installations.
  - 2. Change Orders: All changes from Contract Drawings shall be distinctly encircled and identified by Change Order number correlating to changes listed on the "Title Sheet." The Contractor shall show within the encircled areas the work as actually installed.
- B. Content: Types of items requiring marking include, but are not limited to, the following:
  - 1 Dimensional changes to Drawings.
  - 2 Revisions to details shown on Drawings.
  - 3 Depths of foundations below first floor,
  - 4 Locations and depths of underground utilities.
  - 5 Revisions to routing of piping and conduits.
  - 6 Revisions to electrical circuitry.
  - 7 Actual equipment locations.
  - 8 Duct size and routing.
  - 9 Locations of concealed internal utilities.
  - 10 Changes made by Change Order
  - 11 Changes made following Commissioner's written orders.
  - 12 Details not on the original Contract Drawings.
  - 13 Field records for variable and concealed conditions.
  - 14 Record information on the Work that is shown only schematically.
- C. Progress Record Mylar's (reproducible): As directed by the Resident Engineer at 50% construction completion, review marked-up Record Prints with the Resident Engineer and the Design Consultant. When directed by the Resident Engineer transfer progress mark-ups to a full set of Mylar's (reproducible) and submit one blue line or black line record copy to the Resident Engineer. The marked-up Mylar's (reproducible) shall be retained by the contractor for completion of mark-up and final submission.
- D. Final Contract Record Mylar's (reproducible): Immediately before final inspection for Certificate of Substantial Completion, review marked-up Record Prints with the Resident Engineer and the Design Consultant. When authorized, complete mark-up of a full set of corrected Mylar's (reproducible) of the Contract Drawings.
  - 1. Incorporate changes and additional information previously marked on Record Prints. Erase, redraw, and add details and notations where applicable.
  - 2. Refer instances of uncertainty to Resident Engineer for resolution.
  - 3. Print the As-Built Contract Drawings and Shop Drawings for use as Record Transparencies as described in Sub-Section 1.5.





### **RECORD SPECIFICATIONS. ADDENDA AND CHANGE ORDERS:** 2.2

IEW YORK CITY DEPARTMENT OF **DESIGN + CONSTRUCTION** 

- Preparation: Mark Specifications to indicate the actual product installation where installation varies from Α. that indicated in Specifications, addenda, and contract modifications.
  - Give particular attention to information on concealed products and installations that cannot be 1. readily identified and recorded later.
  - Mark copy with the proprietary name and model number of products, materials, and equipment 2. furnished, including substitutions and product options selected.
  - Record the name of manufacturer, supplier, Installer, and other information necessary to provide a 3. record of selections made
  - For each principal product, indicate whether Record Product Data has been submitted in operation 4. and maintenance manuals instead of submitted as Record Product Data.
  - Note related Change Orders and Record Drawings where applicable. 5.
  - Upon completion of mark-up, submit two (2) complete copies of the marked-up Record 6. Specifications to the Commissioner.

### **RECORD PRODUCT DATA:** 2.3

- Preparation: Mark Product Data to indicate the actual product installation where installation varies A. substantially from that indicated in Product Data submittal.
  - Give particular attention to information on concealed products and installations that cannot be 1. readily identified and recorded later.
  - Include significant changes in the product delivered to Project site and changes in manufacturer's 2. written instructions for installation.
  - If possible, a Change Order proposal should include resubmitting updated Product Data. This 3. eliminates the need to mark up the previous submittal.
  - Note related Change Orders and Record Drawings where applicable. 4
  - Upon completion of mark-up submit to the Commissioner two (2) sets of the marked-up Record 5. Product Data.
  - Where Record Product Data is required as part of Maintenance Manuals, submit marked-up 6. Product Data as an insert in the manual instead of submittal as record Product Data.

### **RECORD SAMPLE SUBMITTAL:** 2.4

- Prior to the date of Substantial Completion, the Contractor shall meet with the Resident Engineer at the Α. site to determine which of the Samples maintained during the construction period shall be transmitted to the Commissioner for record purposes.
- Comply with the Resident Engineer's instructions for packaging, identification marking and delivery to Β. DDC. Dispose of other samples as specified for disposal of surplus and waste material.


### **OPERATING AND MAINTENANCE MANUALS:** 2.5

- The Contractor shall provide preliminary and final versions of Operating and Maintenance Manuals Δ required for those systems, equipment and materials listed in other Sections of the Project Specifications.
- Format: Prepare and assemble Operation and Maintenance Manuals in heavy-duty, 3-ring, hardback B. loose leaf binders in the form of an instructional manual. All binders for each discipline shall be the same color. When multiple binders are used, correlate data into related consistent groupings. Binder front shall contain permanently attached labels displaying the following:

»】D】o YORK CITY DEPARTMENT OF **DESIGN + CONSTRUCTION**  Division 01 - DDC STANDARD GENERAL CONDITIONS SINGLE CONTRACT PROJECTS Issue Date - June 01, 2013

- Heading: 1. The City of New York Department of Design and Construction
- **Division of Public Buildings** 2.
- Capital Budget Project Number (FMS ID) Name and Location of Project 3.
- 4,
- Contractor's Name and Address
- 5. Subcontractor's Name and Address (where applicable)
- Dates of the work covered by the contents of the Project Manual. 6.
- Binder spine shall display Project Number (FMS ID) and date of completion. 7.
- Organization: Include a section in the directory for each of the following: C.
  - 1. List of documents
  - 2. List of systems
  - 3. List of equipment
  - 4. Table of contents
- Arrange content by systems under Specification Section numbers and sequence of Table of Contents of D. the Project manual. Provide tabbed flyleaf for each separate product, equipment and/or system/subsystem with typed description of product and major component parts of equipment.
- Safety warnings or cautions shall be visibly highlighted within each maintenance procedure. Use of such E. highlights shall be limited to only critical items and shall not be used in an excessive manner which would reduce their effectiveness.
- For each product or system, list names, addresses and telephone numbers of Subcontractors and F. Suppliers, including local source of supplies and replacement parts. Vendors and Supplier listings are to include names, addresses and telephone numbers, including nearest field service telephone numbers.
- Where contents of the manual include any manufacturer's catalog pages, clearly indicate the precise G. items and options included in the installation and delete all manufacturers' data regarding products not included in the installation.
- All material within manuals shall be new. Copies used for prior submittals or used in construction shall H. not be used.
- Submit preliminary and final manual editions to the Commissioner according to the approved progress Ι. schedule.
- Manuals shall present all technical material to the greatest extent possible, with respect to text, tabular J. matter and illustrations. Illustrations shall preferably consist of line drawings. All applicable drawings shall be included. If available, color photograph prints may be included.
- Preliminary manual editions shall be as technically complete as the final manual edition. All illustrations K. shall be in final forms.
- Final manual editions shall be technically accurate and complete and shall represent all "as-built" L. systems, pieces of equipment, or materials, which have been accepted by the Commissioner. All illustrations, text and tabular material shall be in final form. All shop drawings shall be included as specified in individual Specification Sections.
- Building products, applied materials, and finishes: Include product data, with catalog number, size, M. composition, and color texture designations. Where applicable, provide information for re-ordering custom manufactured products.
- Instructions for care and maintenance: Include manufacturers' recommendations for cleaning agents and N. methods, and recommended schedule for cleaning and maintenance.





P. Additional Requirements: Specified in individual Specification Sections.

# 2.6 DEMONSTRATION AND ORIENTATION DVD:

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

A. Non-Commissioned Projects: The Contractor shall submit final version of applicable Demonstration and Orientation DVD recordings in compliance with Section 01 79 00, DEMONSTRATION AND OWNER'S PRE-ACCEPTANCE ORIENTATION.

### 2.7 GUARANTEES AND WARRANTIES:

DD

- A. SCHEDULE B Requirements for guarantees and warranties for the Project are set forth in Schedule B, which is included as part of the Addendum.
- B. FORM For all guarantee requirements set forth in Schedule B, the Contractor shall provide a written guaranty, in the form set forth herein.
- C. Submit fully executed and signed manufacturers' Warranties as listed in the Project Specifications and outlined in Schedule B of the Addendum. Refer to Section 01 77 00, CLOSEOUT PROCEDURES for submittal requirements.



	GUARANTY
DDC PROJECT #	
CONTRACT #	
GUARANTY TO BE IN EFFECT FROM	
то	

The Contractor hereby guarantees that the work specified under the above section of the aforesaid Contract will be free from defects of material and/or workmanship, for the period indicated above.

The Contractor also guarantees that it will promptly repair, restore, rebuild or replace whichever may be deemed necessary by the City, any or all defective material or workmanship of the aforementioned section, that may appear within the guaranty period and any finished work to which damage may occur because of such defects, to the satisfaction of the City and without any cost or expense to the City.

The Contractor hereby agrees to pay to the City the cost of the repairs or replacements should the City make the same because of the failure of the Contractor to do so.

Contractor:

By:

Signature of Partner or Corporate Officer


Print Name:

Subscribed and sworn to before me this day of \_\_\_\_\_, year

**₽]₽]●** 

NEW YORK CITY DEPARTMENT OF DESIGN + CONSTRUCTION

Notary Public





### 2.8 WASTE DISPOSAL DOCUMENTATION:

A. Certify and deliver to the Commissioner all documentation including reports, receipts, certificates, records etc. for the collection, handling, storage, classification, testing, transportation, recycling and/or disposal of all Non-Hazardous Construction Waste as required by Section 01 74 19, CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL, and Hazardous Waste as required by other Project Specification Sections. Certify compliance with all applicable governing laws, codes, rules and regulations.

### 2.9 MISCELLANEOUS RECORD DOCUMENTS:

- A. Refer to other Project Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Prior to Final Acceptance, complete miscellaneous records and place in good order, properly identified and bound or otherwise organized to allow for use and reference.
- B. Submit three (3) copies of each document to the Commissioner or as otherwise directed by the Commissioner.

### PART III - EXECUTION

### 3.1 RECORDING AND MAINTENANCE:

- A. Recording: Maintain one copy of each submittal during the construction period for Contract Record Document purposes. Post changes and modifications to Project Record Documents as they occur; do not wait until the end of Project.
- B. Maintenance of Record Documents and Samples: Store Record Documents and Samples in the field office apart from the Contract Documents used for construction. Do not use Contract Record Documents for construction purposes. Maintain Record Documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to the Contract Record Documents for the Resident Engineer's reference during normal working hours.

### END OF SECTION 01 79 39

CONTRACT RECORD DOCUMENTS 01 78 39- 9

PROJECT NO. JOC2013E-2 PROJECT ID: JOCS\_DDC

THE CITY OF NEW YORK

**JOB ORDER CONTRACT** 

DIVISION OF PUBLIC BUILDINGS DEPARTMENT OF DESIGN AND CONSTRUCTION

LONG ISLAND CITY, NEW YORK 11101-3045

**30-30 THOMSON AVENUE** 

TELEPHONE (718) 391-1000

WEBSITE www.nyc.gov/buildnyc

Ø

Contract for Furnishing all Labor and Material Necessary and Required for:

рQ

SI 0-5 N

2102-91-E Hor

' 30

**~** 0Z '

° 20 €

 $\mathcal{N}$ 

Dated

Date

Dated

Contractor

First Assistant Bookkeeper

Acting Coporation Gour

Aptroved as to Form

Certified as to Legal Authority

Entered in the Comptroller's Office

91

.

**bKO1ECL NO 10C5013E-5** 

 bK01ECL ID:
 10C2

# DIVISION OF PUBLIC BUILDINGS DEPARTMENT OF DESIGN AND CONSTRUCTION

WEBSITE www.nyc.gov/buildnyc

30-30 THOMSON AVENUE TELEPHONE (718) 391-1000

Dated

Contract for Furnishing all Labor and Material Necessary and Required for:

# **ТОВ ОКРЕЯ СОИТRACT**

First Assistant Bookkeeper	
Entered in the Comptroller's Office	
Oste02 ,	
Acting Coporation Counsel	
Aprroved as to Form Certified as to Legal Authority	
Dated 20	
Contractor	

**8-058** 

` 50

PROJECT ID:	JOCS_DDC
PROJECT NO.	JOC2013E-2

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF PUBLIC BUILDINGS

30-30 THOMSON AVENUE TELEPHONE (718) 391-1000 LONG ISLAND CITY, NEW YORK 11101-3045 WEBSITE www.nyc.gov/buildnyc

Contract for Furnishing all Labor and Material Necessary and Required for:

# JOB ORDER CONTRACT

Contractor		
Dated	, 20	
Aprroved as to Form Certified as to Legal Authority		
Acting Coporation Counsel		
Date	, 20	
Entered in the Comptroller's Office		
First Assistant Bookkeeper		
Dated	, 20	
		■ 6-0



PROJECT ID: JOCS_DDC			
PROJECT NO. JOC2013E-2	р. — — — — — — — — — — — — — — — — — — —		
THE CITY OF NEW YOR			
	GN AND CONSTRUCTION		
<b>DIVISION OF PUBLIC B</b>	UILDINGS		1. μ
30-30 THOMSON AVENUE TELEPHONE (718) 391-1000	LONG ISLAND CITY, NEW YORK WEBSITE www.nyc.gov/buildnyc	11101-3045	a suite de la constante de la c La constante de la constante de La constante de la constante de
Contract for Furnishing all La	bor and Material Necessary and R	equired for:	NA MARANA ANA MANAZAR
JOB ORDER C	ONTRACT		
ÎFCOATN	Electrical, CO.,	INC.	
Contractor	etechical, co.,		
Dated Marl	09	, 20_16	
Aprroved as to Form Certified as to Legal Authority Acting Coporation Goursel	1.		2074 3-16-3017
Date <u>March 16</u>		, 20 / 5	
Entered in the Comptroller's Office			
First Assistant Bookkeeper			
Dated		, 20	
			5-015