

#### THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

30-30 THOMSON AVENUE LONG ISLAND CITY, NEW YORK 11101-3045 TELEPHONE (718) 391-1000 WEBSITE www.nyc.gov/buildnyc

LAW

#### VOLUME 1 OF 3

BID BOOKLET

FOR FURNISHING ALL LABOR AND MATERIALS NECESSARY AND REQUIRED FOR:

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN: ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD; WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET; FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE; WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE; GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE; MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE; VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND, WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

INCLUDING WATER MAIN WORK

Together With All Work Incidental Thereto
BOROUGH OF STATEN ISLAND
CITY OF NEW YORK

FOR THE DEPARTMENT OF ENVIRONMENTAL PROTECTION PREPARED BY IN-HOUSE DESIGN

February 26, 2014





DR. FENIOSKY A. PEÑA-MORA Commissioner

JOHN GODDARD Agency Chief Contracting Officer

October 14, 2014

CERTIFIED MAIL - RETURN RECEIPT REQUEST INTER CONTRACTING CORP. 274 White Plains Road Eastchester, NY 10709

RE: FMS ID: SER002316

E-PIN: 85014B0130001

DDC PIN: 8502014SE0001C

CONSTRUCTION OF STORM AND

SANITARY SEWERS AND

APPURTENANCES IN: ROSSVILLE

AVENUE BETWEEN MASON

BOULEVARD AND WOODROW ROAD, ETC. - BOROUGH OF STATEN ISLAND

NOTICE OF AWARD

#### Dear Contractor:

You are hereby awarded the above referenced contract based upon your bid in the amount of \$10,721,451.40 submitted at the bid opening on May 28, 2014. Within ten (10) days of your receipt of this notice of award, you are required to take the actions set forth in Paragraphs (1) through (3) below. For your convenience, attached please find a copy of Schedule A of the General Conditions to the Contract, which sets forth the types and amounts of insurance coverage required for this contract.

- (1) Execute four copies of the Agreement in the Contracts Unit, 30-30 Thomson Avenue, 1<sup>st</sup> Floor, Long Island City, New York (IDCNY Building). A Commissioner of Deeds will be available to witness and notarize your signature. The Agreement must be signed by an officer of the corporation or a partner of the firm.
- (2) Submit to the Contracts Unit four properly executed performance and payment bonds. If required for this contract, copies of performance and payment bonds are attached.
- (3) Submit to the Contracts Unit the following insurance documentation: (a) original certificate of insurance for general liability in the amount required by Schedule A, and (b) original certificates of insurance or other proof of coverage for workers' compensation and disability benefits, as required by New York State Law. The insurance documentation specified in this paragraph is required for registration of the contract with the Comptroller's Office.



On or before the contract commencement date, you are required to submit all other certificates of insurance and/or policies in the types and amounts required by Schedule A. Such certificates of Insurance and/or policies must be submitted to the Agency Chief Contracting Office, Attention: Risk Manager, Fourth Floor at the above indicated department address.

Your attention is directed to the section of the Information for Bidders entitled "Failure to Execute Contract". As indicated in this section, in the event you fail to execute the contract and furnish the required bonds within the (10) days of your receipt of this notice of award, your bid security will be retained by the City and you will be liable for the difference between your bid price and the price for which the contract is subsequently awarded, less the amount of the bid security retained.

Sincerely,

John Goddard

#### BID FORM THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

#### BID FOR FURNISHING ALL LABOR AND MATERIAL NECESSARY AND REQUIRED FOR:

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN
WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

#### INCLUDING WATER MAIN WORK

Together With All Work Incidental Thereto BOROUGH OF STATEN ISLAND

Name of Bidder: <u>Taker Contracting Corp.</u>
Date of Bid Opening: May 28, 2014
Bidder is: (Check one, whichever applies) Individual ( ) Partnership ( ) Corporation (X)
Place of Business of Bidder: 274 White Plains Rd, Suite 6, Eastchester, M 1070
Bidder's Telephone Number: 914.337.1350 Fax Number: 914.337.1450
Bidder's E-Mail Address: Mmutino @intercontractingcorp. Com
Residence of Bidder (If Individual):
If Bidder is a Partnership, fill in the following blanks:
Names of Partners Residence of Partners
If Bidder is a Corporation, fill in the following blanks:
Organized under the laws of the State of
Name and Home Address of President: Michael Milino
140 West 86th Street #15C, New York, NY 10024
Name and Home Address of Secretary: Dario Cavaliere
50 Nelson Rd., Scarsdale, NY 10583
Name and Home Address of Treasurer: Michael Motino
Same as above
CITY OF NEW YORK C-1 BID BOOKLET DEPARTMENT OF DESIGN AND CONSTRUCTION DECEMBER 2013

PROJECT ID: SER002316

<u>TOTAL BID PRICE</u>: In the space provided below, the Bidder shall indicate its Total Bid Price in figures. Such Total Bid Price is set forth on the final page of the Bid Schedule.

TOTAL BID PRICE: (a/k/a BID PROPOSAL)

\$ 10,721,451.40 S128114

#### **BIDDER'S SIGNATURE AND AFFIDAVIT**

Bidder: In	ter Contracting Corp.		
By:	16/16		
DC	(Signature of Partner or corporate officer)		
Attacts	Secretary of Corporate Bidder		
Attest: (Corporate Seal)	· · · · · · · · · · · · · · · · · · ·	<b>4</b>	
/coxt	herryoid. Fresident Ho W. AFTS St. Apt 15C, Ny Ny	in Mut	of ic ph
	Affidavit on the following page should be subscribed and sworn to before a Notary Public		
	LESIJE A PASOUALONE Notary Public, State of New York. No. 03PA6283990 Obalitied in New York County Commit. Stan Expires June 17, 26, 17	<b>1</b>	27

#### **AFFIRMATION**

upon d New Y York, r	lebt, confork, and	and bidder affirms and declares that said bidder is not in arrears to the tract or taxes and is not a defaulter, as surety or otherwise, upon oblem has not been declared not responsible, or disqualified, by any agencies any proceeding pending relating to the responsibility or qualification contracts except:	igation to the City of cy of the City of New
. (If non-	e, the bi	dder shall insert the word "None" in the space provided above.)	
Full Na	ame of B	aidder: Inter Contracting Corp.  44 White Plains Rd., Suite 6, Open Mr.	
City_	Eas	Eclester State NY Zip Code	10709
CHECI	K ONE	BOX AND INCLUDE APPROPRIATE NUMBER:	
/	A -	Individual or Sole Proprietorship* SOCIAL SECURITY NUMBER	
<u>/</u> /	В-	Partnership, Joint Venture or other unincorporated organization EMPLOYER IDENTIFICATION NUMBER	
/X/	C-	Corporation EMPLOYER IDENTIFICATION NUMBER 7.4575508	
÷			
By:		12/15	
	Sign	ature	
Title:	Pro	s:dent	
	If a cor	poration, place seal here	$H_{1}(\mathcal{F}_{2},\mathcal{F}_{3})$

This affirmation must be signed by an officer or duly authorized representative.

\*Under the Federal Privacy Act the furnishing of Social Security Numbers by bidders on City contracts is voluntary. Failure to provide a Social Security Number will not result in a bidder's disqualification. Social Security Numbers will be used to identify bidders, proposers or vendors to ensure their compliance with laws, to assist the City in enforcement of laws, as well as to provide the City a means of identifying of businesses which seek City contracts.



CONTRACT PIN: 8502014SE0001C PROJECT ID: SER002316

#### BID SCHEDULE

- NOTE: (1) The Agency may reject a bid if it contains unbalanced bid prices. An unbalanced bid is considered to be for the performance of the items in question. proportionate share of the Bidder's anticipated profit, overhead costs, and other indirect costs, anticipated one containing lump sum or unit items which do not reflect reasonable actual costs plus a reasonable.
- (2) The following bid prices on Unit Price Contracts are to be paid for the actual quantities of the item numbers appliances of every description necessary to complete the entire work, as specified, and the removal of all of debris, temporary work and appliances. in the completed work or structure, and they cover the cost of all work, labor, material, tools, plant and
- (3) PLEASE BE SURE A LEGIBLE BID IS ENTERED, IN INK, FOR EACH ITEM.
  Alterations must be initialed in ink by the bidder.
- (4) The Extended Amount entered in Column 6 shall be the product of the Estimated Quantity in Column 3 times the Unit Price Bid in Column 5.
- (5) Prospective bidders must examine the Bid Schedule carefully and, before bidding, must advise the them. The pages of this Bid Schedule are numbered consecutively, as follows: B - 3 Through B - 27 Commissioner, in writing, if any pages are missing, and must request that such missing pages be furnished

PLEASE BE SURE A LEGIBLE BID IS ENTERED FOR EACH ITEM.
THE BIDDER SHALL INSERT THE TOTAL BID PRICE IN
THE BID FORM ON PAGE C-4 OF THIS BID BOOKLET.

PROJECT ID: SER002316

CONTRACT PIN: 8502014SE0001C

006	005	004	003	002	001	CQL 1 SEQ.NO
4.08 AA CONCRETE CURB (18" DEEP)	4.02 CA BINDER MIXTURE	4.02 AF-R ASPHALTIC CONCRETE WEARING COURSE, 2" THICK	4.02 AB-R ASPHALTIC CONCRETE WEARING COURSE, 1-1/2" THICK	4.01 RAJ ASPHALT MACADAM PAVEMENT, 9" THICK	4.01 RAG ASPHALT MACADAM PAVEMENT, 6" THICK	COL. 2
2,000.00	2,400.00	14,750.00	740.00	14,910.00	6,800.00	COL 8 ENGINEERIS ESTIMATE OF QUANTITY
LF.	TONS	S.Y.	S.Y.	S.Y.	S.Y.	COL.4
∞	512	21	81	5h	20	COLS. UNIT PRICE (IN FIGURES) DOLLARS
0	00	0	00	00	00	· · · · · ·
16,000	516,000	000,711	13,320	056,049	000,381	COL. 6 EXTENDED AMOUNT - ('IN FIGURES') DOLLARS
ပ္ပ	0	00	0	0	00	. CTS

PROJECT ID: SER002316

**CONTRACT PIN: 8502014SE0001C** 

	I					Ø	
012	011	010	009	008	007	GOL1	-
4.13 AAS 4" CONCRETE SIDEWALK (UNPIGMENTED)	4.09 CE CORNER STEEL FACED CONCRETE CURB (21" DEEP)	4.09 CD CORNER STEEL FACED CONCRETE CURB (18" DEEP)	4.09 AE STRAIGHT STEEL FACED CONCRETE CURB (21" DEEP)	4.09 AD STRAIGHT STEEL FACED CONCRETE CURB (18" DEEP)	4.08 BA CONCRETE CURB (21" DEEP)	COL 2  ITEM NUMBER and DESCRIPTION	BID SC
12,600.00	500.00	900.00	50.00	50.00	850.00	ENGINEER'S ESTIMATE OF QUANTITIY	BID SCHEDOLE FOR
ı. ı.	Г	ĻF.	ŗ.	, n	Ë	COL 4	
5	200	25	60	50	48	UNIT PRICE: (IN FIGURES): DOULARS	
0	8	0	00	8	0	S week to see the	
63,000	15,000		3,000	2,500	38,250	EXTENDED AMOUNT (IN FIGURES) DOLLARS	
0	8	0	0	O	8	101s	

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

018	017	016	015	014	013	SEQ. NÖ
4.18 D  MAINTENANCE TREE PRUNING (24" CAL. AND OVER)	4.18 C  MAINTENANCE TREE PRUNING (18" TO UNDER 24" CAL.)	4.18 B  MAINTENANCE TREE PRUNING (12" TO UNDER 18" CAL.)	4.18 A  MAINTENANCE TREE PRUNING (UNDER 12" CAL.)	4.13 DE EMBEDDED PREFORMED DETECTABLE WARNING UNITS	4.13 BAS 7" CONCRETE SIDEWALK (UNPIGMENTED)	COL. 2  ITEM NUMBER and DESCRIPTION
5.00	20.00	96.00	302.00	900.00	7,400.00	COL.3 ENGINEERS ESTIMATE OF QUANTITIY
EACH	EACH	EACH	EACH	S.F.	S.F.	COL 4
300	250	200	175	, <b>o</b>	ر.	COL 5 UNIT PRICE (IN FIGURES DOLLARS
8	8	8 .	00	00	9	CIS
1,500	5,000	19,700	52,850	4,500	40,700	COL 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS
00	0	0	8	0	8	OTS .

PROJECT ID: SER002316

**CONTRACT PIN: 8502014SE0001C** 

024	023	022	021	020	019	SEC NO
50.31MC15 15" E.S.V.P. STORM SEWER, ON CONCRETE CRADLE	50.21M3E042D 42" R.C.P. CLASS III STORM SEWER, ENCASED IN CONCRETE	50.21M3C042D 42" R.C.P. CLASS III STORM SEWER, ON CONCRETE CRADLE	50.21M3C030D 30" R.C.P. CLASS III STORM SEWER, ON CONCRETE CRADLE	50.21M3C024D 24" R.C.P. CLASS III STORM SEWER, ON CONCRETE CRADLE	4.21 TREE CONSULTANT	COL 2
220.00	213.00	1,780.00	685.00	1,215.00	1,000.00	COL 3 ENGINEER'S ESTIMATE OF QUANTITY
L.F.	LF.	LF.	LF.	ŗ.	P/HR	COL. 4 UNIT
285	5hh	365	275	290	<b>7</b> 5	COL 5 UNIT PAICE IN FIGURES
0	0	00	8	8	0	S)
67,700	584,76	647,700	188,375	357,350	75,000	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS
0	0 0	0	0	8	o O	G Provide

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

030	029	028	027	026	025	COL 1
51.11P006 STANDARD 6:-0" DIAMETER PRECAST MANHOLE	50.31SC10 10" E.S.V.P. SANITARY SEWER, ON CONCRETE CRADLE	50.31ME18 18" E.S.V.P. STORM SEWER, ENCASED IN CONCRETE	50.31ME15 15" E.S.V.P. STORM SEWER, ENCASED IN CONCRETE	50.31ME12 12" E.S.V.P. STORM SEWER, ENCASED IN CONCRETE	50.31MC18  18" E.S.V.P. STORM SEWER, ON CONCRETE CRADLE	COL 2  ITEM NUMBER and DESCRIPTION
4.00	6,100.00	195.00	120.00	30.00	350.00	COL 3 ENGINEER'S ESTIMATE OF QUANTITY
EACH	Ë	Ţ.	ĽF.	<u>'</u> ''	Ľ	COL 4
6,500	420	320	558	285	300	COL 5 UNIT PRICE (IN FIGURES
0	0	<b>0</b>	0	8	0	) (CIS
26,000	00 2,562,000	62,400	40,200	6,550	105,000	COL:6 EXTENDED AMOUNT (IN:FIGURES)
00	00	<b>0</b>	0	0	<b>0</b>	CC

PROJECT ID: SER002316

CONTRACT PIN: 8502014SE0001C

						The state of the s
036	035	034	033	032	031	SEQ.NO
51.21S0A3000V STANDARD SHALLOW MANHOLE TYPE A-3	51.21S0A2000V STANDARD MANHOLE TYPE A-2	51.21S0A1000V STANDARD MANHOLE TYPE A-1	51.11P010 STANDARD 10'-0" DIAMETER PRECAST MANHOLE	51.11P008 STANDARD 8'-0" DIAMETER PRECAST MANHOLE	51.11P007 STANDARD 7'-0" DIAMETER PRECAST MANHOLE	COL 2
6.00	11.00	31.00	1.00	1.00	1.00	COL 3 ENGINEER'S ESTIMATE OF QUANTITY
EACH	EACH	EACH	EACH	EACH	EACH	COL:4* UNIT
7,500	8/500	5,000	25,000	15,000	12,000	COL 5 UNITERICE (IN FIGURES DOLLARS
8	0	00	0	0	00	E (1) (1) (1) (1) (1) (1) (1) (1) (1) (1)
45,000	93,500	155,000	25,000	15,000	12,000	EXTENDED AMOUNT  * (IN FIGURES)  * (ACCUPANT OF THE PROPERTY O
0	<b>0</b>	0	Ö	8	9	OTS

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

042	041	040	039	038	037	SEQ NO
52.31V06S10 6" E.S.V.P. SPUR FOR HOUSE CONNECTION ON 10" E.S.V.P. SANITARY SEWER	52.21V08 8" E.S.V.P. RISER FOR HOUSE CONNECTION	52.11D12 12" DUCTILE IRON PIPE BASIN CONNECTION	51.41S001 STANDARD CATCH BASIN, TYPE 1	51.21S0C1042R STANDARD MANHOLE TYPE C-1 ON 42" R.C.P. SEWER	51.21S0B1000V STANDARD MANHOLE TYPE B-1	GOL 2  ITEM NUMBER and DESCRIPTION
175.00	20.00	1,100.00	52.00	7.00	4.00	ENGINEER'S ESTIMATE OF QUANTITY
EACH	V.F.	LF.	EACH	EACH	EACH	COL.4
	25	50	5,200	9,500	12,000	COL 5. UNIT PRICE (IN FIGURES
00	00	<b>00</b>	00	00	8	i CIS
175	1,500	55,000	270,400	66,500	000/34	COL.6: EXTENDED ÁMOUNT (IN FIGURES:)
00	0 0	0	Ç 6	8	9	CIS

PROJECT ID: SER002316

CONTRACT PIN: 8502014SE0001C

048	047	046	045	044	043	GOL 1
6.02 AAN UNCLASSIFIED EXCAVATION	53.11DR TELEVISION INSPECTION AND DIGITAL AUDIO-VISUAL RECORDING OF SEWERS	52.41V08N  NEW 8" E.S.V.P. HOUSE CONNECTION DRAIN ON CONCRETE CRADLE  Unit price bid shall not be greater than: \$80.00	52.41V06R 6" E.S.V.P. HOUSE CONNECTION DRAIN ON CONCRETE CRADLE (RECONNECTION)	52.41V06N  NEW 6" E.S.V.P. HOUSE CONNECTION DRAIN ON CONCRETE CRADLE Unit price bid shall not be greater than: \$ 75.00	52.31V08S10 8" E.S.V.P. SPUR FOR HOUSE CONNECTION ON 10" E.S.V.P. SANITARY SEWER	COL 2
5,400.00	11,300.00	75.00	20.00	1,750.00	6.00	COL 3 ENGINEER'S ESTIMATE OF QUANTITY
.Y.D	L.F.	L.F.	ŗ	Ę.	EACH	COL. 4 UNIT
95		66 60	150	75		COL, 5 ESPANDIANI) DOLARS DOLARS
0	8	000	0	00	00	S)
513,000	11,300	6,000	3,000	131,250	6	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS
0	00	 0	00	00	0	CIS

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

054	053	052	051	050	049	COL 10
6.49 TEMPORARY PAVEMENT MARKINGS (4" WIDE)	6.44 THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS (4" WIDE)	6.40 D ENGINEER'S FIELD OFFICE (TYPE D)	6.28 AA LIGHTED TIMBER BARRICADES	6.26 TIMBER CURB	6.25 RS TEMPORARY SIGNS	COL 2
12,900.00	23,100.00	24.00	1,600.00	11,000.00	9,500.00	COL.3. ENGINEER'S
LF.	LF.	MONTH	L.F.	L.F.	S.F.	COL 4
0	0	052	0	. O	× -	COL 5 UNIT PRICE UN FIGURES
0(	0.5	0	ol	01	\$ \$ 8	S10.
129	11,550	6,000	71	[10	9,500 17500 11,500	COL 6. EXTENDED AMOUNT (INFIGURES) DOLLARS
0	00	0	8	0	<b>\$ % ?</b>	C18

PROJECT ID: SER002316

CONTRACT PIN: 8502014SE0001C

060	059	058	057	056	055	GOL 1
						NO.
60.11R520 FURNISHING AND DELIVERING 20-INCH DUCTILE IRON RESTRAINED JOINT PIPE (CLASS 55)	6.87 PLASTIC BARRELS	6.68 PLASTIC FILTER FABRIC	6.67 SUBBASE COURSE, SELECT GRANULAR MATERIAL	6.53 REMOVE EXISTING LANE MARKINGS (4" WIDE)	6.52 CG CROSSING GUARD	COL 2  ITEM NUMBER and DESCRIPTION
210.00	4,400.00	10.000 10.000	3,800	12,900.00	3,700.00	ENGINEER'S ESTIMATE OF QUANTITY
L.F.	EACH	s.x	C.Y.	LF.	P/HR	COL. 4
501		9	15	0	10	UNIT PRICE UNIT PRICE (IN FIGURES DOLLARS
0	00	0/	8	0/	0	CTS
050,52	4,400	02%	57,000	129	37,000	EXTENDED AMOUNT (IN FIGURES)  DOLLARS
0	00	8	0	8	00	

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

6	C	C				Ø 4 4 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5
066	065	064	063	062	061	SEQ NO
60.12D12 LAYING 12-INCH DUCTILE IRON PIPE AND FITTINGS	60.12D08 LAYING 8-INCH DUCTILE IRON PIPE AND FITTINGS	60.12D06  LAYING 6-INCH DUCTILE IRON PIPE AND FITTINGS	60.11R612 FURNISHING AND DELIVERING 12-INCH DUCTILE IRON RESTRAINED JOINT PIPE (CLASS 56)	60.11R608 FURNISHING AND DELIVERING 8-INCH DUCTILE IRON RESTRAINED JOINT PIPE (CLASS 56)	60.11R606 FURNISHING AND DELIVERING 6-INCH DUCTILE IRON RESTRAINED JOINT PIPE (CLASS 56)	COL 2: ITEM NUMBER and DESCRIPTION
4,650.00	1,330.00	380.00	4,600.00	T,300.00	350.00	COL. 3. ENGINEERS ESTIMATE OF QUANTITY
, <b>7</b> 1	Ľ,	L.F.	L.F.	L.F.	L.F.	LODE:4
\$ \$	55	0)	. 65	Sh	25	UNITARRICE (IN EIGURES
0	00	, 8	00	0	8	CIS
255, 750	73,150	008%	230,000	58,500	05 + 18	COL 6 EXTENDED AMOUNT (IN FIGURES)
00	00	0	0	8	00	CIS

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

Market State of State

00 27,400	00	1,600	EACH	14.00	61.11DMM12 FURNISHING AND DELIVERING 12-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	071
0	000 6,000	1,500	EACH	4.00	61.11DMM08 FURNISHING AND DELIVERING 8-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	070
10,000	00	500	EACH	20.00	61.11DMM06 FURNISHING AND DELIVERING 6-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	069
123,500	0	9,500	TONS	13.00	60.13M0A24 FURNISHING AND DELIVERING DUCTILE IRON MECHANICAL JOINT 24 INCH DIAMETER AND SMALLER FITTINGS, INCLUDING WEDGE TYPE RETAINER GLANDS	068
14,400	00	60	LF.	240.00	60.12D20 LAYING 20-INCH DUCTILE IRON PIPE AND FITTINGS	067
COL 6 4 4 EXTENDED AMOUNT (IN FIGURES)		UNIT PRICE UNIT PRICE (IN FIGURES DOLLARS	COL44	CQL 3 ENGINEER'S ESTIMATE OF QUANTITY	COL 2	GOL 1

PROJECT ID: SER002316

CONTRACT PIN: 8502014SE0001C

			-				
EACH 250 00 1,000	250		EACH		4.00	61.12DMM08  SETTING 8-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	077
25 00 500		25				SETTING 6-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	
EACH	EACH	EACH	EACH		20.00	61.12DMM06	076
00	00					VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	
EACH	EACH	EACH	EACH		1.00	61.11TWC06	075
00 122	l 000					FURNISHING AND DELIVERING 4-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	
EACH	EACH	EACH	EACH		1.00	61.11TWC04	074
000 3	00					FURNISHING AND DELIVERING 3-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	
EACH	EACH	EACH	EACH	1	3.00	61.11TWC03	073
20,000 00 20,000	70,000 00	70,000				IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	
EACH	EACH	EACH	EACH		1.00	61.11DMM20	072
UNIT DOLLARS . GTS - DOLLARS -	DOLLARS. :		TINU	EW:	**OF QUANTITIY	TEM NUMBER and DESCRIPTION	SEQ NO
COL 4  UNIT PRICE EXTENDED AMOUNT (IN FIGURES) (IN FIGURES)			60F.4		ENGINEER'S ESTIMATE	COL-2	COLL
				to the	CHERTON AND COMPANY OF THE PROPERTY OF THE PRO		THE RESERVE OF THE PARTY OF THE

PROJECT ID: SER002316

CONTRACT PIN: 8502014SE0001C

20.00	EACH	1,100		0
61.12TWC06  SETTING 6-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS		EACH	EACH CONTRACTOR	
61.12TWC04 1.00 SETTING 4-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS		EACH		EACH ( 00
61.12TWC03 SETTING 3-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS		EACH	EACH (	-
61.12DMM20 SETTING 20-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS		EACH	500	. ,*
61.12DMM12  SETTING 12-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS		EACH	250	
ENGINEER'S  ESTIMATE  OF QUANTITY	(新星)(A)	UNIT GOL	UNITEPRICE (IN FIGURES)	OLL I
ולים לילות היים לילות היים לילות היים לילות	r		-	

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

089	088	087	086	085	084	SEO NO
64.11ST WITHDRAWING AND REPLACING HOUSE SERVICES USING SMALLER THAN 1-1/2-INCH SCREW TAPS	64.11EL WITHDRAWING AND REPLACING HOUSE SERVICES USING 1-1/2-INCH OR LARGER SCREW TAPS	63.11VC FURNISHING AND DELIVERING VARIOUS CASTINGS	62.14FS FURNISHING, DELIVERING AND INSTALLING HYDRANT FENDERS	62.13RH REMOVING HYDRANTS	62.12SG SETTING HYDRANTS COMPLETE WITH WEDGE TYPE RETAINER GLANDS	COL: 2
84.00	4.00	16.00	42.00	15.00	20.00	COL.3. ENGINEER'S ESTIMATE OF QUANTITY
EACH	EACH	TONS	EACH	EACH	EACH	COL.4 UNIT
055	001	05£	521	00	950	COL.5. UNIT PRICE (IN FIGURES
8	00	00	00	00	00	OIS (
29,400	008	000/21	052,2	1,500	19,000	EXTENDED AMOUNT (IN FIGURES) DOLLARS
9	00	- <b>0</b> 0	<b>0</b> 0	ှ ၀	8	· CIS

PROJECT ID: SER002316

CONTRACT PIN: 8502014SE0001C

095	094	093	092	091	090	SEQ. NO
64.13WC12 FURNISHING, DELIVERING AND INSTALLING WET CONNECTION SLEEVE ON 12-INCH WATER MAIN PIPE WITH VARIOUS OUTLETS	64.13WC08 FURNISHING, DELIVERING AND INSTALLING WET CONNECTION SLEEVE ON 8-INCH WATER MAIN PIPE WITH VARIOUS OUTLETS	64.12ESLT EXTENDING HOUSE SERVICE WATER CONNECTIONS (LESS THAN 3-INCH DIAMETER)	64.12ESEG EXTENDING HOUSE SERVICE WATER CONNECTIONS (EQUAL TO OR GREATER THAN 3-INCH DIAMETER)	64.12COLT  CUTTING AND OFFSETTING HOUSE SERVICE WATER CONNECTIONS (LESS THAN 3-INCH DIAMETER)	64.12COEG  CUTTING AND OFFSETTING HOUSE SERVICE WATER CONNECTIONS (EQUAL TO OR GREATER THAN 3-INCH DIAMETER)	COLUZ.
3.00	1.00	450.00	60.00	300.00	100.00	COL 3 ENGINEERS: ESTIMATE
EACH	EACH	LF.	ĻF.	Ľ.	LF.	COL 4
MA -		110	25	100	25	COL.5 UNIT PRICE (IN FIGURES) DOLLARS
0	0	00	8	8	8	
2	<i>1</i> · ·	49,500	1,500	30,000	7,500	COL.6 (JN FIGURES)  DOLLARS
°C	00	8	8	8	<sup>3</sup> 8	C September 200

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

101 65.61SS FURNISHIN REINFORC	100 65.51PC FURNISHIN AND PREC	099 65.31FF FURNISHIN Unit price	098 65.21PS FURNISHIN Unit price I	097 65.1 FURN WASH	096 64.1	SEG NO
65.61SS FURNISHING, DELIVERING AND PLACING STRUCTURAL, REINFORCING AND MISCELLANEOUS STEEL	65.51PC FURNISHING AND PLACING CAST-IN-PLACE CONCRETE CLASS 40 AND PRECAST CONCRETE CLASS 50	65.31FF FURNISHING, DELIVERING AND PLACING FILTER FABRIC Unit price bid shall not be less than: \$ 0.10	65.21PS FURNISHING AND PLACING POLYETHYLENE SLEEVE Unit price bid shall not be less than: \$ 0.50	65.11BR FURNISHING, DELIVERING AND INSTALLING BANDS, RODS, WASHERS, ETC., COMPLETE, FOR RESTRAINING JOINTS	64.13WC20 FURNISHING, DELIVERING AND INSTALLING WET CONNECTION SLEEVE ON 20-INCH WATER MAIN PIPE WITH VARIOUS OUTLETS	COL 2  ITEM NUMBER and DESCRIPTION
34,000.00	40.00	42,100.00	4,000.00	275.00	3.00	COL 3 ENGINEER'S ESTIMATE OF QUANTITY
LBS.	C.Y.	S.F.	L.F.	LBS.	EACH	COL 4
O	0	0	0			COL.5 UNIT PRICE (IN FIGURES
8	0	<b>?</b>	50	00	00	iejs
340	O	012%	2,000	275	, W	COL 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS
0	40	्र <b>०</b>	)   0	8	00	CIS

PROJECT ID: SER002316

CONTRACT PIN: 8502014SE0001C

107	106	105	104	103	102	COL.1
7.88 AC  BAITING OF RODENT BAIT STATIONS  Unit price bid shall not be less than: \$8.50	7.88 AB RODENT BAIT STATIONS Unit price bid shall not be less than: \$ 60.00	7.88 AA RODENT INFESTATION SURVEY AND MONITORING Unit price bid shall not be less than: \$5,200.00	7.36 PEDESTRIAN STEEL BARRICADES	7.13 B  MAINTENANCE OF SITE  Unit price bid shall not be less than: \$7,500.00	65.71SG FURNISHING, DELIVERING AND PLACING SCREENED GRAVEL OR SCREENED BROKEN STONE BEDDING	COL 2  TIEM NUMBER and DESCRIPTION
1,050.00	1,050.00	1.00	22,700.00	18.00	100.00	CQL 3 ENGINEER'S ESTIMATE OF QUANTITY
EACH	EACH	LS.	L.F.	MONTH	C.Y.	GOL 4
8	60	5,200	S.	7,500	•	COL.5 UNIT PRICE (IN FIGURES DOLLARS
8	00	8	8	0	0_	OTS:
8,925	63,000	5,700	113,500	135,000		EXTENDED AMOUNT (IN RIGURES) DOLLARS
0	0	00	8	0	0	CTS

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

113	112	111111111111111111111111111111111111111	110	109	108	SEQ NO
70.81CB CLEAN BACKFILL Unit price bid shall not be less than: \$ 15.00	70.71SB STONE BALLAST Unit price bid shall not be less than: \$ 15.00	70.61RE ROCK EXCAVATION	70.51EO  EXCAVATION OF BOULDERS IN OPEN CUT  Unit price bid shall not be less than: \$75.00	70.31FN FENCING Unit price bid shall not be less than: \$ 2.00	7.88 AD WATERBUG BAIT APPLICATIONS Unit price bid shall not be less than: \$65.00	COL 2
10,800.00	170.00	50.00	70.00	31,400.00	325.00	COL'3 ENGINEER'S ESTIMATE OF QUANTITIY
C.Y.	C.Y.	C.Y.	C.Y.	L.F.	BLOCK	COL 4
54	5		54	<b>2</b>	65	UNIT PRICE (IN FIGURES DOLLARS
8	8	<sub>ි</sub>	8	00	8	Ols
810,000	2,550	20	5,250	62,800	21,125	COL 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS
00	0	0	G 0	0	<b>,</b>	CTS

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

119	118	117	116	115	114	COL 1
73.31AE0 ADDITIONAL EARTH EXCAVATION INCLUDING TEST PITS (ALL DEPTHS) Unit price bid shall not be less than: \$ 20.00	73.21AC  ADDITIONAL CONCRETE  Unit price bid shall not be less than: \$ 62.50	73.11AB  ADDITIONAL BRICK MASONRY  Unit price bid shall not be less than: \$62.50	72.11HF  HYDRAULIC FILL FOR ABANDONED SEWERS AND WATER MAINS	70.91SW20 FURNISHING AND PLACING SHEETING AND BRACING IN TRENCH FOR WATER MAIN PIPE 20-INCH IN DIAMETER	70.91SW12 FURNISHING AND PLACING SHEETING AND BRACING IN TRENCH FOR WATER MAIN PIPE 12-INCH IN DIAMETER AND LESS	COL 2  ITEM:NUMBER and DESCRIPTION
700.00	300.00	50.00	600.00	2,000.00	7,300.00	COL 3 : ENGINEER'S : ESTIMATE OF QUANTITIY
C.Y.	c.Y.	C.Y.	C.Y.	S.F.	S. T.	COL 4
10	62	62	• •	0	0	Sandatinn Sandatinn Siga
0	8	20	8	2	0	CIO
14,000	18,750	3,125	600	20	73	COL 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS
8	ő	0	9	δ	8	CIS

PROJECT ID: SER002316

**CONTRACT PIN: 8502014SE0001C** 

124		123	122	121	120	SEQ. NO
9.30 STORM WATER POLLUTION PREVENTION	ALLOWANCE FOR ANTI-FREEZE ADDITIVE IN CONCRETE PRICE BID SHALL BE FOR THE FIXED SUM OF \$ 2,000.00	9.04 HW	8.08 VARIABLE MESSAGE BOARD	73.51AS  ADDITIONAL STEEL REINFORCING BARS  Unit price bid shall not be less than: \$ 1.00	73.41AG  ADDITIONAL SELECT GRANULAR BACKFILL  Unit price bid shall not be less than: \$ 15.00	COL 2  FIEM NUMBER and DESCRIPTION
1.00		1.00	2.00	40,500.00	2,300.00	COL 3 ENGINEER'S ESTIMATE OF QUANTITY
L.S.		F.S.	EACH	LBS.	C.Y.	COL 4
5,000		2.000 : 00	500	-	51	COL <sub>L</sub> 5 UNIT PRICE (IN FIGURES) DOLLARS CTS
8		8	8	00	. 00	OIS
5,000		2.000:00	1,000	00 5 0 b	34,500	COL. 6 ** *EXTENDED AMOUNT* (IN FIGURES) ** DOLLARS
00	4) i (	3	00	8	00	टाड

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

130	129	128	127	126	125	SEQ NO
UTL-6.03 REMOVAL OF ABANDONED GAS FACILITIES. ALL SIZES. (S6.03) Unit price bid shall not be less than: \$ 15.00	UTL-6.02  EXTRA EXCAVATION FOR THE INSTALLATION OF CATCH BASIN SEWER DRAIN PIPES WITH GAS INTERFERENCES (S6.02)  Unit price bid shall not be less than: \$ 715.00	UTL-6.01.9 GAS MAIN CROSSING WATER MAIN UP TO 20" IN DIAMETER (S6.01) Unit price bid shall not be less than: \$ 485.00	UTL-6.01.8  GAS SERVICES CROSSING TRENCHES AND/OR EXCAVATIONS (S6.01)  Unit price bid shall not be less than: \$ 465.00	UTL-6.01.3 GAS MAIN CROSSING SEWER 36" THRU 42" IN DIAMETER (S6.01) Unit price bid shall not be less than: \$ 2,040.00	UTL-6.01.1  GAS MAIN CROSSING SEWER UP TO 24" IN DIAMETER (S6.01)  Unit price bid shall not be less than: \$ 1,040.00	COL 2  ITEM NUMBER and DESCRIPTION
3,200.00	9.00	6.00	29.00	2.00	10.00	COL 3 ENGINEER'S ESTIMATE 3 OF QUANTITY
LF.	EACH	EACH	EACH	EACH	EACH	COL 4
5	7/5	584	<i>46</i> \$	2,040	1,040	DOLLARS
° °	0	0	0	00	0	) ) )
48,000	6,435	7,910	13,485	080%	10,400	COL.6 EXTENDED AMOUNT (IN FIGURES) DOLLARS
8	8	0	ं <b>०</b>	0	0	CIS

PROJECT ID: SER002316
CONTRACT PIN: 8502014SE0001C

		T			44
135	134	133	132	131	SEQ NO
UTL-6.07 TEST PITS FOR GAS FACILITIES (S6.07) Unit price bid shall not be less than: \$ 100.00	UTL-6.06  SPECIAL CARE EXCAVATION AND BACKFILLING (S6.06)  Unit price bid shall not be less than: \$ 180.00	UTL-6.05  ADJUST HARDWARE TO GRADE BY RESETTING. (ROAD RECONSTRUCTION.) (S6.05)  Unit price bid shall not be less than: \$ 65.00	UTL-6.04  ADJUST HARDWARE TO GRADE USING SPACER RINGS/ADAPTORS. (STREET REPAVING.) (S6.04)  Unit price bid shall not be less than: \$35.00	UTL-6.03.1  REMOVAL OF ABANDONED GAS FACILITIES WITH POSSIBLE COAL TAR WRAP. ALL SIZES. (S6.03)  Unit price bid shall not be less than: \$ 25.00	ITEM:NUMBER and DESCRIPTION
100.00	1,000.00	30.00	25.00	800.00	ENGINEER'S ESTIMATE OF QUANTITY
C.Y.	C.Y.	EACH	EACH	L.F.	COL 4
00	08)	<b>53</b>	25	25	UNIT RRICE (IN:FIGURES DOLLARS
00	° °	, <b>6</b>	8	00	) CIS
(0,000	000/081	056"	248	20,000	COL.6 EXTENDED AMOUNT (IN FIGURES)
8	, O	00	0	0	CIS

2/21/2014 12:00 AM

# NEW YORK CITY DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE - BUREAU OF DESIGN

PROJECT ID: SER002316

CONTRACT PIN: 8502014SE0001C

### BID SCHEDULE FORM

			136	SEQ NO
	PRICE BID SHALL BE FOR THE FIXED SUM OF \$ 30,000.00	GAS INTERFERENCES AND ACCOMMODATIONS	UTL-GCS-2WS	COL 25  ITEM NUMBER and DESCRIPTION
			1.00	ENGINEER'S ESTIMATE OF QUANTITY
			F.S.	COL.4.
	- ~~		30,000 00	COL.5 UNIT PRICE (IN FIGURES)
			<u> </u>	o see
:	• • •-		30,000 00	COL 6 (TENDED AMOUNT) (IN EIGURES)  DOLLARS CTS

SUB-TOTAL: \$ 10,321, 451.40

		137
BID PRICE OF MOBILIZATION SHALL NOT EXCEED 4% OF THE ABOVE SUB-TOTAL PRICE.	MOBILIZATION	6.39 A
		1.00
		L.S.
	400,000	
	0	
	400,000	
(	0	

TOTAL BID PRICE: \$ 10,721, 451.40

PLEASE BE SURE A LEGIBLE BID IS ENTERED FOR EACH ITEM.
THE BIDDER SHALL INSERT THE TOTAL BID PRICE IN
THE BID FORM ON PAGE C-4 OF THIS BID BOOKLET.

#### **Qualification Form**

List previous projects completed to meet the special experience requirements for this contract. Please photocopy this form for submission of all required projects.

Name of Contractor: Inter Contracting Corp.
Name of Project: SER 002292: Holly Place
Location of Project: Holly Places Stoken Island
Owner or Owner's representative (Architect or Engineer) who is familiar with the work performed:
Name: Shahed Ahmed Title: Phone Number:
Brief description of the Project completed or the Project in progress: SEROO2Z97:
Const. of Seners in Holly Place, Staten Island Sever Construction
Was the Project performed as a prime, a subcontractor or a sub-subcontractor: Prime
Amount of Contract, Subcontract or Sub-subcontract: \$3,878,244.00
Start Date and Completion Date: 1/01/2010 - 4/30/2012
*************
Name of Contractor:
Name of Project:
Location of Project:
Owner or Owner's representative (Architect or Engineer) who is familiar with the work performed:
Name:
Title:Phone Number:
Brief description of the Project completed or the Project in progress:
Was the Project performed as a prime, a subcontractor or a sub-subcontractor:
Amount of Contract, Subcontract or Sub-subcontract:
Start Date and Completion Date:

(NO TEXT ON THIS PAGE)

24 Co. 18 20

Linear Commencing Copp.

Carried to week to grade to grade

and the first of the second se

The state of the s

Tax ID #:_	20	-4	5	75	50	8
------------	----	----	---	----	----	---

SCHEDULE B – M/WBE Utilization Plan

art I: M/WBE Participation Goals

art I to be completed by contracting agency

APT E-	
PIN#:	85014B0130

Contract Overview				
APT E- Pin #	85014B0130	FMS Pr	oject ID#:	SER002316
Project Title/ Agency PIN #	CONSTRUCTION OF STORM & S	SANITARY SEW	/ERS & APPURT	ENANCES/8502014SE00010
Bid/Proposal Response Date	MAY 28, 2014			
Contracting Agency	Department of Design and Co	onstruction		
Agency Address	30-30 Thomson Avenue City	Long Island	d City State	NY Zip Code 1110
Contact Person	Diana A. Benjamin	Title	A	on & Compliance Analyst
Telephone #	(718) 391-3470	Email	BenjamiDi@	ddc.nyc.gov
Project Description (atta	ch additional pages if necessary)			

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;

VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND,

WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

INCLUDING WATER MAIN WORK

Together With All Work Incidental Thereto

BOROUGH OF STATEN ISLAND CITY OF NEW YORK

#### M/WBE Participation Goals for Services

Enter the percentage amount for each group of for an unspecified goal. Please note that there are no goals for Asian Americans in Professional Services.

Prime Contract Industry: Construction

Group	Percentage		
Unspecified*	10%		
or			
Black American	UNSPECIFIED*		
Hispanic American	UNSPECIFIED*		
Asian American	UNSPECIFIED*		
Women	UNSPECIFIED*		
Total Participation Goals	10%	Line 1	

Vote: For this procurement, individual ethnicity and gender goals are not specified. The Total Participation Goal for instruction contracts may be met by using either Black-American, Hispanic-American, Asian American, or Women certified firms or any combination of such firms.

Tax ID #: 20-4	15	75508	سا
----------------	----	-------	----

APT E-	
PIN #:	85014B0130

#### SCHEDULE B - Part II: M/WBE Participation Plan

Part II to be completed by the bidder/proposer.

Please note: For Non-M/WBE Prime Contractors who will NOT subcontract any services and will self-perform the entire contract, you must obtain a FULL waiver by completing the Waiver Application on pages 17 and 18 and timely submitting it to the contracting agency pursuant to the Notice to Prospective Contractors. Once a FULL WAIVER is granted, it must be included with your bid or proposal and you do not have to complete or submit this form with your bid or proposal.

Section I: Prime Contractor Contact Infor	mation						
Tax ID# 20-4575508 FMS Vendor ID#							
Business Name Inter Contracting Corp Contact Person Michael Mit							
Business Name <u>Inter Contracting Corp</u> Contact Person <u>Michael Mulino</u> Address <u>274 White Plains Road, Suite 6, Easechester, NY 10707</u> Tolophone # 911732 126							
Telephone # 914.337.1350 Email Mnutino Pinter contracting Corp. com							
Section II: M/WBE Utilization Goal Calcul				ubsec	ction.		
PRIME CONTRACTOR ADOPTING AG	ENCY M/WBE PAR	TIC	IPATION GOALS				
For Prime Contractors (including Qualified Joint Ventures and M/WBE firms) adopting Agency M/WBE	Total Bid/Proposal Value		Agency Total Participation Goals (Line 1, Page 13)		Calculated M/WBE Participation Amount		
Participation Goals.	10,721,451.40		10%		1,072,145.14		
Calculate the total dollar value of your total bid that you agree will be awarded to M/WBE subcontractors for services and/or credited to an M/WBE prime contractor or Qualified Joint Venture.		•					
Please review the Notice to Prospective Contractors for more information on how to obtain credit for M/WBE participation.	\$	x		=	\$ Line 2		
PRIME CONTRACTOR OBTAINED PAI PARTICIPATION GOALS	RTIAL WAIVER APP	RC	OVAL: ADOPTING MO	DIFII	ED M/WBE		
For Prime Contractors (including Qualified Joint Ventures and M/WBE firms) adopting Modified M/WBE	Total Bid/Proposal Value		Adjusted Participation Goal (From Partial Waiver)		Calculated M/WBE Participation Amount		
Participation Goals.  Calculate the total dollar value of your total bid that you agree will be awarded to M/WBE subcontractors for services and/or credited to an M/WBE prime contractor or Qualified Joint Venture.  Please review the Notice to Prospective Contractors for more information on how to							
obtain credit for M/WBE participation.	\$	x		=	\$ Line 3		

Tax ID #: 20-4575508		APT E- PIN #:	85014B0130	
section III: M/WBE Utilization Plane review the Notice to Prospective participation. Check applicable	e Contractors for more inforn	nation on how to obta	in credit for M/WBE	_
As an M/WBE Prime Contract contract the value of which is at le work subcontracted to non-M/WBI Please check all that apply to Prim  MBE  WBE	east the amount located on Line E firms will not be credited towa ne Contractor:	s 2 or 3 above, as appl ards fulfillment of M/WE	icable. The value of any BE Participation Goals.	
As a Qualified Joint Venture wand/or the value of any work subcabove, as applicable. The value of fulfillment of M/WBE Participation As a non M/WBE Prime Control least the amount located on Lines	contracted to other M/WBE firms of any work subcontracted to no Goals.  ractor that will enter into subcon	s is at least the amount on M/WBE firms will not	located on Lines 2 or 3 be credited towards	
Section IV: General Contract Info	**************************************			
services, regardless of M/WBE	Enter brief description of the type(s) a subcontracting if awarded this contrac participation by MBEs and/or WBEs a end. Use additional sheets if necessary	and dollar value of subcontra ct. For each item, indicate w and the time frame in which s ary.	cts for all/any services you plan on thether the work is designated for such work is scheduled to begin and	
To the second of	1. Paving \$1,100,000	MBE END of	Loyect	
✓ Scopes of Subcontract Work	2. 3. 4. 5. 6. 5. 6. 6. 6. 6. 6. 6. 6. 6. 6. 6. 6. 6. 6.			17. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.
·				

### Section V: Vendor Certification and Required Affirmations

I hereby

- 1) acknowledge my understanding of the M/WBE participation requirements as set forth herein and the pertinent provisions of Section 6-129 of the Administrative Code of the City of New York ("Section 6-129"), and the rules promulgated thereunder:
- 2) affirm that the information supplied in support of this M/WBE Utilization Plan is true and correct;
- 3) agree, if awarded this Contract, to comply with the M/WBE participation requirements of this Contract, the pertinent provisions of Section 6-129, and the rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract;
- 4) agree and affirm that it is a material term of this Contract that the Vendor will award the total dollar value of the M/WBE Participation Goals to certified MBEs and/or WBEs, unless a full waiver is obtained or such goals are modified by the Agency; and
- 5) agree and affirm, if awarded this Contract, to make all reasonable, good faith efforts to meet the M/WBE Participation Goals, or If a partial waiver is obtained or such goals are modified by the Agency, to meet the modified Participation Goals by soliciting and obtaining the participation of certified MBE and/or WBE firms.

	r Auts-Allein og en stellig en er i linge i Rum en das Albaid i elle skilding legalises for timbum og utt fre ag	TR (1965) (19 <b>년 12월</b> ) 16 1년
Signature	Date 5/27/14	
Print Name Michael Miting	Title President	
•		

### SCHEDULE B – PART III – REQUEST FOR WAIVER OF M/WBE PARTICIPATION REQUIREMENT

Contract Overview			
Tax ID#		FMS	Vendor ID #
Business Name			
Contact Name	Telepho	ne #	Email
Type of Procurement	☐ Competitive Sealed Bids	Other	Bid/Response Due Date
APT E-PIN # (for this procurement):		Spiritise Sign	Contracting Agency:
%	on Goals as described in bid/so		cuments.
	Agency M/WBE Participation Goal		
	cipation Goal as anticipated by ve	endor seeki	ng waiver
<u></u> %	f the total contract value anticipa	ted <u>in good</u>	faith by the bidder/proposer to be subcontracted
			ne Contractor or Qualified Joint Venture.
basis ibi vvalver Redi	uest: Check appropriate box & e	xplain in de	etail below (attach additional pages if needed)
Vendor does not sul elf with its own emplo	bcontract services, and has the	capacity a	nd good faith intention to perform all such wor
en with its own empit	Jyees.		
e vendor will self-perf	orm and subcontract to other ve	act. (Attac endors or c	% than bid/solicitation describes, and has the h subcontracting plan outlining services that onsultants.)  The M/WBE Participation Goal above. Explain
Vendor will self-perform vendor has other led der separate cover.  References	orm and subcontract to other vergitimate business reasons for p	act. (Attacendors or control of the	h subcontracting plan outlining services that onsultants.)
e vendor will self-performers  Vendor has other legider separate cover.  References	orm and subcontract to other vergitimate business reasons for particles of the particles of the performed for NYC agencies tracts. Add more pages if necessitizets.	act. (Attace endors or co roposing the roposing the roposing the roposition of the r	h subcontracting plan outlining services that onsultants.)  The M/WBE Participation Goal above. Explain  The Middle Information for each subcontract awarded in
vendor will self-performance of such conferences	orm and subcontract to other vergitimate business reasons for p	act. (Attacendors or control of c	h subcontracting plan outlining services that onsultants.)  ne M/WBE Participation Goal above. Explain
Vendor has other legater separate cover.  References. St 3 most recent contract formance of such con  CONTRACT NO.  Total Contract Amount \$	cts performed for NYC agencies tracts: Add more pages if necess	act. (Attacendors or control of c	h subcontracting plan outlining services that onsultants.)  The M/WBE Participation Goal above. Explain  The Middle Information for each subcontract awarded in
vendor will self-perfective vendor has other leg der separate cover.  eferences if 3 most recent contractormance of such con  CONTRACT NO.  Total Contract  Amount \$ Item of Work	cts performed for NYC agencies tracts. Add more pages if necessions for pages	act. (Attacendors or condors or c	h subcontracting plan outlining services that onsultants.)  The M/WBE Participation Goal above. Explain  Jude Information for each subcontract awarded in the participation between the participation of the participation
vendor will self-perfect vendor has other leg der separate cover.  eferences.  if 3 most recent contrationmance of such contrationmance of such contrationmance version with the such contract amount \$  Item of Work  Subcontracted and	cts performed for NYC agencies tracts. Add more pages if necess  AGEN  Total Amore	act. (Attacendors or condors or c	h subcontracting plan outlining services that onsultants.)  se M/WBE Participation Goal above. Explain  lude information for each subcontract awarded in
vendor will self-perfective vendor has other leg der separate cover.  eferences  3 most recent contrationmance of such contract Amount  Item of Work Subcontracted and alue of subcontract	cts performed for NYC agencies tracts. Add more pages if necessity and Subcontract described by Subcontracted a Subcontracted as	act. (Attacendors or condors or c	h subcontracting plan outlining services that onsultants.)  The M/WBE Participation Goal above. Explain  Subcontract awarded in the plant of Work Subcontracted and
vendor will self-perfect vendor has other leg der separate cover.  eferences.  it 3 most recent contrationmance of such contract Amount \$  Item of Work Subcontracted and alue of subcontract  CONTRACT NO.	cts performed for NYC agencies tracts. Add more pages if necessity and Subcontract de Subcontract de Value of subcontract de AGEN	act. (Attace and or control of the c	h subcontracting plan outlining services that onsultants.)  The M/WBE Participation Goal above. Explain  Subcontract awarded in the plant of Work Subcontracted and
vendor will self-perfective vendor has other leg der separate cover.  eferences  3 most recent contrationmance of such contract Amount  Item of Work Subcontracted and alue of subcontract	cts performed for NYC agencies tracts. Add more pages if necessitracts. Add more pages if necessitracts add more pages if necessitracts. Add more pages if necessitracts add more pages if necessitracts add more pages if necessitracts. Add more pages if necessitracts add more pages if n	act. (Attace and or control of the c	h subcontracting plan outlining services that onsultants.)  ne M/WBE Participation Goal above. Explain  Jude Information for each subcontract awarded in the property of the p
vendor will self-perferences.  eferences.  it 3 most recent contract contract Amount \$ ltem of Work Subcontracted and alue of subcontract Amount \$  CONTRACT NO.  Total Contract and alue of subcontract and alue of subcontract Amount \$  ltem of Work Subcontract S	cts performed for NYC agencies tracts. Add more pages if necessity and Subcontract de Subcontract de Value of subcontract de AGEN	act. (Attace and or control or co	h subcontracting plan outlining services that onsultants.)  se M/WBE Participation Goal above. Explain  lude information for each subcontract awarded in  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract  DATE COMPLETED
vendor will self-perfect vendor has other leg der separate cover.  eferences t 3 most recent contratormance of such contract Amount \$ ltem of Work Subcontracted and alue of subcontract Amount \$ tem of Work Subcontract Amount \$ ltem of Work Subcontracted and	cts performed for NYC agencies tracts. Add more pages if necessity and Subcontracted a Value of subcontracted a Value of subcontracted a Subco	act. (Attace and or condors or co	h subcontracting plan outlining services that onsultants.)  se M/WBE Participation Goal above. Explain  lude information for each subcontract awarded in  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract  DATE COMPLETED  Item of Work Subcontracted and Value of Subcontracted and
vendor will self-perferences.  eferences.  it 3 most recent contract contract Amount \$ ltem of Work Subcontracted and alue of subcontract Amount \$ ltem of Work Subcontract contract co	intention to do so on this controrm and subcontract to other vergitimate business reasons for publicates and more pages if necessariacts. Add more pages if necessariacts add more pages if necessariacts. Add more pages if necessariacts add more pages if necessariacts add more pages if necessariacts. Add more pages if necessariacts add more pages if neces	act. (Attace and or condors or co	h subcontracting plan outlining services that onsultants.)  se M/WBE Participation Goal above. Explain  lude information for each subcontract awarded in the property of the property of the participation of the property of
vendor will self-perfect vendor has other leg der separate cover.  Leferences  It 3 most recent contract contract contract Amount \$  Item of Work Subcontract and alue of subcontract Amount \$  Item of Work Subcontract contract co	cts performed for NYC agencies tracts. Add more pages if necessitracts. Add more pages if necessitracts add more pages if necessitracts. Add more pages if necessitracts add value of subcontracted ad	act. (Attace and or continued to the continue of the continue	h subcontracting plan outlining services that onsultants.)  ne M/WBE Participation Goal above. Explain    Jude Information for each subcontract awarded in the subcontract awarded in the subcontract awarded in the subcontract and value of subcontract awarded in the
vendor will self-perferences.  Seferences.	and subcontract to other very gitimate business reasons for process reacts. Add more pages if necess reacts reacts. Add more pages if necess reacts reacts. Add more pages if necess reacts r	act. (Attace and or continued to the con	h subcontracting plan outlining services that onsultants.)  se M/WBE Participation Goal above. Explain  lude information for each subcontract awarded in  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract  DATE COMPLETED  Item of Work Subcontracted and Value of Subcontracted and
e vendor will self-perfected and	cts performed for NYC agencies tracts. Add more pages if necessitracts. Add more pages if necessitracts add more pages if necessitracts. Add more pages if necessitracts add value of subcontracted ad	act. (Attace and or continued to the con	h subcontracting plan outlining services that onsultants.)  ne M/WBE Participation Goal above. Explain    Jude Information for each subcontract awarded in the subcontract awarded in the subcontract awarded in the subcontract and value of subcontract awarded in the
Vendor has other legider separate cover.  References St 3 most recent contract formance of such con  CONTRACT NO.  Total Contract Amount \$ Item of Work Subcontracted and value of subcontract Amount \$ Item of Work Subcontract CONTRACT NO.  Total Contract Amount \$ Item of Work Subcontract Amount \$ Item of Work CONTRACT NO.  Total Contract Amount \$ Item of Work Subcontracted and value of subcontracted and value of subcontract CONTRACT NO. Total Contract	cts performed for NYC agencies tracts. Add more pages if necessity and Subcontracted a Value of subcontracted a Value of subcontracted a Value of subcontracted a Value of subcontracted a AGEN  AGEN  Total Amore pages if necessity and the subcontracted a Value of Subcontr	act. (Attace and or continued \$ ork and act continued	h subcontracting plan outlining services that onsultants.)  The M/WBE Participation Goal above. Explain  Inde Information for each subcontract awarded in the plant of the pla

(Complete ONLY if vendor has performed fewer than 3 New York City contracts.) DATE COMPLETED **TYPE OF Contract** Manager at entity that hired vendor (Name/Phone No./Email) **Total Contract Total Amount** Amount \$ Subcontracted \$ Type of Work Subcontracted DATE COMPLETED **TYPE OF Contract** AGENCY/ENTITY Manager at agency/entity that hired vendor (Name/Phone No./Email) **Total Contract Total Amount** Amount \$ Subcontracted \$ Item of Work Item of Work Item of Work Subcontracted Subcontracted and Subcontracted and and Value of Value of subcontract Value of subcontract subcontract DATE COMPLETED TYPE OF Contract AGENCY/ENTITY Manager at entity that hired vendor (Name/Phone No./Email) **Total Contract Total Amount** Amount \$ Subcontracted \$ Item of Work Item of Work Item of Work Subcontracted Subcontracted and Subcontracted and and Value of Value of subcontract Value of subcontract subcontract VENDOR CERTIFICATION: I hereby affirm that the information supplied in support of this waiver request is true and correct, and that this request is made in good faith. Date:\_\_\_\_\_ Signature: Print Name: Title: Shaded area below is for agency completion only Vasng Kaliberon Tring of Net Office Repprovis gipkehisa arogurshisnikotsiesakaarroyal valvek letermitations. enikarenerakonakokatek *l*ative e Demierle III s ราสาราโรงคราบรายสาราชาการเกาะเรีย aysach karionisalian. Gisal

List 3 most recent contracts performed for other entities. Include information for each subcontract awarded in

performance of such contracts. Add more pages if necessary.

### Mehak Kapoor, 2014-10-15 14:54:25

RD attachment- once the hearing is completed, are there any additional steps or does it infer that the matter has been resolved? Thank You

### APPRENTICESHIP PROGRAM QUESTIONNAIRE

PROJECT ID:

SER200220 SER002316

The bidder must submit a completed and signed Apprenticeship Program Questionnaire.

1.	Does the bidder have an Apprenticeship Pro [Note: Participation may be by either direct	ogram appropi sponsorship o	riate for the type or through collect	e and scope of vective bargaining	work to be performed? g agreement(s).]
	X	VES		NO	
	Through	CRAS			
2.	Has the bidder's Apprenticeship Program Commissioner of Labor?	been registe	ered with, and	approved by,	the New York State
		YES		NO	
	Provided	Through C	B hs		
3.	Has the bidder's Apprenticeship Program opportunities?	had three y	years of succes	sful experience	e in providing career
	•	YES		NO	
exper	e answer to Question #3 is "Yes", the bide ience the Apprenticeship Program has had in if necessary.	der shall, in the providing ca	CBAs the space below treer opportunit	v, provide info ies. The bidder	rmation regarding the may attach additional
		***************************************	······································		
	*		·		
	and the second s				
	· · · · · · · · · · · · · · · · · · ·				
				•	
		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			
-					
Bidd	er: Inter Contracting Co	rp.			
_		<u>'</u>		Title: P.	ideol
By:	(Signature of Partner or Corp	orate Officer		Title:	(MEPC
Date:	7 2 2 4 4	Potate Officer	<i>,</i>		
	OF NEW YORK RTMENT OF DESIGN AND CONSTRUCTION	20			BID BOOKLET DECEMBER 2013

DEPARTMENT OF DESIGN AND CONSTRUCTION

### SAFETY QUESTIONNAIRE

The bidder must include, with its bid, all information requested on this Safety Questionnaire. Failure to provide a completed and signed Safety Questionnaire at the time of bid opening may result in disqualification of the bid as non-responsive.

1. Bidder Information:		
Company Name: Inter Controction	ing Corp.	
Company Name: Inter Controction  DDC Project Number: SERCO23/6		
Company Size: Ten (10) er	mployees or less	
Greater tha	n ten (10) employees	
Company has previously worked for DDC	X YES	NO NO
2. Type(s) of Construction Work	·	
TYPE OF WORK General Building Construction Residential Building Construction Nonresidential Building Construction Heavy Construction, except building Highway and Street Construction Heavy Construction, except highways Plumbing, Heating, HVAC Painting and Paper Hanging Electrical Work Masonry, Stonework and Plastering Carpentry and Floor Work Roofing, Siding, and Sheet Metal Concrete Work Specialty Trade Contracting Asbestos Abatement Other (specify)  3. Experience Modification Rate:	LAST 3 YEARS  X X X	THIS PROJECT  X X X
The Experience Modification Rate (EMR) is a Insurance (NCCI). This rating is used to determine insurance. The contractor may obtain its EMR contractor cannot obtain its EMR, it must submit to the contractor cannot obtain its EMR, it must submit to the contractor cannot obtain its EMR.	mine the contractor's premiu by contacting its insurance b	m for worker's compensation proker or the NCCI. If the

### Project ID. SER 0023/6

The Contractor must indicate its <u>Intra</u>state and <u>Inter</u>state EMR for the past three years. [Note: For contractors with less than three years of experience, the EMR will be considered to be 1.00].

YEAR	<u>INTRA</u> STATE RATE	<u>INTER</u> STATE RATE
2013	1.02	n/a
2012		_ nla
7011	1.02	

If the Intrastate and/or Interstate EMR for any of the past three years is greater than 1.00, the contractor must attach, to this questionnaire, a written explanation for the rating and identify what corrective action was taken to correct the situation resulting in that rating.

### 4. OSHA Information:

YES	X NO	Contractor has received a willful violation issued by OSHA or New York City Department of Buildings (NYCDOB) within the last three years.
YES	X <sub>NO</sub>	Contractor has had an incident requiring OSHA notification within 8 hours (i.e., fatality, or hospitalization of three or more employees).

The Occupational Safety and Health Act (OSHA) of 1970 requires employers with ten or more employees, on a yearly basis to complete and maintain on file the form entitled "Log of Work-related Injuries and Illnesses". This form is commonly referred to as the OSHA 300 Log (OSHA 200 Log for 2001 and earlier).

The OSHA 300 Log must be submitted for the last three years for contractors with more than ten employees.

The Contractor must indicate the total number of hours worked by its employees, as reflected in payroll records for the past three years.

The contractor must submit the Incident Rate for Lost Time Injuries (the Incident Rate) for the past three years. The Incident Rate is calculated in accordance with the formula set forth below. For each given year, the total number of incidents is the total number of non-fatal injuries and illnesses reported on the OSHA 300 Log. The 200,000 hours represents the equivalent of 100 employees working forty hours a week, fifty weeks per year.

Incident Rate =	X 200,000	
	Total Number of Hours Worked by	y Employees
YEAR	TOTAL NUMBERS OF HOURS WORKED BY EMPLOYEES	INCIDENT RATE
2013	25,/50	7.95
2012	<u> </u>	0
2011	40,141	4.98

22

If the contractor's Incident Rate for any of the past three years is one point higher than the Incident Rate for the type of construction it performs (listed below), the contractor must attach, to this questionnaire, a written explanation for the relatively high rate.

General Building Construction	8.5
Residential Building Construction	7.0
Nonresidential Building Construction	10.2
Heavy Construction, except building	8.7
Highway and Street Construction	9.7
Heavy Construction, except highways	8.3
Plumbing, Heating, HVAC	11.3
Painting and Paper Hanging	6.9
Electrical Work	9.5
Masonry, Stonework and Plastering	10.5
Carpentry and Floor Work	12.2
Roofing, Siding, and Sheet Metal	10.3
Concrete Work	8.6
Specialty Trade Contracting	8.6

### 5. Safety Performance on Previous DDC Project(s)

X YES N	O Contractor previously audited by the DDC Office of Site Safety.
	DDC Project Number(s): SERZOOZSZ, SEQOOZSZ
X YESN	O Accident on previous DDC Project(s).
	DDC Project Number(s): SEQOOZSF,
YES 🔀 N	O Fatality or Life-altering Injury on DDC Project(s) within the last three year [Examples of a life-altering injury include loss of limb, loss of a sense (e.g sight, hearing), or loss of neurological function].
	DDC Project Number(s):,
Date: <u>5/30/</u>	By: (Signature of Owner, Partner, Corporate Officer)
	Title: President

Carticol

# PROJECT REFERENCES – SIMILAR CONTRACTS COMPLETED BY THE BIDDER Ą.

List all contracts substantially completed within the last 4 years similar to the contract being awarded, up to a maximum of 10, in descending order of date of substantial completion.

Project & Location	Contract Type	Contract Amount (\$000)	Date Completed	Owner Reference & Tel. No.	Architect/Engineer Reference & Tel. No. if different from owner
SER 200252 Scorbor Au, St	Savertum \$1.9mm	\$1.900	Slid	ООС	brind Patel
SEQ002657 Francis Lans Blud, Quens	Sewerthm	Sewerthin \$3.3 MM	8//3	241	Fores Abdullmoove
NYCEDK 14830004 Hunts Point Am, Brown	Kneekscope		2/13	MCENC	Javad Assaf 212.312.3715
Reconst. P. Lot, Blobs. 292 Brooklyn Nawy Youl	Hykunyt Prairase	\$3.1 nm	21/01	BUDC	Authory Jareenboushi 718.109.5952
NYCEDC 16920006 Cutsyette Aus, Brant	Saucroum, Highway	1, 24/ un	21/4	NCEDC	Tean / Assart 212.312.3715
SER002292 Holly Plue S. C.	Semen	www.Ex	4/2	DDC	Arrival Potel
569 200520 263 56, Aces	Seach	*720K	11/6	DIC	Celein Francous

BID BOOKLET DECEMBER 2013

# PROJECT REFERENCES - CONTRACTS CURRENTLY UNDER CONSTRUCTION BY THE BIDDER

List all contracts currently under construction even if they are not similar to the contract being awarded.

Architect/En gineer Reference & Tel. No. if different from owner	Adom Aluciss				
Owner Reference & Tel. No.	Dpc			, .	
Date Scheduled to Complete	h1/8				
Uncompleted Portion (\$000)	mm 24				
Subcontracted to Others (\$000)	\$0.5mm	 <b>L</b>			
Contract Amount (\$000)	\$6.9MM	9	·		
Contract Type	Seuc				
Project & Location	SER 200209 Contin Mrs, SI				

CITY OF NEW YORK
DEPARTMENT OF DESIGN AND CONSTRUCTION

BID BOOKLET DECEMBER 2013

27

# PROJECT REFERENCES - PENDING CONTRACTS NOT YET STARTED BY THE BIDDER

List all contracts awarded to or won by the bidder but not yet started.

Architect/Engineer Reference & Tel. No. if different from owner	Sakin Okeowo 212.618.5764				
Owner Reference & Tel. No.	NREPR			·	
Date Scheduled to Start	1/8				
Contract Amount (\$000)	\$ 6.3 mm 8/14				
Contract Type	Highway, Parks				
Project & Location	Abluncic Ave. Extension. Queens, NY				

CITY OF NEW YORK
DEPARTMENT OF DESIGN AND CONSTRUCTION

BID BOOKLET DECEMBER 2013

### VENDEX COMPLIANCE

- (A) Vendex Fees: Pursuant to Procurement Policy Board Rule 2-08(f)(2), the contractor will be charged a fee for the administration of the VENDEX system, including the Vendor Name Check process, if a Vendor Name Check review is required to be conducted by the Department of Investigation. The contractor shall also be required to pay the applicable required fees for any of its subcontractors for which Vendor Name Check reviews are required. The fee(s) will be deducted from payments made to the contractor under the contract. For contracts with an estimated value of less than or equal to \$1,000,000, the fee will be \$175 per Vendor Name Check review. For contracts with an estimated value of greater than \$1,000,000, the fee will be \$350 per Vendor Name Check review.
- (B) <u>Confirmation of Vendex Compliance</u>: The Bidder shall submit this Confirmation of Vendex Compliance to the Department of Design and Construction, Contracts Section, 30-30 Thomson Avenue First Floor, Long Island City, NY 11101.

Bid Information: The Bidder shall complete the bid information set forth below.

	Name of Bidder: Inter Contracting Corp.
	Bidder's Address: 274 White Plains Rd. Svite 6, Easechster, Vr (0709) Bidder's Telephone Number: 914.337.1350
	Ridder's Telephone Number: 9/0.337 /350
	Bidder's Fax Number: 914. 337. 1450
	Date of Bid Opening: 5/28/14
	Project ID: SER002316
Vend	lex Compliance: To demonstrate compliance with Vendex requirements, the Bidder shall complete
	r Section (1) or Section (2) below, whichever applies.
(1)	Submission of Vendex Questionnaires to MOCS: By signing in the space provided below, the
` '	Bidder certifies that as of the date specified below, the Bidder has submitted Vendex
	Questionnaires to the Mayor's Office of Contract Services, Attn: VENDEX, 253 Broadway, 9th
	Floor, New York, New York 10007.
	Date of Submission:
	By:
	(Signature of Partner or corporate officer)
	Print Name:
(2)	Submission of Certification of No Change to DDC: By signing in the space provided below,
•	the Bidder certifies that it has read the instructions in a "Vendor's Guide to Vendex" and that
	such instructions do not require the Bidder to submit Vendex Questionnaires. The Bidder has
	completed TWO ORIGINALS of the Certification of No Change set forth on the next page of
	this Bid Booklet.
	Cata a
	By: /w/ Th
	(Signature of Partner or corporate officer)
	M. I ( M 4:
	$ \sim$ $\sim$ $\sim$ $\sim$ $\sim$ $\sim$ $\sim$ $\sim$ $\sim$ $\sim$

### Principal Questionnaire

This section refers to the most recent principal questionnaire submissions.



Principal Name	Date of signature on last full Principal Questionnaire	Date(s) of signature on Changed Submission (if applicable)
1 Michael Motins	2/5/14	nla
1 Michael Mutino 2 Paris Caraliere	2/5/14	nla
3		
4		
5		
6		
Check if additional changes were submi	itted and attach a document with the	e date of additional submissions.
tified By:  Michael Motino  Name (Print)		
Prosident Title		
Inter Contracting Con	<i>l</i> .	
Name of Submitting Entity		6/3/14
Signature		Date Elizabeth Leichnam
Notarized By:		Notary Public, State of New York No. OilE6004261 Qualified in Queens County Commission Expires June 7, 20 14
Elatet I	Quens	License Number
Notary Public	County License Issued	License Mannoei
Sworn to before me on:	3, 2014	

## The City of New York Department of Small Business Services Division of Labor Services Contract Compliance Unit 110 William Street, New York, New York 10038

Phone: (212) 513 - 6323 Fax: (212) 618-8879

### CONSTRUCTION EMPLOYMENT REPORT

### **GENERAL INFORMATION**

٠.	
1.	Your contractual relationship in this contract is: Prime contractor_x_ Subcontractor
1a.	Are M/WBE goals attached to this project? Yes X No
2.	Please check one of the following if your firm would like information on how to certify with the City of New York as a:
	Minority Owned Business EnterpriseWomen Owned Business EnterpriseDisadvantaged Business EnterpriseX Locally Based Business EnterpriseX Emerging Business Enterprise
2a.	If you are certified as an MBE, WBE, LBE, EBE or DBE, what city/state agency are you certified with? No
3.	Please indicate if you would like assistance from SBS in identifying certified M/WBEs for contracting opportunities: Yes_X_ No
4.	Is this project subject to a project labor agreement? Yes No X
5.	Are you a Union contractor? Yes X No If yes, please list which local(s) you affiliated with _10/0, 731, 14,15,1556
6.	Are you a Veteran owned company? Yes No _X
PAR	T I: CONTRACTOR/SUBCONTRACTOR INFORMATION
7.	TO-4575508 Mouting @intercontracting Corp. Co.  Employer Identification Number or Federal Tax I.D.  Email Address
8.	Inter Contracting Corp.  Company Name
9.	274 White Plains Road, Easechster, NY 10709 Company Address and Zip Code
10.	Michael Mutino 914. 337. 1350
•	Chief Operating Officer Telephone Number
11.	Michael Matino 914.337.1350
	Designated Equal Opportunity Compliance Officer Telephone Number (If same as Item #10, write "same")
12.	Inter Contracting Copp. Michael Motino
	Name of Prime Contractor and Contact Person (If same as Item #8, write "same")

13.	Number of employees in your company:	2	
14.	Contract information:  (a) PPC Contracting Agency (City Agency)	\$ 10,72/, Contract Amou	<i>541.40</i>
	(c) 85020/45E000/C (d) Procurement Identification Number (PIN)	Contract Regis	tration Number (CT#)
	(e) 9/14 (f) Projected Commencement Date	Projected Com	pletion Date
	(g) Description and location of proposed contract:  SER 0023/6: Sewers in Ross	ville Aven	ive, etc.
15.	Has your firm been reviewed by the Division of Labor	Services (DLS) w	ithin the past 36 months
	and issued a Certificate of Approval? Yes X No		
16.	Has DLS within the past month reviewed an Employmand issued a Conditional Certificate of Approval? Yes	ent Report subm	ission for your company
	If yes, attach a copy of certificate.	a complete i spekielle steene hand oppdragsjon i op bringfal i ferbing sko	general general growth and the state of the
W	NOTE: DLS WILL NOT ISSUE A CONTINUED CERTIFIC WITH THIS CONTRACT UNLESS THE REQUIRED COR CONDITIONAL CERTIFICATES OF APPROVAL HAVE E	RECTIVE ACTIO	OVAL IN CONNECTION ONS IN PRIOR
17.	Has an Employment Report already been submitted for Employment Report) for which you have not yet receives No X If yes,	or a different cont ved compliance c	ract (not covered by this ertificate?
	Date submitted: Agency to which submitted: Name of Agency Person: Contract No: Telephone:		
18.	Has your company in the past 36 months been audite Labor, Office of Federal Contract Compliance Program	d by the United S	states Department of es No_X_
	If yes,		
	sed 8/13 OFFICIAL USE ONLY: File No	·	

is responsible for negotiating collective bargaining agreements (CBA) which affect site hiring? Yes No_X_  If yes, attach a list of such associations and all applicable CBA's.  PART II: DOCUMENTS REQUIRED	
(c) Were any corrective actions required or agreed to? Yes No  If yes, attach a copy of such requirements or agreements.  (d) Were any deficiencies found? Yes No  If yes, attach a copy of such findings.  19. Is your company or its affiliates a member or members of an employers' trade ass is responsible for negotiating collective bargaining agreements (CBA) which affect site hiring? Yes No X  If yes, attach a list of such associations and all applicable CBA's.  PART II: DOCUMENTS REQUIRED  20. For the following policies or practices, attach the relevant documents (e.g., printe brochures, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a for the practices. See instructions.  (a) Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)	sociation whicl
If yes, attach a copy of such requirements or agreements.  (d) Were any deficiencies found? Yes No  If yes, attach a copy of such findings.  19. Is your company or its affiliates a member or members of an employers' trade ass is responsible for negotiating collective bargaining agreements (CBA) which affects site hiring? Yes No_X_  If yes, attach a list of such associations and all applicable CBA's.  PART II: DOCUMENTS REQUIRED  20. For the following policies or practices, attach the relevant documents (e.g., printed brochures, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a for the practices. See instructions.  (a) Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)	sociation whicl
If yes, attach a copy of such findings.  Is your company or its affiliates a member or members of an employers' trade ass is responsible for negotiating collective bargaining agreements (CBA) which affect site hiring? Yes No_X_  If yes, attach a list of such associations and all applicable CBA's.  PART II: DOCUMENTS REQUIRED  20. For the following policies or practices, attach the relevant documents (e.g., printed brochures, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a for the practices. See instructions.  (a) Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)	sociation whicl
If yes, attach a copy of such findings.  19. Is your company or its affiliates a member or members of an employers' trade ass is responsible for negotiating collective bargaining agreements (CBA) which affect site hiring? Yes No_X	sociation whic
<ul> <li>Is your company or its affiliates a member or members of an employers' trade assis responsible for negotiating collective bargaining agreements (CBA) which affects site hiring? Yes No X</li> <li>If yes, attach a list of such associations and all applicable CBA's.</li> <li>PART II: DOCUMENTS REQUIRED</li> <li>For the following policies or practices, attach the relevant documents (e.g., printe brochures, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a for the practices. See instructions.</li> <li>(a) Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)</li> </ul>	sociation whicl
is responsible for negotiating collective bargaining agreements (CBA) which affect site hiring? Yes No_X	sociation which
PART II: DOCUMENTS REQUIRED  20. For the following policies or practices, attach the relevant documents (e.g., printe brochures, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a fof the practices. See instructions.  — (a) Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)	t construction
<ul> <li>For the following policies or practices, attach the relevant documents (e.g., printe brochures, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a fof the practices. See instructions.</li> <li>(a) Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)</li> </ul>	
brochures, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a to of the practices. See instructions.  — (a) Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)	
and union employees (whether company or union administered)	ed booklets, full explanation
(b) Disability, life, other insurance coverage/description	
(c) Employee Policy/Handbook	
(d) Personnel Policy/Manual	
(e) Supervisor's Policy/Manual	
(f) Pension plan or 401k coverage/description for all management, nonunion and union employees, whether company or union administered	ed
(g) Collective bargaining agreement(s).	
(h) Employment Application(s)	
(i) Employee evaluation policy/form(s).	
(j) Does your firm have medical and/or non-medical (i.e. education, militar personal, pregnancy, child care) leave policy?	у,

21.	To comply with the Immigration Reform and Control Act of 1986 when and of whom does your firm require the completion of an I-9 Form?
	(a) Prior to job offer (b) After a conditional job offer (c) After a job offer (d) Within the first three days on the job (e) To some applicants (f) To all applicants (g) To some employees (h) To all employees  Yes No  Yes No  Yes No  Yes No  Yes No  Yes No  Yes No
22.	Explain where and how completed 1-9 Forms, with their supportive documentation, are maintained and made accessible.  They are kept in home office and accessible upon request.
23.	Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes No_X_
	If yes, is the medical examination given:
	(a) Prior to a job offer Yes No  (b) After a conditional job offer Yes No  (c) After a job offer Yes No  (d) To all applicants Yes No  (e) Only to some applicants Yes No
	If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.
24.	Do you have a written equal employment opportunity (EEO) policy? Yes X No
25.	Does the company have a current affirmative action plan(s) (AAP) Minorities and WomenIndividuals with handicapsOther. Please specify
26.	Does your firm or collective bargaining agreement(s) have an internal grievance procedure with respect to EEO complaints? Yes_X_ No
	If yes, please attach a copy of this policy.
	If no, attach a report detailing your firm's unwritten procedure for handling EEO complaints.

Page 4
Revised 8/13
FOR OFFICIAL USE ONLY: File No.\_\_\_\_\_\_

27.	Has any employee, within the past three years, filed a complaint pursuant to an internal grievance procedure or with any official of your firm with respect to equal employment opportunity? Yes No_X_
	If yes, attach an internal complaint log. See instructions.
28.	Has your firm, within the past three years, been named as a defendant (or respondent) in any administrative or judicial action where the complainant (plaintiff) alleged violation of any anti-discrimination or affirmative action laws? Yes No_X
	If yes, attach a log. See instructions.
29.	Are there any jobs for which there are physical qualifications? Yes_X_ No
	If yes, list the job(s), submit a job description and state the reason(s) for the qualification(s).  Laborers must be adequately strong to lift heavy objects.
30.	Are there any jobs for which there are age, race, color, national origin, sex, creed, disability, marital status, sexual orientation, or citizenship qualifications? Yes No_X_
	If yes, list the job(s), submit a job description and state the reason(s) for the qualification(s).

### SIGNATURE PAGE

11/1/11/11	
I, (print name of authorized official signing) Michael Mutic the information submitted herewith is true and complete to the best of my submitted with the understanding that compliance with New York City's of requirements, as contained in Chapter 56 of the City Charter, Executive amended, and the implementing Rules and Regulations, is a contractual behalf of the company to submit a certified copy of payroll records to the	y knowledge and belief and equal employment Order No. 50 (1980), as obligation. I also agree on
a monthly basis.	
Inter Contracting Corp.  Contractor's Name	
	0 1,
Michael Miting	President Title President
Name of person who prepared this Employment Report	Title
Michael Matino  Name of official authorized to sign on behalf of the contractor	President
•• •	litie
914.337.1350	
Telephone Number	
	6/3/14
Signature of authorized official	Date
56 Section 3H, the Division of Labor Services reserves the right to reque data and to implement an employment program.  Contractors who fail to comply with the above mentioned requirements of noncompliance may be subject to the withholding of final payment.	
Willful or fraudulent falsifications of any data or information submitted he termination of the contract between the City and the bidder or contractor contracts for a period of up to five years. Further, such falsification may criminal prosecution.	r and in disapproval of future
To the extent permitted by law and consistent with the proper discharge Charter Chapter 56 of the City Charter and Executive Order No. 50 (198 and Regulations, all information provided by a contractor to DLS shall be	30) and the implementing Rules
Only original signatures accepted.	
Only Original Signatures accepted.	
Sworn to before me this 3rd day of June 20 14	
S Salvet Li	
11.	
Notary Public Authorized Signature	Date
Notary Public, State of New York	Date
Notary Public State of New York	Date
Notary Public, State of New York	Date



Robert W. Walsh Commissioner 213CY147

June 27, 2013

Mr. Michael Mutino Inter Contracting Corporation 50 Nelson Road Scarsdale, NY 10583

RE: NYC Department of Design and Construction Contract (DDC); Pin Number: 8502013SE0007C; Project No. SER200209; Contract Value: \$6,952,975.81;

Continued Certificate of Approval.

Dear Mr. Mutino:

Please be advised that Inter Contracting Corporation has already received notice of its approval status for the three (3) year period indicated in the Department of Business Services/Division of Labor Services' (DLS') Certificate of Compliance dated **April 11, 2012**.

As your organization continues to meet the equal employment opportunity requirements of the City of New York, DLS approves the awarding of the above-referenced contract. This approval does not extend the initial three (3) year approval (April 11, 2012 to April 10, 2015) referred to above.

If you have any questions, please call Rosalyn Dawson at (212) 618-8843 or e-mail her at *rdawson@sbs.nyc.gov*.

Very truly yours,

Helen Wilson

**Executive Director** 

**Division of Labor Services** 

CC:

Lorraine Holley (DDC)

Rosalyn Dawson

File

### BIDDER'S CERTIFICATION OF COMPLIANCE WITH <u>IRAN DIVESTMENT ACT</u>

Pursuant to General Municipal Law §103-g, which generally prohibits the City from entering into contracts with persons engaged in investment activities in the energy sector of Iran, the bidder/proposer submits the following certification:

[Please Check One]

r.	
BIDDI	ER'S CERTIFICATION
Ø	By submission of this bid or proposal, each bidder/proposer and each person signing or behalf of any bidder/proposer certifies, and in the case of a joint bid each party thereto certifies as to its own organization, under penalty of perjury, that to the best of its knowledge and belief, that each bidder/proposer is not on the list created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law.
	I am unable to certify that my name and the name of the bidder/proposer does not appear on the list created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law. I have attached a signed statement setting forth in detail why I cannot secretify.
Dated	Easeclosear, New York  June 3, 20/4
. 5-2-6-	SIGNATURE
	Michael Miin
	PRINTED NAME  President
	TITLE
	to before me this day of June, 20 14
2	Sala Le
Dated	Public  Elizabeth Leichnam  Notary Public, State of New York No. OlLE6004261  Qualified in Queens County Commission Expires June 7, 20

### ATTACH TO CONTRACT DOCUMENTS

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION INFRASTRUCTURE DIVISION BUREAU OF DESIGN

**PROJECT ID: SER002316** 

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN
WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

**INCLUDING WATER MAIN WORK** 

Together With All Work Incidental Thereto

**BOROUGH OF STATEN ISLAND** 

ADDENDUM NO. 5

DATED: May 7, 2014

This Addendum is issued for the purpose of amending the requirements of the Contract Documents and is hereby made part of said Contract Documents to the same extent as if it was originally included therein.

Refer to the Contract Drawings;

Add the following drawings (attached to the end of this addendum) to the end of the contract drawings:

Verizon Drawings, sheets No. 1 to 3.

Con Edison Drawings, sheets No. 1 to 16.

By signing in the space provided below, the bidder acknowledges receipt of one (1) page of this Addendum plus nineteen (19) sheets of contract drawings.

THIS ADDENDUM MUST BE SIGNED BY ALL BIDDERS AND ATTACHED TO THEIR BIDS.

**GURDIP SAINI, P.E.** 

**Assistant Commissioner/Design** 

Name of Bidder

### ATTACH TO CONTRACT DOCUMENTS

## THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION INFRASTRUCTURE DIVISION BUREAU OF DESIGN

PROJECT ID: SER002316

### FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN
WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

### **INCLUDING WATER MAIN WORK**

**Together With All Work Incidental Thereto** 

### **BOROUGH OF STATEN ISLAND**

ADDENDUM NO. 6

DATED: May 22, 2014

This Addendum is issued for the purpose of amending the requirements of the contract documents and is hereby made part of said contract documents to the same extent as if it was originally included therein.

- (1) Refer to the Bid and Contract Documents, Volume 1 of 3, BID SCHEDULE, page B-13, Item No. 6.67, Sequence No. 057;

  Delete "3,300.00" under COL. 2, ENGINEER'S ESTIMATE OF QUANTITIES, and;

  Substitute "3,800.00".
- (2) Refer to the Bid and Contract Documents, Volume 1 of 3, BID SCHEDULE, page B-13, Item No. 6.68, Sequence No. 058;

  Delete "10,500.00" under COL. 2, ENGINEER'S ESTIMATE OF QUANTITIES, and;

  Substitute "46,000.00".
- (3) Refer to the Bid and Contract Documents, Volume 3 of 3, ADDENDUM NO. 2, Article (20), paragraph (E)(1), subparagraph (a), Page A2-12;

  Delete subparagraph (a), in its entirety;

  Substitute the following:
  - "(a) The entire width of existing roadway and six (6) inches of existing roadway subgrade shall be removed from curb to curb or edge to edge and the permanent restoration over the entire width of roadway shall consist of nine (9) inches of Asphaltic Macadam Pavement on a subbase course of six (6) inches of Select Granular Material (Material D only) on Plastic Filter Fabric. The above areas are approximate the actual final areas of restoration shall be determined by the Engineer."

ADDENDUM NO. 6 PROJECT ID.: SER002316

(4) Refer to the Bid and Contract Documents, Volume 3 of 3, ADDENDUM NO. 2, Article (20), paragraph (E)(2), subparagraph (a), Page A2-12;

Delete subparagraph (a), in its entirety;

Substitute the following:

"(a) The entire width of existing roadway and six (6) inches of existing roadway subgrade shall be removed from **curb to curb** or **edge to edge** and the permanent restoration over the **entire width of roadway** shall consist of six (6) inches of Asphaltic Macadam Pavement on a subbase course of six (6) inches of Select Granular Material (Material D only) on Plastic Filter Fabric. The above areas are approximate the actual final areas of restoration shall be determined by the Engineer."

(54)<u>Refer</u> to the Bid and Contract Documents, Volume 3 of 3, ADDENDUM NO. 2, Article (20), paragraph (E)(4), table under subparagraph (i), Page A2-13;

Add the following to the end of the table under the appropriate headings shown:

Item No.	<u>Item</u>	Payment Description
6.67	Subbase Course, Select Granular Material	(For 6" sub-base course under entire width of roadway restoration.)
6.68	Plastic Filter Fabric	(For placement under sub-base course.)

By signing in the space provided below, the bidder acknowledges receipt of two (2) pages of this Addendum.

**GURDIP SAINI, P.E.** 

Assistant Commissioner/Design

### BID BOND 1 FORM OF BID BOND

KNOW ALL MEN BY THESE PRESENTS. That we,
Inter Contracting Corp.
274 White Plains Road, Suite 6, Eastchester, NY 10709
hereinafter referred to as the "Principal", and
International Fidelity Insurance Company
One Newark Center, 20th Floor , Newark, NJ 07102-5207
hereinafter referred to as the "Surety" are held and firmly bound to THE CITY OF NEW YORK, hereinafter referred to as the "CITY", or to its successors and assigns in the penal sum of
Ten Percent of Amount Bid
(\$\(\)_10\%), Dollars lawful money of the United States, for the payment of which said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.
Whereas, the Principal is about to submit (or has submitted) to the City the accompanying proposal, hereby made a part hereof, to enter into a contract in writing for Project ID: SER002316. Construction of Storm
and Sanitary Sewers and Appurtenances In: Rossville Avenue Between Mason Boulevard and Woodrow
Road etc. Borough of Staten Island.
NOW, THEREFORE, the conditions of this obligation are such that if the Principal shall not withdraw said Proposal without the consent of the City for a period of forty-five (45) days after the opening of bids and in the event of acceptance of the Principal's Proposal by the City, if the Principal shall:
(a) Within ten (10) days after notification by the City, execute in quadruplicate and deliver to the City all the executed counterparts of the Contract in the form set forth in the Contract Documents, in accordance with the proposal as accepted, and
(b) Furnish a performance bond and separate payment bond, as may be required by the City, for the faithful performance and proper fulfullment of such Contract, which bonds shall be satisfactory in all respects to the City and shall be executed by good and sufficient sureties, and
(c) In all respects perform the agreement created by the acceptance of said Proposal as provided in the Information for Bidders, bound herewith and made a part hereof, or if the City shall reject the aforesaid Proposal, then this obligation shall be null and void; otherwise to remain in full force and effect.

### BID BOND 2

In the event that the Proposal of the Principal shall be accepted and the Contract be awarded to him the Surety hereunder agrees subject only to the payment by the Principal of the premium therefore, if requested by the City, to write the aforementioned performance and payment bonds in the form set forth in the Contract Documents.

It is expressly understood and agreed that the liability of the Surety for any and all claims hereunder shall in no event exceed the penal amount of this obligation as herein stated.

There shall be no liability under this bond if, in the event of the acceptance of the Principal's Proposal by the City, either a performance bond or payment bond, or both, shall not be required by the City on or before the 30th day after the date on which the City signs the Contract.

The surety, for the value received, hereby stipulates and agrees that the obligations of the Surety and its bond shall in no way be impaired or affected by any postponements of the date upon which the City will receive or open bids, or by any extensions of time within which the City may accept the Principal's Proposal, or by any waiver by the City of any of the requirements of the Information for Bidders, and the Surety hereby waives notice of any such postponements, extensions, or waivers.

their proper officers the	21st	day of	May		<b>-</b>	
(Seal)			Inter Contra	cting Corp.  Principal		(L.S.
		Ву:				
		by.				
(Seal)			Internationa	I Fidelity Insuran Surety	ce Company	
		Ву:	alle	Attment	uir.	
		•	Colette R C	hisholm	Attorney-in-Fact	

### BID BOND 3

### ACKNOWLEDGEMENT OF PRINCIPAL, IF A CORPORATION

State of New Yev	h County of Ne	wyork	ss:	
On this '2	7 day of $M_a$	xy $20$		ly came
MicHael Mux	to me kno	wn, who, being by	me duly sworn, did depose and s	ay that he
resides at/	40 W. 86 5 ST	reet, Apt	15C, NY NY 1000	24
that he is the Pre	sident of	Inter Contracting	Corp.	
corporation; that one	bed in and which execut of the seals affixed to sai tration, and that he signe	id instrument is suc	strument; that he knows the seal on the seal of the seal; that it was so affixed by one by like order.	of said rder of the
	Notary Public No. 03 Qualified in	PASQUALONE C, State of New York BPA6283990 New York County opires June 17, 20	\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \	
	ACKNOWLEDG	EMENT OF PRI	NCIPAL, IF A PARTNERSHII	<u>P</u>
State of	County of		ss:	
On this	day of	•	, before me personally	
	to me kı	own and known to	me to be one of the members of	the firm of
		described in and w	ho executed the foregoing instrum	nent, and he
acknowledged to me t	hat he executed the sam	e as and for the act	and deed of said firm.	
			Notary Public	
	ACKNOWLEDG	EMENT OF PRI	NCIPAL, IF AN INDIVIDUA	<u>L</u>
State of	County of		ss:	
On this	day of		, before me personally	y appeared
			o me to be the person described i	and who
executed the foregoin	g instrument and acknow	vledged that he exc	ecuted the same.	
			Notary Public	
	•			

AFFIX ACKNOWLEDGEMENTS AND JUSTIFICATION OF SURETIES

### ACKNOWLEDGMENT OF SURETY COMPANY

ST	ATE OF! OUNTY OF	IEW YOR NASSAU		} :	3S									
	On this	. May 2	1, 2014		, bef	ore me p	erson	ally came	C	olette R.	Chishol	lm		
lnte abov such his/h Insur York quali York	me known, York County  mational Fidelity In we instrument n corporate se ner name the rance of the S n issued to ification evides as surety and not been revol	who, surance that h al; that reto by state of internations the	Company e/she ki is was s like one New Ye tional Fide	nows the so affixed der, and ork, has allity insurance in the source in	e seal d by the seal of said	sworn,  New You  of said of  e Board of  iffiant did  ant to Sepany  Company	did ork corpora of Dire I furthe	depose, the corporation; that ctors of ser depose 1111 of the cufficient corporation.	and hat he pration it the said co e and the instancy united in a sency united in a s	say; /she is descri seal af rporati say ti surance (Si	that the A bed in fixed ton; an hat the Law urety) ny law h; and	he/she ttorney-it which ex to said in d that he e Superi of the S his/her c	resides n-Fact of xecuted to nstrument she sign ntendent tate of N certificate	the the nt is ned to of

NY acknowledgement

DANA GRANICE
Notary Public, State of New York,
No. 01GR6099128
Qualified in Nassau County
Commission Expires September 22, 2015

### POWER OF ATTORNEY

### INTERNATIONAL FIDELITY INSURANCE COMPANY ALLEGHENY CASUALTY COMPANY

ONE NEWARK CENTER, 20TH FLOOR NEWARK, NEW JERSEY 07102-5207

KNOW ALL MEN BY THESE PRESENTS: That INTERNATIONAL FIDELITY INSURANCE COMPANY, a corporation organized and existing under the laws of the State of New Jersey, and ALLEGHENY CASUALTY COMPANY a corporation organized and existing under the laws of the State of Pennsylvania, having their principal office in the City of Newark, New Jersey, do hereby constitute and appoint

COLETTE R. CHISHOLM, CAMILLE MAITLAND

Uniondale, NY.

their true and lawful attorney(s)-in-fact to execute, seal and deliver for and on its behalf as surety, any and all bonds and undertakings, contracts of indemnity and other writings obligatory in the nature thereof, which are or may be allowed, required or permitted by law, statute, rule, regulation, contract or otherwise, and the execution of such instrument(s) in pursuance of these presents, shall be as binding upon the said INTERNATIONAL FIDELITY INSURANCE COMPANY and ALLEGHENY CASUALTY COMPANY, as fully and amply, to all intents and purposes; as if the same had been duly executed and acknowledged by their regularly elected officers at their principal offices.

This Power of Attorney is executed, and may be revoked, pursuant to and by authority of the By-Laws of INTERNATIONAL FIDELITY INSURANCE COMPANY and ALLEGHENY CASUALTY COMPANY and is granted under and by authority of the following resolution adopted by the Board of Directors of INTERNATIONAL FIDELITY INSURANCE COMPANY at a meeting duly held on the 20th day of July, 2010 and by the Board of Directors of ALLEGHENY CASUALTY COMPANY at a meeting duly held on the 15th day of August, 2000:

"RESOLVED, that (1) the President, Vice President, Executive Vice President or Secretary of the Corporation shall have the power to appoint, and to revoke the appointments of, Attorneys-in-Fact or agents with power and authority as defined or limited in their respective powers of attorney; and to execute on behalf of the Corporation and affix the Corporation's seal thereto, bonds, undertakings, recognizances, contracts of indemnity and other written obligations in the nature thereof or related thereto, and (2) any such Officers of the Corporation may appoint and revoke the appointments of joint-control custodians, agents for acceptance of process, and Attorneys-in-fact with authority to execute waivers and consents on behalf of the Corporation; and (3) the signature of any such Officer of the Corporation and the Corporation's seal may be affixed by facsimile to any power of attorney or certification given for the execution of any bond, undertaking, recognizance, contract of indemnity or other written obligation in the nature thereof or related thereto, such signature and seals when so used whether heretofore or hereafter, being hereby adopted by the Corporation as the original signature of such officer and the original seal of the Corporation, to be valid and binding upon the Corporation with the same force and effect as though manually affixed."

IN WITNESS WHEREOF, INTERNATIONAL FIDELITY INSURANCE COMPANY and ALLEGHENY CASUALTY COMPANY have each executed and attested these presents on this 12th day of March, 2012.

SEAL OF THE PROPERTY OF THE PR

STATE OF NEW JERSEY County of Essex

Abotant

ROBERT W. MINSTER
Executive Vice President/Chief Operating Officer
(International Fidelity Insurance Company)
and President (Allegheny Casualty Company)



On this 12th day of March 2012, before me came the individual who executed the preceding instrument, to me personally known, and, being by me duly sworn, said he is the therein described and authorized officer of INTERNATIONAL FIDELITY INSURANCE COMPANY and ALLEGHENY CASUALTY COMPANY; that the seals affixed to said instrument are the Corporate Seals of said Companies; that the said Corporate Seals and his signature were duly affixed by order of the Boards of Directors of said Companies.

IN TESTIMONY WHEREOF, I have hereunto set my hand affixed my Official Seal, at the City of Newark, New Jersey the day and year first above written.



A NOTARY PUBLIC OF NEW JERSEY My Commission Expires Mar. 27, 2014

Cathy Vargue

### CERTIFICATION

I, the undersigned officer of INTERNATIONAL FIDELITY INSURANCE COMPANY and ALLEGHENY CASUALTY COMPANY do hereby certify that I have compared the foregoing copy of the Power of Attorney and affidavit, and the copy of the Sections of the By-Laws of said Companies as set forth in said Power of Attorney, with the originals on file in the home office of said companies, and that the same are correct transcripts thereof, and of the whole of the said originals, and that the said Power of Attorney has not been revoked and is now in full force and effect.

TESTIMONY WHEREOF. I have hereunto set my hand this

MAY 7 1 2014 day of

Maria A. Granco

MARIA BRANCO, Assistant Secretary

### INTERNATIONAL FIDELITY INSURANCE COMPANY

ONE NEWARK CENTER, 20TH FLOOR, NEWARK, NEW JERSEY 07102-5207

STATEMENT OF ASSETS, LIABILITIES, SURPLUS AND OTHER FUNDS

### AT JUNE 30, 2013

ASSETS	
	004 055 400
Bonds (Amortized Value)	\$31,357,102
Preferred Stocks (Market Value)	2,500,000
Common Stocks (Market Value)	82,350,907
Mortgage Loans on Real Estate	996,402
Cash & Bank Deposits	84,469,089
Other Invested Assets	338,798
Unpaid Premiums & Assumed Balances	16,053,132
Reinsurance Recoverable from Reinsurers	5,829,997
Current federal & foreign income tax recoverable and interest thereon	1,214,259
Electronic Data Processing Equipment	309,696
Investment Income Due and Accrued	346,481
Net Deferred Tax Assets	6,045,046
Receivables from parent, subsidiaries and affiliates	201,595
Health Care (_) and other amounts receivable	88,000
Other Assets	11,859,408
Other Assets	11/00//200
TOTAL ASSETS	\$243,959,912
LIABILITIES, SURPLUS & OTHER FUNDS	
Losses (Reported Losses Net as to Reinsurance Ceded and	
Incurred But Not Reported Losses)	\$12,317,302
Reinsurance Payable on Paid Losses and Loss Adjustment	
Expenses (Schedule F, Part 1, Column 6)	2,437,728
Loss Adjustment Expenses	4,542,164
Contingent Commissions & Other Similar Charges	5,022,648
Other Expenses (Excluding Taxes, Licenses and Fees)	3,590,479
Taxes, Licenses & Fees (Excluding Federal Income Tax)	488,870
Unearned Premiums	39,111,384
Dividends Declared & Unpaid: Policyholders	500,000
Ceded Reinsurance Premiums Payable	5,122,365
Funds Held by Company under Reinsurance Treaties	1,031
	69,969,227
Amounts Withheld by Company for Account of Others	1,043
Provisions for Reinsurance	148,487
Payable to Parent, Subsidiaries and Affiliates	•
Other Liabilities	4,975
TOTAL LIABILITIES	<u>\$143,257,703</u>
Common Capital Stock	\$1,500,000
Gross Paid-in & Contributed Surplus	374,600
<del>_</del>	16,000,000
<del>-</del>	87,215,513
Unassigned Funds (Surplus)	• •
Less: Treasury Stock at cost (97,509 shares common) (value incl. \$45.)	4,387,905
Surplus as Regards Policyholders	\$100,702,208
TOTAL LIABILITIES, SURPLUS & OTHER FUNDS	\$243,959,911

I, Francis L. Mitterhoff, President of INTERNATIONAL FIDELITY INSURANCE COMPANY, certify that the foregoing is a fair statement of Assets, Liabilities, Surplus and Other Funds of this Company, at the close of business, June 30, 2013, as reflected by its books and records and as reported in its statement on file with the Insurance Department of the State of New Jersey.



IN TESTIMONY WHEREOF, I have set my hand and affixed the seal of the Company, this  $12^{th}$  day of August, 2013. INTERNATIONAL FIDELITY INSURANCE COMPANY



### BID BOND 1 FORM OF BID BOND

KNOW ALL MEN BY THESE PRESENTS. That we,					
hereinafter referred to as the "Principal", and					
hereinafter referred to as the "Surety" are held and firmly bound to THE CITY OF NEW YORK, hereinafter referred to as the "CITY", or to its successors and assigns in the penal sum of					
(\$), Dollars lawful money of the United States, for the payment of which said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.					
Whereas, the Principal is about to submit (or has submitted) to the City the accompanying proposal, hereby made a part hereof, to enter into a contract in writing for					
NOW, THEREFORE, the conditions of this obligation are such that if the Principal shall not withdraw said Proposal without the consent of the City for a period of forty-five (45) days after the opening of bids and in the event of acceptance of the Principal's Proposal by the City, if the Principal shall:					
(a) Within ten (10) days after notification by the City, execute in quadruplicate and deliver to the City all the executed counterparts of the Contract in the form set forth in the Contract Documents, in accordance with the proposal as accepted, and					
(b) Furnish a performance bond and separate payment bond, as may be required by the City, for the faithful performance and proper fulfillment of such Contract, which bonds shall be satisfactory in all respects to the City and shall be executed by good and sufficient sureties, and					
(c) In all respects perform the agreement created by the acceptance of said Proposal as provided in the Information for Bidders, bound herewith and made a part hereof, or if the City shall reject the aforesaid Proposal, then this obligation shall be null and void; otherwise to remain in full force and effect.					

### BID BOND 3

### ACKNOWLEDGMENT OF PRINCIPAL, IF A CORPORATION

State of	County of	ss:
On this	day of	, before me personally came
		to me known, who, being by me duly sworn, did depose and say
that he resides at_		of
that he is the		of
corporation; that o	ne of the seals affixed	executed the foregoing instrument; that he knows the seal of said I to said instrument is such seal; that it was so affixed by order of at he signed his name thereto by like order.
		Notary Public
	ACKNOWLEDGM	ENT OF PRINCIPAL, IF A PARTNERSHIP
State of	County of	sc.
On this	day of	ss:, before me personally appeared
On this	uay or	to me known and known to me to be one of the members of the
firm of		described in and who expected the foresting
	1111	described in and who executed the foregoing that he executed the same as and for the act and deed of said
firm.		
		Notary Public
	ACKNOWLEDGM	IENT OF PRINCIPAL, IF AN INDIVIDUAL
State of	County of	ss:
On thisand who executed	day ofthe foregoing instrume	ss:
		Notary Public
ŧ	AFFIX ACKNOWLED	OGMENTS AND JUSTIFICATION OF SURETIES

### **SPECIAL NOTICE TO BIDDERS**

The New York City Department of Small Business Services (SBS), in conjunction with the New York Business Development Corporation (NYBDC), have established a **NYC Construction Loan** pilot program to provide prime contractors and subcontractors financing for mobilization costs on certain City construction projects.

Under this initiative, loans are available for early stage mobilization needs such as insurance, labor, supplies and equipment. Bidders are strongly encouraged to visit "Growing Your Business" at <a href="www.nyc.gov/nycbusiness">www.nyc.gov/nycbusiness</a> to learn more about the loan or contact <a href="constructionloan@sbs.nyc.gov">constructionloan@sbs.nyc.gov</a> / (212) 513-6444 to obtain details and to determine preliminary eligibility.

A successful loan applicant will be required to make an assignment of its contract (or subcontract) payments to the lender NYBDC until the loan is repaid. If the loan is to a subcontractor, a prime contractor must honor the terms of such an assignment.

A prime contractor may not discriminate against a subcontractor or potential subcontractor by reason of the subcontractor's participation, or nonparticipation, in the NYC Construction Loan program.

(NO TEXT ON THIS PAGE)

### **CITY OF NEW YORK**

### DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

### **BID BOOKLET**

FOR FURNISHING ALL LABOR AND MATERIALS NECESSARY AND REQUIRED FOR:

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD; WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET; FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE; WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE; GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE; MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE; VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND, WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

INCLUDING WATER MAIN WORK

Together With All Work Incidental Thereto BOROUGH OF STATEN ISLAND

(NO TEXT ON THIS PAGE)

### **PROJECT ID: SER002316**

### CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

### **BID BOOKLET**

### TABLE OF CONTENTS

SECT	ION	PAGE
PART	A ·	
1.	Table of Contents	1
2.	Special Notice to Bidders	2
3.	Attachment 1 – Bid Information	A-1
4.	Bid Schedule	B-1
5.	Bid Form	C-1
6.	Affirmation	C-6
7.	Bid Bond	C-7
8.	M/WBE Program: M/WBE Utilization Plan	5
9.	Apprenticeship Program Requirements	19
PART	${f B}$	
10.	Safety Questionnaire	21
11.	Pre-award Process	24
12.	Project Reference Form	26
13.	Contract Certificate	29
14.	Vendex Compliance	30
15.	Iran Divestment Act Compliance Rider	31
16.	Construction Employment Report	33

(NO TEXT ON THIS PAGE)

### CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

### SPECIAL NOTICE TO BIDDERS

### **BID SUBMISSION REQUIREMENTS**

### THE FOLLOWING DOCUMENTS ARE TO BE COMPLETED AND SUBMITTED WITH THE BID:

- 1. Bid Schedule and Bid Form, including Affirmation
- 2. Bid Security (if required, see Attachment 1 on Page A-1)
- 3. Schedule B: M/WBE Utilization Plan (if participation goals have been established)

### FAILURE TO SUBMIT ITEMS (1), (2) AND (3) WILL RESULT IN THE DISQUALIFICATION OF THE BID.

- 4. Safety Questionnaire
- 5. Construction Employment Report (if bid is \$1,000,000 or more)
- 6. Contract Certificate (if bid is less than \$1,000,000)
- 7. Confirmation of Vendex Compliance
- 8. Bidder's Certification of Compliance with Iran Divestment Act
- 9. Special Experience Requirements (if applicable)
- 10. Apprenticeship Program Questionnaire (if applicable)
- 11. Any addenda issued prior to the receipt of bids

### FAILURE TO SUBMIT ITEMS (4) THROUGH (11) MAY RESULT IN THE DISQUALIFICATION OF THE BID.

### NOTES:

- (1) All of the above referred to blank forms to be completed and submitted with the bid are included in the BID BOOKLET.
- (2) If the bidder has any questions or requires additional information, please contact the Department of Design and Construction by phone (718-391-2601) or by fax (718-391-2615).
- (3) <u>VENDEX QUESTIONNAIRES</u>: The Bidder is advised that Vendex Questionnaires and procedures have been changed. Vendex Questionnaires, as well as detailed instructions, may be obtained at <u>www.nyc.gov/vendex</u>. The bidder may also obtain Vendex forms and instructions by contacting the Agency Chief Contracting Officer or the contact person for this contract.
- (4) <u>SPECIAL EXPERIENCE REQUIREMENTS</u>: The Bidder is advised that Special Experience Requirements may apply to this contract. Such requirements are set forth on pages 3, 3a, 3b, and 4 of this Bid Booklet.

### SPECIAL NOTICE TO BIDDERS

### SPECIAL EXPERIENCE REQUIREMENTS (Revised 03/2014)

(A) SPECIAL EXPERIENCE REQUIREMENTS FOR THE BIDDER: The Special Experience Requirements set forth below apply to the bidder. Compliance with such Special Experience Requirements will be determined solely by the City prior to an award of contract. Failure to comply with the Special Experience Requirements will result in rejection of the bid as non-responsive.

The requirements in this Section (A) apply to this contract where indicated by a blackened box (a).

The bidder must, within the last seven (7) consecutive years prior to the bid opening, have successfully completed in a timely fashion at least one (1) project similar in scope and type to the required work. Such prior project may have been performed as a prime contractor, subcontractor or sub-subcontractor.

The Special Experience Requirements next to the blackened box below apply to the bidder. If the bidder intends to perform such work itself, it must demonstrate compliance with the Special Experience Requirements. If the bidder intends to subcontract this work, the proposed subcontractor or sub-subcontractor must demonstrate compliance with the Special Experience Requirements. The contractor, subcontractor or sub-subcontractor (hereinafter referred to as the "entity") that will perform any specific area of work indicated by the blackened box below, may have performed the required prior project(s) as a prime contractor, subcontractor or sub-subcontractor. Once approved, no substitution will be permitted, unless the qualifications of the proposed replacement have been approved in writing in advance by the City.

qual	fication	ns of the proposed replacement have been approved in writing in advance by the City.
	last	nk Water Main Work: The entity that will perform the trunk water main work must, within the seven (7) consecutive years prior to the bid opening, have successfully completed in a timely on at least one (1) project similar in scope and type to the required work.
	the E must	Management Practice Work: Best Management Practice ("BMP") Work is any item of work in Bid Schedule that begins with the prefix "BMP". The entity that will perform any BMP Work, within the last five (5) consecutive years prior to the bid opening, have successfully completed in the last three (3) projects similar in scope and type to the required work.
	indiv	professional services in connection with BMP Work, (i.e., monitoring and reporting services), the ridual who will perform the required services must, within the last five (5) consecutive years prior e bid opening, have successfully completed in a timely fashion at least three (3) projects similar in e and type to the required work. Additional requirements are set forth below.
		The individual serving as the Restoration Specialist (Construction Monitor) must be a Registered Landscape Architect licensed by the state of New York, or must have equivalent professional experience.
		The individual serving as the Erosion and Sediment Control Licensed/Certified Professional must be a Certified Professional in Erosion and Sediment Control (CPESC), certified by CPESC, Inc.
	work	ro-Tunneling/Pipe Jacking Work: The entity that will perform the micro-tunneling/pipe jacking must, within the last five (5) consecutive years prior to the bid opening, have successfully pleted in a timely fashion at least two (2) projects similar in scope and type to the required work.
	ОТН	IER:
	-	

### SPECIAL EXPERIENCE REQUIREMENTS FOR SPECIFIC AREAS OF WORK (to be provided after an award of contract):

The requirements in this Section (B) apply to this contract where indicated by a blackened box (11).

The Special Experience Requirements set forth below apply to the contractor, subcontractor or subsubcontractor that will perform the specific area of work. Compliance with such Special Experience Requirements will be determined solely by the City after an award of contract. After an award of contract, when requested by the City, the contractor will be required to submit the qualifications of the contractor, subcontractor or sub-subcontractor that will perform the specific area of work. If the bidder intends to perform such work itself, it must demonstrate compliance with the Special Experience Requirements. If the bidder intends to subcontract this work, the proposed subcontractor or sub-subcontractor must demonstrate compliance with the Special Experience Requirements. Once approved, no substitution will be permitted, unless the qualifications of the proposed replacement have been approved in writing in advance by the City.

Special Experience Requirements apply to the contractor, subcontractor or sub-subcontractor (hereinafter referred to as the "entity") that will perform any specific area of work indicated by a blackened box. The entity may have performed the required prior project(s) as a prime contractor, subcontractor or subsubcontractor.

8.01. The entity that will perform any Hazmat Work must, within the last three (3) consecutive years prior to the bid opening, have successfully completed in a timely fashion at least five (5) projects similar in scope and type to the required work.
Pile, CFA Pile, and/or Mini-Pile Work: The entity that will perform the Pile, CFA Pile and/or Mini-Pile Work must, within the last three (3) consecutive years prior to the bid opening, have successfully completed in a timely fashion at least two (2) projects similar in scope and type to the required work.
For professional services in connection with Pile Work, (i.e., engineering and inspection services), the individual who will perform the required services must be a Professional Engineer licensed by the state of New York. Such individual must also comply with the above requirements for prior projects.
Construction Report, Monitoring And Post-Construction Report, and Continuous Real-Time Monitoring For Vibrations And Movements And Post-Construction Report Work: The entity that will perform the Construction Report, Monitoring For Vibrations And Movements, and Post-Construction Report Work must, within the last three (3) consecutive years prior to the bid opening, have successfully completed in a timely fashion at least two (2) projects similar in scope and type to the required work.
For professional services in connection with Reporting and Monitoring Work, (i.e., engineering and inspection services), the individual who will perform the required services must be a Professional Engineer licensed by the state of New York. Such individual must also comply with the above requirements for prior projects.
OTHER:

- (C) <u>SPECIFICATIONS</u>: In the event of any conflict, omission or inconsistency between (1) the Specifications and/or Contract Drawings, and (2) the Special Experience Requirements in Section (B) of the Special Notice To Bidders, the special experience listed in the Specifications and/or Contract Drawings shall be controlling. The Special Experience Requirements in Section (B) of this Special Notice To Bidders are only for the convenience of the bidders.
- Experience Requirements, the bidder must complete and submit the Qualification Form included in the Bid Booklet. The City will only evaluate a project if the following criteria are met: (1) the project is described on the Qualification Form, and (2) all information on the Qualification Form is provided. The City will not evaluate any project which does not comply with the criteria set forth herein, including any project which is referred to only on the resume of an individual.

If Special Experience Requirements are indicated for any specific area of work, the submission requirement set forth above shall apply to the entity that will perform the specific area of work.

- (E) <u>CONDITIONS</u>: In determining compliance with the Special Experience Requirements for the bidder set forth above, the City may consider prior projects completed by principal(s) or other employees of the bidder while affiliated with another entity, subject to the conditions set forth below.
  - Any principal or other employee on whose prior experience the bidder is relying to demonstrate compliance with this special experience requirement must have held the following: (a) a significant management role in the prior entity with which he/she was affiliated, and (b) a significant management role in the entity submitting the bid for a period of six (6) months or more from the inception of the bidding entity.
  - The bidder may not rely on the experience of its principals or other employees to demonstrate compliance with any other requirements, including without limitation, financial requirements or requirements for a specified minimum amount of annual gross revenues.
- (F) <u>JOINT VENTURES</u>: In the event the bidder is a joint venture, at least one firm in the joint venture must meet the above described experience requirements.

### **Qualification Form**

List previous projects completed to meet the special experience requirements for this contract. Please photocopy this form for submission of all required projects.

Name of Contractor:
Name of Project:
Location of Project:
Owner or Owner's representative (Architect or Engineer) who is familiar with the work performed:
Name:
Title: Phone Number:
Brief description of the Project completed or the Project in progress:
Was the Project performed as a prime, a subcontractor or a sub-subcontractor:
Amount of Contract, Subcontract or Sub-subcontract:
Start Date and Completion Date:
***********
Name of Contractor:
Name of Project:
Location of Project:
Owner or Owner's representative (Architect or Engineer) who is familiar with the work performed:
Name:
Title:Phone Number:
Brief description of the Project completed or the Project in progress:
Was the Project performed as a prime, a subcontractor or a sub-subcontractor:
Amount of Contract, Subcontract or Sub-subcontract:
Start Date and Completion Date:

(NO TEXT ON THIS PAGE)

### ATTACHMENT 1 - BID INFORMATION

### PROJECT ID: SER002316 PIN: 8502014SE0001C

Description and Locat	Appurtenances In: Rossville Avenue Between Mason Boulevard Woodrow Road; Woodrow Road Between Rossville Avenue And Po Street; Foster Road Between Woodrow Road And Ramapo Ave Wieland Avenue Between Lenevar Avenue And Vernon Avenue; Gi Street Between Woodrow Road And West Castor Avenue; M Avenue Between Woodrow Road And Venus Place; Venus P Between Marcy Avenue And Powell Street; Powell Street Between Woodrow Road And West Castor Place; And, West Castor P Between Powell Street And Marcy Avenue, Including Water M Work, Together With All Work Incidental Thereto, Borough Of St Island.	And well enue; ilroy farcy Place ween Main
Documents Available A	t: 30-30 Thomson Avenue First Floor Bid Procurement Room Long Island City, New York 11101 8:30 A.M. to 4:00 P.M Monday through Friday	
Submission of Bids To:	30-30 Thomson Avenue First Floor Bid Procurement Room Long Island City, New York 11101 Before 11:00 A.M. on	
Bid Opening:	30-30 Thomson Avenue First Floor Bid Procurement Room Long Island City, New York 11101	
	Time and Date: 11:00 A.M. on MAY 28, 2014	
Pre-Bid Conference:	Yes NoX	
	If Yes, Mandatory: Optional: Time and Date: Location:	_
Bid Security:	Bid Security is required in the amount set forth below; provided, however, b security is not required if the TOTAL BID PRICE set forth on the Bid Form less than \$1,000,000.00.	
	(1) Bond in an amount not less than 10% of the TOTAL BID PRICE set	t
	forth on the Bid Form, OR  (2) Certified Check in an amount not less than 2% of the TOTAL BID PRICE set forth on the Bid Form.	
Performance and Paym Performance Security a Price.	ent Security: Required for contracts in the amount of \$1,000,000 or more. and Payment Security shall each be in an amount equal to 100% of the Contract.	ct
Agency Contact Person	Lorraine Holley Phone: 718-391-2601 FAX: 718-391-2615	

(NO TEXT ON THIS PAGE)

Project ID: SER002316

### BID SCHEDULE

### NOTICE TO BIDDERS

Items listed in this Bid Schedule which have one (1) digit followed by a decimal (e.g. 4.02 AG), excluding items beginning with the number "8.01", shall comply with the requirements of the corresponding numerical Sections of the NYCDOT Standard Highway Specifications as amended by Addendum No. 1 and Addendum No. 2, herein Volume 3 of 3.

Items listed in this Bid Schedule which have two (2) digits beginning with the number "5" followed by a decimal (e.g. 50.31CC15) shall comply with the requirements of the New York City Department of Environmental Protection (NYCDEP) Standard Sewer Specifications dated August 1, 2009, as amended by Addendum No. 2, herein Volume 3 of 3.

Items listed in this Bid Schedule which have two (2) digits beginning with the number "6" followed by a decimal (e.g. 60.11R612) shall comply with the requirements of the New York City Department of Environmental Protection (NYCDEP) Standard Water Main Specifications dated August 1, 2009, as amended by Addendum No. 2, herein Volume 3 of 3.

Items listed in this Bid Schedule which have two (2) digits beginning with the number "7" followed by a decimal (e.g. 70.31FN) shall comply with the requirements of the New York City Department of Environmental Protection (NYCDEP) Standard Sewer Specifications dated August 1, 2009, and Standard Water Main Specifications dated August 1, 2009, as amended by Addendum No. 2, herein Volume 3 of 3.

Items listed in this Bid Schedule beginning with the prefix "UTL-" (e.g. UTL-6.01.8) are for Gas Cost Sharing (EP-7) work and shall comply with the requirements of Addendum No. 3, herein Volume 3 of 3.

Project ID: SER002316

(NO TEXT ON THIS PAGE)



CONTRACT PIN: 8502014SE0001C PROJECT ID: SER002316

### **BID SCHEDULE**

- proportionate share of the Bidder's anticipated profit, overhead costs, and other indirect costs, anticipated NOTE: (1) The Agency may reject a bid if it contains unbalanced bid prices. An unbalanced bid is considered to be one containing lump sum or unit items which do not reflect reasonable actual costs plus a reasonable for the performance of the items in question.
- (2) The following bid prices on Unit Price Contracts are to be paid for the actual quantities of the item numbers appliances of every description necessary to complete the entire work, as specified, and the removal of all in the completed work or structure, and they cover the cost of all work, labor, material, tools, plant and debris, temporary work and appliances.
- (3) PLEASE BE SURE A LEGIBLE BID IS ENTERED, IN INK, FOR EACH ITEM. Alterations must be initialed in ink by the bidder.
- (4) The Extended Amount entered in Column 6 shall be the product of the Estimated Quantity in Column 3 times the Unit Price Bid in Column 5.
- Commissioner, in writing, if any pages are missing, and must request that such missing pages be furnished them. The pages of this Bid Schedule are numbered consecutively, as follows: B - 3 Through B - 27 (5) Prospective bidders must examine the Bid Schedule carefully and, before bidding, must advise the

PLEASE BE SURE A LEGIBLE BID IS ENTERED FOR EACH ITEM.
THE BIDDER SHALL INSERT THE TOTAL BID PRICE IN
THE BID FORM ON PAGE C-4 OF THIS BID BOOKLET.

2/21/2014 12:00 AM

## NEW YORK CITY DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE - BUREAU OF DESIGN

CONTRACT PIN: 8502014SE0001C

PROJECT ID: SER002316

COL 1 SEQ. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL. 3 ENGINEER'S ESTIMATE OF QUANTITY	COL 4	COL. 5 UNIT PRICE (IN FIGURES) DOLLARS : CTS	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS : CTS
001	4.01 RAG ASPHALT MACADAM PAVEMENT, 6" THICK	6,800.00			
005	4.01 RAJ ASPHALT MACADAM PAVEMENT, 9" THICK	14,910.00	% ≻.		
003	4.02 AB-R ASPHALTIC CONCRETE WEARING COURSE, 1-1/2" THICK	740.00	χ. Σ.		
400	4.02 AF-R ASPHALTIC CONCRETE WEARING COURSE, 2" THICK	14,750.00	S.Y.		
005	4.02 CA BINDER MIXTURE	2,400.00	TONS		
900	4.08 AA CONCRETE CURB (18" DEEP)	2,000.00	F.		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS CTS						
COL. 5 UNIT PRICE (IN FIGURES) DOLLARS:CTS						
COL.4 UNIT	L.F.	L.F.	L.F.	L.F.	L.F.	R.
COL. 3 ENGINEER'S ESTIMATE OF QUANTITIY	850.00	50.00	20.00	00.006	500.00	12,600.00
COL. 2  (TEM NUMBER and DESCRIPTION	4.08 BA CONCRETE CURB (21" DEEP)	4.09 AD STRAIGHT STEEL FACED CONCRETE CURB (18" DEEP)	4.09 AE STRAIGHT STEEL FACED CONCRETE CURB (21" DEEP)	4.09 CD CORNER STEEL FACED CONCRETE CURB (18" DEEP)	4.09 CE CORNER STEEL FACED CONCRETE CURB (21" DEEP)	4.13 AAS 4" CONCRETE SIDEWALK (UNPIGMENTED)
COL 1 SEQ. NO	007	800	600	010	011	012

2/21/2014 12:00 AM

## NEW YORK CITY DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE - BUREAU OF DESIGN

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 1 SEQ. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL.3 ENGINEER'S ESTIMATE OF QUANTITY	COL. 4 COL. 5 UNIT PRICE EXTE (IN FIGURES) (II UNIT DOLLARS CTS	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS : CTS
013	4.13 BAS 7" CONCRETE SIDEWALK (UNPIGMENTED)	7,400.00		
014	4.13 DE EMBEDDED PREFORMED DETECTABLE WARNING UNITS	00.006	Ä.	
015	4.18 A MAINTENANCE TREE PRUNING (UNDER 12" CAL.)	302.00	ЕАСН	
016	4.18 B MAINTENANCE TREE PRUNING (12" TO UNDER 18" CAL.)	00'96	ЕАСН	
017	<b>4.18 C</b> MAINTENANCE TREE PRUNING (18" TO UNDER 24" CAL.)	20.00	ЕАСН	
018	4.18 D MAINTENANCE TREE PRUNING (24" CAL. AND OVER)	5.00	ЕАСН	

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 1 SEQ. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL.3 ENGINEER'S ESTIMATE OF QUANTITY	COL 4	COL. 5 COL. 6 UNIT PRICE EXTENDED AMOUNT (IN FIGURES) DOLLARS CTS DOLLARS	INT
019	4.21 TREE CONSULTANT	1,000.00	P/HR		
020	<b>50.21M3C024D</b> 24" R.C.P. CLASS III STORM SEWER, ON CONCRETE CRADLE	1,215.00	L.F.		
021	<b>50.21M3C030D</b> 30" R.C.P. CLASS III STORM SEWER, ON CONCRETE CRADLE	685.00	L.F.		
022	<b>50.21M3C042D</b> 42" R.C.P. CLASS III STORM SEWER, ON CONCRETE CRADLE	1,780.00	L.F.		
023	<b>50.21M3E042D</b> 42" R.C.P. CLASS III STORM SEWER, ENCASED IN CONCRETE	213.00	L.F.		
024	50.31MC15 15" E.S.V.P. STORM SEWER, ON CONCRETE CRADLE	220.00	L.F.		:

2/21/2014 12:00 AM

## NEW YORK CITY DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE - BUREAU OF DESIGN

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 5 UNIT PRICE EXTENDED AMOUNT (IN FIGURES) (IN FIGURES) DOLLARS : CTS						
COL. 3 ENGINEER'S ESTIMATE OF QUANTITIY UNIT DG	350.00 L.F.	. 30.00 L.F.	120.00 L.F.	195.00 L.F.	6,100.00 L.F.	4.00 ЕАСН
	Щ	Ľ	Ľ	£		
COL.2 ITEM NUMBER and DESCRIPTION	50.31MC18 18" E.S.V.P. STORM SEWER, ON CONCRETE CRADLE	50.31ME12 12" E.S.V.P. STORM SEWER, ENCASED IN CONCRETE	50.31ME15 15" E.S.V.P. STORM SEWER, ENCASED IN CONCRETE	<b>50.31ME18</b> 18" E.S.V.P. STORM SEWER, ENCASED IN CONCRETE	<b>50.31SC10</b> 10" E.S.V.P. SANITARY SEWER, ON CONCRETE CRADLE	<b>51.11P006</b> STANDARD 6'-0" DIAMETER PRECAST MANHOLE
COL. 1 SEQ. NO	025	026	027	028	029	030

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 6 UNIT PRICE EXTENDED AMOUNT (IN FIGURES) (IN FIGURES) DOLLARS CTS DOLLARS CTS						
COL 4 UNIT	0 ЕАСН	0 ЕАСН	0 ЕАСН	0 ЕАСН	0 ЕАСН	0 ЕАСН
COL. 3 ENGINEER'S ESTIMATE OF QUANTITY	1.00	1.00	1.00	31.00	11.00	6.00
COL.2 TEM NUMBER and DESCRIPTION	51.11P007 STANDARD 7:0" DIAMETER PRECAST MANHOLE	51.11P008 STANDARD 8'-0" DIAMETER PRECAST MANHOLE	51.11P010 STANDARD 10:-0" DIAMETER PRECAST MANHOLE	51.21S0A1000V STANDARD MANHOLE TYPE A-1	<b>51.21S0A2000V</b> STANDARD MANHOLE TYPE A-2	51.21S0A3000V STANDARD SHALLOW MANHOLE TYPE A-3
COL. 1 SEQ. NO	031	032	033	034	035	036

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

TEM NUMBER and DESCRIPTION  51.21S0B1000V STANDARD MANHOLE TYPE B-1  51.21S0C-1042R STANDARD MANHOLE TYPE C-1 ON 42" R.C.P. SEWER  51.21S0C-1042R STANDARD MANHOLE TYPE C-1 ON 42" R.C.P. SEWER  51.41S001 STANDARD CATCH BASIN, TYPE 1  52.11D12  12" DUCTILE IRON PIPE BASIN CONNECTION  52.21V08 8" E.S.V.P. RISER FOR HOUSE CONNECTION 10" E.S.V.P. SWIRTPARY SEWER	COL. 3 COL. 4 COL. 5 COL. 6 ENGINEER'S (IN FIGURES) (IN FIGURES) OF QUANTITY UNIT DOLLARS CTS	0 EACH	7.00 EACH	52.00 EACH	1,100.00 L.F.	20.00 V.F.	175.00 EACH
037 038 039 040 040 042	COL. 2 ITEM NUMBER and DESCRIPTION		51.21S0C1042R STANDARD MANHOLE TYPE C-1 ON 42" R.C.P. SEWER	<b>51.41S001</b> STANDARD CATCH BASIN, TYPE 1	<b>52.11D12</b> 12" DUCTILE IRON PIPE BASIN CONNECTION	<b>52.21V08</b> 8" E.S.V.P. RISER FOR HOUSE CONNECTION	OR HOUSE CONNECTION ON 10" E.S.V

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 1 SEQ. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL.3 ENGINEER'S ESTIMATE OF QUANTITY	COL. 4	COL. 5 UNIT PRICE (IN FIGURES) DOLLARS:CTS	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS CTS
043	<b>52.31V08S10</b> 8" E.S.V.P. SPUR FOR HOUSE CONNECTION ON 10" E.S.V.P. SANITARY SEWER	6.00	ЕАСН		
044	52.41V06N NEW 6" E.S.V.P. HOUSE CONNECTION DRAIN ON CONCRETE CRADLE Unit price bid shall not be greater than: \$ 75.00	1,750.00	LF.		
045	<b>52.41V06R</b> 6" E.S.V.P. HOUSE CONNECTION DRAIN ON CONCRETE CRADLE (RECONNECTION)	20.00	L.F.		
046	52.41V08N NEW 8" E.S.V.P. HOUSE CONNECTION DRAIN ON CONCRETE CRADLE Unit price bid shall not be greater than: \$80.00	75.00	L.F.		
047	<b>53.11DR</b> TELEVISION INSPECTION AND DIGITAL AUDIO-VISUAL RECORDING OF SEWERS	11,300.00	L.F.		
048	6.02 AAN UNCLASSIFIED EXCAVATION	5,400.00	C.Y.		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL.1 SEQ.NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL. 3 ENGINEER'S ESTIMATE OF QUANTITY	COL 4	COL 5 UNIT PRICE (IN FIGURES) DOLLARS CTS	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS : CTS
049	6.25 RS TEMPORARY SIGNS	9,500.00	ñ.	· • • • • • • • • • • • • • • • • • • •	
050	<b>6.26</b> TIMBER CURB	11,000.00	L.F.		
051	6.28 AA LIGHTED TIMBER BARRICADES	1,600.00	L.F.		
052	<b>6.40 D</b> ENGINEER'S FIELD OFFICE (TYPE D)	24.00	MONTH		
053	<b>6.44</b> THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS (4" WIDE)	23,100.00	L.F.		
054	<b>6.49</b> TEMPORARY PAVEMENT MARKINGS (4" WIDE)	12,900.00	r.		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL 1 SEQ. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL. 3 ENGINEER'S ESTIMATE OF QUANTITY	COL 4	COL. 5 UNIT PRICE (IN FIGURES) DOLLARS CTS	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS CTS	
055	6.52 CG CROSSING GUARD	3,700.00	P/HR			
056	6.53 REMOVE EXISTING LANE MARKINGS (4" WIDE)	12,900.00	L.F.	-		
057	6.67 SUBBASE COURSE, SELECT GRANULAR MATERIAL	3,300.00	C.Y.			
058	6.68 PLASTIC FILTER FABRIC	10,500.00	S.Y.			
028	<b>6.87</b> PLASTIC BARRELS	4,400.00	ЕАСН			
090	60.11R520 FURNISHING AND DELIVERING 20-INCH DUCTILE IRON RESTRAINED JOINT PIPE (CLASS 55)	210.00	L.F.			

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL.1	2 ¬CO¬ 5	COL. 3 ENGINEER'S ESTIMATE	80L 4	COL. 5 UNIT PRICE (IN FIGURES)	COL. 6 EXTENDED AMOUNT
SEQ. NO	ITEM NUMBER and DESCRIPTION	OF QUANTITIY	UNIT	DOLLARS CTS	
061	60.11R606 FURNISHING AND DELIVERING 6-INCH DUCTILE IRON RESTRAINED JOINT PIPE (CLASS 56)	350.00	L.F.		
062	60.11R608 FURNISHING AND DELIVERING 8-INCH DUCTILE IRON RESTRAINED JOINT PIPE (CLASS 56)	1,300.00	H.		
063	60.11R612 FURNISHING AND DELIVERING 12-INCH DUCTILE IRON RESTRAINED JOINT PIPE (CLASS 56)	4,600.00	⊩ '		
064	60.12D06 LAYING 6-INCH DUCTILE IRON PIPE AND FITTINGS	380.00	<u>"</u>		
065	60.12D08 LAYING 8-INCH DUCTILE IRON PIPE AND FITTINGS	1,330.00	F.		
990	60.12D12 LAYING 12-INCH DUCTILE IRON PIPE AND FITTINGS	4,650.00	L.F.		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 1 SEQ. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL 3 ENGINEER'S ESTIMATE OF QUANTITY	COL. 4	COL. 5 UNIT PRICE (IN FIGURES) DOLLARS : CTS	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS CTS
<b>290</b>	<b>60.12D20</b> LAYING 20-INCH DUCTILE IRON PIPE AND FITTINGS	240.00	Ä.		
890	60.13M0A24 FURNISHING AND DELIVERING DUCTILE IRON MECHANICAL JOINT 24-INCH DIAMETER AND SMALLER FITTINGS, INCLUDING WEDGE TYPE RETAINER GLANDS	13.00	TONS		
690	61.11DMM06 FURNISHING AND DELIVERING 6-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	20.00	ЕАСН		
070	61.11DMM08 FURNISHING AND DELIVERING 8-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	4.00	ЕАСН		
071	61.11DMM12 FURNISHING AND DELIVERING 12-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	14.00	ЕАСН		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 1 SEQ. NO	COL. 2  ITEM NUMBER and DESCRIPTION	COL. 3 ENGINEER'S ESTIMATE OF QUANTITIY	COL. 4 UNIT	COL. 5 UNIT PRICE (IN FIGURES) DOLLARS : CTS	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS : CTS
072	61.11DMM20 FURNISHING AND DELIVERING 20-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	1.00	ЕАСН		
073	61.11TWC03 FURNISHING AND DELIVERING 3-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	3.00	ЕАСН		
074	61.11TWC04 FURNISHING AND DELIVERING 4-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	1.00	ЕАСН		
075	61.11TWC06 FURNISHING AND DELIVERING 6-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	1.00	ЕАСН		
076	61.12DMM06 SETTING 6-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	20.00	ЕАСН		
077	61.12DMM08 SETTING 8-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	4.00	ЕАСН		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 6  COL. 7  COL. 6  COL. 7  COL. 7						
COL 4 COL 5 UNIT PRICE (IN FIGURES Y UNIT DOLLARS	00 ЕАСН	1.00 ЕАСН	3.00 ЕАСН	1.00 ЕАСН	1.00 ЕАСН	00 ЕАСН
COL.3 ENGINEER'S ESTIMATE OF QUANTITY	14.00 ALVE					20.00
COL. 2 ITEM NUMBER and DESCRIPTION	61.12DMM12 SETTING 12-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	61.12DMM20 SETTING 20-INCH MECHANICAL JOINT DUCTILE IRON GATE VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	61.12TWC03 SETTING 3-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	61.12TWC04 SETTING 4-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	61.12TWC06 SETTING 6-INCH WET CONNECTION TAPPING VALVE COMPLETE WITH WEDGE TYPE RETAINER GLANDS	62.11SD FURNISHING AND DELIVERING HYDRANTS
COL. 1 SEQ. NO	078	079	080	081	082	083

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 1 SEQ. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL. 3 ENGINEER'S ESTIMATE OF QUANTITY	COL.4 COL.5 UNIT PRICE (IN FIGURES) UNIT DOLLARS : CTS	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS : CTS
084	62.12SG SETTING HYDRANTS COMPLETE WITH WEDGE TYPE RETAINER GLANDS	20.00	ЕАСН	
085	<b>62.13RH</b> REMOVING HYDRANTS	15.00	ЕАСН	
086	<b>62.14FS</b> FURNISHING, DELIVERING AND INSTALLING HYDRANT FENDERS	42.00	ЕАСН	
087	<b>63.11VC</b> FURNISHING AND DELIVERING VARIOUS CASTINGS	16.00	TONS	
088	<b>64.11EL</b> WITHDRAWING AND REPLACING HOUSE SERVICES USING 1-1/2- INCH OR LARGER SCREW TAPS	4.00	ЕАСН	
089	64.11ST WITHDRAWING AND REPLACING HOUSE SERVICES USING SMALLER THAN 1-1/2-INCH SCREW TAPS	84.00	ЕАСН	

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 5 COL. 6 UNIT PRICE (IN FIGURES) (IN FIGURES) DOLLARS CTS						
COL 4 UNIT	100.00 L.F.	300.00 L.F.	60.00 L.F.	450.00 L.F.	1.00 ЕАСН	3.00 ЕАСН
COL. 3 ENGINEER'S ESTIMATE OF QUANTITY						
COL. 2 TTEM NUMBER and DESCRIPTION	64.12COEG CUTTING AND OFFSETTING HOUSE SERVICE WATER CONNECTIONS (EQUAL TO OR GREATER THAN 3-INCH DIAMETER)	64.12COLT CUTTING AND OFFSETTING HOUSE SERVICE WATER CONNECTIONS (LESS THAN 3-INCH DIAMETER)	64.12ESEG EXTENDING HOUSE SERVICE WATER CONNECTIONS (EQUAL TO OR GREATER THAN 3-INCH DIAMETER)	64.12ESLT EXTENDING HOUSE SERVICE WATER CONNECTIONS (LESS THAN 3-INCH DIAMETER)	64.13WC08 FURNISHING, DELIVERING AND INSTALLING WET CONNECTION SLEEVE ON 8-INCH WATER MAIN PIPE WITH VARIOUS OUTLETS	64.13WC12 FURNISHING, DELIVERING AND INSTALLING WET CONNECTION SLEEVE ON 12-INCH WATER MAIN PIPE WITH VARIOUS OUTLETS
COL. 1 SEQ. NO	060	091	092	093	094	960

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL1	7 TOD	COL. 3 ENGINEER'S ESTIMATE	COL. 4	COL. 5 COL. 6 UNIT PRICE EXTENDED AMOUNT (IN FIGURES)	MOUNT
SEQ. NO	ITEM NUMBER and DESCRIPTION	<b>OF QUANTITIY</b>	TINO	CTS	S CTS
960	<b>64.13WC20</b> FURNISHING, DELIVERING AND INSTALLING WET CONNECTION SLEEVE ON 20-INCH WATER MAIN PIPE WITH VARIOUS OUTLETS	3.00	ЕАСН		
260	<b>65.11BR</b> FURNISHING, DELIVERING AND INSTALLING BANDS, RODS, WASHERS, ETC., COMPLETE, FOR RESTRAINING JOINTS	275.00	LBS.		
860	65.21PS FURNISHING AND PLACING POLYETHYLENE SLEEVE Unit price bid shall not be less than: \$ 0.50	4,000.00	r.		
660	65.31FF FURNISHING, DELIVERING AND PLACING FILTER FABRIC Unit price bid shall not be less than: \$ 0.10	42,100.00	S.F.		
100	65.51PC FURNISHING AND PLACING CAST-IN-PLACE CONCRETE CLASS 40 AND PRECAST CONCRETE CLASS 50	40.00	C.Y.		
101	65.61SS FURNISHING, DELIVERING AND PLACING STRUCTURAL, REINFORCING AND MISCELLANEOUS STEEL	34,000.00	LBS.		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

65.71SG	COL. 2 ITEM NUMBER and DESCRIPTION	COL.3 ENGINEER'S ESTIMATE OF QUANTITY 100.00	COL 4 UNIT	COL. 5 UNIT PRICE (IN FIGURES) DOLLARS CTS	COL.6 EXTENDED AMOUNT (IN FIGURES) DOLLARS CTS
FURNISHING, DELIVERING AND PLACING SCREENED GRAVEL OR SCREENED BROKEN STONE BEDDING	ING SCREENED GRAVEL OR		<u>:</u>		
7.13 B MAINTENANCE OF SITE Unit price bid shall not be less than: \$7,500.00	7,500.00	18.00	MONTH		
<b>7.36</b> PEDESTRIAN STEEL BARRICADES		22,700.00	LF.		
7.88 AA RODENT INFESTATION SURVEY AND MONITORING Unit price bid shall not be less than: \$5,200.00	NITORING ,200.00	1.00	L.S.		
7.88 AB RODENT BAIT STATIONS Unit price bid shall not be less than: \$60.00	50.00	1,050.00	ЕАСН		
7.88 AC BAITING OF RODENT BAIT STATIONS Unit price bid shall not be less than: \$8.50	8.50	1,050.00	ЕАСН		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL 1 SEG. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL.3 ENGINEER'S ESTIMATE OF QUANTITIY	COL. 5 UNIT PRICE (IN FIGURES UNIT DOLLARS	COL. 6  EXTENDED AMOUNT S) (IN FIGURES) CTS DOLLARS CTS
108	7.88 AD WATERBUG BAIT APPLICATIONS Unit price bid shall not be less than: \$65.00	325.00	ВГОСК	
109	70.31FN FENCING Unit price bid shall not be less than: \$2.00	31,400.00	L.F.	
110	70.51EO EXCAVATION OF BOULDERS IN OPEN CUT Unit price bid shall not be less than: \$75.00	70.00	C.Y.	
111	70.61RE ROCK EXCAVATION	50.00	C.Y.	
112	70.71SB STONE BALLAST Unit price bid shall not be less than: \$ 15.00	170.00	C.Y.	
113	70.81CB CLEAN BACKFILL Unit price bid shall not be less than: \$15.00	10,800.00	C.Y.	

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

- BUREAU OF DESIGN CONTRACT

COL 1	COL. 2	COL.3 ENGINEER'S ESTIMATE	COL 4	5 RES)	COL. 6 EXTENDED AMOUNT (IN FIGURES)
SEQ. NO	ITEM NUMBER and DESCRIPTION	OF QUANTITY	LINO (	DOLLARS OTS	DOLLARS : CTS
<del>1</del> 4	70.91SW12 FURNISHING AND PLACING SHEETING AND BRACING IN TRENCH FOR WATER MAIN PIPE 12-INCH IN DIAMETER AND LESS	7,300.00	'n.		
115	70.91SW20 FURNISHING AND PLACING SHEETING AND BRACING IN TRENCH FOR WATER MAIN PIPE 20-INCH IN DIAMETER	2,000.00	S.F.		
116	72.11HF HYDRAULIC FILL FOR ABANDONED SEWERS AND WATER MAINS	00.009	C.Y.		:
117	73.11AB ADDITIONAL BRICK MASONRY Unit price bid shall not be less than: \$62.50	50.00	C.Y.		
118	73.21AC ADDITIONAL CONCRETE Unit price bid shall not be less than: \$62.50	300.00	C.Y.		
119	73.31AE0 ADDITIONAL EARTH EXCAVATION INCLUDING TEST PITS (ALL DEPTHS) Unit price bid shall not be less than: \$20.00	700.00	C.Y.		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 1 SEQ. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL.3 ENGINEER'S ESTIMATE OF QUANTITY	COL 4 UNIT	COL. 5 UNIT PRICE ( IN FIGURES ) DOLLARS : CTS	COL. 6 EXTENDED AMOUNT (IN FIGURES) DOLLARS : CTS
120	73.41AG ADDITIONAL SELECT GRANULAR BACKFILL Unit price bid shall not be less than: \$ 15.00	2,300.00	C.Y.		-
121	73.51AS ADDITIONAL STEEL REINFORCING BARS Unit price bid shall not be less than: \$1.00	40,500.00	LBS.		
122	8.08 VARIABLE MESSAGE BOARD	2.00	ЕАСН		
123	9.04 HW ALLOWANCE FOR ANTI-FREEZE ADDITIVE IN CONCRETE PRICE BID SHALL BE FOR THE FIXED SUM OF \$ 2,000.00	1.00	Ř.	2,000	2,000 00
124	9.30 STORM WATER POLLUTION PREVENTION	1.00	L.S.		

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

COL. 5. COL. 6 UNIT PRICE EXTENDED AMOUNT (IN FIGURES) (IN FIGURES) DOLLARS : CTS						
COL. 4 UNIT	ЕАСН	ЕАСН	ЕАСН	ЕАСН	ЕАСН	H.
COL. 3 ENGINEER'S ESTIMATE OF QUANTITY	10.00	2.00	29.00	6.00	9.00	3,200.00
COL. 2 ITEM NUMBER and DESCRIPTION	UTL-6.01.1 GAS MAIN CROSSING SEWER UP TO 24" IN DIAMETER (S6.01) Unit price bid shall not be less than: \$ 1,040.00	UTL-6.01.3 GAS MAIN CROSSING SEWER 36" THRU 42" IN DIAMETER (S6.01) Unit price bid shall not be less than: \$ 2,040.00	UTL-6.01.8 GAS SERVICES CROSSING TRENCHES AND/OR EXCAVATIONS (S6.01) Unit price bid shall not be less than: \$ 465.00	UTL-6.01.9 GAS MAIN CROSSING WATER MAIN UP TO 20" IN DIAMETER (\$6.01) Unit price bid shall not be less than: \$ 485.00	UTL-6.02  EXTRA EXCAVATION FOR THE INSTALLATION OF CATCH BASIN SEWER DRAIN PIPES WITH GAS INTERFERENCES (\$6.02) Unit price bid shall not be less than: \$715.00	UTL-6.03 REMOVAL OF ABANDONED GAS FACILITIES. ALL SIZES. (S6.03) Unit price bid shall not be less than: \$ 15.00
COL 1 SEQ. NO	125	126	127	128	129	130

# NEW YORK CITY DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE - BUREAU OF DESIGN

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

### **BID SCHEDULE FORM**

	COL 2	COL.3 ENGINEER'S ESTIMATE	<b>4</b> 703	COL 5 UNIT PRICE	COL. 6 EXTENDED AMOUNT	
ITEM NUMBER and DESCRIPTION	RIPTION	OF QUANTITIY	TIND	DOLLARS CTS	( IN FIGURES )	CTS
UTL-6.03.1 REMOVAL OF ABANDONED GAS FACILITIES WITH POSS TAR WRAP. ALL SIZES. (S6.03) Unit price bid shall not be less than: \$ 25.00	WITH POSSIBLE COAL	800.00	F.			
UTL-6.04 ADJUST HARDWARE TO GRADE USING SPACER RINGS/ADAPTORS. (STREET REPAVING.) (S6.04) Unit price bid shall not be less than: \$ 35.00	CER RINGS/ADAPTORS.	25.00	ЕАСН			
UTL-6.05 ADJUST HARDWARE TO GRADE BY RESETTING. (ROAD RECONSTRUCTION.) (S6.05) Unit price bid shall not be less than: \$ 65.00	NG. (ROAD	30.00	ЕАСН			
UTL-6.06 SPECIAL CARE EXCAVATION AND BACKFILLING (S6.06) Unit price bid shall not be less than: \$ 180.00	NG (S6.06)	1,000.00	C.Y.			
UTL-6.07 TEST PITS FOR GAS FACILITIES (S6.07) Unit price bid shall not be less than: \$ 100.00	0	100.00	C.Y.			

2/21/2014 12:00 AM

NEW YORK CITY DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE - BUREAU OF DESIGN

PROJECT ID: SER002316 CONTRACT PIN: 8502014SE0001C

## **BID SCHEDULE FORM**

COL. 1 SEQ. NO	COL. 2 ITEM NUMBER and DESCRIPTION	COL. 3 ENGINEER'S ESTIMATE OF QUANTITY	COL. 4 UNIT	COL. 5 UNIT PRICE ( IN FIGURES ) DOLLARS :CTS	EXTENDED AMOUNT (IN FIGURES) DOLLARS COLS
136	UTL-GCS-2WS	1.00	F.S.	30,000 00	30,000; 00
	GAS INTERFERENCES AND ACCOMMODATIONS				
	PRICE BID SHALL BE FOR THE FIXED SUM OF \$ 30,000.00				

SUB-TOTAL: \$\_

137	137 6.39 A	1.00	L.S.	· .	 	
	MOBILIZATION		-		 	
	BID PRICE OF MOBILIZATION SHALL NOT EXCEED 4% OF THE ABOVE SUB-TOTAL PRICE.					

TOTAL BID PRICE: \$

PLEASE BE SURE A LEGIBLE BID IS ENTERED FOR EACH ITEM.
THE BIDDER SHALL INSERT THE TOTAL BID PRICE IN
THE BID FORM ON PAGE C-4 OF THIS BID BOOKLET.

### BID FORM THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

### BID FOR FURNISHING ALL LABOR AND MATERIAL NECESSARY AND REQUIRED FOR:

PROJECT ID: SER002316

### FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN
WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

### **INCLUDING WATER MAIN WORK**

### Together With All Work Incidental Thereto BOROUGH OF STATEN ISLAND

Name of Bidder:			
Date of Bid Opening:			
Bidder is: (Check one, whichever applies)	Individual ( )	Partnership ( )	Corporation ( )
Place of Business of Bidder:	·		
Bidder's Telephone Number:	Fax	Number:	
Bidder's E-Mail Address:			
Residence of Bidder (If Individual):			
If Bidder is a Partnership, fill in the following	g blanks:		
Names of Partners		Residence of	Partners
	·		
			· · · ·
If Bidder is a Corporation, fill in the followin	g blanks:		
Organized under the laws of the State of	1846		
Name and Home Address of President:			
		419	
Name and Home Address of Secretary:			
Name and Home Address of Treasurer:	:		
CITY OF NEW YORK	C-1	*	BID BOOKLET

DEPARTMENT OF DESIGN AND CONSTRUCTION

DECEMBER 2013

The above-named Bidder affirms and declares:

- 1. The said bidder is of lawful age and the only one interested in this bid; and no person, firm or corporation other than hereinbefore named has any interest in this bid, or in the Contract proposed to be taken.
- 2. By submission of this bid, each bidder and each person signing on behalf of any bidder certifies, and in the case of a joint bid each party thereto certifies as to its own organization, under penalty of perjury, that to the best of its knowledge and belief: (1) the prices in this bid have been arrived at independently without collusion, consultation, communication or agreement, for the purpose of restricting competition, as to any matter relating to such prices with any other bidder or with any competitor; (2) unless otherwise required by law, the prices quoted in this bid have not been knowingly disclosed by the bidder and will not knowingly be disclosed by the bidder prior to opening, directly or indirectly, to any other bidder or to any competitor; and (3) No attempt has been made or will be made by the bidder to induce any other person, partnership or corporation to submit or not to submit a bid for the purpose of restricting competition.
- 3. No councilman or other officer or employee or person whose salary is payable in whole or in part from the City Treasury is directly or indirectly interested in this bid, or in the supplies, materials, equipment, work or labor to which it relates, or in any of the profits thereof.
- 4. The bidder is not in arrears to the City of New York upon debt or contract or taxes, and is not a defaulter, as surety or otherwise, upon any obligation of the City of New York, and has not been declared not responsible, or disqualified, by any agency of the City of New York or State of New York, nor is there any proceeding pending relating to the responsibility or qualification of the bidder to receive public contracts except as set forth on the Affirmation included as page C-6 of this Bid Booklet.

The bidder hereby affirms that it has paid all applicable City income, excise and other taxes for all years it has conducted business activities in New York City.

5. The bidder, as an individual, or as a member, partner, director or officer of the bidder, if the same be a firm, partnership or corporation, executes this document expressly warranting and representing that should this bid be accepted by the City and the Contract awarded to him, he and his subcontractors engaged in the performance: (1) will comply with the provisions of Section 6-108 of the Administrative Code of the City of New York and the non-discrimination provisions of Section 220a of the New York State Labor Law, as more expressly and in detail set forth in the Agreement; (2) will comply with Section 6-109 of the Administrative Code of the City of New York in relation to minimum wages and other stipulations as more expressly and in detail set forth in the Agreement; (3) have complied with the provisions of the aforesaid laws since their respective effective dates, and (4) will post notices to be furnished by the City, setting forth the requirements of the aforesaid laws in prominent and conspicuous places in each and every plant, factory, building and structure where employees engaged in the performance of the Contract can readily view it, and will continue to keep such notices posted until the supplies, materials and equipment, or work labor and services required to be furnished or rendered by the Contractor have been finally accepted by the City. In the event of any breach or violation of the foregoing, the Contractor may be subject to damages, liquidated or otherwise, cancellation of the Contract and suspension as a bidder for a period of three years. (The words, "the bidder", "he", "his", and "him" where used herein shall mean the individual bidder, firm, partnership or corporation executing the bid).

### 6. Compliance Report

The bidder, as an individual, or as a member, partner, director, or officer of the bidder, if the same be a firm, partnership, or corporation, (1) represents that his attention has been specifically drawn to Executive Order No. 50, dated, April 25, 1980, on Equal Employment Compliance of the contract, and (2) warrants that he will comply with the provisions of Executive Order No. 50. The Employment Report must be submitted as part of the bid.

The bidder, as an individual, or as a member, partner, director, or officer of the bidder, if the same be a firm, partnership, or corporation, executes this document expressly warranting that he will comply with: (1) the provision of the contract on providing records, Chapter 8.

- 7. By submission of this bid, the bidder certifies that it now has and will continue to have the financial capability to fully perform the work required for this contract. Any award of this contract will be made in reliance upon such certification. Upon request therefor, the bidder will submit written verification of such financial capability in a form that is acceptable to the department.
- 8. In accordance with Section 165 of the State Finance Law, the bidder agrees that tropical hardwoods, as defined in Section 165 of the State Finance Law, shall not be utilized in the performance of this Contract, except as the same are permitted by the foregoing provision of law.
- 9. The bidder has visited and examined the site of the work and has carefully examined the Contract in the form approved by the Corporation Counsel, and will execute the Contract and perform all its items, covenants and conditions, and will provide, furnish and deliver all the work, materials, supplies, tools and appliances for all labor and materials necessary or required for the hereinafter named work, all in strict conformity with the Contract, for the prices set forth in the Bid Schedule:
- 10. <u>M/WBE UTILIZATION PLAN</u>: By signing its bid, the bidder agrees to the Vendor Certification and Required Affirmations set forth below, unless a full waiver of the Participation Goals is granted. The Vendor Certification and Required Affirmations will be deemed to satisfy the requirement to complete Section V of Part II of Schedule B: M/WBE Utilization Plan.

### Section V: Vendor Certification and Required Affirmations:

### I hereby:

- 1) acknowledge my understanding of the M/WBE participation requirements as set forth in this Contract and the pertinent provisions of Section 6-129 of the Administrative Code of the City of New York and the rules promulgated thereunder;
- 2) affirm that the information supplied in support of the M/WBE Utilization Plan is true and correct;
- 3) agree, if awarded this Contract, to comply with the M/WBE participation requirements of this Contract, the pertinent provisions of Section 6-129, and the rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract;
- 4) agree and affirm that it is a material term of this Contract that the Vendor will award the total dollar value of the M/WBE Participation Goals to certified MBEs and/or WBEs, unless a full waiver is obtained or such goals are modified by the Agency; and
- 5) agree and affirm, if awarded this Contract, to make all reasonable, good faith efforts to meet the M/WBE Participation Goals, or If a partial waiver is obtained or such goals are modified by the Agency, to meet the modified Participation Goals by soliciting and obtaining the participation of certified MBE and/or WBE firms.

(NO TEXT ON THIS PAGE)

### **BID FORM**

### PROJECT ID: SER002316

TOTAL	BID PRICE:	In the space provided below, the Bidder shall indicate its Total Bid Price in
		Price is set forth on the final page of the Bid Schedule.

TOTAL BID PRICE: (a/k/a BID PROPOSAL)

\$

### **BIDDER'S SIGNATURE AND AFFIDAVIT**

Bidder:		
By:		
29.	(Signature of Partner or corporate officer)	
Attest: (Corporate Seal)	Secretary of Corporate Bidder	

Affidavit on the following page should be subscribed and sworn to before a Notary Public

### **BID FORM** (TO BE NOTARIZED)

<u>AFFIDAVIT</u>	WHERE BIDDER IS AN INDIVIDUAL
STATE OF NEW YORK, COUNTY OF	ss:ss:ss:
I am the person described in and who execurespects true.	sted the foregoing bid, and the several matters therein stated are in all
Subscribed and sworn to before me this day of,	(Signature of the person who signed the Bid)
Notary Public	
AFFIDAVIT	WHERE BIDDER IS A PARTNERSHIP
STATE OF NEW YORK, COUNTY OF	ss: being duly sworn says:
I am a member of bid. I subscribed the name of the firm there respects true.	the firm described in and which executed the foregoing to on behalf of the firm, and the several matters therein stated are in all
Subscribed and sworn to before me this,,	(Signature of Partner who signed the Bid)
Notary Public	<b>-</b> -
AFFIDAVIT	WHERE BIDDER IS A CORPORATION
STATE OF NEW YORK, COUNTY OF	ss: being duly sworn says: of the above named corporation whose name is subscribed to and which
executed the foregoing bid. I reside at I have knowledge of the several matters ther	ein stated, and they are in all respects true.
Subscribed and sworn to before me this day of,	(Signature of Partner who signed the Bid)
Notary Public	
CITY OF NEW YORK	C-5 BID BOOKLET

DECEMBER 2013

DEPARTMENT OF DESIGN AND CONSTRUCTION

### **AFFIRMATION**

n none, me	bidder shall insert the word "None" in the spa	ce provided above.)	
ull Name of	Bidder:		
City	State	Zip Code	
	E BOX AND INCLUDE APPROPRIATE NU	•	
_/ A-	Individual or Sole Proprietorship* SOCIAL SECURITY NUMBER		
B -	Partnership, Joint Venture or other unincome EMPLOYER IDENTIFICATION NUMBER		
/	Corporation EMPLOYER IDENTIFICATION NUMBER	ER .	
i,			

This affirmation must be signed by an officer or duly authorized representative.

\*Under the Federal Privacy Act the furnishing of Social Security Numbers by bidders on City contracts is voluntary. Failure to provide a Social Security Number will not result in a bidder's disqualification. Social Security Numbers will be used to identify bidders, proposers or vendors to ensure their compliance with laws, to assist the City in enforcement of laws, as well as to provide the City a means of identifying of businesses which seek City contracts.

(NO TEXT ON THIS PAGE)

### BID BOND 1 FORM OF BID BOND

KNOW ALL MEN BY THESE PRESENTS. That we,
hereinafter referred to as the "Principal", and
hereinafter referred to as the "Surety" are held and firmly bound to THE CITY OF NEW YORK, hereinafter referred to as the "CITY", or to its successors and assigns in the penal sum of
(\$), Dollars lawful money of the United States, for the payment of which said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.
Whereas, the Principal is about to submit (or has submitted) to the City the accompanying proposal, hereby made a part hereof, to enter into a contract in writing for
NOW, THEREFORE, the conditions of this obligation are such that if the Principal shall not withdraw said Proposal without the consent of the City for a period of forty-five (45) days after the opening of bids and in the event of acceptance of the Principal's Proposal by the City, if the Principal shall:  (a) Within ten (10) days after notification by the City, execute in quadruplicate and deliver to the City all the executed counterparts of the Contract in the form set forth in the Contract Documents, in accordance with the proposal as accepted, and  (b) Furnish a performance bond and separate payment bond, as may be required by the City, for the faithful performance and proper fulfillment of such Contract, which bonds shall be satisfactory in all respects to the City and shall be executed by good and sufficient sureties, and  (c) In all respects perform the agreement created by the acceptance of said Proposal as provided in the Information for Bidders, bound herewith and made a part hereof, or if the City shall reject the aforesaid Proposal, then this obligation shall be null and void; otherwise to remain in full force and effect.

### BID BOND 2

In the event that the Proposal of the Principal shall be accepted and the Contract be awarded to him the Surety hereunder agrees subject only to the payment by the Principal of the premium therefore, if requested by the City, to write the aforementioned performance and payment bonds in the form set forth in the Contract Documents.

It is expressly understood and agreed that the liability of the Surety for any and all claims hereunder shall in no event exceed the penal amount of this obligation as herein stated.

There shall be no liability under this bond if, in the event of the acceptance of the Principal's Proposal by the City, either a performance bond or payment bond, or both, shall not be required by the City on or before the 30th day after the date on which the City signs the Contract.

The surety, for the value received, hereby stipulates and agrees that the obligations of the Surety and its bond shall in no way be impaired or affected by any postponements of the date upon which the City will receive or open bids, or by any extensions of the time within which the City may accept the Principal's Proposal, or by any waiver by the City of any of the requirements of the Information for Bidders, and the Surety hereby waives notice of any such postponements, extensions, or waivers.

and such of them as are corporations have cau	al and the Surety have hereunto set their hands and seals used their corporate seals to be hereto affixed and these
presents to be signed by their proper officers the	day of,
(Seal)	(L.S.)
	Principal
	By:
(Seal)	
	Surety
	By:

### BID BOND 3

### ACKNOWLEDGMENT OF PRINCIPAL, IF A CORPORATION

State of	County of	•	SS:
On this	day of		ss:, before me personally came , being by me duly sworn, did depose and say
		to me known, who	, being by me duly sworn, did depose and say
mai no rostaos ai			, come by me daily sworm, and depose and sa
mai ne is me		OT	·
the corporation d	escribed in and which e	executed the foregoing	ng instrument; that he knows the seal of said
corporation; that	one of the seals affixed	l to said instrument i	s such seal; that it was so affixed by order of
the directors of sa	aid corporation, and tha	t he signed his name	e thereto by like order.
			N. D. 1.1.
			Notary Public
	ACKNOWLEDGM	ENT OF PRINCIPA	L, IF A PARTNERSHIP
•			
State of	County of		ss: , before me personally appeared
On this	day of	,	, before me personally appeared
		to me known and k	nown to me to be one of the members of the
firm of		de	scribed in and who executed the foregoing
instrument, and h	e acknowledged to me	that he executed the	same as and for the act and deed of said
firm.			
			Notary Public
	ACKNOWI FDGM	FNT OF PRINCIPA	L, IF AN INDIVIDUAL
	TIOIL TO WELLOUI	EIVI OI TIMIVOII A	E, I AN INDIVIDUAL
State of	County of		ss.
On this	day of	_	before me personally appeared
		to me known and l	known to me to be the person described in ed that he executed the same.
and who executed	the foregoing instrume	ent and acknowledge	ed that he executed the same.
	•	_	
			Notary Public
	AFEIV ACUNIONI ED		
	AFFIX ACKNOWLED	GMENTS AND JUST	IFICATION OF SURETIES

(NO TEXT ON THIS PAGE)

### M/WBE PROGRAM

### M/WBE UTILIZATION PLAN

<u>M/WBE Program Requirements</u>: The requirements for the M/WBE Program are set forth on the following pages of this Bid Booklet, in the section entitled "Notice to All Prospective Contractors".

Schedule B: M/WBE Utilization Plan: Schedule B: M/WBE Utilization Plan for this Contract is set forth in this Bid Booklet on the pages following the section entitled "Notice to All Prospective Contractors". The M/WBE Utilization Plan (Part I) indicates whether Participation Goals have been established for this Contract. If Participation Goals have been established for this Contract, the bidder must submit an M/WBE Utilization Plan (Part II) with its bid.

<u>Waiver</u>: The bidder may seek a full or partial pre-award waiver of the Participation Goals in accordance with the "Notice to All Prospective Contractors" (See Part A, Section 10). The bidder's request for a waiver must be submitted at least seven (7) calendar days prior to the bid date. Waiver requests submitted after the deadline will not be considered. The form for requesting a waiver of the Participation Goals is set forth in the M/WBE Utilization Plan (Part III).

Rejection of the Bid: The bidder must complete Schedule B: M/WBE Utilization Plan (Part II) set forth in this Bid Booklet on the pages following the section entitled "Notice to All Prospective Contractors". A Schedule B submitted by the bidder which does not include the Vendor Certification and Required Affirmations (See Section V of Part II) will be deemed to be non-responsive, unless a full waiver of the Participation Goals is granted (Schedule B, Part III). In the event that the City determines that the bidder has submitted a Schedule B where the Vendor Certification and Required Affirmations are completed but other aspects of the Schedule B are not complete, or contain a copy or computation error that is at odds with the Vendor Certification and Required Affirmations, the bidder will be notified by the Agency and will be given four (4) calendar days from receipt of notification to cure the specified deficiencies and return a completed Schedule B to the Agency. Failure to do so will result in a determination that the Bid is non-responsive. Receipt of notification is defined as the date notice is emailed or faxed (if the bidder has provided an email address or fax number), or no later than five (5) calendar days from the date of mailing or upon delivery, if delivered.

<u>Impact on LBE Requirements</u>: If Participation Goals have been established for the participation of M/WBEs, the contractor is not required to comply with the Locally Based Enterprise Program ("LBE"). The LBE Program is set forth in Article 67 of the Contract.

### NOTICE TO ALL PROSPECTIVE CONTRACTORS

### PARTICIPATION BY MINORITY-OWNED AND WOMEN-OWNED BUSINESS ENTERPRISES IN CITY PROCUREMENT

### ARTICLE I. M/WBE PROGRAM

Local Law No. 129 of 2005 added and Local Law 1 of 2013 amended Section 6-129 of the Administrative Code of the City of New York (hereinafter "Section 6-129"). Section 6-129 establishes the program for participation in City procurement ("M/WBE Program") by minority- owned business enterprises ("MBEs") and women-owned business enterprises ("WBEs"), certified in accordance with Section 1304 of the New York City Charter. As stated in Section 6-129, the intent of the program is to address the impact of discrimination on the City's procurement process, and to promote the public interest in avoiding fraud and favoritism in the procurement process, increasing competition for City business, and lowering contract costs. The contract provisions contained herein are pursuant to Section 6-129, and the rules of the Department of Small Business Services ("DSBS") promulgated thereunder.

If this Contract is subject to the M/WBE Program established by Section 6-129, the specific requirements of MBE and/or WBE participation for this Contract are set forth in Schedule B of the Contract (entitled the "M/WBE Utilization Plan"), and are detailed below. The Contractor must comply with all applicable MBE and WBE requirements for this Contract.

All provisions of Section 6-129 are hereby incorporated in the Contract by reference and all terms used herein that are not defined herein shall have the meanings given such terms in Section 6-129. Article I, Part A, below, sets forth provisions related to the participation goals for construction, standard and professional services contracts. Article I, Part B, below, sets forth miscellaneous provisions related to the M/WBE Program.

### PART A

### PARTICIPATION GOALS FOR CONSTRUCTION, STANDARD AND PROFESSIONAL SERVICES CONTRACTS OR TASK ORDERS

1. The MBE and/or WBE Participation Goals established for this Contract or Task Orders issued pursuant to this Contract, ("Participation Goals"), as applicable, are set forth on Schedule B, Part I to this Contract (see Page 1, line 1 Total Participation Goals) or will be set forth on Schedule B, Part I to Task Orders issued pursuant to this Contract, as applicable.

The **Participation Goals** represent a percentage of the total dollar value of the Contract or Task Order, as applicable, that may be achieved by awarding subcontracts to firms certified with New York City Department of Small Business Services as MBEs and/or WBEs, and/or by crediting the participation of prime contractors and/or qualified joint ventures as provided in Section 3 below, unless the goals have been waived or modified by Agency in accordance with Section 6-129 and Part A, Sections 10 and 11 below, respectively.

- 2. If **Participation Goals** have been established for this Contract or Task Orders issued pursuant to this Contract, Contractor agrees or shall agree as a material term of the Contract that Contractor shall be subject to the **Participation Goals**, unless the goals are waived or modified by Agency in accordance with Section 6-129 and Part A, Sections 10 and 11 below, respectively.
- 3. If Participation Goals have been established for this Contract or Task Order issued pursuant to this Contract, a Contractor that is an MBE and/or WBE shall be permitted to count its own participation toward fulfillment of the relevant Participation Goal, provided that in accordance with Section 6-129 the value of Contractor's participation shall be determined by subtracting from the total value of the Contract or Task Order, as applicable, any amounts that the Contractor pays to direct subcontractors (as defined in Section 6-129(c)(13)), and provided further that a Contractor that is certified as both an MBE and a WBE may count its own participation either toward the goal for MBEs or the goal for WBEs, but not both.

A Contractor that is a qualified joint venture (as defined in Section 6-129(c)(30)) shall be permitted to count a percentage of its own participation toward fulfillment of the relevant **Participation Goal**. In accordance with Section 6-129, the value of Contractor's participation shall be determined by subtracting from the total value of the Contract or Task Order, as applicable, any amounts that Contractor pays to direct subcontractors, and then multiplying the remainder by the percentage to be applied to total profit to determine the amount to which an MBE or WBE is entitled pursuant to the joint venture agreement, provided that where a participant in a joint venture is certified as both an MBE and a WBE, such amount shall be counted either toward the goal for MBEs or the goal for WBEs, but not both.

- 4. A. If Participation Goals have been established for this Contract, a prospective contractor shall be required to submit with its bid or proposal, as applicable, a completed Schedule B, M/WBE Utilization Plan, Part II (see Pages 2-4) indicating: (a) whether the contractor is an MBE or WBE, or qualified joint venture; (b) the percentage of work it intends to award to direct subcontractors; and (c) in cases where the contractor intends to award direct subcontracts, a description of the type and dollar value of work designated for participation by MBEs and/or WBEs, and the time frames in which such work is scheduled to begin and end. In the event that this M/WBE Utilization Plan indicates that the bidder or proposer, as applicable, does not intend to meet the Participation Goals, the bid or proposal, as applicable, shall be deemed non-responsive, unless Agency has granted the bidder or proposer, as applicable, a pre-award waiver of the Participation Goals in accordance with Section 6-129 and Part A, Section 10 below.
- B. (i) If this Contract is for a master services agreement or other requirements type contract that will result in the issuance of Task Orders that will be individually registered ("Master Services Agreement") and is subject to M/WBE Participation Goals, a prospective contractor shall be required to submit with its bid or proposal, as applicable, a completed Schedule B, M/WBE Participation Requirements for Master Services Agreements That Will Require Individually Registered Task Orders, Part II (page 2) indicating the prospective contractor's certification and required affirmations to make all reasonable good faith efforts to meet participation goals established on each individual Task Order issued pursuant to this Contract, or if a partial waiver is obtained or such goals are modified by the Agency, to meet the modified Participation Goals by soliciting and obtaining the participation of certified MBE and/or WBE firms. In the event that the Schedule B indicates that the bidder or proposer, as applicable, does not intend to meet the Participation Goals that may be established on Task Orders issued pursuant to this Contract, the bid or proposal, as applicable, shall be deemed nonresponsive.
- (ii) Participation Goals on a Master Services Agreement will be established for individual Task Orders issued after the Master Services Agreement is awarded. If Participation Goals have been established on a Task Order, a contractor shall be required to submit a Schedule B M/WBE Utilization Plan For Independently Registered Task Orders That Are Issued Pursuant to Master Services Agreements, Part II (see Pages 2-4) indicating: (a) whether the contractor is an MBE or WBE, or qualified joint venture; (b) the percentage of work it intends to award to direct subcontractors; and (c) in cases where the contractor intends to award direct subcontracts, a description of the type and dollar value of work designated for participation by MBEs and/or WBEs, and the time frames in which such work is scheduled to begin and end. The contractor must engage in good faith efforts to meet the Participation Goals as established for the Task Order unless Agency has granted the contractor a pre-award waiver of the Participation Goals in accordance with Section 6-129 and Part A, Section 10 below.
- C. THE BIDDER/PROPOSER MUST COMPLETE THE SCHEDULE B INCLUDED HEREIN (SCHEDULE B, PART II). A SCHEDULE B SUBMITTED BY THE BIDDER/PROPOSER WHICH DOES NOT INCLUDE THE VENDOR CERTIFICATION AND REQUIRED AFFIRMATIONS (SEE SECTION V OF PART II) WILL BE DEEMED TO BE NON-RESPONSIVE, UNLESS A FULL WAIVER OF THE PARTICIPATION GOALS IS GRANTED (SCHEDULE B, PART III). IN THE EVENT THAT THE CITY DETERMINES THAT THE BIDDER/PROPOSER HAS SUBMITTED A SCHEDULE B WHERE THE VENDOR CERTIFICATION AND REQUIRED AFFIRMATIONS ARE COMPLETED BUT OTHER ASPECTS OF THE SCHEDULE B ARE NOT COMPLETE, OR CONTAIN A COPY OR COMPUTATION ERROR THAT IS AT ODDS WITH THE VENDOR CERTIFICATION AND AFFIRMATIONS, THE BIDDER/PROPOSER WILL BE NOTIFIED BY THE AGENCY AND WILL BE GIVEN FOUR (4) CALENDAR DAYS FROM RECEIPT OF NOTIFICATION TO CURE THE SPECIFIED DEFICIENCIES AND RETURN A COMPLETED SCHEDULE B TO THE AGENCY. FAILURE TO DO

SO WILL RESULT IN A DETERMINATION THAT THE BID/PROPOSAL IS NON-RESPONSIVE. RECEIPT OF NOTIFICATION IS DEFINED AS THE DATE NOTICE IS E-MAILED OR FAXED (IF THE BIDDER/PROPOSER HAS PROVIDED AN E-MAIL ADDRESS OR FAX NUMBER), OR NO LATER THAN FIVE (5) CALENDAR DAYS FROM THE DATE OF MAILING OR UPON DELIVERY, IF DELIVERED.

- Where an M/WBE Utilization Plan has been submitted, the Contractor shall, within 30 days of issuance by Agency of a notice to proceed, submit a list of proposed persons or entities to which it intends to award subcontracts within the subsequent 12 months. In the case of multiyear contracts, such list shall also be submitted every year thereafter. The Agency may also require the Contractor to report periodically about the contracts awarded by its direct subcontractors to indirect subcontractors (as defined in Section 6-129(c)(22)). PLEASE NOTE: If this Contract is a public works project subject to GML §101(5) (i.e., a contract valued at or below \$3M for projects in New York City) or if the Contract is subject to a project labor agreement in accordance with Labor Law §222, and the bidder is required to identify at the time of bid submission its intended subcontractors for the Wicks trades (plumbing and gas fitting; steam heating, hot water heating, ventilating and air conditioning (HVAC); and electric wiring), the Contractor must identify all those to which it intends to award construction subcontracts for any portion of the Wicks trade work at the time of bid submission, regardless of what point in the life of the contract such subcontracts will occur. In identifying intended subcontractors in the bid submission, bidders may satisfy any Participation Goals established for this Contract by proposing one or more subcontractors that are MBEs and/or WBEs for any portion of the Wicks trade work. In the event that the Contractor's selection of a subcontractor is disapproved, the Contractor shall have a reasonable time to propose alternate subcontractors.
- 6. MBE and WBE firms must be certified by DSBS in order for the Contractor to credit such firms' participation toward the attainment of the **Participation Goals**. Such certification must occur prior to the firms' commencement of work. A list of MBE and WBE firms may be obtained from the DSBS website at www.nyc.gov/buycertified, by emailing DSBS at buyer@sbs.nyc.gov, by calling (212) 513-6356, or by visiting or writing DSBS at 110 William St., New York, New York, 10038, 7th floor. Eligible firms that have not yet been certified may contact DSBS in order to seek certification by visiting www.nyc.gov/getcertified, emailing MWBE@sbs.nyc.gov, or calling the DSBS certification helpline at (212) 513-6311. A firm that is certified as both an MBE and a WBE may be counted either toward the goal for MBEs or the goal for WBEs, but not both. No credit shall be given for participation by a graduate MBE or graduate WBE, as defined in Section 6-129(c)(20).
- 7. Where an M/WBE Utilization Plan has been submitted, the Contractor shall, with each voucher for payment, and/or periodically as Agency may require, submit statements, certified under penalty of perjury, which shall include, but not be limited to,: the total amount the Contractor paid to its direct subcontractors, and, where applicable pursuant to Section 6-129(j), the total amount direct subcontractors paid to indirect subcontractors; the names, addresses and contact numbers of each MBE or WBE hired as a subcontractor by the Contractor, and, where applicable, hired by any of the Contractor's direct subcontractors; and the dates and amounts paid to each MBE or WBE. The Contractor shall also submit, along with its voucher for final payment: the total amount it paid to subcontractors, and, where applicable pursuant to Section 6-129(j), the total amount its direct subcontractors paid directly to their indirect subcontractors; and a final list, certified under penalty of perjury, which shall include the name, address and contact information of each subcontractor that is an MBE or WBE, the work performed by, and the dates and amounts paid to each.
- 8. If payments made to, or work performed by, MBEs or WBEs are less than the amount specified in the Contractor's M/WBE Utilization Plan, Agency shall take appropriate action, in accordance with Section 6-129 and Article II below, unless the Contractor has obtained a modification of its M/WBE Utilization Plan in accordance with Section 6-129 and Part A, Section 11 below.
- 9. Where an M/WBE Utilization Plan has been submitted, and the Contractor requests a change order the value of which exceeds the greater of 10 percent of the Contract or Task Order, as applicable, or \$500,000, Agency shall review the scope of work for the Contract or Task Order, as applicable, and the scale and types of work involved in the change order, and determine whether the **Participation Goals** should be modified.

- 10. Pre-award waiver of the **Participation Goals**. (a) A bidder or proposer, or contractor with respect to a Task Order, may seek a pre-award full or partial waiver of the **Participation Goals** in accordance with Section 6-129, which requests that Agency change one or more **Participation Goals** on the grounds that the **Participation Goals** are unreasonable in light of the availability of certified firms to perform the services required, or by demonstrating that it has legitimate business reasons for proposing a lower level of subcontracting in its M/WBE Utilization Plan.
- (b) To apply for a full or partial waiver of the Participation Goals, a bidder, proposer, or contractor, as applicable, must complete Part III (Page 5) of Schedule B and submit such request no later than seven (7) calendar days prior to the date and time the bids, proposals, or Task Orders are due, in writing to the Agency by email at poped@ddc.nyc.gov or via facsimile at (718) 391-1886. Bidders, proposers, or contractors, as applicable, who have submitted requests will receive an Agency response by no later than two (2) calendar days prior to the due date for bids, proposals, or Task Orders; provided, however, that if that date would fall on a weekend or holiday, an Agency response will be provided by close-of-business on the business day before such weekend or holiday date.
- (c) If the Agency determines that the **Participation Goals** are unreasonable in light of the availability of certified firms to perform the services required, it shall revise the solicitation and extend the deadline for bids and proposals, or revise the Task Order, as applicable.
- (d) Agency may grant a full or partial waiver of the Participation Goals to a bidder, proposer or contractor, as applicable, who demonstrates—before submission of the bid, proposal or Task Order, as applicable—that it has legitimate business reasons for proposing the level of subcontracting in its M/WBE Utilization Plan. In making its determination, Agency shall consider factors that shall include, but not be limited to, whether the bidder, proposer or contractor, as applicable, has the capacity and the bona fide intention to perform the Contract without any subcontracting, or to perform the Contract without awarding the amount of subcontracts represented by the Participation Goals. In making such determination, Agency may consider whether the M/WBE Utilization Plan is consistent with past subcontracting practices of the bidder, proposer or contractor, as applicable, whether the bidder, proposer or contractor, as applicable, has made efforts to form a joint venture with a certified firm, and whether the bidder, proposer, or contractor, as applicable, has made good faith efforts to identify other portions of the Contract that it intends to subcontract.
- 11. Modification of M/WBE Utilization Plan. (a) A Contractor may request a modification of its M/WBE Utilization Plan after award of this Contract. PLEASE NOTE: If this Contract is a public works project subject to GML §101(5) (i.e., a contract valued at or below \$3M for projects in New York City) or if the Contract is subject to a project labor agreement in accordance with Labor Law §222, and the bidder is required to identify at the time of bid submission its intended subcontractors for the Wicks trades (plumbing and gas fitting; steam heating, hot water heating, ventilating and air conditioning (HVAC); and electric wiring), the Contractor may request a Modification of its M/WBE Utilization Plan as part of its bid submission. The Agency may grant a request for Modification of a Contractor's M/WBE Utilization Plan if it determines that the Contractor has established, with appropriate documentary and other evidence, that it made reasonable, good faith efforts to meet the Participation Goals. In making such determination, Agency shall consider evidence of the following efforts, as applicable, along with any other relevant factors:
- (i) The Contractor advertised opportunities to participate in the Contract, where appropriate, in general circulation media, trade and professional association publications and small business media, and publications of minority and women's business organizations;
- (ii) The Contractor provided notice of specific opportunities to participate in the Contract, in a timely manner, to minority and women's business organizations;
- (iii) The Contractor sent written notices, by certified mail or facsimile, in a timely manner, to advise MBEs or WBEs that their interest in the Contract was solicited;
- (iv) The Contractor made efforts to identify portions of the work that could be substituted for portions originally designated for participation by MBEs and/or WBEs in the M/WBE Utilization Plan, and for which the Contractor claims an inability to retain MBEs or WBEs;

- (v) The Contractor held meetings with MBEs and/or WBEs prior to the date their bids or proposals were due, for the purpose of explaining in detail the scope and requirements of the work for which their bids or proposals were solicited;
- (vi) The Contractor made efforts to negotiate with MBEs and/or WBEs as relevant to perform specific subcontracts, or act as suppliers or service providers;
- (vii) Timely written requests for assistance made by the Contractor to Agency's M/WBE liaison officer and to DSBS;
- (viii) Description of how recommendations made by DSBS and Agency were acted upon and an explanation of why action upon such recommendations did not lead to the desired level of participation of MBEs and/or WBEs.

Agency's M/WBE officer shall provide written notice to the Contractor of the determination.

- (b) The Agency may modify the **Participation Goals** when the scope of the work has been changed by the Agency in a manner that affects the scale and types of work that the Contractor indicated in its **M/WBE** Utilization Plan would be awarded to subcontractors.
- 12. If this Contract is for an indefinite quantity of construction, standard or professional services or is a requirements type contract and the Contractor has submitted an M/WBE Utilization Plan and has committed to subcontract work to MBEs and/or WBEs in order to meet the Participation Goals, the Contractor will not be deemed in violation of the M/WBE Program requirements for this Contract with regard to any work which was intended to be subcontracted to an MBE and/or WBE to the extent that the Agency has determined that such work is not needed.
- 13. If Participation Goals have been established for this Contract or a Task Order issued pursuant to this Contract, at least once annually during the term of the Contract or Task Order, as applicable, Agency shall review the Contractor's progress toward attainment of its M/WBE Utilization Plan, including but not limited to, by reviewing the percentage of work the Contractor has actually awarded to MBE and/or WBE subcontractors and the payments the Contractor made to such subcontractors.
- 14. If **Participation Goals** have been established for this Contract or a Task Order issued pursuant to this Contract, Agency shall evaluate and assess the Contractor's performance in meeting those goals, and such evaluation and assessment shall become part of the Contractor's overall contract performance evaluation.

### PART B: MISCELLANEOUS

- 1. The Contractor shall take notice that, if this solicitation requires the establishment of an M/WBE Utilization Plan, the resulting contract may be audited by DSBS to determine compliance with Section 6-129. See §6-129(e)(10). Furthermore, such resulting contract may also be examined by the City's Comptroller to assess compliance with the M/WBE Utilization Plan.
- 2. Pursuant to DSBS rules, construction contracts that include a requirement for an M/WBE Utilization Plan shall not be subject to the law governing Locally Based Enterprises set forth in Section 6-108.1 of the Administrative Code of the City of New York.
- 3. DSBS is available to assist contractors and potential contractors in determining the availability of MBEs and/or WBEs to participate as subcontractors, and in identifying opportunities that are appropriate for participation by MBEs and/or WBEs in contracts.
- 4. Prospective contractors are encouraged to enter into qualified joint venture agreements with MBEs and/or WBEs as defined by Section 6-129(c)(30).

5. By submitting a bid or proposal the Contractor hereby acknowledges its understanding of the M/WBE Program requirements set forth herein and the pertinent provisions of Section 6-129, and any rules promulgated thereunder, and if awarded this Contract, the Contractor hereby agrees to comply with the M/WBE Program requirements of this Contract and pertinent provisions of Section 6-129, and any rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract. The Contractor hereby agrees to make all reasonable, good faith efforts to solicit and obtain the participation of MBEs and/or WBEs to meet the required **Participation Goals**.

### ARTICLE II. ENFORCEMENT

- 1. If Agency determines that a bidder or proposer, as applicable, has, in relation to this procurement, violated Section 6-129 or the DSBS rules promulgated pursuant to Section 6-129, Agency may disqualify such bidder or proposer, as applicable, from competing for this Contract and the Agency may revoke such bidder's or proposer's prequalification status, if applicable.
- 2. Whenever Agency believes that the Contractor or a subcontractor is not in compliance with Section 6-129 or the DSBS rules promulgated pursuant to Section 6-129, or any provision of this Contract that implements Section 6-129, including, but not limited to any M/WBE Utilization Plan, Agency shall send a written notice to the Contractor describing the alleged noncompliance and offering the Contractor an opportunity to be heard. Agency shall then conduct an investigation to determine whether such Contractor or subcontractor is in compliance.
- 3. In the event that the Contractor has been found to have violated Section 6-129, the DSBS rules promulgated pursuant to Section 6-129, or any provision of this Contract that implements Section 6-129, including, but not limited to, any M/WBE Utilization Plan, Agency may determine that one of the following actions should be taken:
- (a) entering into an agreement with the Contractor allowing the Contractor to cure the violation;
- (b) revoking the Contractor's pre-qualification to bid or make proposals for future contracts;
- (c) making a finding that the Contractor is in default of the Contract;
- (d) terminating the Contract;
- (e) declaring the Contractor to be in breach of Contract;
- (f) withholding payment or reimbursement;
- (g) determining not to renew the Contract;
- (h) assessing actual and consequential damages;
- (i) assessing liquidated damages or reducing fees, provided that liquidated damages may be based on amounts representing costs of delays in carrying out the purposes of the M/WBE Program, or in meeting the purposes of the Contract, the costs of meeting utilization goals through additional procurements, the administrative costs of investigation and enforcement, or other factors set forth in the Contract;
- (j) exercising rights under the Contract to procure goods, services or construction from another contractor and charge the cost of such contract to the Contractor that has been found to be in noncompliance; or
- (k) taking any other appropriate remedy.
- 4. If an M/WBE Utilization Plan has been submitted, and pursuant to this Article II, Section 3, the Contractor has been found to have failed to fulfill its Participation Goals contained in its M/WBE Utilization Plan or the Participation Goals as modified by Agency pursuant to Article I, Part A, Section 11, Agency may assess liquidated damages in the amount of ten percent (10%) of the difference between the dollar amount of work required to be awarded to MBE and/or WBE firms to meet the Participation Goals and the dollar amount the Contractor actually awarded and paid, and/or credited, to MBE and/or WBE firms. In view of the difficulty of accurately ascertaining the loss which the City will suffer by reason of Contractor's failure to meet the Participation Goals, the foregoing amount is hereby fixed and agreed as the liquidated damages that the City will suffer by reason of such failure, and not as a penalty. Agency may deduct and retain out of any monies which may become due under this Contract the amount of any such liquidated damages; and in case the amount which may become due under this Contract shall be less than the amount of liquidated damages suffered by the City, the Contractor shall be liable to pay the difference.

- 5. Whenever Agency has reason to believe that an MBE and/or WBE is not qualified for certification, or is participating in a contract in a manner that does not serve a commercially useful function (as defined in Section 6-129(c)(8)), or has violated any provision of Section 6-129, Agency shall notify the Commissioner of DSBS who shall determine whether the certification of such business enterprise should be revoked.
- 6. Statements made in any instrument submitted to Agency pursuant to Section 6-129 shall be submitted under penalty of perjury and any false or misleading statement or omission shall be grounds for the application of any applicable criminal and/or civil penalties for perjury. The making of a false or fraudulent statement by an MBE and/or WBE in any instrument submitted pursuant to Section 6-129 shall, in addition, be grounds for revocation of its certification.
- 7. The Contractor's record in implementing its M/WBE Utilization Plan shall be a factor in the evaluation of its performance. Whenever Agency determines that a Contractor's compliance with an M/WBE Utilization Plan has been unsatisfactory, Agency shall, after consultation with the City Chief Procurement Officer, file an advice of caution form for inclusion in VENDEX as caution data.

	APT E-	
ax ID #:	PIN #:	85014B0130
dx 10 #		

SCHEDULE B – M/WBE Utilization Plan Part I: M/WBE Participation Goals

Part I to be completed by contracting agency

Contract Overview					
APT E- Pin #	85014B0130	FMS Pr	oject ID#:	SER002316	
Project Title/ Agency PIN #	CONSTRUCTION OF STORM & SA	ANITARY SEW	/ERS & APPURT	FENANCES/8502014	SE0001C
Bid/Proposal Response Date	MAY 28, 2014				
Contracting Agency	Department of Design and Co	nstruction			
Agency Address	30-30 Thomson Avenue City	Long Island	d City State	NY Zip Code	11101
Contact Person	Diana A. Benjamin	Title	_MWBE Liaiso	on & Compliance A	Analyst
Telephone #	(718) 391-3470	Email	BenjamiDi@d	ddc.nyc.gov	
Project Description (att	ach additional pages if necessary)				

PROJECT ID: SER002316
FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;

VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND,

WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

**INCLUDING WATER MAIN WORK** 

Together With All Work Incidental Thereto BOROUGH OF STATEN ISLAND CITY OF NEW YORK

### M/WBE Participation Goals for Services

Enter the percentage amount for each group or for an unspecified goal. Please note that there are no goals for Asian Americans in Professional Services.

Prime Contract Industry: Construction

	Percentage	Group
	10%	<u>Unspecified</u> *
		or
	UNSPECIFIED*	Black American
	UNSPECIFIED*	Hispanic American
	UNSPECIFIED*	Asian American
	UNSPECIFIED*	Women
Line 1	10%	al Participation Goals

\*Note: For this procurement, individual ethnicity and gender goals are not specified. The Total Participation Goal for construction contracts may be met by using either Black-American, Hispanic-American, Asian American, or Women certified firms or any combination of such firms.

		THE CONTRACTOR			Oktobija in monopus voje je njem kon klad septropora, odeno o klad oktobi oktobi oktobija o oden alike konke openinoje i
SCHEDULE B - Part II: M/WBE Particip	ation Plan				* • ·
Part II to be completed by the bidder/proportion of the proposition of the contract, you must obtain a FULL was submitting it to the contracting agency purposed, it must be included with your bid bid or proposal.	ntractors who will N waiver by completing ursuant to the Notice	the e to	<ul> <li>Waiver Application on Prospective Contractors</li> </ul>	page: s. Or	s 17 and 18 and timely nce a FULL WAIVER is
Section I: Prime Contractor Contact Infor	mation			in a second	
Tax ID #			FMS Vendor ID# _		
Business Name			Contact Person _		
Address					
Telephone #	Email _		· · · · · · · · · · · · · · · · · · ·		
Section II: M/WBE Utilization Goal Calcul	ation: Check the app	olica	ble box and complete s	ubsed	etion.
PRIME CONTRACTOR ADOPTING AG	ENCY M/WBE PAR	<b>TIC</b>	PATION GOALS		
For Prime Contractors (including Qualified Joint Ventures and M/WBE firms) adopting Agency M/WBE	Total Bid/Proposal Value		Agency Total Participation Goals (Line 1, Page 13)		Calculated M/WBE Participation Amount
Participation Goals.  Calculate the total dollar value of your total bid that you agree will be awarded to M/WBE subcontractors for services and/or credited to an M/WBE prime contractor or Qualified Joint Venture.					
Please review the Notice to Prospective Contractors for more information on how to obtain credit for M/WBE participation.	\$	X		=	\$ Line 2
PRIME CONTRACTOR OBTAINED PAI PARTICIPATION GOALS	RTIAL WAIVER API		OVAL: ADOPTING MO	DIFIE	<del></del>
For Prime Contractors (including Qualified Joint Ventures and M/WBE firms) adopting Modified M/WBE	Total Bid/Proposal Value		Adjusted Participation Goal (From Partial Waiver)		Calculated M/WBE Participation Amount
Participation Goals.  Calculate the total dollar value of your total bid that you agree will be awarded to M/WBE subcontractors for services and/or credited to an M/WBE prime contractor or Qualified Joint Venture.  Please review the Notice to Prospective					
Contractors for more information on how to obtain credit for M/WBE participation.	\$	x		=	\$   Line 3

Tax ID #:\_\_\_\_\_

APT E-PIN #: <u>85014B0130</u>

Гах ID #:	APT E- PIN #: 85014B0130
•	
review the Notice to Prospecti	Plan: How Proposer/Bidder Will Fulfill M/WBE Participation Goals. Please ve Contractors for more information on how to obtain credit for M/WBE e box. The Proposer or Bidder will fulfill the M/WBE Participation Goals:
contract the value of which is at I	ctor that will self-perform and/or subcontract to other M/WBE firms a portion of the east the amount located on Lines 2 or 3 above, as applicable. The value of any 3E firms will not be credited towards fulfillment of M/WBE Participation Goals. me Contractor:
As a Qualified Joint Venture and/or the value of any work sub above, as applicable. The value fulfillment of M/WBE Participation	with an M/WBE partner, in which the value of the M/WBE partner's participation contracted to other M/WBE firms is at least the amount located on Lines 2 or 3 of any work subcontracted to non M/WBE firms will not be credited towards n Goals.
As a non M/WBE Prime Con least the amount located on Line	tractor that will enter into subcontracts with M/WBE firms the value of which is at a 2 or 3 above, as applicable.
Section IV: General Contract Info	ormation
What is the expected percenta services, regardless of M/WBB	age of the total contract dollar value that you expect to award in subcontracts for   status? %
✓ Scopes of Subcontract Work	Enter brief description of the type(s) and dollar value of subcontracts for all/any services you plan on subcontracting if awarded this contract. For each item, indicate whether the work is designated for participation by MBEs and/or WBEs and the time frame in which such work is scheduled to begin and end. Use additional sheets if necessary.  1

15

Tax ID #:	APT E- PIN #:	85014B0130
Section V: Vendor Certification and Required Af I hereby:	firmations	
1) acknowledge my understanding of the M/WBE papertinent provisions of Section 6-129 of the Adminis 129"), and the rules promulgated thereunder;	strative Code of the City of	New York ("Section 6-
2) affirm that the information supplied in support of (3) agree, if awarded this Contract, to comply with the pertinent provisions of Section 6-129, and the rudeemed to be material terms of this Contract;	e M/WBE participation rec	quirements of this Contract,
4) agree and affirm that it is a material term of this (value of the M/WBE Participation Goals to certified or such goals are modified by the Agency; and	Contract that the Vendor w MBEs and/or WBEs, unles	rill award the total dollar ss a full waiver is obtained
5) agree and affirm, if awarded this Contract, to make M/WBE Participation Goals, or If a partial waiver is to meet the modified Participation Goals by soliciting and/or WBE firms.	obtained or such goals are	e modified by the Agency,
Signature	Date	
Print Name	Title	

### SCHEDULE B – PART III – REQUEST FOR WAIVER OF M/WBE PARTICIPATION REQUIREMENT

Contract Overview						
Tax ID #	FMS Vendor ID #					
Business Name						
Contact Name	Telephone #	Email				
Type of Procurement	☐ Competitive Sealed Bids ☐ Other	Bid/Response Due Date				
APT E-PIN # (for this procurement):		Contracting Agency:				
<b>%</b>	on Goals as described in bid/solicitation do Agency M/WBE Participation Goal	cuments				
V. A hard and a state of the st	cipation Goal as anticipated by vendor seekii	ng waiver				
. O/	。这个是一个是是一个主义,是是不是一个人,我们们的时候就是不是不是一个人,我们就是一个人,我们就是一个人,我们就是一个人,我们的人,我们就是一个人,他们的人,他 第一个					
fc	or services and/or credited to an M/WBE Prim	faith by the bidder/proposer to be subcontracted to contracted to contractor or Qualified Joint Venture.				
[曹重和[編集] [[李] [[李] [[李] [[李] [[李] [[李] [[李] [[		tail below (attach additional pages if needed)				
☐ Vendor does not suitself with its own emplo	bcontract services, and has the capacity ar	nd good faith intention to perform all such wor				
capacity and good faith	intention to do so on this contract. (Attac	6 than bid/solicitation describes, and has the				
capacity and good faith the vendor will self-perf  Vendor has other le	intention to do so on this contract. (Attac orm and subcontract to other vendors or c	h subcontracting plan outlining services that				
capacity and good faith the vendor will self-perf  Vendor has other le	intention to do so on this contract. (Attac orm and subcontract to other vendors or c	h subcontracting plan outlining services that onsultants.)				
capacity and good faith the vendor will self-perf  Vendor has other legunder separate cover.  References	intention to do so on this contract. (Attac orm and subcontract to other vendors or c gitimate business reasons for proposing th	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra	intention to do so on this contract. (Attac orm and subcontract to other vendors or c gitimate business reasons for proposing th octs performed for NYC agencies (if any), Inc.	h subcontracting plan outlining services that onsultants.)				
capacity and good faith the vendor will self-perf Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con	intention to do so on this contract. (Attac orm and subcontract to other vendors or c gitimate business reasons for proposing th	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con CONTRACT NO.	intention to do so on this contract. (Attactorm and subcontract to other vendors or congitimate business reasons for proposing the facts performed for NYC agencies (if any). Incontracts. Add more pages if necessary.  AGENCY	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain				
capacity and good faith the vendor will self-perf Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con	intention to do so on this contract. (Attactorm and subcontract to other vendors or congitimate business reasons for proposing the letter performed for NYC agencies (if any). Incontracts. Add more pages if necessary.  AGENCY Total Amount	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con  CONTRACT NO. Total Contract	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract business reasons for proposing the sector performed for NYC agencies (if any). Increases. Add more pages if necessary.  AGENCY  Total Amount Subcontracted \$	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain  lude information for each subcontract awarded i				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con  CONTRACT NO.  Total Contract Amount \$ Item of Work Subcontracted and	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract business reasons for proposing the sets performed for NYC agencies (if any). Incontracts. Add more pages if necessary.  AGENCY  Total Amount Subcontracted \$  Item of Work Subcontracted and	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain  lude information for each subcontract awarded i  DATE COMPLETED  Item of Work Subcontracted and				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con  CONTRACT NO.  Total Contract Amount \$ Item of Work	intention to do so on this contract. (Attactorm and subcontract to other vendors or congitimate business reasons for proposing the sects performed for NYC agencies (if any). Incontracts. Add more pages if necessary.  AGENCY  Total Amount Subcontracted \$ Item of Work	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain  lude information for each subcontract awarded I  DATE COMPLETED  Item of Work				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con  CONTRACT NO.  Total Contract Amount \$ item of Work Subcontracted and	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract business reasons for proposing the sets performed for NYC agencies (if any). Incontracts. Add more pages if necessary.  AGENCY  Total Amount Subcontracted \$  Item of Work Subcontracted and	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain  lude information for each subcontract awarded i  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con  CONTRACT NO. Total Contract Amount \$ Item of Work Subcontracted and Value of subcontract  CONTRACT NO. Total Contract  CONTRACT NO. Total Contract	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract to other vendors or contracts business reasons for proposing the state of the sta	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain  lude information for each subcontract awarded i  DATE COMPLETED  Item of Work Subcontracted and				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con  CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract  CONTRACT NO. Total Contract Amount \$  CONTRACT NO.  Total Contract Amount \$  CONTRACT NO.  Total Contract Amount	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract to other vendors or contracts. It is presented to the contract to other vendors or contracts. Add more pages if necessary.  AGENCY  Total Amount Subcontracted and Value of subcontract to AGENCY  Total Amount Subcontracted \$	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain  lude information for each subcontract awarded i  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con  CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract  CONTRACT NO. Total Contract Amount Item of Work Subcontract Subcontract Amount Item of Work Item of Work	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract to other vendors or contract to other vendors or contracts and subcontract to other vendors or contracts. Add more pages if of any). Incontracts. Add more pages if necessary.  AGENCY  Total Amount Subcontracted \$  Item of Work Subcontracted and Value of subcontract  AGENCY  Total Amount Subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted \$  Item of Work	h subcontracting plan outlining services that onsultants.)  le M/WBE Participation Goal above. Explain  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract  DATE COMPLETED  Item of Work Subcontracted Item of Work Subcontracted Item of Work Subcontracted Item of Work Subcontracted Item of Work DATE COMPLETED				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con  CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract  CONTRACT NO. Total Contract Amount \$  CONTRACT NO.  Total Contract Amount \$  CONTRACT NO.  Total Contract Amount	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract to other vendors or contracts. It is presented to the contract to other vendors or contracts. Add more pages if necessary.  AGENCY  Total Amount Subcontracted and Value of subcontract to AGENCY  Total Amount Subcontracted \$	h subcontracting plan outlining services that onsultants.)  le M/WBE Participation Goal above. Explain    DATE COMPLETED				
capacity and good faith the vendor will self-perf  Vendor has other leg under separate cover.  References List 3 most recent contra performance of such con  CONTRACT NO. Total Contract Amount \$ item of Work Subcontracted and Value of subcontract  CONTRACT NO. Total Contract Amount \$ item of Work Subcontracted and Value of subcontract Amount \$ item of Work Subcontracted and	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract to other vendors or contract to other vendors or contracts. It is performed for NYC agencies (if any). Incontracts. Add more pages if necessary.  AGENCY  Total Amount Subcontracted \$  Item of Work Subcontracted and Value of subcontracted \$  Item of Work Subcontracted and Value of subcontracted and Value of subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted and Value of subcontracted \$  Item of Subcontracted \$  Item of Work Subcontracted and Value of subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted and Value of subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted and Value of subcontracted and Value of subcontracted \$  Item of Work Subcontracted and Value of subcontracted and Value of subcontracted \$  Item of Work Subcontracted and Value of subcontracted and Value of subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted and Value of subcontracted \$  Item of Work	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain    DATE COMPLETED				
capacity and good faith the vendor will self-perf  Vendor has other legunder separate cover.  References List 3 most recent contraperformance of such contract Amount \$ Item of Work Subcontracted and Value of subcontract  CONTRACT NO.  Total Contract Amount \$ Item of Work Subcontracted and Value of subcontracted	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract to other vendors or contracts of the subcontract of the subco	h subcontracting plan outlining services that onsultants.)  le M/WBE Participation Goal above. Explain  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract				
capacity and good faith the vendor will self-perf  Vendor has other legunder separate cover.  References List 3 most recent contraperformance of such contract Amount \$ Item of Work Subcontracted and Value of subcontract Amount \$ Item of Work Subcontract CONTRACT NO. Total Contract Amount \$ Item of Work Subcontract Amount \$ Item of Work Subcontract Amount \$ Item of Work Subcontracted and Value of subcontracted and Value of subcontract CONTRACT NO.	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract to other vendors or contract to other vendors or contract business reasons for proposing the sector performed for NYC agencies (if any). Increases Add more pages if necessary.  AGENCY  Total Amount Subcontracted \$  Item of Work Subcontracted and Value of subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted and Value of subcontracted and Value of subcontracted AGENCY	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain    DATE COMPLETED				
capacity and good faith the vendor will self-perf  Vendor has other legunder separate cover.  References List 3 most recent contraperformance of such contract Amount \$ Item of Work Subcontracted and Value of subcontract  CONTRACT NO.  Total Contract Amount \$ Item of Work Subcontracted and Value of subcontracted and Value of subcontract  CONTRACT NO.  Total Contract Amount \$ Item of Work Subcontracted and Value of subcontracted and Value of subcontract  CONTRACT NO.  Total Contract Amount \$ Item of Work	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract to other vendors or contracts. Add more pages if or proposing the contracts. Add more pages if necessary.  AGENCY  Total Amount Subcontracted and Value of subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted and Value of subcontracted and Value of subcontracted \$  AGENCY  Total Amount Subcontracted \$  Item of Work	h subcontracting plan outlining services that onsultants.)  e M/WBE Participation Goal above. Explain    DATE COMPLETED				
capacity and good faith the vendor will self-perf  Vendor has other legunder separate cover.  References List 3 most recent contraperformance of such contract Amount \$ Item of Work Subcontracted and Value of subcontract Amount \$ Item of Work Subcontracted and Value of subcontract CONTRACT NO. Total Contract Amount \$ Item of Work Subcontracted and Value of subcontract CONTRACT NO. Total Contract Amount \$ CONTRACT NO. Total Contract Amount \$	intention to do so on this contract. (Attactorm and subcontract to other vendors or contract to other vendors or contracts. Add more pages if or proposing the contracts. Add more pages if necessary.  AGENCY  Total Amount Subcontracted and Value of subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted \$  Item of Work Subcontracted and Value of subcontracted \$  AGENCY  Total Amount Subcontract  AGENCY  Total Amount Subcontracted \$	h subcontracting plan outlining services that onsultants.)  le M/WBE Participation Goal above. Explain  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract  DATE COMPLETED  Item of Work Subcontracted and Value of subcontract  DATE COMPLETED  OATE COMPLETED  DATE COMPLETED				

performance of such	i contracts. Add mo	for other entities. Includ ore pages if necessary. fewer than 3 New York Cit	- Sociologica de la composición de la c La composición de la	ubcontract awarded in
TYPE OF Contract		ENTITY	•	DATE COMPLETED
Manager at enti	ty that hired vendor	(Name/Phone No./Email	)	
Total Contract Amount	\$	Total Amount Subcontracted \$		
Type of Work Subcontracted		· 		
TYPE OF Contract		AGENCY/ENTITY	<u> </u>	DATE COMPLETED
Manager at agency/e	entity that hired ven	dor (Name/Phone		
Total Contract	<b>~</b>	Total Amount		
Amount_	<b>3</b>	Subcontracted \$  Item of Work	_	
Item of Work		Subcontracted		Item of Work
Subcontracted and		and Value of		Subcontracted and
Value of subcontract		subcontract		Value of subcontract
TYPE OF Contract		AGENCY/ENTITY	·	DATE COMPLETED
Manager at enti	ty that hired vendor	· (Name/Phone No./Email	)	
<b>Total Contract</b>		Total Amount		
Amount_	\$	Subcontracted \$		
Item of Work	•	Item of Work Subcontracted		Item of Work
Subcontracted and		and Value of		Subcontracted and
Value of subcontract	•	subcontract		Value of subcontract
correct, and that this				f this waiver request is true and
Signature:			Date:	
Print Name:			Title:	
Shaded area below i	recontraction to the contraction of the contraction	BENERAL MARKETER STORY TO A SERVICE OF THE SERVICE		
AGENCY CHIEF C Signature:	ONTRACTING OF	HIGER APPROVAL	Date:	
CITY CHIEF PROC	UREMENT OFFIC	ER APPROVAL	Bear Barbara	August Company of the Company of the Company
Signature:			Tate:	THE PARTY OF THE P
Waiver Determinat	ion V			
Full Waiver Approve Waiver Denied: Partial Waiver Appro				
Revised Participatio				Consider the second sec
APPENDING CONTRACTOR			or meaning of the first of the	

### APPRENTICESHIP PROGRAM REQUIREMENTS

Bidders are advised that the Apprenticeship Program Requirements set forth below apply to each contract for which a check mark is indicated before the word "Yes". Compliance with these requirements will be determined solely by the City.

$\checkmark$	YES	NO

### (1) Apprenticeship Program Requirements

Notice to Bidders: Please be advised that, pursuant to the authority granted to the City under Labor Law Section 816-b, the Department of Design and Construction hereby requires that the contractor awarded a contract as a result of this Invitation for Bids, and any of its subcontractors with subcontracts worth one million dollars or over, have, prior to entering into such contract or subcontract, apprenticeship agreements appropriate for the type and scope of work to be performed that have been registered with, and approved by, the New York State Commissioner of Labor. In addition, the contractor and its subcontractors will be required to show that such apprenticeship programs have three years of current, successful experience in providing career opportunities.

The failure to prove, upon request, that these requirements have been met shall result in the contract not being awarded to the contractor or the subcontract not being approved.

Please be further advised that, pursuant to Labor Law Section 220, the allowable ratio of apprentices to journeypersons in any craft classification shall not be greater than the ratio permitted to the contractor as to its workforce on any job under the registered apprenticeship program.

### (2) Apprenticeship Program Questionnaire

The bidder must submit a completed and signed Apprenticeship Program Questionnaire. The Questionnaire is set forth on the following page of the Bid Booklet.

### APPRENTICESHIP PROGRAM QUESTIONNAIRE

**PROJECT ID:** 

**SER002316** 

The bidder must submit a completed and signed Apprenticeship Program Questionnaire.

1.	Does the bidder have an Apprenticeship Pro [Note: Participation may be by either direct	gram appropriate sponsorship or thr	for the type and scor ough collective barg	be of work to be performed? aining agreement(s).]
		YES		NO
2.	Has the bidder's Apprenticeship Program Commissioner of Labor?	been registered	with, and approved	1 by, the New York State
		YES		NO
3.	Has the bidder's Apprenticeship Program opportunities?	had three years	of successful expe	rience in providing career
		YES		NO
experi	answer to Question #3 is "Yes", the bidd ence the Apprenticeship Program has had in if necessary.	er shall, in the sp providing career	pace below, provide opportunities. The b	information regarding the pidder may attach additional
•				
				-
		112	WW	
				44.
		He .		
				7.00
				- 120
			774	
Bidder	=	1177		
By:			Title:	
Date:	(Signature of Partner or Corpo	orate Officer)		
	F NEW YORK TMENT OF DESIGN AND CONSTRUCTION	20		BID BOOKLET

DECEMBER 2013

<b>Project</b>	ID.		
•		 	

### **SAFETY QUESTIONNAIRE**

The bidder must include, with its bid, all information requested on this Safety Questionnaire. Failure to provide a completed and signed Safety Questionnaire at the time of bid opening may result in disqualification of the bid as non-responsive.

Company Name:		
DDC Project Number:		: 
Company Size: Ten (10	) employees or less	
Greater	than ten (10) employees	
Company has previously worked for DDC	YES	NO
2. Type(s) of Construction Work		
TYPE OF WORK General Building Construction Residential Building Construction Nonresidential Building Construction Heavy Construction, except building Highway and Street Construction Heavy Construction, except highways Plumbing, Heating, HVAC Painting and Paper Hanging Electrical Work Masonry, Stonework and Plastering Carpentry and Floor Work Roofing, Siding, and Sheet Metal Concrete Work Specialty Trade Contracting Asbestos Abatement Other (specify)	LAST 3 YEARS	THIS PROJECT

The Experience Modification Rate (EMR) is a rating generated by the National Council of Compensation Insurance (NCCI). This rating is used to determine the contractor's premium for worker's compensation insurance. The contractor may obtain its EMR by contacting its insurance broker or the NCCI. If the contractor cannot obtain its EMR, it must submit a written explanation as to why.

			rioject ib.
The Contractor mucontractors with le	st indicate its <u>Intra</u> sta	ate and <u>Interstate EMR</u> for the experience, the EMR will be	e past three years. [Note: For considered to be 1.00].
YEAR	<u>INTR</u> 4	STATE RATE	INTERSTATE RATE
	· <del></del>		· · · · · · · · · · · · · · · · · · ·
contractor must a	ttach, to this questic	R for any of the past three onnaire, a written explanation resulting	years is greater than 1.00, the on for the rating and identify g in that rating.
4. OSHA Inform	ition:		
YES	NO Contractor ha Department o	s received a willful violation f Buildings (NYCDOB) with	issued by OSHA or New York City in the last three years.
YES	NO Contractor ha (i.e., fatality,	s had an incident requiring O or hospitalization of three or	SHA notification within 8 hours more employees).
employees, on a ye	arly basis to complete es". This form is con	t (OSHA) of 1970 requires ene and maintain on file the formation on the the formation of the OSI (Control of the Cost) and the OSI (Cost) of the Cost (Cost) of the C	n entitled "Log of Work-related
The OSHA 300 Lo employees.	g must be submitted t	for the last three years for con	tractors with more than ten
	st indicate the total nather than the past three years.	umber of hours worked by its	employees, as reflected in
past three years. For each given ye illnesses reported	The Incident Rate is ar, the total number on the OSHA 300	is calculated in accordance er of incidents is the total:	juries (the Incident Rate) for the with the formula set forth below number of non-fatal injuries and represents the equivalent of 100
Incident Rate =		Total Number of Inc	
		Total Number of Hours Worl	ked by Employees
YEAR		RS OF HOURS WORKED BY EMPLOYEES	INCIDENT RATE

<b>Project</b>	ID.	

If the contractor's Incident Rate for any of the past three years is one point higher than the Incident Rate for the type of construction it performs (listed below), the contractor must attach, to this questionnaire, a written explanation for the relatively high rate.

General Building Construction	8.5	
Residential Building Construction	7.0	
Nonresidential Building Construction	10.2	
Heavy Construction, except building	8.7	
Highway and Street Construction	9.7	
Heavy Construction, except highways	8.3	
Plumbing, Heating, HVAC	11.3	
Painting and Paper Hanging	6.9	
Electrical Work	9.5	
Masonry, Stonework and Plastering	10.5	
Carpentry and Floor Work	12.2	
Roofing, Siding, and Sheet Metal	10.3	
Concrete Work	8.6	
Specialty Trade Contracting		

### 5. Safety Performance on Previous DDC Project(s)

YES	NO	Contractor previously audited by the DDC Office of Site Safety.
		DDC Project Number(s):
YES	NO	Accident on previous DDC Project(s).
		DDC Project Number(s):
YES	NO	Fatality or Life-altering Injury on DDC Project(s) within the last three years [Examples of a life-altering injury include loss of limb, loss of a sense (e.g., sight, hearing), or loss of neurological function].
		DDC Project Number(s):
Date:		By:(Signature of Owner, Partner, Corporate Officer)
÷		Title:

(NO TEXT ON THIS PAGE)

### **Pre-Award Process**

The bidder is advised that as part of the pre-award review of its bid, it may be required to submit the information described in Sections (A) through (D) below. If required, such information must be submitted by the bidder within five (5) business days following receipt of notification from DDC that it is among the low bidders. Such notification from DDC will be by facsimile or in writing and will specify the types of information must be submitted. The types of information the bidder may be required to submit are described below. In the event the bidder fails to submit the required information within the specified time frame, its bid may be rejected as nonresponsive.

\*\*\*\*\*\*\*\*\*\*\*\*\*

- (A) **Project Reference Form**: If required, the bidder must complete and submit the Project Reference Form set forth on pages 26 through 28 of this Bid Booklet. The Project Reference Form consists of 3 parts: (1) Similar Contracts Completed by the Bidder, (2) Contracts Currently Under Construction by the Bidder, and (3) Pending Contracts Not Yet Started by the Bidder.
- (B) Copy of License: If required, the bidder must submit a copy of the license under which the bidder will be performing the work. Such license must clearly show the following: (1) Name of the Licensee, (2) License Number, and (3) Expiration date of the License. A copy of the license will be required from bidders for the following contracts: Plumbing Work, Electrical Work and Asbestos Abatement.
- (C) **Financial Information**: If required, the bidder must submit the financial information described below:
  - (1) Audited Financial Statements: Financial statements (Balance Sheet and Income Statement) of the entity submitting the bid, as audited by an independent auditor licensed to practice as a certified public accountant (CPA). Audited financial statements for the three most recent fiscal years must be submitted. Each such financial statement must include the auditor's standard report.

If the bidder does not have audited financial statements, it must submit an affidavit attesting to the fact that the bidder does not have such statements. In addition, the bidder must submit the following documentation covering the three most recent fiscal years: signed federal tax returns, unaudited financial statements, and a "certified review letter" from a certified public accountant (CPA) verifying the unaudited financial statements.

Unless the most recent audited or unaudited financial statement was issued within ninety (90) days, the bidder must submit interim financial information that includes data on financial position and results of operation (income data) for the current fiscal year. Such information may be summarized on a monthly or quarterly basis or at other intervals.

(2) Schedule of Aged Accounts Receivable, including portion due within ninety (90) days.

- (D) **Project Specific Information**: If required, the bidder must submit the project specific information described below:
  - (1) Statement indicating the number of years of experience the bidder has had and in what type of construction.
  - (2) Resumes of all key personnel to be involved in the project, including the proposed project superintendent.
  - (3) List of significant pieces of equipment expected to be used for the contract, and whether such equipment is owned or leased.
  - (4) Description of work expected to be subcontracted, and to what firms, if known.
  - (5) List of key material suppliers.
  - (6) Preliminary bar chart time schedule
  - (7) Contractor's expected means of financing the project. This should be based on the assumption that the contractor is required to finance 2X average monthly billings throughout the contract period.
  - (8) Any other issues the contractor sees as impacting his ability to complete the project according to the contract.

In addition to the information described in Sections (A) through (D) above, the bidder shall submit such additional information as the Commissioner may require, including without limitation, an explanation or justification for specific unit price items.

The bidder is further advised that it may be required to attend a pre-award meeting with DDC representatives. If such a meeting is convened, the bidder will be advised as to any additional material to be provided.

## PROJECT REFERENCES - SIMILAR CONTRACTS COMPLETED BY THE BIDDER Ą.

List all contracts substantially completed within the last 4 years similar to the contract being awarded, up to a maximum of 10, in descending order of date of substantial completion.

if.			T 10.52		
Architect/Engineer Reference & Tel. No. if different from owner					
A Refe dif					
Owner Reference & Tel. No.					
Date Completed	•				
Contract Amount (\$000)					
Contract Type					
Project & Location					

CITY OF NEW YORK
DEPARTMENT OF DESIGN AND CONSTRUCTION

26

BID BOOKLET DECEMBER 2013

# PROJECT REFERENCES - CONTRACTS CURRENTLY UNDER CONSTRUCTION BY THE BIDDER ä

List all contracts currently under construction even if they are not similar to the contract being awarded.

u 2	 T .	<u> </u>	1	1
Architect/Engineer Reference & Tel. No.if different				
Owner Reference & Tel. No.				
Date Scheduled to Complete				
Uncompleted Portion (\$000)				
Subcontracted to Others (\$000)				
Contract Amount (\$000)				
Contract				
Project & Location				

CITY OF NEW YORK
DEPARTMENT OF DESIGN AND CONSTRUCTION

BID BOOKLET DECEMBER 2013

## PROJECT REFERENCES - PENDING CONTRACTS NOT YET STARTED BY THE BIDDER ن

List all contracts awarded to or won by the bidder but not yet started.

			<u> </u>	 	
Architect/Engineer Reference & Tel. No. if different from owner					
Owner Reference & Tel. No.		·	-		
Date Scheduled to Start	į				
Contract Amount (\$000)					
Contract Type					
Project & Location					

CITY OF NEW YORK
DEPARTMENT OF DESIGN AND CONSTRUCTION

BID BOOKLET DECEMBER 2013 (NO TEXT ON THIS PAGE)

### OFFICE OF THE MAYOR BUREAU OF LABOR SERVICES CONTRACT CERTIFICATE

To be completed if the contract is less than \$1,000,000

Contractor:			-
Address:			
			-
Telephone Number:			<u>.</u>
Name and Title of Signatory:			
		, .	=
Contracting Agency or Owner:	W. Tank Folder		
Project Number:			_
Proposed Contract Amount:			_
Description and Address of Proposed Contract:			
Names of Subcontractors in the amount of 750,000 or more state indicating that trades will be subcontracted):			ne, so
I, (fill in name of person signing) hereby affirm that I am authorized by the above-named corproposed contract with the above-named owner or city age is made in accordance with Executive Order No. 50 (1980)	ncy is less than \$1,00	0,000. This affirma	—, ition tions.
Date	Signature	W 5454	
WILLFUL OR FRAUDULENT FALSIFICATION OF SUBMITTED HEREWITH MAY RESULT IN THE TERMITHE CITY AND THE BIDDER OR CONTRACTOR AND FOR PARTICIPATION IN ANY CITY CONTRACT FOR A PERSUCH FALSIFICATION MAY RESULT IN CRIMINAL PROBLEM.	INATION OF ANY CO BAR THE BIDDER OF LIOD OF UP TO THR	ONTRACT BETWE	ROM

(NO TEXT ON THIS PAGE)

### VENDEX COMPLIANCE

- (A) Vendex Fees: Pursuant to Procurement Policy Board Rule 2-08(f)(2), the contractor will be charged a fee for the administration of the VENDEX system, including the Vendor Name Check process, if a Vendor Name Check review is required to be conducted by the Department of Investigation. The contractor shall also be required to pay the applicable required fees for any of its subcontractors for which Vendor Name Check reviews are required. The fee(s) will be deducted from payments made to the contractor under the contract. For contracts with an estimated value of less than or equal to \$1,000,000, the fee will be \$175 per Vendor Name Check review. For contracts with an estimated value of greater than \$1,000,000, the fee will be \$350 per Vendor Name Check review.
- **(B)** Confirmation of Vendex Compliance: The Bidder shall submit this Confirmation of Vendex Compliance to the Department of Design and Construction, Contracts Section, 30-30 Thomson Avenue First Floor, Long Island City, NY 11101.

**<u>Bid Information</u>**: The Bidder shall complete the bid information set forth below.

	Name of Bidder:
	Bidder's Address:
	Bidder's Telephone Number:
	Bidder's Fax Number:
	Date of Bid Opening: Project ID:
	Project ID:
Vend either	<b>lex Compliance:</b> To demonstrate compliance with Vendex requirements, the Bidder shall complete r Section (1) or Section (2) below, whichever applies.
(1)	Submission of Vendex Questionnaires to MOCS: By signing in the space provided below, the
	Bidder certifies that as of the date specified below, the Bidder has submitted Vendex
	Questionnaires to the Mayor's Office of Contract Services, Attn: VENDEX, 253 Broadway, 9th
	Floor, New York, New York 10007.
	Date of Submission:
	By:
	By:(Signature of Partner or corporate officer)
	Print Name:
(0)	
(2)	Submission of Certification of No Change to DDC: By signing in the space provided below,
	the Bidder certifies that it has read the instructions in a "Vendor's Guide to Vendex" and that
	such instructions do not require the Bidder to submit Vendex Questionnaires. The Bidder has
	completed TWO ORIGINALS of the Certification of No Change set forth on the next page of this Bid Booklet.
	uns bid bookiet.
	D.,,
	By:(Signature of Partner or corporate officer)
	(Signature of Partner or corporate officer)
	Print Name:

(NO TEXT ON THIS PAGE)

### **Certificate of No Change Form**



- Please submit two completed forms. Copies will not be accepted.
- Please send both copies to the agency that requested it, unless you are advised to send it directly to the Mayor's Office of Contract Services (MOCS).
- A materially false statement willfully or fraudulently made in connection with this certification, and/or the failure to conduct appropriate due diligence in verifying the information that is the subject of this certification, may result in rendering the submitting entity non-responsible for the purpose of contract award.
- A materially false statement willfully or fraudulently made in connection with this certification may subject the person making the false statement to criminal charges

I,, being duly sworn, state that I have read
Enter Your Name
and understand all the items contained in the vendor questionnaire and any submission of change as identified on page one of this form and certify that as of this date, these items have not changed. I further certify that, to the best of my knowledge, information and belief, those answers are full, complete, and accurate; and that, to the best of my knowledge, information, and belief, those answers continue to be full, complete, and accurate.
In addition, I further certify on behalf of the submitting vendor that the information contained in the principal questionnaire(s) and any submission of change identified on page two of this form have not changed and have been verified and continue, to the best of my knowledge, to be full, complete and accurate.
I understand that the City of New York will rely on the information supplied in this certification as additional inducement to enter into a contract with the submitting entity.
Vendor Questionnaire This section is required.  This refers to the vendor questionnaire(s) submitted for the vendor doing business with the City.
Name of Submitting Entity:
Vendor's Address:
Vendor's EIN or TIN: Requesting Agency:
Are you submitting this Certification as a parent? (Please circle one) Yes No
Signature date on the last full vendor questionnaire signed for the submitting vendor:
Signature date on change submission for the submitting vendor:



Principal Questionnaire

This section refers to the most recent principal questionnaire submissions.

Principal Name	Date of signature on last full Principal	Date(s) of signature o	
·	Questionnaire	submission of change	
1		<del></del>	
2			
3			
4			
5		·	
6		and the second s	
ertification This section	re submitted and attach a document with the submitted attach attach and attach attac		
Name (Print)			
Title			
Name of Submitting Entity			
Signature		Date	
Notarized By:			
Notary Public	County License Issued	License Number	
Sworn to before me on:			

### **Certificate of No Change Form**



- Please submit two completed forms. Copies will not be accepted.
- Please send both copies to the agency that requested it, unless you are advised to send it directly to the Mayor's Office of Contract Services (MOCS).
- A materially false statement willfully or fraudulently made in connection with this certification, and/or the failure to conduct appropriate due diligence in verifying the information that is the subject of this certification, may result in rendering the submitting entity non-responsible for the purpose of contract award.
- A materially false statement willfully or fraudulently made in connection with this certification may subject the person making the false statement to criminal charges

I,, being duly sworn, state that I have read
Enter Your Name
and understand all the items contained in the vendor questionnaire and any submission of change as identified on page one of this form and certify that as of this date, these items have not changed. I further certify that, to the best of my knowledge, information and belief, those answers are full, complete, and accurate; and that, to the best of my knowledge, information, and belief, those answers continue to be full, complete, and accurate.
In addition, I further certify on behalf of the submitting vendor that the information contained in the principal questionnaire(s) and any submission of change identified on page two of this form have not changed and have been verified and continue, to the best of my knowledge, to be full, complete and accurate.
I understand that the City of New York will rely on the information supplied in this certification as additional inducement to enter into a contract with the submitting entity.
Vendor Questionnaire This section is required.  This refers to the vendor questionnaire(s) submitted for the vendor doing business with the City.
Name of Submitting Entity:
Vendor's Address:
Vendor's EIN or TIN: Requesting Agency:
Are you submitting this Certification as a parent? (Please circle one) Yes No
Signature date on the last full vendor questionnaire signed for the submitting vendor:
Signature date on change submission for the submitting vendor:



Principal Questionnaire

This section refers to the most recent principal questionnaire submissions.

Principal Name	Date of signature on last full Principal Questionnaire	Date(s) of signature o submission of change	
	the state of the s		
· · · · · · · · · · · · · · · · · · ·		,	
		<u> </u>	
ertified By:	required. rized. Please complete this twice. Co	opies will not be accepted.	
Name (Print)		**	
Title			
Title  Name of Submitting Entity			
		Date	
Name of Submitting Entity Signature		Date	
Name of Submitting Entity Signature	County License Issued	Date License Number	
Name of Submitting Entity Signature Iotarized By:	County License Issued		

### IRAN DIVESTMENT ACT COMPLIANCE RIDER

### FOR NEW YORK CITY CONTRACTORS

The Iran Divestment Act of 2012, effective as of April 12, 2012, is codified at State Finance Law ("SFL") §165-a and General Municipal Law ("GML") §103-g. The Iran Divestment Act, with certain exceptions, prohibits municipalities, including the City, from entering into contracts with persons engaged in investment activities in the energy sector of Iran. Pursuant to the terms set forth in SFL §165-a and GML §103-g, a person engages in investment activities in the energy sector of Iran if:

- (a) The person provides goods or services of twenty million dollars or more in the energy sector of Iran, including a person that provides oil or liquefied natural gas tankers, or products used to construct or maintain pipelines used to transport oil or liquefied natural gas, for the energy sector of Iran; or
- (b) The person is a financial institution that extends twenty million dollars or more in credit to another person, for forty-five days or more, if that person will use the credit to provide goods or services in the energy sector in Iran and is identified on a list created pursuant to paragraph (b) of subdivision three of Section 165-a of the State Finance Law and maintained by the Commissioner of the Office of General Services.

A bid or proposal shall not be considered for award nor shall any award be made where the bidder or proposer fails to submit a signed and verified bidder's certification.

Each bidder or proposer must certify that it is not on the list of entities engaged in investment activities in Iran created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law. In any case where the bidder or proposer cannot certify that they are not on such list, the bidder or proposer shall so state and shall furnish with the bid or proposal a signed statement which sets forth in detail the reasons why such statement cannot be made. The City of New York may award a bid to a bidder who cannot make the certification on a case by case basis if:

- (1) The investment activities in Iran were made before the effective date of this section (i.e., April 12, 2012), the investment activities in Iran have not been expanded or renewed after the effective date of this section and the person has adopted, publicized and is implementing a formal plan to cease the investment activities in Iran and to refrain from engaging in any new investments in Iran; or
- (2) The City makes a determination that the goods or services are necessary for the City to perform its functions and that, absent such an exemption, the City would be unable to obtain the goods or services for which the contract is offered. Such determination shall be made in writing and shall be a public document.

### BIDDER'S CERTIFICATION OF COMPLIANCE WITH <u>IRAN DIVESTMENT ACT</u>

Pursuant to General Municipal Law §103-g, which generally prohibits the City from entering into contracts with persons engaged in investment activities in the energy sector of Iran, the bidder/proposer submits the following certification:

[Please Check One]

BIDDER'S CERTIFICATION							
behalf of any bidder/proposer certification certifies as to its own organization knowledge and belief, that each bid	By submission of this bid or proposal, each bidder/proposer and each person signing of behalf of any bidder/proposer certifies, and in the case of a joint bid each party there certifies as to its own organization, under penalty of perjury, that to the best of knowledge and belief, that each bidder/proposer is not on the list created pursuant paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law.						
on the list created pursuant to paragra	and the name of the bidder/proposer does not appear aph (b) of subdivision 3 of Section 165-a of the State ned statement setting forth in detail why I cannot so						
Dated:, New York, 20	· .						
· · · · · · · · · · · · · · · · · · ·							
	SIGNATURE						
	PRINTED NAME						
Sworn to before me this day of, 20	TITLE						
Notary Public							
Dated:							

### THE CITY OF NEW YORK **DEPARTMENT OF SMALL BUSINESS SERVICES DIVISION OF LABOR SERVICES CONTRACT COMPLIANCE UNIT** 110 WILLIAMS STREET **NEW YORK, NEW YORK 10038**

PHONE: (212) 513-6323

FAX:

(212) 618-8879

### **CONSTRUCTION**

### **EMPLOYMENT**

### **REPORT**

33

(NO TEXT ON THIS PAGE)

The City of New York
Department of Small Business Services
Division of Labor Services
Contract Compliance Unit
110 William Street
New York, New York 10038
Phone: (212) 513 - 6323

Fax: (212) 618-8879

### CONSTRUCTION EMPLOYMENT REPORT INSTRUCTIONS

### WHO MUST FILE A CONSTRUCTION EMPLOYMENT REPORT

A Construction Employment Report (ER) must be filed if you meet the following conditions:

CONTRACT FUNDING SOURCE	CONTRACTOR	CONTRACT WALTE	SUBMISSION REQUIREMENT	
Federal/Federally assisted	Prime and subcontractors	\$10,000 or greater		
	Prime contractor	\$1,000,000 or greater	Construction Employment Report	
City and state funded	Cuboostrostor	\$750,000 or greater		
	Subcontractor	Less than \$750,000	Less than \$750,000 Certificate (City/State Only)	

### Prime Contractor:

- A general contractor or construction manager selected to perform work on a construction project funded (in whole
  or in part) by the federal government with a proposed contract value of \$10,000 or more.
- A general contractor or construction manager selected to perform work on a construction project funded or assisted by the City of New York with a proposed contract value of \$1,000,000 or more.

### Subcontractor:

- A subcontractor selected to perform work on a construction project funded (in whole or in part) by the federal government with a proposed contract value of \$10,000 or more.
- A subcontractor selected to perform work on a construction project funded or assisted by the City of New York with a proposed contract value of \$750,000 or more.
- A subcontractor selected to perform work on a construction project funded or assisted by the City of New York
  with a proposed contract value of less than \$750,000 must submit a "Less than \$750,000" certificate.

### WHERE TO FILE

Employment Reports must be filed with the City agency awarding the contract. If you are a contractor or subcontractor who will be working for a private developer in receipt of funding or assistance from the City, the ER must be filed with the City agency with jurisdiction over the developer's project.

### **DLS REVIEW PROCESS**

In accordance with Executive Order 50 (EO 50), upon receipt by DLS of a completed ER, DLS conducts a review of the contractor's current employment policies, practices and procedures, as well as perform a statistical analysis of the contractor's workforce, if necessary. The process is as follows:

- 1. Within five (5) business days, DLS will review the ER for completeness and accuracy. If any information is omitted or incorrect, or if necessary documents are not submitted, the submission shall be deemed incomplete and DLS will inform the contractor. The substantive compliance review does not commence until the submission is complete. An incomplete submission will delay the review process and may preclude or interrupt the contract approval.
- 2. If the ER submission is complete, the compliance review will proceed, resulting in one of the following:

### Certificate of Approval

The contractor is found to be in compliance with all applicable laws and regulations. The approval is valid for 36 months.

### **Continued Approval Certificate**

The contractor has been issued a Certificate of Approval in the previous 36 months which is good for the applicable contract.

### **Conditional Certificate of Compliance**

The contractor is required to take corrective actions in order to be in compliance with EO 50. The contractor must meet the conditions within one month of the issue of the Conditional Certificate.

### **Determination of Nonperformance**

The contractor has failed to take the required corrective actions stipulated in the Conditional Certificate. A determination of nonperformance may prevent a contractor from receiving an award of a contract.

### HOW TO COMPLETE THE EMPLOYMENT REPORT

### Contents

General Information

Part I: Contractor/Subcontractor Information
Part II: Employment Policies and Practices

Part III: Contract Bid Information and Projected and Current Workforce Forms

Signature Page

### PART I: CONTRACTOR/SUBCONTRACTOR INFORMATION

Questions 7 – 11: Please provide the required contact information for your company. All contracts must have a designated Equal Employment Officer.

Question 12: If you are a subcontractor, you must state the name of the contractor for whom you are providing the construction services.

Question 13: Please provide the number of permanent employees in your company.

Question 14a-g: The Project Identification Number (PIN) and the Contract Registration ID Number (CT#) can be obtained from the City agency. Provide a description of the trade work you will perform on this project and the address where the work will be performed. Subcontractors can obtain this information from the contract they have with the prime contractor.

Questions 15 – 18: If your company has received a valid Certificate of Approval within the past 36 months, been audited by the United States Department of Labor, Office of Federal Contract Compliance Programs (OFCCP), or if your company has submitted an ER for a different contract for which you have not yet received a compliance certificate, then you only need to complete and submit the following:

- · General Information section
- · Part I Contractor/Subcontractor Information
- Form B Projected Workforce
- Signature Page

If your company is currently waiting for an approval on another contract previously submitted, be certain to identify the date on which you submitted the completed Employment Report, the name of the City contracting agency with which the contract was made, and the name and telephone number of the person to whom the Employment Report was submitted.

If your company was issued a Condition al Certificate of Approval, all required corrective actions must have been taken or DLS will not issue a Continued Certificate.

Question 18:

If the company was audited by the OFCCP, also provide the following:

- Identify the reviewing OFCCP office by its name and address
- If an unconditional certificate of compliance was issued by the OFCCP, attach a copy of the certificate in lieu of completing Parts II and III;
- Include copies of all corrective actions and documentation of OFCCP's performance; and
- · Provide a copy of all stated OFCCP findings.

Question 19:

Please provide a copy of any Collective Bargaining Agreement(s) which is negotiated through an employer trade association on behalf of your organization or any of its affiliates.

### PART II: EMPLOYMENT POLICIES AND PRACTICES

Remember to label all documents with the question number for which they are submitted.

- Questions 20a j: You must respond to the questions as to whether or not your firm has documents reflecting written policies, benefits and procedures. If so, then you must identify by name each document in which the policy(ies), procedure(s) and benefit(s) is located and submit copies of all of the document(s). If your firm follows unwritten practices or procedures, include an explanation of how they operate. Please submit the most current document(s), including all applicable amendments. Label each document and/or unwritten practice according to the question to which it corresponds (e.g. 20a, 20b, etc.)
- Questions 21a h: Inquires about the manner/methods by which you comply with the requirements of the Immigration Reform and Control Act of 1986 (IRCA).
- Question 22: Inquires into where and how I-9 forms are maintained and stored.
- Questions 23a e: Inquires into whether or not there is a requirement that an applicant or employee be subjected to a medical examination at any given time. Copes of the medical information questionnaire and instructions must be submitted with the Employment Report.
- Question 24: Indicate the existence and location of all statements of your firm's Equal Employment Opportunity policy and attach a copy of each statement.
- Question 25: Submit any current Affirmative Action Plan(s) created pursuant to Executive Order 11246.
- Question 26: If your firm or collective bargaining agreement has an internal grievance procedure, indicate this and submit a copy of the policy and procedure. If unwritten, explain its nature and operation. Explain how your firm's procedure addresses EEO complaints.
- Question 27: If your employees have used the procedure in the last three (3) years, please submit an explanation in the format indicated below:

Number of complaint(s)	Nature of the complaint(s)	3. Position(s) of the complainant(s)	4. Was an investigation conducted?	5. Current status of the disposition
			Y/N	

### Question 28:

Indicate whether in the past three (3) years complaints have been filed with a court of law or administrative agency, naming your company as a defendant (or respondent) in a complaint alleging violation of any anti-discrimination or affirmative action laws. If yes, develop and submit a log to show, for each administrative/and or judicial action filed, the following information:

Name(s) of complainant(s)	Administrative agency or court in which action was filed	3. Nature of the complaint(s)	4. Current status	5. If not pending, the complaint's disposition
---------------------------	--	-------------------------------	-------------------	--

Question 29:

Identify each job for which a physical qualification exists. Identify and explain the physical qualification(s) for each stated job. Submit job descriptions for each job and the reasons for the qualifications.

Question 30:

Identify each job for which there exists any qualification related to age, race, color, national origin, sex, creed, disability, marital status, sexual orientation or citizenship status. Identify and explain the specific related qualification for each job stated. Submit job descriptions for each job and the reasons for the qualifications.

### PART III: CONTRACT BID INFORMATION AND PROJECTED AND CURRENT WORKFORCE FORMS

### FORM A: CONTRACT BID INFORMATION - USE OF SUBCONTRACTORS/TRADES

Your projections for the utilization of subcontractors on the proposed contract are to be provided in this section. A chart has been provided for the identification of subcontractors. Information is to be provided to the extent known at the time the ER is filed for review by DLS. If the subcontractor's name is unknown, then write "unknown". Under "ownership", enter the appropriate race/ethnic and gender code. If the contract is federally funded or assisted and the subcontractor is being utilized in accordance with applicable federal requirements with respect to Minority Business Enterprise or Woman Business Enterprise requirements, enter the appropriate code. This will also apply to state funded contracts with similar requirements for minority and female owned businesses.

### FORM B: PROJECTED WORKFORCE FOR WORK TO BE PERFORMED ON THIS PROJECT

For each trade to be engaged by your company for this project, enter the projected workforce for Males and Females by trade classification in the charts provided.

### FORM C: CURRENT WORKFORCE FOR WORK TO BE PERFORMED ON THIS PROJECT

For each trade *currently* engaged by your company for all work performed in NYC, enter the current workforce for Males and Females by trade classification in the charts provided.

### SIGNATURE PAGE

The signatory of this Employment Report and all other documents submitted to DLS must be an official authorized to enter into a binding legal agreement. The signature page must be completed in its entirety and notarized. Only original signatures will be accepted.

### The City of New York Department of Small Business Services Division of Labor Services Constract Compliance Unit 110 William Street, New York, New York 10038

Phone: (212) 513 - 6323 Fax: (212) 618-8879

### CONSTRUCTION EMPLOYMENT REPORT

### GENERAL INFORMATION

•	Your contractual relationship in this contract is: Prim	e contractor_x_ Subcontractor
а.	Are M/WBE goals attached to this project? Yes	No
	Please check one of the following if your firm would like i City of New York as a:	information on how to certify with the
	Minority Owned Business EnterpriseWomen Owned Business EnterpriseDisadvantaged Business Enterprise	Locally Based Business Enterprise Emerging Business Enterprise
<b>a.</b>	If you are certified as an MBE, WBE, LBE, EBE or DBE certified with? Are	i, what city/state agency are you you DBE certified? Yes No
	Please indicate if you would like assistance from SBS in contracting opportunities: Yes No	identifying certified M/WBEs for
	Is this project subject to a project labor agreement? Yes	No
	Are you a Union contractor? Yes No If yes with	, please list which local(s) you affiliated
	Are you a Veteran owned company? Yes No	
<b>ART</b>	T I: CONTRACTOR/SUBCONTRACTOR INFORMATION	
	Employer Identification Number or Federal Tax I.D.	Email Address
	Company Name	
	Company Address and Zip Code	
	Chi. Co	
	Chief Operating Officer	Telephone Number
•	Designated Equal Opportunity Compliance Officer (If same as Item #10, write "same")	Telephone Number
•	Name of Prime Contractor and Contact Person	
	(If same as Item #8, write "same")	

13.	Number of employees in your company:	
14.	Contract information:	
	(a) Contracting Agency (City Agency)	(b)Contract Amount
	(c)Procurement Identification Number (PIN)	(d)Contract Registration Number (CT#)
	(e) Projected Commencement Date	(f) Projected Completion Date
	(g) Description and location of proposed contrac	
15.	Has your firm been reviewed by the Division of La and issued a Certificate of Approval? Yes No.	abor Services (DLS) within the past 36 months
16.	If yes, attach a copy of certificate.  Has DLS within the past month reviewed an Empand issued a Conditional Certificate of Approval?  If yes, attach a copy of certificate.	loyment Report submission for your company Yes No
Wi.	TE: DLS WILL NOT ISSUE A CONTINUED CER TH THIS CONTRACT UNLESS THE REQUIRED ( NDITIONAL CERTIFICATES OF APPROVAL HAV	CORRECTIVE ACTIONS IN PRIOR
17.	Has an Employment Report already been submitted:  Yes No If yes,  Date submitted:  Agency to which submitted:  Name of Agency Person:  Contract No:  Telephone:	eceived compliance certificate?
18.	Has your company in the past 36 months been at Labor, Office of Federal Contract Compliance Pro-	udited by the United States Department of ograms (OFCCP)? Yes No

Page 2 Revised 8/13

FOR OFFICIAL USE ONLY: File No.

	(a) Na	me and address of OFCCP office.
	(b) Wa	as a Certificate of Equal Employment Compliance issued within the past 36 months?  No
	lf y	es, attach a copy of such certificate.
	(c) We	ere any corrective actions required or agreed to? Yes No
	lf y	es, attach a copy of such requirements or agreements.
		re any deficiencies found? Yes No
		es, attach a copy of such findings.
19.	ls your is respo	company or its affiliates a member or members of an employers' trade association which onsible for negotiating collective bargaining agreements (CBA) which affect construction ng? Yes No
	If yes, a	attach a list of such associations and all applicable CBA's.
PAR	TII: DOC	UMENTS REQUIRED
20.	Diochui	following policies or practices, attach the relevant documents (e.g., printed booklets, es, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a full explanation ractices. See instructions.
	(a)	Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)
	(b)	
	(c)	Employee Policy/Handbook
	(d)	Personnel Policy/Manual
	(e)	Supervisor's Policy/Manual
	(f)	Pension plan or 401k coverage/description for all management, nonunion and union employees, whether company or union administered
	(g)	Collective bargaining agreement(s).
	(h)	Employment Application(s)
	(i)	Employee evaluation policy/form(s).
	(j)	Does your firm have medical and/or non-medical (i.e. education, military, personal, pregnancy, child care) leave policy?

21.	To comply with the Immigration Reform and Control Act of 1986 when and of whom does your firm require the completion of an I-9 Form?
	(a) Prior to job offer Yes No
	AL ARTHUR DE LA LA CO
	1 ) 1 de la companya
	7-1V ARM 1- 0 - C - 1 0
	(a) Talana (1) (1)
	(f) T = 1
	/-> T
	// <del>- " " - " - " - " - " - " - " - " - " </del>
	(n) To all employees Yes No
22.	Explain where and how completed I-9 Forms, with their supportive documentation, are maintained and made accessible.
23.	Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes No
	If yes, is the medical examination given:
	(a) Prior to a job offer Yes No
	(b) After a conditional job offer Yes No
	(c) After a job offer Yes No
•	(d) To all applicants YesNo
,	(e) Only to some applicants  YesNo
	(e) only to come approants
	If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.
24.	Do you have a written equal employment opportunity (EEO) policy? Yes No
	If yes, list the document(s) and page number(s) where these written policies are located.
25.	Does the company have a current affirmative action plan(s) (AAP) Minorities and Women Individuals with handicaps Other. Please specify
26.	Does your firm or collective bargaining agreement(s) have an internal grievance procedure with respect to EEO complaints? Yes No
	If yes, please attach a copy of this policy.
	If no, attach a report detailing your firm's unwritten procedure for handling EEO complaints.

Page 4
Revised 8/13
FOR OFFICIAL USE ONLY: File No.

27.	Has any employee, within the past three years, <b>f</b> iled a complaint pursuant to an internal grievance procedure or with any official of your <b>f</b> irm with respect to equal employment opportunity? Yes No
	If yes, attach an internal complaint log. See instructions.
28.	Has your firm, within the past three years, been named as a defendant (or respondent) in any administrative or judicial action where the complainant (plaintiff) alleged violation of any anti-discrimination or affirmative action laws? Yes No
	If yes, attach a log. See instructions.
29.	Are there any jobs for which there are physical qualifications? Yes No
	If yes, list the job(s), submit a job description and state the reason(s) for the qualification(s).
30.	Are there any jobs for which there are age, race, color, national origin, sex, creed, disability, marital status, sexual orientation, or citizenship qualifications? Yes No
	If yes, list the job(s), submit a job description and state the reason(s) for the qualification(s).

### SIGNATURE PAGE

I, (print name of authorized office the information submitted herew submitted with the understandin requirements, as contained in C amended, and the implementing behalf of the company to submit a monthly basis.	with is true and complete g that compliance with hapter 56 of the City Ch g Rules and Regulations	New York City's on arter, Executive is, is a contractua	y knowledge and equal employmen Order No. 50 (19 I obligation, I als	nt 980), as so agree on
Contractor's Name		·		
Name of person who prepared t	his Employment Report		Title	
Name of official authorized to sign	gn on behalf of the cont	ractor	Title	·
Telephone Number	^			
Signature of authorized official			Date	
If contractors are found to be un 56 Section 3H, the Division of Lidata and to implement an employ of Contractors who fail to comply we see that the complex of the complex	abor Services reserves byment program.	the right to reque	est the contractor	's workforce
noncompliance may be subject	to the withholding of fin	al payment.	or are rearing to be	7 III <sub>.</sub> .
Willful or fraudulent falsifications termination of the contract betweentracts for a period of up to fix criminal prosecution.	een the City and the bid	der or contractor	and in disapprov	val of future
To the extent permitted by law a Charter Chapter 56 of the City Cand Regulations, all information	Charter and Executive C	Order No. 50 (198	0) and the imple	ibilities under menting Rules
	Only original signat	ures accepted.		
Sworn to before me this	day of	20	_	
Notary Public	Authorized Signal	ture	Date	

Page 6
Revised 8/13
FOR OFFICIAL USE ONLY: File No.\_\_\_\_\_

## CONTRACT BID INFORMATION: USE OF SUBCONTRACTORS/TRADES FORM A.

- Do you plan to subcontractor work on this contract? Yes\_\_\_ No\_\_
- If yes, complete the chart below. 2

NOTE: All proposed subcontractors with a subcontract in excess of \$750,000 must complete an Employment Report for review and approval before the contract may be awarded and work commences.

	<u> </u>	 1	 ,
PROJECTED DOLLAR VALUE OF SUBCONTRACT	-		
TRADE PROJECTED FOR USE BY SUBCONTRACTOR			
WORK TO BE PERFORMED BY SUBCONTRACTOR			
OWNERSHIP (ENTER APPROPRIATE CODE LETTERS BELOW)	· · ·		
SUBCONTRACTOR'S NAME*			

\*If subcontractor is presently unknown, please enter the trade (craft name).

### OWNERSHIP CODES

W: White

Black

H: Hispanic

A: Asian N: Native American F: Female

FOR OFFICIAL USE ONLY: File No. Revised 8/13

### FORM B: PROJECTED WORKFORCE


### TRADE CLASSIFICATION CODES

(J) Journeylevel Workers (H) Helper

(TOT) Total by Column

(A) Apprentice (TRN) Trainee

For each trade to be engaged by your company for this project, enter the projected workforce for Males and Females by trade classification on the charts below.



What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?

Page 9
Revised 8/13
FOR OFFICIAL USE ONLY: File No.

What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?		
--	--	--

### FORM C: CURRENT WORKFORCE


### TRADE CLASSIFICATION CODES

(J) Journeylevel Workers (H) Helper

(TOT) Total by Column

(A) Apprentice (TRN) Trainee

For each trade currently engaged by your company for all work performed in New York City, enter the current workforce for Males and Females by trade classification on the charts below.



What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?

Page 11 Revised 8/13 FOR OFFICE AT USE ONLY: File No.

FORM C: WARRENT WORKFORCE

Trade:			2	MALES		٠			FEN	FEMALES		
		(1) White	(2) Black	(3)	(4)	(2)	5	(6) /hite	(7) Black	(8)	(6)	(10)
Union Affiliation, if applicable		Non Hisp.	Non Hisp.	Hisp.	Asian	Native Amer.	ZI	Non Hisp.	Non Hisp.	Hisp.	Asian	Native Amer.
Total (Col. #1-10):	<b>7</b>					·						
Total Minority, Male & Female	I											
(Col. #2,3,4,5,7,8,9, & 10):	∢											
Total Female (Col. #6 – 10):	TRN											
	TOT											

What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?

(NO TEXT ON THIS PAGE)

### The City of New York Department of Small Business Services Division of Labor Services Contract Compliance Unit 110 William Street, New York, New York 10038

Phone: (212) 513 - 6323 Fax: (212) 618-8879

### CONSTRUCTION EMPLOYMENT REPORT

### **GENERAL INFORMATION**

•	Your contractual relationship in this contract is:	Prime contractor	_ Subcontractor_x_
a. ,	Are M/WBE goals attached to this project? Yes _	No	
	Please check one of the following if your firm wou City of New York as a:	ld like information on h	now to certify with the
	Minority Owned Business EnterpriseWomen Owned Business EnterpriseDisadvantaged Business Enterprise	Locally Base Emerging Bu	ed Business Enterprise usiness Enterprise
a.	If you are certified as an MBE, WBE, LBE, EBE certified with?	or <b>DBE</b> , what city/state Are you DBE certifi	e agency are you ed? Yes No
•	Please indicate if you would like assistance from scontracting opportunities: Yes No	SBS in identifying certif	fied M/WBEs for
•	Is this project subject to a project labor agreement	? Yes No	
•	Are you a Union contractor? Yes No with	If yes, please list whi	ch local(s) you affiliated
	Are you a Veteran owned company? Yes		
ART	i: CONTRACTOR/SUBCONTRACTOR INFORM		
	Employer Identification Number or Federal Tax I.E	).	Email Address
	Company Name		
	Company Address and Zip Code		
<b>)</b> .			
	Chief Operating Officer	Telephone N	umber
•	Designated Equal Opportunity Compliance Officer (If same as Item #10, write "same")	Telephone No	umber
2.			
	Name of Prime Contractor and Contact Person (If same as Item #8, write "same")		

13.	Number of employees in your company:	
14.	Contract information:	(b)
	Contracting Agency (City Agency)	(b) Contract Amount
	(c) Procurement Identification Number (PIN)	(d) Contract Registration Number (CT#)
	(e) Projected Commencement Date	(f)Projected Completion Date
	(g) Description and location of proposed contract	<b>:</b>
15.	Has your firm been reviewed by the Division of La and issued a Certificate of Approval? Yes No	abor Services (DLS) within the past 36 months
	If yes, attach a copy of certificate.	
16.	Has DLS within the past month reviewed an Empland issued a Conditional Certificate of Approval?	oyment Report submission for your company Yes No
	If yes, attach a copy of certificate.	
W!	TE: DLS WILL NOT ISSUE A CONTINUED CERT TH THIS CONTRACT UNLESS THE REQUIRED ON NOITIONAL CERTIFICATES OF APPROVAL HAN	CORRECTIVE ACTIONS IN PRIOR
17.	Has an Employment Report already been submitted Employment Report) for which you have not yet res No If yes,	ed for a different contract (not covered by this eceived compliance certificate?
	Date submitted: Agency to which submitted:	
	Name of Agency Person:  Contract No: Telephone:	
18.	Has your company in the past 36 months been au Labor, Office of Federal Contract Compliance Pro-	dited by the United States Department of
	If yes,	

Page 2 Revised 8/13 FOR OFFICIAL USE ONLY: File No.\_

	(a) Na — —	me and address of OFCCP office.
	(b) Wa	as a Certificate of Equal Employment Compliance issued within the past 36 months?  No
	lf y	es, attach a copy of such certificate.
	(c) We	re any corrective actions required or agreed to? Yes No
	If y	es, attach a copy of such requirements or agreements.
	(d) We	re any deficiencies found? Yes No
	lf y	es, attach a copy of such findings.
19.	is resh	company or its affiliates a member or members of an employers' trade association which onsible for negotiating collective bargaining agreements (CBA) which affect construction ng? Yes No
	If yes, a	attach a list of such associations and all applicable CBA's.
PART	il: DOC	UMENTS REQUIRED
20.	Diochui	following policies or practices, attach the relevant documents (e.g., printed booklets, es, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a full explanation ractices. See instructions.
	(a)	Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)
	(b)	
	(c)	Employee Policy/Handbook
	(d)	Personnel Policy/Manual
	(e)	Supervisor's Policy/Manual
	(f)	Pension plan or 401k coverage/description for all management, nonunion and union employees, whether company or union administered
	(g)	Collective bargaining agreement(s).
	(h)	Employment Application(s)
	(i)	Employee evaluation policy/form(s).
	(j)	Does your firm have medical and/or non-medical (i.e. education, military, personal, pregnancy, child care) leave policy?

Page 3
Revised 8/13
FOR OFFICIAL USE ONLY: File No.

(a) Prior to job offer (b) After a conditional job offer (c) After a conditional job offer (d) Within the first three days on the job (e) To some applicants (f) To all applicants (g) To some employees (h) To all employees (h) After a conditional job offer (h) After a polo file (h) To all applicants (h) To all	To comply with the Immigration Reform and Control Act of 1986 when and of whom does your firm require the completion of an I-9 Form?
(c) After a conditional job offer Yes_No_ (d) Within the first three days on the job Yes_No_ (e) To some applicants Yes_No_ (f) To all applicants Yes_No_ (h) To all employees Yes_No_ (l) After a conditional job offer Yes_No_ (l) After a conditional job offer Yes_No_ (l) After a job offer Yes_No_ (l) To all applicants Yes_No_ (l) Only to some applicants Yes_No_ (l) Only to some applicants Yes_No_ (l) Only to some applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes_No_  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP) Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wite respect to EEO complaints? Yes_No_  If yes, please attach a copy of this policy.	(a) Prior to job offer
(c) After a job offer	46.5
(a) Within the first three days on the job Yes_No_ (e) To some applicants Yes_No_ (g) To some applicants Yes_No_ (g) To some employees Yes_No_ (h) To all applicants Yes_No_ (h) To all employees Yes_No_ Explain where and how completed I-9 Forms, with their supportive documentation, are maintained and made accessible.  Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes_No_  If yes, is the medical examination given:  (a) Prior to a job offer Yes_No_ (b) After a conditional job offer Yes_No_ (c) After a job offer Yes_No_ (d) To all applicants Yes_No_ (e) Only to some applicants Yes_No_  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes_No_  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women  Individuals with handicaps  Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes_No_  If yes, please attach a copy of this policy.	
(e) To some applicants (f) To all applicants (g) To some employees (h) To all examination? Yes No (h) After a conditional job offer (h) After a conditional	The same and the s
(f) To all applicants (g) To some employees (h) To all employees  Explain where and how completed I-9 Forms, with their supportive documentation, are maintained and made accessible.  Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes No  If yes, is the medical examination given:  (a) Prior to a job offer	
(f) To all applicants (g) To some employees (h) To all employees Yes No Explain where and how completed I-9 Forms, with their supportive documentation, are maintained and made accessible.  Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes No  If yes, is the medical examination given:  (a) Prior to a job offer	
(g) To some employees (h) To all employees (h) To all employees YesNo  Explain where and how completed I-9 Forms, with their supportive documentation, are maintained and made accessible.  Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes No  If yes, is the medical examination given:  (a) Prior to a job offer	(t) To all applicants Yes No
Explain where and how completed I-9 Forms, with their supportive documentation, are maintained and made accessible.  Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes No  If yes, is the medical examination given:  (a) Prior to a job offer	
Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes No  If yes, is the medical examination given:  (a) Prior to a job offer	// \ T =
If yes, is the medical examination given:  (a) Prior to a job offer Yes No (b) After a conditional job offer Yes No (c) After a job offer Yes No (d) To all applicants Yes No (e) Only to some applicants Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	Explain where and how completed I-9 Forms, with their supportive documentation, are maintained and made accessible.
If yes, is the medical examination given:  (a) Prior to a job offer Yes No  (b) After a conditional job offer Yes No  (c) After a job offer Yes No  (d) To all applicants Yes No  (e) Only to some applicants Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	
If yes, is the medical examination given:  (a) Prior to a job offer Yes No (b) After a conditional job offer Yes No (c) After a job offer Yes No (d) To all applicants Yes No (e) Only to some applicants Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	
If yes, is the medical examination given:  (a) Prior to a job offer Yes No (b) After a conditional job offer Yes No (c) After a job offer Yes No (d) To all applicants Yes No (e) Only to some applicants Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	Does your firm or any of its collective bargaining agreements require job applicants to take a
(a) Prior to a job offer Yes No (b) After a conditional job offer Yes No (c) After a job offer Yes No (d) To all applicants Yes No (e) Only to some applicants Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO compiaints? Yes No  If yes, please attach a copy of this policy.	medical examination? Tes No
(b) After a conditional job offer Yes No (c) After a job offer Yes No (d) To all applicants Yes No (e) Only to some applicants Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	If yes, is the medical examination given:
(b) After a conditional job offer Yes No (c) After a job offer Yes No (d) To all applicants Yes No (e) Only to some applicants Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	(a) Prior to a job offer Yes No.
(c) After a job offer Yes No (d) To all applicants Yes No (e) Only to some applicants Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	
(d) To all applicants Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	(b) After a conditional job offer Yes No
(e) Only to some applicants  Yes No  If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women  Individuals with handicaps  Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure with respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	(c) After a job offer Yes No
If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP) Minorities and Women	(d) To all applicants Yes No
If yes, list for which applicants below and attach copies of all medical examination or questionnaire forms and instructions utilized for these examinations.  Do you have a written equal employment opportunity (EEO) policy? Yes No  If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP) Minorities and Women	(e) Only to some applicants  Yes  No
If yes, list the document(s) and page number(s) where these written policies are located.  Does the company have a current affirmative action plan(s) (AAP)  Minorities and Women  Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	questionnaire forms and instructions utilized for these examinations.
Does the company have a current affirmative action plan(s) (AAP) Minorities and Women Individuals with handicaps Other. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	Do you have a written equal employment opportunity (EEO) policy? Yes No
Minorities and WomenIndividuals with handicapsOther. Please specify  Does your firm or collective bargaining agreement(s) have an internal grievance procedure wit respect to EEO complaints? Yes No  If yes, please attach a copy of this policy.	If yes, list the document(s) and page number(s) where these written policies are located.
Other. Please specify	Minorities and Women
If yes, please attach a copy of this policy.	
	Does your firm or collective bargaining agreement(s) have an internal grievance procedure with respect to EEO complaints? Yes No
If no, attach a report detailing your firm's unwritten procedure for handling EEO complaints.	If yes, please attach a copy of this policy.

27.	Has any employee, within the past three years, filed a complaint pursuant to an internal grievance procedure or with any official of your firm with respect to equal employment opportunity? Yes No
	If yes, attach an internal complaint log. See instructions.
28.	Has your firm, within the past three years, been named as a defendant (or respondent) in any administrative or judicial action where the complainant (plaintiff) alleged violation of any anti-discrimination or affirmative action laws? Yes No
	If yes, attach a log. See instructions.
29.	Are there any jobs for which there are physical qualifications? Yes No
	If yes, list the job(s), submit a job description and state the reason(s) for the qualification(s).
30.	Are there any jobs for which there are age, race, color, national origin, sex, creed, disability, marital status, sexual orientation, or citizenship qualifications? Yes No
	If yes, list the job(s), submit a job description and state the reason(s) for the qualification(s).

FOR OFFICIAL USE ONLY: File No.

# SIGNATURE PAGE

requirements, as contained in C amended, and the implementing	vith is true and complete to the be g that compliance with New York hapter 56 of the City Charter, Ex g Rules and Regulations, is a con-	hereby certify that est of my knowledge and belief and control country is equal employment ecutive Order No. 50 (1980), as intractual obligation. I also agree on the distriction of Labor Services on
Contractor's Name		
Name of person who prepared t	his Employment Report	Title
Name of official authorized to sign	gn on behalf of the contractor	Title
Telephone Number		
Signature of authorized official		Date
If contractors are found to be un 56 Section 3H, the Division of Ladata and to implement an employed	abor Services reserves the right t	es in any given trade based on Chapter to request the contractor's workforce
Contractors who fail to comply we noncompliance may be subject	with the above mentioned required to the withholding of final paymer	ments or are found to be in
termination of the contract between	s of any data or information submeen the City and the bidder or core years. Further, such falsification	ntractor and in disapproval of future
Charter Chapter 56 of the City C	nd consistent with the proper dis Charter and Executive Order No. ( provided by a contractor to DLS	charge of DLS' responsibilities under 50 (1980) and the implementing Rules shall be confidential.
	Only original signatures acce	pted.
Sworn to before me this	day of 20	<del></del>
	·	
Notary Public	Authorized Signature	Date

Page 6
Revised 8/13
FOR OFFICIAL USE ONLY: File No.\_\_\_\_\_

# CONTRACT BID INFORMATION: USE OF SUBCONTRACTORS/TRADES

FORM A.

- Do you plan to subcontractor work on this contract? Yes\_\_\_\_ No\_\_
- If yes, complete the chart below. 2

NOTE: All proposed subcontractors with a subcontract in excess of \$750,000 must complete an Employment Report for review and approval before the contract may be awarded and work commences.

SUBCONTRACTOR'S NAME*	OWNERSHIP (ENTER APPROPRIATE CODE LETTERS BELOW)	WORK TO BE PERFORMED BY SUBCONTRACTOR	TRADE PROJECTED FOR USE BY SUBCONTRACTOR	PROJECTED DOLLAR VALUE OF SUBCONTRACT

\*If subcontractor is presently unknown, please enter the trade (craft name).

OWNERSHIP CODES

W: White

Black

H: Hispanic

A: Asian N: Native American F: Female

FOR OFFICIAL USE ONLY: File No. Revised 8/13 Page 8

# FORM B: PROJECTED WORKFORCE


# TRADE CLASSIFICATION CODES

(J) Journeylevel Workers (H) Helper

(TOT) Total by Column

(TRN) Trainee (A) Apprentice

For each trade to be engaged by your company for this project, enter the projected workforce for Males and Females by trade classification on the charts below.



What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?

Revised 8/13 Page 9

VSE ONLY: File No. FOR OFFICE

treach)?	
hires (i.e., unions, government employment office, job tap center, community outreach)?	
overnment employment office	
orojected hires (i.e., unions, g	
What are the recruitment sources for you projected	
What are the r	

# FORM C: CURRENT WORKFORCE


# TRADE CLASSIFICATION CODES

(J) Journeylevel Workers (H) Helper.

(TOT) Total by Column

(A) Apprentice (TRN) Trainee

For each trade currently engaged by your company for all work performed in New York City, enter the current workforce for Males and Females by trade classification on the charts below.



What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?

SE ONLY: File No. Revised 8/13 Page 11

FOR OPFICE

What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?

(NO TEXT ON THIS PAGE)

# The City of New York Department of Small Business Services Division of Labor Services Contract Compliance Unit 110 William Street, New York, New York 10038

Phone: (212) 513 - 6323 Fax: (212) 618-8879

Date_			**************************************	4		File Number	
			LESS THAN S	750,000 SUI	BCONTRACT AND ICIP ON	CERTIFICATE	
Are yo	u currently	certified as o	one of the follow	ving? Please	check yes or	no:	
MBE	YesN	o	WBE Yes	No	LBE	YesNo	
DBE	Yes	No	EBE Yes	No			
If you	are certified	as an MBE	WBE, LBE, EE	BE or DBE, w	hat city/state	agency are you certii	fied with?
				would like in	formation on I	now to certify with the	city of New York as a
	nority Owne		•		Lo	cally based Business	Enterprise
Wo	omen Owne	d Business	Enterprise		Eı	merging Business E	Enterprise
Dis	sadvantaged	l Business E	Enterprise				
Compa	any Name				Employe	r Identification Numb	er or Federal Tax I.D
Compa	any Address	and Zip Co	de				
Contac	ct Person (F	irst Name, L	ast Name)			Telephone Number	
Fax Nu	ımber					E-mail Address	
Descrip	otion and lo	cation of pro	posed subcont	ract:			
Are you	u a Union co	ontractor?	Yes No _	If yes,	please list wh	ich local(s) you affilia	ted with
Are you	u a Veteran	owned com	pany? Yes	No			
	ement Ident ontracts only		mber (PIN)		Contract R (City contra	egistration Number ( acts only)	CT#)
Revised FOR O	l 8/13 FFICIAL US	E ONLY: F	le No				

Block and Lot Number (ICIP projects only)	Contract Amount
I, (print name of authorized official signing) authorized by the above-named subcontractor to cabove named owner or City agency is less than \$7 Charter Chapter 56, Executive Order No. 50 (1980)	hereby certify that I am certify that said subcontractor's proposed contract with the 750,000. This affirmation is made in accordance with NYC 0) and the implementing Rules.
Willful or fraudulent falsifications of any data or info contract between the City and the bidder or contra	ormation surbmitted herewith may result in the termination of the actor and in disapproval of future contracts for a period of up to
five years. Further, such falsification may result in	n civil and/arnd or criminal prosecution.
five years. Further, such falsification may result in Signature of authorized official	civil and/and or criminal prosecution.  Date

Revised 8/13 FOR OFFICIAL USE ONLY: File No.



# INFRASTRUCTURE DIVISION BUREAU OF DESIGN

# **VOLUME 1 OF 3**

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES
IN: ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET
BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

INCLUDING WATER MAIN WORK

Together With All Work Incidental Thereto BOROUGH OF STATEN ISLAND CITY OF NEW YORK

	 Contractor
Dated	



# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

30-30 THOMSON AVENUE LONG ISLAND CITY, NEW YORK 11101-3045 TELEPHONE (718) 391-1000 WEBSITE www.nyc.gov/buildnyc

# **VOLUME 2 OF 3**

# INFORMATION FOR BIDDERS CONTRACT PERFORMANCE AND PAYMENT BONDS PREVAILING WAGE SCHEDULE

FOR FURNISHING ALL LABOR AND MATERIALS NECESSARY AND REQUIRED FOR:

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN: ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD; WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET; FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE; WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE; GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE; MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE; VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND, WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

# **INCLUDING WATER MAIN WORK**

Together With All Work Incidental Thereto
BOROUGH OF STATEN ISLAND
CITY OF NEW YORK

FOR THE DEPARTMENT OF ENVIRONMENTAL PROTECTION PREPARED BY IN-HOUSE DESIGN

February 26, 2014



# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

30-30 THOMSON AVENUE LONG ISLAND CITY, NEW YORK 11101-3045 TELEPHONE (718) 391-1000 WEBSITE www.nyc.gov/buildnyc

# **VOLUME 2 OF 3**

# INFORMATION FOR BIDDERS CONTRACT PERFORMANCE AND PAYMENT BONDS PREVAILING WAGE SCHEDULE

FOR FURNISHING ALL LABOR AND MATERIALS NECESSARY AND REQUIRED FOR:



FOR THE DEPARTMENT OF ENVIRONMENTAL PROTECTION PREPARED BY IN-HOUSE DESIGN

February 26, 2014

# **NOTICE TO BIDDERS**

Please be advised that the City of New York has issued a new Standard Construction Contract. The new Contract, which is incorporated in this bid, is significantly different from the 2008 version previously used by the City. A listing of some of the significant changes is provided below. This notice is only a partial listing. Please refer to the Contract itself for a full understanding of the changes and the actual text of the changes that were made. The text of the revised Standard Construction Contract is the controlling document should there be any discrepancies between this notice and the Standard Construction Contract.

Significant changes include the following:

# ARTICLE 11 DAMAGES CAUSED BY DELAYS

In 2008, the City embarked on a pilot project to test the use of new construction contract language altering the allocation of the risk of project delays, as between the City and the contractor. The City has determined to make the pilot project language the standard language for all City construction contracts. Accordingly, there is now one Standard City Construction Contract that it to be used by all agencies for all bids released after the release of the new contract. The damages for delay language is Article 11. Please note that changes have been made to the damages for delay provisions from the pilot to the adopted version.

# ARTICLE 22 INSURANCE

Changes have been made to the insurance provisions, including incorporating requirements that the insurance provided comply with recent NYC Department of Buildings regulations specifying required dollar limits for CGL insurance for certain projects and requiring proof of builder's risk insurance prior to Work commencing rather than within 10 days of award.

# ARTICLE 26 EXTRA WORK

The percentage paid for overhead for Extra Work pursuant to Section 26.1.11 is increased from 10% to 12% and the calculation of Worker's Compensation insurance costs reimbursed for Extra Work has been clarified.

ARTICLE 37 LABOR LAW REQUIREMENTS

ARTICLE 38 PAYROLL REPORTS

The provisions governing Labor Law provisions have been tightened, including requirements the employee identification cards include a photo (unless the requirement is waived), a prohibition on cash payments to employees and subcontractors, and clear enforcement authority requirements.

# ARTICLE 70 ELECTRONIC FILING

A provision is added to make mandatory the electronic filing of certain alteration permits with the Department of Buildings.

# Other significant changes include the following:

# ARTICLE 7 INDEMNIFICATION

Changes have been made to the indemnification provisions.

ARTICLE14 FINAL ACCEPTANCE OF WORK
ARTICLE 44 SUBSTANTIAL COMPLETION PAYMENT

The Commissioner is no longer required to issue a substantial completion determination in addition to the already existing requirement that the Engineer issue a substantial completion determination and reach an agreement on a punch list of remaining work. Now, the Engineer, when issuing the punch list to the Contractor, must also include a proposed schedule for the completion of the punch list. The Contractor may propose an alternative schedule that is subject to the approval of the Engineer. If the Contractor fails to respond to the Engineer's proposed schedule, the Engineer's schedule is deemed accepted.

# ARTICLE 15 LIQUIDATED DAMAGES

The contract is revised to match Schedule A to provide that liquidated damages are available only until substantial completion.

# ARTICLE 17 SUBCONTRACTS

The requirements for prior approval of subcontractors, and for contractors to be responsible for the actions of their subcontractors, have been tightened. The requirement that the Contractor list subcontractors in the City's Payee Information Portal has been added; the provision was previously attached as a rider.

# ARTICLE 19 SECURITY DEPOSIT

The provisions governing the return of bid deposits are clarified.

# ARTICLE 20 PAYMENT GUARANTEE

The Payment Guaranty provisions, which apply when the City does not require the Contractor to obtain payment bonds, has been significantly revised to track the requirements of State Finance law 137.

# ARTICLE 28 RECORDKEEPING FOR EXTRA OR DISPUTED WORK

The recordkeeping requirement that currently apply to payments for Time & Materials for extra work are expressly made applicable to regular work that is paid for on a T & M basis.

# ARTICLE 35 EMPLOYEES

The whistleblower provisions of local law are added to the construction contract. They previously have been attached as a rider.

# ARTICLE 38 PAYROLL REPORTS ARTICLE 77 RECORDS RETENTION

Requirements that records be maintained for six years and directions on how such records must be made available.

# ARTICLE 42 PARTIAL PAYMENTS

Increased flexibility has been provided for when contractors may submit invoices.

# ARTICLE 62 TAX EXEMPTION

The provisions identifying the State tax exemption for municipalities are revised to more clearly describe State law.

(NO TEXT ON THIS PAGE)

# **CITY OF NEW YORK**

# DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURES

# **INFORMATION FOR BIDDERS**

**SEPTEMBER 2008** 

(NO TEXT ON THIS PAGE)

# CITY OF NEW YORK CITY DEPARTMENT OF DESIGN AND CONSTRUCTION INFORMATION FOR BIDDERS

# TABLE OF CONTENTS

SECTION 1.	DESCRIPTION AND LOCATION OF WORK	1
SECTION 2.	TIME AND PLACE FOR RECEIPT OF BIDS	1
SECTION 3.	DEFINITIONS	1
SECTION 4.	INVITATION FOR BIDS AND CONTRACT DOCUMENTS	1
SECTION 5.	PRE-BID CONFERENCE	2
SECTION 6.	AGENCY CONTACT	2
SECTION 7.	BIDDER'S OATH	2
SECTION 8.	EXAMINATION AND VIEWING OF SITE,	2
	CONSIDERATION OF OTHER SOURCES OF INFORMATION	
	AND CHANGED CONDITIONS	2
SECTION 9.	EXAMINATION OF PROPOSED CONTRACT	3
SECTION 10.	FORM OF BID	3
SECTION 11.	IRREVOCABILITY OF BID	3
SECTION 12.	ACKNOWLEDGMENT OF AMENDMENTS	4
SECTION 13.	BID SAMPLES AND DESCRIPTIVE LITERATURE	4
SECTION 14.	PROPRIETARY INFORMATION/TRADE SECRETS	4
SECTION 15.	PRE-OPENING MODIFICATION OR WITHDRAWAL OF BIDS	4
SECTION 16.	BID EVALUATION AND AWARD	4
SECTION 17.	LATE BIDS, LATE WITHDRAWALS AND LATE MODIFICATIONS	5
SECTION 18.	WITHDRAWAL OF BIDS.	5
SECTION 19.	MISTAKE IN BIDS	5
SECTION 20.	LOW TIE BIDS	. 6
SECTION 21.	REJECTION OF BIDS	. 6
SECTION 22.	RIGHT TO APPEAL DETERMINATIONS OF	O
	NON-RESPONSIVENESS OR NON-RESPONSIBILITY AND	
	RIGHT TO PROTEST SOLICITATIONS AND AWARD	. 7
SECTION 23.	AFFIRMATIVE ACTION AND EQUAL	•
•	EMPLOYMENT OPPORTUNITY	7
SECTION 24.	VENDEX QUESTIONNAIRES	7
SECTION 25.	COMPLAINTS ABOUT THE BID PROCESS	8
SECTION 26.	BID, PERFORMANCE AND PAYMENT SECURITY	8
SECTION 27.	FAILURE TO EXECUTE CONTRACT	9
SECTION 28.	BIDDER RESPONSIBILITIES AND QUALIFICATIONS	ģ
SECTION 29.	EMPLOYMENT REPORT	10
SECTION 30.	LABOR LAW REQUIREMENTS	10
SECTION 31.	INSURANCE	10
SECTION 32.	LUMP SUM CONTRACTS	11
SECTION 33.	UNIT PRICE CONTRACTS	11
SECTION 34.	EXCISE TAX	11
SECTION 35.	LICENSES AND PERMITS	11
SECTION 36.	MULTIPLE PRIME CONTRACTORS	11
SECTION 37.	LOCALLY BASED ENTERPRISE REQUIREMENTS (LBE)	12
SECTION 38.	BID SUBMISSION REQUIREMENTS	13
SECTION 39.	COMPTROLLER'SCERTIFICATE	14
SECTION 40.	PROCUREMENT POLICY BOARD RULES	14
SECTION 41.	DDC SAFETY REQUIREMENTS	14
		- '

i

(NO TEXT ON THIS PAGE)

# INFORMATION FOR BIDDERS

# 1. <u>Description and Location of Work</u>

The description and location of the work for which bids are requested are specified in Attachment 1, "Bid Information". Attachment 1 is included as page A-l of the Bid Booklet.

# 2. <u>Time and Place for Receipt of Bids</u>

Sealed bids shall be received on or before the date and hour specified in Attachment 1, at which time they will be publicly opened and read aloud in the presence of the Commissioner or his or her representative, and any bidders who may desire to be present.

# 3. <u>Definitions</u>

The definitions set forth in the Procurement Policy Board Rules shall apply to this Invitation For Bids.

# 4. <u>Invitation For Bids and Contract Documents</u>

- (A) Except for titles, sub-titles, headings, running headlines, tables of contents and indices (all of which are printed herein merely for convenience) the following, except for such portions thereof as may be specifically excluded, shall be deemed to be part of the Contract and the Invitation for Bids.
  - (1) All provisions required by law to be inserted in this Contract, whether actually inserted or not
  - (2) The Contract Drawings and Specifications
  - (3) The General Conditions, the General Requirements and the Special Conditions, if any
  - (4) The Contract
  - (5) The Information for Bidders; Request for Proposals; Notice of Solicitation and Proposal For Bids; Bid or Proposal, and, if used, the Bid Booklet
  - (6) The Budget Director's Certificate; all Addenda issued prior to the receipt of the bids; the Notice of Award; Performance and Payment Bonds, if required; and the Notice to Proceed with the Work.
- (B) For particulars as to this procurement, including quantity and quality of the purchase, extent of the work or labor to be performed, delivery and performance schedule, and any other special instructions, prospective bidders are referred to the Invitation For Bids Documents. A copy of such documents can be obtained at the location set forth in Attachment 1.
- (C) <u>Deposit for Copy of Invitation For Bids Documents</u>: Prospective bidders may obtain a copy of the Invitation For Bids Documents by complying with the conditions set forth in the Notice of Solicitation. The deposit must be in the form of a check or money order made payable to the City of New York, and drawn upon a state or national bank or trust company, or a check of such bank or trust company signed by a duly authorized officer thereof.
- (D) Return of Invitation For Bids Documents: All Invitation For Bids Documents must be returned to the Department upon request. If the bidder elects not to submit a bid thereunder, the

Invitation For Bids Documents shall be returned to the Department, along with a statement that no bid will be submitted.

- (E) Return of Deposit: Such deposit will be returned within 30 days after the award of the contract or the rejection of all bids as set forth in the advertisement, provided the Invitation For Bids Documents are returned to the location specified in Attachment 1, in physical condition satisfactory to the Commissioner.
- (F) Additional Copies: Additional copies of the Invitation For Bids Documents may be obtained, subject to the conditions set forth in the advertisement for bids.

#### 5. <u>Pre-Bid Conference</u>

A pre-bid conference shall be held as set forth in Attachment 1. Nothing stated at the pre-bid conference shall change the terms or conditions of the Invitation For Bids Documents, unless a change is made by written amendment as provided in Section 9 below. Failure to attend a mandatory pre-bid conference shall constitute grounds for the rejection of the bid.

# 6. Agency Contact

Any questions or correspondence relating to this bid solicitation shall be addressed to the Agency Contact person specified in Attachment 1.

#### 7. Bidder's Oath

- (A) The bid-shall be properly signed by an authorized representative of the bidder and the bid shall be verified by the written oath of the authorized representative who signed the bid, that the several matters stated and information furnished therein are in all aspects true.
- (B) A materially false statement willfully or fraudulently made in connection with the bid or any of the forms completed and submitted with the bid may result in the termination of any Contract between the City and the Bidder. As a result, the Bidder may be barred from participating in future City contracts as well as be subject to possible criminal prosecution.

# 8. Examination and Viewing of Site, Consideration of Other Sources of Information and Changed Conditions

- (A) Pre-Bidding (Investigation) Viewing of Site -Bidders must carefully view and examine the site of the proposed work, as well as its adjacent area, and seek other usual sources of information, for they will be conclusively presumed to have full knowledge of any and all conditions on, about or above the site relating to or affecting in any way the performance of the work to be done under the Contract which were or should have been indicated to a reasonably prudent bidder. To arrange a date for visiting the work site, bidders are to contact the Agency Contact person specified in Attachment 1.
- (B) Should the contractor encounter during the progress of the work subsurface conditions at the site materially differing from any shown on the Contract Drawings or indicated in the Specifications or such subsurface conditions as could not reasonably have been anticipated by the contractor and were not anticipated by the City, which conditions will materially affect the cost of the work to be done under the

Contract, the attention of the Commissioner must be called immediately to such conditions before they are disturbed. The Commissioner shall thereupon promptly investigate the conditions. If he finds that they do so materially differ, or that they could not have been reasonably anticipated by the contractor and were not anticipated by the City, the Contract may be modified with his written approval.

# 9. Examination of Proposed Contract

- (A) Request for Interpretation or Correction: Prospective bidders must examine the Contract Documents carefully and before bidding must request the Commissioner in writing for an interpretation or correction of every patent ambiguity, inconsistency or error therein which should have been discovered by a reasonably prudent bidder. Such interpretation or correction, as well as any additional contract provisions the Commissioner may decide to include, will be issued in writing by the Commissioner as an addendum to the Contract, which will be transmitted to each person recorded as having received a copy of the Contract Documents from the Department. Transmission of such addendum will be by mail, e-mail, facsimile or hand delivery. Such addendum will also be posted at the place where the Contract Documents are available for the inspection of prospective bidders. Upon transmission as provided for herein, such addendum shall become a part of the Contract Documents, and binding on all bidders, whether or not actual notice of such addendum is shown.
- (B) Only Commissioner's Interpretation or Correction Binding: Only the written interpretation or correction so given by the Commissioner shall be binding, and prospective bidders are warned that no other officer, agent or employee of the City is authorized to give information concerning, or to explain or interpret, the Contract.
- (C) Documents given to a subcontractor for the purpose of soliciting the subcontractor's bid shall include either a copy of the bid cover sheet or a separate information sheet setting forth the project name, the Contract number (if available), the contracting agency and the Project's location.

# 10. Form of Bid

Each bid must be submitted upon the prescribed form and must contain: a) the name, residence and place of business of the person or persons making the same; b) the names of all persons interested therein, and if no other person is so interested, such fact must be distinctly stated; c) a statement to the effect that it is made without any connection with any other person making a bid for the same purpose and that it is in all respects fair and without collusion or fraud; d) a statement that no Council member or other officer or employee or person whose salary is payable in whole or part from the City Treasury is directly or indirectly interested therein or in the supplies, materials or equipment and work or labor to which it relates, or in any portion of the profits thereof; e) a statement that the bidder is not in arrears to the City or to any agency upon a debt or contract or taxes, and is not a defaulter as surety or otherwise upon any obligation to the City to any agency thereof, except as set forth in the bid.

THE BID SHALL BE TYPEWRITTEN OR WRITTEN LEGIBLY IN INK. THE BID SHALL BE SIGNED IN INK. ERASURES OR ALTERATIONS SHALL BE INITIALED BY THE SIGNER IN INK. FAILURE TO CONFORM TO THE REQUIREMENTS OF THIS SECTION 10 SHALL RESULT IN THE REJECTION OF THE BID.

# 11. <u>Irrevocability of Bid</u>

The prices set forth in the bid cannot be revoked and shall be effective until the award of the Contract, unless the bid is withdrawn as provided for in Sections 15 and 18 below.

# 12. Acknowledgment of Amendments

The receipt of any amendment to the Contract Documents shall be acknowledged by the bidder in its bid submission.

# 13. <u>Bid Samples and Descriptive Literature</u>

Bid samples and descriptive literature shall not be submitted by the bidder, unless expressly requested elsewhere in the Contract or Contract Documents. Any unsolicited bid samples or descriptive literature which are submitted shall not be examined or tested and shall not be deemed to vary any of the provisions of this Contract.

# 14. <u>Proprietary Information/Trade Secrets</u>

- (A) The bidder shall identify those portions of the bid which it deems to be confidential, proprietary information or trade secrets, and provide justification why such materials shall not be disclosed by the City. All such materials shall be clearly indicated by stamping the pages on which such information appears, at the top and bottom thereof with the word "Confidential". Such materials stamped "Confidential" must be easily separable from the non-confidential sections of the bid.
- (B) All such materials so indicated shall be reviewed by the Agency and any decision not to honor a request for confidentiality shall be communicated in writing to the bidder. For those bids which are unsuccessful, all such confidential materials shall be returned to the bidder. Prices, makes and model or catalog numbers of the items offered, deliveries, and terms of payment shall be publicly available after bid opening, regardless of any designation of confidentiality made by the bidder.

# 15. Pre-Opening Modification or Withdrawal of Bids

Bids may be modified or withdrawn by written notice received in the office designated in Attachment 1, before the time and date set for the bid opening. If a bid is withdrawn in accordance with this Section, the bid security, if any, shall be returned to the bidder.

# 16. Bid Evaluation and Award

In accordance with the New York City Charter, the Procurement Policy Board Rules and the terms and conditions of this Invitation For Bids, this Contract shall be awarded, if at all, to the responsible bidder whose bid meets the requirements and evaluation criteria set forth in the Invitation For Bids, and whose bid price is either the most favorable bid price or, if the Invitation For Bids so states, the most favorable evaluated bid price. A bid may not be evaluated for any requirement or criterion that is not disclosed in the Invitation For Bids.

<u>Restriction</u>: No negotiations with any bidder shall be allowed to take place except under the circumstances and in the manner set forth in Section 21. Nothing in this Section shall be deemed to permit a contract award to a bidder submitting a higher quality item than that designated in the Invitation For Bids, if that bid is not also the most favorable bid.

# 17. Late Bids, Late Withdrawals and Late Modifications

Any bid received at the place designated in the solicitation after the time and date set for receipt of bids is late and shall not be considered. Any request for withdrawal or modification received at the place designated in the solicitation after the time and date set for receipt of bids is late and shall not be considered. The exception to this provision is that a late modification of a successful bid that makes the bid terms more favorable to the City shall be considered at any time it is received.

# 18. Withdrawal of Bids.

Except as provided for in Section 15, above, a bidder may not withdraw its bid before the expiration of forty-five (45) days after the date of the opening of bids; thereafter, a bidder may withdraw its bid only in writing and in advance of an actual award. If within sixty (60) days after the execution of the Contract, the Commissioner fails to fix the date for commencement of work by written notice to the bidder, the bidder, at his option, may ask to be relieved of his obligation to perform the work called for by written notice to the Commissioner. If such notice is given to the Commissioner, and the request to withdraw is granted, the bidder waives all claims in connection with this Contract.

# 19. Mistake in Bids

(A) <u>Mistake Discovered Before Bid Opening</u>: A bidder may correct mistakes discovered before the time and date set for bid opening by withdrawing or correcting the bid as provided in Section 15 above.

# (B) Mistakes Discovered Before Award

- (1) In accordance with General Municipal Law (Section 103, subdivision 11), where a unilateral error or mistake is discovered in a bid, such bid may be withdrawn upon written approval of the Agency Chief Contracting Officer if the following conditions are met:
  - (a) The mistake is known or made known to the agency prior to the awarding of the Contract or within 3 days after the opening of the bid, whichever period is shorter; and
  - (b) The price bid was based upon an error of such magnitude that enforcement would be unconscionable; and
  - (c) The bid was submitted in good faith and the bidder submits credible evidence that the mistake was a clerical error as opposed to a judgment error; and
  - (d) The error in the bid is actually due to an unintentional and substantial arithmetic error or an unintentional omission of a substantial quantity of work, labor, material or services made directly in the compilation of the bid, which unintentional arithmetic error or unintentional omission can be clearly shown by objective evidence drawn from inspection of the original work paper, documents, or materials used in the preparation of the bid sought to be withdrawn; and
  - (e) It is possible to place the agency in the same position as existed prior to the bid.
- (2) Unless otherwise required by law, the sole remedy for a bid mistake in accordance with this Article shall be withdrawal of the bid, and the return of the bid bond, or other security, if any, to the bidder. Thereafter, the agency may, in its discretion, award the Contract to the next lowest bidder or rebid the Contract. Any amendment to or reformation of a bid or a Contract to rectify such an error or mistake

therein is strictly prohibited.

(3) If the mistake and the intended correct bid are clearly evident on the face of the bid document, the bid shall be corrected to the intended correct bid and may not be withdrawn. Examples of mistakes that may be corrected are typographical errors, errors in extending unit prices, transposition errors and arithmetical errors.

# 20. Low Tie Bids

- (A) When two or more low responsive bids from responsible bidders are identical in price, meeting all the requirements and criteria set forth in the Invitation For Bids, the Agency Chief Contracting Officer will break the tie in the following manner and order of priority:
  - (1) Award to a certified New York City small, minority or woman-owned business entity bidder;
  - (2) Award to a New York City bidder;
  - (3) Award to a certified New York State small, minority or woman-owned business bidder;
  - (4) Award to a New York State bidder.
- (B) If two or more bidders still remain equally eligible after application of paragraph (A) above, award shall be made by a drawing by lot limited to those bidders. The bidders involved shall be invited to attend the drawing. A witness shall be present to verify the drawing and shall certify the results on the bid tabulation sheet.

# 21. Rejection of Bids

- (A) Rejection of Individual Bids: The Agency may reject a bid if:
- (1) The bidder fails to furnish any of the information required pursuant to Section 24 or 28 hereof; or if
- (2) The bidder is determined to be not responsible pursuant to the Procurement Policy Board Rules; or if
- (3) The bid is determined to be non-responsive pursuant to the Procurement Policy Board Rules; or if
- (4) The bid, in the opinion of the Agency Chief Contracting Officer, contains unbalanced bid prices and is thus non-responsive, unless the bidder can show that the prices are not unbalanced for the probable required quantity of items, or if the imbalance is corrected pursuant to Section 15.
- (B) Rejection of All Bids: The Agency, upon written approval by the Agency Chief Contracting Officer, may reject all bids and may elect to resolicit bids if in its sole opinion it shall deem it in the best interest of the City so to do.
- (C) Rejection of All Bids and Negotiation With All Responsible Bidders: The Agency Head may determine that it is appropriate to cancel the Invitation For Bids after bid opening and before award and to complete the acquisition by negotiation. This determination shall be based on one of the following reasons:

- (1) All otherwise acceptable bids received are at unreasonable prices, or only one bid is received and the Agency Chief Contracting Officer cannot determine the reasonableness of the bid price, or no responsive bid has been received from a responsible bidder; or
- (2) In the judgment of the Agency Chief Contracting Officer, the bids were not independently arrived at in open competition, were collusive, or were submitted in bad faith.
- (D) When the Agency has determined that the Invitation for Bids is to be canceled and that use of negotiation is appropriate to complete the acquisition, the contracting officer may negotiate and award the Contract without issuing a new solicitation, subject to the following conditions:
  - (1) prior notice of the intention to negotiate and a reasonable opportunity to negotiate have been given by the contracting officer to each responsible bidder that submitted a bid in response to the Invitation for Bids;
  - (2) the negotiated price is the lowest negotiated price offered by a responsible bidder; and
  - the negotiated price is lower than the lowest rejected bid price of a responsible bidder that submitted a bid in response to the Invitation for Bids.

# 22. <u>Right to Appeal Determinations of Non-Responsiveness or Non-Responsibility and Right to Protest Solicitations and Award</u>

The bidder has the right to appeal a determination of non-responsiveness or non-responsibility and has the right to protest a solicitation and award. For further information concerning these rights, the bidder is directed to the Procurement Policy Board Rules.

# 23. Affirmative Action and Equal Employment Opportunity

This Invitation For Bids is subject to applicable provisions of Federal, State and Local Laws and executive orders requiring affirmative action and equal employment opportunity.

# 24. <u>VENDEX Questionnaires</u>

- (A) Requirement: Pursuant to Administrative Code Section 6-116.2 and the PPB Rules, bidders may be obligated to complete and submit VENDEX Questionnaires. Generally, if this bid is \$100,000 or more, or if this bid when added to the sum total of all contracts, concessions and franchises the bidder has received from the City and any subcontracts received from City contractors over the past twelve months, equals or exceeds \$100,000, Vendex Questionnaires must be completed. If required, Vendex Questionnaires must be completed and submitted before any award of contract may be made or before approval is given for a proposed subcontractor. Non-compliance with these submission requirements may result in the disqualification of the bid, disapproval of a subcontractor, subsequent withdrawal of approval for the use of an approved subcontractor, or the cancellation of the contract after its award.
- (B) <u>Submission</u>: Vendex Questionnaires must be submitted directly to the Mayor's Office of Contract Services, ATTN: Vendex, 253 Broadway, 9th Floor, New York, New York 10007. In addition, the bidder must submit a Confirmation of Vendex Compliance to the agency. A form for this confirmation is set forth in the Bid Booklet.
- (C) Obtaining Forms: Vendex Questionnaires, as well as detailed instructions, may be obtained at <a href="https://www.nyc.gov/vendex">www.nyc.gov/vendex</a>. The bidder may also obtain Vendex forms and instructions by contacting the

Agency Chief Contracting Office or the contract person for this contract.

# 25. Complaints About the Bid Process

The New York City Comptroller is charged with the audit of contracts in New York City. Any vendor who believes that there has been unfairness, favoritism or impropriety in the bid process should inform the Comptroller, Office of Contract Administration, One Centre Street, Room 835, New York, New York; telephone number (212)669-2797.

# 26. Bid, Performance and Payment Security

- (A) Bid Security: Each bid must be accompanied by bid security in an amount and type specified in Attachment 1 (page A-1 of the Bid Booklet). The bid security shall assure the City of New York of the adherence of the bidder to its proposal, the execution of the Contract, and the furnishing of Performance and Payment Bonds by the bidder, if required in Attachment 1. Bid security shall be returned to the bidder as follows:
  - (1) Within ten (10) days after the bid opening, the Comptroller will be notified to return the deposits of all but the three (3) lowest bidders. Within five (5) days after the award, the Comptroller will be notified to return the deposits of the remaining two unsuccessful bidders.
  - (2) Within five (5) days after the execution of the Contract and acceptance of the Contractor's bonds, the Comptroller will be notified to return the bid security of the successful bidder or, if performance and payment bonds are not required, only after the sum retained under Article 21 of the Contract equals the amount of the bid security.
  - (3) Where all bids are rejected, the Comptroller will be notified to return the deposit of the three (3) lowest bidders at the time of rejection.
- (B) <u>Performance and Payment Security</u>: Performance and Payment Security must be provided in an amount and type specified in Attachment 1 (page A-l of the Bid Booklet). The performance and payment security shall be delivered by the contractor prior to or at the time of execution of the Contract. If a contractor fails to deliver the required performance and payment security, its bid security shall be enforced, and an award of Contract may be made to the next lowest responsible and responsive bidder, or the contract may be rebid.
- (C) <u>Acceptable Types of Security</u>: Acceptable types of security for bids, performance, and payment shall be limited to the following:
  - (1) a one-time bond in a form satisfactory to the City;
  - (2) a bank certified check or money order;
  - (3) obligations of the City of New York; or
  - (4) other financial instruments as determined by the Office of Construction in consultation with the Comptroller.

Whenever the successful bidder deposits obligations of the City of New York as performance and payment security, the Comptroller may sell and use the proceeds thereof for any purpose for which the principal or surety on such bond would be liable under the terms of the Contract. If the money is deposited with the Comptroller, the successful bidder shall not be entitled to receive interest on such money from the City.

(D) Form of Bonds: Security provided in the form of bonds must be prepared on the form of bonds authorized by the City of New York. Forms for bid, performance, and payment bonds are included in the Invitation for Bids Documents. Such bonds must have as surety thereunder such surety company or companies as are: (I) approved by the City of New York; (2) authorized to do business in the State of New York, and (3) approved by the Department of the Treasury of the United States. Premiums for any required bonds must be included in the base bid.

The bidder is advised that submission of a bid bond where the surety on such bond fails to meet the criteria set forth herein, shall result in the rejection of the bid as non-responsive.

The Department of the Treasury of the United States advises that information concerning approved surety companies may be obtained as follows: (1) from the Government Printing Office at 202-512-1800; (2) through the Internet at <a href="http://www.fms.treas.gov/c570/index.html">http://www.fms.treas.gov/c570/index.html</a>, and (3) through a computerized public bulletin board, which can be accessed by using your computer modem and dialing 202-874-6887.

(E) <u>Power of Attorney</u>: Attorneys in fact who sign bid, performance, or payment bonds must file with each bond a certified copy of their power of attorney to sign said bonds.

# 27. Failure to Execute Contract

In the event of failure of the successful bidder to execute the Contract and furnish the required security within ten (10) days after notice of the award of the Contract, the deposit of the successful bidder or so much thereof as shall be applicable to the amount of the award made shall be retained by the City, and the successful bidder shall be liable for and hereby agrees to pay on demand the difference between the price bid and the price for which such Contract shall be subsequently awarded, including the cost of any required reletting and less the amount of such deposit. No plea of mistake in such accepted bid shall be available to the bidder for the recovery of the deposit or as a defense to any action based upon such accepted bid. Further, should the bidder's failure to comply with this Section cause any funding agency, body or group (Federal, State, City, Public, Private, etc.) to terminate, cancel or reduce the funding on this project, the bidder in such event shall be liable also to the City for the amount of actual funding withdrawn by such agency on this project, less the amount of the forfeited deposit.

# 28. <u>Bidder Responsibilities and Qualifications</u>

- (A) Bidders must include with their bids all information necessary for a determination of bidder responsibility, as set forth in the Specifications.
- (B) The Agency may require any bidder or prospective bidder to furnish all books of account, records, vouchers, statements or other information concerning the bidder's financial status for examination as may be required by the Agency to ascertain the bidder's responsibility and capability to perform the Contract. If required, a bidder must also submit a sworn statement setting forth such information as the Agency may require concerning present and proposed plant and equipment, the personnel and qualifications of his working organizations, prior experience and performance record.
- (C) <u>Oral Examination on Qualifications</u>: In addition thereto, and when directed by the Agency, the bidder, or a responsible officer, agent or employee of the bidder, must submit to an oral examination to be conducted by the Agency in relation to his proposed tentative plan and schedule of

operations, and such other matters as the Agency may deem necessary in order to determine the bidder's ability and responsibility to perform the work in accordance with the Contract. Each person so examined must sign and verify a stenographic transcript of such examination noting thereon such corrections as such person may desire to make.

(D) If the bidder fails or refuses to supply any of the documents or information set forth in paragraph (B) hereof or fails to comply with any of the requirements thereof, the Agency may reject the bid.

# 29. Employment Report

In accordance with Executive Order No. 50 (1980) as modified by Executive Order 108 (1986), the filing of a completed Employment Report (ER) is a requirement of doing business with the City of New York for construction contractors with contracts of \$1,000,000 or more and subcontractors with construction subcontracts of \$750,000 or more. The required forms and information are included in the Bid Booklet.

# 30. <u>Labor Law Requirements</u>

- (A) <u>General</u>: The successful bidder will be required to comply strictly with all Federal, State and local labor laws and regulations.
- (B) New York State Labor Law: This Contract is subject to New York State Labor Law Section 220, which requires that construction workers on the site be paid prevailing wages and supplements. The Contractor is reminded that all wage provisions of this Contract will be enforced strictly and failure to comply will be considered when evaluating performance. Noncompliance may result in the contractor being debarred by the City from future contracts. Complaints filed with the Comptroller may result in decisions which may debar a contractor from bidding contracts with any state governmental entity and other political subdivisions.
- (C) <u>Records</u>: The Contractor is expected to submit accurate payroll reports and other required documents and verify attendance and job classifications being utilized in compliance with the law, Contract provisions and agency procedures.

#### 31. Insurance

- (A) Bidders are advised that the insurance requirements contained herein are regarded as material terms of the Contract. As required by Article 22 of the Contract, the contractor must effect and maintain with companies licensed and authorized to do business in the State of New York, the types of insurance set forth therein, when required by and in the amounts set forth in Schedule A of the General Conditions. Such required insurance must be provided from the date the contractor is ordered to commence work and up to the date of final acceptance of all required work.
- (B) The contractor must, within ten days of receipt of the notice of award, submit the following insurance documentation: (a) original certificate of insurance for general liability in the amount required by Schedule A of the General Conditions, and (b) original certificates of insurance or other proof of coverage for workers' compensation and disability benefits, as required by Section 57 of the New York State Workers' Compensation Law and Section 220 of the Disability Benefits Law.

# 32. <u>Lump Sum Contracts</u>

- (A) <u>Comparison of Bids</u>: Bids on Lump Sum Contracts will be compared on the basis of the lump sum price bid, adjusted for alternate prices bid, if any.
- (B) Lump Sum Bids for "General Construction Work" which include excavation shall include all necessary excavation work defined in the Specifications as being included in the lump sum bid. The bidder shall also bid a unit price for the additional cost of excavating material which is defined in the Specifications as excavation for which additional payment will be made. The total estimated additional cost of removing such material will be taken as the quantity set forth in the Engineer's Estimate multiplied by the unit price bid. This total estimated cost of additional excavation shall be added to the lump sum bid for the General Construction Work for the purpose of comparing bids to determine the low bidder.
- (C) <u>Variations from Engineer's Estimate</u>: The Engineer's Estimate of the quantity of excavation for which additional payment will be made is approximate only and is given solely to be used as a uniform basis for the comparison of bids and such estimate is not to be considered as part of this contract. The quantities actually required to complete the contract work may be more or less than the quantities in the Engineer's Estimate and, if so, no action for damages or for loss of profits shall accrue to the contractor by reason thereof.

# 33. Unit Price Contracts

- (A) <u>Comparison of Bids</u>: Bids on Unit Price Contracts will be compared on the basis of a total estimated price, arrived at by taking the sum of the estimated quantities of such items, in accordance with the Engineer's Estimate of Quantities set forth in the Bid Schedule, multiplied by the corresponding unit prices, and including any lump sum bids on individual items.
- (B) <u>Variations from Engineer's Estimate</u>: Bidders are warned that the Engineer's Estimate of Quantities on the various items of work and materials is approximate only, given solely to be used as a uniform basis for the comparison of bids, and is not be considered part of this contract. The quantities actually required to complete the contract work may be less or more than so estimated, and if so, no action for damages or for loss of profits shall accrue to the contractor by reason thereof.
- (C) Overruns: The terms and conditions applicable to overruns of unit price items are set forth in Article 26 of the Contract.

# 34. Excise Tax

Bidders are referred to the Specifications for information on Federal Excise Tax exemptions.

#### 35. Licenses and Permits

The successful bidder will be required to obtain all necessary licenses and permits necessary to perform the work.

#### 36. Multiple Prime Contractors

If more than one prime contractor will be involved on this project, all contractors are required to examine the Invitation for Bid packages for all other parts of the project.

# 37. Locally Based Enterprise Requirements (LBE)

This Contract is subject to the requirements of Administrative Code, Section 6-108.1, and the regulations promulgated thereunder. No construction contract will be awarded unless and until these requirements have been complied with in their entirety. The bidder is advised of the provisions set forth below, as well as the provisions with respect to the Locally Based Enterprise Program contained in Article 67 of the Contract. The contractor is advised that:

- (A) If any portion of the Contract is subcontracted, not less than ten percent of the total dollar amount of the contract shall be awarded to locally based enterprises ("LBEs"); except, where less than ten percent of the total dollar amount of the Contract is subcontracted, such lesser percentage shall be so awarded.
  - (B) No contractor shall require performance and payment bonds from LBE subcontractors.
  - (C) No Contract shall be awarded unless the contractor first identifies in its bid:
  - (1) the percentage, dollar amount and type of work to be subcontracted; and
  - (2) the percentage, dollar amount and type of work to be subcontracted to LBEs.
- (D) Within ten calendar days after notification of low bid, the apparent low bidder shall submit an "LBE Participation Schedule" to the contracting agency. If such schedule does not identify sufficient LBE subcontractors to meet the requirements of Administrative Code Section 6-108.1, the apparent low bidder shall submit documentation of its good faith efforts to meet such requirements.
  - (1) The "LBE Participation Schedule" shall include:
    - (a) the name and address of each LBE that will be given a subcontract,
    - (b) the percentage, dollar amount and type of work to be subcontracted to the LBE, and
    - (c) the dates when the LBE subcontract work will commence and end.
  - (2) The following documents shall be attached to the "LBE Participation Schedule":
    - (a) verification letters from each subcontractor listed in the "LBE Participation Schedule" stating that the LBE will enter into a formal agreement for work,
    - (b) certification documents of any proposed LBE subcontractor which is not on the LBE certified list, and
    - (c) copies of the certification letter of any proposed subcontractor which is an LBE.
  - (3) Documentation of good faith efforts to achieve the required LBE percentage shall include as appropriate but not limited to the following:
    - (a) attendance at prebid meetings, when scheduled by the agency, to advise bidders of contract requirements;

- (b) advertisement where appropriate in general circulation media, trade association publications and small business media of the specific subcontracts that would be at least equal to the percentage goal for LBE utilization specified by the contractor;
- (c) written notification to association of small, minority and women contractors soliciting specific subcontractors:
- (d) written notification by certified mail to LBE firms that their interest in the contract is solicited for specific work items and their estimated values;
- demonstration of efforts made to select portions of the work for performance by LBE firms in order to increase the likelihood of achieving the stated goal;
- (f) documented efforts to negotiate with LBE firms for specific subcontracts, including at a minimum:
  - (i) The names, address and telephone numbers of LBE firms that are contacted;
  - (ii) A description of the information provided to LBE firms regarding the plans and specifications for portions of the work to be performed;
  - (iii) Documentation showing that no reasonable price can be obtained from LBE firms:
  - (iv) A statement of why agreements with LBE firms were not reached;
- (g) a statement of the reason for rejecting any LBE firm which the contractor deemed to be unqualified; and
- (h) documentation of efforts made to assist the LBE firms contacted that needed assistance in obtaining required insurance.
- (E) Unless otherwise waived by the Commissioner with the approval of the Office of Economic and Financial Opportunity, failure of a proposed contractor to provide the information required by paragraphs (C) and (D) above may render the bid non-responsive and the Contract may not be awarded to the bidder. If the contractor states that it will subcontract a specific portion of the work, but can demonstrate despite good faith efforts it cannot achieve its required LBE percentage for subcontracted work until after award of Contract, the Contract may be awarded, subject to a letter of compliance from the contractor stating that it will comply with Administrative Code Section 6-108.1 and subject to approval by the Commissioner. If the contractor has not met its required LBE percentage prior to award, the contractor shall demonstrate that a good faith effort has been made subsequent to award to obtain LBEs on each subcontract until its meets the required percentage.
- (F) When a bidder indicates prior to award that no work will be subcontracted, no work may be subcontracted without the prior written approval of the Commissioner, which shall be granted only if the contractor in good faith seeks LBE subcontractors at least six weeks prior to the start of work.
- (G) The contractor may not substitute or change any LBE which was identified prior to award of the contract without the written permission of the Commissioner. The contractor shall make a written application to the Commissioner for permission to make such substitution or change, explaining why the contractor needs to change its LBE subcontractor and how the contractor will meet its LBE subcontracting requirement. Copies of such application must be served on the originally identified LBE by certified mail return receipt requested, as well as the proposed substitute LBE. The Commissioner shall determine whether or not to grant the contractor's request for substitution.

#### 38. Bid Submission Requirements

The following forms, all of which are contained in the Bid Booklet, are to be completed and submitted with the bid:

- (1) Bid Schedule and Bid Form, including Affirmation
- (2) Bid Security (if required, see Attachment 1 on Page A-1)
- (3) M/WBE Subcontactor Utilization Plan (if participation goals have been established)

# FAILURE TO SUBMIT ITEMS (1), (2) AND (3) WILL RESULT IN THE DISQUALIFICATION OF THE BID.

- (4) Safety Questionnaire
- (5) Construction Employment Report (if bid is \$1,000,000 or more)
- (6) Contract Certificate (if bid is less than \$1,000,000)
- (7) Confirmation of Vendex Compliance
- (8) Special Experience Requirements (if applicable to this contract)
- (9) Apprenticeship Program Questionnaire (if applicable)

# FAILURE TO SUBMIT ITEMS (4) THROUGH (9) MAY RESULT IN THE DISQUALIFICATION OF THE BID.

# 39. Comptroller's Certificate

This Contract shall not be binding or of any force unless it is registered by the Comptroller in accordance with Section 328 of the City Charter and the Procurement Policy Board Rules. This Contract shall continue in force only after annual appropriation of funds by the City of New York and certification as hereinabove set forth.

# 40. Procurement Policy Board Rules

This Invitation For Bids is subject to the Rules of the Procurement Policy Board of the City of New York. In the event of a conflict between said Rules and a provision of this Invitation For Bids, the Rules shall take precedence.

# 41. <u>DDC Safety Requirements</u>

The DDC Safety Requirements apply to the work to be performed pursuant to the Contract. The DDC Safety Requirements are set forth on the following pages.

## **CITY OF NEW YORK**

# DEPARTMENT OF DESIGN AND CONSTRUCTION

## SAFETY REQUIREMENTS

## THE DDC SAFETY REQUIREMENTS INCLUDE THE FOLLOWING SECTIONS:

I.	POLICY ON SITE SAFETY
п.	PURPOSE
ш.	DEFINITIONS
rv.	RESPONSIBILITIES
v.	
	SAFETY QUESTIONNAIRE
VI.	SAFETY PROGRAM AND SITE SAFETY PLAN
VII.	KICK-OFF/PRE-CONSTRUCTION MEETINGS AND SAFETY REVIEW
VIII.	EVALUATION DURING WORK IN PROGRESS
IX.	SAFETY PERFORMANCE EVALUATION

#### I. POLICY ON SITE SAFETY

The City of New York Department of Design and Construction (DDC) is committed to a policy of injury and illness prevention and risk management for construction work that will ensure the safety and health of the workers engaged in the projects and the protection of the general public. Therefore, it is DDC's policy that work carried out by Contractors on DDC jobsites must, at a minimum, comply with applicable federal, state and city laws, rules and regulations, including without limitation:

- □ U. S. Department of Labor 29 Code of Federal Regulations (CFR) Part 1926 and applicable Sub-parts of Part 1910 U.S. Occupational Safety and Health Administration (OSHA) including, but not limited to "Respiratory Protection" (29 CFR 1910.134), "Permit-Required Confined Spaces" (29 CFR 1910.146), and "Hazard Communication" (29 CFR 1910.1200);
- New York State Department of Labor Industrial Code Rule 23 Protection in Construction, Demolition and Excavation;
- New York City Construction Codes, Title 28
- □ NYC Department of Transportation Title 34 Chapter 2 Highway Rules
- New York State Department of Labor Industrial Code Rule 753
- NYC Local Law No. 113 (2005) Noise Control Code

In addition, all regulations promulgated by the NYC Department of Transportation, including requirements for Maintenance and Protection of Traffic (MPT), are applicable when contained in contract specifications. While MPT is a significant component of work in our Infrastructure Division, it does not supersede or exempt Contractors from complying with other applicable health and safety standards (for example, excavating and trenching standards, operation of heavy equipment and compliance with City environmental and noise regulations).

#### II. PURPOSE

The purpose of this policy is to ensure that Contractors perform their work and supervise their employees in accordance with all applicable federal, state and city rules and regulations. Further, Contractors will be expected to minimize or eliminate jobsite and public hazard, through a planning, inspection, auditing and corrective action process. The goal is to control risks so that injuries, illnesses and accidents to contractors' employees, DDC employees and the general public, as well as damage to city-owned and private property, are reduced to the lowest level feasible.

#### III. DEFINITIONS

Agency Chief Contracting Officer (ACCO): The ACCO shall mean the person delegated authority by the Commissioner to organize and supervise the procurement activity of subordinate Agency staff in conjunction with the CCPO.

Competent Person: As defined by OSHA, an individual who is capable of identifying existing and predictable hazards in the surroundings or working conditions that are unsanitary, hazardous, or dangerous to employees or the general public, and who has authorization to take prompt corrective measures to eliminate them.

Construction Safety Auditor: A representative of the QACS Construction Safety Unit who provides inspection and assessment services to enhance health and safety on all DDC construction projects. The activities of the Construction Safety Auditor include performing site surveys, reviewing health and safety plans, reviewing construction permits, and rendering technical advice and assistance to DDC Resident Engineers and Project Managers.

Construction Safety Unit: A part of QACS within the Division of Technical Support that assesses contractor safety on DDC jobsites and advises responsible parties of needed corrective actions.

Construction Superintendent: A representative of the contractor responsible for overseeing performance of the required construction work. This individual must engage in sound construction practices, and is responsible to maintain a safe work site. In the case of a project involving the demolition, alteration or new construction of buildings, the Construction Superintendent must be licensed by the NYC Department of Buildings.

Contractor: For purposes of these Safety Requirements, the term "Contractor" shall mean any person or entity that enters into a contract for the performance of construction work on a DDC project. The term "Contractor" shall include any person or entity which enters into any of the following types of contracts: (1) a prime construction contract for a specific project, (2) a prime construction contract using the Job Order Contracting System ("JOCS Contract"), and (3) a subcontract with a CM/Builder ("First Tier Subcontract").

**Director - Quality Assurance and Construction Safety (QACS)**: Responsible for the operations of the QACS Construction Safety Unit and the DDC Site Safety management programs.

Job Hazard Assessment (JHA): A process of identifying site-specific hazards that may be present during construction and establishing the means and methods to reduce or eliminate those hazards.

Jobsite Safety Coordinator: A person designated by the Contractor to be onsite during all activities. This individual shall have received, at a minimum, the OSHA 10-hour construction safety program. Other examples of acceptable training are the 30-hour OSHA Safety and Health Standards for the Construction Industry training program (OSHA 510) or a degree/certificate in a safety and health from a college-level curriculum. This person does not necessarily have to be dedicated full-time to site safety, but must have sufficient experience and authority to undertake corrective action and must qualify to be a competent person. For certain projects, as defined in NYC Construction Codes – Title 28, this person may be required to have a Site Safety Manager's License issued by the NYC DOB.

Qualified Person: As defined by OSHA, an individual who, by possession of a recognized degree, certificate, license or professional standing, or who by extensive knowledge, training, and experience, has successfully demonstrated his or her ability to solve problems relating to the subject matter, the work, or the project. Qualified Persons are required under regulation to address issues pertaining, but without limit, to fall protection, scaffold design and trenching and shoring, among others.

Resident Engineer (RE) / Construction Project Manager (CPM): Representative of the Commissioner duly designated by the Commissioner to be his/her representative at the site of the work. (The RE/CPM may be a third-party consultant, including a CM, retained by DDC.)

Safety Program: Established by the Contractor that covers all operations of that Contractor and establishes the Contractor's overall safety policy, regulatory compliance plan and minimum safety standards. The Safety Program must be submitted prior to the commencement of work at the site and is subject to review and acceptance by the Construction Safety Unit.

Safety Questionnaire: Used by DDC to evaluate Contractor's current and past safety performance. It is required to be completed by all Contractors initially when submitting bids for Construction work, or when being pre-qualified and updated annually or as requested by the DDC.

Site Safety Plan: A site-specific safety plan developed by the Contractor for a specific project. The Site Safety Plan must identify hazards associated with the project, and include specific safety precautions and training appropriate and necessary to complete the work. The Site Safety Plan must be submitted prior to the commencement of work at the site and is subject to review and acceptance by the Construction Safety Unit.

Unsafe or Unhealthy Condition: A condition that could be potentially hazardous to the health and safety of personnel or the public, and/or damaging to equipment, machinery, property or the environment.

Weekly Safety Meetings: Weekly documented jobsite safety meetings, given to all jobsite personnel by contractor, with the purpose of discussing general safety topics and job specific requirements encountered at the DDC work site.

#### IV. RESPONSIBILITIES

All persons who manage, perform, and provide support for construction projects shall conduct operations in compliance with the requirements identified in this Policy and all applicable governing regulatory agency requirements and guidelines pertaining to safety in construction.

## A. Resident Engineer / Construction Project Manager / Construction Manager

- Monitors the issuance of safety-related permits, approvals and drawings and maintains copies on site.
- Monitors construction-related work activities to confirm that they are conducted in accordance with DDC policies and all applicable regulations that pertain to construction safety.
- Maintains documentation and periodically attends weekly safety meeting.
- Notifies the Construction Safety Unit and the ACCO's Insurance and Risk Management Unit of project-related accidents and emergencies, as per DDC's Construction Safety Emergency Protocol.
- Gathers facts related to all accidents and prepares DDC Accident Reports.
- Notifies the Construction Safety Unit of outside regulatory agency inspections and forwards a copy of the inspection report within three days of its receipt.
- Monitors the conditions at the site for conformance with the Site Safety Plan and DDC construction documents.
- Notifies the contractor and DDC in the event that any condition or activity exists that is not in compliance with the Site Safety Plan, applicable federal, state or local codes or any condition that presents a potential risk of injury to the public or workers or possible damage to property.
- Notifies DDC of any emergency condition and directs the contractor to provide such labor, materials, equipment and supervision to abate such conditions.
- Reports gross safety violations to the Construction Safety Unit immediately.

#### B. Contractors

- Complete a Safety Questionnaire and submit with its bid or as part of a pre-qualification package.
- Provide a Written Job Hazard Assessment (JHA) that identifies expected safety issues of the work to be performed. JHA shall be included with the Site Safety Plan submitted by the contractor.
- Submit a Site Safety Plan and Safety Program within 15 days of issuance of the Notice to Proceed, or as
  otherwise directed. The Site Safety Plan and Safety Program are subject to review and acceptance by the
  Construction Safety Unit prior to the commencement of work at the site. The Site Safety Plan shall be revised and
  updated as necessary.
- Ensure that all employees are aware of the hazards associated with the project through formal and informal training and/or other communications. Conduct and document weekly safety meetings for the duration of the project. Documentation to be provided to the RE/CPM/CM on a monthly basis.
- Name a Construction Superintendent, if required.
- Name a Job Site Safety Coordinator. The Contractor will be required to identify the Job Site Safety Coordinator
  in the Site Safety Plan.
- Comply with all mandated federal, state and local safety and health rules and regulations.
- Comply with all provisions of the Site Safety Plan.
- As part of the Site Safety Plan, prepare a site specific MPT (if not otherwise provided in the contract documents) and comply with all of its provisions.

- Conduct and document site-specific safety orientation for Contractor personnel to review the hazards associated
  with the project as identified in the Site Safety Plan and the specific safety procedures and controls that will be
  used to protect workers, the general public and property. The Job Site Safety Coordinator will conduct this
  training prior to mobilization and provide documentation to the RE/CPM/CM.
- Provide, replace and adequately maintain at or around the project site, suitable and sufficient signage, lights, barricades and enclosures (fences, sidewalk sheds, netting, bracing, etc.).
- Report unsafe conditions or hazards to the DDC RE/CPM/CM as soon as practical, but no more than 24 hours after discovery, and take action to remove or abate such conditions.
- Report any accident involving injuries to workers or the general public, as well as property damage, to the DDC RE/CPM/CM within two (2) hours.
- Notify the DDC RE/CPM/CM within two (2) hours of the start of an inspection by any regulatory agency personnel, including OSHA.
- Maintain all records pertaining to all required compliance documents and accident and injury reports.
- Respond to DDC recommendations on safety, which shall in no way relieve the Contractor of its responsibilities for safety on the project. The Contractor has sole responsibility for safety.

#### V. SAFETY QUESTIONNAIRE

DDC requires that all Contractors provide information regarding their current and past safety and environmental performance and programs. This will be accomplished by the use of the DDC Safety Questionnaire. As a part of the bid submittal package, the contractor must submit a completed DDC Safety Questionnaire listing their workers' compensation experience modification rating and OSHA Incidence Rates for the three (3) years prior to the date of the bid opening. DDC may request a Contractor to update its Questionnaire at any time or to provide more detailed information. The Contractor must provide the requested update within 30 days.

The following criteria will be used by DDC in reviewing the Contractor's responsibility, which will be based on the information provided on the questionnaire:

- Criteria 1: OSHA Injury and Illness Rates (I&IR) are no greater than the average for the industry (based on the most current Bureau of Labor Statistics data for the Contractors SIC code); and
- Criteria 2: Insurance workers compensation Experience Modification Rate (EMR) equal to or less than 1.0; and
- Criteria 3: Any willful violations issued by OSHA or NYC DOB within the last three years; and
- Criteria 4: A fatality (worker or member of public) experienced on or near Contractor's worksite within the last three (3) years; and
- Criteria 5: An unacceptable rating by QACS based on past performance on DDC projects; and
- Criteria 6: Contractor has in place an acceptable corporate safety program and its employees shall have completed all documented relative safety training; and
- Criteria 7: Contractor shall provide OSHA Injury Records (currently OSHA 300 Log) for the last three (3) years.

If the Contractor fails to meet the basic criteria listed above, the Construction Safety Unit may request, through the ACCO, more detail concerning the Contractor's safety experience. DDC may request the Contractor to provide copies of, among other things, OSHA records, OSHA and DOB citations, EPA citations and written Safety Programs.

#### VI. SAFETY PROGRAM AND SITE SAFETY PLAN

Within fifteen (15) days of issuance of the Notice to Proceed, or as otherwise directed, the Contractor shall submit the following: (1) Safety Program, and (2) Site Safety Plan. The Safety Program shall set forth the Contractor's overall safety policy, regulatory compliance plan and minimum safety standard, and the Site Safety Plan shall identify hazards associated with the project, and include specific safety precautions and training appropriate and necessary to complete the work. The Safety Program and the Site Safety Plan are subject to review and acceptance by the Construction Safety Unit prior to the commencement of work at the site. Failure by the contractor to submit an acceptable Site Safety Plan and Safety Program shall be grounds for default.

The Site Safety Plan shall apply to all Contractor and subcontractor operations, and shall have at a minimum, the following elements. Each element shall be described in a separate section in the written document. It may be necessary to modify the basic format for certain unique or high-risk projects (such as tunnels or high-rise construction). The basic elements are as follows:

- Responsibility and Organization: Identify the person or persons with authority and responsibility for implementing the Site Safety Plan. Provide an organization chart and define levels of authority and responsibility. Identify the Competent Person, the Construction Superintendent (if required), the Job Safety Coordinator and the Qualified Person required for this project.
- 2. Communication: Establish a system for communicating with employees and subcontractors on matters relating to worker and public safety and health and environmental protection, including provisions designed to encourage employees to inform the employer of hazards at the worksite without fear of reprisal. An emergency response notification protocol is to be established that also includes after hours contact numbers. The plan must also include provisions for weekly safety meetings held by the Job Site Safety Coordinator.
- 3. Job Hazard Assessment: A written document submitted by the contractor, used to identify expected job hazards and public safety risks and state the specific means and methods to reduce, control or eliminate those hazards. This part of the Site Safety Plan must also include how on-going evaluations of those risks and hazards will be carried out, including plans for periodic inspections to identify unsafe conditions, work practices and public safety hazards.
- 4. Accident/Exposure Investigation: Establish a procedure to investigate and report occupational and public injury or illness, property damage, vehicle accidents or other mishaps.
- 5. Hazard Correction: Establish means, methods and/or procedures for correcting unsafe or unhealthy conditions that might be exposing both the public and workers to hazards. Corrective actions must be taken immediately when observed or discovered. Should an imminent hazard exist which cannot be immediately abated without endangering employees, the public and/or property, remove or restrict all exposed persons from the area except those necessary to correct the existing condition. Employees necessary to correct the hazardous condition shall be provided the necessary safeguards. When corrective actions cannot be taken immediately, temporary measures should be taken until such time permanent measures are taken to eliminate the potential risks or hazards
- 6. Training: Describe site-specific hazard training programs. In addition to the required safety orientation, additional site specific training, in the form of required weekly safety meetings, will be required. Contractors must also initiate training when: a) new employees are hired; b) employees are given new job assignments for which training has not been previously received; c) new substances, processes, procedures or equipment are introduced that might represent a new public or worker hazard; d) the employee is made aware of a new or previously unrecognized hazard; e) new supervisors are assigned to familiarize themselves with the safety and health hazards to which employees under their immediate direction and control may be exposed; and f) after a jobsite incident or accident has occurred.

7. Recordkeeping: Establish procedures to maintain records of scheduled and periodic inspections, weekly safety meetings, and training records. Updated records shall be maintained at the jobsite, accessible to the Construction Safety Auditors and/or Quality Assurance Auditors/RE/CPM, and retained in accordance with DDC policy.

The most critical component of the Site Safety Plan is the Job Hazard Assessment section. This section must address specific hazards that are anticipated throughout the project. Each Site Safety Plan must address, at a minimum:

- Public and pedestrian safety
- Fall protection
- Electrical hazards
- Scaffolding
- Fire protection
- Emergency notification & response
- Housekeeping / debris removal
- Dust control

- Maintenance and protection of traffic
- Trenching and excavating
- Heavy equipment operations
- Material / equipment storage
- Environmental contamination
- Sheeting and shoring
- Alcohol and Drug Abuse Policy

The following additional hazards must be addressed, if applicable, based on the contract safety specifications and/or the results of the JHA (the list is not all-inclusive):

- Basic Personal Protective Equipment
- Compressed Air
- Compressed Gas Cylinders
- Cranes, Derricks and Hoists
- Demolition
- Electrical safety
- Excavations and Trenching
- Fall Protection Floor openings/Stairways
- Fall Protection Guardrails Toe boards etc
- Fall Protection Leading Edge
- Fall Protection Personal Fall Protection Devices
- Fire Protection and Fire Prevention
- Hazard Communication (RIGHT TO KNOW)
- Hazardous Energy & Lock Out / Tag Out
- Housekeeping/Sanitation
- Maintenance and Protection of Traffic (MPT)
- Man Lifts / Aerial Lifts
- Marine Operations
- Motor Vehicle Safety
- Overhead Power lines
- Permit Required Confined Space
- Portable Ladders
- Powered Actuated Tools
- Powered Material Handling Equipment
- Scaffolds Mobile
- Scaffolds Stationary
- Scaffolds Suspended
- Slings
- Steel Erection

- Welding and Cutting (Hot Work)
- Airborne Contaminants Particulates General
- Asbestos
- Blood borne Pathogens
- Hearing Protection
- Lead in Construction
- Mercury in Construction
- PCB's
- Respiratory Protection
- Silica
- Thermal Stress
- West Nile Virus
- Rodents and Vermin
- Noise Mitigation Plan

Certain DDC programs, such as Job Order Contracting System (JOCS), may not necessarily require Site Safety Plans. The JOCS contractor will be required to submit a Safety Program. In addition, certain DDC Operating Units may establish program or client-specific safety requirements. The contractor's Site Safety Plan must address such program or client specific safety requirements.

## VII. KICK-OFF MEETINGS/PRE-CONSTRUCTION AND SAFETY REVIEW

As part of the construction kick-off meeting, a Site Safety Plan review will be part of the agenda. A QACS representative will participate in this meeting with the contractor prior to the start of the project for the purpose of:

- A. Reviewing the safety issues detailed in the contract.
- B. Reviewing the Site Safety Plan.
- C. Reviewing any new issues or information that was not previously addressed.
- D. Discussing planned inspections and audits of the site by DDC personnel.

#### VIII. EVALUATION DURING WORK IN PROGRESS

The Contractor's adherence to these Safety Requirements will be monitored throughout the project. This will be accomplished by the following:

- A. Use of a safety checklist by a representative of the Construction Safety Unit or other designated DDC representative or Consultant during regular, unannounced inspections of the job site. Field Exit Conferences will be held with the RE/CPM, Contractor Superintendents or Safety Representatives.
- B. The RE/CPM will continually monitor the safety and environmental performance of the contractor's employees and work methods. Deficiencies shall be brought to the attention of the contractor's representative on site for immediate correction. The DDC representative will maintain a written record of these deficiencies and forward them to the Construction Safety Unit on a weekly basis. Any critical deficiencies shall be immediately reported to QACS phone# (718) 391-1624 or (718) 391-1911.
- C. If the Contractor's safety performance during the project is not up to DDC standards (safety performance measure, accident/incident rate, etc.) the Director-QACS, or designee will meet with the Contractor's safety representative, the DDC project manager, the RE/CPM, or the DDC Environmental Specialist (if environmental issues are involved). The purpose of this meeting is to 1) determine the level of non-compliance; 2) explain and clarify the safety/environmental provisions; 3) agree on a future course of action to correct the deficiencies.

- D. If the deficiencies continue to occur with inadequate attention by the contractor, this shall, among other remedies available, be grounds for default.
- E. The contractor shall inform the Construction Safety Unit and ACCO Insurance and Risk Management Unit of all medical injuries or illnesses that require doctors' treatment resulting from an on-the-job incident within 24 hours of the occurrence. The Construction Safety Unit shall also be immediately informed of all fatalities, catastrophic accidents with more than one employee hospitalized, any injuries to members of the general public and major equipment damage (e.g., property damage, equipment rollovers, loads dropped from crane). QACS shall maintain a record of all contractor injuries and illnesses during the project and provide regular reports to the Agency.
- F. The Construction Safety Unit shall be immediately notified at the start of any NYS-DOL/ NYC-COSH/ OSHA/ EPA inspections. The Director of Quality Assurance & Construction Safety shall maintain a log of all contractor OSHA/EPA inspections and citations during the project.

#### IX. SAFETY PERFORMANCE EVALUATION

The contractor's safety record, including all DDC inspection results, will be considered as part of the Contractor's performance evaluation at the conclusion of the project. Poor safety performance during the course of the project shall be a reason to rate a Contractor unsatisfactory which will be reflected in the City's Vendex system and will be considered for future procurement actions as set forth in the City's Procurement Policy Board Rules.

(NO TEXT ON THIS PAGE)

# CITY OF NEW YORK STANDARD CONSTRUCTION CONTRACT **DECEMBER 2013**

(NO TEXT ON THIS PAGE)

## CITY OF NEW YORK STANDARD CONSTRUCTION CONTRACT

## TABLE OF CONTENTS

CHAPTER I		
THE CONTRAC	CT AND DEFINITIONS	
A DESCRIBA	THE CONTROLOR	
ARTICLE 1.	THE CONTRACT	1
ARTICLE 2.	DEFINITIONS	1
CHAPTER II		
THE WORK AN	ND ITS PERFORMANCE	
ARTICLE 3.	CHARACTER OF THE WORK	4
ARTICLE 4.	MEANS AND METHODS OF CONSTRUCTION	4
ARTICLE 5.	COMPLIANCE WITH LAWS	4
ARTICLE 6.	INSPECTION	9
ARTICLE 7.	PROTECTION OF WORK AND OF PERSONS AND	
	PROPERTY; NOTICES AND INDEMNIFICATION	10
CHAPTER III		
TIME PROVISI	<u>ONS</u>	
ARTICLE 8.	COMMENCEMENT AND PROTECTION OF THE WORK	11
ARTICLE 9.	PROGRESS SCHEDULES	11
ARTICLE 10.	REQUESTS FOR INFORMATION OR APPROVAL	12
ARTICLE 11.	NOTICE OF CONDITIONS CAUSING DELAY AND	
	DOCUMENTATION OF DAMAGES CAUSED BY DELAY	12
ARTICLE 12.	COORDINATION WITH OTHER CONTRACTORS	13
ARTICLE 13.	EXTENSION OF TIME FOR PERFORMANCE	14
ARTICLE 14.	COMPLETION AND FINAL ACCEPTANCE OF THE WORK	16
ARTICLE 15.	LIQUIDATED DAMAGES	17
ARTICLE 16.	OCCUPATION OR USE PRIOR TO COMPLETION	18
CHAPTER IV		
	TS AND ASSIGNMENTS	
ADDICE D 15	CUID CONTERNA CONC	
ARTICLE 17. ARTICLE 18.	SUBCONTRACTS ASSIGNMENTS	18
ARTICLE 18.	A331GINIVEN I 3	20

# CITY OF NEW YORK STANDARD CONSTRUCTION CONTRACT

## TABLE OF CONTENTS

CHAPTER V		
	'S SECURITY AND GUARANTY	
ARTICLE 19.	SECURITY DEPOSIT	20
ARTICLE 20.	PAYMENT GUARANTEE	20
ARTICLE 21.	RETAINED PERCENTAGE	22
ARTICLE 22.	INSURANCE	23
ARTICLE 23.	MONEY RETAINED AGAINST CLAIMS	28
ARTICLE 24.		28
CHAPTER VI		
CHANGES, EXT	TRA WORK AND DOCUMENTATION OF CLAIM	
ARTICLE 25.	CHANGES	29
ARTICLE 26.	METHODS OF PAYMENT FOR OVERRUNS AND	29
	EXTRA WORK	30
ARTICLE 27.	RESOLUTION OF DISPUTES	32
ARTICLE 28.	RECORD KEEPING FOR EXTRA OR DISPUTED WORK	36
ARTICLE 29.	OMITTED WORK	36
ARTICLE 30.	NOTICE AND DOCUMENTATION OF COSTS AND	50
•	DAMAGES; PRODUCTION OF FINANCIAL RECORDS	37
	,	υ,
CITY A DIRECT TITLE		
CHAPTER VII		
	HE RESIDENT ENGINEER, THE ENGINEER	
OK ARCHITEC	T AND THE COMMISSIONER	
ARTICLE 31.	THE RESIDENT ENGINEER	38
ARTICLE 32.	THE ENGINEER OR ARCHITECT OR PROJECT MANAGER	38
ARTICLE 33.	THE COMMISSIONER	39
ARTICLE 34.	NO ESTOPPEL	39
CHAPTER VIII		
LABOR PROVIS	SIONS	
ARTICLE 35.	EMPLOYEES	39
ARTICLE 36.	NO DISCRIMINATION	40
ARTICLE 37.	LABOR LAW REQUIREMENTS	42
ARTICLE 38.	PAYROLL REPORTS	47
ARTICLE 39.	DUST HAZARDS	47

# CITY OF NEW YORK STANDARD CONSTRU CTION CONTRACT

## TABLE OF CONTENTS

CHAPTER IX		
PARTIAL AND	FINAL PAYMENTS	
ARTICLE 40.	CONTRACT PRICE	47
ARTICLE 41.	BID BREAKDOWN ON LUMP SUM	47
ARTICLE 42.	PARTIAL PAYMENTS	48
ARTICLE 43.	PROMPT PAYMENT	48
ARTICLE 44.	SUBSTANTIAL COMPLETION PAYMENT	49
ARTICLE 45.	FINAL PAYMENT	50
ARTICLE 46.	ACCEPTANCE OF FINAL PAYMENT	50 51
ARTICLE 47.	APPROVAL BY PUBLIC DESIGN COMMISSION	51 51
	The second secon	51
CHAPTER X		
CONTRACTO	R'S DEFAULT	
A DOTOT E 40	COLD MICOLONIED IN DIVINE THE THE	
ARTICLE 48.	COMMISSIONER'S RIGHT TO DECLARE CONTRACTOR	
A DELCT E 40	IN DEFAULT	52
ARTICLE 49.	EXERCISE OF THE RIGHT TO DECLARE DEFAULT	53
ARTICLE 50.	QUITTING THE SITE	53
ARTICLE 51.	COMPLETION OF THE WORK	53
ARTICLE 52.	PARTIAL DEFAULT	53
ARTICLE 53.	PERFORMANCE OF UNCOMPLETED WORK	54
ARTICLE 54.	OTHER REMEDIES	54
CHAPTER XI		
MISCELLANE	<u>OUS PROVISIONS</u>	
ARTICLE 55.	CONTRACTORIC MADRANTING	
ARTICLE 56.	CONTRACTOR'S WARRANTIES	54
ARTICLE 50.	CLAIMS AND ACTIONS THEREON	55
ARTICLE 57.	INFRINGEMENT	55
ARTICLE 50.	NO CLAIM AGAINST OFFICERS, AGENTS OR	
A DOTTOT TO SO	EMPLOYEES  SEPRICES OF NOTICES	55
ARTICLE 59. ARTICLE 60.	SERVICES OF NOTICES	55
ARTICLE OU.	UNLAWFUL PROVISIONS DEEMED STRICKEN	
A DOWN CHE CO	FROM CONTRACT	56
ARTICLE 61.	ALL LEGAL PROVISIONS DEEMED INCLUDED	56
ARTICLE 62.	TAX EXEMPTION	56
ARTICLE 63.	INVESTIGATION(S) CLAUSE	57
ARTICLE 64.	TERMINATION BY THE CITY	59
ARTICLE 65.	CHOICE OF LAW, CONSENT TO JURISDICTION	
	AND VENUE	62

iii

# CITY OF NEW YORK STANDARD CONSTRUCTION CONTRACT

## TABLE OF CONTENTS

# CHAPTER XI (CONT'D) MISCELLANEOUS PROVISIONS

ARTICLE 66.	PARTICIPATION IN AN INTERNATIONAL BOYCOTT	74
ARTICLE 67.	LOCALLY BASED ENTERPRISE PROGRAM	74
ARTICLE 68.	ANTITRUST	75
ARTICLE 69.	MACBRIDE PRINCIPLES PROVISIONS	75 75
ARTICLE 70	ELECTRONIC FILING/NYC DEVELOPMENT HUB	73 77
ARTICLE 71.	PROHIBITION OF TROPICAL HARDWOODS	77
ARTICLE 72.	CONFLICTS OF INTEREST	77 78
ARTICLE 73.	MERGER CLAUSE	78 78
ARTICLE 74.	STATEMENT OF WORK	78
ARTICLE 75.	COMPENSATION TO BE PAID TO CONTRACTOR	78 78
ARTICLE 76:	ELECTRONIC FUNDS TRANSFER	78
ARTICLE 77:	RECORDS RETENTION	70 79
ARTICLE 78:	PARTICIPATION BY MINORITY-OWNED AND WOMEN-	
	BUSINESS ENTERPRISES IN CITY PROCUREMENT	79
	THE TAXOURENTE	19
SIGNATURES		87
<b>ACKNOWLED</b>	GMENT BY CORPORATION	88
<b>ACKNOWLED</b>	GMENT BY PARTNERSHIP	88
<b>ACKNOWLED</b>	GMENT BY INDIVIDUAL	88
<b>ACKNOWLED</b>	GMENT BY COMMISSIONER	88
AUTHORITY	·	89
COMPTROLLE	CR'S CERTIFICATE	90
MAYOR'S CER	TIFICATE	91
PERFORMANC	CE BOND #1	92
PERFORMANO	E BOND #2	92
PAYMENT BOI	ND	100
		100

#### WITNESSETH:

The parties, in consideration of the mutual agreements contained herein, agree as follows:

## CHAPTER I THE CONTRACT AND DEFINITIONS

#### **ARTICLE 1. THE CONTRACT**

- 1.1 Except for titles, subtitles, headings, running headlines, tables of contents and indices (all of which are printed herein merely for convenience), the following, except for such portions thereof as may be specifically excluded, shall be deemed to be part of this Contract:
  - 1.1.1 All provisions required by law to be inserted in this Contract, whether actually inserted or not;
  - 1.1.2 The Contract Drawings and Specifications;
  - 1.1.3 The General Conditions and Special Conditions, if any;
  - 1.1.4 The Contract;
  - 1.1.5 The Information for Bidders; Request for Proposals; Notice of Solicitation and Proposal For Bids; Bid or Proposal, and, if used, the Bid Booklet;
  - 1.1.6 All Addenda issued prior to the receipt of the bids; the Notice of Award; Performance and Payment Bonds, if required; and the Notice to Proceed or the Order to Work.
- 1.2 Should any conflict occur in or between the Drawings and Specifications, the Contractor shall be deemed to have estimated the most expensive way of doing the Work, unless the Contractor shall have asked for and obtained a decision in writing from the Commissioner of the Agency that is entering into this Contract, before the submission of its bid, as to what shall govern.

#### **ARTICLE 2. DEFINITIONS**

- 2.1 The following words and expressions, or pronouns used in their stead, shall, wherever they appear in this Contract, be construed as follows, unless a different meaning is clear from the context:
  - 2.1.1 "Addendum" or "Addenda" shall mean the additional Contract provisions and/or technical clarifications issued in writing by the Commissioner prior to the receipt of bids.
  - 2.1.2 "Agency" shall mean a city, county, borough or other office, position, department, division, bureau, board or commission, or a corporation, institution or agency of government, the expenses of which are paid in whole or in part from the City treasury.
  - 2.1.3 "Agency Chief Contracting Officer" (ACCO) shall mean a person delegated authority by the Commissioner to organize and supervise the procurement activity of subordinate Agency staff in conjunction with the CCPO, or his/her duly authorized representative.

- 2.1.4 "Allowance" shall mean a sum of money which the Agency may include in the total amount of the Contract for such specific contingencies as the Agency believes may be necessary to complete the Work, e.g., lead or asbestos remediation, and for which the Contractor will be paid on the basis of stipulated unit prices or a formula set forth in the Contract or negotiated between the parties provided, however, that if the Contractor is not directed to use the Allowance, the Contractor shall have no right to such money and it shall be deducted from the total amount of the Contract.
- 2.1.5 "City" shall mean the City of New York.
- 2.1.6 "City Chief Procurement Officer" (CCPO) shall mean a person delegated authority by the Mayor to coordinate and oversee the procurement activity of Mayoral agency staff, including the ACCO and any offices which have oversight responsibility for the procurement of construction, or his/her duly authorized representative.
- 2.1.7 "Commissioner" shall mean the head of the Agency that has entered into this Contract, or his/her duly authorized representative.
- 2.1.8 "Comptroller" shall mean the Comptroller of the City of New York.
- 2.1.9 "Contract" or "Contract Documents" shall mean each of the various parts of the contract referred to in Article 1 hereof, both as a whole and severally.
- 2.1.10 "Contract Drawings" shall mean only those drawings specifically entitled as such and listed in the Specifications or in any Addendum, or any drawings furnished by the Commissioner, pertaining or supplemental thereto.
- 2.1.11 "Contract Work" shall mean everything required to be furnished and done by the Contractor by any one or more of the parts of the Contract referred to in Article 1, except Extra Work as hereinafter defined.
- 2.1.12 "Contractor" shall mean the entity which executed this Contract, whether a corporation, firm, partnership, joint venture, individual, or any combination thereof, and its, their, his/her successors, personal representatives, executors, administrators, and assigns, and any person, firm, partnership, joint venture, individual, or corporation which shall at any time be substituted in the place of the Contractor under this Contract.
- 2.1.13 "Days" shall mean calendar days, except where otherwise specified.
- 2.1.14 "Engineer" or "Architect" or "Project Manager" shall mean the person so designated in writing by the Commissioner in the Notice to Proceed or the Order to Work to act as such in relation to this Contract, including a private Architect or Engineer or Project Manager, as the case may be. Subject to written approval by the Commissioner, the Engineer, Architect or Project Manager may designate an authorized representative.
- 2.1.15 "Engineering Audit Officer" (EAO) shall mean the person so designated by the Commissioner to perform responsible auditing functions hereunder.
- 2.1.16 "Extra Work" shall mean Work other than that required by the Contract at the time of award which is authorized by the Commissioner pursuant to Chapter VI of this Contract.
- 2.1.17 "Federal-Aid Contract" shall mean a contract in which the United States (federal) Government provides financial funding as so designated in the Information for Bidders.

- 2.1.18 "Final Acceptance" shall mean final written acceptance of all the Work by the Commissioner, a copy of which shall be sent to the Contractor.
- 2.1.19 "Final Approved Punch List" shall mean a list, approved pursuant to Article 14.2.2, specifying those items of Work to be completed by the Contractor after Substantial Completion and dates for the completion of each item of Work.
- 2.1.20 "Law" or "Laws" shall mean the Constitution of the State of New York, the New York City Charter, the New York City Administrative Code, a statute of the United States or of the State of New York, a local law of the City of New York, any ordinance, rule or regulation having the force of law, or common law.
- 2.1.21 "Materialman" shall mean any corporation, firm, partnership, joint venture, or individual, other than employees of the Contractor, who or which contracts with the Contractor or any Subcontractor, to fabricate or deliver, or who actually fabricates or delivers, plant, materials or equipment to be incorporated in the Work.
- 2.1.22 "Means and Methods of Construction" shall mean the labor, materials, temporary structures, tools, plant, and construction equipment, and the manner and time of their use, necessary to accomplish the result intended by this Contract.
- 2.1.23 "Notice to Proceed" or "Order to Work" shall mean the written notice issued by the Commissioner specifying the time for commencement of the Work and the Engineer, Architect or Project Manager.
- 2.1.24 "Other Contractor(s)" shall mean any contractor (other than the entity which executed this Contract or its Subcontractors) who or which has a contract with the City for work on or adjacent to the building or Site of the Work.
- 2.1.25 "Payroll Taxes" shall mean State Unemployment Insurance (SUI), Federal Unemployment Insurance (FUI), and payments pursuant to the Federal Insurance Contributions Act (FICA).
- 2.1.26 "Project" shall mean the public improvement to which this Contract relates.
- 2.1.27 "Procurement Policy Board" (PPB) shall mean the Agency of the City of New York whose function is to establish comprehensive and consistent procurement policies and rules which shall have broad application throughout the City.
- 2.1.28 "Required Quantity" in a unit price Contract shall mean the actual quantity of any item of Work or materials which is required to be performed or furnished in order to comply with the Contract.
- 2.1.29 "Resident Engineer" shall mean the representative of the Commissioner duly designated by the Commissioner to be his/her representative at the site of the Work.
- 2.1.30 "Site" shall mean the area upon or in which the Contractor's operations are carried on, and such other areas adjacent thereto as may be designated as such by the Engineer.
- 2.1.31 "Small Tools" shall mean items that are ordinarily required for a worker's job function, including but not limited to, equipment that ordinarily has no licensing, insurance

or substantive storage costs associated with it; such as circular and chain saws, impact drills, threaders, benders, wrenches, socket tools, etc.

- 2.1.32 "Specifications" shall mean all of the directions, requirements, and standards of performance applying to the Work as hereinafter detailed and designated under the Specifications.
- 2.1.33 "Subcontractor" shall mean any person, firm or corporation, other than employees of the Contractor, who or which contracts with the Contractor or with its subcontractors to furnish, or actually furnishes labor, or labor and materials, or labor and equipment, or superintendence, supervision and/or management at the Site. Wherever the word Subcontractor appears, it shall also mean sub-Subcontractor.
- 2.1.34 "Substantial Completion" shall mean the written determination by the Engineer that the Work required under this Contract is substantially, but not entirely, complete and the approval of the Final Approved Punch List.
- 2.1.35 "Work" shall mean all services required to complete the Project in accordance with the Contract Documents, including without limitation, labor, material, superintendence, management, administration, equipment, and incidentals, and obtaining any and all permits, certifications and licenses as may be necessary and required to complete the Work, and shall include both Contract Work and Extra Work.

## CHAPTER II THE WORK AND ITS PERFORMANCE

#### ARTICLE 3. CHARACTER OF THE WORK

3.1 Unless otherwise expressly provided in the Contract Drawings, Specifications, and Addenda, the Work shall be performed in accordance with the best modern practice, utilizing, unless otherwise specified in writing, new and unused materials of standard first grade quality and workmanship and design of the highest quality, to the satisfaction of the Commissioner.

#### **ARTICLE 4. MEANS AND METHODS OF CONSTRUCTION**

- 4.1 Unless otherwise expressly provided in the Contract Drawings, Specifications, and Addenda, the Means and Methods of Construction shall be such as the Contractor may choose; subject, however, to the Engineer's right to reject the Means and Methods of Construction proposed by the Contractor which in the opinion of the Engineer:
  - 4.1.1 Will constitute or create a hazard to the Work, or to persons or property; or
  - 4.1.2 Will not produce finished Work in accordance with the terms of the Contract; or
  - 4.1.3 Will be detrimental to the overall progress of the **Project**.
- 4.2 The Engineer's approval of the Contractor's Means and Methods of Construction, or his/her failure to exercise his/her right to reject such means or methods, shall not relieve the Contractor of its obligation to complete the Work as provided in this Contract; nor shall the exercise of such right to reject create a cause of action for damages.

#### ARTICLE 5. COMPLIANCE WITH LAWS

- 5.1 The Contractor shall comply with all Laws applicable to this Contract and to the Work to be done hereunder.
- 5.2 Procurement Policy Board Rules: This Contract is subject to the Rules of the PPB ("PPB Rules") in effect at the time of the bid opening for this Contract. In the event of a conflict between the PPB Rules and a provision of this Contract, the PPB Rules shall take precedence.
  - 5.3 Noise Control Code provisions.
    - 5.3.1 In accordance with the provisions of Section 24-216(b) of the Administrative Code of the City ("Administrative Code"), Noise Abatement Contract Compliance, devices and activities which will be operated, conducted, constructed or manufactured pursuant to this Contract and which are subject to the provisions of the City Noise Control Code shall be operated, conducted, constructed, or manufactured without causing a violation of the Administrative Code. Such devices and activities shall incorporate advances in the art of noise control development for the kind and level of noise emitted or produced by such devices and activities, in accordance with regulations issued by the Commissioner of the City Department of Environmental Protection.
    - 5.3.2 The Contractor agrees to comply with Section 24-219 of the Administrative Code and implementing rules codified at 15 Rules of the City of New York ("RCNY") Section 28-100 et seq. In accordance with such provisions, the Contractor, if the Contractor is the responsible party under such regulations, shall prepare and post a Construction Noise Mitigation Plan at each Site, in which the Contractor shall certify that all construction tools and equipment have been maintained so that they operate at normal manufacturers operating specifications. If the Contractor cannot make this certification, it must have in place an Alternative Noise Mitigation Plan approved by the City Department of Environmental Protection. In addition, the Contractor's certified Construction Noise Mitigation Plan is subject inspection by the City Department of Environmental Protection in accordance with Section 28-101 of Title 15 of RCNY. No Contract Work may take place at a Site unless there is a Construction Noise Mitigation Plan or approved Alternative Noise Mitigation Plan in place. In addition, the Contractor shall create and implement a noise mitigation training program. Failure to comply with these requirements may result in fines and other penalties pursuant to the applicable provisions of the Administrative Code and RCNY.
- 5.4 Ultra Low Sulfur Diesel Fuel: In accordance with the provisions of Section 24-163.3 of the Administrative Code, the Contractor specifically agrees as follows:
  - 5.4.1 Definitions. For purposes of this Article 5.4, the following definitions apply:
    - 5.4.1(a) "Contractor" means any person or entity that enters into a Public Works Contract with a **City Agency**, or any person or entity that enters into an agreement with such person or entity, to perform work or provide labor or services related to such Public Works Contract.
    - 5.4.1(b) "Motor Vehicle" means any self-propelled vehicle designed for transporting persons or property on a street or highway.
    - 5.4.1(c) "Nonroad Engine" means an internal combustion engine (including the fuel system) that is not used in a Motor Vehicle or a vehicle used solely for competition, or that is not subject to standards promulgated under Section 7411 or Section 7521 of

- Title 42 of the United States Code, except that this term shall apply to internal combustion engines used to power generators, compressors or similar equipment used in any construction program or project.
- 5.4.1(d) "Nonroad Vehicle" means a vehicle that is powered by a Nonroad Engine, fifty (50) horsepower and greater, and that is not a Motor Vehicle or a vehicle used solely for competition, which shall include, but not be limited to, excavators, backhoes, cranes, compressors, generators, bulldozers, and similar equipment, except that this term shall not apply to horticultural maintenance vehicles used for landscaping purposes that are powered by a Nonroad Engine of sixty-five (65) horsepower or less and that are not used in any construction program or project.
- 5.4.1(e) "Public Works Contract" means a contract with a City Agency for a construction program or project involving the construction, demolition, restoration, rehabilitation, repair, renovation, or abatement of any building, structure, tunnel, excavation, roadway, park or bridge; a contract with a City Agency for the preparation for any construction program or project involving the construction, demolition, restoration, rehabilitation, repair, renovation, or abatement of any building, structure, tunnel, excavation, roadway, park or bridge; or a contract with a City Agency for any final work involved in the completion of any construction program or project involving the construction, demolition, restoration, rehabilitation, repair, renovation, or abatement of any building, structure, tunnel, excavation, roadway, park or bridge.
- 5.4.1(f) "Ultra Low Sulfur Diesel Fuel" means diesel fuel that has a sulfur content of no more than fifteen parts per million (15 ppm).

#### 5.4.2 Ultra Low Sulfur Diesel Fuel

- 5.4.2(a) All Contractors shall use Ultra Low Sulfur Diesel Fuel in diesel-powered Nonroad Vehicles in the performance of this Contract.
- 5.4.2(b) Notwithstanding the requirements of Article 5.4.2(a), Contractors may use diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm) to fulfill the requirements of this Article 5.4.2, where the Commissioner of the City Department of Environmental Protection ("DEP Commissioner") has issued a determination that a sufficient quantity of Ultra Low Sulfur Diesel Fuel is not available to meet the needs of Agencies and Contractors. Any such determination shall expire after six (6) months unless renewed.
- 5.4.2(c) Contractors shall not be required to comply with this Article 5.4.2 where the City Agency letting this Contract makes a written finding, which is approved, in writing, by the DEP Commissioner, that a sufficient quantity of Ultra Low Sulfur Diesel Fuel, or diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm) is not available to meet the requirements of Section 24-163.3 of the Administrative Code, provided that such Contractor in its fulfillment of the requirements of this Contract, to the extent practicable, shall use whatever quantity of Ultra Low Sulfur Diesel Fuel or diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm) is available. Any finding made pursuant to this Article 5.4.2(c) shall expire after sixty (60) Days, at which time the requirements of this Article 5.4.2 shall be in full force and effect unless the City Agency renews the finding in writing and such renewal is approved by the DEP Commissioner.

- 5.4.2(d) Contractors may check on determinations and approvals issued by the DEP Commissioner pursuant to Section 24-163.3 of the Administrative Code, if any, at <a href="https://www.dep.nyc.gov">www.dep.nyc.gov</a> or by contacting the City Agency letting this Contract.
- 5.4.2(e) The requirements of this Article 5.4.2 do not apply where they are precluded by federal or State funding requirements or where the **Contract** is an emergency procurement.

#### 5.4.3 Best Available Technology

- 5.4.3(a) All Contractors shall utilize the best available technology for reducing the emission of pollutants for diesel-powered Nonroad Vehicles in the performance of this Contract. For determinations of best available technology for each type of diesel-powered Nonroad Vehicle, Contractors shall comply with the regulations of the City Department of Environmental Protection, as and when adopted, Chapter 14 of Title 15 of the Rules of the City of New York (RCNY). The Contractor shall fully document all steps in the best available technology selection process and shall furnish such documentation to the City Agency or the DEP Commissioner upon request. The Contractor shall retain all documentation generated in the best available technology selection process for as long as the selected best available technology is in use.
- 5.4.3(b) No Contractor shall be required to replace best available technology for reducing the emission of pollutants or other authorized technology utilized for a diesel-powered Nonroad Vehicle in accordance with the provisions of this Article 5.4.3 within three (3) years of having first utilized such technology for such vehicle.
- 5.4.3(c) This Article 5.4.3 shall not apply to any vehicle used to satisfy the requirements of a specific Public Works Contract for fewer than twenty (20) **Days**.
- 5.4.3(d) The Contractor shall not be required to comply with this Article 5.4.3 with respect to a diesel-powered Nonroad Vehicle under the following circumstances:
  - 5.4.3(d)(i) Where the City Agency makes a written finding, which is approved, in writing, by the DEP Commissioner, that the best available technology for reducing the emission of pollutants as required by this Article 5.4.3 is unavailable for such vehicle, the Contractor shall use whatever technology for reducing the emission of pollutants, if any, is available and appropriate for such vehicle.
  - 5.4.3(d)(ii) Where the DEP Commissioner has issued a written waiver based upon the Contractor having demonstrated to the DEP Commissioner that the use of the best available technology for reducing the emission of pollutants might endanger the operator of such vehicle or those working near such vehicle, due to engine malfunction, the Contractor shall use whatever technology for reducing the emission of pollutants, if any, is available and appropriate for such vehicle, which would not endanger the operator of such vehicle or those working near such vehicle.
  - 5.4.3(d)(iii) In determining which technology to use for the purposes of Articles 5.4.3(d)(i) and 5.4.3(d)(ii) above, the **Contractor** shall primarily consider the reduction in emissions of particulate matter and secondarily consider the reduction in emissions of nitrogen oxides associated with the use of such

technology, which shall in no event result in an increase in the emissions of either such pollutant.

- 5.4.3(d)(iv) The Contractor shall submit requests for a finding or a waiver pursuant to this Article 5.4.3(d) in writing to the DEP Commissioner, with a copy to the ACCO of the City Agency letting this Contract. Any finding or waiver made or issued pursuant to Articles 5.4.3(d)(i) and 5.4.3(d)(ii) above shall expire after one hundred eighty (180) Days, at which time the requirements of Article 5.4.3(a) shall be in full force and effect unless the City Agency renews the finding, in writing, and the DEP Commissioner approves such finding, in writing, or the DEP Commissioner renews the waiver, in writing.
- 5.4.3(e) The requirements of this Article 5.4.3 do not apply where they are precluded by federal or State funding requirements or where the **Contract** is an emergency procurement.
- 5.4.4 Section 24-163 of the Administrative Code. The **Contractor** shall comply with Section 24-163 of the Administrative Code related to the idling of the engines of motor vehicles while parking.

#### 5.4.5 Compliance

- 5.4.5(a) The Contractor's compliance with Article 5.4 may be independently monitored. If it is determined that the Contractor has failed to comply with any provision of Article 5.4, any costs associated with any independent monitoring incurred by the City shall be reimbursed by the Contractor.
- 5.4.5(b) Any Contractor who violates any provision of Article 5.4, except as provided in Article 5.4.5(c) below, shall be liable for a civil penalty between the amounts of one thousand (\$1,000) and ten thousand (\$10,000) dollars, in addition to twice the amount of money saved by such Contractor for failure to comply with Article 5.4.
- 5.4.5(c) No Contractor shall make a false claim with respect to the provisions of Article 5.4 to a City Agency. Where a Contractor has been found to have done so, such Contractor shall be liable for a civil penalty of twenty thousand (\$20,000) dollars, in addition to twice the amount of money saved by such Contractor in association with having made such false claim.

#### 5.4.6 Reporting

- 5.4.6(a) For all Public Works Contracts covered by this Article 5.4, the Contractor shall report to the City Agency the following information:
  - 5.4.6(a)(i) The total number of diesel-powered Nonroad Vehicles used to fulfill the requirements of this Public Works Contract;
  - 5.4.6(a)(ii) The number of such Nonroad Vehicles that were powered by Ultra Low Sulfur Diesel Fuel;
  - 5.4.6(a)(iii) The number of such Nonroad Vehicles that utilized the best available technology for reducing the emission of pollutants, including a breakdown by vehicle model and the type of technology;

- 5.4.6(a)(iv) The number of such Nonroad Vehicles that utilized such other authorized technology in accordance with Article 5.4.3, including a breakdown by vehicle model and the type of technology used for each such vehicle:
  - 5.4.6(a)(v) The locations where such Nonroad Vehicles were used; and
- 5.4.6(a)(vi) Where a determination is in effect pursuant to Article 5.4.2(b) or 5.4.2(c), detailed information concerning the **Contractor's** efforts to obtain Ultra Low Sulfur Diesel Fuel or diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm).
- 5.4.6(b) The Contractor shall submit the information required by Article 5.4.6(a) at the completion of Work under the Public Works Contract and on a yearly basis no later than August 1 throughout the term of the Public Works Contract. The yearly report shall cover Work performed during the preceding fiscal year (July 1 June 30).
- 5.5 Ultra Low Sulfur Diesel Fuel. In accordance with the Coordinated Construction Act for Lower Manhattan, as amended:
  - 5.5.1 Definitions. For purposes of this Article 5.5, the following definitions apply:
    - 5.5.1(a) "Lower Manhattan" means the area to the south of and within the following lines: a line beginning at a point where the United States pierhead line in the Hudson River as it exists now or may be extended would intersect with the southerly line of West Houston Street in the Borough of Manhattan extended, thence easterly along the southerly side of West Houston Street to the southerly side of Houston Street, thence easterly along the southerly side of Houston Street to the southerly side of East Houston Street, thence northeasterly along the southerly side of East Houston Street to the point where it would intersect with the United States pierhead line in the East River as it exists now or may be extended, including tax lots within or immediately adjacent thereto.
    - 5.5.1(b) "Lower Manhattan Redevelopment Project" means any project in Lower Manhattan that is funded in whole or in part with federal or State funding, or any project intended to improve transportation between Lower Manhattan and the two air terminals in the City known as LaGuardia Airport and John F. Kennedy International Airport, or between Lower Manhattan and the air terminal in Newark known as Newark Liberty International Airport, and that is funded in whole or in part with federal funding.
    - 5.5.1(c) "Nonroad Engine" means an internal combustion engine (including the fuel system) that is not used in a Motor Vehicle or a vehicle used solely for competition, or that is not subject to standards promulgated under Section 7411 or Section 7521 of Title 42 of the United States Code, except that this term shall apply to internal combustion engines used to power generators, compressors or similar equipment used in any construction program or project.
    - 5.5.1(d) "Nonroad Vehicle" means a vehicle that is powered by a Nonroad Engine, fifty (50) horsepower (HP) and greater, and that is not a Motor Vehicle or a vehicle used solely for competition, which shall include, but not be limited to, excavators, backhoes, cranes, compressors, generators, bulldozers, and similar equipment, except

that this terms shall not apply to horticultural maintenance vehicles used for landscaping purposes that are powered by a Nonroad Engine of sixty-five (65) HP or less and that are not used in any construction program or project.

- 5.5.1(e) "Ultra Low Sulfur Diesel Fuel" means diesel fuel that has a sulfur content of no more than fifteen parts per million (15 ppm).
- 5.5.2 Requirements. Contractors and Subcontractors are required to use only Ultra Low Sulfur Diesel Fuel to power the diesel-powered Nonroad Vehicles with engine HP rating of fifty (50) HP and above used on a Lower Manhattan Redevelopment Project and, where practicable, to reduce the emission of pollutants by retrofitting such Nonroad Vehicles with oxidation catalysts, particulate filters, or technology that achieves lowest particulate matter emissions.
- 5.6 Pesticides. In accordance with Section 17-1209 of the Administrative Code, to the extent that the Contractor or any Subcontractor applies pesticides to any property owned or leased by the City, the Contractor, and any Subcontractor shall comply with Chapter 12 of the Administrative Code.
- 5.7 Waste Treatment, Storage, and Disposal Facilities and Transporters. In connection with the Work, the Contractor and any Subcontractor shall use only those waste treatment, storage, and disposal facilities and waste transporters that possess the requisite license, permit or other governmental approval necessary to treat, store, dispose, or transport the waste, materials or hazardous substances.
- 5.8 Environmentally Preferable Purchasing. The Contractor shall ensure that products purchased or leased by the Contractor or any Subcontractor for the Work that are not specified by the City or are submitted as equivalents to a product specified by the City comply with the requirements of the New York City Environmentally Preferable Purchasing Program contained in Chapter 11 of Title 43 of the RCNY, pursuant to Chapter 3 of Title 6 of the Administrative Code.

#### ARTICLE 6. INSPECTION

- 6.1 During the progress of the Work and up to the date of Final Acceptance, the Contractor shall at all times afford the representatives of the City every reasonable, safe, and proper facility for inspecting all Work done or being done at the Site and also for inspecting the manufacture or preparation of materials and equipment at the place of such manufacture or preparation.
- 6.2 The Contractor's obligation hereunder shall include the uncovering or taking down of finished Work and its restoration thereafter; provided, however, that the order to uncover, take down and restore shall be in writing, and further provided that if Work thus exposed proves satisfactory, and if the Contractor has complied with Article 6.1, such uncovering or taking down and restoration shall be considered an item of Extra Work to be paid for in accordance with the provisions of Article 26. If the Work thus exposed proves unsatisfactory, the City has no obligation to compensate the Contractor for the uncovering, taking down or restoration.
- 6.3 Inspection and approval by the Commissioner, the Engineer, Project Manager, or Resident Engineer, of finished Work or of Work being performed, or of materials and equipment at the place of manufacture or preparation, shall not relieve the Contractor of its obligation to perform the Work in strict accordance with the Contract. Finished or unfinished Work not found to be in strict accordance with the Contract shall be replaced as directed by the Engineer, even though such Work may have been previously approved and paid for. Such corrective Work is Contract Work and shall not be deemed Extra Work.

6.4 Rejected Work and materials shall be promptly taken down and removed from the Site, which must at all times be kept in a reasonably clean and neat condition.

# ARTICLE 7. PROTECTION OF WORK AND OF PERSONS AND PROPERTY; NOTICES AND INDEMNIFICATION

- 7.1 During the performance of the Work and up to the date of Final Acceptance, the Contractor shall be under an absolute obligation to protect the finished and unfinished Work against any damage, loss, injury, theft and/or vandalism and in the event of such damage, loss, injury, theft and/or vandalism, it shall promptly replace and/or repair such Work at the Contractor's sole cost and expense, as directed by the Resident Engineer. The obligation to deliver finished Work in strict accordance with the Contract prior to Final Acceptance shall be absolute and shall not be affected by the Resident Engineer's approval of, or failure to prohibit, the Means and Methods of Construction used by the Contractor.
- 7.2 During the performance of the Work and up to the date of Final Acceptance, the Contractor shall take all reasonable precautions to protect all persons and the property of the City and of others from damage, loss or injury resulting from the Contractor's, and/or its Subcontractors' operations under this Contract. The Contractor's obligation to protect shall include the duty to provide, place or replace, and adequately maintain at or about the Site suitable and sufficient protection such as lights, barricades, and enclosures.
- 7.3 The Contractor shall comply with the notification requirements set forth below in the event of any loss, damage or injury to Work, persons or property, or any accidents arising out of the operations of the Contractor and/or its Subcontractors under this Contract.
  - 7.3.1 The Contractor shall make a full and complete report in writing to the Resident Engineer within three (3) Days after the occurrence.
  - 7.3.2 The Contractor shall also send written notice of any such event to all insurance carriers that issued potentially responsive policies (including commercial general liability insurance carriers for events relating to the Contractor's own employees) no later than twenty (20) days after such event and again no later than twenty (20) days after the initiation of any claim and/or action resulting therefrom. Such notice shall contain the following information: the number of the insurance policy, the name of the Named Insured, the date and location of the incident, and the identity of the persons injured or property damaged. For any policy on which the City and/or the Engineer, Architect, or Project Manager are Additional Insureds, such notice shall expressly specify that "this notice is being given on behalf of the City of New York as Additional Insured, such other Additional Insureds, as well as the Named Insured."
    - 7.3.2(a) Whenever such notice is sent under a policy on which the City is an Additional Insured, the Contractor shall provide copies of the notice to the Comptroller, the Commissioner and the City Corporation Counsel. The copy to the Comptroller shall be sent to the Insurance Unit, NYC Comptroller's Office, 1 Centre Street Room 1222, New York, New York, 10007. The copy to the Commissioner shall be sent to the address set forth in Schedule A of the General Conditions. The copy to the City Corporation Counsel shall be sent to Insurance Claims Specialist, Affirmative Litigation Division, New York City Law Department, 100 Church Street, New York, New York 10007.

- 7.3.2(b) If the Contractor fails to provide any of the foregoing notices to any appropriate insurance carrier(s) in a timely and complete manner, the Contractor shall indemnify the City for all losses, judgments, settlements, and expenses, including reasonable attorneys' fees, arising from an insurer's disclaimer of coverage citing late notice by or on behalf of the City.
- 7.4 To the fullest extent permitted by law, the Contractor shall defend, indemnify, and hold the City, its employees, and officials (the "Indemnitees") harmless against any and all claims (including but not limited to claims asserted by any employee of the Contractor and/or its Subcontractors) and costs and expenses of whatever kind (including but not limited to payment or reimbursement of attorneys' fees and disbursements) allegedly arising out of or in any way related to the operations of the Contractor and/or its Subcontractors in the performance of this Contract or from the Contractor's and/or its Subcontractors' failure to comply with any of the provisions of this Contract or of the Law. Such costs and expenses shall include all those incurred in defending the underlying claim and those incurred in connection with the enforcement of this Article 7.4 by way of cross-claim, third-party claim, declaratory action or otherwise. The parties expressly agree that the indemnification obligation hereunder contemplates (1) full indemnity in the event of liability imposed against the Indemnitees without negligence and solely by reason of statute, operation of Law or otherwise; and (2) partial indemnity in the event of any actual negligence on the part of the Indemnitees either causing or contributing to the underlying claim (in which case, indemnification will be limited to any liability imposed over and above that percentage attributable to actual fault whether by statute, by operation of Law, or otherwise). Where partial indemnity is provided hereunder, all costs and expenses shall be indemnified on a pro rata basis.
  - 7.4.1 Indemnification under Article 7.4 or any other provision of the **Contract** shall operate whether or not **Contractor** or its **Subcontractors** have placed and maintained the insurance specified under Article 22.
- 7.5 The provisions of this Article 7 shall not be deemed to create any new right of action in favor of third parties against the **Contractor** or the **City**.

## CHAPTER III TIME PROVISIONS

#### ARTICLE 8. COMMENCEMENT AND PROSECUTION OF THE WORK

8.1 The Contractor shall commence the Work on the date specified in the Notice to Proceed or the Order to Work. The time for performance of the Work under the Contract shall be computed from the date specified in the Notice to Proceed or the Order to Work. TIME BEING OF THE ESSENCE to the City, the Contractor shall thereafter prosecute the Work diligently, using such Means and Methods of Construction as are in accord with Article 4 herein and as will assure its completion not later than the date specified in this Contract, or on the date to which the time for completion may be extended.

#### **ARTICLE 9. PROGRESS SCHEDULES**

9.1 To enable the **Work** to be performed in an orderly and expeditious manner, the **Contractor**, within fifteen (15) **Days** after the **Notice to Proceed** or **Order to Work**, unless otherwise directed by the **Engineer**, shall submit to the **Engineer** a proposed progress schedule based on the Critical Path Method in the form of a bar graph or in such other form as specified by the **Engineer**, and monthly cash flow requirements, showing:

- 9.1.1 The anticipated time of commencement and completion of each of the various operations to be performed under this **Contract**; and
- 9.1.2 The sequence and interrelation of each of these operations with the others and with those of other related contracts; and
- 9.1.3 The estimated time required for fabrication or delivery, or both, of all materials and equipment required for the **Work**, including the anticipated time for obtaining required approvals pursuant to Article 10; and
- 9.1.4 The estimated amount in dollars the Contractor will claim on a monthly basis.
- 9.2 The proposed schedule shall be revised as directed by the **Engineer**, until finally approved by the **Engineer**, and after such approval, subject to the provisions of Article 11, shall be strictly adhered to by the **Contractor**.
- 9.3 If the Contractor shall fail to adhere to the approved progress schedule, or to the schedule as revised pursuant to Article 11, it shall promptly adopt such other or additional Means and Methods of Construction, at its sole cost and expense, as will make up for the time lost and will assure completion in accordance with the approved progress schedule. The approval by the City of a progress schedule which is shorter than the time allotted under the Contract shall not create any liability for the City if the approved progress schedule is not met.
- 9.4 The Contractor will not receive any payments until the proposed progress schedule is submitted.

#### ARTICLE 10. REQUESTS FOR INFORMATION OR APPROVAL

- 10.1 From time to time as the Work progresses and in the sequence indicated by the approved progress schedule, the Contractor shall submit to the Engineer a specific request in writing for each item of information or approval required by the Contractor. These requests shall state the latest date upon which the information or approval is actually required by the Contractor, and shall be submitted in a reasonable time in advance thereof to provide the Engineer a sufficient time to act upon such submissions, or any necessary re-submissions thereof.
- 10.2 The Contractor shall not have any right to an extension of time on account of delays due to the Contractor's failure to submit requests for the required information or the required approval in accordance with the above requirements.

# ARTICLE 11. NOTICE OF CONDITIONS CAUSING DELAY AND DOCUMENTATION OF DAMAGES CAUSED BY DELAY

- 11.1 After the commencement of any condition which is causing or may cause a delay in completion of the **Work**, including conditions for which the **Contractor** may be entitled to an extension of time, the following notifications and submittals are required:
  - 11.1.1 Within seven (7) **Days** after the commencement of such condition, the **Contractor** must notify the **Engineer** in writing of the existence, nature and effect of such condition upon the approved progress schedule and the **Work**, and must state why and in what respects, if any, the condition is causing or may cause a delay.

- 11.1.2 If the Contractor shall claim to be sustaining damages for delay as provided for in this Article 11, within forty-five (45) Days from the time such damages are first incurred, and every thirty (30) Days thereafter for as long as such damages are being incurred, the Contractor shall submit to the Commissioner verified written statements of the details and the amounts of such damages, together with documentary evidence of such damages, ("statement of delay damages") as further detailed in Article 11.6. The Contractor may submit any of the above statements within such additional time as may be granted by the Commissioner in writing upon written request therefor. On failure of the Contractor to strictly comply with all of the foregoing provisions, such claims shall be deemed waived and no right to recover on such claims shall exist. Damages that the Contractor may claim in any action arising under or by reason of this Contract shall not be different from or in excess of the statements made and documentation provided pursuant to this Article 11.
- 11.1.3 Within 60 days of submission of the final verified statement of claims pursuant to Article 44, the Commissioner shall make a determination as to whether a compensable delay has occurred and, if so, the amount of compensation due the Contractor. Notwithstanding the above, the Commissioner may make a determination as to whether a compensable delay has occurred at any time after the Contractor's first submission of a statement of delay damages provided, however, that the amount of compensation due to the Contractor will not be determined until the Commissioner determines that the Work is delayed after the date set for substantial completion.
- 11.2 Failure of the Contractor to strictly comply with the requirements of Article 11.1.1 may, in the discretion of the Commissioner, be deemed sufficient cause to deny any extension of time on account of delay arising out of such condition. Failure of the Contractor to strictly comply with the requirements of Articles 11.1.1 and 11.1.2 shall be deemed a conclusive waiver by the Contractor of any and all claims for damages for delay arising from such condition and no right to recover on such claims shall exist.
- 11.3 When appropriate and directed by the Engineer, the progress schedule shall be revised by the Contractor until finally approved by the Engineer. The revised progress schedule must be strictly adhered to by the Contractor.

#### 11.4 Compensable Delays

- 11.4.1 The Contractor agrees to make claim only for additional costs attributable to delay in the performance of this Contract necessarily extending the time for completion of the Work or resulting from acceleration directed by the Commissioner and required to maintain the Project schedule, occasioned solely by any act or omission to act of the City listed below. The Contractor also agrees that delay from any other cause shall be compensated, if at all, solely by an extension of time to complete the performance of the Work.
  - 11.4.1.1 The failure of the City to take reasonable measures to coordinate and progress the Work, except that the City shall not be responsible for the Contractor's obligation to coordinate and progress the Work of its Subcontractors.
  - 11.4.1.2 Extended delays attributable to the **City** in the review or issuance of change orders, in shop drawing reviews and approvals or as a result of the cumulative impact of multiple change orders, which have a verifiable impact on **Project** costs.
  - 11.4.1.3 The unavailability of the Site for an extended period of time that significantly affects the scheduled completion of the Contract.

- 11.4.1.4 The issuance by the **Engineer** of a stop work order relative to a substantial portion of the **Work** for a period exceeding thirty (30) **Days**, that was not brought about through any action or omission of the **Contractor**.
- 11.4.1.5 Differing site conditions that were neither known nor reasonably ascertainable on a pre-bid inspection of the Site or review of the bid documents or other publicly available sources, and that are not ordinarily encountered in the **Project's** geographical area or neighborhood or in the type of **Work** to be performed.
- 11.4.1.6 Delays caused by the **City's** bad faith or its willful, malicious, or grossly negligent conduct;
- 11.4.1.7 Delays not contemplated by the parties;
- 11.4.1.8 Delays so unreasonable that they constitute an intentional abandonment of the Contract by the City; and
- 11.4.1.9 Delays resulting from the City's breach of a fundamental obligation of the Contract.
- 11.4.2 No claim may be made for any alleged delay in Substantial Completion of the Work by a date earlier than the date of Substantial Completion provided for in Schedule A unless there is a provision in the Contract providing for additional compensation for early completion. No claim may be made for any alleged delay in Substantial Completion of the Work if the work is substantially completed by the date of Substantial Completion provided for in Schedule A unless acceleration has been directed by the Commissioner to meet the date of Substantial Completion set forth in Schedule A.
- 11.4.3 The provisions of this Article 11 apply only to claims for additional costs attributable to delay and do not preclude determinations by the **Commissioner** allowing reimbursements for additional costs for **Extra Work** pursuant to Articles 25 and 26 of this **Contract**. To the extent that any cost attributable to delay is reimbursed as part of a change order, no additional claim for compensation under this Article 11 shall be allowed.
- 11.5 Non-Compensable Delays. The **Contractor** agrees to make no claim for, and is deemed to have included in its bid prices for the various items of the **Contract**, the extra/additional costs attributable to any delays caused by or attributable to the items set forth below. For such items, the **Contractor** shall be compensated, if at all, solely by an extension of time to complete the performance of the **Work**, in accordance with the provisions of Article 13. Such extensions of time will be granted, if at all, pursuant to the grounds set forth in Article 13.3.
  - 11.5.1 The acts or omissions of any third parties, including but not limited to Other Contractors, public/ governmental bodies (other than City Agencies), utilities or private enterprises, who are disclosed in the Contract Documents or are ordinarily encountered or generally recognized as related to the Work;
  - 11.5.2 Any situation which was within the contemplation of the parties at the time of entering into the Contract, including any delay indicated or disclosed in the Contract Documents or generally recognized as related to the nature of the Work, and/or the existence of any facility or appurtenance owned, operated or maintained by any third party, as indicated or disclosed in the Contract Documents or ordinarily encountered or generally recognized as related to the nature of the Work;
  - 11.5.3 Restraining orders, injunctions or judgments issued by a court which were caused by a Contractor's submission, action or inaction or by a Contractor's Means and Methods of

Construction, or by third parties, unless such order, injunction or judgment was the result of an action or omission by the City;

- 11.5.4 Any labor boycott, strike, picketing, lockout or similar situation;
- 11.5.5 Any shortages of supplies or materials, or unavailability of equipment, required by the Contract Work;
- 11.5.6 Climatic conditions, storms, floods, droughts, tidal waves, fires, hurricanes, earthquakes, landslides or other catastrophes or acts of God, or acts of war or of the public enemy or terrorist acts, including the City's reasonable responses thereto; and
- 11.5.7 Extra Work which does not significantly affect the overall completion of the Contract, reasonable delays in the review or issuance of change orders or field orders and/or in shop drawing reviews or approvals.
- 11.6 Required Content of Submission of Statement of Delay Damages
  - 11.6.1 In the verified written statement of delay damages required by Article 11.1.2, the following information shall be provided by the Contractor:
    - 11.6.1.1 For each delay, the start and end dates of the claimed periods of delay and, in addition, a description of the operations that were delayed, an explanation of how they were delayed, and the reasons for the delay, including identifying the applicable act or omission of the City listed in Article 11.4.
    - 11.6.1.2 A detailed factual statement of the claim providing all necessary dates, locations and items of **Work** affected by the claim.
    - 11.6.1.3 The amount of additional compensation sought and a breakdown of that amount into categories as described in Article 26.2, subject to the limitations set forth in Article 11.7.
    - 11.6.1.4 Any additional information requested by the Commissioner.

#### 11.7 Recoverable Costs

- 11.7.1 Delay damages may be recoverable for the following costs actually and necessarily incurred in the performance of the Work:
  - 11.7.1.1 Direct labor, including payroll taxes (subject to statutory wage caps) and supplemental benefits, based on time and materials records;
  - 11.7.1.2 Necessary materials (including transportation to the **Site**), based on time and material records;
  - 11.7.1.3 Reasonable rental value of necessary plant and equipment other than small tools, plus fuel/energy costs according to the applicable formula set forth in Articles 26.2.4 and/or 26.2.8, based on time and material records;
  - 11.7.1.4 Insurance and bond costs;
  - 11.7.1.5 Extended field office costs;
  - 11.7.1.6 Extended Site overhead; and
  - 11.7.1.7 Extended home office overhead.
- 11.7.2 Recoverable Subcontractor Costs. When the Work is performed by a Subcontractor, the Contractor may be paid the actual and necessary costs of such subcontracted Work as outlined above in Articles 11.7.1.1 through 11.7.1.6, and an

additional overhead of five (5%) percent of the costs outlined in Articles 11.7.1.1 through 11.7.1.3.

- 11.7.3 Non-Recoverable Costs. The parties agree that the City will have no liability for the following items and the Contractor agrees it shall make no claim for the following items:
  - 11.7.3.1Profit, or loss of anticipated or unanticipated profit;
  - 11.7.3.2Consequential damages, including but not limited to interest on monies in dispute, including interest which is paid on such monies, loss of bonding capacity, bidding opportunities, or interest in investment, or any resulting insolvency;
  - 11.7.3.3 Indirect costs or expenses of any nature;
  - 11.7.3.4 Direct or indirect costs attributable to performance of Work where the Contractor, because of situations or conditions within its control, has not progressed the Work in a satisfactory manner; and
  - 11.7.3.5 Attorneys' fees and dispute and claims preparation expenses.
- 11.8 Determinations under this Article 11 are not subject to the jurisdiction of the Contract Dispute Resolution Board pursuant to the dispute resolution process set forth in Article 27.
- 11.9 If the parties agree, pursuant to Article 11.1.3 above, that a compensable delay has occurred and agree on the amount of compensation, payment may be made pursuant to a written change order. Payment pursuant to such change order is subject to pre-audit by the Engineering Audit Officer, and may be post-audited by the Comptroller and/or the Agency.

## ARTICLE 12. COORDINATION WITH OTHER CONTRACTORS

- 12.1 During the progress of the Work, Other Contractors may be engaged in performing other work or may be awarded other contracts for additional work on this Project. In that event, the Contractor shall coordinate the Work to be done hereunder with the work of such Other Contractors and the Contractor shall fully cooperate with such Other Contractors and carefully fit its own Work to that provided under other contracts as may be directed by the Engineer. The Contractor shall not commit or permit any act which will interfere with the performance of work by any Other Contractors.
- 12.2 If the Engineer determines that the Contractor is failing to coordinate its Work with the work of Other Contractors as the Engineer has directed, then the Commissioner shall have the right to withhold any payments otherwise due hereunder until the Contractor completely complies with the Engineer's directions.
- 12.3 The Contractor shall notify the Engineer in writing if any Other Contractor on this Project is failing to coordinate its work with the Work of this Contract. If the Engineer finds such charges to be true, the Engineer shall promptly issue such directions to the Other Contractor with respect thereto as the situation may require. The City shall not, however, be liable for any damages suffered by any Other Contractor's failure to coordinate its work with the Work of this Contract or by reason of the Other Contractor's failure to promptly comply with the directions so issued by the Engineer, or by reason of any Other Contractor's default in performance, it being understood that the City does not guarantee the responsibility or continued efficiency of any contractor. The Contractor agrees to make no claim against CITY OF NEW YORK STANDARD CONSTRUCTION CONTRACT 17

December 2013

DDC

the City for any damages relating to or arising out of any directions issued by the Engineer pursuant to this Article 12 (including but not limited to the failure of any Other Contractor to comply or promptly comply with such directions), or the failure of the Engineer to issue any directions, or the failure of any Other Contractor to coordinate its work, or the default in performance of any Other Contractor.

- 12.4 The Contractor shall indemnify and hold the City harmless from any and all claims or judgments for damages and from costs and expenses to which the City may be subjected or which it may suffer or incur by reason of the Contractor's failure to comply with the Engineer's directions promptly; and the Comptroller shall have the right to exercise the powers reserved in Article 23 with respect to any claims which may be made for damages due to the Contractor's failure to comply with the Engineer's directions promptly. Insofar as the facts and Law relating to any claim would preclude the City from being completely indemnified by the Contractor, the City shall be partially indemnified by the Contractor to the fullest extent provided by Law.
- 12.5 Should the Contractor sustain any damage through any act or omission of any Other Contractor having a contract with the City for the performance of work upon the Site or of work which may be necessary to be performed for the proper prosecution of the Work to be performed hereunder, or through any act or omission of a subcontractor of such Other Contractor, the Contractor shall have no claim against the City for such damage, but shall have a right to recover such damage from the Other Contractor under the provision similar to the following provisions which apply to this Contract and have been or will be inserted in the contracts with such Other Contractors:
  - 12.5.1 Should any Other Contractor having or who shall hereafter have a contract with the City for the performance of work upon the Site sustain any damage through any act or omission of the Contractor hereunder or through any act or omission of any Subcontractor of the Contractor, the Contractor agrees to reimburse such Other Contractor for all such damages and to defend at its own expense any action based upon such claim and if any judgment or claim (even if the allegations of the action are without merit) against the City shall be allowed the Contractor shall pay or satisfy such judgment or claim and pay all costs and expenses in connection therewith and agrees to indemnify and hold the City harmless from all such claims. Insofar as the facts and Law relating to any claim would preclude the City from being completely indemnified by the Contractor, the City shall be partially indemnified by the Contractor to the fullest extent provided by Law.
- 12.6 The City's right to indemnification hereunder shall in no way be diminished, waived or discharged by its recourse to assessment of liquidated damages as provided in Article 15, or by the exercise of any other remedy provided for by Contract or by Law.

#### **ARTICLE 13. EXTENSION OF TIME FOR PERFORMANCE**

- 13.1 If performance by the Contractor is delayed for a reason set forth in Article 13.3, the Contractor may be allowed a reasonable extension of time in conformance with this Article 13 and the PPB Rules.
- 13.2 Any extension of time may be granted only by the ACCO or by the Board for the Extension of Time (hereafter "Board") (as set forth below) upon written application by the Contractor.
- 13.3 Grounds for Extension: If such application is made, the Contractor shall be entitled to an extension of time for delay in completion of the Work caused solely:
  - 13.3.1 By the acts or omissions of the City, its officials, agents or employees; or

- 13.3.2 By the act or omissions of Other Contractors on this Project; or
- 13.3.3 By supervening conditions entirely beyond the control of either party hereto (such as, but not limited to, acts of God or the public enemy, excessive inclement weather, war or other national emergency making performance temporarily impossible or illegal, or strikes or labor disputes not brought about by any act or omission of the **Contractor**).
- 13.3.4 The Contractor shall, however, be entitled to an extension of time for such causes only for the number of **Days** of delay which the ACCO or the Board may determine to be due solely to such causes, and then only if the Contractor shall have strictly complied with all of the requirements of Articles 9 and 10.
- 13.4 The Contractor shall not be entitled to receive a separate extension of time for each of several causes of delay operating concurrently, but, if at all, only for the actual period of delay in completion of the Work as determined by the ACCO or the Board, irrespective of the number of causes contributing to produce such delay. If one of several causes of delay operating concurrently results from any act, fault or omission of the Contractor or of its Subcontractors or Materialmen, and would of itself (irrespective of the concurrent causes) have delayed the Work, no extension of time will be allowed for the period of delay resulting from such act, fault or omission.
- 13.5 The determination made by the ACCO or the Board on an application for an extension of time shall be binding and conclusive on the Contractor.
- 13.6 The ACCO or the Board acting entirely within their discretion may grant an application for an extension of time for causes of delay other than those herein referred.
- 13.7 Permitting the Contractor to continue with the Work after the time fixed for its completion has expired, or after the time to which such completion may have been extended has expired, or the making of any payment to the Contractor after such time, shall in no way operate as a waiver on the part of the City of any of its rights under this Contract.
  - 13.8 Application for Extension of Time:
    - 13.8.1 Before the **Contractor's** time extension request will be considered, the **Contractor** shall notify the **ACCO** of the condition which allegedly has caused or is causing the delay, and shall submit a written application to the **ACCO** identifying:
      - 13.8.1(a) The Contractor; the registration number; and Project description;
      - 13.8.1(b) Liquidated damage assessment rate, as specified in the Contract;
      - 13.8.1(c) Original total bid price;
      - 13.8.1(d) The original Contract start date and completion date:
      - 13.8.1(e) Any previous time extensions granted (number and duration); and
      - 13.8.1(f) The extension of time requested.
    - 13.8.2 In addition, the application for extension of time shall set forth in detail:
      - 13.8.2(a) The nature of each alleged cause of delay in completing the Work;

- 13.8.2(b) The date upon which each such cause of delay began and ended and the number of **Days** attributable to each such cause;
- 13.8.2(c) A statement that the **Contractor** waives all claims except for those delineated in the application, and the particulars of any claims which the **Contractor** does not agree to waive. For time extensions for **Substantial Completion** and final completion payments, the application shall include a detailed statement of the dollar amounts of each element of claim item reserved; and
- 13.8.2(d) A statement indicating the Contractor's understanding that the time extension is granted only for purposes of permitting continuation of Contract performance and payment for Work performed and that the City retains its right to conduct an investigation and assess liquidated damages as appropriate in the future.

## 13.9 Analysis and Approval of Time Extensions:

- 13.9.1 For time extensions for partial payments, a written determination shall be made by the ACCO who may, for good and sufficient cause, extend the time for the performance of the Contract as follows:
  - 13.9.1(a) If the Work is to be completed within six (6) months, the time for performance may be extended for sixty (60) Days;
  - 13.9.1(b) If the Work is to be completed within less than one (1) year but more than six (6) months, an extension of ninety (90) Days may be granted;
  - 13.9.1(c) If the **Contract** period exceeds one (1) year, besides the extension granted in Article 13.9.1(b), an additional thirty (30) **Days** may be granted for each multiple of six (6) months involved beyond the one (1) year period; or
  - 13.9.1(d) If exceptional circumstances exist, the ACCO may extend the time for performance beyond the extensions in Articles 13.9.1(a), 13.9.1(b), and 13.9.1(c). In that event, the ACCO shall file with the Mayor's Office of Contract Services a written explanation of the exceptional circumstances.
- 13.9.2 For extensions of time for **Substantial Completion** and final completion payments, the **Engineer**, in consultation with the **ACCO**, shall prepare a written analysis of the delay (including a preliminary determination of the causes of delay, the beginning and end dates for each such cause of delay, and whether the delays are excusable under the terms of this **Contract**). The report shall be subject to review by and approval of the Board, which shall have authority to question its analysis and determinations and request additional facts or documentation. The report as reviewed and made final by the Board shall be made a part of the **Agency** contract file. Neither the report itself nor anything contained therein shall operate as a waiver or release of any claim the **City** may have against the **Contractor** for either actual or liquidated damages.
- 13.9.3 Approval Mechanism for Time Extensions for Substantial Completion or Final Completion Payments: An extension shall be granted only with the approval of the Board which is comprised of the ACCO of the Agency, the City Corporation Counsel, and the Comptroller, or their authorized representatives.

- 13.9.4 Neither the granting of any application for an extension of time to the Contractor or any Other Contractor on this Project nor the papers, records or reports related to any application for or grant of an extension of time or determination related thereto shall be referred to or offered in evidence by the Contractor or its attorneys in any action or proceeding.
- 13.10 No Damage for Delay: The Contractor agrees to make no claim for damages for delay in the performance of this Contract occasioned by any act or omission to act of the City or any of its representatives, except as provided for in Article 11.

#### ARTICLE 14. COMPLETION AND FINAL ACCEPTANCE OF THE WORK

- 14.1 Date for Substantial Completion: The Contractor shall substantially complete the Work within the time fixed in Schedule A of the General Conditions, or within the time to which such Substantial Completion may be extended.
- 14.2 Determining the Date of **Substantial Completion**: The **Work** will be deemed to be substantially complete when the two conditions set forth below have been met.
  - 14.2.1 Inspection: The Engineer has inspected the Work and has made a written determination that it is substantially complete.
  - 14.2.2 Approval of Final Approved Punch List and Date for Final Acceptance: Following inspection of the Work, the Engineer shall furnish the Contractor with a final punch list, specifying all items of Work to be completed and proposing dates for the completion of each specified item of Work. The Contractor shall then submit in writing to the Engineer within ten (10) Days of the Engineer furnishing the final punch list either acceptance of the dates or proposed alternative dates for the completion of each specified item of Work. If the Contractor proposes alternative dates, then, within a reasonable time after receipt, the Engineer, in a written notification to the Contractor, shall approve the Contractor's completion dates or, if they are unable to agree, the Engineer shall establish dates for the completion of each item of Work. If the Contractor neither accepts the dates nor proposes alternative dates within ten (10) Days, the schedule proposed by the Engineer shall be deemed accepted. The latest completion date specified shall be the date for Final Acceptance of the Work.
- 14.3 Date of Substantial Completion. The date of approval of the Final Approved Punch List, shall be the date of Substantial Completion. The date of approval of the Final Approved Punch List shall be either (a) if the Contractor approves the final punch list and proposed dates for completion furnished by the Engineer, the date of the Contractor's approval; or (b) if the Contractor neither accepts the dates nor proposes alternative dates, ten (10) Days after the Engineer furnishes the Contractor with a final punch list and proposed dates for completion; or (c) if the Contractor proposes alternative dates, the date that the Engineer sends written notification to the Contractor either approving the Contractor's proposed alternative dates or establishing dates for the completion for each item of Work.
- 14.4 Determining the Date of Final Acceptance: The Work will be accepted as final and complete as of the date of the Engineer's inspection if, upon such inspection, the Engineer finds that all items on the Final Approved Punch List are complete and no further Work remains to be done. The Commissioner will then issue a written determination of Final Acceptance.

- 14.5 Request for Inspection: Inspection of the Work by the Engineer for the purpose of Substantial Completion or Final Acceptance shall be made within ten (10) Days after receipt of the Contractor's written request therefor.
- 14.6 Request for Re-inspection: If upon inspection for the purpose of Substantial Completion or Final Acceptance, the Engineer determines that there are items of Work still to be performed, the Contractor shall promptly perform them and then request a re-inspection. If upon re-inspection, the Engineer determines that the Work is substantially complete or finally accepted, the date of such re-inspection shall be the date of Substantial Completion or Final Acceptance. Re-inspection by the Engineer shall be made within ten (10) Days after receipt of the Contractor's written request therefor.
- 14.7 Initiation of Inspection by the Engineer: If the Contractor does not request inspection or reinspection of the Work for the purpose of Substantial Completion or Final Acceptance, the Engineer may initiate such inspection or re-inspection.

#### ARTICLE 15. LIQUIDATED DAMAGES

- 15.1 In the event the Contractor fails to substantially complete the Work within the time fixed for such Substantial Completion in Schedule A of the General Conditions, plus authorized time extensions, or if the Contractor, in the sole determination of the Commissioner, has abandoned the Work, the Contractor shall pay to the City the sum fixed in Schedule A of the General Conditions, for each and every Day that the time consumed in substantially completing the Work exceeds the time allowed therefor; which said sum, in view of the difficulty of accurately ascertaining the loss which the City will suffer by reason of delay in the Substantial Completion of the Work hereunder, is hereby fixed and agreed as the liquidated damages that the City will suffer by reason of such delay, and not as a penalty. This Article 15 shall also apply to the Contractor whether or not the Contractor is defaulted pursuant to Chapter X of this Contract. Neither the failure to assess liquidated damages nor the granting of any time extension shall operate as a waiver or release of any claim the City may have against the Contractor for either actual or liquidated damages.
- 15.2 Liquidated damages received hereunder are not intended to be nor shall they be treated as either a partial or full waiver or discharge of the City's right to indemnification, or the Contractor's obligation to indemnify the City, or to any other remedy provided for in this Contract or by Law.
- 15.3 The **Commissioner** may deduct and retain out of the monies which may become due hereunder, the amount of any such liquidated damages; and in case the amount which may become due hereunder shall be less than the amount of liquidated damages suffered by the **City**, the **Contractor** shall be liable to pay the difference.

#### ARTICLE 16. OCCUPATION OR USE PRIOR TO COMPLETION

- 16.1 Unless otherwise provided for in the Specifications, the Commissioner may take over, use, occupy or operate any part of the Work at any time prior to Final Acceptance, upon written notification to the Contractor. The Engineer shall inspect the part of the Work to be taken over, used, occupied, or operated, and will furnish the Contractor with a written statement of the Work, if any, which remains to be performed on such part. The Contractor shall not object to, nor interfere with, the Commissioner's decision to exercise the rights granted by Article 16. In the event the Commissioner takes over, uses, occupies, or operates any part of the Work:
  - 16.1.1 the Engineer shall issue a written determination of Substantial Completion with respect to such part of the Work;

- 16.1.2 the **Contractor** shall be relieved of its absolute obligation to protect such part of the unfinished **Work** in accordance with Article 7;
- 16.1.3 the Contractor's guarantee on such part of the Work shall begin on the date of such use by the City; and;
- 16.1.4 the Contractor shall be entitled to a return of so much of the amount retained in accordance with Article 21 as it relates to such part of the Work, except so much thereof as may be retained under Articles 24 and 44.

# CHAPTER IV SUBCONTRACTS AND ASSIGNMENTS

# **ARTICLE 17. SUBCONTRACTS**

- 17.1 The Contractor shall not make subcontracts totaling an amount more than the percentage of the total Contract price fixed in Schedule A of the General Conditions, without prior written permission from the Commissioner. All subcontracts made by the Contractor shall be in writing. No Work may be performed by a Subcontractor prior to the Contractor entering into a written subcontract with the Subcontractor and complying with the provisions of this Article 17.
- 17.2 Before making any subcontracts, the Contractor shall submit a written statement to the Commissioner giving the name and address of the proposed Subcontractor; the portion of the Work and materials which it is to perform and furnish; the cost of the subcontract; the VENDEX questionnaire if required; the proposed subcontract if requested by the Commissioner; and any other information tending to prove that the proposed Subcontractor has the necessary facilities, skill, integrity, past experience, and financial resources to perform the Work in accordance with the terms and conditions of this Contract.
- 17.3 In addition to the requirements in Article 17.2, Contractor is required to list the Subcontractor in the web based Subcontractor Reporting System through the City's Payee Information Portal (PIP), available at <a href="https://www.nyc.gov/pip.">www.nyc.gov/pip.</a> For each Subcontractor listed, Contractor is required to provide the following information: maximum contract value, description of Subcontractor's Work, start and end date of the subcontract and identification of the Subcontractor's industry. Thereafter, Contractor will be required to report in the system the payments made to each Subcontractor within 30 days of making the payment. If any of the required information changes throughout the Term of the Contract, Contractor will be required to revise the information in the system.

Failure of the Contractor to list a Subcontractor and/or to report Subcontractor payments in a timely fashion may result in the Commissioner declaring the Contractor in default of the Contract and will subject Contractor to liquidated damages in the amount of \$100 per day for each day that the Contractor fails to identify a Subcontractor along with the required information about the Subcontractor and/or fails to report payments to a Subcontractor, beyond the time frames set forth herein or in the notice from the City. Article 15 shall govern the issue of liquidated damages.

<sup>&</sup>lt;sup>1</sup> In order to use the new system, a PIP account will be required. Detailed instructions on creating a PIP account and using the new system are also available at <a href="www.nyc.gov/pip">www.nyc.gov/pip</a>. Additional assistance with PIP may be obtained by emailing the Financial Information Services Agency Help Desk at <a href="pip@fisa.nyc.gov">pip.@fisa.nyc.gov</a>.

- 17.4 If an approved **Subcontractor** elects to subcontract any portion of its subcontract, the proposed sub-subcontract shall be submitted in the same manner as directed above.
- 17.5 The Commissioner will notify the Contractor in writing whether the proposed Subcontractor is approved. If the proposed Subcontractor is not approved, the Contractor may submit another proposed Subcontractor unless the Contractor decides to do the Work. No Subcontractor shall be permitted to enter or perform any work on the Site unless approved.
- 17.6 Before entering into any subcontract hereunder, the Contractor shall provide the proposed Subcontractor with a complete copy of this document and inform the proposed Subcontractor fully and completely of all provisions and requirements of this Contract relating either directly or indirectly to the Work to be performed and the materials to be furnished under such subcontract, and every such Subcontractor shall expressly stipulate that all labor performed and materials furnished by the Subcontractor shall strictly comply with the requirements of this Contract.
- 17.7 Documents given to a prospective **Subcontractor** for the purpose of soliciting the **Subcontractor's** bid shall include either a copy of the bid cover or a separate information sheet setting forth the **Project** name, the **Contract** number (if available), the **Agency** (as noted in Article 2.1.6), and the **Project's** location.
- 17.8 The Commissioner's approval of a Subcontractor shall not relieve the Contractor of any of its responsibilities, duties, and liabilities hereunder. The Contractor shall be solely responsible to the City for the acts or defaults of its Subcontractor and of such Subcontractor's officers, agents, and employees, each of whom shall, for this purpose, be deemed to be the agent or employee of the Contractor to the extent of its subcontract.
- 17.9 If the Subcontractor fails to maintain the necessary facilities, skill, integrity, past experience, and financial resources (other than due to the Contractor's failure to make payments where required) to perform the Work in accordance with the terms and conditions of this Contract, the Contractor shall promptly notify the Commissioner and replace such Subcontractor with a newly approved Subcontractor in accordance with this Article 17.
- 17.10 The Contractor shall be responsible for ensuring that all Subcontractors performing Work at the Site maintain all insurance required by Law.
- 17.11 The Contractor shall promptly, upon request, file with the Engineer a conformed copy of the subcontract and its cost. The subcontract shall provide the following:
  - 17.11.1 Payment to Subcontractors: The agreement between the Contractor and its Subcontractor shall contain the same terms and conditions as to method of payment for Work, labor, and materials, and as to retained percentages, as are contained in this Contract.
  - 17.11.2 Prevailing Rate of Wages: The agreement between the Contractor and its Subcontractor shall include the prevailing wage rates and supplemental benefits to be paid in accordance with Labor Law Section 220.
  - 17.11.3 Section 6-123 of the Administrative Code: Pursuant to the requirements of Section 6-123 of the Administrative Code, every agreement between the Contractor and a Subcontractor in excess of fifty thousand (\$50,000) dollars shall include a provision that the Subcontractor shall not engage in any unlawful discriminatory practice as defined in Title VIII of the Administrative Code (Section 8-101 et seq.).

- 17.11.4 All requirements required pursuant to federal and/or state grant agreement(s), if applicable to the Work.
- 17.12 The Commissioner may deduct from the amounts certified under this Contract to be due to the Contractor, the sum or sums due and owing from the Contractor to the Subcontractors according to the terms of the said subcontracts, and in case of dispute between the Contractor and its Subcontractor, or Subcontractors, as to the amount due and owing, the Commissioner may deduct and withhold from the amounts certified under this Contract to be due to the Contractor such sum or sums as may be claimed by such Subcontractor, or Subcontractors, in a sworn affidavit, to be due and owing until such time as such claim or claims shall have been finally resolved.
- 17.13 On contracts where performance bonds and payment bonds are executed, the Contractor shall include on each requisition for payment the following data: Subcontractor's name, value of the subcontract, total amount previously paid to Subcontractor for Work previously requisitioned, and the amount, including retainage, to be paid to the Subcontractor for Work included in the requisition.
- 17.14 On Contracts where performance bonds and payment bonds are not executed, the Contractor shall include with each requisition for payment submitted hereunder, a signed statement from each and every Subcontractor and/or Materialman for whom payment is requested in such requisition. Such signed statement shall be on the letterhead of the Subcontractor and/or Materialman for whom payment is requested and shall (i) verify that such Subcontractor and/or Materialman has been paid in full for all Work performed and/or material supplied to date, exclusive of any amount retained and any amount included on the current requisition, and (ii) state the total amount of retainage to date, exclusive of any amount retained on the current requisition.

# **ARTICLE 18. ASSIGNMENTS**

- 18.1 The Contractor shall not assign, transfer, convey or otherwise dispose of this Contract, or the right to execute it, or the right, title or interest in or to it or any part thereof, or assign, by power of attorney or otherwise any of the monies due or to become due under this Contract, unless the previous written consent of the Commissioner shall first be obtained thereto, and the giving of any such consent to a particular assignment shall not dispense with the necessity of such consent to any further or other assignments.
- 18.2 Such assignment, transfer, conveyance or other disposition of this Contract shall not be valid until filed in the office of the Commissioner and the Comptroller, with the written consent of the Commissioner endorsed thereon or attached thereto.
- 18.3 Failure to obtain the previous written consent of the Commissioner to such an assignment, transfer, conveyance or other disposition, may result in the revocation and annulment of this Contract. The City shall thereupon be relieved and discharged from any further liability to the Contractor, its assignees, transferees or sublessees, who shall forfeit and lose all monies therefor earned under the Contract, except so much as may be required to pay the Contractor's employees.
- 18.4 The provisions of this clause shall not hinder, prevent, or affect an assignment by the Contractor for the benefit of its creditors made pursuant to the Laws of the State of New York.
- 18.5 This Contract may be assigned by the City to any corporation, agency or instrumentality having authority to accept such assignment.

# CHAPTER V CONTRACTOR'S SECURITY AND GUARANTEE

# **ARTICLE 19. SECURITY DEPOSIT**

- 19.1 If performance and payment bonds are required, the City shall retain the bid security to ensure that the successful bidder executes the Contract and furnishes the required payment and performance security within ten (10) Days after notice of the award of the Contract. If the successful bidder fails to execute the Contract and furnish the required payment and performance security, the City shall retain such bid security as set forth in the Information for Bidders. If the successful bidder executes the Contract and furnishes the required payment and performance security, the City shall return the bid security within a reasonable time after the furnishing of such bonds and execution of the Contract by the City.
- 19.2 If performance and payment bonds are not required, the bid security shall be retained by the City as security for the Contractor's faithful performance of the Contract. If partial payments are provided, the bid security will be returned to the Contractor after the sum retained under Article 21 equals the amount of the bid security, subject to other provisions of this Contract. If partial payments are not provided, the bid security will be released when final payment is certified by the City for payment.
- 19.3 If the Contractor is declared in default under Article 48 prior to the return of the deposit, or if any claim is made such as referred to in Article 23, the amount of such deposit, or so much thereof as the Comptroller may deem necessary, may be retained and then applied by the Comptroller:
  - 19.3.1 To compensate the City for any expense, loss or damage suffered or incurred by reason of or resulting from such default, including the cost of re-letting and liquidated damages; or
    - 19.3.2 To indemnify the City against any and all claims.

## **ARTICLE 20. PAYMENT GUARANTEE**

- 20.1 On Contracts where one hundred (100%) percent performance bonds and payment bonds are executed, this Article 20 does not apply.
- 20.2 In the event the terms of this Contract do not require the Contractor to provide a payment bond or where the Contract does not requite a payment bond for one hundred (100%) percent of the Contract price, the City shall, in accordance with the terms of this Article 20, guarantee payment of all lawful claims for:
  - 20.2.1 Wages and compensation for labor performed and/or services rendered; and
  - 20.2.2 Materials, equipment, and supplies provided, whether incorporated into the Work or not, when demands have been filed with the City as provided hereinafter by any person, firm, or corporation which furnished labor, material, equipment, supplies, or any combination thereof, in connection with the Work performed hereunder (hereinafter referred to as the "beneficiary") at the direction of the City or the Contractor.
  - 20.3 The provisions of Article 20.2 are subject to the following limitations and conditions:

- 20.3.1 If the Contractor provides a payment bond for a value that is less than one hundred (100%) percent of the value of the Contract Work, the payment bond provided by the Contractor shall be primary (and non-contributing) to the payment guarantee provided under this Article 20.
- 20.3.2 The guarantee is made for the benefit of all beneficiaries as defined in Article 20.2 provided that those beneficiaries strictly adhere to the terms and conditions of Article 20.3.4 and 20.3.5.
- 20.3.3 Nothing in this Article 20 shall prevent a beneficiary providing labor, services or material for the Work from suing the Contractor for any amounts due and owing the beneficiary by the Contractor.
- 20.3.4 Every person who has furnished labor or material, to the Contractor or to a Subcontractor of the Contractor, in the prosecution of the Work and who has not been paid in full therefor before the expiration of a period of ninety (90) Days after the date on which the last of the labor was performed or material was furnished by him/her for which the claim is made, shall have the right to sue on this payment guarantee in his/her own name for the amount, or the balance thereof, unpaid at the time of commencement of the action; provided, however, that a person having a direct contractual relationship with a Subcontractor of the Contractor but no contractual relationship express or implied with the Contractor shall not have a right of action upon the guarantee unless he/she shall have given written notice to the Contractor within one hundred twenty (120) Days from the date on which the last of the labor was performed or the last of the material was furnished, for which his/her claim is made, stating with substantial accuracy the amount claimed and the name of the party to whom the material was furnished or for whom the labor was performed. The notice shall be served by delivering the same personally to the Contractor or by mailing the same by registered mail, postage prepaid, in an envelope addressed to the Contractor at any place where it maintains an office or conducts its business; provided, however, that where such notice is actually received by the Contractor by other means, such notice shall be deemed sufficient.
- 20.3.5 Except as provided in Labor Law Section 220-g, no action on this payment guarantee shall be commenced after the expiration of the one-year limitations period set forth in Section 137(4)(b) of the State Finance Law.
- 20.3.6 The Contractor shall promptly forward to the City any notice or demand received pursuant to Article 20.3.4. The Contractor shall inform the City of any defenses to the notice or demand and shall forward to the City any documents the City requests concerning the notice or demand.
- 20.3.7 All demands made against the City by a beneficiary of this payment guarantee shall be presented to the Engineer along with all written documentation concerning the demand which the Engineer deems reasonably appropriate or necessary, which may include, but shall not be limited to: the subcontract; any invoices presented to the Contractor for payment; the notarized statement of the beneficiary that the demand is due and payable, that a request for payment has been made of the Contractor and that the demand has not been paid by the Contractor within the time allowed for such payment by the subcontract; and copies of any correspondence between the beneficiary and the Contractor concerning such demand. The City shall notify the Contractor that a demand has been made. The Contractor shall inform the City of any defenses to the demand and shall forward to the City any documents the City requests concerning the demand.

- 20.3.8 The City shall make payment only if, after considering all defenses presented by the Contractor, it determines that the payment is due and owing to the beneficiary making the demand.
- 20.3.9 No beneficiary shall be entitled to interest from the City, or to any other costs, including, but not limited to, attorneys' fees, except to the extent required by State Finance Law Section 137.
- 20.4 Upon the receipt by the City of a demand pursuant to this Article 20, the City may withhold from any payment otherwise due and owing to the Contractor under this Contract an amount sufficient to satisfy the demand.
  - 20.4.1 In the event the City determines that the demand is valid, the City shall notify the Contractor of such determination and the amount thereof and direct the Contractor to immediately pay such amount to the beneficiary. In the event the Contractor, within seven (7) Days of receipt of such notification from the City, fails to pay the beneficiary, such failure shall constitute an automatic and irrevocable assignment of payment by the Contractor to the beneficiary for the amount of the demand determined by the City to be valid. The Contractor, without further notification or other process, hereby gives its unconditional consent to such assignment of payment to the beneficiary and authorizes the City, on its behalf, to take all necessary actions to implement such assignment of payment, including without limitation the execution of any instrument or documentation necessary to effectuate such assignment.
  - 20.4.2In the event that the amount otherwise due and owing to the Contractor by the City is insufficient to satisfy such demand, the City may, at its option, require payment from the Contractor of an amount sufficient to cover such demand and exercise any other right to require or recover payment which the City may have under Law or Contract.
  - 20.4.3 In the event the City determines that the demand is invalid, any amount withheld pending the City's review of such demand shall be paid to the Contractor; provided, however, no lien has been filed. In the event a claim or an action has been filed, the terms and conditions set forth in Article 23 shall apply. In the event a lien has been filed, the parties will be governed by the provisions of the Lien Law of the State of New York.
- 20.5 The provisions of this Article 20 shall not prevent the City and the Contractor from resolving disputes in accordance with the PPB Rules, where applicable.
- 20.6 In the event the City determines that the beneficiary is entitled to payment pursuant to this Article 20, such determination and any defenses and counterclaims raised by the Contractor shall be taken into account in evaluating the Contractor's performance.
- 20.7 Nothing in this Article 20 shall relieve the Contractor of the obligation to pay the claims of all persons with valid and lawful claims against the Contractor relating to the Work.
- 20.8 The Contractor shall not require any performance, payment or other bonds of any Subcontractor if this Contract does not require such bonds of the Contractor.
- 20.9 The payment guarantee made pursuant to this Article 20 shall be construed in a manner consistent with Section 137 of the State Finance Law and shall afford to persons furnishing labor or materials to the Contractor or its Subcontractors in the prosecution of the Work under this Contract all of the rights and remedies afforded to such persons by such section, including but not limited to, the right CITY OF NEW YORK

  28 STANDARD CONSTRUCTION CONTRACT

  December 2013

to commence an action against the City on the payment guarantee provided by this Article 20 within the one-year limitations period set forth in Section 137(4)(b).

#### ARTICLE 21. RETAINED PERCENTAGE

- 21.1 If this Contract requires one hundred (100%) percent performance and payment security, then as further security for the faithful performance of this Contract, the Commissioner shall deduct, and retain until the substantial completion of the Work, five (5%) percent of the value of Work certified for payment in each partial payment voucher.
- 21.2 If this Contract does not require one hundred (100%) percent performance and payment security and if the price for which this Contract was awarded does not exceed one million (\$1,000,000) dollars, then as further security for the faithful performance of this Contract, the Commissioner shall deduct, and retain until the substantial completion of the Work, five (5%) percent of the value of Work certified for payment in each partial payment voucher.
- 21.3 If this Contract does not require one hundred (100%) percent performance and payment security and if the price for which this Contract was awarded exceeds one million (\$1,000,000) dollars, then as further security for the faithful performance of this Contract, the Commissioner shall deduct, and retain until the substantial completion of the Work, up to ten (10%) percent of the value of Work certified for payment in each partial payment voucher. The percentage to be retained is set forth in Schedule A of the General Conditions.

#### **ARTICLE 22. INSURANCE**

- 22.1 Types of Insurance: The Contractor shall procure and maintain the following types of insurance if, and as indicated, in Schedule A of the General Conditions (with the minimum limits and special conditions specified in Schedule A). Such insurance shall be maintained from the date the Contractor is required to provide Proof of Insurance pursuant to Article 22.3.1 through the date of completion of all required Work (including punch list work as certified in writing by the Resident Engineer), except for insurance required pursuant to Article 22.1.4, which may terminate upon Substantial Completion of the Contract. All insurance shall meet the requirements set forth in this Article 22. Wherever this Article requires that insurance coverage be "at least as broad" as a specified form (including all ISO forms), there is no obligation that the form itself be used, provided that the Contractor can demonstrate that the alternative form or endorsement contained in its policy provides coverage at least as broad as the specified form.
  - 22.1.1Commercial General Liability Insurance: The Contractor shall provide Commercial General Liability Insurance covering claims for property damage and/or bodily injury, including death, which may arise from any of the operations under this Contract. Coverage under this insurance shall be at least as broad as that provided by the latest edition of Insurance Services Office ("ISO") Form CG 0001. Such insurance shall be "occurrence" based rather than "claims-made" and include, without limitation, the following types of coverage: premises operations; products and completed operations; contractual liability (including the tort liability of another assumed in a contract); broad form property damage; independent contractors; explosion, collapse and underground (XCU); construction means and methods; and incidental malpractice. Such insurance shall contain a "per project" aggregate limit, as specified in Schedule A, that applies separately to operations under this Contract.

- 22.1.1(a) Such Commercial General Liability Insurance shall name the City as an Additional Insured. Coverage for the City shall specifically include the City's officials and employees, be at least as broad as the latest edition of ISO Form CG 20 10 and provide completed operations coverage at least as broad as the latest edition of ISO Form CG 20 37.
- 22.1.1(b) Such Commercial General Liability Insurance shall name all other entities designated as additional insureds in Schedule A but only for claims arising from the **Contractor's** operations under this **Contract**, with coverage at least as broad as the latest edition of ISO Form CG 20 26.
- 22.1.1(c) If the Work requires a permit from the Department of Buildings pursuant to 1 RCNY Section 101-08, at <a href="http://www.nyc.gov/html/dob/downloads/rules/1\_RCNY\_101-08.pdf">http://www.nyc.gov/html/dob/downloads/rules/1\_RCNY\_101-08.pdf</a>, the Contractor shall provide Commercial General Liability Insurance with limits of at least those required by 1 RCNY section 101-08. If the Work does not require such a permit, the minimum limits shall be those provided for in Schedule A.
- 22.1.1(d) If any of the Work includes repair of a waterborne vessel owned by or to be delivered to the City, such Commercial General Liability shall include, or be endorsed to include, Ship Repairer's Legal Liability Coverage to protect against, without limitation, liability arising from navigation of such vessels prior to delivery to and acceptance by the City.
- 22.1.2 Workers' Compensation Insurance, Employers' Liability Insurance, and Disability Benefits Insurance: The Contractor shall provide, and shall cause its Subcontractors to provide, Workers Compensation Insurance, Employers' Liability Insurance, and Disability Benefits Insurance in accordance with the Laws of the State of New York on behalf of all employees providing services under this Contract (except for those employees, if any, for which the Laws require insurance only pursuant to Article 22.1.3).
- 22.1.3 United States Longshoremen's and Harbor Workers Act and/or Jones Act Insurance: If specified in Schedule A of the General Conditions or if required by **Law**, the **Contractor** shall provide insurance in accordance with the United States Longshoremen's and Harbor Workers Act and/or the Jones Act, on behalf of all qualifying employees providing services under this **Contract**.
- 22.1.4 Builders Risk Insurance: If specified in Schedule A of the General Conditions, the Contractor shall provide Builders Risk Insurance on a completed value form for the total value of the Work through Substantial Completion of the Work in its entirety. Such insurance shall be provided on an All Risk basis and include coverage, without limitation, for windstorm (including named windstorm), storm surge, flood and earth movement. Unless waived by the Commissioner, it shall include coverage for ordinance and law, demolition and increased costs of construction, debris removal, pollutant clean up and removal, and expediting costs. Such insurance shall cover, without limitation, (a) all buildings and/or structures involved in the Work, as well as temporary structures at the Site, and (b) any property that is intended to become a permanent part of such building or structure, whether such property is on the Site, in transit or in temporary storage. Policies shall name the Contractor as Named Insured and list the City as both an Additional Insured and a Loss Payee as its interest may appear.
  - 22.1.4(a) Policies of such insurance shall specify that, in the event a loss occurs at an occupied facility, occupancy of such facility is permitted without the consent of the issuing insurance company.

- 22.1.4(b) Such insurance may be provided through an Installation Floater, at the Contractor's option, if it otherwise conforms with the requirements of this Article 22.1.4.
- 22.1.5 Commercial Automobile Liability Insurance: The Contractor shall provide Commercial Automobile Liability Insurance for liability arising out of ownership, maintenance or use of any owned (if any), non-owned and hired vehicles to be used in connection with this Contract. Coverage shall be at least as broad as the latest edition of ISO Form CA0001. If vehicles are used for transporting hazardous materials, the Automobile Liability Insurance shall be endorsed to provide pollution liability broadened coverage for covered vehicles (endorsement CA 99 48) as well as proof of MCS 90.
- 22.1.6 Contractors Pollution Liability Insurance: If specified in Schedule A of the General Conditions, the Contractor shall maintain, or cause the Subcontractor doing such Work to maintain, Contractors Pollution Liability Insurance covering bodily injury and property damage. Such insurance shall provide coverage for actual, alleged or threatened emission, discharge, dispersal, seepage, release or escape of pollutants (including asbestos), including any loss, cost or expense incurred as a result of any cleanup of pollutants (including asbestos) or in the investigation, settlement or defense of any claim, action, or proceedings arising from the operations under this Contract. Such insurance shall be in the Contractor's name and list the City as an Additional Insured and any other entity specified in Schedule A. Coverage shall include, without limitation, (a) loss of use of damaged property or of property that has not been physically injured, (b) transportation, and (c) non-owned disposal sites.
  - 22.1.6(a) Coverage for the City as Additional Insured shall specifically include the City's officials and employees and be at least as broad as provided to the Contractor for this Project.
  - 22.1.6(b) If such insurance is written on a claims-made policy, such policy shall have a retroactive date on or before the effective date of this Contract, and continuous coverage shall be maintained, or an extended discovery period exercised, for a period of not less than three (3) years from the time the Work under this Contract is completed.

#### 22.1.7 Marine Insurance:

22.1.7(a) Marine Protection and Indemnity Insurance: If specified in Schedule A of the General Conditions or if the Contractor engages in marine operations in the execution of any part of the Work, the Contractor shall maintain, or cause the Subcontractor doing such Work to maintain, Marine Protection and Indemnity Insurance with coverage at least as broad as Form SP-23. The insurance shall provide coverage for the Contractor or Subcontractor (whichever is doing this Work) and for the City (together with its officials and employees) and any other entity specified in Schedule A as an Additional Insured for bodily injury and property damage arising from marine operations under this Contract. Coverage shall include, without limitation, injury or death of crew members (if not fully provided through other insurance), removal of wreck, damage to piers, wharves and other fixed or floating objects and loss of or damage to any other vessel or craft, or to property on such other vessel or craft.

- 22.1.7(b) Hull and Machinery Insurance: If specified in Schedule A of the General Conditions or if the Contractor engages in marine operations in the execution of any part of the Work, the Contractor shall maintain, or cause the Subcontractor doing such Work to maintain, Hull and Machinery Insurance with coverage for the Contractor or Subcontractor (whichever is doing this Work) and for the City (together with its officials and employees) as Additional Insured at least as broad as the latest edition of American Institute Tug Form for all tugs used under this Contract and Collision Liability at least as broad as the latest edition of American Institute Hull Clauses.
- 22.1.7(c) Marine Pollution Liability Insurance: If specified in Schedule A of the General Conditions or if the Contractor engages in marine operations in the execution of any part of the Work, the Contractor shall maintain, or cause the Subcontractor doing such Work to maintain, Marine Pollution Liability Insurance covering itself (or the Subcontractor doing such Work) as Named Insured and the City (together with its officials and employees) and any other entity specified in Schedule A as an Additional Insured. Coverage shall be at least as broad as that provided by the latest edition of Water Quality Insurance Syndicate Form and include, without limitation, liability arising from the discharge or substantial threat of a discharge of oil, or from the release or threatened release of a hazardous substance including injury to, or economic losses resulting from, the destruction of or damage to real property, personal property or natural resources.
- 22.1.8 The Contractor shall provide such other types of insurance, at such minimum limits and with such conditions, as are specified in Schedule A of the General Conditions.
- 22.2 General Requirements for Insurance Coverage and Policies:
  - 22.2.1 All required insurance policies shall be maintained with companies that may lawfully issue the required policy and have an A.M. Best rating of at least A-/VII or a Standard and Poor's rating of at least A, unless prior written approval is obtained from the City Corporation Counsel.
  - 22.2.2 The Contractor shall be solely responsible for the payment of all premiums for all required policies and all deductibles and self-insured retentions to which such policies are subject, whether or not the City is an insured under the policy.
  - 22.2.3 In his/her sole discretion, the Commissioner may, subject to the approval of the Comptroller and the City Corporation Counsel, accept Letters of Credit and/or custodial accounts in lieu of required insurance.
  - 22.2.4 The City's limits of coverage for all types of insurance required pursuant to Schedule A of the General Conditions shall be the greater of (i) the minimum limits set forth in Schedule A or (ii) the limits provided to the Contractor as Named Insured under all primary, excess, and umbrella policies of that type of coverage.
  - 22.2.5 The Contractor may satisfy its insurance obligations under this Article 22 through primary policies or a combination of primary and excess/umbrella policies, so long as all policies provide the scope of coverage required herein.
  - 22.2.6 Policies of insurance provided pursuant to this Article 22 shall be primary and non-contributing to any insurance or self-insurance maintained by the City.

#### 22.3 Proof of Insurance:

- 22.3.1 For all types of insurance required by Article 22.1 and Schedule A, except for insurance required by Articles 22.1.4 and 22.1.7, the Contractor shall file proof of insurance in accordance with this Article 22.3 within ten (10) Days of award. For insurance provided pursuant to Articles 22.1.4 and 22.1.7, proof shall be filed by a date specified by the Commissioner or ten (10) Days prior to the commencement of the portion of the Work covered by such policy, whichever is earlier.
- 22.3.2 For Workers' Compensation Insurance provided pursuant to Article 22.1.2, the Contractor shall submit one of the following forms: C-105.2 Certificate of Workers' Compensation Insurance; U-26.3 - State Insurance Fund Certificate of Workers' Compensation Insurance; Request for WC/DB Exemption (Form CE-200); equivalent or successor forms used by the New York State Workers' Compensation Board; or other proof of insurance in a form acceptable to the Commissioner. For Disability Benefits Insurance provided pursuant to Article 22.1.2, the Contractor shall submit DB-120.1 - Certificate Of Insurance Coverage Under The NYS Disability Benefits Law, Request for WC/DB Exemption (Form CE-200); equivalent or successor forms used by the New York State Workers' Compensation Board; or other proof of insurance in a form acceptable to the Commissioner. ACORD forms are not acceptable.
- 22.3.3 For policies provided pursuant to all of Article 22.1 other than Article 22.1.2, the Contractor shall submit one or more Certificates of Insurance on forms acceptable to the Commissioner. All such Certificates of Insurance shall certify (a) the issuance and effectiveness of such policies of insurance, each with the specified minimum limits (b) for insurance secured pursuant to Article 22.1.1 that the City and any other entity specified in Schedule A is an Additional Insured with coverage at least as broad as the most recent edition of ISO Forms CG 20 10, CG 20 37, and CG 20 26, as applicable: (c) in the event insurance is required pursuant to Article 22.1.6 and/or Article 22.1.7, that the City is an Additional Insured thereunder; (d) the company code issued to the insurance company by the National Association of Insurance Commissioners (the NAIC number); and (e) the number assigned to the Contract by the City. All such Certificates of Insurance shall be accompanied by either a duly executed "Certification by Broker" in the form contained in Part III of Schedule A or copies of all policies referenced in such Certificate of Insurance as certified by an authorized representative of the issuing insurance carrier. If any policy is not available at the time of submission, certified binders may be submitted until such time as the policy is available, at which time a certified copy of the policy shall be submitted.
- Documentation confirming renewals of insurance shall be submitted to the Commissioner prior to the expiration date of coverage of policies required under this Contract. Such proofs of insurance shall comply with the requirements of Articles 22.3.2 and 22.3.3.
- 22.3.5 The Contractor shall be obligated to provide the City with a copy of any policy of insurance provided pursuant to this Article 22 upon the demand for such policy by the Commissioner or the City Corporation Counsel.

#### 22.4 Operations of the Contractor:

22.4.1 The Contractor shall not commence the Work unless and until all required certificates have been submitted to and accepted by the Commissioner. Acceptance by the Commissioner of a certificate does not excuse the Contractor from securing insurance consistent with all provisions of this Article 22 or of any liability arising from its failure to do so.

- 22.4.2 The Contractor shall be responsible for providing continuous insurance coverage in the manner, form, and limits required by this Contract and shall be authorized to perform Work only during the effective period of all required coverage.
- 22.4.3 In the event that any of the required insurance policies lapse, are revoked, suspended or otherwise terminated, for whatever cause, the Contractor shall immediately stop all Work, and shall not recommence Work until authorized in writing to do so by the Commissioner. Upon quitting the Site, except as otherwise directed by the Commissioner, the Contractor shall leave all plant, materials, equipment, tools, and supplies on the Site. Contract time shall continue to run during such periods and no extensions of time will be granted. The Commissioner may also declare the Contractor in default for failure to maintain required insurance.
- 22.4.4 In the event the Contractor receives notice, from an insurance company or other person, that any insurance policy required under this Article 22 shall be cancelled or terminated (or has been cancelled or terminated) for any reason, the Contractor shall immediately forward a copy of such notice to both the Commissioner and the New York City Comptroller, attn: Office of Contract Administration, Municipal Building, One Centre Street, room 1005, New York, New York 10007. Notwithstanding the foregoing, the Contractor shall ensure that there is no interruption in any of the insurance coverage required under this Article 22.
- 22.4.5 Where notice of loss, damage, occurrence, accident, claim or suit is required under an insurance policy maintained in accordance with this Article 22, the Contractor shall notify in writing all insurance carriers that issued potentially responsive policies of any such event relating to any operations under this Contract (including notice to Commercial General Liability insurance carriers for events relating to the Contractor's own employees) no later than 20 days after such event. For any policy where the City is an Additional Insured, such notice shall expressly specify that "this notice is being given on behalf of the City of New York as Insured as well as the Named Insured." Such notice shall also contain the following information: the number of the insurance policy, the name of the named insured, the date and location of the damage, occurrence, or accident, and the identity of the persons or things injured, damaged or lost. The Contractor shall simultaneously send a copy of such notice to the City of New York c/o Insurance Claims Specialist, Affirmative Litigation Division, New York City Law Department, 100 Church Street, New York, New York 10007.
- 22.4.6 In the event of any loss, accident, claim, action, or other event that does or can give rise to a claim under any insurance policy required under this Article 22, the Contractor shall at all times fully cooperate with the City with regard to such potential or actual claim.
- 22.5 Subcontractor Insurance: In the event the Contractor requires any Subcontractor to procure insurance with regard to any operations under this Contract and requires such Subcontractor to name the Contractor as an Additional Insured thereunder, the Contractor shall ensure that the Subcontractor name the City, including its officials and employees, as an Additional Insured with coverage at least as broad as the most recent edition of ISO Form CG 20 26.
- 22.6 Wherever reference is made in Article 7 or this Article 22 to documents to be sent to the Commissioner (e.g., notices, filings, or submissions), such documents shall be sent to the address set forth in Schedule A of the General Conditions. In the event no address is set forth in Schedule A, such documents are to be sent to the Commissioner's address as provided elsewhere in this Contract.

DDC

- 22.7 Apart from damages or losses covered by insurance provided pursuant to Articles 22.1.2, 22.1.3, or 22.1.5, the Contractor waives all rights against the City, including its officials and employees, for any damages or losses that are covered under any insurance required under this Article 22 (whether or not such insurance is actually procured or claims are paid thereunder) or any other insurance applicable to the operations of the Contractor and/or its employees, agents, or Subcontractors.
- 22.8 In the event the **Contractor** utilizes a self-insurance program to satisfy any of the requirements of this Article 22, the **Contractor** shall ensure that any such self-insurance program provides the **City** with all rights that would be provided by traditional insurance under this Article 22, including but not limited to the defense and indemnification obligations that insurers are required to undertake in liability policies.
- 22.9 Materiality/Non-Waiver: The Contractor's failure to secure policies in complete conformity with this Article 22, or to give an insurance company timely notice of any sort required in this Contract or to do anything else required by this Article 22 shall constitute a material breach of this Contract. Such breach shall not be waived or otherwise excused by any action or inaction by the City at any time.
- 22.10 Pursuant to General Municipal Law Section 108, this Contract shall be void and of no effect unless Contractor maintains Workers' Compensation Insurance for the term of this Contract to the extent required and in compliance with the New York State Workers' Compensation Law.
- 22.11 Other Remedies: Insurance coverage provided pursuant to this Article 22 or otherwise shall not relieve the **Contractor** of any liability under this **Contract**, nor shall it preclude the **City** from exercising any rights or taking such other actions available to it under any other provisions of this **Contract** or **Law**.

## **ARTICLE 23. MONEY RETAINED AGAINST CLAIMS**

- 23.1 If any claim shall be made by any person or entity (including Other Contractors with the City on this Project) against the City or against the Contractor and the City for any of the following:
  - (a) An alleged loss, damage, injury, theft or vandalism of any of the kinds referred to in Articles 7 and 12, plus the reasonable costs of defending the City, which in the opinion of the Comptroller may not be paid by an insurance company (for any reason whatsoever); or
  - (b) An infringement of copyrights, patents or use of patented articles, tools, etc., as referred to in Article 57; or
  - (c) Damage claimed to have been caused directly or indirectly by the failure of the Contractor to perform the Work in strict accordance with this Contract,

the amount of such claim, or so much thereof as the Comptroller may deem necessary, may be withheld by the Comptroller, as security against such claim, from any money due hereunder. The Comptroller, in his/her discretion, may permit the Contractor to substitute other satisfactory security in lieu of the monies so withheld.

23.2 If an action on such claim is timely commenced and the liability of the City, or the Contractor, or both, shall have been established therein by a final judgment of a court of competent jurisdiction, or if such claim shall have been admitted by the Contractor to be valid, the Comptroller

shall pay such judgment or admitted claim out of the monies retained by the Comptroller under the provisions of this Article 23, and return the balance, if any, without interest, to the Contractor.

# ARTICLE 24. MAINTENANCE AND GUARANTY

- 24.1 The Contractor shall promptly repair, replace, restore or rebuild, as the Commissioner may determine, any finished Work in which defects of materials or workmanship may appear or to which damage may occur because of such defects, during the one (1) year period subsequent to the date of Substantial Completion (or use and occupancy in accordance with Article 16), except where other periods of maintenance and guaranty are provided for in Schedule A.
- 24.2 As security for the faithful performance of its obligations hereunder, the Contractor, upon filing its requisition for payment on Substantial Completion, shall deposit with the Commissioner a sum equal to one (1%) percent of the price (or the amount fixed in Schedule A of the General Conditions) in cash or certified check upon a state or national bank and trust company or a check of such bank and trust company signed by a duly authorized officer thereof and drawn to the order of the Comptroller, or obligations of the City, which the Comptroller may approve as of equal value with the sum so required.
- 24.3 In lieu of the above, the Contractor may make such security payment to the City by authorizing the Commissioner in writing to deduct the amount from the Substantial Completion payment which shall be deemed the deposit required above.
- 24.4 If the Contractor has faithfully performed all of its obligations hereunder the Commissioner shall so certify to the Comptroller within five (5) Days after the expiration of one (1) year from the date of Substantial Completion and acceptance of the Work or within thirty (30) Days after the expiration of the guarantee period fixed in the Specifications. The security payment shall be repaid to the Contractor without interest within thirty (30) Days after certification by the Commissioner to the Comptroller that the Contractor has faithfully performed all of its obligations hereunder.
- 24.5 Notice by the **Commissioner** to the **Contractor** to repair, replace, rebuild or restore such defective or damaged **Work** shall be timely, pursuant to this article, if given not later than ten (10) **Days** subsequent to the expiration of the one (1) year period or other periods provided for herein.
- 24.6 If the Contractor shall fail to repair, replace, rebuild or restore such defective or damaged Work promptly after receiving such notice, the Commissioner shall have the right to have the Work done by others in the same manner as provided for in the completion of a defaulted Contract, under Article 51.
- 24.7 If the security payment so deposited is insufficient to cover the cost of such Work, the Contractor shall be liable to pay such deficiency on demand by the Commissioner.
- 24.8 The Engineer's certificate setting forth the fair and reasonable cost of repairing, replacing, rebuilding or restoring any damaged or defective Work when performed by one other than the Contractor, shall be binding and conclusive upon the Contractor as to the amount thereof.
- 24.9 The Contractor shall obtain all manufacturers' warranties and guaranties of all equipment and materials required by this Contract in the name of the City and shall deliver same to the Commissioner. All of the City's rights and title and interest in and to said manufacturers' warranties and guaranties may be assigned by the City to any subsequent purchasers of such equipment and materials or lessees of the premises into which the equipment and materials have been installed.

# CHAPTER VI CHANGES, EXTRA WORK, AND DO CUMENTATION OF CLAIM

#### **ARTICLE 25. CHANGES**

- 25.1 Changes may be made to this Contract only as duly authorized in writing by the Commissioner in accordance with the Law and this Contract. All such changes, modifications, and amendments will become a part of the Contract. Work so ordered shall be performed by the Contractor.
- 25.2 Contract changes will be made only for Work necessary to complete the Work included in the original scope of the Contract and/or for non-material changes to the scope of the Contract. Changes are not permitted for any material alteration in the scope of Work in the Contract.
- 25.3 The Contractor shall be entitled to a price adjustment for Extra Work performed pursuant to a written change order. Adjustments to price shall be computed in one or more of the following ways:
  - 25.3.1 By applicable unit prices specified in the Contract; and/or
  - 25.3.2 By agreement of a fixed price; and/or
  - 25.3.3 By time and material records; and/or
  - 25.3.4 In any other manner approved by the CCPO.
- 25.4 All payments for change orders are subject to pre-audit by the Engineering Audit Officer and may be post-audited by the Comptroller and/or the Agency.

#### ARTICLE 26. METHODS OF PAYMENT FOR OVERRUNS AND EXTRA WORK

- 26.1 Overrun of Unit Price Item: An overrun is any quantity of a unit price item which the **Contractor** is directed to provide which is in excess of one hundred twenty-five (125%) percent of the estimated quantity for that item set forth in the bid schedule.
  - 26.1.1For any unit price item, the Contractor will be paid at the unit price bid for any quantity up to one hundred twenty-five (125%) percent of the estimated quantity for that item set forth in the bid schedule. If during the progress of the Work, the actual quantity of any unit price item required to complete the Work approaches the estimated quantity for that item, and for any reason it appears that the actual quantity of any unit price item necessary to complete the Work will exceed the estimated quantity for that item by twenty-five (25%) percent, the Contractor shall immediately notify the Engineer of such anticipated overrun. The Contractor shall not be compensated for any quantity of a unit price item provided which is in excess of one hundred twenty-five (125%) percent of the estimated quantity for that item set forth in the bid schedule without written authorization from the Engineer.
  - 26.1.2If the actual quantity of any unit price item necessary to complete the Work will exceed one hundred twenty five (125%) percent of the estimated quantity for that item set forth in the bid schedule, the City reserves the right and the Contractor agrees to negotiate a new unit price for such item. In no event shall such negotiated new unit price exceed the unit bid price. If the City and Contractor cannot agree on a new unit price, then the City shall order the Contractor and the Contractor agrees to provide additional quantities of the

item on the basis of time and material records for the actual and reasonable cost as determined under Article 26.2, but in no event at a unit price exceeding the unit price bid.

- 26.2 Extra Work: For Extra Work where payment is by agreement on a fixed price in accordance with Article 25.3.2, the price to be paid for such Extra Work shall be based on the fair and reasonable estimated cost of the items set forth below. For Extra Work where payment is based on time and material records in accordance with Article 25.3.3, the price to be paid for such Extra Work shall be the actual and reasonable cost of the items set forth below, calculated in accordance with the formula specified therein, if any.
  - 26.2.1 Necessary materials (including transportation to the Site); plus
  - 26.2.2 Necessary direct labor, including payroll taxes (subject to statutory wage caps) and supplemental benefits; plus
  - 26.2.3 Sales and personal property taxes, if any, required to be paid on materials not incorporated into such Extra Work; plus
  - Reasonable rental value of Contractor-owned (or Subcontractor-owned, as 26.2.4 applicable), necessary plant and equipment other than Small Tools, plus fuel/energy costs. Except for fuel costs for pick-up trucks which shall be reimbursed based on a consumption of five (5) gallons per shift, fuel costs shall be reimbursed based on actual costs or, in the absence of auditable documentation, the following fuel consumption formula per operating hour: (.035) x (HP rating) x (Fuel cost/gallon). Reasonable rental value is defined as the lower of either seventy-five percent of the monthly prorated rental rates established in "The AED Green Book, Rental Rates and Specifications for Construction Equipment" published by Equipment Watch (the "Green Book"), or seventy-five percent of the monthly prorated rental rates established in the "Rental Rate Blue Book for Construction Equipment" published by Equipment Watch (the "Blue Book") (the applicable Blue Book rate being for rental only without the addition of any operational costs listed in the Blue Book). The reasonable rental value is deemed to be inclusive of all operating costs except for fuel/energy consumption and equipment operator's wages/costs. For multiple shift utilization, reimbursement shall be calculated as follows: first shift shall be seventy-five (75%) percent of such rental rates; second shift shall be sixty (60%) percent of the first shift rate; and third shift shall be forty (40%) percent of the first shift rate. Equipment on standby shall be reimbursed at one-third (1/3) the prorated monthly rental rate. Contractor-owned (or Subcontractor-owned, as applicable) equipment includes equipment from rental companies affiliated with or controlled by the Contractor (or Subcontractor, as applicable), as determined by the Commissioner. In establishing cost reimbursement for non-operating Contractor-owned (or Subcontractor-owned, as applicable) equipment (scaffolding, sheeting systems, road plates, etc.), the City may restrict reimbursement to a purchase-salvage/life cycle basis if less than the computed rental costs; plus
  - 26.2.5 Necessary installation and dismantling of such plant and equipment, including transportation to and from the Site, if any, provided that, in the case of non-Contractor-owned (or non-Subcontractor-owned, as applicable) equipment rented from a third party, the cost of installation and dismantling are not allowable if such costs are included in the rental rate; plus
  - 26.2.6 Necessary fees charged by governmental entities; plus

- 26.2.7 Necessary construction-related service fees charged by non-governmental entities, such as landfill tipping fees; plus
- 26.2.8 Reasonable rental costs of non-Contractor-owned (or non-Subcontractor-owned, as applicable) necessary plant and equipment other than Small Tools, plus fuel/energy costs. Except for fuel costs for pick-up trucks which shall be reimbursed based on a consumption of five (5) gallons per shift, fuel costs shall be reimbursed based on actual costs or, in the absence of auditable documentation, the following fuel consumption formula per hour of operation: (.035) x (HP rating) x (Fuel cost/gallon). In lieu of renting, the City reserves the right to direct the purchase of non-operating equipment (scaffolding, sheeting systems, road plates, etc.), with payment on a purchase-salvage/life cycle basis, if less than the projected rental costs; plus
- 26.2.9 Workers' Compensation Insurance, and any insurance coverage expressly required by the City for the performance of the Extra Work which is different than the types of insurance required by Article 22 and Schedule A of the General Conditions. The cost of Workers' Compensation Insurance is subject to applicable payroll limitation caps and shall be based upon the carrier's Manual Rate for such insurance derived from the applicable class Loss Cost ("LC") and carrier's Lost Cost Multiplier ("LCM") approved by the New York State Department of Financial Services, and with the exception of experience rating, rate modifiers as promulgated by the New York Compensation Insurance Rating Board ("NYCIRB"); plus
- Additional costs incurred as a result of the Extra Work for performance and payment bonds; plus
- 26.2.11 Twelve percent (12%) percent of the total of items in Articles 26.2.1 through 26.2.5 as compensation for overhead, except that no percentage for overhead will be allowed on Payroll Taxes or on the premium portion of overtime pay or on sales and personal property taxes. Overhead shall include without limitation, all costs and expenses in connection with administration, management superintendence, small tools, and insurance required by Schedule A of the General Conditions other than Workers' Compensation Insurance; plus
- 26.2.12 Ten (10%) percent of the total of items in Articles 26.2.1 through 26.2.5, plus the items in Article 26.2.11, as compensation for profit, except that no percentage for profit will be allowed on Payroll Taxes or on the premium portion of overtime pay or on sales and personal property taxes; plus
- 26.2.13 Five (5%) percent of the total of items in Articles 26.2.6 through 26.2.10 as compensation for overhead and profit.
- 26.3 Where the Extra Work is performed in whole or in part by other than the Contractor's own forces pursuant to Article 26.2, the Contractor shall be paid, subject to pre-audit by the Engineering Audit Officer, the cost of such Work computed in accordance with Article 26.2 above, plus an additional allowance of five (5%) percent to cover the Contractor's overhead and profit.
- 26.4 Where a change is ordered, involving both Extra Work and omitted or reduced Contract Work, the Contract price shall be adjusted, subject to pre-audit by the EAO, in an amount based on the difference between the cost of such Extra Work and of the omitted or reduced Work.
- 26.5 Where the Contractor and the Commissioner can agree upon a fixed price for Extra Work in accordance with Article 25.3.2 or another method of payment for Extra Work in accordance with Article CITY OF NEW YORK 39

25.3.4, or for Extra Work ordered in connection with omitted Work, such method, subject to pre-audit by the EAO, may, at the option of the Commissioner, be substituted for the cost plus a percentage method provided in Article 26.2; provided, however, that if the Extra Work is performed by a Subcontractor, the Contractor shall not be entitled to receive more than an additional allowance of five (5%) percent for overhead and profit over the cost of such Subcontractor's Work as computed in accordance with Article 26.2.

#### **ARTICLE 27. RESOLUTION OF DISPUTES**

- 27.1 All disputes between the City and the Contractor of the kind delineated in this Article 27.1 that arise under, or by virtue of, this Contract shall be finally resolved in accordance with the provisions of this Article 27 and the PPB Rules. This procedure for resolving all disputes of the kind delineated herein shall be the exclusive means of resolving any such disputes.
  - 27.1.1 This Article 27 shall not apply to disputes concerning matters dealt with in other sections of the **PPB** Rules, or to disputes involving patents, copyrights, trademarks, or trade secrets (as interpreted by the courts of New York State) relating to proprietary rights in computer software.
  - 27.1.2 This Article 27 shall apply only to disputes about the scope of Work delineated by the Contract, the interpretation of Contract documents, the amount to be paid for Extra Work or disputed work performed in connection with the Contract, the conformity of the Contractor's Work to the Contract, and the acceptability and quality of the Contractor's Work; such disputes arise when the Engineer, Resident Engineer, Engineering Audit Officer, or other designee of the Commissioner makes a determination with which the Contractor disagrees.
- 27.2 All determinations required by this Article 27 shall be made in writing clearly stated, with a reasoned explanation for the determination based on the information and evidence presented to the party making the determination. Failure to make such determination within the time required by this Article 27 shall be deemed a non-determination without prejudice that will allow application to the next level.
- 27.3 During such time as any dispute is being presented, heard, and considered pursuant to this Article 27, the Contract terms shall remain in force and the Contractor shall continue to perform Work as directed by the ACCO or the Engineer. Failure of the Contractor to continue Work as directed shall constitute a waiver by the Contractor of its claim.

#### 27.4 Presentation of Disputes to Commissioner.

Notice of Dispute and Agency Response. The Contractor shall present its dispute in writing ("Notice of Dispute") to the Commissioner within thirty (30) Days of receiving written notice of the determination or action that is the subject of the dispute. This notice requirement shall not be read to replace any other notice requirements contained in the Contract. The Notice of Dispute shall include all the facts, evidence, documents, or other basis upon which the Contractor relies in support of its position, as well as a detailed computation demonstrating how any amount of money claimed by the Contractor in the dispute was arrived at. Within thirty (30) Days after receipt of the detailed written submission comprising the complete Notice of Dispute, the Engineer, Resident Engineer, Engineering Audit Officer, or other designee of the Commissioner shall submit to the Commissioner all materials he or she deems pertinent to the dispute. Following initial submissions to the Commissioner, either party may demand of the other the production of any document or other material the demanding party believes may be relevant to the dispute. The requested party shall produce all relevant materials that are not otherwise

protected by a legal privilege recognized by the courts of New York State. Any question of relevancy shall be determined by the **Commissioner** whose decision shall be final. Willful failure of the **Contractor** to produce any requested material whose relevancy the **Contractor** has not disputed, or whose relevancy has been affirmatively determined, shall constitute a waiver by the **Contractor** of its claim.

- 27.4.1 Commissioner Inquiry. The Commissioner shall examine the material and may, in his or her discretion, convene an informal conference with the Contractor, the ACCO, and the Engineer, Resident Engineer, Engineering Audit Officer, or other designee of the Commissioner to resolve the issue by mutual consent prior to reaching a determination. The Commissioner may seek such technical or other expertise as he or she shall deem appropriate, including the use of neutral mediators, and require any such additional material from either or both parties as he or she deems fit. The Commissioner's ability to render, and the effect of, a decision hereunder shall not be impaired by any negotiations in connection with the dispute presented, whether or not the Commissioner participated therein. The Commissioner may or, at the request of any party to the dispute, shall compel the participation of any Other Contractor with a contract related to the Work of this Contract, and that Contractor shall be bound by the decision of the Commissioner. Any Other Contractor thus brought into the dispute resolution proceeding shall have the same rights and obligations under this Article 27 as the Contractor initiating the dispute.
- 27.4.2 Commissioner Determination. Within thirty (30) Days after the receipt of all materials and information, or such longer time as may be agreed to by the parties, the Commissioner shall make his or her determination and shall deliver or send a copy of such determination to the Contractor, the ACCO, and Engineer, Resident Engineer, Engineering Audit Officer, or other designee of the Commissioner, as applicable, together with a statement concerning how the decision may be appealed.
- 27.4.3 Finality of Commissioner's Decision. The Commissioner's decision shall be final and binding on all parties, unless presented to the Contract Dispute Resolution Board pursuant to this Article 27. The City may not take a petition to the Contract Dispute Resolution Board. However, should the Contractor take such a petition, the City may seek, and the Contract Dispute Resolution Board may render, a determination less favorable to the Contractor and more favorable to the City than the decision of the Commissioner.
- 27.5 Presentation of Dispute to the Comptroller. Before any dispute may be brought by the Contractor to the Contract Dispute Resolution Board, the Contractor must first present its claim to the Comptroller for his or her review, investigation, and possible adjustment.
  - 27.5.1 Time, Form, and Content of Notice. Within thirty (30) Days of its receipt of a decision by the Commissioner, the Contractor shall submit to the Comptroller and to the Commissioner a Notice of Claim regarding its dispute with the Agency. The Notice of Claim shall consist of (i) a brief written statement of the substance of the dispute, the amount of money, if any, claimed and the reason(s) the Contractor contends the dispute was wrongly decided by the Commissioner; (ii) a copy of the written decision of the Commissioner; and (iii) a copy of all materials submitted by the Contractor to the Agency, including the Notice of Dispute. The Contractor may not present to the Comptroller any material not presented to the Commissioner, except at the request of the Comptroller.
  - 27.5.2 Response. Within thirty (30) Days of receipt of the Notice of Claim, the Agency shall make available to the Comptroller a copy of all material submitted by the Agency to the Commissioner in connection with the dispute. The Agency may not present to the

Comptroller any material not presented to the Commissioner except at the request of the Comptroller.

- 27.5.3 Comptroller Investigation. The Comptroller may investigate the claim in dispute and, in the course of such investigation, may exercise all powers provided in Sections 7-201 and 7-203 of the Administrative Code. In addition, the Comptroller may demand of either party, and such party shall provide, whatever additional material the Comptroller deems pertinent to the claim, including original business records of the Contractor. Willful failure of the Contractor to produce within fifteen (15) Days any material requested by the Comptroller shall constitute a waiver by the Contractor of its claim. The Comptroller may also schedule an informal conference to be attended by the Contractor, Agency representatives, and any other personnel desired by the Comptroller.
- 27.5.4 Opportunity of Comptroller to Compromise or Adjust Claim. The Comptroller shall have forty-five (45) Days from his or her receipt of all materials referred to in Article 27.5.3 to investigate the disputed claim. The period for investigation and compromise may be further extended by agreement between the Contractor and the Comptroller, to a maximum of ninety (90) Days from the Comptroller's receipt of all materials. The Contractor may not present its petition to the Contract Dispute Resolution Board until the period for investigation and compromise delineated in this Article 27.5.4 has expired. In compromising or adjusting any claim hereunder, the Comptroller may not revise or disregard the terms of the Contract between the parties.
- 27.6 Contract Dispute Resolution Board. There shall be a Contract Dispute Resolution Board composed of:
  - 27.6.1 The chief administrative law judge of the Office of Administrative Trials and Hearings (OATH) or his/her designated OATH administrative law judge, who shall act as chairperson, and may adopt operational procedures and issue such orders consistent with this Article 27 as may be necessary in the execution of the Contract Dispute Resolution Board's functions, including, but not limited to, granting extensions of time to present or respond to submissions;
  - 27.6.2 The CCPO or his/her designee; any designee shall have the requisite background to consider and resolve the merits of the dispute and shall not have participated personally and substantially in the particular matter that is the subject of the dispute or report to anyone who so participated; and
  - 27.6.3 A person with appropriate expertise who is not an employee of the City. This person shall be selected by the presiding administrative law judge from a prequalified panel of individuals, established and administered by OATH with appropriate background to act as decision-makers in a dispute. Such individual may not have a contract or dispute with the City or be an officer or employee of any company or organization that does, or regularly represents persons, companies, or organizations having disputes with the City.
- 27.7 Petition to the Contract Dispute Resolution Board. In the event the claim has not been settled or adjusted by the Comptroller within the period provided in this Article 27, the Contractor, within thirty (30) Days thereafter, may petition the Contract Dispute Resolution Board to review the Commissioner's determination.
- 27.7.1 Form and Content of Petition by Contractor. The Contractor shall present its dispute to the Contract Dispute Resolution Board in the form of a petition, which shall CITY OF NEW YORK

  DDC

  42 STANDARD CONSTRUCTION CONTRACT

  December 2013

include (i) a brief written statement of the substance of the dispute, the amount of money, if any, claimed, and the reason(s) the **Contractor** contends the dispute was wrongly decided by the **Commissioner**; (ii) a copy of the written Decision of the **Commissioner**, (iii) copies of all materials submitted by the **Contractor** to the Agency; (iv) a copy of the written decision of the **Comptroller**, if any, and (v) copies of all correspondence with, or written material submitted by the **Contractor**, to the **Comptroller**. The **Contractor** shall concurrently submit four (4) complete sets of the Petition: one set to the **City** Corporation Counsel (Attn: Commercial and Real Estate Litigation Division) and three (3) sets to the Contract Dispute Resolution Board at OATH's offices with proof of service on the **City** Corporation Counsel. In addition, the **Contractor** shall submit a copy of the written statement of the substance of the dispute, cited in (i) above, to both the **Commissioner** and the **Comptroller**.

- 27.7.2 Agency Response. Within thirty (30) Days of its receipt of the Petition by the City Corporation Counsel, the Agency shall respond to the brief written statement of the Contractor and make available to the Contract Dispute Resolution Board all material it submitted to the Commissioner and Comptroller. Three (3) complete copies of the Agency response shall be provided to the Contract Dispute Resolution Board and one to the Contractor. Extensions of time for submittal of the Agency response shall be given as necessary upon a showing of good cause or, upon consent of the parties, for an initial period of up to thirty (30) Days.
- 27.7.3 Further Proceedings. The Contract Dispute Resolution Board shall permit the Contractor to present its case by submission of memoranda, briefs, and oral argument. The Contract Dispute Resolution Board shall also permit the Agency to present its case in response to the Contractor by submission of memoranda, briefs, and oral argument. If requested by the City Corporation Counsel, the Comptroller shall provide reasonable assistance in the preparation of the Agency's case. Neither the Contractor nor the Agency may support its case with any documentation or other material that was not considered by the Comptroller, unless requested by the Contract Dispute Resolution Board. The Contract Dispute Resolution Board, in its discretion, may seek such technical or other expert advice as it shall deem appropriate and may seek, on its own or upon application of a party, any such additional material from any party as it deems fit. The Contract Dispute Resolution Board, in its discretion, may combine more than one dispute between the parties for concurrent resolution.
- 27.7.4 Contract Dispute Resolution Board Determination. Within forty-five (45) Days of the conclusion of all written submissions and oral arguments, the Contract Dispute Resolution Board shall render a written decision resolving the dispute. In an unusually complex case, the Contract Dispute Resolution Board may render its decision in a longer period, not to exceed ninety (90) Days, and shall so advise the parties at the commencement of this period. The Contract Dispute Resolution Board's decision must be consistent with the terms of the Contract. Decisions of the Contract Dispute Resolution Board shall only resolve matters before the Contract Dispute Resolution Board and shall not have precedential effect with respect to matters not before the Contract Dispute Resolution Board.
- 27.7.5 Notification of Contract Dispute Resolution Board Decision. The Contract Dispute Resolution Board shall send a copy of its decision to the Contractor, the ACCO, the Engineer, the Comptroller, the City Corporation Counsel, the CCPO, and the PPB. A decision in favor of the Contractor shall be subject to the prompt payment provisions of the PPB Rules. The Required Payment Date shall be thirty (30) Days after the date the parties are formally notified of the Contract Dispute Resolution Board's decision.

27.7.6 Finality of Contract Dispute Resolution Board Decision. The Contract Dispute Resolution

Board's decision shall be final and binding on all parties. Any party may seek review of the Contract Dispute Resolution Board's decision solely in the form of a challenge, filed within four (4) months of the date of the Contract Dispute Resolution Board's decision, in a court of competent jurisdiction of the State of New York, County of New York pursuant to Article 78 of the Civil Practice Law and Rules. Such review by the court shall be limited to the question of whether or not the Contract Dispute Resolution Board's decision was made in violation of lawful procedure, was affected by an error of Law, or was arbitrary and capricious or an abuse of discretion. No evidence or information shall be introduced or relied upon in such proceeding that was not presented to the Contract Dispute Resolution Board in accordance with this Article 27.

Any termination, cancellation, or alleged breach of the Contract prior to or during the pendency of any proceedings pursuant to this Article 27 shall not affect or impair the ability of the Commissioner or Contract Dispute Resolution Board to make a binding and final decision pursuant to this Article 27.

# ARTICLE 28. RECORD KEEPING FOR EXTRA OR DISPUTED WORK OR WORK ON A TIME & MATERIALS BASIS

- 28.1 While the Contractor or any of its Subcontractors is performing Work on a time and material basis or Extra Work on a time and material basis ordered by the Commissioner under Article 25, or where the Contractor believes that it or any of its Subcontractors is performing Extra Work but a final determination by Agency has not been made, or the Contractor or any of its Subcontractors is performing disputed Work (whether on or off the Site), or complying with a determination or order under protest in accordance with Articles 11, 27, and 30, in each such case the Contractor shall furnish the Resident Engineer daily with three (3) copies of written statements signed by the Contractor's representative at the Site showing:
  - 28.1.1 The name, trade, and number of each worker employed on such Work or engaged in complying with such determination or order, the number of hours employed, and the character of the Work each is doing; and
  - 28.1.2 The nature and quantity of any materials, plant and equipment furnished or used in connection with the performance of such **Work** or compliance with such determination or order, and from whom purchased or rented.
- 28.2 A copy of such statement will be countersigned by the Resident Engineer, noting thereon any items not agreed to or questioned, and will be returned to the Contractor within two (2) Days after submission.
- 28.3 The Contractor and its Subcontractors, when required by the Commissioner, or the Comptroller, shall also produce for inspection, at the office of the Contractor or Subcontractor, any and all of its books, bid documents, financial statements, vouchers, records, daily job diaries and reports, and cancelled checks, and any other documents relating to showing the nature and quantity of the labor, materials, plant and equipment actually used in the performance of such Work, or in complying with such determination or order, and the amounts expended therefor, and shall permit the Commissioner and the Comptroller to make such extracts therefrom, or copies thereof, as they or either of them may desire.
- 28.4 In connection with the examination provided for herein, the Commissioner, upon demand therefor, will produce for inspection by the Contractor such records as the Agency may have with CITY OF NEW YORK

  44 STANDARD CONSTRUCTION CONTRACT

  DDC

  December 2013

respect to such Extra Work or disputed Work performed under protest pursuant to order of the Commissioner, except those records and reports which may have been prepared for the purpose of determining the accuracy and validity of the Contractor's claim.

28.5 Failure to comply strictly with these requirements shall constitute a waiver of any claim for extra compensation or damages on account of the performance of such Work or compliance with such determination or order.

#### ARTICLE 29. OMITTED WORK

- 29.1 If any Contract Work in a lump sum Contract, or if any part of a lump sum item in a unit price, lump sum, or percentage-bid Contract is omitted by the Commissioner pursuant to Article 33, the Contract price, subject to audit by the EAO, shall be reduced by a pro rata portion of the lump sum bid amount based upon the percent of Work omitted subject to Article 29.4. For the purpose of determining the pro rata portion of the lump sum bid amount, the bid breakdown submitted in accordance with Article 41 shall be considered, but shall not be the determining factor.
- 29.2 If the whole of a lump sum item or units of any other item is so omitted by the **Commissioner** in a unit price, lump sum, or percentage-bid **Contract**, then no payment will be made therefor except as provided in Article 29.4.
- 29.3 For units that have been ordered but are only partially completed, the unit price shall be reduced by a pro rata portion of the unit price bid based upon the percentage of **Work** omitted subject to Article 29.4.
- 29.4 In the event the Contractor, with respect to any omitted Work, has purchased any non-cancelable material and/or equipment that is not capable of use except in the performance of this Contract and has been specifically fabricated for the sole purpose of this Contract, but not yet incorporated into the Work, the Contractor shall be paid for such material and/or equipment in accordance with Article 64.2.1(b); provided, however, such payment is contingent upon the Contractor's delivery of such material and/or equipment in acceptable condition to a location designated by the City.
- 29.5 The Contractor agrees to make no claim for damages or for loss of overhead and profit with regard to any omitted Work.

# ARTICLE 30. NOTICE AND DOCUMENTATION OF COSTS AND DAMAGES; PRODUCTION OF FINANCIAL RECORDS

30.1 If the Contractor shall claim to be sustaining damages by reason of any act or omission of the City or its agents, it shall submit to the Commissioner within forty-five (45) Days from the time such damages are first incurred, and every thirty (30) Days thereafter for as long as such damages are incurred, verified statements of the details and the amounts of such damages, together with documentary evidence of such damages. The Contractor may submit any of the above statements within such additional time as may be granted by the Commissioner in writing upon written request therefor. Failure of the Commissioner to respond in writing to a written request for additional time within thirty (30) Days shall be deemed a denial of the request. On failure of the Contractor to strictly comply with the foregoing provisions, such claims shall be deemed waived and no right to recover on such claims shall exist. Damages that the Contractor may claim in any action or dispute resolution procedure arising under or by reason of this Contract shall not be different from or in excess of the statements and documentation made pursuant to this Article 30.

- 30.2 In addition to the foregoing statements, the Contractor shall, upon notice from the Commissioner, produce for examination at the Contractor's office, by the Engineer, Architect or Project Manager, all of its books of account, bills, invoices, payrolls, subcontracts, time books, daily reports, bank deposit books, bank statements, check books, and cancelled checks, showing all of its acts and transactions in connection with or relating to or arising by reason of this Contract, and submit itself and persons in its employment, for examination under oath by any person designated by the Commissioner or Comptroller to investigate claims made or disputes against the City under this Contract. At such examination, a duly authorized representative of the Contractor may be present.
- 30.3 In addition to the statements required under Article 28 and this Article 30, the Contractor and/or its Subcontractor shall, within thirty (30) Days upon notice from the Commissioner or Comptroller, produce for examination at the Contractor's and/or Subcontractor's office, by a representative of either the Commissioner or Comptroller, all of its books of account, bid documents, financial statements, accountant workpapers, bills, invoices, payrolls, subcontracts, time books, daily reports, bank deposit books, bank statements, check books, and cancelled checks, showing all of its acts and transactions in connection with or relating to or arising by reason of this Contract. Further, the Contractor and/or its Subcontractor shall submit any person in its employment, for examination under oath by any person designated by the Commissioner or Comptroller to investigate claims made or disputes against the City under this Contract. At such examination, a duly authorized representative of the Contractor may be present.
- 30.4 Unless the information and examination required under Article 30.3 is provided by the Contractor and/or its Subcontractor upon thirty (30) Days' notice from the Commissioner or Comptroller, or upon the Commissioner's or Comptroller's written authorization to extend the time to comply, the City shall be released from all claims arising under, relating to or by reason of this Contract, except for sums certified by the Commissioner to be due under the provisions of this Contract. It is further stipulated and agreed that no person has the power to waive any of the foregoing provisions and that in any action or dispute resolution procedure against the City to recover any sum in excess of the sums certified by the Commissioner to be due under or by reason of this Contract, the Contractor must allege in its complaint and prove, at trial or during such dispute resolution procedure, compliance with the provisions of this Article 30.
- 30.5 In addition, after the commencement of any action or dispute resolution procedure by the Contractor arising under or by reason of this Contract, the City shall have the right to require the Contractor to produce for examination under oath, up until the trial of the action or hearing before the Contract Dispute Resolution Board, the books and documents described in Article 30.3 and submit itself and all persons in its employ for examination under oath. If this Article 30 is not complied with as required, then the Contractor hereby consents to the dismissal of the action or dispute resolution procedure.

# CHAPTER VII POWERS OF THE RESIDENT ENGINEER, THE ENGINEER OR ARCHITECT AND THE COMMISSIONER

#### ARTICLE 31. THE RESIDENT ENGINEER

31.1 The **Resident Engineer** shall have the power to inspect, supervise, and control the performance of the **Work**, subject to review by the **Commissioner**. The **Resident Engineer** shall not, however, have the power to issue an **Extra Work** order, except as specifically designated in writing by the **Commissioner**.

# ARTICLE 32. THE ENGINEER OR ARCHITECT OR PROJECT MANAGER

- 32.1 The Engineer or Architect or Project Manager, in addition to those matters elsewhere herein delegated to the Engineer and expressly made subject to his/her determination, direction or approval, shall have the power, subject to review by the Commissioner:
  - 32.1.1 To determine the amount, quality, and location of the Work to be paid for hereunder; and
  - 32.1.2 To determine all questions in relation to the Work, to interpret the Contract Drawings, Specifications, and Addenda, and to resolve all patent inconsistencies or ambiguities therein; and
  - 32.1.3 To determine how the Work of this Contract shall be coordinated with Work of Other Contractors engaged simultaneously on this Project, including the power to suspend any part of the Work, but not the whole thereof; and
  - 32.1.4 To make minor changes in the Work as he/she deems necessary, provided such changes do not result in a net change in the cost to the City or to the Contractor of the Work to be done under the Contract; and
  - 32.1.5 To amplify the Contract Drawings, add explanatory information and furnish additional Specifications and drawings, consistent with this Contract.
- 32.2 The foregoing enumeration shall not imply any limitation upon the power of the Engineer or Architect or Project Manager, for it is the intent of this Contract that all of the Work shall generally be subject to his/her determination, direction, and approval, except where the determination, direction or approval of someone other than the Engineer or Architect or Project Manager is expressly called for herein.
- 32.3 The Engineer or Architect or Project Manager shall not, however, have the power to issue an Extra Work order, except as specifically designated in writing by the Commissioner.

#### **ARTICLE 33. THE COMMISSIONER**

- 33.1 The **Commissioner**, in addition to those matters elsewhere herein expressly made subject to his/her determination, direction or approval, shall have the power:
  - 33.1.1 To review and make determinations on any and all questions in relation to this Contract and its performance; and
  - 33.1.2 To modify or change this Contract so as to require the performance of Extra Work (subject, however, to the limitations specified in Article 25) or the omission of Contract Work; and
  - 33.1.3 To suspend the whole or any part of the **Work** whenever in his/her judgment such suspension is required:
    - 33.1.3(a) In the interest of the City generally; or

- 33.1.3(b) To coordinate the **Work** of the various contractors engaged on this **Project** pursuant to the provisions of Article 12; or
- 33.1.3(c) To expedite the completion of the entire **Project** even though the completion of this particular **Contract** may thereby be delayed.

#### **ARTICLE 34. NO ESTOPPEL**

- 34.1 Neither the City nor any Agency, official, agent or employee thereof, shall be bound, precluded or estopped by any determination, decision, approval, order, letter, payment or certificate made or given under or in connection with this Contract by the City, the Commissioner, the Engineer, the Resident Engineer, or any other official, agent or employee of the City, either before or after the final completion and acceptance of the Work and payment therefor:
  - 34.1.1 From showing the true and correct classification, amount, quality or character of the Work actually done; or that any such determination, decision, order, letter, payment or certificate was untrue, incorrect or improperly made in any particular, or that the Work, or any part thereof, does not in fact conform to the requirements of this Contract; and
  - 34.1.2 From demanding and recovering from the Contractor any overpayment made to it, or such damages as the City may sustain by reason of the Contractor's failure to perform each and every part of its Contract.

#### CHAPTER VIII LABOR PROVISIONS

#### **ARTICLE 35. EMPLOYEES**

- 35.1 The Contractor and its Subcontractors shall not employ on the Work:
  - 35.1.1 Anyone who is not competent, faithful and skilled in the Work for which he/she shall be employed; and whenever the Commissioner shall inform the Contractor, in writing, that any employee is, in his/her opinion, incompetent, unfaithful or disobedient, that employee shall be discharged from the Work forthwith, and shall not again be employed upon it; or
  - 35.1.2 Any labor, materials or means whose employment, or utilization during the course of this Contract, may tend to or in any way cause or result in strikes, work stoppages, delays, suspension of Work or similar troubles by workers employed by the Contractor or its Subcontractors, or by any of the trades working in or about the buildings and premises where Work is being performed under this Contract, or by Other Contractors or their Subcontractors pursuant to other contracts, or on any other building or premises owned or operated by the City, its Agencies, departments, boards or authorities. Any violation by the Contractor of this requirement may, upon certification of the Commissioner, be considered as proper and sufficient cause for declaring the Contractor to be in default, and for the City to take action against it as set forth in Chapter X of this Contract, or such other article of this Contract as the Commissioner may deem proper; or
- 35.1.3 In accordance with Section 220.3-e of the Labor Law of the State of New York (hereinafter "Labor Law"), the Contractor and its Subcontractors shall not employ on the Work any apprentice, unless he/she is a registered individual, under a bona fide program CITY OF NEW YORK

  48 STANDARD CONSTRUCTION CONTRACT December 2013

registered with the New York State Department of Labor. The allowable ratio of apprentices to journey-level workers in any craft classification shall not be greater than the ratio permitted to the Contractor as to its work force on any job under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered as above, shall be paid the wage rate determined by the Comptroller of the City for the classification of Work actually performed. The Contractor or Subcontractor will be required to furnish written evidence of the registration of its program and apprentices as well as all the appropriate ratios and wage rates, for the area of the construction prior to using any apprentices on the Contract Work.

- 35.2 If the total cost of the Work under this Contract is at least two hundred fifty thousand (\$250,000) dollars, all laborers, workers, and mechanics employed in the performance of the Contract on the public work site, either by the Contractor, Subcontractor or other person doing or contracting to do the whole or a part of the Work contemplated by the Contract, shall be certified prior to performing any Work as having successfully completed a course in construction safety and health approved by the United States Department of Labor's Occupational Safety and Health Administration that is at least ten (10) hours in duration.
- 35.3 In accordance with Local Law Nos. 30-2012 and 33-2012, codified at sections 6-132 and 12-113 of the Administrative Code, respectively,
  - 35.3.1 The Contractor shall not take an adverse personnel action with respect to an officer or employee in retaliation for such officer or employee making a report of information concerning conduct which such officer or employee knows or reasonably believes to involve corruption, criminal activity, conflict of interest, gross mismanagement or abuse of authority by any officer or employee relating to this Contract to (a) the Commissioner of the Department of Investigation, (b) a member of the New York City Council, the Public Advocate, or the Comptroller, or (c) the CCPO, ACCO, Agency head, or Commissioner.
  - 35.3.2 If any of the **Contractor**'s officers or employees believes that he or she has been the subject of an adverse personnel action in violation of Article 35.3.1, he or she shall be entitled to bring a cause of action against the **Contractor** to recover all relief necessary to make him or her whole. Such relief may include but is not limited to: (a) an injunction to restrain continued retaliation, (b) reinstatement to the position such employee would have had but for the retaliation or to an equivalent position, (c) reinstatement of full fringe benefits and seniority rights, (d) payment of two times back pay, plus interest, and (e) compensation for any special damages sustained as a result of the retaliation, including litigation costs and reasonable attorney's fees.
  - 35.3.3 The Contractor shall post a notice provided by the City in a prominent and accessible place on any site where work pursuant to the Contract is performed that contains information about:
    - 35.3.3(a) how its employees can report to the New York City Department of Investigation allegations of fraud, false claims, criminality or corruption arising out of or in connection with the Contract; and
    - 35.3.3(b) the rights and remedies afforded to its employees under Administrative Code sections 7-805 (the New York City False Claims Act) and 12-113 (the Whistleblower Protection Expansion Act) for lawful acts taken in connection with the reporting of allegations of fraud, false claims, criminality or corruption in connection with the **Contract**.

- 35.3.4 For the purposes of this Article 35.3, "adverse personnel action" includes dismissal, demotion, suspension, disciplinary action, negative performance evaluation, any action resulting in loss of staff, office space, equipment or other benefit, failure to appoint, failure to promote, or any transfer or assignment or failure to transfer or assign against the wishes of the affected officer or employee.
- 35.3.5 This Article 35.3 is applicable to all of the Contractor's Subcontractors having subcontracts with a value in excess of \$100,000; accordingly, the Contractor shall include this rider in all subcontracts with a value a value in excess of \$100,000.
- 35.4 Article 35.3 is not applicable to this **Contract** if it is valued at \$100,000 or less. Articles 35.3.1, 35.3.2, 35.3.4, and 35.3.5 are not applicable to this **Contract** if it was solicited pursuant to a finding of an emergency.

# **ARTICLE 36. NO DISCRIMINATION**

- 36.1 The Contractor specifically agrees, as required by Labor Law Section 220-e, as amended, that:
  - 36.1.1 In the hiring of employees for the performance of Work under this Contract or any subcontract hereunder, neither the Contractor, Subcontractor, nor any person acting on behalf of such Contractor or Subcontractor, shall by reason of race, creed, color or national origin discriminate against any citizen of the State of New York who is qualified and available to perform the Work to which the employment relates;
  - 36.1.2 Neither the Contractor, Subcontractor, nor any person on its behalf shall, in any manner, discriminate against or intimidate any employee hired for the performance of Work under this Contract on account of race, creed, color or national origin;
  - 36.1.3 There may be deducted from the amount payable to the Contractor by the City under this Contract a penalty of fifty (\$50.00) dollars for each person for each Day during which such person was discriminated against or intimidated in violation of the provisions of this Contract; and
  - 36.1.4 This Contract may be cancelled or terminated by the City and all moneys due or to become due hereunder may be forfeited, for a second or any subsequent violation of the terms or conditions of this Article 36.
  - 36.1.5 This Article 36 covers all construction, alteration and repair of any public building or public work occurring in the State of New York and the manufacture, sale, and distribution of materials, equipment, and supplies to the extent that such operations are performed within the State of New York pursuant to this **Contract**.
- 36.2 The Contractor specifically agrees, as required by Section 6-108 of the Administrative Code, as amended, that:
  - 36.2.1 It shall be unlawful for any person engaged in the construction, alteration or repair of buildings or engaged in the construction or repair of streets or highways pursuant to a **Contract** with the **City** or engaged in the manufacture, sale or distribution of materials, equipment or supplies pursuant to a **Contract** with the **City** to refuse to employ or to refuse to continue in any employment any person on account of the race, color or creed of such person.

- 36.2.2 It shall be unlawful for any person or any servant, agent or employee of any person, described in Article 36.1.2, to ask, indicate or transmit, orally or in writing, directly or indirectly, the race, color or creed or religious affiliation of any person employed or seeking employment from such person, firm or corporation.
- 36.2.3 Breach of the foregoing provisions shall be deemed a violation of a material provision of this Contract.
- 36.2.4 Any person, or the employee, manager or owner of or officer of such firm or corporation who shall violate any of the provisions of this Article 36.2 shall, upon conviction thereof, be punished by a fine of not more than one hundred (\$100.00) dollars or by imprisonment for not more than thirty (30) Days, or both.
- 36.3 This Contract is subject to the requirements of Executive Order No. 50 (1980) ("E.O. 50"), as revised, and the rules and regulations promulgated thereunder. No contract will be awarded unless and until these requirements have been complied with in their entirety. By signing this Contract, the Contractor agrees that it:
  - 36.3.1 Will not engage in any unlawful discrimination against any employee or applicant for employment because of race, creed, color, national origin, sex, age, disability, marital status or sexual orientation with respect to all employment decisions including, but not limited to, recruitment, hiring, upgrading, demotion, downgrading, transfer, training, rates of pay or other forms of compensation, layoff, termination, and all other terms and conditions of employment; and
  - 36.3.2 Will not engage in any unlawful discrimination in the selection of **Subcontractors** on the basis of the owner's race, color, creed, national origin, sex, age, disability, marital status or sexual orientation; and
  - 36.3.3 Will state in all solicitations or advertisements for employees placed by or on behalf of the Contractor that all qualified applicants will receive consideration for employment without unlawful discrimination based on race, creed, color, national origin, sex, age, citizens status, disability, marital status, sexual orientation, or that it is an equal employment opportunity employer; and
  - 36.3.4 Will send to each labor organization or representative of workers with which it has a collective bargaining agreement or other contract or memorandum of understanding, written notification of its equal employment opportunity commitments under E.O. 50 and the rules and regulations promulgated thereunder; and
  - 36.3.5 Will furnish, before the award of the Contract, all information and reports, including an employment report, that are required by E.O. 50, the rules and regulations promulgated thereunder, and orders of the City Department of Business Services, Division of Labor Services (DLS) and will permit access to its books, records, and accounts by the DLS for the purposes of investigation to ascertain compliance with such rules, regulations, and orders.
- 36.4 The Contractor understands that in the event of its noncompliance with the nondiscrimination clauses of this Contract or with any of such rules, regulations, or orders, such noncompliance shall constitute a material breach of this Contract and noncompliance with E.O. 50 and the rules and regulations promulgated thereunder. After a hearing held pursuant to the rules of the DLS, the Director of the DLS may direct the Commissioner to impose any or all of the following sanctions:

- 36.4.1 Disapproval of the Contractor; and/or
- 36.4.2 Suspension or termination of the Contract; and/or
- 36.4.3 Declaring the Contractor in default; and/or
- 36.4.4 In lieu of any of the foregoing sanctions, the Director of the DLS may impose an employment program.

In addition to any actions taken under this Contract, failure to comply with E.O. 50 and the rules and regulations promulgated thereunder, in one or more instances, may result in a City Agency declaring the Contractor to be non-responsible in future procurements. The Contractor further agrees that it will refrain from entering into any Contract or Contract modification subject to E.O. 50 and the rules and regulations promulgated thereunder with a Subcontractor who is not in compliance with the requirements of E.O. 50 and the rules and regulations promulgated thereunder.

- 36.5 The Contractor specifically agrees, as required by Section 6-123 of the Administrative Code, that:
  - 36.5.1 The Contractor will not engage in any unlawful discriminatory practice in violation of Title 8 of the Administrative Code; and
  - 36.5.2 Any failure to comply with this Article 36.5 may subject the Contractor to the remedies set forth in Section 6-123 of the Administrative Code, including, where appropriate, sanctions such as withholding of payment, imposition of an employment program, finding the Contractor to be in default, cancellation of the Contract, or any other sanction or remedy provided by Law or Contract.

## **ARTICLE 37. LABOR LAW REQUIREMENTS**

- 37.1 The Contractor shall strictly comply with all applicable provisions of the Labor Law, as amended. Such compliance is a material term of this Contract.
- 37.2 The Contractor specifically agrees, as required by Labor Law Sections 220 and 220-d, as amended, that:
  - 37.2.1 Hours of Work: No laborer, worker, or mechanic in the employ of the Contractor, Subcontractor or other person doing or contracting to do the whole or a part of the Work contemplated by this Contract shall be permitted or required to work more than eight (8) hours in any one (1) Day, or more than five (5) Days in any one (1) week, except as provided in the Labor Law and in cases of extraordinary emergency including fire, flood, or danger to life or property, or in the case of national emergency when so proclaimed by the President of the United States of America.
  - 37.2.2 In situations in which there are not sufficient laborers, workers, and mechanics who may be employed to carry on expeditiously the Work contemplated by this Contract as a result of such restrictions upon the number of hours and Days of labor, and the immediate commencement or prosecution or completion without undue delay of the Work is necessary for the preservation of the Site and/or for the protection of the life and limb of the persons using the same, such laborers, workers, and mechanics shall be permitted or required to

work more than eight (8) hours in any one (1) Day; or five (5) Days in any one (1) week; provided, however, that upon application of any Contractor, the Commissioner shall have first certified to the Commissioner of Labor of the State of New York (hereinafter "Commissioner of Labor") that such public Work is of an important nature and that a delay in carrying it to completion would result in serious disadvantage to the public; and provided, further, that such Commissioner of Labor shall have determined that such an emergency does in fact exist as provided in Labor Law Section 220.2.

- 37.2.3 Failure of the Commissioner to make such a certification to the Commissioner of Labor shall not entitle the Contractor to damages for delay or for any cause whatsoever.
- 37.2.4 Prevailing Rate of Wages: The wages to be paid for a legal day's Work to laborers, workers, or mechanics employed upon the Work contemplated by this Contract or upon any materials to be used thereon shall not be less than the "prevailing rate of wage" as defined in Labor Law Section 220, and as fixed by the Comptroller in the attached Schedule of Wage Rates and in updated schedules thereof. The prevailing wage rates and supplemental benefits to be paid are those in effect at the time the Work is being performed.
- 37.2.5 Requests for interpretation or correction in the Information for Bidders includes all requests for clarification of the classification of trades to be employed in the performance of the Work under this Contract. In the event that a trade not listed in the Contract is in fact employed during the performance of this Contract, the Contractor shall be required to obtain from the Agency the prevailing wage rates and supplementary benefits for the trades used and to complete the performance of this Contract at the price at which the Contract was awarded.
- 37.2.6 Minimum Wages: Except for employees whose wage is required to be fixed pursuant to Labor Law Section 220, all persons employed by the Contractor and any Subcontractor in the manufacture or furnishing of the supplies, materials, or equipment, or the furnishing of work, labor, or services, used in the performance of this Contract, shall be paid, without subsequent deduction or rebate unless expressly authorized by Law, not less than the sum mandated by Law.
- 37.3 Working Conditions: No part of the Work, labor or services shall be performed or rendered by the Contractor in any plants, factories, buildings or surroundings or under working conditions which are unsanitary or hazardous or dangerous to the health and safety of employees engaged in the performance of this Contract. Compliance with the safety, sanitary, and factory inspection Laws of the state in which the Work is to be performed shall be prima facie evidence of compliance with this Article 37.3.
- 37.4 Prevailing Wage Enforcement: The Contractor agrees to pay for all costs incurred by the City in enforcing prevailing wage requirements, including the cost of any investigation conducted by or on behalf of the Agency or the Comptroller, where the City discovers a failure to comply with any of the requirements of this Article 37 by the Contractor or its Subcontractor(s). The Contractor also agrees that, should it fail or refuse to pay for any such investigation, the Agency is hereby authorized to deduct from a Contractor's account an amount equal to the cost of such investigation.
  - 37.4.1 The Labor Law Section 220 and Section 220-d, as amended, provide that this Contract shall be forfeited and no sum paid for any Work done hereunder on a second conviction for willfully paying less than:
    - 37.4.1(a) The stipulated prevailing wage scale as provided in Labor Law section 220, as amended, or

37.4.1(b) The stipulated minimum hourly wage scale as provided in Labor Law section 220-d, as amended.

37.4.2 For any breach or violation of either working conditions (Article 37.3) or minimum wages (Article 37.2.6) provisions, the party responsible therefor shall be liable to the City for liquidated damages, which may be withheld from any amounts due on any contracts with the City of such party responsible, or may be recovered in actions brought by the City Corporation Counsel in the name of the City, in addition to damages for any other breach of this Contract, for a sum equal to the amount of any underpayment of wages due to any employee engaged in the performance of this Contract. In addition, the Commissioner shall have the right to cancel contracts and enter into other contracts for the completion of the original contract, with or without public letting, and the original Contractor shall be liable for any additional cost. All sums withheld or recovered as deductions, rebates, refunds, or underpayment of wages hereunder, shall be held in a special deposit account and shall be paid without interest, on order of the Comptroller, directly to the employees who have been paid less than minimum rates of pay as set forth herein and on whose account such sums were withheld or recovered, provided that no claims by employees for such payments shall be entertained unless made within two (2) years from the date of actual notice to the Contractor of the withholding or recovery of such sums by the City.

37.4.3 A determination by the Comptroller that a Contractor and/or its Subcontractor willfully violated Labor Law Section 220 will be forwarded to the City's five District Attorneys for review.

37.4.4 The Contractor's or Subcontractor's noncompliance with this Article 37.4 and Labor Law Section 220 may result in an unsatisfactory performance evaluation and the Comptroller may also find and determine that the Contractor or Subcontractor willfully violated the New York Labor Law.

37.4.4(a) An unsatisfactory performance evaluation for noncompliance with this Article 37.4 may result in a determination that the **Contractor** is a non-responsible bidder on subsequent procurements with the **City** and thus a rejection of a future award of a contract with the **City**, as well as any other sanctions provided for by **Law**.

37.4.4(b) Labor Law Section 220-b, as amended, provides that when two (2) final determinations have been rendered against a Contractor or Subcontractor within any consecutive six (6) year period determining that such Contractor or Subcontractor has willfully failed to pay the prevailing rate of wages or to provide supplements in accordance with the Labor Law and this Article 37.4, whether such failures were concurrent or consecutive and whether or not such final determinations concerning separate public works projects are rendered simultaneously, such Contractor or Subcontractor shall be ineligible to submit a bid on or be awarded any public works contract with the City for a period of five (5) years from the second final determination. If the final determination involves the falsification of payroll records or the kickback of wages or supplements, the Contractor or Subcontractor shall be ineligible to submit a bid on or be awarded any public works contract with the City for a period of five (5) years from the first final determination.

37.4.4(c) Labor Law Section 220, as amended, provides that the **Contractor** or **Subcontractor** found to have violated this Article 37.4 may be directed to make payment of wages or supplements including interest found to be due, and the **Contractor** or **Subcontractor** may be directed to make payment of a further sum as

a civil penalty in an amount not exceeding twenty-five (25%) percent of the total amount found to be due.

- 37.5 The Contractor and its Subcontractors shall within ten (10) Days after mailing of a Notice of Award or written order, post in prominent and conspicuous places in each and every plant, factory, building, and structure where employees of the Contractor and its Subcontractors engaged in the performance of this Contract are employed, notices furnished by the City, in relation to prevailing wages and supplements, minimum wages, and other stipulations contained in Sections 220 and 220-h of the Labor Law, and the Contractor and its Subcontractors shall continue to keep such notices posted in such prominent and conspicuous places until Final Acceptance of the supplies, materials, equipment, or Work, labor, or services required to be furnished or rendered under this Contract.
- 37.6 The **Contractor** shall strictly comply with all of the provisions of Articles 37.6.1 through 37.6.5, and provide for all workers, laborers or mechanics in its employ, the following:
  - 37.6.1 Notices Posted At Site: Post, in a location designated by the City, schedules of prevailing wages and supplements for this **Project**, a copy of all re-determinations of such schedules for the **Project**, the Workers' Compensation Law Section 51 notice, all other notices required by Law to be posted at the Site, the City notice that this **Project** is a public works project on which each worker is entitled to receive the prevailing wages and supplements for the occupation at which he or she is working, and all other notices which the City directs the Contractor to post. The Contractor shall provide a surface for such notices which is satisfactory to the City. The Contractor shall maintain and keep current such notices in a legible manner and shall replace any notice or schedule which is damaged, defaced, illegible or removed for any reason. The Contractor shall post such notices before commencing any Work on the Site and shall maintain such notices until all Work on the Site is complete; and
  - 37.6.2 Daily Site Sign-in Sheets: Maintain daily Site sign-in sheets, and require that Subcontractors maintain daily Site sign-in sheets for its employees, which include blank spaces for an employee's name to be both printed and signed, job title, date started and Social Security number, the time the employee began work and the time the employee left work, until Final Acceptance of the supplies, materials, equipment, or Work, labor, or services to be furnished or rendered under this Contract unless exception is granted by the Comptroller upon application by the Agency. In the alternative, subject to the approval of the CCPO, the Contractor and Subcontractor may maintain an electronic or biometric sign-in system, which provides the information required by this Article 37.6.2; and
  - 37.6.3 Individual Employee Information Notices: Distribute a notice to each worker, laborer or mechanic employed under this Contract, in a form provided by the Agency, that this Project is a public works project on which each worker, laborer or mechanic is entitled to receive the prevailing rate of wages and supplements for the occupation at which he or she is working. If the total cost of the Work under this Contract is at least two hundred fifty thousand (\$250,000) dollars, such notice shall also include a statement that each worker, laborer or mechanic must be certified prior to performing any Work as having successfully completed a course in construction safety and health approved by the United States Department of Labor's Occupational Safety and Health Administration that is at least ten (10) hours in duration. Such notice shall be distributed to each worker before he or she starts performing any Work of this Contract and with the first paycheck after July first of each year. "Worker, laborer or mechanic" includes employees of the Contractor and all Subcontractors and all employees of suppliers entering the Site. At the time of distribution, the Contractor shall have each worker, laborer or mechanic sign a statement, in a form provided by the Agency, certifying that the worker has received the notice required by this

Article 37.6.3, which signed statement shall be maintained with the payroll records required by this Contract; and

37.6.3(a) The Contractor and each Subcontractor shall notify each worker, laborer or mechanic employed under this Contract in writing of the prevailing rate of wages for their particular job classification. Such notification shall be given to every worker, laborer, and mechanic on their first pay stub and with every pay stub thereafter; and

37.6.4 Site Laminated Identification Badges: The Contractor shall provide laminated identification badges which include a photograph of the worker's, laborer's or mechanic's face and indicate the worker's, laborer's or mechanic's name, trade, employer's name, and employment starting date (month/day/year). Further, the Contractor shall require as a condition of employment on the Site, that each and every worker, laborer or mechanic wear the laminated identification badge at all times and that it may be seen by any representative of the City. The Commissioner may grant a written waiver from the requirement that the laminated identification badge include a photograph if the Contractor demonstrates that the identity of an individual wearing a laminated identification badge can be easily verified by another method; and

37.6.5 Language Other Than English Used On Site: Provide the ACCO notice when three (3) or more employees (worker and/or laborer and/or mechanic) on the Site, at any time, speak a language other than English. The ACCO will then provide the Contractor the notices described in Article 37.6.1 in that language or languages as may be required. The Contractor is responsible for all distributions under this Article 37; and

37.6.6 Provision of Records: The Contractor and Subcontractor(s) shall produce within five (5) Days on the Site of the Work and upon a written order of the Engineer, the Commissioner, the ACCO, the Agency EAO, or the Comptroller, such records as are required to be kept by this Article 37.6; and

37.6.7 The Contractor and Subcontractor(s) shall pay employees by check or direct deposit. If this Contract is for an amount greater than one million (\$1,000,000) dollars. checks issued by the Contractor to covered employees shall be generated by a payroll service or automated payroll system (an in-house system may be used if approved by the Agency). For any subcontract for an amount greater than seven hundred fifty thousand (\$750,000) dollars, checks issued by a Subcontractor to covered employees shall be generated by a payroll service or automated payroll system (an in-house system may be used if approved by the Agency); and

37.6.8 The failure of the Contractor or Subcontractor(s) to comply with the provisions of Articles 37.6.1 through 37.6.7 may result in the Commissioner declaring the Contractor in default and/or the withholding of payments otherwise due under the Contract.

37.7 The Contractor and its Subcontractors shall keep such employment and payroll records as are required by Section 220 of the Labor Law. The failure of the Contractor or Subcontractor(s) to comply with the provisions of this Article 37.7 may result in the Commissioner declaring the Contractor in default and/or the withholding of payments otherwise due under the Contract.

37.8 At the time the Contractor makes application for each partial payment and for final payment, the Contractor shall submit to the Commissioner a written payroll certification, in the form provided by this Contract, of compliance with the prevailing wage, minimum wage, and other provisions and stipulations required by Labor Law Section 220 and of compliance with the training requirements of CITY OF NEW YORK STANDARD CONSTRUCTION CONTRACT 56

December 2013

Labor Law Section 220-h set forth in Article 35.2. This certification of compliance shall be a condition precedent to payment and no payment shall be made to the **Contractor** unless and until each such certification shall have been submitted to and received by the **Commissioner**.

- 37.9 This Contract is executed by the Contractor with the express warranty and representation that the Contractor is not disqualified under the provisions of Section 220 of the Labor Law from the award of the Contract.
- 37.10 Any breach or violation of any of the foregoing shall be deemed a breach or violation of a material provision of this **Contract**, and grounds for cancellation thereof by the **City**.

#### **ARTICLE 38. PAYROLL REPORTS**

- 38.1 The Contractor and its Subcontractor(s) shall maintain on the Site during the performance of the Work the original payrolls or transcripts thereof which the Contractor and its Subcontractor(s) are required to maintain and shall submit such original payrolls or transcripts, subscribed and affirmed by it as true, within thirty (30) Days after issuance of its first payroll, and every thirty (30) Days thereafter, pursuant to Labor Law Section 220(3-a)(a)(iii). The Contractor and Subcontractor(s) shall submit such original payrolls or transcripts along with each and every payment requisition. If payment requisitions are not submitted at least once a month, the Contractor and its Subcontractor(s) shall submit original payrolls and transcripts both along with its payment requisitions and independently of its payment requisitions.
- 38.2 The Contractor shall maintain payrolls or transcripts thereof for six (6) years from the date of completion of the Work on this Contract. If such payrolls and transcripts are maintained outside of New York City after the completion of the Work and their production is required pursuant to this Article 38, the Contractor shall produce such records in New York City upon request by the City.
- 38.3 The Contractor and Subcontractor(s) shall comply with any written order, direction, or request made by the Engineer, the Commissioner, the ACCO, the Agency EAO, the Agency Labor Law Investigator(s), or the Comptroller, to provide to the requesting party any of the following information and/or records within five (5) Days of such written order, direction, or request:
  - 38.3.1 Such original payrolls or transcripts thereof subscribed and affirmed by it as true and the statements signed by each worker pursuant to this Chapter VIII; and/or
  - 38.3.2 Attendance sheets for each **Day** on which any employee of the **Contractor** and/or any of the **Subcontractor(s)** performed **Work** on the **Site**, which attendance sheet shall be in a form acceptable to the **Agency** and shall provide information acceptable to the **Agency** to identify each such employee; and/or
  - 38.3.3 Any other information to satisfy the Engineer, the Commissioner, the ACCO, the Agency EAO, the Agency Labor Law Investigator(s) or the Comptroller, that this Chapter VIII and the Labor Law, as to the hours of employment and prevailing rates of wages and/or supplemental benefits, are being observed.
- 38.4 The failure of the Contractor or Subcontractor(s) to comply with the provisions of Articles 38.1 and/or 38.2 may result in the Commissioner declaring the Contractor in default and/or the withholding of payments otherwise due under the Contract.

## **ARTICLE 39. DUST HAZARDS**

39.1 Should a harmful dust hazard be created in performing the Work of this Contract, for the elimination of which appliances or methods have been approved by the Board of Standards and Appeals of the City of New York, such appliances and methods shall be installed, maintained, and effectively operated during the continuance of such harmful dust hazard. Failure to comply with this provision after notice shall make this Contract voidable at the sole discretion of the City.

# CHAPTER IX PARTIAL AND FINAL PAYMENTS

#### **ARTICLE 40. CONTRACT PRICE**

40.1 The City shall pay, and the Contractor agrees to accept, in full consideration for the Contractor's performance of the Work subject to the terms and conditions hereof, the lump sum price or unit prices for which this Contract was awarded, plus the amount required to be paid for any Extra Work ordered by the Commissioner under Article 25, less credit for any Work omitted pursuant to Article 29.

## ARTICLE 41. BID BREAKDOWN ON LUMP SUM

- 41.1 Within fifteen (15) Days after the commencement date specified in the Notice to Proceed or Order to Work, unless otherwise directed by the Resident Engineer, the Contractor shall submit to the Resident Engineer a breakdown of its bid price, or of lump sums bid for items of the Contract, showing the various operations to be performed under the Contract, as directed in the progress schedule required under Article 9, and the value of each of such operations, the total of such items to equal the lump sum price bid. Said breakdown must be approved in writing by the Resident Engineer.
- 41.2 No partial payment will be approved until the Contractor submits a bid breakdown that is acceptable to the Resident Engineer.
- 41.3 The Contractor shall also submit such other information relating to the bid breakdown as directed by the Resident Engineer. Thereafter, the breakdown may be used only for checking the Contractor's applications for partial payments hereunder, but shall not be binding upon the City, the Commissioner, or the Engineer for any purpose whatsoever.

#### **ARTICLE 42. PARTIAL PAYMENTS**

- 42.1 From time to time as the Work progresses satisfactorily, but not more often than once each calendar month (except where the Commissioner approves in writing the submission of invoices on a more frequent basis and for invoices relating to Work performed pursuant to a change order), the Contractor may submit to the Engineer a requisition for a partial payment in the prescribed form, which shall contain an estimate of the quantity and the fair value of the Work done during the payment period.
- 42.2 Partial payments may be made for materials, fixtures, and equipment in advance of their actual incorporation in the **Work**, as the **Commissioner** may approve, and upon the terms and conditions set forth in the General Conditions.

- 42.3 The Contractor shall also submit to the Commissioner in connection with every application for partial payment a verified statement in the form prescribed by the Comptroller setting forth the information required under Labor Law Section 220-a.
- 42.4 Within thirty (30) **Days** after receipt of a satisfactory payment application, and within sixty (60) **Days** after receipt of a satisfactory payment application in relation to **Work** performed pursuant to a change order, the **Engineer** will prepare and certify, and the **Commissioner** will approve, a voucher for a partial payment in the amount of such approved estimate, less any and all deductions authorized to be made by the **Commissioner** under the terms of this **Contract** or by **Law**.

## **ARTICLE 43. PROMPT PAYMENT**

- 43.1 The Prompt Payment provisions of the **PPB** Rules in effect at the time of the bid will be applicable to payments made under this **Contract**. The provisions require the payment to the **Contractor** of interest on payments made after the required payment date, except as set forth in the **PPB** Rules.
- 43.2 The Contractor shall submit a proper invoice to receive payment, except where the Contract provides that the Contractor will be paid at predetermined intervals without having to submit an invoice for each scheduled payment.
  - 43.3 Determination of interest due will be made in accordance with the PPB Rules.
- 43.4 If the Contractor is paid interest, the proportionate share(s) of that interest shall be forwarded by the Contractor to its Subcontractor(s).
- 43.5 The Contractor shall pay each Subcontractor or Materialman not later than seven (7) Days after receipt of payment out of amounts paid to the Contractor by the City for Work performed by the Subcontractor or Materialman under this Contract.
  - 43.5.1 If Contractor fails to make any payment to any Subcontractor or Materialman within seven (7) Days after receipt of payment by the City pursuant to this Article 43.5, then the Contractor shall pay interest on amounts due to such Subcontractor or Materialman at the rate of interest in effect on the date such payment is made by the Contractor computed in accordance with Section 756-b (1)(b) of the New York General Business Law. Accrual of interest shall commence on the Day immediately following the expiration of the seventh Day following receipt of payment by the Contractor from the City and shall end on the date on which payment is made.
- 43.6 The Contractor shall include in each of its subcontracts a provision requiring each Subcontractor to make payment to each of its Subcontractors or Materialmen for Work performed under this Contract in the same manner and within the same time period set forth above.

# ARTICLE 44. SUBSTANTIAL COMPLETION PAYMENT

- 44.1 The Contractor shall submit with the Substantial Completion requisition:
  - 44.1.1 A final verified statement of any pending Article 27 disputes in accordance with the **PPB** Rules and this **Contract** and any and all alleged claims against the **City**, in any way connected with or arising out of this **Contract** (including those as to which details may have been furnished pursuant to Articles 11, 27, 28, and 30) setting forth with respect to each

such claim the total amount thereof, the various items of labor and materials included therein, and the alleged value of each item; and if the alleged claim be one for delay, the alleged cause of each such delay, the period or periods of time, giving the dates when the **Contractor** claims the performance of the **Work** or a particular part thereof was delayed, and an itemized statement and breakdown of the amount claimed for each such delay.

44.1.1(a) With respect to each such claim, the Commissioner, the Comptroller and, in the event of litigation, the City Corporation Counsel shall have the same right to inspect, and to make extracts or copies of, the Contractor's books, vouchers, records, etc., as is referred to in Articles 11, 27, 28, and 30. Nothing contained in this Article 44.1.1(a) is intended to or shall relieve the Contractor from the obligation of complying strictly with Articles 11, 27, 28, and 30. The Contractor is warned that unless such claims are completely set forth as herein required, the Contractor upon acceptance of the Substantial Completion payment pursuant to this Article 44, will have waived any such claims.

#### 44.1.2 A Final Approved Punch List.

- 44.1.3 Where required, a request for an extension of time to achieve Substantial Completion or final extension of time.
- 44.2 The Commissioner shall issue a voucher calling for payment of any part or all of the balance due for Work performed under the Contract, including monies retained under Article 21, less any and all deductions authorized to be made by the Commissioner, under this Contract or by Law, and less twice the amount the Commissioner considers necessary to ensure the completion of the balance of the Work by the Contractor. Such a payment shall be considered a partial and not a final payment. No Substantial Completion payment shall be made under this Article 44 where the Contractor failed to complete the Work within the time fixed for such completion in the Schedule A of the General Conditions, or within the time to which completion may have been extended, until an extension or extensions of time for the completion of Work have been acted upon pursuant to Article 13.
- 44.3 No further partial payments shall be made to the Contractor after Substantial Completion, except the Substantial Completion payment and payment pursuant to any Contractor's requisition that were properly filed with the Commissioner prior to the date of Substantial Completion; however, the Commissioner may grant a waiver for further partial payments after the date of Substantial Completion to permit payments for change order Work and/or release of retainage and deposits pursuant to Articles 21 and 24. Such waiver shall be in writing.
- 44.4 The Contractor acknowledges that nothing contained in this Article 44 is intended to or shall in any way diminish the force and effect of Article 13.

#### ARTICLE 45. FINAL PAYMENT

45.1 After completion and Final Acceptance of the Work, the Contractor shall submit all required certificates and documents, together with a requisition for the balance claimed to be due under the Contract, less the amount authorized to be retained for maintenance under Article 24. Such submission shall be within 90 days of the date of the Commissioner's written determination of Final Acceptance, or within such additional time as may be granted by the Commissioner in writing. If the Contractor fails to submit all required certificates and documents within the time allowed, no payment of the balance claimed shall be made to the Contractor and the Contractor shall be deemed to have forfeited its right to

payment of any balance claimed. A verified statement similar to that required in connection with applications for partial payments shall also be submitted to the Commissioner.

- 45.2 Amended Verified Statement of Claims: The Contractor shall also submit with the final requisition any amendments to the final verified statement of any pending dispute resolution procedures in accordance with the PPB Rules and this Contract and any and all alleged claims against the City, in any way connected with or arising out of this Contract (including those as to which details may have been furnished pursuant to Articles 11, 27, 28, and 30) that have occurred subsequent to Substantial Completion, setting forth with respect to each such claim the total amount thereof, the various items of labor and materials included therein, and the alleged value of each such item; and if the alleged claim be one for delay, the alleged cause of each such delay, the period or periods of time, giving the dates when the Contractor claims the performance of the Work or a particular part thereof was delayed, and an itemized statement and breakdown of the amount claimed for each such delay. With reference to each such claim, the Commissioner, the Comptroller and, in the event of litigation, the City Corporation Counsel shall have the same right to inspect, and to make extracts or copies of, the Contractor's books. vouchers, records, etc., as is referred to in Articles 11, 27, 28, and 30. Nothing contained in this Article 45.2, is intended to or shall relieve the Contractor from the obligation of complying strictly with Articles 11, 27, 28, and 30. The Contractor is warned that unless such claims are completely set forth as herein required, the Contractor, upon acceptance of the Final Payment pursuant to Article 46, will have waived any such claims.
- 45.3 Preparation of Final Voucher: Upon determining the balance due hereunder other than on account of claims, the **Engineer** will prepare and certify, for the Commissioner's approval, a voucher for final payment in that amount less any and all deductions authorized to be made by the **Commissioner** under this **Contract** or by **Law**. In the case of a lump sum **Contract**, the **Commissioner** shall certify the voucher for final payment within thirty (30) **Days** from the date of completion and acceptance of the **Work**, provided all requests for extensions of time have been acted upon.
  - 45.3.1 All prior certificates and vouchers upon which partial payments were made, being merely estimates made to enable the **Contractor** to prosecute the **Work** more advantageously, shall be subject to correction in the final voucher, and the certification of the **Engineer** thereon and the approval of the **Commissioner** thereof, shall be conditions precedent to the right of the **Contractor** to receive any money hereunder. Such final voucher shall be binding and conclusive upon the **Contractor**.
  - 45.3.2 Payment pursuant to such final voucher, less any deductions authorized to be made by the Commissioner under this Contract or by Law, shall constitute the final payment, and shall be made by the Comptroller within thirty (30) Days after the filing of such voucher in his/her office.
- 45.4 The Contractor acknowledges that nothing contained in this Article 45 is intended to or shall in any way diminish the force and effect of Article 13.

#### **ARTICLE 46. ACCEPTANCE OF FINAL PAYMENT**

46.1 The acceptance by the Contractor, or by anyone claiming by or through it, of the final payment, whether such payment be made pursuant to any judgment of any court, or otherwise, shall constitute and operate as a release of the City from any and all claims of and liability to the Contractor for anything heretofore done or furnished for the Contractor relating to or arising out of this Contract and the Work done hereunder, and for any prior act, neglect or default on the part of the City or any of its officials, agents or employees, excepting only a claim against the City for the amounts deducted or retained in accordance with the terms and provisions of this Contract or by Law, and excepting any CITY OF NEW YORK

CONSTRUCTION CONTRAC

DDC

claims, not otherwise waived, or any pending dispute resolution procedures which are contained in the verified statement filed with the Contractor's substantial and final requisitions pursuant to Articles 44 and 45.

- 46.2 The Contractor is warned that the execution by it of a release, in connection with the acceptance of the final payment, containing language purporting to reserve claims other than those herein specifically excepted from the operation of this Article 46, or those for amounts deducted by the Commissioner from the final requisition or from the final payment as certified by the Engineer and approved by the Commissioner, shall not be effective to reserve such claims, anything stated to the Contractor orally or in writing by any official, agent or employee of the City to the contrary notwithstanding.
- 46.3 Should the Contractor refuse to accept the final payment as tendered by the Comptroller, it shall constitute a waiver of any right to interest thereon.
- 46.4 The Contractor, however, shall not be barred by this Article 46 from commencing an action for breach of Contract to the extent permitted by Law and by the terms of the Contract for any claims that are contained in the verified statement filed with the Contractor's substantial and final requisitions pursuant to Articles 44 and 45 or that arose after submission of the final payment requisition, provided that a detailed and verified statement of claim is served upon the contracting Agency and Comptroller not later than forty (40) Days after the making of such final payment by electronic funds transfer (EFT) or the mailing of such final payment. The statement shall specify the items upon which the claim will be based and any such claim shall be limited to such items.

## ARTICLE 47. APPROVAL BY PUBLIC DESIGN COMMISSION

47.1 All works of art, including paintings, mural decorations, stained glass, statues, bas-reliefs, and other sculptures, monuments, fountains, arches, and other structures of a permanent character intended for ornament or commemoration, and every design of the same to be used in the performance of this Contract, and the design of all bridges, approaches, buildings, gates, fences, lamps, or structures to be erected, pursuant to the terms of this Contract, shall be submitted to the Art Commission, d/b/a the Public Design Commission of the City of New York, and shall be approved by the Public Design Commission prior to the erection or placing in position of the same. The final payment shall not become due or payable under this Contract unless and until the Public Design Commission shall certify that the design for the Work herein contracted for has been approved by the said Public Design Commission, and that the same has been executed in substantial accordance with the design so approved, pursuant to the provisions of Chapter 37, Section 854 of the City Charter, as amended.

# CHAPTER X CONTRACTOR'S DEFAULT

## ARTICLE 48. COMMISSIONER'S RIGHT TO DECLARE CONTRACTOR IN DEFAULT

- 48.1 In addition to those instances specifically referred to in other Articles herein, the Commissioner shall have the right to declare the Contractor in default of this Contract if:
  - 48.1.1 The Contractor fails to commence Work when notified to do so by the Commissioner; or

if

48.1.2 The Contractor shall abandon the Work; or if

- 48.1.3 The Contractor shall refuse to proceed with the Work when and as directed by the Commissioner; or if
- 48.1.4 The Contractor shall, without just cause, reduce its working force to a number which, if maintained, would be insufficient, in the opinion of the Commissioner, to complete the Work in accordance with the progress schedule; or if
- 48.1.5 The Contractor shall fail or refuse to increase sufficiently such working force when ordered to do so by the Commissioner; or if
- 48.1.6 The Contractor shall sublet, assign, transfer, convert or otherwise dispose of this Contract other than as herein specified; or sell or assign a majority interest in the Contractor; or if
- 48.1.7 The Contractor fails to secure and maintain all required insurance; or if
- 48.1.8 A receiver or receivers are appointed to take charge of the Contractor's property or affairs; or if
- 48.1.9 The Commissioner shall be of the opinion that the Contractor is or has been unnecessarily or unreasonably or willfully delaying the performance and completion of the Work, or the award of necessary subcontracts, or the placing of necessary material and equipment orders; or if
- 48.1.10 The Commissioner shall be of the opinion that the Contractor is or has been willfully or in bad faith violating any of the provisions of this Contract; or if
- 48.1.11 The Commissioner shall be of the opinion that the Work cannot be completed within the time herein provided therefor or within the time to which such completion may have been extended; provided, however, that the impossibility of timely completion is, in the Commissioner's opinion, attributable to conditions within the Contractor's control; or if
- 48.1.12 The Work is not completed within the time herein provided therefor or within the time to which the Contractor may be entitled to have such completion extended; or if
- 48.1.13 Any statement or representation of the Contractor in the Contract or in any document submitted by the Contractor with respect to the Work, the Project, or the Contract (or for purposes of securing the Contract) was untrue or incorrect when made; or if
- 48.1.14 The Contractor or any of its officers, directors, partners, five (5%) percent shareholders, principals, or other persons substantially involved in its activities, commits any of the acts or omissions specified as the grounds for debarment in the PPB Rules.
- 48.2 Before the Commissioner shall exercise his/her right to declare the Contractor in default, the Commissioner shall give the Contractor an opportunity to be heard, upon not less than two (2) Days notice.

#### ARTICLE 49. EXERCISE OF THE RIGHT TO DECLARE DEFAULT

- 49.1 The right to declare the **Contractor** in default for any of the grounds specified or referred to in Article 48 shall be exercised by sending the **Contractor** a notice, signed by the **Commissioner**, setting forth the ground or grounds upon which such default is declared (hereinafter referred to as a "Notice of Default").
- 49.2 The Commissioner's determination that the Contractor is in default shall be conclusive, final, and binding on the parties and such a finding shall preclude the Contractor from commencing a plenary action for any damages relating to the Contract. If the Contractor protests the determination of the Commissioner, the Contractor may commence an action in a court of competent jurisdiction of the State of New York under Article 78 of the New York Civil Practice Law and Rules.

#### ARTICLE 50. QUITTING THE SITE

50.1 Upon receipt of such notice the Contractor shall immediately discontinue all further operations under this Contract and shall immediately quit the Site, leaving untouched all plant, materials, equipment, tools, and supplies then on the Site.

#### ARTICLE 51. COMPLETION OF THE WORK

- 51.1 The Commissioner, after declaring the Contractor in default, may then have the Work completed by such means and in such manner, by contract with or without public letting, or otherwise, as he/she may deem advisable, utilizing for such purpose such of the Contractor's plant, materials, equipment, tools, and supplies remaining on the Site, and also such Subcontractors, as he/she may deem advisable.
- 51.2 After such completion, the Commissioner shall make a certificate stating the expense incurred in such completion, which shall include the cost of re-letting and also the total amount of liquidated damages (at the rate provided for in the Contract) from the date when the Work should have been completed by the Contractor in accordance with the terms hereof to the date of actual completion of the Work. Such certificate shall be binding and conclusive upon the Contractor, its sureties, and any person claiming under the Contractor, as to the amount thereof.
- 51.3 The expense of such completion, including any and all related and incidental costs, as so certified by the Commissioner, and any liquidated damages assessed against the Contractor, shall be charged against and deducted out of monies which are earned by the Contractor prior to the date of default. Should the expense of such completion, as certified by the Commissioner, exceed the total sum which would have been payable under the Contract if it had been completed by the Contractor, any excess shall be paid by the Contractor.

#### ARTICLE 52. PARTIAL DEFAULT

52.1 In case the Commissioner shall declare the Contractor in default as to a part of the Work only, the Contractor shall discontinue such part, shall continue performing the remainder of the Work in strict conformity with the terms of this Contract, and shall in no way hinder or interfere with any Other

Contractor(s) or persons whom the Commissioner may engage to complete the Work as to which the Contractor was declared in default.

52.2 The provisions of this Chapter relating to declaring the Contractor in default as to the entire Work shall be equally applicable to a declaration of partial default, except that the Commissioner shall be entitled to utilize for completion of the part of the Work as to which the Contractor was declared in default only such plant, materials, equipment, tools, and supplies as had been previously used by the Contractor on such part.

#### ARTICLE 53. PERFORMANCE OF UNCOMPLETED WORK

53.1 In completing the whole or any part of the **Work** under the provisions of this Chapter X, the **Commissioner** shall have the power to depart from or change or vary the terms and provisions of this **Contract**, provided, however, that such departure, change or variation is made for the purpose of reducing the time or expense of such completion. Such departure, change or variation, even to the extent of accepting a lesser or different performance, shall not affect the conclusiveness of the **Commissioner's** certificate of the cost of completion referred to in Article 51, nor shall it constitute a defense to an action to recover the amount by which such certificate exceeds the amount which would have been payable to the **Contractor** hereunder but for its default.

#### **ARTICLE 54. OTHER REMEDIES**

- 54.1 In addition to the right to declare the **Contractor** in default pursuant to this Chapter X, the **Commissioner** shall have the absolute right, in his/her sole discretion and without a hearing, to complete or cause to be completed in the same manner as described in Articles 51 and 53, any or all unsatisfactory or uncompleted punch list **Work** that remains after the completion date specified in the **Final Approved Punch List**. A written notice of the exercise of this right shall be sent to the **Contractor** who shall immediately guit the **Site** in accordance with the provisions of Article 50.
- 54.2 The expense of completion permitted under Article 54.1, including any and all related and incidental costs, as so certified by the **Commissioner**, shall be charged against and deducted out of monies which have been earned by the **Contractor** prior to the date of the exercise of the right set forth in Article 54.1; the balance of such monies, if any, subject to the other provisions of this **Contract**, to be paid to the **Contractor** without interest after such completion. Should the expense of such completion, as certified by the **Commissioner**, exceed the total sum which would have been payable under the **Contract** if it had been completed by the **Contractor**, any excess shall be paid by the **Contractor**.
- 54.3 The previous provisions of this Chapter X shall be in addition to any and all other remedies available under Law or in equity.
- 54.4 The exercise by the City of any remedy set forth herein shall not be deemed a waiver by the City of any other legal or equitable remedy contained in this Contract or provided under Law.

# CHAPTER XI MISCELLANEOUS PROVISIONS

## **ARTICLE 55. CONTRACTOR'S WARRANTIES**

- 55.1 In consideration of, and to induce, the award of this Contract to the Contractor, the Contractor represents and warrants:
  - 55.1.1 That it is financially solvent, sufficiently experienced and competent to perform the Work; and
  - 55.1.2 That the facts stated in its bid and the information given by it pursuant to the Information for Bidders is true and correct in all respects; and
  - 55.1.3 That it has read and complied with all requirements set forth in the Contract.

# ARTICLE 56. CLAIMS AND ACTIONS THEREON

- 56.1 Any claim, that is not subject to dispute resolution under the **PPB** Rules or this **Contract**, against the **City** for damages for breach of **Contract** shall not be made or asserted in any action, unless the **Contractor** shall have strictly complied with all requirements relating to the giving of notice and of information with respect to such claims, as herein before provided.
- 56.2 Nor shall any action be instituted or maintained on any such claims unless such action is commenced within six (6) months after Substantial Completion; except that:
  - 56.2.1 Any claims arising out of events occurring after Substantial Completion and before Final Acceptance of the Work shall be asserted within six (6) months of Final Acceptance of the Work;
  - 56.2.2 Any claims for monies deducted, retained or withheld under the provisions of this Contract shall be asserted within six (6) months after the date when such monies otherwise become due and payable hereunder; and
  - 56.2.3 If the Commissioner exercises his/her right to terminate the Contract pursuant to Article 64, any such action shall be commenced within six (6) months of the date the Commissioner exercises said right.

#### ARTICLE 57. INFRINGEMENT

57.1 The Contractor shall be solely responsible for and shall defend, indemnify, and hold the City harmless from any and all claims (even if the allegations of the lawsuit are without merit) and judgments for damages and from costs and expenses to which the City may be subject to or which it may suffer or incur allegedly arising out of or in connection with any infringement by the Contractor of any copyright, trade secrets, trademark or patent rights or any other property or personal right of any third party by the Contractor and/or its Subcontractors in the performance or completion of the Work. Insofar as the facts or Law relating to any claim would preclude the City from being completely indemnified by the Contractor, the City shall be partially indemnified by the Contractor to the fullest extent permitted by Law.

#### ARTICLE 58. NO CLAIM AGAINST OFFICIALS, AGENTS OR EMPLOYEES

58.1 No claim whatsoever shall be made by the Contractor against any official, agent or employee of the City for, or on account of, anything done or omitted to be done in connection with this Contract.

#### **ARTICLE 59. SERVICE OF NOTICES**

- 59.1 The Contractor hereby designates the business address, fax number, and email address specified in its bid, as the place where all notices, directions or other communications to the Contractor may be delivered, or to which they may be mailed. Any notice, direction, or communication from either party to the other shall be in writing and shall be deemed to have been given when (i) delivered personally; (ii) sent by certified mail, return receipt requested; (iii) delivered by overnight or same day courier service in a properly addressed envelope with confirmation; or (iv) sent by fax or email and, unless receipt of the fax or e-mail is acknowledged by the recipient by fax or e-mail, deposited in a post office box regularly maintained by the United States Postal Service in a properly addressed, postage prepaid envelope.
- 59.2 Contractor's notice address, email address, or fax number may be changed at any time by an instrument in writing, executed and acknowledged by the Contractor, and delivered to the Commissioner.
- 59.3 Nothing herein contained shall, however, be deemed to preclude or render inoperative the service of any notice, direction or other communication upon the Contractor personally, or, if the Contractor is a corporation, upon any officer thereof.

#### ARTICLE 60. UNLAWFUL PROVISIONS DEEMED STRICKEN FROM CONTRACT

60.1 If this Contract contains any unlawful provision not an essential part of the Contract and which shall not appear to have been a controlling or material inducement to the making thereof, the same shall be deemed of no effect and shall, upon notice by either party, be deemed stricken from the Contract without affecting the binding force of the remainder.

#### ARTICLE 61. ALL LEGAL PROVISIONS DEEMED INCLUDED

61.1 It is the intent and understanding of the parties to this Contract that each and every provision of Law required to be inserted in this Contract shall be and is inserted herein. Furthermore, it is hereby stipulated that every such provision is to be deemed to be inserted herein, and if, through mistake or otherwise, any such provision is not inserted, or is not inserted in correct form, then this Contract shall forthwith upon the application of either party be amended by such insertion so as to comply strictly with the Law and without prejudice to the rights of either party hereunder.

#### **ARTICLE 62. TAX EXEMPTION**

62.1 The City is exempt from payment of Federal, State, and local taxes, including sales and compensating use taxes of the State of New York and its cities and counties on all tangible personal property sold to the City pursuant to the provisions of this Contract. These taxes are not to be included in bids. However, this exemption does not apply to tools, machinery, equipment or other property leased by or to the Contractor, Subcontractor or Materialman or to tangible personal property which, even CITY OF NEW YORK STANDARD CONSTRUCTION CONTRACT

DDC

though it is consumed, is not incorporated into the completed Work (consumable supplies) and tangible personal property that the Contractor is required to remove from the Site during or upon completion of the Work. The Contractor and its Subcontractors and Materialmen shall be responsible for and pay any and all applicable taxes, including sales and compensating use taxes, on such leased tools, machinery, equipment or other property and upon all such consumable supplies and tangible personal property that the Contractor is required to remove from the Site during or upon completion of the Work.

- 62.2 The Contractor agrees to sell and the City agrees to purchase all tangible personal property, other than consumable supplies and other tangible personal property that the Contractor is required to remove from the Site during or upon completion of the Work, that is required, necessary or proper for or incidental to the construction of the Project covered by this Contract. The sum paid under this Contract for such tangible personal property shall be in full payment and consideration for the sale of such tangible personal property.
  - 62.2.1 The Contractor agrees to construct the Project and to perform all Work, labor and services rendered, necessary, proper or incidental thereto for the sum shown in the bid for the performance of such Work, labor, and services, and the sum so paid pursuant to this Contract for such Work, labor, and services, shall be in full consideration for the performance by the Contractor of all its duties and obligations under this Contract in connection with said Work, labor, and services.
- 62.3 20 NYCRR Section 541.3(d) provides that a Contractor's purchases of tangible personal property that is either incorporated into real property owned by a governmental entity or purchased for and sold to a governmental entity are exempt from sales and use tax. The City shall not pay sales tax for any such tangible personal property that it purchases from the Contractor pursuant to the Contract. With respect to such tangible personal property, the Contractor, at the request of the City, shall furnish to the City such bills of sale and other instruments as may be required by the City, properly executed, acknowledged and delivered assuring to the City title to such tangible personal property, free of liens and/or encumbrances, and the Contractor shall mark or otherwise identify all such tangible personal property as the property of the City.
- 62.4 Title to all tangible personal property to be sold by the Contractor to the City pursuant to the provisions of the Contract shall immediately vest in and become the sole property of the City upon delivery of such tangible personal property to the Site. Notwithstanding such transfer of title, the Contractor shall have the full and continuing responsibility to install such tangible personal property in accordance with the provisions of this Contract, protect it, maintain it in a proper condition and forthwith repair, replace and make good any damage thereto, theft or disappearance thereof, and furnish additional tangible personal property in place of any that may be lost, stolen or rendered unusable, without cost to the City, until such time as the Work covered by the Contract is fully accepted by the City. Such transfer of title shall in no way affect any of the Contractor's obligations hereunder. In the event that, after title has passed to the City, any of the tangible personal property is rejected as being defective or otherwise unsatisfactory, title to all such tangible personal property shall be deemed to have been transferred back to the Contractor.
- 62.5 The purchase by **Subcontractors** or **Materialmen** of tangible personal property to be sold hereunder shall be a purchase or procurement for resale to the **Contractor** (either directly or through other **Subcontractors**) and therefore not subject to the aforesaid sales and compensating use taxes, provided that the subcontracts and purchase agreements provide for the resale of such tangible personal property and that such subcontracts and purchase agreements are in a form similar to this **Contract** with respect to the separation of the sale of consumable supplies and tangible personal property that the **Contractor** is required to remove from the **Site** during or upon completion of the **Work** from the **Work** and labor, services, and any other matters to be provided, and provided further that the subcontracts and

purchase agreements provide separate prices for tangible personal property and all other services and matters. Such separation shall actually be followed in practice, including the separation of payments for tangible personal property from the payments for other **Work** and labor and other things to be provided.

- 62.6 The Contractor and its Subcontractors and Materialmen shall furnish a Contractor Exempt Purchase Certificate to all persons, firms or corporations from which they purchase tangible personal property for the performance of the Work covered by this Contract.
- 62.7 In the event any of the provisions of this Article 62 shall be deemed to be in conflict with any other provisions of this Contract or create any ambiguity, then the provisions of this Article 62 shall control.

## **ARTICLE 63. INVESTIGATION(S) CLAUSE**

- 63.1 The parties to this **Contract** agree to cooperate fully and faithfully with any investigation, audit or inquiry conducted by a United States, a State of New York (State) or a **City** governmental agency or authority that is empowered directly or by designation to compel the attendance of witnesses and to examine witnesses under oath, or conducted by the Inspector General of a governmental agency that is a party in interest to the transaction, submitted bid, submitted proposal, contract, lease, permit or license that is the subject of the investigation, audit or inquiry.
- 63.2 If any person who has been advised that his/her statement, and any information from such statement, will not be used against him/her in any subsequent criminal proceeding refuses to testify before a grand jury or other governmental agency or authority empowered directly or by designation to compel the attendance of witnesses and to examine witnesses under oath concerning the award of or performance under any transaction, agreement, lease, permit, contract, or license entered into with the City, the State, or any political subdivision or public authority thereof, or the Port Authority of New York and New Jersey, or any local development corporation within the City, or any public benefit corporation organized under the Laws of the State of New York, or;
- 63.3 If any person refuses to testify for a reason other than the assertion of his/her privilege against self incrimination in an investigation, audit or inquiry conducted by a City or State governmental agency or authority empowered directly or by designation to compel the attendance of witnesses and to take testimony under oath, or by the Inspector General of the governmental agency that is a party in interest in, and is seeking testimony concerning the award of, or performance under any transaction, agreement, lease, permit, contract, or license entered into with the City, the State, or any political subdivision thereof or any local development corporation within the City, then;
- 63.4 The Commissioner whose Agency is a party in interest to the transaction, submitted bid, submitted proposal, contract, lease, permit, or license shall convene a hearing, upon not less than five (5) Days' written notice to the parties involved to determine if any penalties should attach for the failure of a person to testify.
- 63.5 If any non-governmental party to the hearing requests an adjournment, the Commissioner who convened the hearing may, upon granting the adjournment, suspend any contract, lease, permit, or license, pending the final determination pursuant to Article 63.7 without the City incurring any penalty or damages for delay or otherwise.
- 63.6 The penalties which may attach after a final determination by the Commissioner may include but shall not exceed:

- 63.6.1 The disqualification for a period not to exceed five (5) years from the date of an adverse determination for any person, or any entity of which such person was a member at the time the testimony was sought, from submitting bids for, or transacting business with, or entering into or obtaining any contract, lease, permit or license with or from the City; and/or
- 63.6.2 The cancellation or termination of any and all such existing City contracts, leases, permits or licenses that the refusal to testify concerns and that have not been assigned as permitted under this Contract, nor the proceeds of which pledged, to an unaffiliated and unrelated institutional lender for fair value prior to the issuance of the notice scheduling the hearing, without the City incurring any penalty or damages on account of such cancellation or termination; monies lawfully due for goods delivered, work done, rentals, or fees accrued prior to the cancellation or termination shall be paid by the City.
- 63.7 The Commissioner shall consider and address in reaching his/her determination and in assessing an appropriate penalty the factors in Articles 63.7.1 and 63.7.2. The Commissioner may also consider, if relevant and appropriate, the criteria established in Articles 63.7.3 and 63.7.4, in addition to any other information which may be relevant and appropriate:
  - 63.7.1 The party's good faith endeavors or lack thereof to cooperate fully and faithfully with any governmental investigation or audit, including but not limited to the discipline, discharge, or disassociation of any person failing to testify, the production of accurate and complete books and records, and the forthcoming testimony of all other members, agents, assignees or fiduciaries whose testimony is sought.
  - 63.7.2 The relationship of the person who refused to testify to any entity that is a party to the hearing, including but not limited to, whether the person whose testimony is sought has an ownership interest in the entity and/or the degree of authority and responsibility the person has within the entity.
  - 63.7.3 The nexus of the testimony sought to the subject entity and its contracts, leases, permits or licenses with the City.
  - 63.7.4 The effect a penalty may have on an unaffiliated and unrelated party or entity that has a significant interest in an entity subject to penalties under Article 63.6, provided that the party or entity has given actual notice to the **Commissioner** upon the acquisition of the interest, or at the hearing called for in Article 63.4, gives notice and proves that such interest was previously acquired. Under either circumstance the party or entity shall present evidence at the hearing demonstrating the potential adverse impact a penalty will have on such person or entity.

#### 63.8 Definitions:

- 63.8.1 The term "license" or "permit" as used in this Article 63 shall be defined as a license, permit, franchise or concession not granted as a matter of right.
- 63.8.2 The term "person" as used in this Article 63 shall be defined as any natural person doing business alone or associated with another person or entity as a partner, director, officer, principal or employee.
- 63.8.3 The term "entity" as used in this Article 63 shall be defined as any firm, partnership, corporation, association, joint venture, or person that receives monies, benefits, licenses, leases, or permits from or through the City or otherwise transacts business with the City.

- 63.8.4 The term "member" as used in this Article 63 shall be defined as any person associated with another person or entity as a partner, director, officer, principal or employee.
- 63.9 In addition to and notwithstanding any other provision of this Contract, the Commissioner may in his/her sole discretion terminate this Contract upon not less than three (3) Days' written notice in the event the Contractor fails to promptly report in writing to the Commissioner of the Department of Investigations ("DOI") of the City any solicitation of money, goods, requests for future employment or other benefit or thing of value, by or on behalf of any employee of the City or other person, firm, corporation or entity for any purpose which may be related to the procurement or obtaining of this Contract by the Contractor, or affecting the performance of this Contract.

#### **ARTICLE 64. TERMINATION BY THE CITY**

- 64.1 In addition to termination pursuant to any other article of this Contract, the Commissioner may, at any time, terminate this Contract by written notice to the Contractor. In the event of termination, the Contractor shall, upon receipt of such notice, unless otherwise directed by the Commissioner:
  - 64.1.1 Stop Work on the date specified in the notice;
  - 64.1.2 Take such action as may be necessary for the protection and preservation of the City's materials and property;
  - 64.1.3 Cancel all cancelable orders for material and equipment;
  - 64.1.4 Assign to the City and deliver to the Site or another location designated by the Commissioner, any non-cancelable orders for material and equipment that is not capable of use except in the performance of this Contract and has been specifically fabricated for the sole purpose of this Contract and not incorporated in the Work;
  - 64.1.5 Take no action which will increase the amounts payable by the City under this Contract.
- 64.2 In the event of termination by the **City** pursuant to this Article 64, payment to the **Contractor** shall be in accordance with Articles 64.2.1, 64.2.2 or 64.2.3, to the extent that each respective article applies.
  - 64.2.1 Lump Sum Contracts or Items: On all lump sum Contracts, or on lump sum items in a Contract, the City will pay the Contractor the sum of the amounts described in Articles 64.2.1(a) and 64.2.1(b), less all payments previously made pursuant to this Contract. On lump sum Contracts only, the City will also pay the Contractor an additional sum as provided in Article 64.2.1(c).
    - 64.2.1(a) For Work completed prior to the notice of termination, the Contractor shall be paid a pro rata portion of the lump sum bid amount, plus approved change orders, based upon the percent completion of the Work, as determined by the Commissioner. For the purpose of determining the pro rata portion of the lump sum bid amount to which the Contractor is entitled, the bid breakdown submitted in accordance with Article 41 shall be considered, but shall not be dispositive. The Commissioner's determination hereunder shall be final, binding, and conclusive.

- 64.2.1(b) For non-cancelable material and equipment that is not capable of use except in the performance of this Contract and has been specifically fabricated for the sole purpose of this Contract, but not yet incorporated in the Work, the Contractor shall be paid the lesser of the following, less salvage value:
  - 64.2.1(b)(i) The Direct Cost, as defined in Article 64.2.4; or
  - 64.2.1(b)(ii) The fair and reasonable value, if less than Direct Cost, of such material and equipment, plus necessary and reasonable delivery costs.
  - 64.2.1(b)(iii) In addition, the **Contractor** shall be paid five (5%) percent of the amount described in Article 64.2.1(b)(i) or Article 64.2.1(b)(ii), whichever applies.
- 64.2.1(c) Except as otherwise provided in Article 64.2.1(d), on all lump sum Contracts, the Contractor shall be paid the percentage indicated below applied to the difference between the total lump sum bid amount and the total of all payments made prior to the notice of termination plus all payments allowed pursuant to Articles 64.2.1(a) and 64.2.1(b):
  - 64.2.1(c)(i) Five (5%) percent of the first five million (\$5,000,000) dollars; and
  - 64.2.1(c)(ii) Three (3%) percent of any amount between five million (\$5,000,000) dollars and fifteen million (\$15,000,000) dollars; plus
  - 64.2.1(c)(iii) One (1%) percent of any amount over fifteen million (\$15,000,000) dollars.
- 64.2.1(d) In the event the City terminates a lump sum Contract pursuant to this Article 64 within ninety (90) Days after registration of the Contract with the Comptroller, the Contractor shall be paid one (1%) percent of the difference between the lump sum bid amount and the total of all payments made pursuant to this Article 64.2.
- 64.2.2 Unit Price Contracts or Items: On all unit price Contracts, or on unit price items in a Contract, the City will pay the Contractor the sum of the amounts described in Articles 64.2.2(a) and 64.2.2(b), less all payments previously made pursuant to this Contract:
  - 64.2.2(a) For all completed units, the unit price stated in the Contract, and
  - 64.2.2(b) For units that have been ordered but are only partially completed, the Contractor will be paid:
    - 64.2.2(b)(i) A pro rata portion of the unit price stated in the Contract based upon the percent completion of the unit and
    - 64.2.2(b)(ii) For non-cancelable material and equipment, payment will be made pursuant to Article 64.2.1(b).
- 64.2.3 Time and Materials Contracts or Items Based on Time and Material Records: On all Contracts or items in a Contract where payment for the Work is based on time and

material records, the Contractor shall be paid in accordance with Article 26, less all payments previously made pursuant to this Contract.

- 64.2.4 Direct Costs: Direct Costs as used in this Article 64.2 shall mean:
  - 64.2.4(a) The actual purchase price of material and equipment, plus necessary and reasonable delivery costs,
  - 64.2.4(b) The actual cost of labor involved in construction and installation at the Site, and
  - 64.2.4(c) The actual cost of necessary bonds and insurance purchased pursuant to requirements of this Contract less any amounts that have been or should be refunded by the Contractor's sureties or insurance carriers.
  - 64.2.4(d) Direct Costs shall not include overhead.
- 64.3 In no event shall any payments under this Article 64 exceed the Contract price for such items.
- 64.4 All payments pursuant to Article 64 shall be in the nature of liquidated damages and shall be accepted by the Contractor in full satisfaction of all claims against the City.
- 64.5 The City may deduct or set off against any sums due and payable pursuant to this Article 64, any deductions authorized by this Contract or by Law (including but not limited to liquidated damages) and any claims it may have against the Contractor. The City's exercise of the right to terminate the Contract pursuant to this Article 64 shall not impair or otherwise effect the City's right to assert any claims it may have against the Contractor in a plenary action.
- 64.6 Where the Work covered by the Contract has been substantially completed, as determined in writing by the Commissioner, termination of the Work shall be handled as an omission of Work pursuant to Articles 29 and 33, in which case a change order will be issued to reflect an appropriate reduction in the Contract sum, or if the amount is determined after final payment, such amount shall be paid by the Contractor.

#### ARTICLE 65. CHOICE OF LAW, CONSENT TO JURISDICTION AND VENUE

- 65.1 This Contract shall be deemed to be executed in the City regardless of the domicile of the Contractor, and shall be governed by and construed in accordance with the Laws of the State of New York and the Laws of the United States, where applicable.
- 65.2 The parties agree that any and all claims asserted against the City arising under this Contract or related thereto shall be heard and determined in the courts of the State of New York ("New York State Courts") located in the City and County of New York. To effect this Contract and intent, the Contractor agrees:
  - 65.2.1 If the City initiates any action against the Contractor in Federal court or in a New York State Court, service of process may be made on the Contractor either in person, wherever such Contractor may be found, or by registered mail addressed to the Contractor at its address as set forth in this Contract, or to such other address as the Contractor may provide to the City in writing; and

- 65.2.2 With respect to any action between the **City** and the **Contractor** in a New York State Court, the **Contractor** hereby expressly waives and relinquishes any rights it might otherwise have:
  - 65.2.2(a) To move to dismiss on grounds of forum non conveniens;
  - 65.2.2(b) To remove to Federal Court; and
  - 65.2.2(c) To move for a change of venue to a New York State Court outside New York County.
- 65.2.3 With respect to any action brought by the City against the Contractor in a Federal Court located in the City, the Contractor expressly waives and relinquishes any right it might otherwise have to move to transfer the action to a Federal Court outside the City.
- 65.2.4 If the Contractor commences any action against the City in a court located other than in the City and County of New York, upon request of the City, the Contractor shall either consent to a transfer of the action to a New York State Court of competent jurisdiction located in the City and County of New York or, if the Court where the action is initially brought will not or cannot transfer the action, the Contractor shall consent to dismiss such action without prejudice and may thereafter reinstate the action in a New York State Court of competent jurisdiction in New York County.
- 65.3 If any provision(s) of this Article 65 is held unenforceable for any reason, each and all other provision(s) shall nevertheless remain in full force and effect.

#### ARTICLE 66. PARTICIPATION IN AN INTERNATIONAL BOYCOTT

- 66.1 The Contractor agrees that neither the Contractor nor any substantially owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the Federal Export Administration Act of 1979, as amended, or the regulations of the United States Department of Commerce (Commerce Department) promulgated thereunder.
- 66.2 Upon the final determination by the Commerce Department or any other agency of the United States as to, or conviction of the Contractor or a substantially-owned affiliated company thereof for participation in an international boycott in violation of the provisions of the Export Administration Act of 1979, as amended, or the regulations promulgated thereunder, the Comptroller may, at his/her option, render forfeit and void this Contract.
- 66.3 The Contractor shall comply in all respects, with the provisions of Section 6-114 of the Administrative Code and the rules and regulations issued by the Comptroller thereunder.

### ARTICLE 67. LOCALLY BASED ENTERPRISE PROGRAM

67.1 This Contract is subject to the requirements of Section 6-108.1 of the Administrative Code and regulations promulgated thereunder. No construction contract shall be awarded unless and until these requirements have been complied with in their entirety; however, compliance with this Article 67 is not required if the Agency sets Subcontractor Participation Goals for Minority- and Women-Owned Business Enterprises (M/WBEs).

- 67.2 Unless specifically waived by the Commissioner with the approval of the Division of Economic and Financial Opportunity of the City Department of Business Services, if any portion of the Contract is subcontracted, not less than ten (10%) percent of the total dollar amount of the Contract shall be awarded to locally based enterprises (LBEs); except that where less than ten (10%) percent of the total dollar amount of the Contract is subcontracted, such lesser percentage shall be so awarded.
  - 67.3 The Contractor shall not require performance and payment bonds from LBE Subcontractors.
- 67.4 If the Contractor has indicated prior to award that no Work will be subcontracted, no Work shall be subcontracted without the prior approval of the Commissioner, which shall be granted only if the Contractor makes a good faith effort beginning at least six (6) weeks before the Work is to be performed to obtain LBE Subcontractors to perform the Work.
- 67.5 If the Contractor has not identified sufficient LBE Subcontractors prior to award, it shall sign a letter of compliance stating that it complies with Section 6-108.1 of the Administrative Code, recognizes that achieving the LBE requirement is a condition of its Contract, and shall submit documentation demonstrating its good faith efforts to obtain LBEs. After award, the Contractor shall begin to solicit LBE's to perform subcontracted Work at least six (6) weeks before the date such Work is to be performed and shall demonstrate that a good faith effort has been made to obtain LBEs on each subcontract until it meets the required percentage.
- 67.6 Failure of the Contractor to comply with the requirements of Section 6-108.1 of the Administrative Code and the regulations promulgated thereunder shall constitute a material breach of this Contract. Remedy for such breach may include the imposition of any or all of the following sanctions:
  - 67.6.1 Reducing the Contractor's compensation by an amount equal to the dollar value of the percentage of the LBE subcontracting requirement not complied with;
  - 67.6.2 Declaring the Contractor in default;
  - 67.6.3 If the Contractor is an LBE, de-certifying and declaring the Contractor ineligible to participate in the LBE program for a period of up to three (3) years.

#### ARTICLE 68. ANTITRUST

68.1 The Contractor hereby assigns, sells, and transfers to the City all right, title, and interest in and to any claims and causes of action arising under the antitrust Laws of New York State or of the United States relating to the particular goods or services purchased or procured by the City under this Contract.

#### ARTICLE 69. MacBRIDE PRINCIPLES PROVISIONS

- 69.1 Notice To All Prospective Contractors:
  - 69.1.1 Local Law No. 34 of 1991 became effective on September 10, 1991 and added Section 6-115.1 of the Administrative Code. The local Law provides for certain restrictions on City Contracts to express the opposition of the people of the City to employment discrimination practices in Northern Ireland to promote freedom of work-place opportunity.
- 69.1.2 Pursuant to Section 6-115.1, prospective Contractors for Contracts to provide goods or services involving an expenditure of an amount greater than ten thousand STANDARD CONSTRUCTION CONTRACT CITY OF NEW YORK 75

- (\$10,000.) dollars, or for construction involving an amount greater than fifteen thousand (\$15,000.) dollars, are asked to sign a rider in which they covenant and represent, as a material condition of their Contract, that any business operations in Northern Ireland conducted by the Contractor and any individual or legal entity in which the Contractor holds a ten (10%) percent or greater ownership interest in the Contractor will be conducted in accordance with the MacBride Principles of nondiscrimination in employment.
- 69.1.3 Prospective Contractors are not required to agree to these conditions. However, in the case of Contracts let by competitive sealed bidding, whenever the lowest responsible bidder has not agreed to stipulate to the conditions set forth in this notice and another bidder who has agreed to stipulate to such conditions has submitted a bid within five (5%) percent of the lowest responsible bid for a Contract to supply goods, services or contraction of comparable quality, the Agency shall refer such bids to the Mayor, the Speaker or other officials, as appropriate, who may determine, in accordance with applicable Law, that it is in the best interest of the City that the Contract be awarded to other than the lowest responsible pursuant to Section 313(b)(2) of the City Charter.
- 69.1.4 In the case of Contracts let by other than competitive sealed bidding, if a prospective Contractor does not agree to these conditions, no Agency, elected official or the City Council shall award the Contract to that bidder unless the Agency seeking to use the goods, services or construction certifies in writing that the Contract is necessary for the Agency to perform its functions and there is no other responsible Contractor who will supply goods, services or construction of comparable quality at a comparable price.
- 69.2 In accordance with Section 6-115.1 of the Administrative Code, the Contractor stipulates that such Contractor and any individual or legal entity in which the Contractor holds a ten (10%) percent or greater ownership interest in the Contractor either:
  - 69.2.1 Have no business operations in Northern Ireland, or
  - 69.2.2 Shall take lawful steps in good faith to conduct any business operations they have in Northern Ireland in accordance with the MacBride Principles, and shall permit independent monitoring of their compliance with such principles.
  - 69.3 For purposes of this Article, the following terms shall have the following meanings:
    - 69.3.1 "MacBride Principles" shall mean those principles relating to nondiscrimination in employment and freedom of work-place opportunity which require employers doing business in Northern Ireland to:
      - 69.3.1(a) increase the representation of individuals from under-represented religious groups in the workforce, including managerial, supervisory, administrative, clerical and technical jobs;
      - 69.3.1(b) take steps to promote adequate security for the protection of employees from under-represented religious groups both at the work-place and while traveling to and from **Work**;
      - 69.3.1(c) ban provocative religious or political emblems from the workplace;
      - 69.3.1(d) publicly advertise all job openings and make special recruitment efforts to attract applicants from under-represented religious groups;

- 69.3.1(e) establish layoff, recall, and termination procedures which do not in practice favor a particular religious group;
- 69.3.1(f) abolish all job reservations, apprenticeship restrictions and different employment criteria which discriminate on the basis of religion;
- 69.3.1(g) develop training programs that will prepare substantial numbers of current employees from under-represented religious groups for skilled jobs, including the expansion of existing programs and the creation of new programs to train, upgrade, and improve the skills of workers from under-represented religious groups;
- 69.3.1(h) establish procedures to asses, identify, and actively recruit employees from under-represented religious groups with potential for further advancement; and
- 69.3.1(i) appoint a senior management staff member to oversee affirmative action efforts and develop a timetable to ensure their full implementation.
- 69.4 The Contractor agrees that the covenants and representations in Article 69.2 are material conditions to this Contract. In the event the Agency receives information that the Contractor who made the stipulation required by this Article 69 is in violation thereof, the Agency shall review such information and give the Contractor an opportunity to respond. If the Agency finds that a violation has occurred, the Agency shall have the right to declare the Contractor in default in default and/or terminate this Contract for cause and procure supplies, services or Work from another source in the manner the Agency deems proper. In the event of such termination, the Contractor shall pay to the Agency, or the Agency in its sole discretion may withhold from any amounts otherwise payable to the Contractor, the difference between the Contract price for the uncompleted portion of this Contract and the cost to the Agency of completing performance of this Contract either itself or by engaging another Contractor or Contractors. In the case of a requirement Contract, the Contractor shall be liable for such difference in price for the entire amount of supplies required by the Agency for the uncompleted term of Contractor's Contract. In the case of a construction Contract, the Agency shall also have the right to hold the Contractor in partial or total default in accordance with the default provisions of this Contract, and/or may seek debarment or suspension of the Contractor. The rights and remedies of the Agency hereunder shall be in addition to, and not in lieu of, any rights and remedies the Agency has pursuant to this Contract or by operation of Law.

#### ARTICLE 70. ELECTRONIC FILING/NYC DEVELOPMENT HUB

70.1 The Contractor shall electronically file all alteration type-2 and alteration type-3 applications via the New York City Development Hub Web site, except applications for the following types of minor alterations: enlargements, curb cuts, legalizations, fire alarms, builders pavement plans, and jobs filed on Landmark Preservation Commission calendared properties. All such filings must be professionally certified. Information about electronic filing via the New York City Development Hub is available on the City Department of Buildings Web site at www.nyc.gov/buildings.

#### **ARTICLE 71. PROHIBITION OF TROPICAL HARDWOODS**

71.1 Tropical hardwoods, as defined in Section 165 of the New York State Finance Law (Finance Law), shall not be utilized in the performance of this Contract except as expressly permitted by Section 165 of the Finance Law.

#### **ARTICLE 72. CONFLICTS OF INTEREST**

72.1 Section 2604 of the City Charter and other related provisions of the City Charter, the Administrative Code, and the Penal Law are applicable under the terms of this Contract in relation to conflicts of interest and shall be extended to Subcontractors authorized to perform Work, labor and services pursuant to this Contract and further, it shall be the duty and responsibility of the Contractor to so inform its respective Subcontractors. Notice is hereby given that, under certain circumstances, penalties may be invoked against the donor as well as the recipient of any form of valuable gift.

# ARTICLE 73. MERGER CLAUSE

73.1 The written Contract herein, contains all the terms and conditions agreed upon by the parties hereto, and no other agreement, oral or otherwise, regarding the subject matter of this Contract shall be deemed to exist or to bind any of the parties hereto, or to vary any of the terms contained herein.

## **ARTICLE 74. STATEMENT OF WORK**

74.1 The Contractor shall furnish all labor and materials and perform all Work in strict accordance with the Specifications and Addenda thereto, numbered \_\_\_\_\_\_.

#### ARTICLE 75. COMPENSATION TO BE PAID TO CONTRACTOR

75.1 The City will pay and the Contractor will accept in full consideration for the performance of the Contract, subject to additions and deductions as provided herein, the total sum of:

| Dollars, (\$ 10, 72 | 45 | 40), this said sum being the amount at which the Contract was awarded to the Contractor at a public letting thereof, based upon the Contractor's bid for the Contract. Thousand four further than the Contract of the Contractor's bid for the Contract.

# <u>ARTICLE 76. ELECTRONIC FUNDS TRANSFER</u>

- 76.1 In accordance with Section 6-107.1 of the Administrative Code, the Contractor agrees to accept payments under this Contract from the City by electronic funds transfer (EFT). An EFT is any transfer of funds, other than a transaction originated by check, draft or similar paper instrument, which is initiated through an electronic terminal, telephonic instrument or computer or magnetic tape so as to order, instruct or authorize a financial institution to debit or credit an account. Prior to the first payment made under this Contract, the Contractor shall designate one financial institution or other authorized payment agent and shall complete the attached "EFT Vendor Payment Enrollment Form" in order to provide the Commissioner of the City Department of Finance with information necessary for the Contractor to receive electronic funds transfer payments through a designated financial institution or authorized payment agent. The crediting of the amount of a payment to the appropriate account on the books of a financial institution or other authorized payment agent designated by the Contractor shall constitute full satisfaction by the City for the amount of the payment under this Contract. The account information supplied by the Contractor to facilitate the electronic funds transfer shall remain confidential to the fullest extent provided by Law.
- 76.2 The Commissioner may waive the application of the requirements of this Article 76 to payments on contracts entered into pursuant to Section 315 of the City Charter. In addition, the Commissioner of the Department of Finance and the Comptroller may jointly issue standards pursuant to CITY OF NEW YORK

  78 STANDARD CONSTRUCTION CONTRACT

  DDC

  December 2013

which the **Agency** may waive the requirements of this Article 76 for payment in the following circumstances: (i) for individuals or classes of individuals for whom compliance imposes a hardship; (ii) for classifications or types of checks; or (iii) in other circumstances as may be necessary in the interest of the **City**.

#### **ARTICLE 77. RECORDS RETENTION**

77.1 The **Contractor** agrees to retain all books, records, and other documents relevant to this **Contract** for six years after the final payment or termination of this **Contract**, whichever is later. **City**, state, and federal auditors and any other persons duly authorized by the **City** shall have full access to and the right to examine any such books, records, and other documents during the retention period.

# ARTICLE 78. PARTICIPATION BY MINORITY-OWNED AND WOMEN-OWNED BUSINESS ENTERPRISES IN CITY PROCUREMENT

#### **NOTICE TO ALL PROSPECTIVE CONTRACTORS**

#### ARTICLE I. M/WBE PROGRAM

Local Law No. 129 of 2005 added and Local Law 1 of 2013 amended Section 6-129 of the Administrative Code of the City of New York (hereinafter "Section 6-129"). Section 6-129 establishes the program for participation in City procurement ("M/WBE Program") by minority- owned business enterprises ("MBEs") and women-owned business enterprises ("WBEs"), certified in accordance with Section 1304 of the New York City Charter. As stated in Section 6-129, the intent of the program is to address the impact of discrimination on the City's procurement process, and to promote the public interest in avoiding fraud and favoritism in the procurement process, increasing competition for City business, and lowering contract costs. The contract provisions contained herein are pursuant to Section 6-129, and the rules of the Department of Small Business Services ("DSBS") promulgated thereunder.

If this Contract is subject to the M/WBE Program established by Section 6-129, the specific requirements of MBE and/or WBE participation for this Contract are set forth in Schedule B of the Contract (entitled the "M/WBE Utilization Plan"), and are detailed below. The Contractor must comply with all applicable MBE and WBE requirements for this Contract.

All provisions of Section 6-129 are hereby incorporated in the Contract by reference and all terms used herein that are not defined herein shall have the meanings given such terms in Section 6-129. Article I, Part A, below, sets forth provisions related to the participation goals for construction, standard and professional services contracts. Article I, Part B, below, sets forth miscellaneous provisions related to the M/WBE Program.

#### PART A

# PARTICIPATION GOALS FOR CONSTRUCTION, STANDARD AND PROFESSIONAL SERVICES CONTRACTS OR TASK ORDERS

1. The MBE and/or WBE Participation Goals established for this Contract or Task Orders issued pursuant to this Contract, ("Participation Goals"), as applicable, are set forth on Schedule B, Part I to this Contract (see Page 1, line 1 Total Participation Goals) or will be set forth on Schedule B, Part I to Task Orders issued pursuant to this Contract, as applicable.

The Participation Goals represent a percentage of the total dollar value of the Contract or Task Order, as applicable, that may be achieved by awarding subcontracts to firms certified with New York City Department of Small Business Services as MBEs and/or WBEs, and/or by crediting the participation of prime contractors and/or qualified joint ventures as provided in Section 3 below, unless the goals have been waived or modified by Agency in accordance with Section 6-129 and Part A, Sections 10 and 11 below, respectively.

- 2. If Participation Goals have been established for this Contract or Task Orders issued pursuant to this Contract, Contractor agrees or shall agree as a material term of the Contract that Contractor shall be subject to the Participation Goals, unless the goals are waived or modified by Agency in accordance with Section 6-129 and Part A, Sections 10 and 11 below, respectively.
- 3. If Participation Goals have been established for this Contract or Task Order issued pursuant to this Contract, a Contractor that is an MBE and/or WBE shall be permitted to count its own participation toward fulfillment of the relevant Participation Goal, provided that in accordance with Section 6-129 the value of Contractor's participation shall be determined by subtracting from the total value of the Contract or Task Order, as applicable, any amounts that the Contractor pays to direct subcontractors (as defined in Section 6-129(c)(13)), and provided further that a Contractor that is certified as both an MBE and a WBE may count its own participation either toward the goal for MBEs or the goal for WBEs, but not both.

A Contractor that is a qualified joint venture (as defined in Section 6-129(c)(30)) shall be permitted to count a percentage of its own participation toward fulfillment of the relevant **Participation Goal**. In accordance with Section 6-129, the value of Contractor's participation shall be determined by subtracting from the total value of the Contract or Task Order, as applicable, any amounts that Contractor pays to direct subcontractors, and then multiplying the remainder by the percentage to be applied to total profit to determine the amount to which an MBE or WBE is entitled pursuant to the joint venture agreement, provided that where a participant in a joint venture is certified as both an MBE and a WBE, such amount shall be counted either toward the goal for MBEs or the goal for WBEs, but not both.

- 4. A. If **Participation Goals** have been established for this Contract, a prospective contractor shall be required to submit with its bid or proposal, as applicable, a completed Schedule B, M/WBE Utilization Plan, Part II (see Pages 2-4) indicating: (a) whether the contractor is an MBE or WBE, or qualified joint venture; (b) the percentage of work it intends to award to direct subcontractors; and (c) in cases where the contractor intends to award direct subcontracts, a description of the type and dollar value of work designated for participation by MBEs and/or WBEs, and the time frames in which such work is scheduled to begin and end. In the event that this M/WBE Utilization Plan indicates that the bidder or proposer, as applicable, does not intend to meet the **Participation Goals**, the bid or proposal, as applicable, shall be deemed non-responsive, unless Agency has granted the bidder or proposer, as applicable, a pre-award waiver of the Participation Goals in accordance with Section 6-129 and Part A, Section 10 below.
- B. (i) If this Contract is for a master services agreement or other requirements type contract that will result in the issuance of Task Orders that will be individually registered ("Master Services Agreement") and is subject to M/WBE Participation Goals, a prospective contractor shall be required to submit with its bid or proposal, as applicable, a completed Schedule B, M/WBE Participation Requirements for Master Services Agreements That Will Require Individually Registered Task Orders, Part II (page 2) indicating the prospective contractor's certification and required affirmations to make all reasonable good faith efforts to meet participation goals established on each individual Task Order issued pursuant to this Contract, or if a partial waiver is obtained or such goals are modified by the Agency, to meet the modified Participation Goals by soliciting and obtaining the participation of certified MBE and/or WBE firms. In the event that the Schedule B indicates that the bidder or proposer, as applicable, does not intend to meet the Participation Goals that may be established on Task Orders issued pursuant to this Contract, the bid or proposal, as applicable, shall be deemed nonresponsive.

- (ii) Participation Goals on a Master Services Agreement will be established for individual Task Orders issued after the Master Services Agreement is awarded. If Participation Goals have been established on a Task Order, a contractor shall be required to submit a Schedule B M/WBE Utilization Plan For Independently Registered Task Orders That Are Issued Pursuant to Master Services Agreements, Part II (see Pages 2-4) indicating: (a) whether the contractor is an MBE or WBE, or qualified joint venture; (b) the percentage of work it intends to award to direct subcontractors; and (c) in cases where the contractor intends to award direct subcontracts, a description of the type and dollar value of work designated for participation by MBEs and/or WBEs, and the time frames in which such work is scheduled to begin and end. The contractor must engage in good faith efforts to meet the Participation Goals as established for the Task Order unless Agency has granted the contractor a pre-award waiver of the Participation Goals in accordance with Section 6-129 and Part A, Section 10 below.
- C. THE BIDDER/PROPOSER MUST COMPLETE THE SCHEDULE B INCLUDED HEREIN (SCHEDULE B, PART II). A SCHEDULE B SUBMITTED BY THE BIDDER/PROPOSER WHICH DOES NOT INCLUDE THE VENDOR CERTIFICATION AND REQUIRED AFFIRMATIONS (SEE SECTION V OF PART II) WILL BE DEEMED TO BE NON-RESPONSIVE, UNLESS A FULL WAIVER OF THE PARTICIPATION GOALS IS GRANTED (SCHEDULE B, PART III). IN THE EVENT THAT THE CITY DETERMINES THAT THE BIDDER/PROPOSER HAS SUBMITTED A SCHEDULE B WHERE THE CERTIFICATION AND REQUIRED AFFIRMATIONS ARE COMPLETED BUT OTHER ASPECTS OF THE SCHEDULE B ARE NOT COMPLETE, OR CONTAIN A COPY OR COMPUTATION ERROR THAT IS AT ODDS WITH THE VENDOR CERTIFICATION AND AFFIRMATIONS, THE BIDDER/PROPOSER WILL BE NOTIFIED BY THE AGENCY AND WILL BE GIVEN FOUR (4) CALENDAR DAYS FROM RECEIPT OF NOTIFICATION TO CURE THE SPECIFIED DEFICIENCIES AND RETURN A COMPLETED SCHEDULE B TO THE AGENCY. FAILURE TO DO SO WILL RESULT IN A DETERMINATION THAT THE BID/PROPOSAL IS NON-RESPONSIVE. RECEIPT OF NOTIFICATION IS DEFINED AS THE DATE NOTICE IS E-MAILED OR FAXED (IF THE BIDDER/PROPOSER HAS PROVIDED AN E-MAIL ADDRESS OR FAX NUMBER), OR NO LATER THAN FIVE (5) CALENDAR DAYS FROM THE DATE OF MAILING OR UPON DELIVERY, IF DELIVERED.
- 5. Where an M/WBE Utilization Plan has been submitted, the Contractor shall, within 30 days of issuance by Agency of a notice to proceed, submit a list of proposed persons or entities to which it intends to award subcontracts within the subsequent 12 months. In the case of multiyear contracts, such list shall also be submitted every year thereafter. The Agency may also require the Contractor to report periodically about the contracts awarded by its direct subcontractors to indirect subcontractors (as defined in Section 6-129(c)(22)). PLEASE NOTE: If this Contract is a public works project subject to GML §101(5) (i.e., a contract valued at or below \$3M for projects in New York City) or if the Contract is subject to a project labor agreement in accordance with Labor Law §222, and the bidder is required to identify at the time of bid submission its intended subcontractors for the Wicks trades (plumbing and gas fitting; steam heating, hot water heating, ventilating and air conditioning (HVAC); and electric wiring), the Contractor must identify all those to which it intends to award construction subcontracts for any portion of the Wicks trade work at the time of bid submission, regardless of what point in the life of the contract such subcontracts will occur. In identifying intended subcontractors in the bid submission, bidders may satisfy any Participation Goals established for this Contract by proposing one or more subcontractors that are MBEs and/or WBEs for any portion of the Wicks trade work. In the event that the Contractor's selection of a subcontractor is disapproved, the Contractor shall have a reasonable time to propose alternate subcontractors.
- 6. MBE and WBE firms must be certified by DSBS in order for the Contractor to credit such firms' participation toward the attainment of the **Participation Goals**. Such certification must occur prior to the

firms' commencement of work. A list of MBE and WBE firms may be obtained from the DSBS website at www.nyc.gov/buycertified, by emailing DSBS at buyer@sbs.nyc.gov, by calling (212) 513-6356, or by visiting or writing DSBS at 110 William St., New York, New York, 10038, 7th floor. Eligible firms that have not yet been certified may contact DSBS in order to seek certification by visiting www.nyc.gov/getcertified, emailing MWBE@sbs.nyc.gov, or calling the DSBS certification helpline at (212) 513-6311. A firm that is certified as both an MBE and a WBE may be counted either toward the goal for MBEs or the goal for WBEs, but not both. No credit shall be given for participation by a graduate MBE or graduate WBE, as defined in Section 6-129(c)(20).

- Where an M/WBE Utilization Plan has been submitted, the Contractor shall, with each voucher for payment, and/or periodically as Agency may require, submit statements, certified under penalty of perjury, which shall include, but not be limited to,: the total amount the Contractor paid to its direct subcontractors, and, where applicable pursuant to Section 6-129(j), the total amount direct subcontractors paid to indirect subcontractors; the names, addresses and contact numbers of each MBE or WBE hired as a subcontractor by the Contractor, and, where applicable, hired by any of the Contractor's direct subcontractors; and the dates and amounts paid to each MBE or WBE. The Contractor shall also submit, along with its voucher for final payment: the total amount it paid to subcontractors, and, where applicable pursuant to Section 6-129(j), the total amount its direct subcontractors paid directly to their indirect subcontractors; and a final list, certified under penalty of perjury, which shall include the name, address and contact information of each subcontractor that is an MBE or WBE, the work performed by, and the dates and amounts paid to each.
- 8. If payments made to, or work performed by, MBEs or WBEs are less than the amount specified in the Contractor's M/WBE Utilization Plan, Agency shall take appropriate action, in accordance with Section 6-129 and Article II below, unless the Contractor has obtained a modification of its M/WBE Utilization Plan in accordance with Section 6-129 and Part A, Section 11 below.
- 9. Where an M/WBE Utilization Plan has been submitted, and the Contractor requests a change order the value of which exceeds the greater of 10 percent of the Contract or Task Order, as applicable, or \$500,000, Agency shall review the scope of work for the Contract or Task Order, as applicable, and the scale and types of work involved in the change order, and determine whether the Participation Goals should be modified.
- 10. Pre-award waiver of the **Participation Goals**. (a) A bidder or proposer, or contractor with respect to a Task Order, may seek a pre-award full or partial waiver of the **Participation Goals** in accordance with Section 6-129, which requests that Agency change one or more **Participation Goals** on the grounds that the **Participation Goals** are unreasonable in light of the availability of certified firms to perform the services required, or by demonstrating that it has legitimate business reasons for proposing a lower level of subcontracting in its M/WBE Utilization Plan.
- (b) To apply for a full or partial waiver of the Participation Goals, a bidder, proposer, or contractor, as applicable, must complete Part III (Page 5) of Schedule B and submit such request no later than seven (7) calendar days prior to the date and time the bids, proposals, or Task Orders are due, in writing to the Agency by email at <a href="mailto:poped@ddc.nyc.gov">poped@ddc.nyc.gov</a> or via facsimile at (718) 391-1886. Bidders, proposers, or contractors, as applicable, who have submitted requests will receive an Agency response by no later than two (2) calendar days prior to the due date for bids, proposals, or Task Orders; provided, however, that if that date would fall on a weekend or holiday, an Agency response will be provided by close-of-business on the business day before such weekend or holiday date.
- (c) If the Agency determines that the **Participation Goals** are unreasonable in light of the availability of certified firms to perform the services required, it shall revise the solicitation and extend the deadline for bids and proposals, or revise the Task Order, as applicable.

- (d) Agency may grant a full or partial waiver of the Participation Goals to a bidder, proposer or contractor, as applicable, who demonstrates—before submission of the bid, proposal or Task Order, as applicable—that it has legitimate business reasons for proposing the level of subcontracting in its M/WBE Utilization Plan. In making its determination, Agency shall consider factors that shall include, but not be limited to, whether the bidder, proposer or contractor, as applicable, has the capacity and the bona fide intention to perform the Contract without any subcontracting, or to perform the Contract without awarding the amount of subcontracts represented by the Participation Goals. In making such determination, Agency may consider whether the M/WBE Utilization Plan is consistent with past subcontracting practices of the bidder, proposer or contractor, as applicable, whether the bidder, proposer, or contractor, as applicable, has made efforts to form a joint venture with a certified firm, and whether the bidder, proposer, or contractor, as applicable, has made good faith efforts to identify other portions of the Contract that it intends to subcontract.
- 11. Modification of M/WBE Utilization Plan. (a) A Contractor may request a modification of its M/WBE Utilization Plan after award of this Contract. PLEASE NOTE: If this Contract is a public works project subject to GML §101(5) (i.e., a contract valued at or below \$3M for projects in New York City) or if the Contract is subject to a project labor agreement in accordance with Labor Law §222, and the bidder is required to identify at the time of bid submission its intended subcontractors for the Wicks trades (plumbing and gas fitting; steam heating, hot water heating, ventilating and air conditioning (HVAC); and electric wiring), the Contractor may request a Modification of its M/WBE Utilization Plan as part of its bid submission. The Agency may grant a request for Modification of a Contractor's M/WBE Utilization Plan if it determines that the Contractor has established, with appropriate documentary and other evidence, that it made reasonable, good faith efforts to meet the Participation Goals. In making such determination, Agency shall consider evidence of the following efforts, as applicable, along with any other relevant factors:
- (i) The Contractor advertised opportunities to participate in the Contract, where appropriate, in general circulation media, trade and professional association publications and small business media, and publications of minority and women's business organizations;
- (ii) The Contractor provided notice of specific opportunities to participate in the Contract, in a timely manner, to minority and women's business organizations;
- (iii) The Contractor sent written notices, by certified mail or facsimile, in a timely manner, to advise MBEs or WBEs that their interest in the Contract was solicited;
- (iv) The Contractor made efforts to identify portions of the work that could be substituted for portions originally designated for participation by MBEs and/or WBEs in the M/WBE Utilization Plan, and for which the Contractor claims an inability to retain MBEs or WBEs;
- (v) The Contractor held meetings with MBEs and/or WBEs prior to the date their bids or proposals were due, for the purpose of explaining in detail the scope and requirements of the work for which their bids or proposals were solicited;
- (vi) The Contractor made efforts to negotiate with MBEs and/or WBEs as relevant to perform specific subcontracts, or act as suppliers or service providers;
- (vii) Timely written requests for assistance made by the Contractor to Agency's M/WBE liaison officer and to DSBS;
- (viii) Description of how recommendations made by DSBS and Agency were acted upon and an explanation of why action upon such recommendations did not lead to the desired level of participation of MBEs and/or WBEs.

Agency's M/WBE officer shall provide written notice to the Contractor of the determination.

(b) The Agency may modify the **Participation Goals** when the scope of the work has been changed by the Agency in a manner that affects the scale and types of work that the Contractor indicated in its **M/WBE** Utilization Plan would be awarded to subcontractors.

- 12. If this Contract is for an indefinite quantity of construction, standard or professional services or is a requirements type contract and the Contractor has submitted an M/WBE Utilization Plan and has committed to subcontract work to MBEs and/or WBEs in order to meet the Participation Goals, the Contractor will not be deemed in violation of the M/WBE Program requirements for this Contract with regard to any work which was intended to be subcontracted to an MBE and/or WBE to the extent that the Agency has determined that such work is not needed.
- 13. If Participation Goals have been established for this Contract or a Task Order issued pursuant to this Contract, at least once annually during the term of the Contract or Task Order, as applicable, Agency shall review the Contractor's progress toward attainment of its M/WBE Utilization Plan, including but not limited to, by reviewing the percentage of work the Contractor has actually awarded to MBE and/or WBE subcontractors and the payments the Contractor made to such subcontractors.
- 14. If Participation Goals have been established for this Contract or a Task Order issued pursuant to this Contract, Agency shall evaluate and assess the Contractor's performance in meeting those goals, and such evaluation and assessment shall become part of the Contractor's overall contract performance evaluation.

#### **PART B: MISCELLANEOUS**

- 1. The Contractor shall take notice that, if this solicitation requires the establishment of an M/WBE Utilization Plan, the resulting contract may be audited by DSBS to determine compliance with Section 6-129. See §6-129(e)(10). Furthermore, such resulting contract may also be examined by the City's Comptroller to assess compliance with the M/WBE Utilization Plan.
- 2. Pursuant to DSBS rules, construction contracts that include a requirement for an M/WBE Utilization Plan shall not be subject to the law governing Locally Based Enterprises set forth in Section 6-108.1 of the Administrative Code of the City of New York.
- 3. DSBS is available to assist contractors and potential contractors in determining the availability of MBEs and/or WBEs to participate as subcontractors, and in identifying opportunities that are appropriate for participation by MBEs and/or WBEs in contracts.
- 4. Prospective contractors are encouraged to enter into qualified joint venture agreements with MBEs and/or WBEs as defined by Section 6-129(c)(30).
- 5. By submitting a bid or proposal the Contractor hereby acknowledges its understanding of the M/WBE Program requirements set forth herein and the pertinent provisions of Section 6-129, and any rules promulgated thereunder, and if awarded this Contract, the Contractor hereby agrees to comply with the M/WBE Program requirements of this Contract and pertinent provisions of Section 6-129, and any rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract. The Contractor hereby agrees to make all reasonable, good faith efforts to solicit and obtain the participation of MBEs and/or WBEs to meet the required **Participation Goals**.

#### ARTICLE II. ENFORCEMENT

1. If Agency determines that a bidder or proposer, as applicable, has, in relation to this procurement, violated Section 6-129 or the DSBS rules promulgated pursuant to Section 6-129, Agency may disqualify such bidder or proposer, as applicable, from competing for this Contract and the Agency may revoke such bidder's or proposer's prequalification status, if applicable.

- 2. Whenever Agency believes that the Contractor or a subcontractor is not in compliance with Section 6-129 or the DSBS rules promulgated pursuant to Section 6-129, or any provision of this Contract that implements Section 6-129, including, but not limited to any M/WBE Utilization Plan, Agency shall send a written notice to the Contractor describing the alleged noncompliance and offering the Contractor an opportunity to be heard. Agency shall then conduct an investigation to determine whether such Contractor or subcontractor is in compliance.
- 3. In the event that the Contractor has been found to have violated Section 6-129, the DSBS rules promulgated pursuant to Section 6-129, or any provision of this Contract that implements Section 6-129, including, but not limited to, any M/WBE Utilization Plan, Agency may determine that one of the following actions should be taken:
- (a) entering into an agreement with the Contractor allowing the Contractor to cure the violation;
- (b) revoking the Contractor's pre-qualification to bid or make proposals for future contracts;
- (c) making a finding that the Contractor is in default of the Contract;
- (d) terminating the Contract;
- (e) declaring the Contractor to be in breach of Contract;
- (f) withholding payment or reimbursement;
- (g) determining not to renew the Contract;
- (h) assessing actual and consequential damages;
- (i) assessing liquidated damages or reducing fees, provided that liquidated damages may be based on amounts representing costs of delays in carrying out the purposes of the M/WBE Program, or in meeting the purposes of the Contract, the costs of meeting utilization goals through additional procurements, the administrative costs of investigation and enforcement, or other factors set forth in the Contract;
- (j) exercising rights under the Contract to procure goods, services or construction from another contractor and charge the cost of such contract to the Contractor that has been found to be in noncompliance; or
- (k) taking any other appropriate remedy.
- 4. If an M/WBE Utilization Plan has been submitted, and pursuant to this Article II, Section 3, the Contractor has been found to have failed to fulfill its Participation Goals contained in its M/WBE Utilization Plan or the Participation Goals as modified by Agency pursuant to Article I, Part A, Section 11, Agency may assess liquidated damages in the amount of ten percent (10%) of the difference between the dollar amount of work required to be awarded to MBE and/or WBE firms to meet the Participation Goals and the dollar amount the Contractor actually awarded and paid, and/or credited, to MBE and/or WBE firms. In view of the difficulty of accurately ascertaining the loss which the City will suffer by reason of Contractor's failure to meet the Participation Goals, the foregoing amount is hereby fixed and agreed as the liquidated damages that the City will suffer by reason of such failure, and not as a penalty. Agency may deduct and retain out of any monies which may become due under this Contract the amount of any such liquidated damages; and in case the amount which may become due under this Contract shall be less than the amount of liquidated damages suffered by the City, the Contractor shall be liable to pay the difference.
- 5. Whenever Agency has reason to believe that an MBE and/or WBE is not qualified for certification, or is participating in a contract in a manner that does not serve a commercially useful function (as defined in Section 6-129(c)(8)), or has violated any provision of Section 6- 129, Agency shall notify the Commissioner of DSBS who shall determine whether the certification of such business enterprise should be revoked.

- 6. Statements made in any instrument submitted to Agency pursuant to Section 6-129 shall be submitted under penalty of perjury and any false or misleading statement or omission shall be grounds for the application of any applicable criminal and/or civil penalties for perjury. The making of a false or fraudulent statement by an MBE and/or WBE in any instrument submitted pursuant to Section 6-129 shall, in addition, be grounds for revocation of its certification.
- 7. The Contractor's record in implementing its M/WBE Utilization Plan shall be a factor in the evaluation of its performance. Whenever Agency determines that a Contractor's compliance with an M/WBE Utilization Plan has been unsatisfactory, Agency shall, after consultation with the City Chief Procurement Officer, file an advice of caution form for inclusion in VENDEX as caution data.

IN WITNESS WHEREOF, the Commissioner, on behalf of the City of New York, and the Contractor, have executed this agreement in quadruplicate, two parts of which are to remain with the Commissioner, another to be filed with the Comptroller of the City, and the fourth to be delivered to the Contractor.

THE CIT I OF	NEW :	UKK			
By: Doputy		dission	lar er	- Carlon Source	
		1			1

CONTRACTOR: Inter Contracting Corp.

(Member of Firm or Officer of Corporation)

Title: President

(Where Contractor is a Corporation, add): Attest:

Secretary

Michael Metino

(Seal)

# ACKNOWLEDGEMENT OF PRINCIPAL, IF A CORPORATION County of Cheens On this Zoth day of Oct , 2014, before me personally came Michael Mitino to me known who, being by me duly sworn did depose and say that he resides at New York, M \_ that he is the /resident of the corporation described in and which executed the foregoing instrument; that he knows the seal of said corporation; that one of the seals affixed to said instrument is such seal) that it was so affixed by order of the directors of said corporation, and that he signed his name the feto by like order. VICTORIA AYO-VAUGHAN Notary Public, State of New York Registration #01AY5014042 Notary Pyolic or Commissioner of Deeds Qualified in Queens County Commission Expires July 15, 2 ACKNOWLEDGEMENT OF PRINCIPAL, IF A PARTNERSHIP State of \_\_\_\_\_ County of \_\_\_\_ ss: On this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_, before me personally appeared to me known, and known to me to be one of the members of the firm of described in and who executed the foregoing instrument; and he acknowledged to me that he executed the same as and for the act and deed of said firm. Notary Public or Commissioner of Deeds ACKNOWLEDGEMENT OF PRINCIPAL, IF AN INDIVIDUAL \_\_\_\_\_ County of \_\_\_\_\_ ss: On this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_, before me personally appeared to me known, and known to me to be the person described in and who executed the foregoing instrument; and acknowledged that he executed the same.

Notary Public or Commissioner of Deeds

# State of New York County of Queen ss: On this Other Acknown to be the Deputy Commissioner of the Department of Design and Construction of The City of New York, the person described as such in and who as such executed the foregoing instrument and acknowledged to me that he executed the same as Deputy Commissioner for the purposes therein mentioned.

VICTORIA AYO-VAUGHAN
Notary Public, State of New York
Registration #01AY5014042
Qualified in Queens County
Commission Expires July 15,

Commissioner of Deeds

# AUTHORITY

# MAYOR'S CERTIFICATE NO. CBX BUDGET DIRECTOR'S CERTIFICATE NO.

DATED DATED

# APPROPRIATION COMMISSIONER'S CERTIFICATE

In conformity with the provisions of Section 6-101 of the Administrative Code of the City of New York, it is hereby certified that the estimated cost of the work, materials and supplies required by the within
Contract, amounting to
Jen million seven hundred twenty
one thousand four hundred fifty one dollars and forty cents
one dollars and forty cents.
Dollars (\$ 10, 721, 451.40)
is chargeable to the fund of the Department of Design and Construction entitled Code
Department of Design and Construction
2 optimization of 2005gn and Constitution
Thombs and the state of the sta
I hereby certify that the specifications contained herein comply with the terms and conditions of the BUDGET.
The head in the
Don'ty Commissioner
COMPTROLLERS GERTING A TOP
COMPTROLLER'S CERTIFICATE
The City of New York
Pursuant to the provisions of Section 6-101 of the Administrative Code of the City of New York, I hereby certify that there remains unapplied and unexpended a balance of the above mentioned fund applicable to this Contract sufficient to pay the estimated expense of executing the same viz:
\$
Compteeller
Comptroller

# MAYOR'S CERTIFICATE OR CERTIFICATE OF THE DIRECTOR OF THE BUDGET

# Performance Bond #2 (Pages 96 to 99): Use if the total contract price is more than \$5 Million.

PERFORMANCE BOND #2 (Page 1)

Bond No. HGNE102690010

PERFORMANCE BOND #2 Bond No. HGNE102690010
KNOW ALL PERSONS BY THESE PRESENTS:, That we, Inter Contracting Corp.
274 White Plains Road, Suite 6, Eastchester, NY 10709
nereinafter referred to as the "Principal," and, Hudson Insurance Company
360 State Route 24, Chester, NJ 07930
nereinafter referred to as the "Surety" ("Sureties") are held and firmly bound to THE CITY OF NEW YORK, hereinafter referred to as the "City" or to its successors and assigns in the penal sum of Ten Million Seven Hundred Twenty One Thousand Four Hundred Fifty One and 40/100
(\$\frac{10,721,451.40}{}\) Dollars, lawful money of the United States for the payment of which said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.
WHEREAS, the Principal is about to enter, or has entered, into a Contract in writing with the City for
Project ID: SER002316. Construction of Storm and Sanitary Sewers and Appurtenances In:
Rossville Avenue Between Mason Boulevard and Woodrow Road etc. Borough of Staten Island
a copy of which Contract is annexed to and hereby made a part of this bond as though herein set forth in full;
NOW, THEREFORE, the conditions of this obligation are such that if the Principal, his or its representatives or assigns, shall well and faithfully perform the said Contract and all modifications, amendments, additions and alterations thereto that may hereafter be made, according to its terms and its true intent and meaning, including repair and or replacement of defective work and guarantees of maintenance for the periods stated in the Contract, and shall fully indemnify and save harmless the City from all cost and damage which it may suffer by reason of the Principal's default of the Contract, and

shall fully reimburse and repay the City for all outlay and expense which the City may incur in making

PERFORMANCE BOND #2 (Page 2)

good any such default and shall protect the said City of New York against, and pay any and all amounts, damages, cost and judgments which may or shall be recovered against said City or its officers or agents or which the said City of New York may be called upon to pay any person or corporation by reason of any damages arising or growing out of the Principal's default of the Contract, then this obligation shall be null and void, otherwise to remain in full force and effect.

The Surety (Sureties), for value received, hereby stipulates and agrees, upon written notice from the City that the City has determined that the Principal is in default of the Contract, to either (1) pay the full amount of the above penal sum in complete discharge and exoneration of this bond and of all the liabilities of the Surety relating to this bond, or (2) fully perform and complete the Work to be performed under the Contract, pursuant to the terms, conditions, and covenants thereof. The Surety (Sureties) further agrees, at its option, either to tender the penal sum or to commence and diligently perform the Work specified in the Contract, including physical site work, within twenty-five (25) business days after written notice thereof from the City and to complete all Work within the time set forth in the Contract or such other time as agreed to between the City and Surety in accordance with the Contract. The Surety and the City reserve all rights and defenses each may have against the other; provided, however, that the Surety expressly agrees that its reservation of rights shall not provide a basis for non-performance of its obligation to commence and to complete all Work as provided herein.

The Surety (Sureties), for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of said Surety (Sureties) and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition, or change in or to the said Contract or the Work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any Work to be performed or any moneys due or to become due thereunder; and said Surety (Sureties) does hereby waive notice of any and all of such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers, and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to said Surety (Sureties) as though done or omitted to be done by or in relation to said Principal.

#### PERFORMANCE BOND #2 (Page 3)

IN WITNESS WHEREOF, The Principal and the Surety (Sureties) have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereunto affixed and these presents to be signed by their proper officers, this

16th	_ day of	October	2014	
(Seal)	-	Inter Contra	acting Corp.	(L.S.)
		7/	Principal	
(Seal)		Ву:		<del></del>
(552)		Hudaan Inauk	Surety ance Company	
		By:	Dan Klippel	
(Seal)			Attorney-In-Fact Surety	
		Ву:		
(Seal)			Surety	
		Ву:		*
(Seal)			Surety	<del>•</del>
		Ву:		
(Seal)			Surety	
		Ву:	· .	
Bond Premium Rate	. 48 Japan			
Bond Premium Cost		-Anna-	<u>.</u>	
If the Contractor (Principal) is a partners.	partnership,	the bond should be	e signed by each of the individ	uals who a

If the Contractor (Principal) is a corporation, the bond should be signed in its correct corporate name by a duly authorized officer, agent, or attorney-in-fact.

There should be executed an appropriate number of counterparts of the bond corresponding to the number of counterparts of the Contract.

PERFORMANCE BOND #2 (Page 4)

	<u>ACF</u>	NOWLEDGE	MENT OF PRI	NCIPAL IF A	<u>CORPORATION</u>
State of	New You	1_	County of	Quens	ss:
On this	rael Mutin	day of 0	tober	, 2014	before me personally
to me known	, who, being b	y me duly swon	n did depose and	say that he resid	es
at New	York N	4	; that	he/she is the	President nt; that he/she signed his/her name to the
of the corpor	ation describe	d in and which	executed the fo	regoing instrume	nt; that he/she signed his/her name to the
foregoing ins	trument by ord	ler of the direct	ors of said compo	ration as the duly abein Leichham blic, State of New Y D. OilE6004261 d in Queens County Expires June 7, 20	authorized and binding act thereof.
Notary Public	or Commissi	oner of Deeds.	Commission	Expires June 7, 20	<b>'</b> 18
					PARTNERSHIP
State of	····		County of	· · · · · · · · · · · · · · · · · · ·	ss:
On this		day of	······································	, 20	before me personally
to me known	who, being b	v me duly swor	, n did depose and	say that he/she r	esides
	,	, 1110 <b>- 111</b>	0.0 00p000 III.		
			· that	ha/sha is	partner of
**************************************		, a limi	ted/general part	ership existing u	nder the laws of the State of
		, the partner	rship described i	n and which exec	uted the foregoing instrument;
		er name to the	foregoing instru	ment as the duly a	authorized and binding act of
said partnersl	up.				
		· · · · · · · · · · · · · · · · · · ·			
Notary Public	c or Commissi	oner of Deeds			
	AC	KNOWLEDG	MENT OF PR	INCIPAL IF A	N INDIVIDUAL
State of			County of		ss:
			•		
came		day of		, 20	before me personally
to me known	, who, being b	y me duly swor	n did depose and	say that he/she r	resides
		•	-	•	
					individual whose name is
		crument and accepted the ins		e that by his/her	signature on the
11104 61110111, 01	ing monvioum	oxocaas inc mi	stramont.		
Notary Public	or Commissi	oner of Deeds	•		
duly certified representative of Attorney or	copy of Power of Principal or r other certifica	of Attorney or Surety; (c) a date of authority	other certificate uly certified extr	of authority when act from By-Laws er or representativ	ents of the respective parties; (b) appropriate e bond is executed by agent, officer or other or resolutions of Surety under which Power was issued, and (d) certified copy of latest
			****	***	
•		Affix Ackn	owledgments a	nd Justification	of Sureties.
CITY OF NE	W YORK DDC	-	99	STAM	December 2013

#### **ACKNOWLEDGMENT OF SURETY COMPANY**

ST/	NEW. UNTY OF .New.	York ssau	} ss									,	
(	On this	October 16,	2014	., befo	ore me p	person	ally cam	e		Sus	an Lupski	••••••	
abov such his/h Insur York quali York	me known, au County  ve instrument; a corporate sea er name there rance of the S , issued to fication eviden	who, being  Hudson Insu that he/she kr il; that is was s eto by like ord tate of New Yo Huds cing the qualifi guarantor, and	by me, Sta rance Co nows the o affixed ler; and ork, has, on Insura cation o	duly te of . mpany seal by the the a pursuance C	sworn, New Yo  of said e Board iffiant did iant to S company Compan	did ork corpor of Dire d furth ection y and	depose the corporation; that ectors of a ler depose 1111 of its suffici	and that he pration at the said cose and the inserve uving it	say; descriseal a prporat I say t suranc (Sander a	that ibed ir ffixed ion; ar that the e Law burety) any lav ch; and	he/she Attorney-in which e to said in that he he Super of the Shis/her of the Shis/her	resides n-Fact of executed nstrumer e/she sig intenden State of N certificate	f the the nt is ned nt of New te of
	•								,				

NY acknowledgement

DANA GRANICE
Notary Public, State of New York
No. 01GR6099128
Qualified in Nassau County
Commission Expires September 22, 2015



#### POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS: That HUDSON INSURANCE COMPANY, a corporation of the State of Delaware, with offices at 100 William Street, New York, New York, 10038, has made, constituted and appointed, and by these presents, does make, constitute and appoint

#### Susan Lupski, George O. Brewster of the State of New York

its true and lawful Attorney(s)-in-Fact, at New York, New York, each of them alone to have full power to act without the other or others, to make, execute and deliver on its behalf, as Surety, bonds and undertakings given for any and all purposes, also to execute and deliver on its behalf as aforesaid renewals, extensions, agreements, waivers, consents or stipulations relating to such bonds or undertakings provided, however, that no single bond or undertaking shall obligate said Company for any portion of the penal sum thereof in excess of the sum of Ten Million Dollars (\$10,000,000.00).

Such bonds and undertakings when duly executed by said Attorney(s)-in-Fact, shall be binding upon said Company as fully and to the same extent as if signed by the President of said Company under its corporate seal attested by its Secretary.

In Witness Whereof, HUDSON INSURANCE COMPANY has caused these presents to be of its Executive Vice President thereunto duly \_, 20 14 at New York, New York. on this 17th day of July

SEAL 1918 Dina Daskalakis

Corporate Secretary

STATE OF NEW YORK COUNTY OF NEW YORK.

SS

HUDSON INSURANCE COMPANY

Christopher T. Suarez **Executive Vice President** 

, 20 14 before me personally came Christopher T. Suarez to me known, who being by me duly sworn did depose and say that he is an Executive Vice President of HUDSON INSURANCE COMPANY, the corporation described herein and which executed the above On the 17th day of July instrument, that he knows the seal of said Corporation, that the seal affixed to said instrument is such corporate seal, that it was so affixed by order of the Board of



Notary Public, State of New No. 01MU6067553

Qualified in Nassau County Commission Expires December 10, 2017

CERTIFICATION

STATE OF NEW YORK COUNTY OF NEW YORK

The undersigned Dina Daskalakis hereby certifies:

That the original resolution, of which the following is a true and correct copy, was duly adopted by unanimous written consent of the Board of Directors of Hudson Insurance Company dated July 27th, 2007, and has not since been revoked, amended or modified:

"RESOLVED, that the President, the Executive Vice Presidents, the Senior Vice Presidents and the Vice Presidents shall have the authority and discretion, to appoint such agent or agents, or attorney or attorneys-in-fact, for the purpose of carrying on this Company's surety business, and to empower such agent or agents, or attorney or attorneys-in-fact, to execute and deliver, under this Company's seal or otherwise, bonds obligations, and recognizances, whether made by this Company as surety thereon or otherwise, indemnity contracts, contracts and certificates, and any and all other contracts and undertakings made in the course of this Company's surety business, and renewals, extensions, agreements, waivers, consents or stipulations regarding undertakings so made; and

FURTHER RESOVLED, that the signature of any such Officer of the Company and the Company's seal may be affixed by facsimile to any power of attorney or certification given for the execution of any bond, undertaking, recognizance, contract of indemnity or other written obligation in the nature thereof or related thereto, such signature and seal when so used whether heretofore or hereafter, being hereby adopted by the Company as the original signature of such officer and the original seal of the Company, to be valid and binding upon the Company with the same force and effect as though

manually affixed. THAT the above and foregoing is a full, true and correct copy of Power of Attorney issued by said Company, and of the whole of the original and that the said Power of Attorney is still in full force and effect and has not been revoked, and furthermore that the Resolution of the Board of Directors, set forth in the said Power of Attorney is now in force.

Witness the hand of the undersigned and the seal of said Corporation this

Dina Daskalakis, Corporate Secretary

0 8 2010 (v1)

#### **HUDSON INSURANCE COMPANY**

#### SHORT FORM FINANCIAL STATEMENT AS OF DECEMBER 31, 2013

#### **ASSETS**

Bonds Real estate Cash on hand and on deposit Reinsurance Receivable FIT recoverable (including net deferred tax asset) Aggregate write-ins for other than invested assets Deferred premiums, agents' balances and installments booked but and not yet due (including earned but unbilled premiums) Stocks Other Assets	\$ deferred	284,085,903 0 59,765,430 100,508,310 22,520,339 133,606,839 22,438,369 178,507,869 17,611,354
	\$ and the second	819.044,413
<u>LIABILITIES &amp; SUI</u>	RPLUS	
Losses Loss adjustment expense Other expenses Unearned premiums Ceded reinsurance premiums payable Payable to parent, subsidiaries and affiliates Commissions payable, contingent commissions and other similar Other Liabilities  Common capital stock Gross paid in and contributed surplus Unassigned funds (surplus) Surplus as regards policyholders	\$ charges \$\$	139,056,862 13,488,009 15,715,028 25,943,552 170,134,375 8,068,736 7,085,785 25,603,414 405,095,761 7,500,000 293,480,097 112,968,317 413,948,652 819,044,413
STATE OF NEW YORK ) ss:  COUNTY OF NEW YORK )		
I, the undersigned Senior Vice President and Chief Financial Officer of foregoing to be a short form financial statement in the form of a balance provisional basis, at the close of hydrogen on December 31, 2013	f Hudson Insurance Company sheet, showing the Company's	hereby certify the sassets and liabilities on a

provisional basis, at the close of business on December 31, 2013.

Senior Vice President and Chief Financial Officer

12 day of Morch 20174 Subscribed the sample of My commission property



PAYMENT BOND (Page 1)

PAYMENT BOND	Bond No. HGNE102690010
KNOW ALL PERSONS BY THESE PRESENTS, That we,Inte	r Contracting Corp.
274 White Plains Road, Suite 6, Eastchester, NY 10709	
hereinafter referred to as the "Principal", and Hudson Insurance Compan	у
360 State Route 24, Chester, NJ 07930	
·	
hereinafter referred to as the "Surety" ("Sureties") are held and firmly bour hereinafter referred to as the "City" or to its successors and assigns, in the per Ten Million Seven Hundred Twenty One Thousand Four Hundred Fifty	nal sum of
(\$\frac{10,721,451.40}{}\) Dollars, lawful money of the United States, for the payme and truly to be made, we, and each of us, bind ourselves, our heirs, executassigns, jointly and severally, firmly by these presents.	ent of which said sum of money well ators, administrators, successors and
WHEREAS, the Principal is about to enter, or has entered, into a Co	ontract in writing with the City for
Project ID: SER002316. Construction of Storm and Sanitary Sewers and Appl	urtenances In: Rossville
Avenue Between Mason Boulevard and Woodrow Road etc. Borough of State	n Island.
a copy of which Contract is annexed to and hereby made a part of this bond a NOW, THEREFORE, the conditions of this obligation are suc	

CITY OF NEW YORK DDC

the prosecution of the Work under said Contract, and any amendment or extension thereof or addition thereto, whether such persons be agents servants or employees of the Principal or any such Subcontractor, including all persons so engaged who perform the work of laborers or mechanics at or in the vicinity of the site

Wages and compensation for labor performed and services rendered by all persons engaged in

PAYMENT BOND (Page 2)

of the Project regardless of any contractual relationship between the Principal or such Subcontractors, or his or their successors or assigns, on the one hand and such laborers or mechanics on the other, but not including office employees not regularly stationed at the site of the project; and

(b) Materials and supplies (whether incorporated in the permanent structure or not), as well as teams, fuels, oils, implements or machinery furnished, used or consumed by said Principal or any subcontractor at or in the vicinity of the site of the Project in the prosecution of the Work under said Contract and any amendment or extension thereof or addition thereto; then this obligation shall be void, otherwise to remain in full force and effect.

This bond is subject to the following additional conditions, limitations and agreements:

- (a) The Principal and Surety (Sureties) agree that this bond shall be for the benefit of any materialmen or laborer having a just claim, as well as the City itself.
- (b) All persons who have performed labor, rendered services or furnished materials and supplies, as aforesaid, shall have a direct right of action against the Principal and his, its or their successors and assigns, and the Surety (Sureties) herein, or against either or both or any of them and their successors and assigns. Such persons may sue in their own name, and may prosecute the suit to judgment and execution without the necessity of joining with any other persons as party plaintiff.
- (c) The Principal and Surety (Sureties) agree that neither of them will hold the City liable for any judgment for costs of otherwise, obtained by either or both of them against a laborer or materialman in a suit brought by either a laborer or materialman under this bond for moneys allegedly due for performing work or furnishing material.
- (d) The Surety (Sureties) or its successors and assigns shall not be liable for any compensation . recoverable by an employee or laborer under the Workmen's Compensation Law.
- (e) In no event shall the Surety (Sureties), or its successors or assigns, be liable for a greater sum than the penalty of this bond or be subject to any suit, action or proceeding hereon that is instituted by any person, firm, or corporation hereunder later than two years after the complete performance of said Contract and final settlement thereof.

The Principal, for himself and his successors and assigns, and the Surety (Sureties), for itself and its successors and assigns, do hereby expressly waive any objection that might be interposed as to the right of the City to require a bond containing the foregoing provisions, and they do hereby further expressly waive any defense which they or either of them might interpose to an action brought hereon by any person, firm or corporation, including subcontractors, materialmen and third persons, for work, labor, services, supplies or material performed rendered, or furnished as aforesaid upon the ground that there is no law authorizing the City to require the foregoing provisions to be place in this bond.

And the Surety (Sureties), for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of said Surety (Sureties), and its bonds shall be in no way impaired or affected by any extension of time, modification, omission, addition, or change in or of the said Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any part thereof, or of any Work to be performed, or any moneys due to become due thereunder and said Surety (Sureties) does hereby waive notice of any and all of such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers, and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, Subcontractors, and other transferees shall have the same effect as to said Surety (Sureties) as though done or omitted to be done or in relation to said Principal.

CITY OF NEW YORK

PAYMENT BOND (Page 3)

IN WITNESS WHEREOF, the and seals, and such of them as are corporthese presents to be signed by their properties.	Principal and the Surety (Sureties) have hereunto set their hands rations have caused their corporate seals to be hereunto affixed and er officers, this 16th day of October , 2014
(Seal)	Inter Contracting Corp. (L.S.)
	Ву:
(Seal)	Hudson Insurance Company Surety
	By:
(Seal)	Surety
	Ву:
(Seal)	Surety
	Ву:
(Seal)	Surety
	By:
•	

If the Contractor (Principal) is a partnership, the bond should be signed by each of the individuals who are partners.

If the Contractor (Principal) is a corporation, the bond should be signed in its correct corporate name by a duly authorized officer, agent, or attorney-in-fact.

There should be executed an appropriate number of counterparts of the bond corresponding to the number of counterparts of the Contract.

PAYMENT BOND (Page 4)

ACKNOV	VLEDGMENT C	F PRINCIPAL,	IF A CORPOR	ATION	
State of	New York	County of _	Queens	ss:	
the corporation	whi, who, being by New York ation described in a; that one of the	and which execuseals affixed to s	nd depose and sa that he is the the foregoin aid instrument is	y that he resides at resides at great resider	of the knows the seal of said was so affixed by order of
			SQOLEL	4	٠
ACKNOV	VLEDGMENT O	Nota F PRINCIPAL,	•	nunissioner of Deeds	Notary Public, State of New You No. Oile6004261 Qualified in Queens County Commission Expires June 7, 20
State of	······································	County of _		ss:	
to me knov	vn, and known to	me to be one of the described in	he members of the and who exec	e firm of	g instrument; and he
		Nota	ry Public or Con	missioner of Deeds	<u> </u>
ACKNOW	LEDGMENT O	F PRINCIPAL,	IF AN INDIVI	DUAL	
State of		County of		ss:	
to me knov	day of vn, and known to vledged that he ex	me to be the per	son described in	lly appeared and who executed	the foregoing instrument;
		Nota	ry Public or Com	nmissioner of Deeds	<u>-</u> -
parties; (b) is executed By-Laws o agent, offic	appropriate duly of by agent, officer resolutions of S	certified copy of or other represer Surety under whi we was issued, an	Power of Attorned tative of Princip ich Power of Att	ey or other certificate all or Surety; (c) a content or other cer	edgments of the respective te of authority where bond duly certified extract from tificate of authority of its hed financial statement of
	A	ffix Acknowledg		cation of Sureties.	
CITY OF N		<del>.</del>			STRUCTION CONTRACT

CITY OF NEW YORK DDC STANDARD CONSTRUCTION CONTRACT
December 2013

### **ACKNOWLEDGMENT OF SURETY COMPANY**

STATE OFNew.York	ss	
On this October 16, 2014	before me personally came	Susan Lupski
Nassau County	me duly sworn, did depose and , State of New York, that he	e/she is the Attorney-in-Fact of the
Tidason insurance	the corporation	described in which executed the
such corporate seal; that is was so aff his/her name thereto by like order; Insurance of the State of New York, I York, issued to Hudson Ir qualification evidencing the qualification	s the seal of said corporation; that the fixed by the Board of Directors of said co and the affiant did further depose and has, pursuant to Section 1111 of the Insurance Company on of said Company and its sufficiency us propriety of accepting and approving it	orporation; and that he/she signed is ay that the Superintendent of surance Law of the State of New (Surety) his/her certificate of under any law of the State of New

NY acknowledgement

DANA GRANICE
Notary Public, State of New York
No. 01GR6099128
Qualified in Nassau County
Commission Expires September 22, 2015



#### POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS: That HUDSON INSURANCE COMPANY, a corporation of the State of Delaware, with offices at 100 William Street, New York, New York, 10038, has made, constituted and appointed, and by these presents, does make, constitute and appoint

#### Susan Lupski, George O. Brewster of the State of New York

its true and lawful Attorney(s)-in-Fact, at New York, New York, each of them alone to have full power to act without the other or others, to make, execute and deliver on its behalf, as Surety, bonds and undertakings given for any and all purposes, also to execute and deliver on its behalf as aforesaid renewals, extensions, agreements, waivers, consents or stipulations relating to such bonds or undertakings provided, however, that no single bond or undertaking shall obligate said Company for any portion of the penal sum thereof in excess of the sum of Ten Million Dollars (\$10,000,000.00).

Such bonds and undertakings when duly executed by said Attorney(s)-in-Fact, shall be binding upon said Company as fully and to the same extent as if signed by the President of said Company under its corporate scal attested by its Secretary.

In Witness Whereof, HUDSON INSURANCE COMPANY has caused these presents to be of its Executive Vice President thereunto duly on this 17th day of July , 20 14 at New York, New York.

HUDSON INSURANCE COMPANY


Christopher T. Suarez Executive Vice President

Dina Daskalakis Corporate Secretary

1918

STATE OF NEW YORK COUNTY OF NEW YORK.

On the 17th day of July , 20 14 before me personally came Christopher T. Suarez to me known, who being by me duly sworn did depose and say that he is an Executive Vice President of HUDSON INSURANCE COMPANY, the corporation described herein and which executed the above instrument, that he knows the seal of said Corporation, that the seal affixed to said instrument is such corporate seal, that it was so affixed by order of the Board of



ANN M. MURPHY Notary Public, State of No. 01MU6067553

Qualified in Nassau County Commission Expires December 10, 2017

CERTIFICATION

STATE OF NEW YORK COUNTY OF NEW YORK

The undersigned Dina Daskalakis hereby certifies:

That the original resolution, of which the following is a true and correct copy, was duly adopted by unanimous written consent of the Board of Directors of Hudson Insurance Company dated July 27th, 2007, and has not since been revoked, amended or modified:

"RESOLVED, that the President, the Executive Vice Presidents, the Senior Vice Presidents and the Vice Presidents shall have the authority and discretion, to appoint such agent or agents, or attorney or attorneys-in-fact, for the purpose of carrying on this Company's surety business, and to empower such agent or agents, or attorney or attorneys-in-fact, to execute and deliver, under this Company's seal or otherwise, bonds obligations, and recognizances, whether made by this Company as surety thereon or otherwise, indemnity contracts, contracts and certificates, and any and all other contracts and undertakings made in the course of this Company's surety business, and renewals, extensions, agreements, waivers, consents or stipulations regarding undertakings so made; and

FURTHER RESOVLED, that the signature of any such Officer of the Company and the Company's seal may be affixed by facsimile to any power of attorney or certification given for the execution of any bond, undertaking, recognizance, contract of indemnity or other written obligation in the nature thereof or related thereto, such signature and seal when so used whether heretofore or hereafter, being hereby adopted by the Company as the original signature of such officer and the original seal of the Company, to be valid and binding upon the Company with the same force and effect as though manually affixed.'

THAT the above and foregoing is a full, true and correct copy of Power of Attorney issued by said Company, and of the whole of the original and that the said Power of Attorney is still in full force and effect and has not been revoked, and furthermore that the Resolution of the Board of Directors, set forth in the said Power of Attorney is now in force.

Witness the hand of the undersigned and the seal of said Corporation this

Dina Daskalakis, Corporate Secretary

10 8 2010 (v1)

#### **HUDSON INSURANCE COMPANY**

## SHORT FORM FINANCIAL STATEMENT AS OF DECEMBER 31, 2013

#### **ASSETS**


Bonds	\$	284,085,903
Real estate		50.765.420
Cash on hand and on deposit		59,765,430
Reinsurance Receivable		100,508,310
FIT recoverable (including net deferred tax asset)		22,520,339
Aggregate write-ins for other than invested assets		133,606,839
Deferred premiums, agents' balances and installments booked but deferred		00 420 270
and not yet due (including earned but unbilled premiums)		22,438,369
Stocks		178,507,869
Other Assets	•	17,611,354
	\$	819,044,413
LIABILITIES & SURPLUS	-	
Losses	\$	139,056,862
Loss adjustment expense	•	13,488,009
Other expenses		15,715,028
Unearned premiums		25,943,552
Ceded reinsurance premiums payable		170,134,375
Payable to parent, subsidiaries and affiliates		8,068,736
Commissions payable, contingent commissions and other similar charges		7,085,785
Other Liabilities		25,603,414
- WITH EDWG 11972	\$	405,095,761
Common capital stock	\$	7,500,000
Gross paid in and contributed surplus		293,480,097
Unassigned funds (surplus)		112,968,317
Surplus as regards policyholders	\$	413,948,652
	S	819.044.413
<u> </u>		· · · · · · · · · · · · · · · · · · ·
STATE OF NEW YORK )		
) ss:		
COUNTY OF NEW YORK )		
I, the undersigned Senior Vice President and Chief Financial Officer of Hudson In	surance Company	hereby certify the

I, the undersigned Senior Vice President and Chief Financial Officer of Hudson Insurance Company hereby certify the foregoing to be a short form financial statement in the form of a balance sheet, showing the Company's assets and liabilities on a provisional basis, at the close of business on December 31, 2013.

IN TESTIMON TO MCKING THE REOF, I have set my hand and affixed the seal of the Company, this 12 day of March, 2014.

John Verbich
Senior Vice President and Chief Financial Officer

Subscribed the service me this 12 day of 12 day of 14 2011 of My commission experience.



PERFORMANCE BOND #1 (Page 1)

### PERFORMANCE BOND #1

KNOW ALL PERSONS BY THESE PRESENTS:,
That we,
hereinafter referred to as the "Principal,"
and,
hereinafter referred to as the "Surety" ("Sureties") are held and firmly bound to THE CITY OF NEW
YORK, hereinafter referred to as the "City" or to its successors and assigns in the penal sum
of
01
(\$) Dollars, lawful money of the United States for the payment of which
said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors,
administrators, successors and assigns, jointly and severally, firmly by these presents.
administrators, successors and assigns, jointry and severally, rinning by allose presents.
WHEREAS, the Principal is about to enter, or has entered, into a Contract in writing with the City for
WITEREAS, the 1 interparts about to enter, or has entered, into a contract in writing with the city for
a copy of which Contract is annexed to and hereby made a part of this bond as though herein set forth in
full;
·
NOW, THEREFORE, the conditions of this obligation are such that if the Principal, his or its
representatives or assigns, shall well and faithfully perform the said Contract and all modifications,
amendments, additions and alterations thereto that may hereafter be made, according to its terms and its
true intent and meaning, including repair and or replacement of defective work and guarantees of
maintenance for the periods stated in the Contract, and shall fully indemnify and save harmless the City
from all cost and damage which it may suffer by reason of the Principal's default of the Contract, and shall
fully reimburse and repay the City for all outlay and expense which the City may incur in making

PERFORMANCE BOND #1 (Page 2)

good any such default and shall protect the said City of New York against, and pay any and all amounts, damages, cost and judgments which may or shall be recovered against said City or its officers or agents or which the said City of New York may be called upon to pay any person or corporation by reason of any damages arising or growing out of the Principal's default of the Contract, then this obligation shall be null and void, otherwise to remain in full force and effect.

The Surety (Sureties), for value received, hereby stipulates and agrees, upon written notice from the City that the City has determined that the Principal is in default of the Contract, to (1) pay the City the cost to complete the contract as determined by the City in excess of the balance of the Contract held by the City, plus any damages or costs to which the City is entitled, up to the full amount of the above penal sum, (2) fully perform and complete the Work to be performed under the Contract, pursuant to the terms, conditions, and covenants thereof, or (3) tender a completion Contractor that is acceptable to the City. The Surety (Sureties) further agrees, at its option, either to notify the City that it elects to pay the city the cost of completion plus any applicable damages and costs under option (1) above, or to commence and diligently perform the Work specified in the Contract, including physical site work, within twenty-five (25) business days after written notice thereof from the City and, if the Surety elects to fully perform and complete the Work, then to complete all Work within the time set forth in the Contract or such other time as agreed to between the City and Surety in accordance with the Contract. If the Surety elects to tender payment pursuant to (1) above, then the Surety shall tender such amount within fifteen (15) business days notification from the City of the cost of completion. The Surety and the City reserve all rights and defenses each may have against the other; provided, however, that the Surety expressly agrees that its reservation of rights shall not provide a basis for non-performance of its obligation to pay the City the cost of completion, to commence and complete all Work as provided herein, or to tender a completion contractor.

The Surety (Sureties), for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of said Surety (Sureties) and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition, or change in or to the said Contract or the Work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or any moneys due or to become due thereunder; and said Surety (Sureties) does hereby waive notice of any and all of such extensions, modifications, omissions, additions, changes, payments, and waivers, and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to subcontractors shall have the same effect as to said Surety (Sureties) as though done or omitted to be done by or in relation to said Principal. Notwithstanding the above, if the City makes payments to the Principal before the time required by the contract that in the aggregate exceed \$100,000 or 10% of the Contract price, whichever is less, and that have not become earned prior to the Principal being found to be in default, then all payments made to the Principal before the time required by the Contract shall be added to the remaining contract value available to be paid for the completion of the Contract as if such sums had not been paid to the Principal, but shall not provide a basis for non-performance of its obligation to pay the City the cost of completion, to commence and to complete all Work as provided herein, or to tender a completion contractor.

PERFORMANCE BOND #1 (Page 3)

IN WITNESS WHEREOF, The Principal and the Surety (Sureties) have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereunto affixed and these presents to be signed by their proper officers, this

day of		, 20	
(Seal)			
			(L.S.)
		Principal	· ·
	Ву:		<u>.                                    </u>
(Seal)		Surety	
	Ву:		<u>.</u>
(Seal)		Surety	•
	Ву:	· · · · · · · · · · · · · · · · · · ·	<u> </u>
(Seal)	-	Surety	<u> </u>
	Ву:		
(Seal)		Surety	•
	Ву:		
(Seal)	*****	Surety	•
	Ву:		•
Bond Premium Rate		<del>.</del>	
Bond Premium Cost			

If the Contractor (Principal) is a partnership, the bond should be signed by each of the individuals who are partners.

If the Contractor (Principal) is a corporation, the bond should be signed in its correct corporate name by a duly authorized officer, agent, or attorney-in-fact.

There should be executed an appropriate number of counterparts of the bond corresponding to the number of counterparts of the Contract.

CITY OF NEW YORK DDC

PERFORMANCE BOND #1 (Page 4)

### ACKNOWLEDGMENT OF PRINCIPAL IF A CORPORATION

State of	Count	y of	ss:
On this	day of	, 20	before me personally
came	,		
	being by me duly sworn did dep	oose and say that he/she resid	es
at		, that halaha is the	
of the corporation d	escribed in and which executed	the foregoing instrument: or	nd that he/she signed his/her name to
the foregoing instru	ment by order of the directors o	f said corporation as the duly	authorized and binding act thereof.
Notary Public or Co	ommissioner of Deeds.		
round rubbe of Co		OF PRINCIPAL IF A PAF	PTNFPSHIP
State of	Count		
		y or	
		, 20	before me personally
came			
at	being by me duly sworn did dis	•	
at		that he/she is	partner of
	, a limited/general part	nership existing under the la	ws of the State of
	the partnership describe	ed in and which executed the	foregoing instrument
and that he/she sign	ed his/her name to the foregoing	instrument as the duly author	roregoing histament,
said partnership.	od morner name to the reregoniz	mstument as the duty addit	orized and omding act of
sare paraneromp.			•
			•
Notary Public or Co	ommissioner of Deeds.		•
		OF PRINCIPAL IF AN IN	
State of	Count	y of	ss:
			before me personally
to me known, who	being by me duly sworn did dep	oose and say that he/she resid	es
at		and say mad no she rest	· ·
		, and that he/she is the in	ndividual whose name is
subscribed to the wi	thin instrument and acknowledg	ged to me that by his/her sign	ature on the
instrument, said ind	ividual executed the instrument		
Notary Public or Co	mmissioner of Deeds		
Each executed bond	should be accompanied by: (a) a	ppropriate acknowledgments	of the respective parties; (b) appropria
duly certified copy o	of Power of Attorney or other cer	tificate of authority where both	nd is executed by agent, officer or other
representative of Prin	ncipal or Surety; (c) a duly certif	ied extract from By-Laws or r	esolutions of Surety under which Power
of Attorney or other	certificate of authority of its age	nt, officer or representative wa	as issued, and (d) certified copy of late
published financial st	tatement of assets and liabilities of	f Surety.	<del></del>

Affix Acknowledgments and Justification of Sureties.

CITY OF NEW YORK DDC

PERFORMANCE BOND #2 (Page 1)

#### PERFORMANCE BOND #2

KNOW ALL PERSONS BY THESE PRESENTS:,

	· · · · · · · · · · · · · · · · · · ·
hereinafter referred to as the "Principal," and,	
hereinafter referred to as the "Surety" ("Sureties" YORK, hereinafter referred to as the "City" or to its of	
(\$	wful money of the United States for the payment of made, we, and each of us, bind ourselves, our heirs, bintly and severally, firmly by these presents.
WHEREAS, the Principal is about to enter, or has e	entered, into a Contract in writing with the City for
a copy of which Contract is annexed to and hereby full;	made a part of this bond as though herein set forth in
representatives or assigns, shall well and faithfu amendments, additions and alterations thereto that true intent and meaning, including repair and of	this obligation are such that if the Principal, his or its illy perform the said Contract and all modifications, may hereafter be made, according to its terms and its or replacement of defective work and guarantees of , and shall fully indemnify and save harmless the City

from all cost and damage which it may suffer by reason of the Principal's default of the Contract, and shall fully reimburse and repay the City for all outlay and expense which the City may incur in making

PERFORMANCE BOND #2 (Page 2)

good any such default and shall protect the said City of New York against, and pay any and all amounts, damages, cost and judgments which may or shall be recovered against said City or its officers or agents or which the said City of New York may be called upon to pay any person or corporation by reason of any damages arising or growing out of the Principal's default of the Contract, then this obligation shall be null and void, otherwise to remain in full force and effect.

The Surety (Sureties), for value received, hereby stipulates and agrees, upon written notice from the City that the City has determined that the Principal is in default of the Contract, to either (1) pay the full amount of the above penal sum in complete discharge and exoneration of this bond and of all the liabilities of the Surety relating to this bond, or (2) fully perform and complete the Work to be performed under the Contract, pursuant to the terms, conditions, and covenants thereof. The Surety (Sureties) further agrees, at its option, either to tender the penal sum or to commence and diligently perform the Work specified in the Contract, including physical site work, within twenty-five (25) business days after written notice thereof from the City and to complete all Work within the time set forth in the Contract or such other time as agreed to between the City and Surety in accordance with the Contract. The Surety and the City reserve all rights and defenses each may have against the other; provided, however, that the Surety expressly agrees that its reservation of rights shall not provide a basis for non-performance of its obligation to commence and to complete all Work as provided herein.

The Surety (Sureties), for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of said Surety (Sureties) and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition, or change in or to the said Contract or the Work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any Work to be performed or any moneys due or to become due thereunder; and said Surety (Sureties) does hereby waive notice of any and all of such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers, and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to said Surety (Sureties) as though done or omitted to be done by or in relation to said Principal.

PERFORMANCE BOND #2 (Page 3)

IN WITNESS WHEREOF, The Principal and the Surety (Sureties) have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereunto affixed and these presents to be signed by their proper officers, this

	day of		20	
(Seal)				
			Principal	(L.S.)
(Seal)		Ву:		
(Seal)			Surety	
		Ву:	<del></del>	
(Seal)			Surety	<del></del>
		Ву:		·
(Seal)	•		Surety	· · · · · · · · · · · · · · · · · · ·
		Ву:		<del></del>
(Seal)			Surety	
		Ву:	·	•
(Seal)			Surety	
		Ву:		
Bond Premium Rate	* 11.1 MATERIA			
Bond Premium Cost				

If the Contractor (Principal) is a partnership, the bond should be signed by each of the individuals who are partners.

If the Contractor (Principal) is a corporation, the bond should be signed in its correct corporate name by a duly authorized officer, agent, or attorney-in-fact.

There should be executed an appropriate number of counterparts of the bond corresponding to the number of counterparts of the Contract.

PERFORMANCE BOND #2 (Page 4)

### ACKNOWLEDGMENT OF PRINCIPAL IF A CORPORATION

State of		County of		ss:
On this	day of	er e	, 20	before me personally
came				
	o, being by me duly sw	orn did depose and	say that he reside	S .
at		_		•
		; that	he/she is the	
				nt; that he/she signed his/her name to the authorized and binding act thereof.
Notary Public or	Commissioner of Deed	ds.		
	ACKNOWLEI	OGMENT OF PRI	NCIPAL IF A	<u>PARTNERSHIP</u>
State of		County of		ss:
				before me personally
to me known, who	o, being by me duly sv	vorn did depose and	say that he/she re	esides
		; that l	he/she is	partner of
	, a li	imited/general partne	ership existing u	partner of der the laws of the State of
	, the par	mership described in	and which exec	uted the foregoing instrument;
and that he/she sig	gned his/her name to the	he foregoing instrum	ent as the duly a	uthorized and binding act of
said partnership.	B		as eno car, a	amorabod and omeans not of .
ome paratoromp.				
Notary Public or	Commissioner of Deed	is		
	ACKNOWLE	DGMENT OF PR	INCIPAL IF A	N INDIVIDUAL
State of		County of		ss:
On this	day of	·-············· - ······	, 20	before me personally
to me known, who	o, being by me duly sv	vorn did depose and	say that he/she re	esides
at				
				individual whose name is
	within instrument and ndividual executed the		e that by his/her s	signature on the
Notary Public or 6	Commissioner of Deed			
round rubic or	Commissioner of Deec	15		
duly certified copy representative of F of Attorney or oth	y of Power of Attorney Principal or Surety; (c)	or other certificate of a duly certified extra ty of its agent, office I liabilities of Surety.	of authority where ct from By-Laws or or representative	nts of the respective parties; (b) appropriate bond is executed by agent, officer or other or resolutions of Surety under which Power was issued, and (d) certified copy of lates
		* * * *	* * * *	

Affix Acknowledgments and Justification of Sureties.

CITY OF NEW YORK DDC

PAYMENT BOND (Page 1)

#### PAYMENT BOND

	KNOW ALL PERSONS BY THESE PRESENTS, That we,
herei	nafter referred to as the "Principal", and
herei	nafter referred to as the "City" or to its successors and assigns, in the penal sum of
and t	Dollars, lawful money of the United States, for the payment of which said sum of money we ruly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors an ns, jointly and severally, firmly by these presents.  WHEREAS, the Principal is about to enter, or has entered, into a Contract in writing with the City for
а сор	y of which Contract is annexed to and hereby made a part of this bond as though herein set forth in full;
repre	NOW, THEREFORE, the conditions of this obligation are such that if the Principal, his or it sentatives or assigns and other Subcontractors to whom Work under this Contract is sublet and his or the essors and assigns shall promptly pay or cause to be paid all lawful claims for

(a) Wages and compensation for labor performed and services rendered by all persons engaged in the prosecution of the Work under said Contract, and any amendment or extension thereof or addition thereto, whether such persons be agents servants or employees of the Principal or any such Subcontractor, including all persons so engaged who perform the work of laborers or mechanics at or in the vicinity of the site

PAYMENT BOND (Page 2)

of the Project regardless of any contractual relationship between the Principal or such Subcontractors, or his or their successors or assigns, on the one hand and such laborers or mechanics on the other, but not including office employees not regularly stationed at the site of the project; and

(b) Materials and supplies (whether incorporated in the permanent structure or not), as well as teams, fuels, oils, implements or machinery furnished, used or consumed by said Principal or any subcontractor at or in the vicinity of the site of the Project in the prosecution of the Work under said Contract and any amendment or extension thereof or addition thereto; then this obligation shall be void, otherwise to remain in full force and effect.

This bond is subject to the following additional conditions, limitations and agreements:

- (a) The Principal and Surety (Sureties) agree that this bond shall be for the benefit of any materialmen or laborer having a just claim, as well as the City itself.
- (b) All persons who have performed labor, rendered services or furnished materials and supplies, as aforesaid, shall have a direct right of action against the Principal and his, its or their successors and assigns, and the Surety (Sureties) herein, or against either or both or any of them and their successors and assigns. Such persons may sue in their own name, and may prosecute the suit to judgment and execution without the necessity of joining with any other persons as party plaintiff.
- (c) The Principal and Surety (Sureties) agree that neither of them will hold the City liable for any judgment for costs of otherwise, obtained by either or both of them against a laborer or materialman in a suit brought by either a laborer or materialman under this bond for moneys allegedly due for performing work or furnishing material.
- (d) The Surety (Sureties) or its successors and assigns shall not be liable for any compensation recoverable by an employee or laborer under the Workmen's Compensation Law.
- (e) In no event shall the Surety (Sureties), or its successors or assigns, be liable for a greater sum than the penalty of this bond or be subject to any suit, action or proceeding hereon that is instituted by any person, firm, or corporation hereunder later than two years after the complete performance of said Contract and final settlement thereof.

The Principal, for himself and his successors and assigns, and the Surety (Sureties), for itself and its successors and assigns, do hereby expressly waive any objection that might be interposed as to the right of the City to require a bond containing the foregoing provisions, and they do hereby further expressly waive any defense which they or either of them might interpose to an action brought hereon by any person, firm or corporation, including subcontractors, materialmen and third persons, for work, labor, services, supplies or material performed rendered, or furnished as aforesaid upon the ground that there is no law authorizing the City to require the foregoing provisions to be place in this bond.

And the Surety (Sureties), for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of said Surety (Sureties), and its bonds shall be in no way impaired or affected by any extension of time, modification, omission, addition, or change in or of the said Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any part thereof, or of any Work to be performed, or any moneys due to become due thereunder and said Surety (Sureties) does hereby waive notice of any and all of such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers, and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, Subcontractors, and other transferees shall have the same effect as to said Surety (Sureties) as though done or omitted to be done or in relation to said Principal.

CITY OF NEW YORK

PAYMENT BOND (Page 3)

IN WITNESS WHEREOF, the Princip and seals, and such of them as are corporations these presents to be signed by their proper office	have caused the	ir corporate seals to	be hereunto affixed and
(Seal)			_(L.S.)
		Principal	_(2.5.)
	Ву:		
(Seel)			
(Seal)	-	Surety	· ·
	Ву:		****
(Seal)			
(Scar)		Surety	<del></del>
	Ву:	<u>.</u>	<u>.</u>
(Seal)			
(Scal)		Surety	· .
	Ву:		<del></del>
(Seal)			
(Scal)		Surety	<del></del>
	By:		

If the Contractor (Principal) is a partnership, the bond should be signed by each of the individuals who are partners.

If the Contractor (Principal) is a corporation, the bond should be signed in its correct corporate name by a duly authorized officer, agent, or attorney-in-fact.

There should be executed an appropriate number of counterparts of the bond corresponding to the number of counterparts of the Contract.

PAYMENT BOND (Page 4)

ACKNOWLEDGME	NT OF PRINCIPAL, IF A	CORPORATION	
State of	County of	ss:	
On this day of _ to me known, who, bei	ng by me duly sworn did dep	me personally came	es at
corporation; that one of	bed in and which executed the first the seals affixed to said in reportation, and that he signed	strument is such seal; tha	that he knows the seal of said tit was so affixed by order of order.
	Notary Pul	blic or Commissioner of I	Deeds
ACKNOWLEDGME	NT OF PRINCIPAL, IF A	PARTNERSHIP	
State of	County of	ss:	
On this day of	,, before	me personally appeared	
to me known, and know	wn to me to be one of the me	mbers of the firm of	
	described in and	who executed the fore	egoing instrument; and he
		blic or Commissioner of I	Deeds
	NT OF PRINCIPAL, IF A		
State of	County of	ss:	
On this day of	,, before	me personally appeared	
to me known, and kno and acknowledged that	wn to me to be the person d	escribed in and who exec	uted the foregoing instrument;
	Notary Pul	blic or Commissioner of I	Deeds
parties; (b) appropriate is executed by agent, o By-Laws or resolution	duly certified copy of Powe officer or other representative is of Surety under which Po- centative was issued, and (d)	or of Attorney or other cert e of Principal or Surety; ( ower of Attorney or othe	nowledgments of the respective difficate of authority where bond c) a duly certified extract from r certificate of authority of its ublished financial statement of

CITY OF NEW YORK DDC

Affix Acknowledgments and Justification of Sureties.

(NO TEXT ON THIS PAGE)

#### SCHEDULE OF WORKMEN, MECHANICS AND LABORERS

The following is a list of classifications for workmen, mechanics and laborers which are anticipated to be employed in the performance of work under this contract, followed by a schedule of the prevailing wage rates and supplemental benefits for all classifications as established by the Comptroller of the City of New York.

Request for interpretation or correction under Subsection A of Section No. 3 in the Information for Bidders includes all requests for clarification of the classification of trades to be employed in the performance of the work under this contract.

In the event that a trade not listed in the classification of trades required to be used at the time of the award of the contract is in fact employed during the performance of this contract, the Contractor shall be required to obtain from the agency the prevailing wage rates and supplementary benefits for the trades used and to complete the performance of this contract at the price at which the contract was awarded.

CODE	CLASSIFICATION
15 42 001 15 42 002	Rigger Sign Erector
16 11 001 16 11 002 16 11 003	Gardener Tree Pruner Tree Remover
16 11 011 16 11 012 16 11 013 16 11 014 16 11 015 16 11 016 16 11 017	Asphalt Raker (Highway & Paving) Tamper (Highway & Paving) Curbsetter (Highway & Paving) Formsetter (Highway & Paving) Rammerman (Highway & Paving) Laborer (Highway & Paving) ALL OTHER TITLES (Highway & Paving)
16 23 001 16 23 002 16 23 003 16 23 004 16 23 005 16 23 006 16 23 007	Laborer Operating Engineer (Heavy Construction-Maintenance) Junior Operating Engineer Junior Operating Engineer Junior Operating Engineer Fireman (Heavy Construction) Oiler (Heavy Construction)
16 23 051 16 23 052 16 23 053 16 23 057 16 23 058 16 23 059	Surveyor-Heavy Construction Surveyor-Heavy Construction-Instrument Man Surveyor-Heavy Construction-Rodman Surveyor-Land Surveying-Party Chief Surveyor-Land Surveying-Instrument Man Surveyor-Land Surveying-Rodman

COL	<u>DE</u>	CLASSIFICATION
16 16 16	23 062	Operating Engineer-Road & Heavy Construction Operating Engineer-Paving Operating Engineer-Concrete
16 16 16 16	23 073	Teamster-Heavy Equipment Trailer Driver Teamster-Dump Truck Driver Teamster-Flat Bed Trailer Driver (3-Axle) Teamster-Redi-Mix (Sand and Gravel)
16	29 011	Drill Runners
17	11 001	Plumbers
17	21 001	Painter (Brush & Roller)
17	31 001	Electrician
17 17 17	41 001 41 002 41 004	Bricklayer Mason Tender Cement Mason
17	42 002	Metallic Lather
17 17	51 001 51 002	Carpenter Dock Builder
17	71 001	Cement & Concrete Worker
17	91 001	Structural Iron Worker
17	95 001	Barman
17	96 021	Derrickmen & Riggers
17 17 17	99 001 99 002 99 005	Ornamental Iron Worker Sandblaster Pointers (Waterproofer)
17	99 011	Welders

Each classification may include trainees depending upon project staffing schedules and as required by the terms of this contract.

#### LABOR LAW §220 PREVAILING WAGE SCHEDULE

Workers, Laborers and Mechanics employed on a public work project must receive not less than the prevailing rate of wage and benefits for the classification of work performed by each upon such public work. Pursuant to Labor Law §220 the Comptroller of the City of New York has promulgated this schedule solely for Workers, Laborers and Mechanics engaged by private contractors on New York City public work contracts.

Contracting agencies anticipating doing work which requires the employment of a trade or classification not included in this schedule must request the Comptroller to establish a proper classification for the work pursuant to Labor Law §220 (3-a) (a). The prevailing rate schedule as promulgated by the Comptroller, must, in compliance with law, be annexed to and form part of the contract.

Contractors are solely responsible for maintaining original payroll records which delineate, among other things, the hours each employee worked within a given classification. Contractors using rates and/or classifications not promulgated by the Comptroller do so at their own risk. Additionally, prior to bid, Agency Chief Contracting Officers must contact the Bureau of Labor Law when the need arises for a work classification not published in this schedule.

The appropriate schedule of prevailing wages and benefits must be posted at all public work sites pursuant to Labor Law §220 (3-a) (a).

This schedule is applicable for work performed during the effective period, unless otherwise noted. You will be notified of any changes to this schedule by addenda published on our web site at www.comptroller.nyc.gov. The rate of wages and supplemental benefits to be paid or provided are those that prevail at the time the work is being performed. Preliminary schedules for future one-year periods are published annually in the City Record on or about June 1<sup>st</sup> of each succeeding year. Final schedules are published on or about July 1<sup>st</sup> in the City Record and on our web site at www.comptroller.nyc.gov.

The Comptroller's Office has attempted to include all overtime, shift and night differential, Holiday, Saturday, Sunday or other premium time work. However, this schedule does not set forth every prevailing practice with respect to such rates with which employers must comply. All such practices are nevertheless part of the employer's prevailing wage obligation and contained in the collective bargaining agreements of the prevailing wage unions. These collective bargaining agreements are available for inspection by appointment. Requests for appointments may be made by calling (212) 669-4443, Monday through Friday between the hours of 9 a.m. and 5 p.m.

Answers to questions concerning prevailing trade practices may be obtained from the Classification Unit by calling (212) 669-7974. Please direct all other compliance issues to: Bureau of Labor Law, Attn: Wasyl Kinach, P.E., Office of the Comptroller, 1 Centre Street, Room 1122, New York, N.Y. 10007; Fax (212) 669-4002.

Prevailing rates and ratios for apprentices are attached to this schedule in the Appendix. Pursuant to Labor Law §220 (3-e), only apprentices who are individually registered in a bona fide program to which the employer contractor is a participant, registered with the New York State Department of Labor, may be employed on a public work project. Workers who are not journey persons or not registered apprentices pursuant to Labor Law §220 (3-e) may not be substituted for apprentices and must be paid as journey persons.

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 1 of 86 PUBLISH DATE: 1/20/2014

The second secon

Contractors are advised to review the applicable Collective Bargaining Agreements and the Comptroller's Prevailing Wage Schedule before bidding on Public Work. If there are any questions concerning prevailing wages, benefits, overtime, Holiday pay, shift differentials or any prevailing practice, please contact this office.

Public Work construction, reconstruction, demolition, excavation, rehabilitation, repair, renovation, alteration, or improvement contracts awarded pursuant to a Project Labor Agreement ("PLA") in accordance with Labor Law section 222 may have different labor standards for shift, premium and overtime work. Please refer to the PLA's pre-negotiated labor agreements for wage and benefit rates applicable to work performed outside of the regular workday. More information is available at the Mayor's Office of Contract Services (MOCS) web page at http://www.nyc.gov/html/mocs/html/vendors/pla.shtml.

All the provisions of Labor Law section 220 remain applicable to PLA work including, but not limited to, the enforcement of prevailing wage requirements by the Comptroller; however, we will enforce shift, premium, overtime and other non-standard rates as they appear in a project's prenegotiated labor agreement.

Any error as to compensation under the prevailing wage law or other information as to trade classification, made by the contracting agency in the contract documents or in any other communication, will <u>not</u> preclude a finding against the contractor of prevailing wage violation.

In order to meet their obligation to provide prevailing supplemental benefits to each covered employee, employers must either:

- 1) Provide bona-fide benefits which cost the employer no less than the prevailing supplemental benefits rate; or
- 2) Supplement the employee's hourly wage by an amount no less than the prevailing supplemental benefits rate; or
- 3) Provide a combination of bona-fide benefits and wage supplements which cost the employer no less than the prevailing supplemental benefits rate in total.

Particular attention should be given to the supplemental benefits requirement. Although in most instances the payment or provision for supplemental benefits is for each hour worked, some classifications require the payment or provision of supplemental benefits for each hour paid. Consequently, some prevailing practices require benefits to be purchased at the overtime, shift differential, Holiday, Saturday, Sunday or other premium time rate.

### Benefits are paid for **EACH HOUR WORKED** unless otherwise noted.

Wasyl Kinach, P.E.
Director of Classifications
Bureau of Labor Law

### 220 SCHEDULE OF PREVAILING WAGES AND SUPPLEMENTAL BENEFITS ADDENDUM EFFECTIVE PERIOD JANUARY 20, 2014 THROUGH JUNE 30, 2014

#### **List of Amended Classifications**

- 1. ASBESTOS HANDLER
- 2. BRICKLAYER
- 3. CARPENTER BUILDING COMMERCIAL
- 4. CEMENT & CONCRETE WORKER
- 5. CORE DRILLER
- 6. ELECTRICIAN
- 7. FLOOR COVERER
- 8. HEAT AND FROST INSULATOR
- 9. HOUSE WRECKER
- 10. IRON WORKER ORNAMENTAL
- 11. IRON WORKER STRUCTURAL
- 12. MARBLE MECHANIC
- 13. MASON TENDER
- 14. MASON TENDER (INTERIOR DEMOLITION WORKER)
- 15. MOSAIC MECHANIC
- **16. PAINTER STRUCTURAL STEEL**
- 17. PLASTERER
- **18. PLASTERER TENDER**
- 19. PLUMBER
- 20. PLUMBER (MECHNICAL EQUIPMENT AND SERVICE)
- 21. PLUMBER (RESIDENTIAL RATES FOR 1, 2 AND 3 FAMILY HOME CONSTRUCTION)
- 22. PLUMBER: PUMP & TANK
- 23. ROOFER
- 24. STEAMFITTER
- 25. STEAMFITTER REFRIGERATION AND AIR CONDITIONER
- **26. STONE MASON SETTER**
- **27. TILE FINISHER**
- 28. TILE LAYER SETTER

A STATE OF THE STA

## **TABLE OF CONTENTS**

CLASSIFICATION	PAGE
CLASSIFICATION ASBESTOS HANDLER	6
BLASTER	6
BOILERMAKER	8
BRICKLAYER	
CARPENTER - BUILDING COMMERCIAL	10
CARPENTER - HEAVY CONSTRUCTION WORK	11
CEMENT & CONCRETE WORKER	12
CEMENT MASON	
CORE DRILLER	
DERRICKPERSON AND RIGGER	15
DIVER	
DOCKBUILDER - PILE DRIVER	
DRIVER: TRUCK (TEAMSTER)	
ELECTRICIAN	20
ELECTRICIAN - ALARM TECHNICIAN	24
ELECTRICIAN-STREET LIGHTING WORKER	25
ELEVATOR CONSTRUCTOR	
ELEVATOR REPAIR & MAINTENANCE	27
ENGINEER	27
ENGINEER - CITY SURVEYOR AND CONSULTANT	32
ENGINEER - FIELD (BUILDING CONSTRUCTION)	
ENGINEER - FIELD (HEAVY CONSTRUCTION)	
ENGINEER - FIELD (STEEL ERECTION)	
ENGINEER - OPERATING	
FLOOR COVERER	
GLAZIER	
GLAZIER - REPAIR & MAINTENANCE	
HEAT AND FROST INSULATOR	
HOUSE WRECKER	
IRON WORKER - ORNAMENTAL	
IRON WORKER - STRUCTURAL	
LABORER	
LANDSCAPING	
MARBLE MECHANIC	
MASON TENDER	
MASON TENDER (INTERIOR DEMOLITION WORKER)	
METALLIC LATHER	
MILLWRIGHT	
MOSAIC MECHANIC	58
PAINTER	59
PAINTER - SIGN	
PAINTER - STRIPER	64

PAINTER - STRUCTURAL STEEL	62
PAPERHANGER	63
PAVER AND ROADBUILDER	63
PLASTERER	65
PLASTERER - TENDER	66
PLUMBER	67
PLUMBER (MECHNICAL EQUIPMENT AND SERVICE)	
PLUMBER (RESIDENTIAL RATES FOR 1, 2 AND 3 FAMILY HOME CONSTRUCTION)	68
PLUMBER: PUMP & TANK	
POINTER - WATERPROOFER, CAULKER MECHANIC (EXTERIOR BUILDING RENOVATION)	70
ROOFER	
SANDBLASTER - STEAMBLASTER	
SHEET METAL WORKER	
SHEET METAL WORKER - SPECIALTY	
SIGN ERECTOR	
STEAMFITTER	
STEAMFITTER - REFRIGERATION AND AIR CONDITIONER	
STONE MASON - SETTER	
TAPER	
TELECOMMUNICATION WORKER	
TILE FINISHER	
TILE LAYER - SETTER	
TIMBERPERSON	
TUNNEL WORKER	
WELDER	86

### **ASBESTOS HANDLER**

(Hazardous Material; Disturbs, removes, encapsulates, repairs, or encloses friable asbestos material)

### **Asbestos Handler**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$35.90

Supplemental Benefit Rate per Hour: \$15.05

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$36.00

Supplemental Benefit Rate per Hour: \$15.45

#### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Sunday.

Time and one half the regular hourly rate after 40 hours in any work week.

#### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s).

New Year's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day
Easter

### Paid Holidays

None

(Local #78 and Local #12A)

#### BLASTER

### <u>Blaster</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$44.40

Supplemental Benefit Rate per Hour: \$38.44

### **Blaster (Hydraulic)**

19月春日 《《《美历·传》 海绵 性體的

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$45.17

Supplemental Benefit Rate per Hour: \$38.44

### **Blaster - Trac Drill Hydraulic**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$40.04

Supplemental Benefit Rate per Hour: \$38.44

### Blaster - Wagon: Air Trac: Quarry Bar: Drillrunners

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$39.30

Supplemental Benefit Rate per Hour: \$38.44

### Blaster - Operators of Jack Hammers

Chippers: Spaders: Concrete Breakers: and all other pneumatic tools of like usage: Walk Behind Self Propelled

Hydraulic Asphalt and Concrete Breakers: Hydro (Water) Demolition

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$38.32

Supplemental Benefit Rate per Hour: \$38.44

### **Blaster - Powder Carriers**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$34.66

Supplemental Benefit Rate per Hour: \$38.44

### Blaster - Hydraulic Trac Drill Chuck Tender

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$33.46

Supplemental Benefit Rate per Hour: \$38.44

### Blaster - Chuck Tender & Nipper

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$32.75

Supplemental Benefit Rate per Hour: \$38.44

### Blaster - Magazine Keepers: (Watch Person)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$19.76

ADDENDUM 1

Supplemental Benefit Rate per Hour: \$38.44

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 7 of 86

**PUBLISH DATE: 1/20/2014** 

The second secon

### **Overtime Description**

Magazine Keepers:

Time and one half for work performed in excess of forty (40) hours per week and for work performed on Saturdays, Sundays and Holidays.

All Other Employees:

Time and one-half for the first eight hours of work on Saturday and for Make-up Time. Double time for all hours over eight Monday through Friday (except make-up hours) and for all hours worked on Sunday and Holidays.

#### **Overtime**

Double time the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).

New Year's Day

Memorial Day
Independence Day
Labor Day
Columbus Day
Presidential Election Day
Thanksgiving Day
Christmas Day

### **Paid Holidays**

None

#### Shift Rates

A single shift shall be 8 hours plus an unpaid lunch, starting at 8:00 A.M (or between 6:00 A.M. and 10:00 A.M. on weekdays). When two (2) shifts are employed, each shift shall be 8 hours plus  $\frac{1}{2}$  hour unpaid lunch. When three (3) shifts are employed, each shift will work seven and one-half (7  $\frac{1}{2}$ ) hours, but will be paid for eight (8) hours, since only one-half ( $\frac{1}{2}$ ) hour is allowed for mealtime. When two (2) or more shifts are employed, single time will be paid for each shift. The first 8 hours of any and all work performed Monday through Friday inclusive of any off-shift shall be at the single time rate.

(Local #29)

#### **BOILERMAKER**

### <u>Boilermaker</u>

Effective Period: 7/1/2013 - 12/31/2013

Wage Rate per Hour: \$49.47

Supplemental Benefit Rate per Hour: \$39.78

Supplemental Note: For time and one half overtime - \$59.08; For double overtime - \$78.37.

Effective Period: 1/1/2014 - 6/30/2014

Wage Rate per Hour: \$50.45

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 8 of 86 PUBLISH DATE: 1/20/2014

The second secon

Supplemental Benefit Rate per Hour: \$41.31

Supplemental Note: For time and one half overtime - \$61.37; For double overtime - \$81.43.

### **Overtime Description**

For Repair and Maintenance work:

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

For New Construction work:

Double time the regular rate after an 8 hour day.

Double time the regular time rate for Saturday.

Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).

**New Year's Day** 

President's Day

Memorial Day

Independence Day

Columbus Day

**Election Day** 

**Veteran's Day** 

Thanksgiving Day

**Christmas Day** 

Quadruple time the regular rate for work on the following holiday(s). Labor Day

### **Paid Holidays**

Good Friday
Day after Thanksgiving
Day before Christmas
Day before New Year's Day

#### **Shift Rates**

When shifts are required, the first shift shall work eight (8) hours at the regular straight-time hourly rate. The second shift shall work seven and one-half (7 ½) hours and receive eight hours at the regular straight time hourly rate plus twenty-five cents (\$0.25) per hour. The third shift shall work seven (7) hours and receive eight hours at the regular straight time hourly rate plus fifty cents (\$0.50) per hour. A thirty (30) minute lunch period shall not be considered as time worked. Work in excess of the above shall be paid overtime at the appropriate new construction work or repair work overtime wage and supplemental benefit hourly rate.

(Local #5)

#### **BRICKLAYER**

## **Bricklayer**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$46.44

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

Page 9 of 86

**PUBLISH DATE: 1/20/2014** 

Commence of the second of the

Supplemental Benefit Rate per Hour: \$27.53

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$47.78

Supplemental Benefit Rate per Hour: \$28.03

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

Memorial Day

Independence Day

Labor Day

Thanksgiving Day

Christmas Day

#### **Paid Holidays**

None

### **Shift Rates**

Overtime rates to be paid outside the regular scheduled work day.

(Bricklayer District Council)

### **CARPENTER - BUILDING COMMERCIAL**

# **Building Commercial**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$48.08

Supplemental Benefit Rate per Hour: \$41.10

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$48.88

Supplemental Benefit Rate per Hour: \$42.70

#### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Control of the Contro

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).
New Year's Day
Washington's Birthday
Memorial Day
Independence Day
Labor Day
Columbus Day
Presidential Election Day
Thanksgiving Day

### **Paid Holidays**

Day after Thanksgiving

None

#### **Shift Rates**

**Christmas Day** 

The second shift will receive one hour at the double time rate of pay for the last hour of the shift; eight hours pay for seven hours of work, nine hours pay for eight hours of work. There must be a first shift in order to work a second shift.

(Carpenters District Council)

# CARPENTER - HEAVY CONSTRUCTION WORK (Construction of Engineering Structures and Building Foundations)

# **Heavy Construction Work**

Effective Period: 7/1/2013 - 7/17/2013

Wage Rate per Hour: \$46.74

Supplemental Benefit Rate per Hour: \$42.37

Effective Period: 7/18/2013 - 6/30/2014

Wage Rate per Hour: \$46.82

Supplemental Benefit Rate per Hour: \$44.97

#### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### **Overtime Holidays**

SADO A PARA PROPERTY SALES

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day

ADDENDUM 1 EFFECTIVE P

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 PUBLISH DATE: 1/20/2014

The state of the s

Page 11 of 86

Memorial Day Independence Day Labor Day Columbus Day Presidential Election Day Thanksgiving Day Christmas Day

### **Paid Holidays**

None

#### Shift Rates

Off shift work commencing between 5:00 P.M. and 11:00 P.M. shall work eight and one half hours allowing for one half hour for lunch. The wage rate shall be 113% of the straight time hourly wage rate.

(Carpenters District Council)

#### **CEMENT & CONCRETE WORKER**

## **Cement & Concrete Worker**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$42.33

Supplemental Benefit Rate per Hour: \$26.17

Supplemental Note: \$28.92 on Saturdays; \$31.67 on Sundays & Holidays

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$42.38

Supplemental Benefit Rate per Hour: \$26.17

Supplemental Note: \$28.92 on Saturdays; \$31.67 on Sundays & Holidays

### Overtime Description

Time and one half the regular rate after 7 hour day (time and one half the regular rate after an 8 hour day when working with Dockbuilders on pile cap forms and for work below street level to the top of the foundation wall, not to exceed 2 feet or 3 feet above the sidewalk-brick shelf, when working on the foundation and structure.)

#### **Overtime**

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day

Controller Indiana area (Charles

Presidential Election Day Thanksgiving Day Christmas Day

#### Paid Holidays

1/2 day before Christmas Day 1/2 day before New Year's Day

#### **Shift Rates**

On shift work extending over a twenty-four hour period, all shifts are paid at straight time.

(Cement Concrete Workers District Council) -

#### **CEMENT MASON**

## **Cement Mason**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$38.63

Supplemental Benefit Rate per Hour: \$39.05

Supplemental Note: Overtime supplemental benefit rate per hour: \$57.55

### **Overtime Description**

Time and one-half the regular rate after an 8 hour day, double time the regular rate after 10 hours. Time and one-half the regular rate on Saturday, double time the regular rate after 10 hours. Double time the regular rate on Sunday.

#### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day
President's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day
Presidential Election Day
Thanksgiving Day
Christmas Day

### **Paid Holidays**

Any worker who reports to work on Christmas Eve or New Year's Eve pursuant to his employer's instruction shall be entitled to three (3) hours afternoon pay without working.

#### Shift Rates

ADDENDUM 1

For an off shift day, (work at times other than the regular 7:00 A.M. to 3:30 P.M. work day) a cement mason shall be paid at the regular hourly rate plus a 25% per hour differential. Four Days a week at Ten (10)hour day.

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 13 of 86 PUBLISH DATE: 1/20/2014

(Local #780)

#### CORE DRILLER

### **Core Driller**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$35.44

Supplemental Benefit Rate per Hour: \$19.75

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$35.71

Supplemental Benefit Rate per Hour: \$21.69

## Core Driller Helper

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$28.60

Supplemental Benefit Rate per Hour: \$19.75

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$28.60

Supplemental Benefit Rate per Hour: \$21.69

# Core Driller Helper(Third year in the industry)

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$25.74

Supplemental Benefit Rate per Hour: \$19.75

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$25.74

Supplemental Benefit Rate per Hour: \$21.69

# Core Driller Helper (Second year in the industry)

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$22.88

Supplemental Benefit Rate per Hour: \$19.75

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$22.88

Supplemental Benefit Rate per Hour: \$21.69

# Core Driller Helper (First year in the industry)

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$20.02

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

**PUBLISH DATE: 1/20/2014** 

Page 14 of 86

and the second of the second second second second second second second

Supplemental Benefit Rate per Hour: \$19.75

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$20.02

Supplemental Benefit Rate per Hour: \$21.69

#### **Overtime Description**

Time and one half the regular rate for work on a holiday plus Holiday pay when worked.

#### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Time and one half the regular rate for work on the following holiday(s).

### **Paid Holidays**

New Year's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

#### **Shift Rates**

The shift day shall be the continuous eight and one-half (8½) hours from 6:00 A.M. to 2:30 P.M. and from 2:30 P.M. to 11:00 P.M., including one-half (½) hour of employees regular rate of pay for lunch. When two (2) or more shifts are employed, single time shall be paid for each shift, but those employees employed on a shift other than from 8:00 A.M. to 5:00 P.M. shall, in addition, receive seventy-five cents (\$0.75) per hour differential for each hour worked. When three (3) shifts are needed, each shift shall work seven and one-half (\$7\$½) hours paid for eight (8) hours of labor and be permitted one-half (\$7\$½) hour for mealtime.

(Carpenters District Council)

### **DERRICKPERSON AND RIGGER**

# **Derrick Person & Rigger**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$41.00

Supplemental Benefit Rate per Hour: \$46.07

Supplemental Note: The above supplemental rate applies for work performed in Manhattan, Bronx, Brooklyn and

Queens. \$47.49 - For work performed in Staten Island.

# **Derrick Person & Rigger - Site Work**

Janes MARKET SW

For site work where no rigging is involved.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$30.00

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 15 of 86 PUBLISH DATE: 1/20/2014

The second secon

Supplemental Benefit Rate per Hour: \$31.32

### **Overtime Description**

The first two hours of overtime on weekdays and the first seven hours of work on Saturdays are paid at time and one half for wages and supplemental benefits. All additional overtimes is paid at double time for wages and supplemental benefits. Deduct \$1.42 from the Staten Island hourly benefits rate before computing overtime.

#### **Overtime**

Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day
Washington's Birthday
Good Friday
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

### **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M.

(Local #197)

#### **DIVER**

# **Diver (Marine)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$59.40

Supplemental Benefit Rate per Hour: \$44.97

# **Diver Tender (Marine)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$42.05

Supplemental Benefit Rate per Hour: \$44.97

#### Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

· \*\*

The committee of the same of t

# **Overtime Holidays**

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 16 of 86 PUBLISH DATE: 1/20/2014

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Christmas Day

### **Paid Holidays**

None

### **Shift Rates**

When three shifts are utilized each shift shall work seven and one half-hours (7 1/2 hours) and paid for 8 hours, allowing for one half hour for lunch.

(Carpenters District Council)

#### **DOCKBUILDER - PILE DRIVER**

### <u> Dockbuilder - Pile Driver</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$46.82

Supplemental Benefit Rate per Hour: \$44.97

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

# **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day

Independence Day
Labor Day
Columbus Day
Presidential Election Day

Presidential Election Day

**ADDENDUM 1** 

Thanksgiving Day Christmas Day

# Paid Holidays

None

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 17 of 86

The state of the s

PUBLISH DATE: 1/20/2014

The state of the s

#### Shift Rates

Off shift work commencing between 5:00 P.M. and 11:00 P.M. shall work eight and one half hours allowing for one half hours is allowing for one half hour for lunch. The wage rate shall be 113% of the straight time hourly wage rate.

(Carpenters District Council)

**DRIVER: TRUCK (TEAMSTER)** 

## **Driver - Automobile Chauffeur (Dump Truck)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$38.11

Supplemental Benefit Rate per Hour: \$40.20

### **Driver - Heavy Equipment Trailer Driver**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$39.61

Supplemental Benefit Rate per Hour: \$40.20

Note: For time and one half overtime Wage Rate - \$57.16; for double time overtime Wage Rate - \$76.21

### **Driver - Euclid & Turnapull Operator**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$38.67

Supplemental Benefit Rate per Hour: \$40.20

# <u> Driver - Six Wheeler(3 Axle) Tractors & Trailers</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$39.11

Supplemental Benefit Rate per Hour: \$40.20

Note: For time and one half overtime Wage Rate - \$58.01; for double time overtime Wage Rate - \$77.34

### **Driver - Boom Truck**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$39.36

Supplemental Benefit Rate per Hour: \$40.20

Note: For time and one half overtime Wage Rate - \$58.01; for double time overtime Wage Rate - \$77.34

### **Overtime Description**

For Paid Holidays: Holiday pay for all holidays shall be prorated based two hours per day for each day worked in the holiday week, not to exceed 8 hours of holiday pay. For Thanksgiving week, the prorated share shall be 5 1/3 hours of holiday pay for each day worked in Thanksgiving week.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

### **Paid Holidays**

New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

# <u> Driver - Redi-Mix Driver (Sand & Gravel)</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$35.71

Supplemental Benefit Rate per Hour: \$37.27

### **Overtime Description**

For Paid Holidays: Employees working two (2) days in the calendar week in which the holiday falls are to paid for these holidays, provided they shape each remaining workday during that calendar week.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### Overtime Holidays

Double time the regular rate for work on the following holiday(s). President's Day
Columbus Day
Veteran's Day

A Commence of the Commence of

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 19 of 86 PUBLISH DATE: 1/20/2014

and the state of t

ADDENDUM 1

Triple time the regular rate for work on the following holiday(s).
New Year's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

### **Paid Holidays**

New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day Election Day Thanksgiving Day Christmas Day

(Local #282)

### **ELECTRICIAN**

(Including all low voltage cabling carrying data; video; and voice in combination with data and or video.)

# Electrician "A" (Regular Day)

Effective Period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$52.00

Supplemental Benefit Rate per Hour: \$46.13

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$53.00

Supplemental Benefit Rate per Hour: \$47.54

# **Electrician "A" (Regular Day Overtime)**

Effective Period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$78.00

Supplemental Benefit Rate per Hour: \$49.39

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$79.50

Supplemental Benefit Rate per Hour: \$50.86

# Electrician "A" (Day Shift)

Effective Period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$52.00

Supplemental Benefit Rate per Hour: \$46.13

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$53.00

Supplemental Benefit Rate per Hour: \$47.54

## Electrician "A" (Day Shift Overtime After 8 hours)

Effective Period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$78.00

Supplemental Benefit Rate per Hour: \$49.39

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$79.50

Supplemental Benefit Rate per Hour: \$50.86

## Electrician "A" (Swing Shift)

Effective Period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$61.01

Supplemental Benefit Rate per Hour: \$52.47

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$62.19

Supplemental Benefit Rate per Hour: \$54.07

# Electrician "A" (Swing Shift Overtime After 7.5 hours)

Effective Period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$91.52

Supplemental Benefit Rate per Hour: \$56.30

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$93.29

Supplemental Benefit Rate per Hour: \$57.97

# **Electrician "A" (Graveyard Shift)**

Effective Period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$68.34

Supplemental Benefit Rate per Hour: \$57.83

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$69.66

Supplemental Benefit Rate per Hour: \$59.59

# Electrician "A" (Graveyard Shift Overtime After 7 hours)

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 21 of 86

**PUBLISH DATE: 1/20/2014** 

Effective Period: 7/1/2013 - 5/13/2014 Wage Rate per Hour: \$102.51

Supplemental Benefit Rate per Hour: \$62.11

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$104.49

Supplemental Benefit Rate per Hour: \$63.96

#### Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### **Overtime Holidays**

Time and one half the regular rate for work on a holiday.

New Year's Day

Martin Luther King Jr. Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

## **Paid Holidays**

None

#### Shift Rates

When so elected by the Employer, one or more shifts of at least five days duration may be scheduled as follows: Day Shift: 8:00 am to 4:30 pm, Swing Shift 4:30 pm to 12:30 am, Graveyard Shift: 12:30 am to 8:00 am.

For multiple shifts of temporary light and/or power, the temporary light and/or power employee shall be paid for 8 hours at the straight time rate. For three or less workers performing 8 hours temporary light and/or power the supplemental benefit rate is \$22.86 effective 1/20/2014 and \$23.63 effective 5/14/2014.

# Electrician "M" (First 8 hours)

"M" rated work shall be defined as jobbing: electrical work of limited duration and scope, also consisting of repairs and/or replacement of electrical and tele-data equipment. Includes all work necessary to retrofit, service, maintain and repair all kinds of lighting fixtures and local lighting controls and washing and cleaning of foregoing fixtures.

Effective Period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$26.50

Supplemental Benefit Rate per Hour: \$19.56

First and Second Year "M" Wage Rate Per Hour - Hired on or before 5/10/07: \$25.80 First and Second Year "M" Supplemental Rate- Hired on or before 5/10/07: \$19.21 First and Second Year "M" Wage Rate Per Hour - Hired after 5/10/07: \$22.00

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 22 of 86
PUBLISH DATE: 1/20/2014

Charles Market

- Contract of

**第一次第**5 一点一个生态。

First and Second Year "M" Supplemental Rate- Hired after 5/10/07: \$17.30

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$27.00

Supplemental Benefit Rate per Hour: \$20.32

First and Second Year "M" Wage Rate Per Hour - Hired on or before 5/10/07: \$26.30 First and Second Year "M" Supplemental Rate- Hired on or before 5/10/07: \$19.96 First and Second Year "M" Wage Rate Per Hour - Hired after 5/10/07: \$22.50 First and Second Year "M" Supplemental Rate- Hired after 5/10/07: \$18.06

### Electrician "M" (Overtime After First 8 hours)

"M" rated work shall be defined as jobbing: electrical work of limited duration and scope, also consisting of repairs and/or replacement of electrical and tele-data equipment. Includes all work necessary to retrofit, service, maintain and repair all kinds of lighting fixtures and local lighting controls and washing and cleaning of foregoing fixtures.

Effective Period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$39.75

Supplemental Benefit Rate per Hour: \$21.23

First and Second Year "M" Wage Rate Per Hour - Hired on or before 5/10/07: \$38.70 First and Second Year "M" Supplemental Rate- Hired on or before 5/10/07: \$20.83 First and Second Year "M" Wage Rate Per Hour - Hired after 5/10/07: \$33.00 First and Second Year "M" Supplemental Rate- Hired after 5/10/07: \$18.68

Effective Period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$40.50

Supplemental Benefit Rate per Hour: \$21.01

First and Second Year "M" Wage Rate Per Hour - Hired on or before 5/10/07: \$39.45 First and Second Year "M" Supplemental Rate- Hired on or before 5/10/07: \$21.61 First and Second Year "M" Wage Rate Per Hour - Hired after 5/10/07: \$33.75 First and Second Year "M" Supplemental Rate- Hired after 5/10/07: \$19.47

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

# Paid Holidays

ADDENDUM 1

**Christmas Day** 

None

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 23 of 86 PUBLISH DATE: 1/20/2014

A CONTRACTOR OF THE CONTRACTOR

(Local #3)

#### **ELECTRICIAN - ALARM TECHNICIAN**

(Scope of Work - Inspect, test, repair, and replace defective, malfunctioning, or broken devices, components and controls of Fire, Burglar and Security Systems)

### **Alarm Technician**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$30.40

Supplemental Benefit Rate per Hour: \$13.90

Supplemental Note: \$12.40 only after 8 hours worked in a day

### **Overtime Description**

Time and one half the regular rate for work on the following holidays: Columbus Day, Veterans Day, Day after Thanksgiving.

Double time the regular rate for work on the following holidays: New Year's day, Martin Luther King Jr. Day,

President's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Christmas Day.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Paid Holidays**

New Year's Day
Martin Luther King Jr. Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

#### **Shift Rates**

Night Differential is based upon a ten percent (10%) differential between the hours of 4:00 P.M. and 12:30 A.M. and a fifteen percent (15%) differential for the hours 12:00 A.M. to 8:00 A.M.

#### Vacation

At least 1 year of employment	ten (10) days
5 years or more of employment	
10 years of employment	

and the shall be the same

Plus one Personal Day per year

Sick Days: One day per Year

(Local #3)

## **ELECTRICIAN-STREET LIGHTING WORKER**

### Electrician - Electro Pole Electrician

Effective Period: 7/1/2013 - 5/20/2014

Wage Rate per Hour: \$52.00

Supplemental Benefit Rate per Hour: \$47.90

Effective Period: 5/21/2014 - 6/30/2014

Wage Rate per Hour: \$53.00

Supplemental Benefit Rate per Hour: \$49.34

### **Electrician - Electro Pole Foundation Installer**

Effective Period: 7/1/2013 - 5/20/2014

Wage Rate per Hour: \$39.42

Supplemental Benefit Rate per Hour: \$36.46

Effective Period: 5/21/2014 - 6/30/2014

Wage Rate per Hour: \$40.18

Supplemental Benefit Rate per Hour: \$37.73

#### **Electrician - Electro Pole Maintainer**

Effective Period: 7/1/2013 - 5/20/2014

Wage Rate per Hour: \$33.75

Supplemental Benefit Rate per Hour: \$32.83

Effective Period: 5/21/2014 - 6/30/2014

Wage Rate per Hour: \$34.40

Supplemental Benefit Rate per Hour: \$34.00

#### **Overtime Description**

Electrician - Electro Pole Electrician: Time and one half the regular rate after a 7 hour day and after 5 consecutive days worked per week.

Electrician - Electro Pole Foundation Installer: Time and one half the regular rate after 8 hours within a 24 hour period and Saturday and Sunday.

Electrician - Electro Pole Maintainer: Time and one half the regular rate after a 7 hour day and after 5 consecutive days worked per week. Saturdays and Sundays may be used as a make-up day at straight time when a day is lost during the week to inclement weather.

# **Overtime Holidays**

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 25 of 86

The state of the s

**PUBLISH DATE: 1/20/2014** 

Time and one half the regular rate for work on the following holiday(s). **New Year's Day** Martin Luther King Jr. Day President's Day **Memorial Day** Independence Day **Labor Day** Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving **Christmas Day** 

### **Paid Holidays**

None

(Local #3)

#### **ELEVATOR CONSTRUCTOR**

### **Elevator Constructor**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$57.01

Supplemental Benefit Rate per Hour: \$34.48

### Overtime Description

For New Construction: work performed after 7 or 8 hour day, Saturday, Sunday or between 4:30pm and 7:00am shall be paid at double time rate.

Existing buildings: work performed after an 8 hour day, Saturday, Sunday or between 5:30pm and 7:00 am shall be paid time and one half.

#### Overtime

Double time the regular rate for work on the following holiday(s).

### Paid Holidays

New Year's Day **President's Day Good Friday** Memorial Day **Independence Day** Labor Day **Columbus Day Veteran's Day Thanksgiving Day** Day after Thanksgiving **Christmas Day** 

#### Vacation

Employer contributes 8% of regular basic hourly rate as vacation pay for employees with more than 15 years of service, and 6% for employees with 5 to 15 years of service, and 4% for employees with less than 5 years of service.

(Local #1)

### **ELEVATOR REPAIR & MAINTENANCE**

### **Elevator Service/Modernization Mechanic**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$45.14

Supplemental Benefit Rate per Hour: \$33.02

### **Overtime Description**

For Service Work: Double time - all work performed on Sundays, Holidays, and between midnight and 7:00am.

#### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Time and one half the regular rate for Sunday.

Time and one half the regular rate for work on a holiday plus the day's pay.

### Paid Holidays

New Year's Day

**President's Day** 

**Good Friday** 

**Memorial Day** 

Independence Day

**Labor Day** 

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

**Christmas Day** 

#### Shift Rates

For Modernization Work (4pm to 12:30am) - regularly hourly rate plus a (15%) fifteen percent differential.

#### Vacation

Employer contributes 8% of regular basic hourly rate as vacation pay for employees with more than 15 years of service, and 6% for employees with 5 to 15 years of service, and 4% for employees with less than 5 years of service.

(Local #1)

### ENGINEER

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 27 of 86

to the second of the second of

PUBLISH DATE: 1/20/2014

# **Engineer - Heavy Construction Operating Engineer I**

Cherrypickers 20 tons and over and Loaders (rubber tired and/or tractor type with a manufacturer's minimum rated capacity of six cubic yards and over).

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$61.05

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$97.68

# **Engineer - Heavy Construction Operating Engineer II**

Backhoes, Basin Machines, Groover, Mechanical Sweepers, Bobcat, Boom Truck, Barrier Transport (Barrier Mover) & machines of similar nature. Operation of Churn Drills and machines of a similar nature, Stetco Silent Hoist and machines of similar nature, Vac-Alls, Meyers Machines, John Beam and machines of a similar nature, Ross Carriers and Travel Lifts and machines of a similar nature, Bulldozers, Scrapers and Turn-a-Pulls: Tugger Hoists (Used exclusively for handling excavated material); Tractors with attachments, Hyster and Roustabout Cranes, Cherrypickers. Austin Western, Grove and machines of a similar nature, Scoopmobiles, Monorails, Conveyors, Trenchers: Loaders-Rubber Tired and Tractor: Barber Greene and Eimco Loaders and Eimco Backhoes; Mighty Midget and similar breakers and Tampers, Curb and Gutter Pavers and Motor Patrol, Motor Graders and all machines of a similar nature. Locomotives 10 Tons or under. Mini-Max, Break-Tech and machines of a similar nature; Milling machines, robotic and demolition machines and machines of a similar nature, shot blaster, skid steer machines and machines of a similar nature including bobcat, pile rig rubber-tired excavator (37,000 lbs. and under), 2 man auger.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$59.24

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$94.78

# **Engineer - Heavy Construction Operating Engineer III**

Minor Equipment such as Tractors, Post Hole Diggers, Ditch Witch (Walk Behind), Road Finishing Machines, Rollers five tons and under, Tugger Hoists, Dual Purpose Trucks, Fork Lifts, and Dempsey Dumpers, Fireperson.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$56.22

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$89.95

the amount

# **Engineer - Heavy Construction Maintenance Engineer I**

Installing, Repairing, Maintaining, Dismantling and Manning of all equipment including Steel Cutting, Bending and Heat Sealing Machines, Mechanical Heaters, Grout Pumps, Bentonite Pumps & Plants, Screening Machines, Fusion Coupling Machines, Tunnel Boring Machines Moles and Machines of a similar nature, Power Packs, Mechanical Hydraulic Jacks; all drill rigs including but not limited to Churn, Rotary Caisson, Raised Bore & Drills of a similar nature; Personnel, Inspection & Safety Boats or any boats used to perform functions of same, Mine Hoists, Whirlies, all Climbing Cranes, all Tower Cranes, including but not limited to Truck Mounted and Crawler Type and machines of similar nature; Maintaining Hydraulic Drills and machines of a similar nature; Well Point System-Installation and dismantling; Burning, Welding, all Pumps regardless of size and/or motor power, except

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 28 of 86 PUBLISH DATE: 1/20/2014

River Cofferdam Pumps and Wells Point Pumps; Motorized Buggies (three or more); equipment used in the cleaning and televising of sewers, but not limited to jet-rodder/vacuum truck, vacall/vactor, closed circuit television inspection equipment; high powered water pumps, jet pumps; screed machines and concrete finishing machines of a similar nature; vermeers.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$58.97

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$94.35

## **Engineer - Heavy Construction Maintenance Engineer II**

**On Base Mounted Tower Cranes** 

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$77.30

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$123.68

## **Engineer - Heavy Construction Maintenance Engineer III**

On Generators, Light Towers

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$39.10

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$62.56

# **Engineer - Heavy Construction Maintenance Engineer IV**

On Pumps and Mixers including mud sucking

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$40.11

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$64.18

# **Engineer - Heavy Construction Oilers I**

Gradalls, Cold Planer Grader, Concrete Pumps, Driving Truck Cranes, Driving and Operating Fuel and Grease Trucks.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$53.22

Supplemental Benefit Rate per Hour: \$31.93
Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$85.15

**ADDENDUM 1** 

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 29 of 86

The second secon

**PUBLISH DATE: 1/20/2014** 

# **Engineer - Heavy Construction Oilers II**

All gasoline, electric, diesel or air operated Shovels, Draglines, Backhoes, Keystones, Pavers, Gunite Machines, Battery of Compressors, Crawler Cranes, two-person Trenching Machines.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$36.97

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$59.15

## <u> Engineer - Steel Erection Maintenance Engineers</u>

Derrick, Travelers, Tower, Crawler Tower and Climbing Cranes

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$57.05

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$91.28

## **Engineer - Steel Erection Oiler I**

On a Truck Crane

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$53.43

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$85.49

# **Engineer - Steel Erection Oiler II**

On a Crawler Crane

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$40.84

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

Shift Wage Rate: \$65.34

## Overtime Description

On jobs of more than one shift, if the next shift employee fails to report for work through any cause over which the employer has no control, the employee on duty who works the next shift continues to work at the single time rate.

#### Overtime

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

### **Paid Holidays**

**New Year's Day** Lincoln's Birthday President's Day **Memorial Day Independence Day Labor Day** Columbus Day **Veteran's Day** Thanksgiving Day Day after Thanksgiving **Christmas Day** 

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

### **Engineer - Building Work Maintenance Engineers I**

Installing, repairing, maintaining, dismantling (of all equipment including: Steel Cutting and Bending Machines, Mechanical Heaters, Mine Hoists, Climbing Cranes, Tower Cranes, Linden Peine, Lorain, Liebherr, Mannes, or machines of a similar nature, Well Point Systems, Deep Well Pumps, Concrete Mixers with loading Device, Concrete Plants, Motor Generators when used for temporary power and lights), skid steer machines of a similar nature including bobcat.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$54.04

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

# **Engineer - Building Work Maintenance Engineers II**

On Pumps, Generators, Mixers and Heaters

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$42.10

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

# **Engineer - Building Work Oilers I**

All gasoline, electric, diesel or air operated Gradealls: Concrete Pumps, Overhead Cranes in Power Houses: Their duties shall be to assist the Engineer in oiling, greasing and repairing of all machines; Driving Truck Cranes: Driving and Operating Fuel and Grease Trucks, Cherrypickers (hydraulic cranes) over 70,000 GVW, and machines of a similar nature.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$51.40

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

> ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 31 of 86 **PUBLISH DATE: 1/20/2014**

> > The second secon

## **Engineer - Building Work Oilers II**

Oilers on Crawler Cranes, Backhoes, Trenching Machines, Gunite Machines, Compressors (three or more in Battery).

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$38.31

Supplemental Benefit Rate per Hour: \$31.93 Supplemental Note: \$57.46 on overtime

### Overtime Description

On jobs of more than one shift, if an Employee fails to report for work through any cause over which the Employer has no control, the Employee on duty will continue to work at the rate of single time.

#### **Overtime**

Double time the regular rate after an 8 hour day.

Double time the regular time rate for Saturday.

Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

### **Paid Holidays**

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

#### Shift Rates

Off Shift: double time the regular hourly rate.

(Local #15)

### **ENGINEER - CITY SURVEYOR AND CONSULTANT**

# Party Chief

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$35.55

Supplemental Benefit Rate per Hour: \$17.65

## **Instrument Person**

4.44 Sept. 18

Effective Period: 7/1/2013 - 6/30/2014

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

**PUBLISH DATE: 1/20/2014** 

Wage Rate per Hour: \$29.41

Supplemental Benefit Rate per Hour: \$17.65

### Rodperson

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$25.54

Supplemental Benefit Rate per Hour: \$17.65

### Overtime Description

Overtime Benefit Rate - \$23.63 per hour (time & one half) \$29.95 per hour (double time). Time and one half the regular rate after an 8 hour day, Time and one half the regular rate for Saturday for the first eight hours worked, Double time the regular time rate for Saturday for work performed in excess of eight hours, Double time the regular rate for Sunday and Double time the regular rate for work on a holiday.

### Paid Holidays

**New Year's Day** Lincoln's Birthday President's Day **Memorial Day** Independence Day **Labor Day Columbus Day** Veteran's Day Thanksgiving Day Day after Thanksgiving **Christmas Day** 

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

## **ENGINEER - FIELD (BUILDING CONSTRUCTION)** (Construction of Building Projects, Concrete Superstructures, etc.)

# Field Engineer - BC Party Chief

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$55.40

Supplemental Benefit Rate per Hour: \$30.62

Supplemental Note: Overtime Benefit Rate - \$42.73 per hour (time & one half) \$54.84 per hour (double time).

# Field Engineer - BC Instrument Person

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$43.10

Supplemental Benefit Rate per Hour: \$30.62

Supplemental Note: Overtime Benefit Rate - \$42.73 per hour (time & one half) \$54.84 per hour (double time).

ADDENDUM 1 **EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014** Page 33 of 86 **PUBLISH DATE: 1/20/2014** 

The state of the s

## Field Engineer - BC Rodperson

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$27.96

Supplemental Benefit Rate per Hour: \$30.62

Supplemental Note: Overtime Benefit Rate - \$42.73 per hour (time & one half) \$54.84 per hour (double time).

### **Overtime Description**

Time and one half the regular rate after a 7 hour work and time and one half the regular rate for Saturday for the first seven hours worked, Double time the regular time rate for Saturday for work performed in excess of seven hours, Double time the regular rate for Sunday and Double time the regular rate for work on a holiday.

### **Paid Holidays**

New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

# **ENGINEER - FIELD (HEAVY CONSTRUCTION)**

(Construction of Roads, Tunnels, Bridges, Sewers, Building Foundations, Engineering Structures etc.)

# Field Engineer - HC Party Chief

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$62.61

Supplemental Benefit Rate per Hour: \$30.62

Supplemental Note: Overtime benefit rate - \$42.73 per hour (time & one half), \$54.84 per hour (double time).

# Field Engineer - HC Instrument Person

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$46.00

Supplemental Benefit Rate per Hour: \$30.62

Supplemental Note: Overtime benefit rate - \$42.73 per hour (time & one half), \$54.84 per hour (double time).

# Field Engineer - HC Rodperson

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 34 of 86 PUBLISH DATE: 1/20/2014

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$38.61

Supplemental Benefit Rate per Hour: \$30.62

Supplemental Note: Overtime benefit rate - \$42.73 per hour (time & one half), \$54.84 per hour (double time).

### **Overtime Description**

Time and one half the regular rate after an 8 hour day, Time and one half the regular rate for Saturday for the first eight hours worked, Double time the regular time rate for Saturday for work performed in excess of eight hours, Double time the regular rate for Sunday and Double time the regular rate for work on a holiday.

#### Paid Holidays

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

# **ENGINEER - FIELD (STEEL ERECTION)**

# Field Engineer - Steel Erection Party Chief

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$58.50

Supplemental Benefit Rate per Hour: \$30.62

Supplemental Note: Overtime benefit rate - \$42.73 per hour (time & one half), \$54.84 per hour (double time).

# <u>Field Engineer - Steel Erection Instrument Person</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$45.53

Supplemental Benefit Rate per Hour: \$30.62

Supplemental Note: Overtime benefit rate - \$42.73 per hour (time & one half), \$54.84 per hour (double time).

## Field Engineer - Steel Erection Rodperson

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$30.43

was a second of the second

Supplemental Benefit Rate per Hour: \$30.62

Supplemental Note: Overtime benefit rate - \$42.73 per hour (time & one half), \$54.84 per hour (double time).

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 35 of 86 PUBLISH DATE: 1/20/2014

The state of the s

### **Overtime Description**

Time and one half the regular rate for Saturday for the first eight hours worked.

Double time the regular rate for Saturday for work performed in excess of eight hours.

#### **Overtime**

Time and one half the regular rate after an 8 hour day.

Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

#### Paid Holidays

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

#### **ENGINEER - OPERATING**

# **Operating Engineer - Road & Heavy Construction I**

Back Filling Machines, Cranes, Mucking Machines and Dual Drum Paver.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$67.70

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$108.32

# **Operating Engineer - Road & Heavy Construction II**

Backhoes, Power Shovels, Hydraulic Clam Shells, Steel Erection, Moles and machines of a similar nature.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$70.10

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: 51.75 overtime hours

Shift Wage Rate: \$112.16

# **Operating Engineer - Road & Heavy Construction III**

Mine Hoists, Cranes, etc. (Used as Mine Hoists)

Larger of the control of the control

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 36 of 86 PUBLISH DATE: 1/20/2014

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$72.34

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$115.74

## **Operating Engineer - Road & Heavy Construction IV**

Gradealls, Keystones, Cranes on land or water (with digging buckets), Bridge Cranes, Vermeer Cutter and machines of a similar nature, Trenching Machines.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$70.63

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$113.01

## Operating Engineer - Road & Heavy Construction V

Pile Drivers & Rigs (employing Dock Builder foreperson): Derrick Boats, Tunnel Shovels.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$69.23

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$110.77

# **Operating Engineer - Road & Heavy Construction VI**

Mixers (Concrete with loading attachment), Concrete Pavers, Cableways, Land Derricks, Power Houses (Low Air Pressure Units).

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$65.76

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$105.22

# **Operating Engineer - Road & Heavy Construction VII**

Barrier Movers, Barrier Transport and Machines of a Similar Nature.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$53.08

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$84.93

Some special section of the second

# Operating Engineer - Road & Heavy Construction VIII

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 37 of 86

**PUBLISH DATE: 1/20/2014** 

#### **Utility Compressors**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$41.18

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$51.93

## **Operating Engineer - Road & Heavy Construction IX**

**Horizontal Boring Rig** 

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$62.53

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$100.05

## **Operating Engineer - Road & Heavy Construction X**

Elevators (manually operated as personnel hoist).

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$57.46

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$91.94

# Operating Engineer - Road & Heavy Construction XI

Compressors (Portable 3 or more in battery), Driving of Truck Mounted Compressors, Well-point Pumps, Tugger Machines Well Point Pumps, Churn Drill.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$44.63

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$71.41

# Operating Engineer - Road & Heavy Construction XII

All Drills and Machines of a similar nature.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$66.45

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$106.32

# **Operating Engineer - Road & Heavy Construction XIII**

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 PUBLISH DATE: 1/20/2014

Page 38 of 86

Concrete Pumps, Concrete Plant, Stone Crushers, Double Drum Hoist, Power Houses (other than above).

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$64.34

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$102.94

## **Operating Engineer - Road & Heavy Construction XIV**

**Concrete Mixer** 

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$61.53

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$98.45

## Operating Engineer - Road & Heavy Construction XV

Compressors (Portable Single or two in Battery, not over 100 feet apart), Pumps (River Cofferdam) and Welding Machines, Push Button Machines, All Engines Irrespective of Power (Power-Pac) used to drive auxiliary equipment, Air, Hydraulic, etc.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$41.44

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$66.30

# **Operating Engineer - Road & Heavy Construction XVI**

Concrete Breaking Machines, Hoists (Single Drum), Load Masters, Locomotives (over ten tons) and Dinkies over ten tons, Hydraulic Crane-Second Engineer.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$58.74

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.85 overtime hours

Shift Wage Rate: \$93.98

# Operating Engineer - Road & Heavy Construction XVII

On-Site concrete plant engineer, On-site Asphalt Plant Engineer, and Vibratory console.

Effective Period: 7/1/2013 - 6/30/2014

THE RESERVE OF THE PROPERTY OF

Wage Rate per Hour: \$59.21

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$94.74

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 39 of 86 PUBLISH DATE: 1/20/2014

Salar Sa

# **Operating Engineer - Road & Heavy Construction XVIII**

**Tower Crane** 

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$85.00

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$136.00

## Operating Engineer - Paving I

Asphalt Spreaders, Autogrades (C.M.I.), Roto/Mil

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$65.76

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$105.22

## <u> Operating Engineer - Paving II</u>

**Asphalt Roller** 

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$64.04

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$102.46

# **Operating Engineer - Paving III**

**Asphalt Plants** 

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$54.17

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$86.67

# **Operating Engineer - Concrete I**

**Cranes** 

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$70.32

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

# **Operating Engineer - Concrete II**

#### Compressors

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$41.76

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

### **Operating Engineer - Concrete III**

Micro-traps (Negative Air Machines), Vac-All Remediation System.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$56.16

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

### **Operating Engineer - Steel Erection I**

Three Drum Derricks

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$73.37

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$117.39

# **Operating Engineer - Steel Erection II**

Cranes, 2 Drum Derricks, Hydraulic Cranes, Fork Lifts and Boom Trucks.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$70.50

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$112.80

# **Operating Engineer - Steel Erection III**

Compressors, Welding Machines.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$41.84

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$66.94

# **Operating Engineer - Steel Erection IV**

Compressors - Not Combined with Welding Machine.

The second se

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014
PUBLISH DATE: 1/20/2014

Page 41 of 86

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$39.85

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

Shift Wage Rate: \$63.76

### Operating Engineer - Building Work I

Forklifts, Plaster (Platform machine), Plaster Bucket, Concrete Pump and all other equipment used for hoisting material.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$57.82

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

### **Operating Engineer - Building Work II**

Compressors, Welding Machines (Cutting Concrete-Tank Work), Paint Spraying, Sandblasting, Pumps (with the exclusion of Concrete Pumps), All Engines irrespective of Power (Power-Pac) used to drive Auxiliary Equipment, Air, Hydraulic, Jacking System, etc.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$43.28

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

# Operating Engineer - Building Work III

**Double Drum** 

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$65.83

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

# **Operating Engineer - Building Work IV**

Stone Derrick, Cranes, Hydraulic Cranes Boom Trucks.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$69.74

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

# Operating Engineer - Building Work V

Dismantling and Erection of Cranes, Relief Engineer.

CAL GOOD IN

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$64.26

4 45 To 100

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 42 of 86 PUBLISH DATE: 1/20/2014

The Waste Co. Co.

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

### Operating Engineer - Building Work VI

4 Pole Hoist, Single Drum Hoists.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$63.58

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

## Operating Engineer - Building Work VII

Rack & Pinion and House Cars

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$50.53

Supplemental Benefit Rate per Hour: \$28.60 Supplemental Note: \$51.75 overtime hours

For New House Car projects started after 7/1/11 only: Wage Rate per Hour \$40.31

### **Overtime Description**

On jobs of more than one shift, if an Employee fails to report for work through any cause over which the Employer has no control, the Employee on duty will continue to work at the rate of single time.

For House Cars and Rack & Pinion only: Overtime paid at time and one-half for all hours in excess of eight hours in a day, Saturday, Sunday and Holidays worked.

#### **Overtime**

Double time the regular rate after an 8 hour day.

Double time the regular time rate for Saturday.

Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

### **Paid Holidays**

New Year's Day
Lincoln's Birthday
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

#### **Shift Rates**

For Steel Erection Only: Shifts may be worked at the single time rate at other than the regular working hours (8:00 A.M. to 4:30 P.M.) on the following work ONLY: Heavy construction jobs on work below the street level, over railroad tracks and on building jobs.

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 43 of 86 PUBLISH DATE: 1/20/2014

(Operating Engineer Local #14)

#### **FLOOR COVERER**

(Interior vinyl composition tile, sheath vinyl linoleum and wood parquet tile including site preparation and synthetic turf not including site preparation)

## Floor Coverer

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$46.15

Supplemental Benefit Rate per Hour: \$38.50

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$48.88

Supplemental Benefit Rate per Hour: \$42.70

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

## **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

#### **Shift Rates**

Two shifts may be utilized with the first shift working 8:00 A.M. to the end of the shift at the straight time of pay. The second shift will receive one hour at double time rate for the last hour of the shift. (eight for seven, nine for eight).

(Carpenters District Council)

### **GLAZIER**

(New Construction, Remodeling, and Alteration)

### **Glazier**

Effective Period: 7/1/2013 - 10/31/2013

Wage Rate per Hour: \$42.00

Supplemental Benefit Rate per Hour: \$33.24

Supplemental Note: Supplemental Benefit Overtime Rate: \$41.24

Effective Period: 11/1/2013 - 6/30/2014

Wage Rate per Hour: \$42.00

Supplemental Benefit Rate per Hour: \$34.09

Supplemental Note: Supplemental Benefit Overtime Rate: \$42.59

### Overtime Description

An optional 8th hour can be worked at straight time rate. If 9th hour is worked, then both hours or more (8th & 9th or more) will be at the double time rate of pay.

#### **Overtime**

Double time the regular rate after a 7 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

### **Paid Holidays**

None

### **Shift Rates**

Shifts shall be any 7 hours beyond 4:00 P.M. for which the glazier shall receive 8 hours pay for 7 hours worked.

Companies of the Association of

(Local #1281)

### **GLAZIER - REPAIR & MAINTENANCE**

(For the Installation of Glass - All repair and maintenance work on a particular building, whenever performed, where the total cumulative contract value is under \$105,000. Except where enumerated (i.e. plate glass windows) does not apply to non-residential buildings.)

### Craft Jurisdiction for repair, maintenance and fabrication

Plate glass replacement, Residential glass replacement, Residential mirrors and shower doors, Storm windows and storm doors, Residential replacement windows, Herculite door repairs, Door closer repairs, Retrofit apartment house (non commercial buildings), Glass tinting.

Effective Period: 7/1/2013 - 4/30/2014

Wage Rate per Hour: \$23.50

Supplemental Benefit Rate per Hour: \$18.54

Effective Period: 5/1/2014 - 6/30/2014

Wage Rate per Hour: \$23.60

Supplemental Benefit Rate per Hour: \$19.04

#### Overtime

Time and one half the regular rate after an 8 hour day.

Double time the regular rate for Sunday.

Time and one half the regular hourly rate after 40 hours in any work week.

### **Paid Holidays**

New Year's Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day Day after Thanksgiving Christmas Day

(Local #1281)

### **HEAT AND FROST INSULATOR**

### **Heat & Frost Insulator**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$56.48

Supplemental Benefit Rate per Hour: \$33.31

Effective Period: 1/20/2014 - 6/30/2014

· 大學學 ( ) ( ) ( )

Wage Rate per Hour: \$56.98

Supplemental Benefit Rate per Hour: \$34.81

### **Overtime Description**

Double time shall be paid for supplemental benefits during overtime work. 8th hour paid at time and one half.

### **Overtime**

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).
New Year's Day
Martin Luther King Jr. Day
President's Day
Memorial Day
Independence Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Triple time the regular rate for work on the following holiday(s).

Labor Day

### **Paid Holidays**

None

### **Shift Rates**

The first shift shall work seven hours at the regular straight time rate. The second and third shift shall work seven hours the regular straight time hourly rate plus a fourteen percent wage and benefit premium. Off hour work in occupied or retail buildings may be worked on weekdays with an increment of \$1.00 per hour and eight hours pay for seven (7) hours worked. Double time will apply for over seven (7) hours worked on weekdays, weekends or holidays.

(Local #12)

CANADA NO DE CONTRA DE CON

# HOUSE WRECKER (TOTAL DEMOLITION)

### **House Wrecker - Tier A**

On all work sites the first, second, eleventh and every third House Wrecker thereafter shall be Tier A House Wreckers (i.e. 1st, 2nd, 11th, 14th etc). The 10th and 20th House Wrecker shall be apprentices. Other House Wreckers shall be Tier B House Wreckers.

- Same and the same of the sam

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 47 of 86 PUBLISH DATE: 1/20/2014

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$34.01

Supplemental Benefit Rate per Hour: \$25.14

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$34.51

Supplemental Benefit Rate per Hour: \$25.59

### House Wrecker - Tier B

On all work sites the first, second, eleventh and every third House Wrecker thereafter shall be Tier A House Wreckers (i.e. 1st, 2nd, 11th, 14th etc). The 10th and 20th House Wrecker shall be apprentices. Other House Wreckers shall be Tier B House Wreckers.

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$23.75

Supplemental Benefit Rate per Hour: \$18.62

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$24.02

Supplemental Benefit Rate per Hour: \$19.12

### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

### Paid Holidays

None

(Mason Tenders District Council)

### **IRON WORKER - ORNAMENTAL**

### <u>Iron Worker - Ornamental</u>

Effective Period: 7/1/2013 - 1/19/2014

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 48 of 86 PUBLISH DATE: 1/20/2014

Wage Rate per Hour: \$42.30

Supplemental Benefit Rate per Hour: \$43.54

Supplemental Note: Supplemental benefits are to be paid at the applicable overtime rate when overtime is in

effect.

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$42.70

Supplemental Benefit Rate per Hour: \$44.57

Supplemental Note: Supplemental benefits are to be paid at the applicable overtime rate when overtime is in

effect.

### **Overtime Description**

Time and one half the regular rate after a 7 hour day for a maximum of two hours on any regular work day (the 8th and 9th hour) and double time shall be paid for all work on a regular work day thereafter, time and one half the regular rate for Saturday for the first seven hours of work and double time shall be paid for all work on a Saturday thereafter.

### **Overtime**

Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day

Labor Day Thanksgiving Day Christmas Day

### **Paid Holidays**

None

### **Shift Rates**

For off shift work - 8 hours pay for 7 hours of work. When two or three shifts are employed on a job, Monday through Friday, the workday for each shift shall be seven hours and paid for ten and one-half hours at the single time rate. When two or three shifts are worked on Saturday, Sunday or holidays, each shift shall be seven hours and paid fifteen and three-quarters hours.

(Local #580)

### **IRON WORKER - STRUCTURAL**

### Iron Worker - Structural

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$46.75

ADDENDUM 1

The state of the s

Supplemental Benefit Rate per Hour: \$62.48

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 49 of 86 PUBLISH DATE: 1/20/2014

The second secon

PUBLISH DATE: 1/20/.

Supplemental Note: Supplemental benefits are to be paid at the applicable overtime rate when overtime is in effect.

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$47.25

Supplemental Benefit Rate per Hour: \$64.43

Supplemental Note: Supplemental benefits are to be paid at the applicable overtime rate when overtime is in

effect.

### **Overtime Description**

Monday through Friday- the first eight hours are paid at straight time, the 9th and 10th hours are paid at time and one-half the regular rate, all additional weekday overtime is paid at double the regular rate. Saturdays- the first eight hours are paid at time and one-half the regular rate, double time thereafter. Sunday-all shifts are paid at double time.

#### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).
New Year's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

### **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

### **Shift Rates**

Monday through Friday - First Shift: First eight hours are paid at straight time, the 9th & 10th hours are paid at time and a half, double time paid thereafter. Second and third Shifts: First eight hours are paid at time and one-half, double time thereafter. Saturdays: All shifts, first eight hours paid at time and one-half, double time thereafter: Sunday all shifts are paid at double time.

(Local #40 & #361)

### **LABORER**

(Foundation, Concrete, Excavating, Street Pipe Layer and Common)

### **Laborer**

Excavation and foundation work for buildings, heavy construction, engineering work, and hazardous waste removal in connection with the above work. Landscaping tasks in connection with heavy construction work, engineering work and building projects. Projects include, but are not limited to pollution plants, sewers, parks, subways, bridges, highways, etc.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$39.25

Supplemental Benefit Rate per Hour: \$33.25

### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).
New Year's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Presidential Election Day
Thanksgiving Day
Christmas Day

### **Paid Holidays**

Labor Day Thanksgiving Day

#### **Shift Rates**

When two shifts are employed, single time rate shall be paid for each shift. When three shifts are found necessary, each shift shall work seven and one half hours (7  $\frac{1}{2}$ ), but shall be paid for eight (8) hours of labor, and be permitted one half hour for lunch.

(Local #731)

### **LANDSCAPING**

(Landscaping tasks, as well as tree pruning, tree removing, spraying and maintenance in connection with the planting of street trees and the planting of trees in city parks but not when such activities are performed as part of, or in connection with, other construction or reconstruction projects.)

### Landscaper (Above 6 years experience)

Effective Period: 7/1/2013 - 6/30/2014 Wage Rate per Hour: \$24.25

A CONTRACTOR OF THE PARTY OF TH

Supplemental Benefit Rate per Hour: \$12.30

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 51 of 86

The second secon

**PUBLISH DATE: 1/20/2014** 

### <u>Landscaper (3 - 6 years experience)</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$23.25

Supplemental Benefit Rate per Hour: \$12.30

### Landscaper (up to 3 years experience)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$20.75

Supplemental Benefit Rate per Hour: \$12.30

### Groundperson

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$20.75

Supplemental Benefit Rate per Hour: \$12.30

### **Tree Remover / Pruner**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$29.25

Supplemental Benefit Rate per Hour: \$12.30

### Landscaper Sprayer (Pesticide Applicator)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$19.25

Supplemental Benefit Rate per Hour: \$12.30

### Watering - Plant Maintainer

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$14.25

Supplemental Benefit Rate per Hour: \$12.30

### **Overtime Description**

For all overtime work performed, supplemental benefits shall include an additional seventy-five (\$0.75) cents per hour.

### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Time and one half the regular rate for work on a holiday plus the day's pay.

### **Paid Holidays**

New Year's Day Memorial Day

Independence Day Labor Day Thanksgiving Day Christmas Day

### **Shift Rates**

Work performed on a 4pm to 12am shift has a 15% differential. Work performed on a 12am to 8am shift has a 20% differential.

(Local #175)

### MARBLE MECHANIC

### **Marble Setter**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$49.19

Supplemental Benefit Rate per Hour: \$32.24

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$50.57

Supplemental Benefit Rate per Hour: \$33.82

### **Marble Finisher**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$39.05

Supplemental Benefit Rate per Hour: \$31.43

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$39.71

Supplemental Benefit Rate per Hour: \$33.10

### **Marble Polisher**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$34.73

Supplemental Benefit Rate per Hour: \$24.60

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$35.64

Supplemental Benefit Rate per Hour: \$25.64

CHILL WAY

### **Overtime Description**

Supplemental Benefit contributions are to be made at the applicable overtime rates. Time and one half the regular rate after a 7 hour day or time and one half the regular rate after an 8 hour day - chosen by Employer at the start of the project and then would last for the full duration of the project.

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 53 of 86 PUBLISH DATE: 1/20/2014

- The water of the same of

### **Overtime**

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s). New Year's Day **President's Day Good Friday Memorial Day Independence Day Labor Day** Columbus Day Veteran's Day **Thanksgiving Day** Day after Thanksgiving

### Paid Holidays

**Christmas Day** 

None

(Local #7)

### **MASON TENDER**

### **Mason Tender**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$35.00

Supplemental Benefit Rate per Hour: \$25.74

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$35.53

Supplemental Benefit Rate per Hour: \$26.31

### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday. Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement

weather.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s). **New Year's Day** President's Day **Memorial Day** Independence Day **Labor Day** 

Thanksgiving Day Christmas Day

### Paid Holidays

None

### **Shift Rates**

The Employer may work two (2) shifts with the first shift at the straight time wage rate and the second shift receiving eight (8) hours paid for seven (7) hours work at the straight time wage rate.

(Local #79)

### MASON TENDER (INTERIOR DEMOLITION WORKER)

(The erection, building, moving, servicing and dismantling of enclosures, scaffolding, barricades, protection and site safety structures etc., on Interior Demolition jobs.)

### **Mason Tender Tier A**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$34.07

Supplemental Benefit Rate per Hour: \$19.77

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$34.59

Supplemental Benefit Rate per Hour: \$20.75

### <u>Mason Tender Tier B</u>

On Interior Demolition job sites 33 1/3 % of the employees shall be classified as Tier A Interior Demolition Workers and 66 2/3 % shall be classified as Tier B Interior Demolition Workers; provided that the employer may employ more than 33 1/3 % Tier A Interior Demolition Workers on the job site. Where the number of employees on a job site is not divisible by 3, the first additional employee (above the number of employees divisible by three) shall be a Tier B Interior Demolition Worker, and the second additional employee shall be a Tier A Interior Demolition Worker.

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$23.27

Supplemental Benefit Rate per Hour: \$14.08

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$23.78

Supplemental Benefit Rate per Hour: \$15.07

#### Overtime

Time and one half the regular rate after an 8 hour day.

The second secon

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 PUBLISH DATE: 1/20/2014

Page 55 of 86

Time and one half the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Thanksgiving Day

Christmas Day

### **Paid Holidays**

None

(Local #79)

### **METALLIC LATHER**

### **Metallic Lather**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$41.43

Supplemental Benefit Rate per Hour: \$40.15

Supplemental Note: Supplemental benefits for overtime are paid at the appropriate overtime rate.

### **Overtime Description**

Overtime would be time and one half the regular rate after a seven (7) or eight (8) hours workday, which would be set at the start of the job.

### **Overtime**

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

Washington's Birthday

Good Friday

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Christmas Day

### Paid Holidays

1/2 day on Christmas Eve if work is performed in the A.M.

1/2 day on New Year's Eve if work is performed in the A.M.

### Shift Rates

There shall be either two (2) or three (3) shifts, each shift shall be eight (8) hours with nine (9) hours pay, including one half (½) hour for lunch. Off-Hour Start shall commence after 3:30 P.M. and shall conclude by 6:00 A.M. The first consecutive seven (7) hours shall be at straight time with a differential of twelve dollars (\$12.00) per hour. Fringes shall be paid at the straight time rate.

(Local #46)

### MILLWRIGHT

### Millwright

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$47.69

Supplemental Benefit Rate per Hour: \$48.87

### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).

**New Year's Day** 

**President's Day** 

**Good Friday** 

**Memorial Day** 

Independence Day

**Labor Dav** 

**Columbus Day** 

**Presidential Election Day** 

**Thanksgiving Day** 

**Christmas Day** 

### **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

### Shift Rates

The first shift shall receive the straight time rate of pay. The second shift receives the straight time rate of pay plus fifteen (15%) per cent. Members of the second shift shall be allowed one half hour to eat, with this time being included in the hours of the workday established. There must be a first shift to work a second shift. All additional hours worked shall be paid at the time and one-half rate of pay plus fifteen (15%) per cent for weekday hours.

the state of the s

(Local #740)

### MOSAIC MECHANIC

### Mosaic Mechanic - Mosaic & Terrazzo Mechanic

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$44.39

Supplemental Benefit Rate per Hour: \$35.11

Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$46.08 per hour.

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$44.64

Supplemental Benefit Rate per Hour: \$35.83

Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$46.80 per hour.

### Mosaic Mechanic - Mosaic & Terrazzo Finisher

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$42.78

Supplemental Benefit Rate per Hour: \$35.11

Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$46.08 per hour.

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$43.03

Supplemental Benefit Rate per Hour: \$35.82

Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$46.79 per hour.

### Mosaic Mechanic - Machine Operator Grinder

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$42.78

Supplemental Benefit Rate per Hour: \$35.11

Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$46.08 per hour.

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$43.03

Supplemental Benefit Rate per Hour: \$35.82

Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$46.79 per hour.

#### Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s). New Year's Day Washington's Birthday

Carlo Carlo

Good Friday
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

### **Paid Holidays**

None

(Local #7)

### **PAINTER**

### Painter - Brush & Roller

Effective Period: 7/1/2013 - 4/30/2014

Wage Rate per Hour: \$37.50

Supplemental Benefit Rate per Hour: \$25.62 Supplemental Note: \$30.25 on overtime

Effective Period: 5/1/2014 - 6/30/2014

Wage Rate per Hour: \$39.50

Supplemental Benefit Rate per Hour: \$26.12 Supplemental Note: \$30.75 on overtime

### Spray & Scaffold / Decorative / Sandblast

Effective Period: 7/1/2013 - 4/30/2014

Wage Rate per Hour: \$40.50

Supplemental Benefit Rate per Hour: \$25.62 Supplemental Note: \$30.25 on overtime

Effective Period: 5/1/2014 - 6/30/2014

Wage Rate per Hour: \$42.50

Supplemental Benefit Rate per Hour: \$26.12 Supplemental Note: \$30.75 on overtime

### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s). New Year's Day President's Day

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 59 of 86 PUBLISH DATE: 1/20/2014

Frank Company Company

A CONTRACTOR OF THE PARTY OF TH

Memorial Day Independence Day Labor Day Columbus Day Thanksgiving Day Christmas Day

### Paid Holidays

None

(District Council of Painters #9)

### **PAINTER - SIGN**

### <u>Designer</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$36.15

Supplemental Benefit Rate per Hour: \$9.66

### <u>Journeyperson</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$33.62

Supplemental Benefit Rate per Hour: \$9.66

### **Overtime**

Time and one half the regular rate after an 8 hour day.
Time and one half the regular rate for Saturday.
Time and one half the regular rate for Sunday.
Double time the regular rate for work on the following holiday(s).

### **Paid Holidays**

New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Election Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

### **Shift Rates**

All work performed outside the regular 8 hour work day (either 7:00 A.M to 3:30 P.M or 8:00 A.M. to 4:30 P.M) shall be paid at time and one half the regular hourly rate.

THE REAL PROPERTY.

majoradata 🗀 je i naslata je čina.)

(Local #8A-28A)

### **PAINTER - STRIPER**

### Striper (paint)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$33.50

Supplemental Benefit Rate per Hour: \$11.62

Supplemental Note: Overtime Supplemental Benefit rate - \$7.42; New Hire Rate (0-3 months) - \$0.00

### **Lineperson (thermoplastic)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$37.50

Supplemental Benefit Rate per Hour: \$11.62

Supplemental Note: Overtime Supplemental Benefit rate - \$7.42; New Hire Rate (0-3 months) - \$0.00

### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Time and one half the regular rate for work on the following holiday(s).

### **Paid Holidays**

New Year's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day
Presidential Election Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

#### Shift Rates

Employees hired before April 1, 2003: 15% night shift premium differential for work commenced at 9:00 PM or later.

#### Vacation

Employees with one to two years service shall accrue vacation based on hours worked: 250 hours worked - 1 day vacation; 500 hours worked - 2 days vacation; 750 hours worked - 3 days vacation; 900 hours worked - 4 days vacation; 1,000 hours worked - 5 days vacation. Employees with two to five years service receive two weeks vacation. Employees with five to twenty years service receive three weeks vacation. Employees with twenty to twenty-five years service receive four weeks vacation. Employees with 25 or more years service receive five weeks vacation. Vacation must be taken during winter months. 2 Personal Days except employees hired after 4/1/12 who do not have 2 years of service.

(Local #917)

The second of the second of the second of

### **PAINTER - STRUCTURAL STEEL**

### **Painters on Structural Steel**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$47.00

Supplemental Benefit Rate per Hour: \$32.08

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$47.00

Supplemental Benefit Rate per Hour: \$33.58

### **Painter - Power Tool**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$53.00

Supplemental Benefit Rate per Hour: \$32.08

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$53.00

Supplemental Benefit Rate per Hour: \$33.58

#### Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

### Paid Holidays

None

### **Shift Rates**

Regular hourly rates plus a ten per cent (10%) differential

(Local #806)

Colon to the colon of the

### **PAPERHANGER**

### **Paperhanger**

Effective Period: 7/1/2013 - 4/30/2014

Wage Rate per Hour: \$39.00

Supplemental Benefit Rate per Hour: \$29.23

Supplemental Note: Supplemental benefits are to be paid at the appropriate straight time and overtime rate.

Effective Period: 5/1/2014 - 6/30/2014

Wage Rate per Hour: \$41.08

Supplemental Benefit Rate per Hour: \$29.23

Supplemental Note: Supplemental benefits are to be paid at the appropriate straight time and overtime rate.

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Day after Thanksgiving

### **Paid Holidays**

None

### **Shift Rates**

**Christmas Day** 

Evening shift - 4:30 P.M. to 12:00 Midnight (regular rate of pay); any work performed before 7:00 A.M. shall be at time and one half the regular base rate of pay.

(District Council of Painters #9)

### PAVER AND ROADBUILDER

### Paver & Roadbuilder - Formsetter

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$43.54

Supplemental Benefit Rate per Hour: \$33.55

### Paver & Roadbuilder - Laborer

the same and the s

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 63 of 86

The second of the second of

**PUBLISH DATE: 1/20/2014** 

Paving and road construction work, regardless of material used, including but not limited to preparation of job sites, removal of old surfaces, asphalt and/or concrete, by whatever method, including but not limited to milling; laying of concrete; laying of asphalt for temporary, patchwork, and utility paving (but not production paving); site preparation and incidental work before the installation of rubberized materials and similar surfaces; installation and repair of temporary construction fencing; slurry seal coating, maintenance of safety surfaces; play equipment installation, and other related work.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$39.67

Supplemental Benefit Rate per Hour: \$33.55

### <u>Production Paver & Roadbuilder - Screed Person</u>

(Production paving is asphalt paving when using a paving machine or on a project where a paving machine is traditionally used)

Adjustment of paving machinery on production paving jobs.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$45.12

Supplemental Benefit Rate per Hour: \$33.55

### Production Paver & Roadbuilder - Raker

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$44.61

Supplemental Benefit Rate per Hour: \$33.55

### Production Paver & Roadbuilder - Shoveler

General laborer (except removal of surfaces - see Paver and Roadbuilder-Laborer) including but not limited to tamper, AC paint and liquid tar work.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$41.32

Supplemental Benefit Rate per Hour: \$33.55

### Overtime Description

Veteran's Day is a Paid Holiday for employees working on production paving.

If an employee works New Year's Day or Christmas Day, they receive the single time rate plus 25%.

Employees who work on a holiday listed below receive the straight time rate plus one day's pay for the holiday.

#### Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Paid Holidays**

**Memorial Day** 

Independence Day Labor Day Presidential Election Day Thanksgiving Day

### **Shift Rates**

When two shifts are employed, the work period for each shift shall be a continuous eight (8) hours. When three shifts are employed, each shift will work seven and one half (7  $\frac{1}{2}$ ) hours but will be paid for eight (8) hours since only one half (1/2) hour is allowed for meal time.

When two or more shifts are employed, single time will be paid for each shift.

Night Work - On night work, the first eight (8) hours of work will be paid for at the single time rate, except that production paving work shall be paid at 20% over the single time rate for the screed person, rakers and shovelers directly involved only. All other workers will be exempt. Hours worked over eight (8) hours during said shift shall be paid for at the time and one-half rate.

(Local #1010)

### **PLASTERER**

### **Plasterer**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$41.13

Supplemental Benefit Rate per Hour: \$24.95

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$41.78

Supplemental Benefit Rate per Hour: \$27.95

### **Overtime**

Time and one half the regular rate after a 7 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement

The same of the sa

weather.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

**President's Day** 

**Good Friday** 

**Memorial Day** 

Independence Day

**Labor Day** 

**Columbus Day** 

**Presidential Election Day** 

ADDENDUM 1

Thanksgiving Day

**Christmas Day** 

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 65 of 86 PUBLISH DATE: 1/20/2014

Alexander of the second of the

### **Paid Holidays**

None

### **Shift Rates**

When it is not possible to conduct alteration work during regular work hours, in a building occupied by tenants, said work shall proceed on a shift basis: however work over seven (7) hours in any twenty four (24) hour period, the time after seven (7) hours shall be considered overtime.

The second shift shall start at a time between 3:30 p.m. and 7:00 p.m. and shall consist of seven (7) working hours and shall receive eight (8) hours of wages and benefits at the straight time rate. The workers on the second shift shall be allowed one-half (½) hour to eat with this time being included in the seven (7) hours of work.

(Local #530)

### **PLASTERER - TENDER**

### Plasterer - Tender

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$35.00

Supplemental Benefit Rate per Hour: \$25.74

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$35.53

Supplemental Benefit Rate per Hour: \$26.31

#### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

1.4

### Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
Washington's Birthday
Memorial Day
Independence Day
Labor Day
Presidential Election Day
Thanksgiving Day
Christmas Day

### **Paid Holidays**

None

### **Shift Rates**

one for the law on

When work commences outside regular work hours, workers receive an hour additional (differential) wage and supplement payment. Eight hours pay for seven hours work or nine hours pay for eight hours work.

(Mason Tenders District Council)

### **PLUMBER**

### **Plumber**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$52.36

Supplemental Benefit Rate per Hour: \$37.34

Supplemental Note: Overtime supplemental benefit rate per hour: \$74.40

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$64.87

Supplemental Benefit Rate per Hour: \$25.18

Supplemental Note: Overtime supplemental benefit rate per hour: \$50.08

### **Overtime Description**

Double time the regular rate after a 7 hour day - unless for new construction site work where the plumbing contract price is \$1.5 million or less, the hours of labor can be 8 hours per day at the employers option. On Alteration jobs when other mechanical trades at the site are working an eighth hour at straight time, then the plumber shall also work an eighth hour at straight time.

### **Overtime**

Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

#### Shift Rates

Shift work, when directly specified in public agency or authority documents where plumbing contract is \$8 million or less, will be permitted. 30% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shifts Monday to Friday. 50% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shift work performed on weekends. For shift work on holidays, double time wages and fringe benefits shall be paid.

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 67 of 86 PUBLISH DATE: 1/20/2014

A Committee of the Comm

(Plumbers Local #1)

# PLUMBER (MECHNICAL EQUIPMENT AND SERVICE) (Mechanical Equipment and Service work shall include any repair and/or replacement of the present plumbing system.)

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$33.46

Supplemental Benefit Rate per Hour: \$16.93

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$38.27

Supplemental Benefit Rate per Hour: \$12.84

### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

### Paid Holidays

None

(Plumbers Local # 1)

# PLUMBER (RESIDENTIAL RATES FOR 1, 2 AND 3 FAMILY HOME CONSTRUCTION)

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$37.11

Supplemental Benefit Rate per Hour: \$25.56

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$44.91

Supplemental Benefit Rate per Hour: \$18.37

The state of the s

### **Overtime**

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

### **Paid Holidays**

None

### Shift Rates

30% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shifts Monday to Friday. 50% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shift work performed on weekends. For shift work on holidays, double time wages and fringe benefits shall be paid.

(Plumbers Local #1)

# PLUMBER: PUMP & TANK (Installation and Maintenance)

### Plumber - Pump & Tank

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$53.01

Supplemental Benefit Rate per Hour: \$31.86

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$62.83

Supplemental Benefit Rate per Hour: \$21.37

### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday.

Time and one half the regular rate for Sunday.

**Overtime Holidays** 

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 69 of 86

The second of th

AND THE RESIDENCE OF THE PARTY OF THE PARTY

PUBLISH DATE: 1/20/2014

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

### **Paid Holidays**

None

### **Shift Rates**

All work outside the regular workday (8:00 A.M. to 3:30 P.M.) is to be paid at time and one half the regular hourly rate

(Plumbers Local #1)

# POINTER - WATERPROOFER, CAULKER MECHANIC (EXTERIOR BUILDING RENOVATION)

### Pointer - Waterproofer, Caulker Mechanic

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$45.41

Supplemental Benefit Rate per Hour: \$23.29

### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Time and one half the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).
New Year's Day
Martin Luther King Jr. Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day

### **Paid Holidays**

**Christmas Day** 

Tender to the second se

None

### **Shift Rates**

All work outside the regular work day (an eight hour workday between the hours of 6:00 A.M. and 4:30 P.M.) is to be paid at time and one half the regular rate.

(Bricklayer District Council)

### ROOFER

### Roofer

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$39.00

Supplemental Benefit Rate per Hour: \$27.37

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$40.00

Supplemental Benefit Rate per Hour: \$27.87

### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Presidential Election Day

Thanksgiving Day

Christmas Day

### **Paid Holidays**

None

### **Shift Rates**

Second shift - Regular hourly rate plus a 10% differential. Third shift - Regular hourly rate plus a 15% differential.

(Local #8)

A PER BUTTON OF THE PER BUTTON

racing the contract of the con

# SANDBLASTER - STEAMBLASTER (Exterior Building Renovation)

### Sandblaster / Steamblaster

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$45.41

Supplemental Benefit Rate per Hour: \$23.29

### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

### **Overtime Holidays**

Time and one half the regular rate for work on the following holiday(s).
New Year's Day
Martin Luther King Jr. Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day

### **Paid Holidays**

None

160

### Shift Rates

**Christmas Day** 

All work outside the regular work day (an eight hour workday between the hours of 6:00 A.M. and 4:30 P.M.) is to be paid at time and one half the regular rate.

(Bricklayer District Council)

### SHEET METAL WORKER

### Sheet Metal Worker

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$45.96

Supplemental Benefit Rate per Hour: \$43.19

Supplemental Note: Supplemental benefit contributions are to be made at the applicable overtime rates.

### **Sheet Metal Worker - Duct Cleaner**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$12.90

Supplemental Benefit Rate per Hour: \$8.07

### **Sheet Metal Worker - Fan Maintenance**

(The temporary operation of fans or blowers in new or existing buildings for heating and/or ventilation, and/or air conditioning prior to the completion of the project.)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$36.77

Supplemental Benefit Rate per Hour: \$43.19

### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).
New Year's Day
Martin Luther King Jr. Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

### **Paid Holidays**

None

### **Shift Rates**

Work that can only be performed outside regular working hours (seven hours of work between 7:30 A.M. and 3:30 P.M.) - First shift (work between 3:30 P.M. and 11:30 P.M.) - 10% differential above the established hourly rate. Second shift (work between 11:30 P.M. and 7:30 A.M.) - 15% differential above the established hourly rate.

For Fan Maintenance: On all full shifts of fan maintenance work the straight time hourly rate of pay will be paid for each shift, including nights, Saturdays, Sundays, and holidays. No journeyperson engaged in fan maintenance shall work in excess of forty (40) hours in any work week.

(Local #28)

# SHEET METAL WORKER - SPECIALTY (Decking & Siding)

Commence of the Commence of th

more than a second

### **Sheet Metal Specialty Worker**

The first worker to perform this work must be paid at the rate of the Sheet Metal Worker. The second and third workers shall be paid the Specialty Worker Rate. The ratio of One Sheet Metal Worker, then Two Specialty Workers shall be utilized thereafter.

Effective Period: 7/1/2013 - 7/31/2013

Wage Rate per Hour: \$41.28

Supplemental Benefit Rate per Hour: \$22.88

Supplemental Note: Supplemental benefit contributions are to be made at the applicable overtime rates.

Effective Period: 8/1/2013 - 6/30/2014

Wage Rate per Hour: \$40.78

Supplemental Benefit Rate per Hour: \$23.38

Supplemental Note: Supplemental benefit contributions are to be made at the applicable overtime rates.

### **Overtime**

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

### **Paid Holidays**

**Christmas Day** 

None

With the contract

(Local #28)

## SIGN ERECTOR (Sheet Metal, Plastic, Electric, and Neon)

### Sign Erector

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$42.80

Supplemental Benefit Rate per Hour: \$42.17

ADDENDUM 1 EFFECTIVE PERIOD

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 74 of 86 PUBLISH DATE: 1/20/2014

The same of the sa

### **Overtime**

Time and one half the regular rate after a 7 hour day.

Time and one half the regular rate for Saturday.

Time and one half the regular rate for Sunday.

Time and one half the regular rate for work on the following holiday(s).

### **Paid Holidays**

New Year's Day
Washington's Birthday
Memorial Day
Independence Day
Labor Day
Columbus Day
Election Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

### **Shift Rates**

Time and one half the regular hourly rate is to be paid for all hours worked outside the regular workday either (7:00 A.M. through 2:30 P.M.) or (8:00 A.M. through 3:30 P.M.)

(Local #137)

### STEAMFITTER

### Steamfitter I

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$52.50

Supplemental Benefit Rate per Hour: \$50.54

Supplemental Note: Overtime supplemental benefit rate: \$100.34

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$53.25

Supplemental Benefit Rate per Hour: \$51.04

Supplemental Note: Overtime supplemental benefit rate: \$101.34

### **Overtime**

Double time the regular rate after a 7 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s). New Year's Day President's Day Memorial Day

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 75 of 86 PUBLISH DATE: 1/20/2014

The second secon

Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

### Paid Holidays

None

### **Shift Rates**

Work performed between 3:30 P.M. and 7:00 A.M. and on Saturdays, Sundays and Holidays shall be at double time the regular hourly rate and paid at the overtime supplemental benefit rate above.

### Steamfitter II

For heating, ventilation, air conditioning and mechanical public works contracts with a dollar value not to exceed \$15,000,000 and for fire protection/sprinkler public works contracts not to exceed \$1,500,000.

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$52.50

Supplemental Benefit Rate per Hour: \$50.54

Supplemental Note: Overtime supplemental benefit rate: \$100.34

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$53.25

Supplemental Benefit Rate per Hour: \$51.04

Supplemental Note: Overtime supplemental benefit rate: \$101.34

### **Overtime**

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Paid Holidays

**Christmas Day** 

Day after Thanksgiving

None

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 76 of 86 PUBLISH DATE: 1/20/2014

The state of the s

### Shift Rates

May be performed outside of the regular workday except Saturday, Sunday and Holidays. A shift shall consist of eight working hours. All work performed in excess of eight hours shall be paid at double time. No shift shall commence after 7:00 P.M. on Friday or 7:00 P.M. the day before holidays. All work performed after 12:01 A.M. Saturday or 12:01 A.M. the day before a Holiday will be paid at double time. When shift work is performed the wage rate for regular time worked is a thirty percent premium together with fringe benefits.

On Transit Authority projects, where work is performed in the vicinity of tracks all shift work on weekends and holidays may be performed at the regular shift rates.

Local #638

### STEAMFITTER - REFRIGERATION AND AIR CONDITIONER (Maintenance and Installation Service Person)

### Refrigeration and Air Conditioner Mechanic

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$38.05

Supplemental Benefit Rate per Hour: \$12.26

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$38.30

Supplemental Benefit Rate per Hour: \$12.76

### Refrigeration and Air Conditioner Service Person V

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$31.26

Supplemental Benefit Rate per Hour: \$11.13

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$31.47

Supplemental Benefit Rate per Hour: \$11.55

### Refrigeration and Air Conditioner Service Person IV

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$25.90

Supplemental Benefit Rate per Hour: \$10.16

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$26.07

Supplemental Benefit Rate per Hour: \$10.52

ADDENDUM 1

10.00

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 77 of 86 **PUBLISH DATE: 1/20/2014** 

### Refrigeration and Air Conditioner Service Person III

Filter changing and maintenance thereof, oil and greasing, tower and coil cleaning, scraping and painting, general housekeeping, taking of water samples.

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$22.23

Supplemental Benefit Rate per Hour: \$9.44

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$22.38

Supplemental Benefit Rate per Hour: \$9.76

### Refrigeration and Air Conditioner Service Person II

Filter changing and maintenance thereof, oil and greasing, tower and coil cleaning, scraping and painting, general housekeeping, taking of water samples.

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$18.44

Supplemental Benefit Rate per Hour: \$8.78

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$18.56

Supplemental Benefit Rate per Hour: \$9.06

### Refrigeration and Air Conditioner Service Person I

Filter changing and maintenance thereof, oil and greasing, tower and coil cleaning, scraping and painting, general housekeeping, taking of water samples.

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$13.48

Supplemental Benefit Rate per Hour: \$8.10

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$13.57

Supplemental Benefit Rate per Hour: \$8.30

#### **Overtime**

SHOW SHOW STATE TO THE WAY

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s). New Year's Day Independence Day Labor Day Veteran's Day Thanksgiving Day

### **Christmas Day**

Double time and one half the regular rate for work on the following holiday(s).

Martin Luther King Jr. Day

President's Day

Memorial Day

Columbus Day

### **Paid Holidays**

New Year's Day
Martin Luther King Jr. Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Christmas Day

(Local #638B)

### STONE MASON - SETTER

### **Stone Mason - Setters**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$47.72

Supplemental Benefit Rate per Hour: \$35.28

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$46.56

Supplemental Benefit Rate per Hour: \$36.40

### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

### Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
Washington's Birthday
Good Friday
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

ADDENDUM 1

Selection and District

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014
PUBLISH DATE: 1/20/2014

Page 79 of 86

A CONTRACTOR OF THE PARTY OF TH

### **Paid Holidays**

1/2 day on Christmas Eve if work is performed in the A.M.

#### **Shift Rates**

For all work outside the regular workday (8:00 A.M. to 3:30 P.M. Monday through Friday), the pay shall be straight time plus a ten percent (10%) differential.

(Bricklayers District Council)

### **TAPER**

### **Drywall Taper**

Effective Period: 7/1/2013 - 12/31/2013

Wage Rate per Hour: \$44.32

Supplemental Benefit Rate per Hour: \$21.66

Effective Period: 1/1/2014 - 6/24/2014

Wage Rate per Hour: \$44.82

Supplemental Benefit Rate per Hour: \$21.66

Effective Period: 6/25/2014 - 6/30/2014

Wage Rate per Hour: \$45.32

Supplemental Benefit Rate per Hour: \$21.66

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

### Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

President's Day

Good Friday

Memorial Day

Independence Day

Labor Day

Columbus Day

Thanksgiving Day

Christmas Day

### **Paid Holidays**

Any worker who reports to work on Christmas Eve or New Year's Eve pursuant to his employer's instruction shall be entitled to three (3) hours afternoon pay without working.

### **Shift Rates**

Time and one half the regular rate outside the regular work hours (8:00 A.M. through 3:30 P.M.)

(Local #1974)

## TELECOMMUNICATION WORKER (Voice Installation Only)

#### **Telecommunication Worker**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$35.94

Supplemental Benefit Rate per Hour: \$13.19

Supplemental Note: The above rate applies for Manhattan, Bronx, Brooklyn, Queens. \$12.64 for Staten Island

only.

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

#### Overtime Holidays

Time and one half the regular rate for work on the following holiday(s). **New Year's Day** 

Lincoln's Birthday

Washington's Birthday

**Memorial Day** 

**Independence Day** 

**Labor Day** 

**Columbus Day** 

**Election Day** 

**Veteran's Day** 

**Thanksgiving Day** 

**Christmas Day** 

#### Paid Holidays

**New Year's Day** 

Lincoln's Birthday

**Washington's Birthday** 

**Memorial Day** 

**Independence Day** 

**Labor Day** 

**Columbus Day** 

**Election Day** 

**Veteran's Day** 

Thanksgiving Day

**Christmas Day** 

· Porting to the state of the state of

Employees have the option of observing either Martin Luther King's Birthday or the day after Thanksgiving instead of Lincoln's Birthday

Carried State (125-4) and fight the

#### Shift Rates

For any workday that starts before 8A.M. or ends after 6P.M. there is a 10% differential for the applicable worker's hourly rate.

#### Vacation

(C.W.A.)

#### TILE FINISHER

#### Tile Finisher

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$38.49

Supplemental Benefit Rate per Hour: \$27.40

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$38.80

Supplemental Benefit Rate per Hour: \$28.03

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Good Friday

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

4-1-14

#### **Paid Holidays**

None

#### **Shift Rates**

Off shift work day (work performed outside the regular 8:00 A.M. to 3:30 P.M. workday): shift differential of one and one quarter (1½) times the regular straight time rate of pay for the seven hours of actual off-shift work.

(Local #7)

#### **TILE LAYER - SETTER**

#### Tile Layer - Setter

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$48.35

Supplemental Benefit Rate per Hour: \$31.44

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$49.25

Supplemental Benefit Rate per Hour: \$31.82

#### **Overtime**

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

#### Overtime Holidays

Double time the regular rate for work on the following holiday(s).

**New Year's Day President's Day Good Friday Memorial Day Independence Day** 

**Labor Day** 

**Columbus Day** Veteran's Day

**Thanksgiving Day** 

Day after Thanksgiving

**Christmas Day** 

#### Shift Rates

Off shift work day (work performed outside the regular 8:00 A.M. to 3:30 P.M. workday): shift differential of one and one quarter (11/4) times the regular straight time rate of pay for the seven hours of actual off-shift work.

(Local #7)

#### **TIMBERPERSON**

#### Timberperson

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$42.63

ADDENDUM 1

The second of th

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

Page 83 of 86

Supplemental Benefit Rate per Hour: \$44.54

#### **Overtime**

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Time and one half the regular hourly rate after 40 hours in any work week.

#### **Overtime Holidays**

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Christmas Day

#### Paid Holidays

None

#### Shift Rates

Off shift work commencing between 5:00 P.M. and 11:00 P.M. shall work eight and one half hours allowing for one half hour for lunch. The wage rate shall be 113% of the straight time hourly wage rate.

(Local #1536)

#### TUNNEL WORKER

# Blasters, Mucking Machine Operators (Compressed Air Rates)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$54.20

Supplemental Benefit Rate per Hour: \$48.20

## **Tunnel Workers (Compressed Air Rates)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$52.31

Supplemental Benefit Rate per Hour: \$46.59

# **Top Nipper (Compressed Air Rates)**

Effective Period: 7/1/2013 - 6/30/2014

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 84 of 86

Wage Rate per Hour: \$51.35

Supplemental Benefit Rate per Hour: \$45.78

# <u>Outside Lock Tender, Outside Gauge Tender, Muck Lock Tender (Compressed Air Rates)</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$50.42

Supplemental Benefit Rate per Hour: \$44.91

## Bottom Bell & Top Bell Signal Person: Shaft Person (Compressed Air Rates)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$50.42

Supplemental Benefit Rate per Hour: \$44.92

## **Changehouse Attendant: Powder Watchperson (Compressed Air Rates)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$43.94

Supplemental Benefit Rate per Hour: \$42.55

#### **Blasters (Free Air Rates)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$51.72

Supplemental Benefit Rate per Hour: \$46.03

## **Tunnel Workers (Free Air Rates)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$49.48

Supplemental Benefit Rate per Hour: \$44.06

# **All Others (Free Air Rates)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$45.73

Supplemental Benefit Rate per Hour: \$40.75

## **Microtunneling (Free Air Rates)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$39.58

Supplemental Benefit Rate per Hour: \$35.25

Name and American Company of the Com

#### **Overtime Description**

For Repair-Maintenance Work on Existing Equipment and Facilities - Time and one half the regular rate after a 7 hour day, or for Saturday, or for Sunday. Double time the regular rate for work on a holiday.

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 85 of 86

For Small-Bore Micro Tunneling Machines - Time and one-half the regular rate shall be paid for all overtime.

#### **Overtime**

Double time the regular rate after an 8 hour day.

Double time the regular time rate for Saturday.

Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

#### **Paid Holidays**

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day Labor Day Columbus Day Election Day Veteran's Day Thanksgiving Day Christmas Day

(Local #147)

WELDER
TO BE PAID AT THE RATE OF THE JOURNEYPERSON IN THE TRADE
PERFORMING THE WORK.

a de la la la companya de la companya della companya de la companya de la companya della company

with the party

d Mar

## OFFICE OF THE COMPTROLLER

#### CITY OF NEW YORK

# 220 APPRENTICESHIP PREVAILING WAGE SCHEDULE

#### **APPENDIX**

Pursuant to Labor Law §220 (3-e), only apprentices who are individually registered in a bona fide program to which the employer contractor is a participant and registered with the New York State Department of Labor, may be employed on a public work project.

Any employee listed on a payroll at an apprentice wage rate, who is not registered as above, shall be paid the journey person wage rate for the classification of work he actually performed.

Apprentice ratios are established to ensure the proper safety, training and supervision of apprentices. A ratio establishes the number of journey workers required for each apprentice in a program and on a job site. Ratios are interpreted as follows: in the case of a 1:1, 1:4 ratio, there must be one journey worker for the first apprentice, and four additional journey workers for each subsequent apprentice.

# APPRENTICESHIP SCHEDULE OF PREVAILING WAGES AND SUPPLEMENTAL BENEFITS ADDENDUM

#### EFFECTIVE PERIOD JANUARY 20, 2014 THROUGH JUNE 30, 2014

#### **List of Amended Classifications**

- 1. ASBESTOS HANDLER
- 2. BRICKLAYER
- 3. FLOOR COVERER
- 4. HOUSE WRECKER
- 5. IRONWORKER ORNAMENTAL
- 6. IRON WORKER STRUCTURAL
- 7. MASON TENDER
- 8. PLASTERER
- 9. PLUMBER

CANADA TO THE PARTY OF THE PART

# **TABLE OF CONTENTS**

CLASSIFICATION	PAGE
CLASSIFICATION ASBESTOS HANDLER	4
BOILERMAKER	4
BRICKLAYER	
CARPENTER	
CEMENT MASON	8
CEMENT AND CONCRETE WORKER	8
DERRICKPERSON & RIGGER (STONE)	9
DOCKBUILDER/PILE DRIVER	
ELECTRICIAN	10
ELEVATOR CONSTRUCTOR	13
ELEVATOR REPAIR & MAINTENANCE	14
ENGINEER	15
ENGINEER - OPERATING	15
FLOOR COVERER	16
GLAZIER	17
HEAT & FROST INSULATOR	17
HOUSE WRECKER	18
IRON WORKER - ORNAMENTAL	19
IRON WORKER - STRUCTURAL	21
LABORER (FOUNDATION, CONCRETE, EXCAVATING, STREET PIPE LAYER & COMMO	
MARBLE MECHANICS	
MASON TENDER	24
METALLIC LATHER	
MILLWRIGHT	26
PAVER AND ROADBUILDER	26
PAINTER	27
PAINTER - STRUCTURAL STEEL	28
PLASTERER	
PLUMBER	29
POINTER - WATERPROOFER, CAULKER MECHANIC (EXTERIOR BUILDING RENOVAT	<b>ION) .31</b>
ROOFER	31
SHEET METAL WORKER	32
SIGN ERECTOR	
STEAMFITTER	35
STONE MASON - SETTER	
TAPER	36
TILE LAYER - SETTER	37
TIMPEDDEDONI	^=

#### **ASBESTOS HANDLER**

(Ratio of Apprentice Journeyperson: 1 to 1, 1 to 3)

#### **Asbestos Handler (First 1000 Hours)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 78% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$15.05

Effective 1/20/2014 - Supplemental Benefits Per Hour: 15.45

#### Asbestos Handler (Second 1000 Hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$15.05

Effective 1/20/2014 – Supplemental Benefits Per Hour: 15.45

#### Asbestos Handler (Third 1000 Hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 83% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$15.05

Effective 1/20/2014 - Supplemental Benefits Per Hour: 15.45

# Asbestos Handler (Fourth 1000 Hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 89% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$15.05

Effective 1/20/2014 - Supplemental Benefits Per Hour: 15.45

(Local #78)

#### BOILERMAKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

## Boilermaker (First Year)

Effective Period: 7/1/2013 - 12/31/2013

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$28.75

Effective Period: 1/1/2014 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate

ADDENDUM 1

The state of the s

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 4 of 38 PUBLISH DATE: 1/20/2014

and the second s

Supplemental Benefit Rate Per Hour: \$29.74

## **Boilermaker (Second Year: 1st Six Months)**

Effective Period: 7/1/2013 - 12/31/2013

Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.33

Effective Period: 1/1/2014 - 6/30/2014

Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.40

## **Boilermaker (Second Year: 2nd Six Months)**

Effective Period: 7/1/2013 - 12/31/2013

Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$31.91

Effective Period: 1/1/2014 - 6/30/2014

Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.05

#### **Boilermaker (Third Year: 1st Six Months)**

Effective Period: 7/1/2013 - 12/31/2013

Wage Rate Per Hour: 80% of Journeyperson's rat Supplemental Benefit Rate Per Hour: \$33.49

Effective Period: 1/1/2014 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rat Supplemental Benefit Rate Per Hour: \$34.69

# **Boilermaker (Third Year: 2nd Six Months)**

Effective Period: 7/1/2013 - 12/31/2013

Wage Rate Per Hour: 85% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$35.05

Effective Period: 1/1/2014 - 6/30/2014

Wage Rate Per Hour: 85% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$36.34

# **Boilermaker (Fourth Year: 1st Six Months)**

Effective Period: 7/1/2013 - 12/31/2013

Wage Rate Per Hour: 90% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$36.63

Effective Period: 1/1/2014 - 6/30/2014

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$38.00

· Aten

The state of the s

#### **Boilermaker (Fourth Year: 2nd Six Months)**

Effective Period: 7/1/2013 - 12/31/2013

Wage Rate Per Hour: 95% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$38.19

Effective Period: 1/1/2014 - 6/30/2014

Wage Rate Per Hour: 95% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$39.65

(Local #5)

#### BRICKLAYER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

#### **Bricklayer (First 750 Hours)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$16.60

Effective 1/20/2014 - Supplemental Benefits Per Hour: 17.10

## Bricklayer (Second 750 Hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$16.60

Effective 1/20/2014 - Supplemental Benefits Per Hour: 17.10

# Bricklayer (Third 750 Hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$16.60

Effective 1/20/2014 - Supplemental Benefits Per Hour: 17.10

# Bricklayer (Fourth 750 Hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$16.60

Effective 1/20/2014 - Supplemental Benefits Per Hour: 17.10

# **Bricklayer (Fifth 750 Hours)**

Effective Period: 7/1/2013 - 6/30/2014

**ADDENDUM 1** 

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 6 of 38 **PUBLISH DATE: 1/20/2014** 

一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个 

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$16.60

Effective 1/20/2014 - Supplemental Benefits Per Hour: 17.10

#### **Bricklayer (Sixth 750 Hours)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 95% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$16.60

Effective 1/20/2014 - Supplemental Benefits Per Hour: 17.10

(Bricklayer District Council)

#### **CARPENTER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

#### **Carpenter (First Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30,29

#### **Carpenter (Second Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.29

# **Carpenter (Third Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.29

# Carpenter (Fourth Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.29

(Carpenters District Council)

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 7 of 38 PUBLISH DATE: 1/20/2014

The first of the second of the

#### **CEMENT MASON**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

#### **Cement Mason (First Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's Rate

#### **Cement Mason (Second Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's Rate

#### **Cement Mason (Third Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 70% of Journeyperson's Rate

(Local #780)

#### **CEMENT AND CONCRETE WORKER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# Cement & Concrete Worker (0 - 500 hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.04

# Cement & Concrete Worker (501 - 1000 hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.87

# Cement & Concrete Worker (1001 - 2000 hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$24.25

Miles and the State of the Stat

# Cement & Concrete Worker (2001 - 4000 hours)

Effective Period: 7/1/2013 - 6/30/2014

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

Autorities and the state of the

**PUBLISH DATE: 1/20/2014** 

Page 8 of 38

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$25.07

(Cement Concrete Workers District Council)

## **DERRICKPERSON & RIGGER (STONE)**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

## <u>Derrickperson & Rigger (stone) - First Year</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 50% of Journeyperson's rate

#### Derrickperson & Rigger (stone) - Second Year: 1st Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

#### Derrickperson & Rigger (stone) - Second Year: 2nd Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

## Derrickperson & Rigger (stone) - Third Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

(Local #197)

and the

#### DOCKBUILDER/PILE DRIVER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

# **Dockbuilder/Pile Driver (First Year)**

Effective Period: 7/1/2013 - 6/30/2014

Complete Committee Committ

Wage Rate Per Hour: 40% of Journeyperson's rate

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

The second of th

Page 9 of 38

Supplemental Benefit Rate Per Hour: \$30.29

#### <u>Dockbuilder/Pile Driver (Second Year)</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.29

#### **Dockbuilder/Pile Driver (Third Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.29

#### **Dockbuilder/Pile Driver (Fourth Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.29

(Carpenters District Council)

#### **ELECTRICIAN**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# **Electrician (First Term: 0-6 Months)**

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$12.50

Supplemental Benefit Rate per Hour: \$10.86
Overtime Supplemental Rate per Hour: \$11.68

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$12.50

Supplemental Benefit Rate per Hour: \$11.10
Overtime Supplemental Rate per Hour: \$11.93

## **Electrician (First Term: 7-12 Months)**

11.15年11年 11.16

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$13.50

Supplemental Benefit Rate per Hour: \$11.37
Overtime Supplemental Rate per Hour: \$12.26

Effective period: 5/14/2014 - 6/30/2014

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 10 of 38

Wage Rate per Hour: \$13.50

Supplemental Benefit Rate per Hour: \$11.62
Overtime Supplemental Rate per Hour: \$12.51

#### Electrician (Second Term: 0-6 Months)

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$14.50

Supplemental Benefit Rate per Hour: \$11.88

Overtime Supplemental Rate per Hour: \$12.83

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$14.50

Supplemental Benefit Rate per Hour: \$12.13
Overtime Supplemental Rate per Hour: \$13.08

#### Electrician (Second Term: 7-12 Months)

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$15.50

Supplemental Benefit Rate per Hour: \$12.39
Overtime Supplemental Rate per Hour: \$13.41

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$15.50

Supplemental Benefit Rate per Hour: \$12.64
Overtime Supplemental Rate per Hour: \$13.66

## **Electrician (Third Term: 0-6 Months)**

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$16.50

Supplemental Benefit Rate per Hour: \$12.90
Overtime Supplemental Rate per Hour: \$13.98

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$16.50

Supplemental Benefit Rate per Hour: \$13.15
Overtime Supplemental Rate per Hour: \$14.23

# Electrician (Third Term: 7-12 Months)

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$17.50

Supplemental Benefit Rate per Hour: \$13.40
Overtime Supplemental Rate per Hour: \$14.56

Effective period: 5/14/2014 - 6/30/2014

ALCOHOLD THE MANAGEMENT AND ADMINISTRATION OF THE PARTY O

Wage Rate per Hour: \$17.50

Supplemental Benefit Rate per Hour: \$13.65

ADDENDUM 1 EFFECTIVE

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 11 of 38

Control of the second s

Overtime Supplemental Rate per Hour: \$14.81

#### Electrician (Fourth Term: 0-6 Months - Hired on or after 5/10/07)

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$18.50

Supplemental Benefit Rate per Hour: \$13.91
Overtime Supplemental Rate per Hour: \$15.13

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$18.50

Supplemental Benefit Rate per Hour: \$14.16
Overtime Supplemental Rate per Hour: \$15.38

#### Electrician (Fourth Term: 7-12 Months - Hired on or after 5/10/07)

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$20.25

Supplemental Benefit Rate per Hour: \$14.80 Overtime Supplemental Rate per Hour: \$16.14

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$20.50

Supplemental Benefit Rate per Hour: \$15.18
Overtime Supplemental Rate per Hour: \$16.53

## Electrician (Fifth Term: 0-12 Months - Hired on or after 5/10/07)

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$22.00

Supplemental Benefit Rate per Hour: \$17.30 Overtime Supplemental Rate per Hour: \$18.68

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$22.50

Supplemental Benefit Rate per Hour: \$18.06

Overtime Supplemental Rate per Hour: \$19.47

# Electrician (Fifth Term: 13-18 Months - Hired on or after 5/10/07)

into the second

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$26.50

Supplemental Benefit Rate per Hour: \$19.56
Overtime Supplemental Rate per Hour: \$21.23

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$27.00

Supplemental Benefit Rate per Hour: \$20.32 Overtime Supplemental Rate per Hour: \$22.01

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 12 of 38 PUBLISH DATE: 1/20/2014

Market W.

#### Electrician (Fourth Term: 0-6 Months - Hired before 5/10/07)

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$22.10

Supplemental Benefit Rate per Hour: \$15.74

Overtime Supplemental Rate per Hour: \$17.20

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$22.10

Supplemental Benefit Rate per Hour: \$15.99 Overtime Supplemental Rate per Hour: \$17.45

#### Electrician (Fourth Term: 7-12 Months - Hired before 5/10/07)

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$23.95

Supplemental Benefit Rate per Hour: \$16.69
Overtime Supplemental Rate per Hour: \$18.26

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$24.20

Supplemental Benefit Rate per Hour: \$17.06

Overtime Supplemental Rate per Hour: \$18.66

#### Electrician (Fifth Term: 0-18 Months - Hired before 5/10/07)

Effective period: 7/1/2013 - 5/13/2014

Wage Rate per Hour: \$25.80

Supplemental Benefit Rate per Hour: \$19.21 Overtime Supplemental Rate per Hour: \$20.83

Effective period: 5/14/2014 - 6/30/2014

Wage Rate per Hour: \$26.30

Supplemental Benefit Rate per Hour: \$19.96
Overtime Supplemental Rate per Hour: \$21.61

#### **Overtime Description**

Overtime Wage paid at time and one half the regular rate For "A" rated Apprentices (work in excess of 7 hours per day) For "M" rated Apprentices (work in excess of 8 hours per day)

and the state of t

(Local #3)

#### **ELEVATOR CONSTRUCTOR**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

The second of th

#### **Elevator (Constructor) - First Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$26.87

#### Elevator (Constructor) - Second Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$27.92

#### **Elevator (Constructor) - Third Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$29.38

#### **Elevator (Constructor) - Fourth Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$30.84

(Local #1)

#### **ELEVATOR REPAIR & MAINTENANCE**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

# **Elevator Service/Modernization Mechanic (First Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Benefit Per Hour: \$26.79

# **Elevator Service/Modernization Mechanic (Second Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Benefit Per Hour: \$27.12

# **Elevator Service/Modernization Mechanic (Third Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate

ADDENDUM 1 E

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

**PUBLISH DATE: 1/20/2014** 

Page 14 of 38

Supplemental Benefit Per Hour: \$28.43

#### **Elevator Service/Modernization Mechanic (Fourth Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Benefit Per Hour: \$29.74

(Local #1)

#### **ENGINEER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 5)

#### **Engineer - First Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$22.49

Supplemental Benefit Rate per Hour: \$20.68

#### **Engineer - Second Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$28.11

Supplemental Benefit Rate per Hour: \$20.68

## **Engineer - Third Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$20.92

Supplemental Benefit Rate per Hour: \$20.68

## **Engineer - Fourth Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$33.73

Supplemental Benefit Rate per Hour: \$20.68

(Local #15)

## **ENGINEER - OPERATING**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 5)

Charles Control

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 15 of 38 PUBLISH DATE: 1/20/2014

Salar Sa

#### **Operating Engineer - First Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour 40% of Journeyperson's Rate

Supplemental Benefit Per Hour: \$18.60

#### **Operating Engineer - Second Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's Rate

Supplemental Benefit Per Hour: \$18.60

#### **Operating Engineer - Third Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's Rate

Supplemental Benefit Per Hour: \$18.60

(Local #14)

#### **FLOOR COVERER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# Floor Coverer (First Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$25.75

Effective 1/20/2014 - Supplemental Benefits Per Hour: 29.55

# Floor Coverer (Second Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$25.75

Effective 1/20/2014 - Supplemental Benefits Per Hour: 29.55

# Floor Coverer (Third Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$25.75

Effective 1/20/2014 – Supplemental Benefits Per Hour: 29.55

Page 16 of 38

#### Floor Coverer (Fourth Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$25.75

Effective 1/20/2014 - Supplemental Benefits Per Hour: 29.55

(Carpenters District Council)

#### **GLAZIER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

#### **Glazier (First Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$11.97

#### Glazier (Second Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$21.13

## Glazier (Third Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$23.54

# Glazier (Fourth Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$28.34

(Local #1281)

#### **HEAT & FROST INSULATOR**

ADDENDUM 1

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

The second secon

The state of the s

#### **Heat & Frost Insulator (First Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

#### **Heat & Frost Insulator (Second Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

#### **Heat & Frost Insulator (Third Year)**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 70% of Journeyperson's rate

#### Heat & Frost Insulator (Fourth Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #12)

# HOUSE WRECKER (TOTAL DEMOLITION)

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# House Wrecker - First Year

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$20.36

Supplemental Benefit Rate per Hour: \$16.35

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$20.52

Supplemental Benefit Rate per Hour: \$16.60

# House Wrecker - Second Year

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$21.46

Supplemental Benefit Rate per Hour: \$16.35

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$21.67

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 18 of 38

Supplemental Benefit Rate per Hour: \$16.60

#### House Wrecker - Third Year

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$23.01

Supplemental Benefit Rate per Hour: \$16.35

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$23.27

Supplemental Benefit Rate per Hour: \$16.60

#### **House Wrecker - Fourth Year**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$25.36

Supplemental Benefit Rate per Hour: \$16.35

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$25.83

Supplemental Benefit Rate per Hour: \$16.60

(Local #79)

#### **IRON WORKER - ORNAMENTAL**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

# Iron Worker (Ornamental) - 1st Four Months - Hired on or Before 8/1/08

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$35.78

## Iron Worker (Ornamental) 5 - 10 Months - Hired on or Before 8/1/08

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$36.75

## <u>Iron Worker (Ornamental) 11 - 16 Months - Hired on or Before 8/1/08</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$37.72

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 19 of 38

City of the second seco

## Iron Worker (Ornamental) 17 - 22 Months - Hired on or Before 8/1/08

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$39.66

#### Iron Worker (Ornamental) 23 - 28 Months - Hired on or Before 8/1/08

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 85% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.63

# Iron Worker (Ornamental) 29 - 36 Months - Hired on or Before 8/1/08

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 95% of Journeyperson's rate

Supplemental Rate Per Hour: \$42.57

#### <u>Iron Worker (Ornamental)</u> - 1st Ten Months - Hired After 8/1/08

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.84

Effective 1/20/2014 – Supplemental Benefits Per Hour: 34.55

#### <u>Iron Worker (Ornamental) - 11 - 16 Months - Hired After 8/1/08</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$34.81

Effective 1/20/2014 - Supplemental Benefits Per Hour: 35.55

# Iron Worker (Ornamental) - 17 - 22 Months - Hired After 8/1/08

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$35.78

Effective 1/20/2014 - Supplemental Benefits Per Hour: 36.55

# <u>Iron Worker (Ornamental) - 23 - 28 Months - Hired After 8/1/08</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$37.72

Effective 1/20/2014 - Supplemental Benefits Per Hour: 38.56

# Iron Worker (Ornamental) - 29 - 36 Months - Hired After 8/1/08

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$39.66

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

Page 20 of 38

Street A . All Ser

4.4

Effective 1/20/2014 - Supplemental Benefits Per Hour: 40.56

(Local #580)

## **IRON WORKER - STRUCTURAL**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

#### Iron Worker (Structural) - 1st Six Months

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$24.48

Supplemental Benefit Rate per Hour: \$43.87

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$24.73

Supplemental Benefit Rate per Hour: \$45.07

#### Iron Worker (Structural) - 7- 18 Months

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$25.08

Supplemental Benefit Rate per Hour: \$43.87

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$25.33

Supplemental Benefit Rate per Hour: \$45.07

## Iron Worker (Structural) - 19 - 36 months

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$25.68

Supplemental Benefit Rate per Hour: \$43.87

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$25.93

Supplemental Benefit Rate per Hour: \$45.07

(Local #40 and #361)

The second secon

# LABORER (FOUNDATION, CONCRETE, EXCAVATING, STREET PIPE LAYER & COMMON)

(Ratio Apprentice to Journeyperson: 1 to 1, 1 to 3)

# <u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) - First</u> 1000 hours

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.25

# <u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) - Second 1000 hours</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.25

# <u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) -</u> Third 1000 hours

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.25

# <u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) -</u> <u>Fourth 1000 hours</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.25

(Local #731)

#### MARBLE MECHANICS

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

#### **Cutters & Setters - First 750 Hours**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

NO BENEFITS PAID DURING THE FIRST TWO MONTHS (PROBATIONARY PERIOD)

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 22 of 38

#### Cutters & Setters - Second 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 55% of Journeyperson's rate

#### **Cutters & Setters - Third 750 Hours**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 65% of Journeyperson's rate

#### **Cutters & Setters - Fourth 750 Hours**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

#### **Cutters & Setters - Fifth 750 Hours**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 85% of Journeyperson's rate

#### **Cutters & Setters - Sixth 750 Hours**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 95% of Journeyperson's rate

#### Polishers & Finishers - First 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

NO BENEFITS PAID DURING THE FIRST TWO MONTHS (PROBATIONARY PERIOD)

# Polishers & Finishers - Second 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

## Polishers & Finishers - Third 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

## Polishers & Finishers - Fourth 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 90% of Journeyperson's rate

(Local #7)

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 23 of 38 **PUBLISH DATE: 1/20/2014** 

The state of the s

#### **MASON TENDER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

#### **Mason Tender - First Year**

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$20.63

Supplemental Benefit Rate per Hour: \$17.06

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$20.79

Supplemental Benefit Rate per Hour: \$17.58

#### Mason Tender - Second Year

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$21.73

Supplemental Benefit Rate per Hour: \$17.06

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$21.94

Supplemental Benefit Rate per Hour: \$17.58

# Mason Tender - Third Year

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$23.33

Supplemental Benefit Rate per Hour: \$17.06

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$23.59

Supplemental Benefit Rate per Hour: \$17.58

## Mason Tender - Fourth Year

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$25.93

Supplemental Benefit Rate per Hour: \$17.06

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$26.25

Supplemental Benefit Rate per Hour: \$17.58

(Local #79)

#### **METALLIC LATHER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

#### Metallic Lather (First Year -Called Prior to 6/29/11)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$28.11

Supplemental Benefit Rate per Hour: \$22.79

#### Metallic Lather (Second Year - Called Prior to 6/29/11)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$32.71

Supplemental Benefit Rate per Hour: \$24.44

#### Metallic Lather (Third Year - Called Prior to 6/29/11)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$37.77

Supplemental Benefit Rate per Hour: \$25.59

# Metallic Lather (First Year -Called On Or After 6/29/11)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$17.71

Supplemental Benefit Rate per Hour: \$19.85

## Metallic Lather (Second Year - Called On Or After 6/29/11)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$22.81

Supplemental Benefit Rate per Hour: \$19.85

# Metallic Lather (Third Year - Called On Or After 6/29/11)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$27.91

Supplemental Benefit Rate per Hour: \$19.85

(Local #46)

and the contract of the contra

#### **MILLWRIGHT**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

## Millwright (First Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$26.23

Supplemental Benefit Rate per Hour: \$31.51

#### Millwright (Second Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$31.00

Supplemental Benefit Rate per Hour: \$34.77

#### Millwright (Third Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$35.77

Supplemental Benefit Rate per Hour: \$39.19

#### Millwright (Fourth Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$45.30

Supplemental Benefit Rate per Hour: \$44.63

(Local #740)

#### PAVER AND ROADBUILDER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# Paver and Roadbuilder - First Year (Minimum 1000 hours)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$26.19

Supplemental Benefit Rate per Hour: \$16.20

# Paver and Roadbuilder - Second Year (Minimum 1000 hours)

Effective Period: 7/1/2013 - 6/30/2014

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 26 of 38 PUBLISH DATE: 1/20/2014

Wage Rate per Hour: \$27.77

Supplemental Benefit Rate per Hour: \$16.20

(Local #1010)

#### PAINTER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

#### Painter - Brush & Roller - First Year

Effective Period: 7/1/2013 - 4/30/2014

Wage Rate per Hour: \$15.00

Supplemental Benefit Rate per Hour: \$11.38

Effective Period: 5/1/2014 - 6/30/2014

Wage Rate per Hour: \$15.80

Supplemental Benefit Rate per Hour: \$11.88

#### Painter - Brush & Roller - Second Year

Effective Period: 7/1/2013 - 4/30/2014

Wage Rate per Hour: \$18.75

Supplemental Benefit Rate per Hour: \$15.23

Effective Period: 5/1/2014 - 6/30/2014

Wage Rate per Hour: \$19.75

Supplemental Benefit Rate per Hour: \$15.73

## Painter - Brush & Roller - Third Year

Effective Period: 7/1/2013 - 4/30/2014

Wage Rate per Hour: \$22.50

Supplemental Benefit Rate per Hour: \$18.14

Effective Period: 5/1/2014 - 6/30/2014

Wage Rate per Hour: \$23.70

Supplemental Benefit Rate per Hour: \$18.64

## Painter - Brush & Roller - Fourth Year

Effective Period: 7/1/2013 - 4/30/2014

Wage Rate per Hour: \$30.00

ADDENDUM 1

Supplemental Benefit Rate per Hour: \$23.52

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 27 of 38

Effective Period: 5/1/2014 - 6/30/2014

Wage Rate per Hour: \$31.60

Supplemental Benefit Rate per Hour: \$24.02

(District Council of Painters)

#### **PAINTER - STRUCTURAL STEEL**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

#### Painters - Structural Steel (First Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

#### Painters - Structural Steel (Second Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

#### Painters - Structural Steel (Third Year)

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #806)

#### **PLASTERER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

# Plasterer - First Year: 1st Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$12.76

Effective 1/20/2014 - Supplemental Benefits Per Hour: 15.76

## Plasterer - First Year: 2nd Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 45% of Journeyperson's rate

Supplemental Rate Per Hour: \$13.24

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

Page 28 of 38

Effective 1/20/2014 - Supplemental Benefits Per Hour: 16.24

#### Plasterer - Second Year: 1st Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$15.21

Effective 1/20/2014 - Supplemental Benefits Per Hour: 18.21

#### Plasterer - Second Year: 2nd Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$16.29

Effective 1/20/2014 - Supplemental Benefits Per Hour: 19.29

#### Plasterer - Third Year: 1st Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$18.46

Effective 1/20/2014 - Supplemental Benefits Per Hour: 21.46

#### Plasterer - Third Year: 2nd Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$19.54

Effective 1/20/2014 - Supplemental Benefits Per Hour: 22.54

(Local #530)

#### **PLUMBER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

#### Plumber - First Year: 1st Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$14.00

Supplemental Benefit Rate per Hour: \$0.71

#### Plumber - First Year: 2nd Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$14.00

ALCOHOL THE STATE OF THE STATE

Supplemental Benefit Rate per Hour: \$2.96

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 29 of 38

**PUBLISH DATE: 1/20/2014** 

The second secon

#### Plumber - Second Year

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$18.26

Supplemental Benefit Rate per Hour: \$16.32

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$23.67

Supplemental Benefit Rate per Hour: \$11.16

#### Plumber - Third Year

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$20.36

Supplemental Benefit Rate per Hour: \$16.32

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$25.77

Supplemental Benefit Rate per Hour: \$11.16

#### Plumber - Fourth Year

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$23.21

Supplemental Benefit Rate per Hour: \$16.32

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$28.62

Supplemental Benefit Rate per Hour: \$11.16

## Plumber - Fifth Year: 1st Six Months

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$24.61

Supplemental Benefit Rate per Hour: \$16.32

Effective Period: 1/20/2014 - 6/30/2014

Wage Rate per Hour: \$30.02

Supplemental Benefit Rate per Hour: \$11.16

#### Plumber - Fifth Year: 2nd Six Months

Effective Period: 7/1/2013 - 1/19/2014

Wage Rate per Hour: \$36.68

Supplemental Benefit Rate per Hour: \$16.32

Effective Period: 1/20/2014 - 6/30/2014

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

Page 30 of 38

Wage Rate per Hour: \$42.09

Supplemental Benefit Rate per Hour: \$11.16

(Plumbers Local #1)

# POINTER - WATERPROOFER, CAULKER MECHANIC (EXTERIOR BUILDING RENOVATION)

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

## Pointer - Waterproofer, Caulker Mechanic - First Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$25.00

Supplemental Benefit Rate per Hour: \$3.64

#### Pointer - Waterproofer, Caulker Mechanic - Second Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$27.25

Supplemental Benefit Rate per Hour: \$8.59

## Pointer - Waterproofer, Caulker Mechanic - Third Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$32.23

Supplemental Benefit Rate per Hour: \$11.34

## Pointer - Waterproofer, Caulker Mechanic - Fourth Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$38.66

Supplemental Benefit Rate per Hour: \$11.34

(Bricklayer District Council)

#### ROOFER

et par en en de de de la company de la compa

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

## Roofer - First Year

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 31 of 38 PUBLISH DATE: 1/20/2014

The state of the s

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 35% of Journeyperson's Rate

#### Roofer - Second Year

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's Rate

## Roofer - Third Year

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's Rate

#### Roofer - Fourth Year

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's Rate

(Local #8)

#### SHEET METAL WORKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

## **Sheet Metal Worker - First Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 30% of Journeyperson's rate

Supplemental Rate Per Hour: \$15.37

## Sheet Metal Worker - Second Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 35% of Journeyperson's rate

Supplemental Rate Per Hour: \$18.24

## **Sheet Metal Worker - Third Year (1st Six Months)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$20.06

## **Sheet Metal Worker - Third Year (2nd Six Months)**

Effective Period: 7/1/2013 - 6/30/2014

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

Page 32 of 38

**PUBLISH DATE: 1/20/2014** 

Wage Rate Per Hour: 45% of Journeyperson's rate

Supplemental Rate Per Hour: \$21.87

#### <u> Sheet Metal Worker - Fourth Year (1st Six Months)</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$23.69

### Sheet Metal Worker - Fourth Year (2nd Six Months)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$25.33

#### **Sheet Metal Worker - Fifth Year (1st Six Months)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$27.47

#### **Sheet Metal Worker - Fifth Year(2nd Six Months)**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.23

(Local #28)

#### SIGN ERECTOR

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

## Sign Erector - First Year: 1st Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 35% of Journeyperson's rate

Supplemental Rate Per Hour: \$5.96

## Sign Erector - First Year: 2nd Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$6.75

## Sign Erector - Second Year: 1st Six Months

ADDENDUM 1 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

Page 33 of 38

The second secon

**PUBLISH DATE: 1/20/2014** 

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 45% of Journeyperson's rate

Supplemental Rate Per Hour: \$7.55

#### Sign Erector - Second Year: 2nd Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$8.34

#### Sign Erector - Third Year: 1st Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$9.13

#### Sign Erector - Third Year: 2nd Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$9.92

#### Sign Erector - Fourth Year: 1st Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$10.72

## Sign Erector - Fourth Year: 2nd Six Months

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$11.51

## Sign Erector - Fifth Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$12.30

## <u> Sign Erector - Sixth Year</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$12.30

(Local #137)

#### **STEAMFITTER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

### Steamfitter - First Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate and Supplemental Per Hour: 40% of Journeyperson's rate

#### Steamfitter - Second Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate and Supplemental Rate Per Hour: 50% of Journeyperson's rate.

#### Steamfitter - Third Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate and Supplemental Rate per Hour: 65% of Journeyperson's rate.

#### Steamfitter - Fourth Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate and Supplemental Rate Per Hour: 80% of Journeyperson's rate.

#### Steamfitter - Fifth Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate and Supplemental Rate Per Hour: 85% of Journeyperson's rate.

(Local #638)

#### **STONE MASON - SETTER**

(Ratio Apprentice of Journeyperson: 1 to 1, 1 to 2)

## Stone Mason - Setters - First 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

## Stone Mason - Setters - Second 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

ADDENDUM 1

EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014

Page 35 of 38

**PUBLISH DATE: 1/20/2014** 

#### Stone Mason - Setters - Third 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

#### Stone Mason - Setters - Fourth 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

#### Stone Mason - Setters - Fifth 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

#### Stone Mason - Setters - Sixth 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 100% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

(Bricklayers District Council)

#### **TAPER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

## **Drywall Taper - First Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

## **Drywall Taper - Second Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

## **Drywall Taper - Third Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #1974)

#### **TILE LAYER - SETTER**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

#### <u>Tile Layer - Setter - First 750 Hours</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

#### Tile Layer - Setter - Second 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 55% of Journeyperson's rate

#### Tile Layer - Setter - Third 750 Hours

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 65% of Journeyperson's rate

#### <u>Tile Layer - Setter - Fourth 750 Hours</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

## <u>Tile Layer - Setter - Fifth 750 Hours</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 85% of Journeyperson's rate

## <u>Tile Layer - Setter - Sixth 750 Hours</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage and Supplemental Rate Per Hour: 95% of Journeyperson's rate

(Local #7)

#### **TIMBERPERSON**

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

market and the state of the sta

#### **Timberperson - First Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$30.04

## <u>Timberperson - Second Year</u>

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$30.04

#### Timberperson - Third Year

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$30.04

## **Timberperson - Fourth Year**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$30.04

(Local #1536)

## NYC ADMINISTRATIVE CODE § 6-109 SCHEDULE OF "LIVING WAGES"

Contractors who provide the following services to the City of New York must post a copy of this Living Wage Schedule at their work site(s) as required by New York City Administrative Code § 6-109:

- Building Services,
- Day Care Services,
- Food Services,
- · Head Start Services,
- Homecare Services.
- Services to Persons with Cerebral Palsy, and
- Temporary Services.

In accordance with NYC Administrative Code § 6-109, the Comptroller of the City of New York promulgated this schedule of living wages for the above services on contracts for non-emergency work in excess of the small purchase limit set by the Procurement Policy Board; contracting agencies must annex this schedule to such contracts.

A city service contractor or subcontractor that provides homecare services, day care services, head start services or services to persons with cerebral palsy must pay its covered employees that directly render such services in performance of the city service contract or subcontract no less than the living wage and must provide its employees health benefits (supplemental benefits) or must supplement their hourly wage rate by an amount no less than the health benefits supplement rate. This requirement applies for each hour that the employee works performing the city service contract or subcontract.

A city service contractor or subcontractor that provides building services, food services or temporary services must pay its employees that are engaged in performing the city service contract or subcontract no less than the living wage or the prevailing wage, whichever is greater. Where the living wage is greater than the prevailing wage, the city service contractor or subcontractor must either provide its employees health benefits or must supplement their hourly wage rate by an amount no less than the health benefits supplement rate. Where the prevailing wage is greater than the living wage, the city service contractor or subcontractor must provide its employees the prevailing wage and supplements. These requirements apply for each hour that the employee works performing the city service contract or subcontract.

The appropriate schedule of living wages must be posted at all work sites pursuant to NYC Administrative Code 6-109.

The schedule is applicable for work performed during the effective period, unless otherwise noted. You will be notified of any changes to this schedule by addenda published on our web site www.comptroller.nyc.gov. Schedules for future one-year periods will be published annually in the City Record on or about July 1<sup>st</sup> of each succeeding year and on our web site www.comptroller.nyc.gov.

The living wage rate and the health benefit supplement rate are known through June 30 of each year and those rates are listed in this schedule.

The living wage rates listed in this schedule may not include all hourly wage calculations for pvertime, shift differential, Holiday, Saturday, Sunday or other premium time work. Similarly, this schedule does not set forth every living wage practice with which employers must comply.

PUBLISH DATE: 7/1/2013 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 1 of 8

Some of the rates in this schedule are based on collective bargaining agreements. These agreements are available for inspection by appointment. Requests for appointments may be made by calling (212) 669-4443, Monday through Friday between the hours of 9 a.m. and 5 p.m.

Answers to questions concerning prevailing wage practices may be obtained from the Classification Unit by calling (212) 669-7974. Please direct all other compliance issues to; Bureau of Labor Law, Attn: Wasyl Kinach, P.E., Office of the Comptroller, 1 Centre Street, Room 1122, New York, N.Y. 10007; Fax (212) 669-4002.

Contractors are solely responsible for maintaining original payroll records, which delineate, among other things, the hours each employee worked within a given classification. Contractors using rates and/or classifications not promulgated by the Comptroller do so at their own risk. Additionally, prior to bid, an agency's chief contracting officer must contact the Bureau of Labor Law to obtain a wage determination for a work classification not published in this schedule.

The information listed below is intended to assist you in meeting your living wage and prevailing wage obligation. Contractors are advised to review the Comptroller's Living Wage Schedule prior to submitting a bid for City work. Any wage rate error made by the contracting agency in the contract documents will <u>not</u> preclude a finding against the contractor for an underpayment of the applicable living wage or the applicable prevailing wage.

This schedule sets forth the living wage and benefit rates required to be annexed to and form part of the contract specifications for work covered by New York City Administrative Code § 6-109. Contractors performing such work are required to pay not less that the rates specified in this schedule for the applicable trade or occupation.

Benefits are paid for <u>EACH HOUR WORKED</u> unless otherwise noted.

Wasyl Kinach, P.E.
Director of Classifications
Bureau of Labor Law

## **TABLE OF CONTENTS**

CLASSIFICATION	PAGE
BUILDING CLEANER AND MAINTAINER (OFFICE)	
BUILDING CLEANER AND MAINTAINER (RESIDENTIAL)	4
CLEANER (PARKING GARAGE)	
DAY CARE SERVICES	4
FOOD SERVICE EMPLOYEES	4
GARDENER	5
HEAD START SERVICES	5
HOMECARE SERVICES	6
SECURITY GUARD (ARMED)	6
SECURITY GUARD (UNARMED)	
SERVICES TO PERSONS WITH CEREBRAL PALSY	6
TEMPORARY OFFICE SERVICES	7
WINDOW CLEANER	

## **BUILDING CLEANER AND MAINTAINER (OFFICE)**

For the above building service classification, see the Labor Law Section 230 Schedule.				
<u></u>				•
	· · · · · · · · · · · · · · · · · · ·		·	
BUILDING CLEANER AND MAINTAINER (RESIDENTIAL)				

For the above building service classification, see the Labor Law Section 230 Schedule.

## **CLEANER (PARKING GARAGE)**

For the above building service classification, see the Labor Law Section 230 Schedule.

#### DAY CARE SERVICES

### **Day Care Services**

'Day Care Services' means provision of day care services through the city's center-based day care program administered under contract with the city's Administration for Children's Services. No other day care programs shall be covered, including family-based day care programs administered by city-contracted day care centers.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$10.00

Supplemental Benefit Rate per Hour: \$1.50

(NYC Administrative Code §6-109)

#### FOOD SERVICE EMPLOYEES

## Cook

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$15.62

Supplemental Benefit Rate per Hour: \$1.72

## Cafeteria Attendant

PUBLISH DATE: 7/1/2013 EFFECTIVE PERIOD: JULY 1, 2013 THROUGH JUNE 30, 2014 Page 4 of 8

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$10.48

Supplemental Benefit Rate per Hour: \$1.72

## **Counter Attendant**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$9.95

Supplemental Benefit Rate per Hour: \$1.72

#### Kitchen Helper / Dishwasher

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$9.60

Supplemental Benefit Rate per Hour: \$1.72

#### **Overtime**

Time and one half the regular hourly rate after 40 hours in any work week.

(Based on data from NYS Department of Labor Occupational Employment Statistics and US Department of Labor Bureau of Labor Statistics)

#### **GARDENER**

For the above building service classification, see the Labor Law Section 230 Schedule.

#### **HEAD START SERVICES**

## **Head Start Services**

'Head Start Services' means provision of head start services through the city's center-based head start program administered under contract with the city's Administration for Children's Services. No other head start programs shall be covered.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$10.00

Supplemental Benefit Rate per Hour: \$1.50

(NYC Administrative Code §6-109)

#### HOMECARE SERVICES

#### **Home Care Services**

'Homecare Services' means the provision of homecare services under the city's Medicaid Personal Care/Home Attendant or Housekeeping Programs, including but not limited to the In-Home Services for the Elderly Programs administered by the Department for the Aging.

For homecare services provided under the Personal Care Services program, the wage and supplemental benefit rate above shall apply only as long as the state and federal government maintain their combined aggregate proportionate share of funding and approved rates for homecare services in effect as of the date of the enactment of this section.

For contractors or subcontractors providing homecare services, the supplemental benefit rate may be waived by the terms of a bona fide collective bargaining agreement with respect to employees who have never worked a minimum of eighty (80) hours per month for two consecutive months for that covered employer, but such provision may not be waived for any employee once a minimum of eighty (80) hours for two consecutive months has been achieved.

Effective Period: 7/1/2013 - 6/30/2014 Wage Rate per Hour: \$10.00

Supplemental Benefit Rate per Hour: \$1.50

(NYC Administrative Code §6-109)

## SECURITY GUARD (ARMED)

For the above building service classification, see the Labor Law Section 230 Schedule.

## **SECURITY GUARD (UNARMED)**

For the above building service classification, see the Labor Law Section 230 Schedule.

#### SERVICES TO PERSONS WITH CEREBRAL PALSY

## Services To Person With Cerebral Palsy

'Services to Persons with Cerebral Palsy' means provision of services which enable persons with cerebral palsy and related disabilities to lead independent and productive lives through an agency that provides health care, education, employment, housing and technology resources to such persons under contract with the city or the department of education.

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$10.00

Supplemental Benefit Rate per Hour: \$1.50

(NYC Administrative Code §6-109)

## **TEMPORARY OFFICE SERVICES**

## **Administrative Assistant**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$32.83

Supplemental Benefit Rate per Hour: None

## Cashier

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$11.50

Supplemental Benefit Rate per Hour: None

## Clerk (various)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$14.86

Supplemental Benefit Rate per Hour: None

## **Computer Assistant**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$21.23

Supplemental Benefit Rate per Hour: None

## **Data Entry Operator**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$16.21

Supplemental Benefit Rate per Hour: None

## Receptionist

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$14.88

Supplemental Benefit Rate per Hour: None

## Secretary (various)

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$18.66

Supplemental Benefit Rate per Hour: None

#### **Word Processor**

Effective Period: 7/1/2013 - 6/30/2014

Wage Rate per Hour: \$20.02

Supplemental Benefit Rate per Hour: None

#### **Overtime**

Time and one half the regular hourly rate after 40 hours in any work week.

(Based on data from NYS Department of Labor Occupational Employment Statistics and US Department of Labor Bureau of Labor Statistics or NYC Administrative Code §6-109)

#### WINDOW CLEANER

For the above building service classification, see the Labor Law Section 230 Schedule.



# THE CITY OF NEW YORK OFFICE OF THE COMPTROLLER 1 CENTRE STREET ROOM 1120 NEW YORK, N.Y. 10007-2341

TELEPHONE: (212) 669-3622 FAX NUMBER: (212) 669-8499

ALAN G. HEVESI COMPTROLLER

#### MEMORANDUM

November 6, 2000

To

Agency Chief Contracting Officers

From:

Leonard A. Mancusi

Re:

Security at Construction Sites

Prior to the enactment of Administrative Code §6-109, security guards on construction sites were not subject to prevailing wages. Security guards under the New York State labor law are covered under §230 which provides that prevailing wages are to be paid for security guards in existing buildings. §6-109 of the Administrative Code which was enacted in 1996 closed this loophole by including all security guards working pursuant to a city contract as a prevailing wage trade.

Although some construction contract boilerplate language has been amended to include §6-109, sub-contractors performing security services have advised us that they were not aware of this provision and, since traditionally, security guards were not a covered trade on construction sites, and they were not advised by a prime contractor that they would have to pay prevailing wages, they have not been doing so.

To avoid the possibility of issuing stop payments against prime contractors for the failure of their security service sub-contractors to pay

prevailing wages, we suggest-that you write to all your existing security guard sub-contractors and their primes and in the future, upon approval of a security guard sub-contractor, advise the contractors of their obligation to pay prevailing wages under §6-109 of the Administrative Code.

As always, your cooperation is appreciated.

·LAM:er ACCO.SECURITY AT SITES



## INFRASTRUCTURE DIVISION BUREAU OF DESIGN

## **VOLUME 2 OF 3**

	Contractor
Dated	, 20
APPROVED AS TO FORM CERTIFIED AS TO LEGAL AUTHORITY	
	Acting Corporation Counsel
Dated	



## INFRASTRUCTURE DIVISION BUREAU OF DESIGN

## **VOLUME 2 OF 3**

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES
IN: ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET
BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

INCLUDING WATER MAIN WORK

Together With All Work Incidental Thereto BOROUGH OF STATEN ISLAND CITY OF NEW YORK

Inter Contracting	Corp.
J	Contractor
Dated October 20,	, 20 J
APPROVED AS TO FORM CERTIFIED AS TO LEGAL AUTHORITY	Acting Corporation Counsel 3/14/14
Dated Asch 14	Acting Corporation Counsel, 20/4



# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

30-30 THOMSON AVENUE LONG ISLAND CITY, NEW YORK 11101-3045 TELEPHONE (718) 391-1000 WEBSITE www.nyc.gov/buildnyc

LAW

**VOLUME 3 OF 3** 

SCHEDULE A ADDENDA NOS. 1 TO 4

FOR FURNISHING ALL LABOR AND MATERIALS NECESSARY AND REQUIRED FOR:

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN: ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD; WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET; FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE; WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE; GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE; MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE; VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND, WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

**INCLUDING WATER MAIN WORK** 

Together With All Work Incidental Thereto BOROUGH OF STATEN ISLAND CITY OF NEW YORK

FOR THE DEPARTMENT OF ENVIRONMENTAL PROTECTION PREPARED BY IN-HOUSE DESIGN

February 26, 2014



#### SPECIFICATIONS AND STANDARDS OF NEW YORK CITY

The following NYC Department of Transportation reference documents are available on-line at:

http://www.nyc.gov/html/ddc/html/pubs/pubs\_infrastdts.shtml or for purchase between 9:00 A.M. and 3:00 P.M. at 55 Water St., Ground Floor, NYC, N.Y. 10041. Contact: Ms Vivian Cruz, Tel. (212) 839-9434

- 1. New York City Standard Highway Specifications, November 1, 2010
- 2. New York City Standard Highway Details of Construction, July 1, 2010
- 3. New York City Division of Street Lighting Specifications
- 4. New York City Division of Street Lighting Standard Drawings
- 5. New York City Standard Specifications for Traffic Signals
- 6. New York City Standard Drawings for Traffic Signals

The following reference documents for Sewer Work are available on-line at: <a href="http://www.nyc.gov/html/ddc/html/pubs/pubs\_infrastdts.shtml">http://www.nyc.gov/html/ddc/html/pubs/pubs\_infrastdts.shtml</a> or for pick up between 8:00 A.M. and 4:00 P.M. at 30-30 Thomson Avenue, 3rd Floor, Division of Infrastructure, Long Island City, N.Y. 11101. Contact: Mr. William Patalano, Tel. (718) 391-2054

- 1. New York City DEP Standard Sewer Specifications, August 1, 2009
- 2. New York City DEP Instructions for Concrete Specifications, Jan. 92
- 3. New York City DEP General Specification 11-Concrete, November 1991
- 4. New York City DEP Sewer Design Standards, (September 2007) Revised January 2009

The following reference documents for Water Mains Work are available online at: <a href="http://www.nyc.gov/html/ddc/html/pubs/pubs\_infrastdts.shtml">http://www.nyc.gov/html/ddc/html/pubs/pubs\_infrastdts.shtml</a> or for pick up between 8:00 A.M. and 4:00 P.M. at 30-30 Thomson Avenue, 3rd Floor, Division of Infrastructure, Long Island City, N.Y. 11101. Contact: Mr. Robert Kuhlmann, Tel. (718) 391-2145

- 1. New York City Department of Environmental Protection, Standard Water Main Specifications, dated August 1, 2009
- 2. New York City Department of Environmental Protection Water Main Standard Drawings
- 3. Specifications for Trunk Main Work, dated February 2010

The water main work material specifications are available at the Department of Environmental Protection, 59-17 Junction Boulevard, 3rd Floor Low-Rise Building, Flushing, N.Y. 11373-5108.

Contact: Mr. Tarlock Sahansra, P.E., Tel. (718) 595-5302 E-mail: TSAHANSRA@DEP.NYC.GOV

Standard Specifications and Drawings for Fire Department Communications facilities of New York City are available at 87 Union Street, Engineering Office, Brooklyn, N.Y. 11231-1416.

Contact: Mr. Ed Durkin, Tel. (718) 624-3752

Tree Planting Standards of the City of New York Parks & Recreation are available at the following Department of Parks & Recreation website: <a href="http://www.nycgovparks.org/pagefiles/53/Tree-Planting-Standards.pdf">http://www.nycgovparks.org/pagefiles/53/Tree-Planting-Standards.pdf</a>

#### SPECIFICATIONS AND STANDARDS OF PRIVATE UTILITIES

The Following reference document for Private Utility Work is available for pick up between 8:30 A.M. and 4:00 P.M. at 30-30 Thomson Avenue, First Floor Bid Procurement Room, L.I.C., N.Y. 11101.

1. CET SPECIFICATIONS AND SKETCHES dated November 2010

(NO TEXT ON THIS PAGE)

## **SCHEDULE "A"**

# (GENERAL CONDITIONS TO CONSTRUCTION CONTRACT) (INCLUDING GENERAL CONDITIONS RELATED TO ARTICLE 22 - INSURANCE)

## PART I. REQUIRED INFORMATION

See Attachment 1 (page A-1 of the Bid Booklet)
See Attachment 1 (page A-1 of the Bid Booklet)
See Page SA-4
For Each Consecutive Calendar Day Over Substantial Completion Time: \$1,500.00
Not to Exceed 35% of the Contract Price
5% of the Value of the <b>Work</b>
See pages SA-5 through SA-9

CONTRACT ARTICLE 24.  DEPOSIT GUARANTEE  As security for the faithful performance of its obligations, the Contractor, upon filing its requisition for payment on Substantial Completion, shall deposit with the Commissioner a sum equal to the percentage of the Contract price indicated to the right.	1% of Contract Price
CONTRACT ARTICLE 24. PERIOD OF GUARANTEE  Periods of maintenance and guarantee other than the period set forth in Article 24.1 are indicated to the right.	Eighteen (18) Months, excluding Trees  Twenty-Four (24) Months for Tree Planting
CONTRACT ARTICLE 74. STATEMENT OF WORK  The Contractor shall furnish all labor and materials and perform all Work in strict accordance with the Contract Drawings, Specifications, and all Addenda thereto.	See Contract Article 74
CONTRACT ARTICLE 75. COMPENSATION TO BE PAID TO CONTRACTOR  The City shall pay and the Contractor shall accept in full consideration for the performance of the Contract, subject to additions and deductions as provided in Contract Article 75, this said sum being the amount at which the Contract was awarded to the Contractor at a public letting thereof, based upon the Contractor's bid for the Contract.	See Contract Article 75
CONTRACT ARTICLE 78.  PARTICIPATION BY MINORITY-OWNED AND WOMEN- OWNED BUSINESS ENTERPRISES IN CITY PROCUREMENT	See M/WBE Utilization Plan in the Bid Booklet

# STANDARD HIGHWAY SPECIFICATIONS SECTION 6.40 LIQUIDATED DAMAGES FOR ENGINEER'S FIELD OFFICE

If the Contractor fails to satisfactorily provide the field office and all equipment specified in **Section 6.40 - Engineer's Field Office**, and/or if a cited deficiency exceed seventy two (72) hours after notice from the Engineer in writing, or is permitted to recur, liquidated damages will be assessed in the amount specified herein for each subsequent calendar day or part thereof that a cited deficiency resulting in nonpayment, as described in **Section 6.40.5**, is not corrected.

For Each Calendar Day of Deficiency: \$250.00

# STANDARD HIGHWAY SPECIFICATIONS SECTION 6.70 LIQUIDATED DAMAGES FOR MAINTENANCE AND PROTECTION OF TRAFFIC

For each instance of failure to comply with the Maintenance and Protection of Traffic requirements within three (3) hours after written notice from the Engineer: \$250.00

For each and every hour of failing to open the entire width of roadway to traffic the morning following a night/weekend work operation: \$500.00

# STANDARD HIGHWAY SPECIFICATIONS SECTION 7.13 LIQUIDATED DAMAGES FOR MAINTENANCE OF SITE

If the Contractor fails to comply, within three (3) consecutive hours after written notice from the Engineer, with the requirements of **Section 7.13 - Maintenance of Site**, the Contractor shall pay to the City of New York, until such notice has been complied with or rescinded, the sum specified above per calendar day, for each instance of such failure, as liquidated damages and not as a penalty, for such default.

For Each Calendar Day, for Each Occurrence: \$250.00

#### Date for Substantial Completion (Reference: Article 14)

The Contractor sha with the terms and	all substantially complete the Work conditions set forth herein.	within the Final Contract Duration determi	ined in accordance
The Base Contract	Duration for this project is54	consecutive calendar days ("ccds"	).
"NO", below, and s		et Duration when a check mark is indicate adjusted by the table set forth below whe	
	√ YES	NO	
W			

When the Final Contract Duration is indicated above to be adjusted by the table below, the table may increase the Base Contract Duration depending on the date of scheduled substantial completion to avoid a scheduled substantial completion of the Work during the winter months. The date of the scheduled substantial completion shall be determined by adding the Base Contract Duration to the date specified to commence work in the written Notice To Proceed. The Final Contract Duration shall then be determined as follows:

- (a) Find the row that corresponds to the month of the substantial completion based on the Base Contract Duration added to the date specified to commence work in the written Notice To Proceed.
- (b) Find the number of days to be added to the Base Contract Duration in the table below. Add that number of days to the Base Contract Duration to obtain the Final Contract Duration in consecutive calendar days.

Month Of Substantial Completion Based On The Base Contract Duration	Number Of Days Of Adjustment
January	150
February	120
March	90
April	60
May	30
June	0
July	0
August	0
September	0
October	0
November - December 15	0
December 16 - December 31	180

In addition, should Item No. 9.30 - STORM WATER POLLUTION PREVENTION exist in the Contract and the required Storm Water Pollution Prevention Plan (SWPPP) does not conform to NYSDEC's recommended Standards, an additional 60-ccds shall be added to the above Final Contract Duration.

# (GENERAL CONDITIONS RELATING TO ARTICLE 22 - INSURANCE) PART II. TYPES OF INSURANCE, MINIMUM LIMITS AND SPECIAL CONDITIONS

<u>Note</u>: All certificate(s) of insurance submitted pursuant to Contract Article 22.3.3 must be accompanied by a Certification by Broker consistent with Part III below and include the following information:

- For each insurance policy, the name and NAIC number of issuing company, number of policy, and effective dates;
- Policy limits consistent with the requirements listed below;
- Additional insureds or loss payees consistent with the requirements listed below; and
- The number assigned to the Contract by the City (in the "Description of Operations" field).

Insurance indicated by a blackened box ( ) or by an X in a box ( ) to left will be required under this contract

TYPES OF INSURANC (per Article 22 in its entirety, including		MINIMUM LIMITS AND SPECIAL CONDITIONS
Commercial General Liability	Art. 22.1.1	The minimum limits shall be \$1,000,000 per Occurrence and \$2,000,000 per Project Aggregate applicable to this Contract.  Additional Insureds:  (1) City of New York, including its officials and employees, with coverage at least as broad as ISO Form CG 20 10 and CG 20 37.  (2) All person(s) or organization(s), if any, that Article 22.1.1(b) of the Contract requires to be named as Additional Insured(s), with coverage at least as broad as ISO Form CG 20 26. The Additional Insured endorsement shall either specify the entity's name, if known, or the entity's title (e.g., Project Manager).  (3) National Grid  (4)

Workers' Compensation	Art. 22.1.2	Workers' Compensation, Employers' Liability, and Disability Benefits Insurance: Statutory per New York State law without
■ Disability Benefits Insurance	Art. 22.1.2	regard to jurisdiction.
Employers' Liability	Art. 22.1.2	Note: The following forms are acceptable: (1) New York State Workers' Compensation Board Form No. C-105.2, (2)
☐ Jones Act	Art. 22.1.3	State Insurance Fund Form No. U-26.3, (3) New York State Workers' Compensation Board Form No. DB-120.1 and (4)
U.S. Longshoremen's and Harbor Workers Compensation Act	Art. 22.1.3	Request for WC/DB Exemption Form No. CE-200. The City will not accept an ACORD form as proof of Workers' Compensation or Disability Insurance.
		Jones Act and U.S. Longshoremen's and Harbor Workers' Compensation Act: Statutory per U.S. Law.
		Additional Requirements:
		(1)
		(2)
☐ Builders' Risk	Art. 22.1.4	100% of Total Value of <b>Work</b>
		Contractor the Named Insured; the City both an Additional Insured and one of the loss payees as its interests may appear.
		If the <b>Work</b> does not involve construction of a new building or gut renovation work, the <b>Contractor</b> may provide an installation floater in lieu of Builders Risk insurance.
		Note: Builders Risk Insurance may terminate upon Substantial Completion of the Work in its entirety.
Commercial Auto Liability	Art. 22.1.5	\$2,000,000 per accident combined single limit
		If vehicles are used for transporting hazardous materials, the <b>Contractor</b> shall provide pollution liability broadened coverage for covered vehicles (endorsement CA 99 48) as well as proof of MCS 90.
•		Additional Insureds:
		(1) City of New York, including its officials and employees.
		(2)
		(3)

☐ Contractors Pollution Liability	Art. 22.1.6	\$ per occurrence
		\$ aggregate
		Additional Insureds:
		(1) City of New York, including its officials and employees.
		(2)
		(3)
☐ Marine Protection and Indemnity	Art. 22.1.7(a)	\$ each occurrence
		<u>\$</u> aggregate
	•	Additional Insureds:
	•	(1) City of New York, including its officials and employees.
		(2)
		(3)
☐ Hull and Machinery Insurance	Art. 22.1.7(b)	\$ per occurrence
		\$aggregate
		Additional Insureds:
		(1) City of New York, including its officials and employees.
		(2)
		(3)
☐ Marine Pollution Liability	Art. 22.1.7(c)	\$ per occurrence
		\$aggregate
		Additional Insureds:
		(1) City of New York, including its officials and employees.
		(2)
		(3)

[OTHER] Art. 22.1.8  Railroad Protection Liability Policy	\$2,000,000 per occurrence	
(ISO-RIMA or equivalent form) approved by Permittor covering the work to be performed at the designated site and affording protection for damages arising out of bodily injury or death, physical damage to or destruction of property, including damage to the Insured's own property and conforming to the following:	\$6,000,000 annual aggregate Named Insureds: (1) (2)	
<ul> <li>Policy Endorsement CG 28 31 - Pollution Exclusion Amendment is required to be endorsed onto the policy when environmental- related work and/or exposures exist.</li> </ul>		
<ul> <li>Indicate the Name and address of the Contractor to perform the work, the Contract Number and the name of the railroad property where the work is being performed and the Agency Permit.</li> </ul>	•	
<ul> <li>Evidence of Railroad Protective Liability Insurance, must be provided in the form of the Original Policy. A detailed Insurance Binder (ACORD or Manuscript Form) will be accepted pending issuance of the Original Policy, which must be provided within thirty (30) days of the Binder Approval.</li> </ul>		
[OTHER] ☐ Professional Liability	Art. 22.1.8	
A. The Contractor's Professional Engineer shall maintain and submit evidence of Professional Liability Insurance in the minimum amount of \$1,000,000 per claim. The policy or policies shall include an endorsement to cover the liability assumed by the Contractor under this Contract arising out of the negligent performance of professional services or caused by an error, omission or negligent act of the Contractor's Professional Engineer or anyone employed by the Contractor's Professional Engineer.		
B. Claims-made policies will be accepted for Professional Liability Insurance. All such policies shall have an extended reporting period option or automatic coverage of not less than two (2) years. If available as an option, the Contractor's Professional Engineer shall purchase extended reporting period coverage effective on cancellation or termination of such insurance unless a new policy is secured with a retroactive date, including at least the last policy year.		
[OTHER] Art. 22.1.8		
Engineer's Field Office Section 6.40, Standard Highway Specifications  Fire insurance, extended coverage and vandalism, malicious mischief and burglary, and theft insurance coverage in the amount of \$40,000		
[OTHER]  The Following Additional Insurance Must Be Provided	Art. 22.1.8	
<u>Umbrella/Excess Liability Insurance</u> - The Contractor shall provide Umbrella/Excess Liability Insurance in the minimum amount of \$10,000,000 per Occurrence and \$10,000,000 in Aggregate. The policy terms and condition should be at least as broad as the underlying policies. The underlying policies should comply with the insurance provision as outlined by the contract. Defense cost should be in addition to the limit of liability. The City of New York, including its officials and employees, should be included as additional insured as respects to the noted project.		

# SCHEDULE "A" (GENERAL CONDITIONS TO CONSTRUCTION CONTRACT) (GENERAL CONDITIONS RELATING TO ARTICLE 22 - INSURANCE)

#### PART III. BROKER'S CERTIFICATION

Pursuant to Article 22.3.3 of the **Contract**, every Certificate Of Insurance must be accompanied by either the following certification by the broker setting forth the following text and required information and signatures or certified copies of all policies referenced in the Certificate Of Insurance.

#### **CERTIFICATION BY BROKER**

The undersigned insurance broker represents to the City of New York that the attached Certificate Of Insurance is accurate in all material respects, and that the described insurance is effective as of the date of this Certification.

	[Name Of Broker (Typewritten)]				
	[Address Of Broker (Typewritten)]				
	[E-Mail Address Of Broker (Typewritten)]				
	[Phone Number/Fax Number Of Broker (Typewritten)]				
	[Signature Of Authorized Official Or Broker]				
	[Name And Title Of Authorized Official (Typewritten)]				
State of)					
) ss.: County of)					
Sworn to before me this day of _	, 20				
NOTARY PUBLIC FOR THE STATE O	F				

#### **SCHEDULE "A"**

## (GENERAL CONDITIONS TO CONSTRUCTION CONTRACT)

#### PART IV. ADDRESS OF COMMISSIONER

Wherever reference is made in Article 7 or Article 22 to documents to be sent to the **Commissioner** (e.g., notices, filings, or submissions), such documents shall be sent to the address set forth below or, in the absence of such address, to the **Commissioner's** address as provided elsewhere in this **Contract**.

DDC Director, Insurance Risk Manager				
30 - 30 Thomson Avenue, 4th Floor (IDCNY Building)				
Long Island City, NY 11101				

#### ATTACH TO CONTRACT DOCUMENTS

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION INFRASTRUCTURE DIVISION BUREAU OF DESIGN

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET
BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

#### INCLUDING WATER MAIN WORK

Together With All Work Incidental Thereto BOROUGH OF STATEN ISLAND CITY OF NEW YORK

Al	DDENDUM	NO	٠.	1	
DATED:	Februai	-Y	24	,	2014

THIS ADDENDUM IS HEREBY MADE A PART OF THE CONTRACT DOCUMENTS

The New York City Department of Transportation Standard Highway Specifications, dated November 1, 2010, (which include, but are not limited to, "General Conditions", "Basic Materials of Construction", "Combined Materials of Construction", "Construction Methods", "Inspection and Testing of Materials, Adjustments for Deficiencies, and Maintenance", and "Supplemental Construction Methods"), as modified by addenda issued prior to the opening of bids, shall apply to and become a part of the contract.

All references contained herein are to the New York City Department of Transportation, Standard Highway Specifications, dated November 1, 2010. The said Specifications are hereby revised. Included hereunder are the following REVISIONS:

- 1. Amendments to Standard Highway Specifications, Volume I
- 2. Amendments to Standard Highway Specifications, Volume II, including Section 7.88 (Revised) and new Sections 6.44 PO and 6.52 CG.

1. AMENDMENTS TO STANDARD HIGHWAY SPECIFICATIONS, VOLUME I

The following amendments to the Contract Requirements shall become a part of and apply to the contract:

#### [Added 12-09-2010]

1. Refer to Page 15, Subsection 1.06.23.(C) CONFORMANCE WITH FEDERAL, STATE AND CITY AGENCIES;

Add the following new paragraphs:

"The Contractor is notified that all vehicles that are owned, leased or operated by the Contractor or its subcontractors and used in connection with the Project shall comply with the following requirement:

Every truck, tractor, and tractor-trailer or semitrailer combination, having a gross vehicle weight rating of twenty-six thousand pounds or more, and a conventional cab configuration in which more than half of the engine length is forward of the foremost point of the windshield base, and the steering wheel hub is in the forward quarter of the vehicle length shall be equipped with a convex mirror on the front of such vehicle or combination of vehicles. Such convex mirror shall be adjusted so as to enable the operator of such vehicle or combination of vehicles to see all points on an imaginary horizontal line which is three feet above the road, is one foot directly forward from the midpoint of the front of such vehicle or combination of vehicles, and extends the full width of the front of such vehicle or combination of vehicles.

Any vehicle that does not comply with this provision may be prohibited from entering the Project site and/or supplying equipment or materials to the Project. The Contractor shall not be entitled to any damages as a result of such prohibition."

#### [Added 01-09-2011]

2. Refer to Page 240, Subsection 4.16.5.(B) STUMP REMOVAL;

Delete Subsection 4.16.5.(B) STUMP REMOVAL, in its entirety:
Substitute the following revised Subsection 4.16.5.(B):

#### "(B) STUMP REMOVAL

- 1. Tree stumps designated to be removed and their roots shall be completely excavated to a minimum depth of three (3) feet below the existing grade. A portable stump cutter may be required in some locations. It may be necessary to remove concrete, asphalt, pavers, and/or other types of material surrounding the base of the stump. All excess debris, including chips from tree stumps, shall be removed and disposed of by the Contractor, away from the site prior to backfilling and the area shall be restored by completion of the workday, to the satisfaction of the Engineer. The disposal of tree stumps by burning in open fires will not be permitted.
- 2. All voids and excavations left after the removal of the stump and roots shall be backfilled to grade with clean earth fill. Fill shall be placed and compacted to a minimum of 95 percent of Standard Proctor Maximum Density by acceptable methods to the satisfaction of the Engineer. Where paving blocks exist, they are to be reset to the existing grade as directed.
- 3. Maximum safety and care must be used by Contractor during stump removal. The Contractor shall carefully protect against damage all existing trees, plants, curbs, sidewalks and utilities and other features to remain. The Contractor is responsible for locating and protecting underground utilities from damage during stump removal procedures. During stump grinding operations, plywood must be used to protect adjacent vehicles, real property, and pedestrians. If, when removing stumps, existing sidewalks or curbs are disturbed, the Contractor shall restore and/or reset these sidewalks and curbs, at no additional cost to the City. Restoration work shall be done to match the existing, to the satisfaction of the Engineer. All damaged trees, curbs, sidewalks, real property, vehicles and utilities must be addressed within three (3) days."

# [Added 04-18-2011]

3. Refer to Pages 218 and 219, Subsection 4.13.4.(H) PIGMENT;

Delete the first three (3) paragraphs on page 219:

Substitute the following revised three (3) paragraphs.

"Where the color of the concrete is required to simulate the color of dark gray bluestone, the concrete shall be integrally pigmented to produce a gray color equivalent to: Davis Colors No. 884-3%; Lansco Color No. 437 "Strong Black" 5 lbs. per 94 lbs. Light Grey Portland Cement and 3 parts sand; L.M. Scofield "Cool Black No. 4"; Bayferrox Limestone 330, 2 lbs. per 94 lbs. Light Gray Portland Cement; or an approved equivalent, unless otherwise specified.

Where the color of the concrete is required to simulate the color of light to medium gray granite, the concrete shall be integrally pigmented to produce a gray color equal to: Davis Colors No. 884-1%; Lansco Color No. 437 "Strong Black" 2.5 lbs. per 94 lbs. Light Grey Portland Cement and 3 parts sand; L.M. Scofield "Cool Black No. 1"; Bayferrox Silver 330, 1 lb. per 94 lbs. Light Gray Portland Cement; or an approved equivalent, unless otherwise specified.

Where the sidewalk is designated to have a saw cut joint finish the color of the concrete shall be integrally pigmented to produce a gray color equivalent to L.M. Scofield "Landmarks Grey" K-157-4; L.M. Scofield "Cool Black No. 4"; Davis Colors No. 884-3%; Lansco Color No. 437 "Strong Black" 5 lbs. per 94 lbs. Light Grey Portland Cement and 3 parts sand; Bayferrox NYC Landmark Commission Gray, 3.5 lbs. per 94 lbs. Light Gray Portland Cement; or an approved equivalent, unless otherwise specified."

#### [Added 07-01-2011]

- 4. Refer to Page 14, Subsection 1.06.23.(A) PERMITS;

  Delete line (b) under the first paragraph;

  Substitute the following text:
  - "(b) Any planned work requiring a DOT Construction Permit that may potentially be within 100 feet of a bridge structure will be placed on a Bridge Hold. If any proposed work is within 100 feet of a bridge structure, permittees must submit a scaled drawing showing the work and exact location, along with the following:
    - Plan layout of the project area.
    - The scope of work.
    - The contractor's means and methods.
    - Indicate if work will be done of the bridge itself or its abutments, and the type of work.

If the work is more than 100 feet away from the bridge structure, permittees may send a certification by e-mail stating so. Either response must be sent to the Division of Bridges at bridgeshold@dot.nyc.gov for review and release prior to commencing work. Emergency work will not be placed on hold and shall proceed in accordance with the New York City Highway Rules, section 2-11 (g);

(c) Permits from the Department of Sanitation for use of City landfills;"

#### [Added 07-27-2011]

- 5. Refer to Page 37, Subsection 1.06.46.(A) 6. Sign Graphics;

  Delete article "a." beginning with the words "All visual components of the sign are in an Adobe \*.pdf file, . . ." and ending with the words ". . . DDC to the Contractor (on a CD or via E-mail) for printing.", in its entirety;

  Substitute the following revised article "a":
  - "a. All visual components of the sign are in an Adobe \*.pdf file, which is provided by the Commissioner's representative. The file is not to be altered for composition, type font or image from the version provided by DDC. The Commissioner's representative shall provide a complete file with data and image. The digital file shall be provided by DDC to the Contractor (on a CD or via E-mail) for printing."

#### [Added 09-27-2012]

6. Refer to Page 36, Subsection 1.06.46. Project Sign;

Delete the words "Unless otherwise specified in the Special

Provisions of the contract, the following shall apply:";

Substitute the following revised text:

"The Contractor is notified that he shall be required to furnish, install, maintain, and remove, when directed, Construction Project Information Signs (CPIS) as per Sec. 2-02(c)(4) and (5) of the NYC DOT Highway Rule and the cost shall be deemed included under all scheduled items of the contract. In addition, unless otherwise specified in the Special Provisions of the contract, the following Project Sign shall also apply:"

#### [Added 04-08-2013]

- 7. Refer to Page 200, Subsection 4.11.2.(B), first paragraph, sixth line;

  Delete the word "porcelain,".
- 8. Refer to Page 201, Subsection 4.11.3.(B) FILL AND BACKFILL, second and third paragraphs;

 $\frac{\text{Delete}}{4.11.3.(\text{B})}$ , in their entirety; Substitute the following revised two paragraphs:

"Glass or Recycled Porcelain Aggregate (RPA) from recycling facilities that meets the requirements of **Subsection 4.11.3.(E)** for Glass and **Subsection 4.11.3.(F)** for RPA shall be considered suitable material for mixing with fill provided the Contractor maintains the gradations specified herein. However, glass shall not be placed in contact with synthetic liners, geogrids, geotextiles or other geosynthetics.

Glass and/or RPA incorporated into fill shall be thoroughly mixed with other suitable material so that glass, RPA or combination of both constitutes no more than 30 percent by volume anywhere in the fill as visually determined by the Engineer."

- 9. Refer to Page 202, Subsection 4.11.3.(E) GLASS;
  Add the following new Subsection 4.11.3.(F) RECYCLED PORCELAIN
  AGGREGATE (RPA):
  - "(F) RECYCLED PORCELAIN AGGREGATE (RPA)

All porcelain to be used as RPA shall be crushed by a New York City Department of Environmental Protection (NYCDEP) approved recycling facility to a maximum particle size of 3/8 inch and graded to meet the gradation specified above for use in either fill, backfill or select fill, as may be required. RPA from any other source will not be permitted. The NYCDEP approved recycling facility will also certify that the RPA being furnished is free from organic material and other unsuitable material.

Should the Contractor desire to use RPA in his fill or backfill material, he shall contact Mr. Vasyl Kravchyk at NYCDEP (Tel. No. 718-595-7512) to determine the availability of RPA and from which recycling facility it can be obtained.

The Contractor shall be required to make arrangement with the recycling plant, at least two (2) weeks in advance of when he would need the material, to schedule the time, date and quantity available for pickup. The Contractor shall be required to furnish the recycling facility with a complete list of his trucks involved in transporting the material, which shall include the name of the registered owner (Contractor), Consumer Affairs or DOS Permit numbers, body license plate number, and truck volume. This information must be supplied to the facility prior to the start of picking up the RPA.

Weight ticket receipt slips given by the recycling facility to each truck driver picking up RPA shall be collected by the Contractor and given to the Engineer upon delivering fill or backfill material to the site that contains RPA, and the Contractor agrees and warrants that in obtaining the RPA that such material has originated only from a NYCDEP approved recycling plant and it has not been mixed with porcelain material from any other source.

The Contractor shall be required to transport said material from the approved recycling facility to his yard for storage and mixing with his fill material; however, there is not guarantee that the material will actually be available.

The Contractor is advised that there is no guarantee that RPA will in fact be available for his use from a NYCDEP approved recycling plant and he shall make no claim against the City for loss of anticipated profits should the material not be available upon request by the Contractor.

All excess RPA not used in the fill or backfill shall remain the property of the DDC Contractor.

The Contractor must comply with all rules and regulations of the Department of Transportation and the Department of Environmental Protections governing the use of RPA in its fill and backfill material."

10. Refer to Pages 218 and 219, Subsection 4.13.4.(H) PIGMENTING, first four paragraphs;

"Where pigmenting is specified, the concrete sidewalks shall be pigmented with an admixture complying with the requirements of **Section 2.19** and the following requirements:

'Commercial Gray': In commercial districts C4–4 through C4–7, C5 and C6, as defined in the Zoning Resolution of the City of New York, and in areas under the jurisdiction of the Lower Manhattan Development Corporation the color of the concrete shall be integrally pigmented to produce a gray color equivalent to L.M. Scofield 'Landmarks Grey' K-157-4; L.M. Scofield 'Cool Black No. 4'; Davis Colors No. 884-3%; Lansco Color No. 437 'Strong Black' 5 lbs. per 94 lbs. Light Grey Portland Cement and 3 parts sand; Bayferrox NYC Landmark Commission Gray, 3.5 lbs. per 94 lbs. Light Gray Portland Cement; or an approved equivalent, unless otherwise specified.

'Bluestone': Where the color of the concrete is required to simulate the color of dark gray bluestone, the concrete shall be integrally pigmented to produce a gray color equivalent to: Davis Colors No. 884-3%; Lansco Color No. 437 'Strong Black' 5 lbs. per 94 lbs. Light Grey Portland Cement and 3 parts sand; L.M. Scofield 'Cool Black No. 4'; Bayferrox Limestone 330, 2 lbs. per 94 lbs. Light Gray Portland Cement; or an approved equivalent, unless otherwise specified.

'Granite': Where the color of the concrete is required to simulate the color of light to medium gray granite, the concrete shall be integrally pigmented to produce a gray color equal to: Davis Colors No. 884-1%; Lansco Color No. 437 'Strong Black' 2.5 lbs. per 94 lbs. Light Grey Portland Cement and 3 parts sand; L.M. Scofield 'Cool Black No. 1'; Bayferrox Silver 330, 1 lb. per 94 lbs. Light Gray Portland Cement; or an approved equivalent, unless otherwise specified."

#### [Added 05-24-2013]

- 11. Refer to Page 14, Subsection 1.06.23.(A) PERMITS, first paragraph as modified by Article 4 on page A1-1b;
  Add the following new text:
  - "(d) All necessary permits from the Department of Environmental Protection which may include, but are not limited to, permits for use of City water."
- 12. Refer to Page 14, Subsection 1.06.23.(A) PERMITS, second paragraph;

  Add the following as the third paragraph:

"No fee permits for use of City water necessary to complete roadway pavement reconstruction project in conjunction with installation of sewers and/or water mains, will be issued by the Department of Environmental Protection. However, for all other type projects (such as installation of sidewalks, installation of pedestrian ramps, pavement milling, resurfacing, rehabilitation of retaining walls, and bridge reconstruction type projects) the Contractor will be required to obtain the water use permit at its own cost."

#### [Added 08-05-2013]

- 13. Refer to page 116, second paragraph up from the bottom of the page, first line;
  - <u>Change</u> the words "Concrete of Type IA and IIA shall have ..." to read "Concrete of Type IA, IIA and IIIA shall have ..."

# [Added 09-04-2013]

- 14. Refer to page 100, Subsection 3.01.3.(C)1.(c);
  - <u>Delete</u> the last two lines of text beginning with the words "The proportion of reclaimed asphalt pavement permitted within each mix...";
  - Substitute the following sentence: "The proportion of reclaimed asphalt pavement permitted within each mix shall be not less than 30 percent for the top and bottom courses as per Local Law #71 of 2011."
- 15. Refer to page 110, Subsection 3.05.2.(A), Table 3.05-I; Insert the following text at the bottom of Table 3.05-I:
  - "Note: The above proportions shown for non-High-Early mixes shall be modified by pozzolan substitutes as per **Subsection 3.05.4**."

16. Refer to page 112, Subsection 3.05.3.(C), second paragraph;

Delete the second paragraph in its entirety;

Substitute the following paragraph:

"Water shall be potable and drawn from municipal water mains."

17. Refer to page 113, first line of text, beginning with the words "condition making up one (1) cubic yard of concrete.";

<u>Insert</u> the following sentence between the words "condition making up one (1) cubic yard of concrete." and "The range of water-cement ratio within which the . . .":

"The calculated yield of the mix shall be within ± 2% of the Theoretical (1) cubic yard."

18. Refer to Page 113, second paragraph beginning with the words "The Contractor may substitute Portland cement . . .";

Delete the second paragraph under Subsection 3.05.4., in its entirety;

Substitute the following revised paragraph:

"With the exception of high-early strength concrete, the Contractor shall be required to substitute Portland cement with pozzolans (Fly Ash or GGBFS) such that the maximum amount of Portland cement per cubic yard of concrete does not exceed 400 pounds, and with the use of an approved non-corrosive, non-chloride admixture as required to obtain a minimum compressive strength of 3,000 psi in seven (7) days. For high-early strength concrete the Contractor may substitute Portland cement with pozzolans (Fly Ash or GGBFS), pound for pound, up to 20% (or up to 25% for tidal/sea water spray areas) of the weight of cement specified for any concrete mixture provided the Contractor can obtain a minimum compressive strength of 3,000 p.s.i. in three (3) days. The Contractor, immediately following but not later than eight weeks after the date of the Contractor's Notice to Proceed, shall file with the Engineer, Age-Strength data of the job mix he proposes to use for the various ambient temperatures anticipated during the period of concrete placement. This data shall be presented in both tabular and graphical form for those various ambient temperatures with a maximum setting period of seven (7) days for Class B-32 concrete or seventy-two (72) hours for High-Early Strength Concrete."

- 19. Refer to Page 115, TABLE 3.05-III INGREDIENT MATERIALS;

  Change in the third row, second column, the type of Portland

  Cement from "Type III\*" to read "Type II or Type III\*"
- 20. Refer to page 132, Subsection 3.06.3.(D);

  Change the words "Water shall be drawn from mains owned by The City of New York." to read "Water shall be potable and drawn from municipal water mains."
- 21. Refer to page 133, Subsection 3.07.3.(D);

  Change the words "Water shall be drawn from mains owned by or supplying water to The City of New York." to read "Water shall be potable and drawn from municipal water mains."
- 22. Refer to page 134, Subsection 3.08.4.(D);

  Change the words "Water shall be drawn from mains owned by or supplying water to The City of New York." to read "Water shall be potable and drawn from municipal water mains."

- 23. Refer to Page 166, Subsection 4.05.2.(A);

  Delete Subsection 4.05.2.(A), in their entirety;

  Substitute the following revised Subsection 4.05.2.(A):
- "(A) Concrete Pavement shall be of the following types:

Type 1--Non-reinforced

Type 2--Reinforced (Unpigmented or pigmented if specified)

Type 3--High Early Strength Reinforced (Unpigmented or pigmented if specified)

Type 2 and Type 3 pavements shall consist of a concrete surface course, which shall be unpigmented or pigmented if specified, laid on a concrete base course, which may or may not be pigmented at the Contractor's option, while the base course is still plastic, of the thickness shown on the Contract Drawings, with reinforcement placed between the surface and base courses."

```
24. Refer to Page 166, Subsection 4.05.3.(A);
Insert the following new Subsection 4.05.3.(A1):

"(A1) PIGMENTING
```

Where pigmenting is specified, the surface course of the concrete bus pad shall be pigmented with an admixture complying with Section 2.19 and the following requirements:

Where the color of the concrete is required to simulate the red color of the Red Bus Lane Pavement Overlay (Item 6.44 POR in Section 6.44 PO), the surface course concrete shall be integrally pigmented to produce a red color equivalent to Scofield's quarry red.

Except for the use of an air-entraining agent complying with ASTM Designation C 260 and water reducing admixtures complying with ASTM Designation C 494 used in combination with the Pigment Admixture as per the pigment manufacturer's instruction, no other admixtures (including, but not limited to, calcium chloride) shall be used unless stated in writing by the manufacturer of the Pigment Admixture to be of no consequence to the colorfastness of the concrete mixture and is approved by the Engineer.

All pigmented concrete at different locations shall be identical, unless otherwise directed. Variations in color/tint/hue will not be acceptable. Therefore, the same brand and type of cement and the same source and type of aggregate shall be used throughout the project.

Prior to the mix design being made, the cement intended for use shall be checked to determine that its lightness/darkness is similar to the cement used in the original approved sample. The Pigmented Admixture shall be added in the standard proportion specified by the manufacturer."

```
25. Refer to Page 170, Subsection 4.05.5.(A) GENERAL;

Insert the following two new paragraphs:
```

"For pigmented concrete, the Contractor shall within eight weeks of the notice to proceed, submit the name of its proposed roadway installer upon which his bid is based, along with their respective work history experience in placing pigmented concrete. The installer shall have documented experience in working with pigmented concrete.

Prior to making any field samples and the placing of any pigmented concrete, the Contractor, its concrete supplier, installer, cement producer, laboratory, the pigmented admixture's representative, and the Engineer shall meet and agree on the specifications and methods of handling the pigmented concrete."

- 26. Refer to Page 183, Subsection 4.05.9. PRICES TO COVER, 4<sup>th</sup> line; Insert in the fourth line, the words "pigment when specified" between the words "specifications, including, but not limited to," and "furnishing and installing...":
- 27. Refer to Page 183, Subsection 4.05.9. PRICES TO COVER;

  Insert the following two new Items to the list of Item Nos. at the bottom of Subsection 4.05.9:
- "4.05 ACP REINFORCED CONCETE PAVEMENT (BUS STOPS)(PIGMENTED) C.Y.
- 4.05 AXP HIGH-EARLY STRENGTH REINFORCED CONCRETE PAVEMENT (BUS STOPS)(PIGMENTED) C.Y."

AMENDMENTS TO STANDARD HIGHWAY SPECIFICATIONS, VOLUME II

#### [Added 01-25-2012]

Refer to Pages 365 and 366, Subsection 6.40.2.(C)(c)(1) Personal Computer(s) - Workstation Configuration;

Delete the text under Subsections (a), (b), (c), (d), (h), (i), and (m), in their entirety; Substitute the following revised text:

> "(a) Make and Model:

Dell; HP; Gateway; Acer; or, an approved equivalent. (Note: an approved equivalent requires written approval of the Assistant

Commissioner of ITS.)

(b) Processor: i5-2400 (6MB Cache, 3.1GHz) or faster computer - Single Processor.

(c) System Ram: Minimum of 4GB (Gigabytes) Dual

Channel DDR3 SDRAM at 1333MHz - 2 DIMMSs.

(d) Hard Disk Drive(s): 500 GB (Gigabytes) Serial ATA (7200RPM) w/DataBurst Cache, or

larger."

"(h) Video Display Card: HD Graphics (VGA, HDMI) with a

minimum of 64 MB of RAM.

(i) Monitor: 22" W, 23.0 Inch VIS, Widescreen,

VGA/DVI LCD Monitor."

"(m) Software Requirements: Microsoft Windows 7 Professional

SP1, 64 bit: Microsoft Office Professional 2010; Microsoft Project 2010; Adobe Acrobat reader: Anti-Virus software package with 2 year updates subscription; and, either Auto Cad 2012 LT or Microsoft Visio 2010 Standard Edition, as directed by

the Engineer."

Refer to Page 366, Subsection 6.40.2.(C)(c)(2)(b); Delete the text under Subsection (b), which begins with the words "(b) One (1) 600 DPI HP Laser Jet . . ", in its entirety; Substitute the following revised text:

> One (1) 600 DPI HP Color Laser Jet all-in-one "(b) Printer/Scanner/Copier/Fax (twelve (12) pages per minute or faster) with one (1) Extra Paper Tray (Legal Size) networked to all office computers."

3. Refer to Page 367, Subsection 6.40.3. SPECIFIC REQUIREMENTS FOR ENGINEERS FIELD OFFICE (TYPE A, B, C, CU, D OR DU), first paragraph;

Delete the text in the first paragraph of Subsection 6.40.3., in

Delete the text in the first paragraph of Subsection 6.40.3., in its entirety;

Substitute the following revised text:

6.40.3. SPECIFIC REQUIREMENTS FOR ENGINEER'S FIELD OFFICE (TYPE A, B, C, CU, D, OR DU). In addition to the general requirements, each type of Field Office shall have the minimum floor area indicated in Table 6.40-I calculated based on usable area only, excluding any loss factors. Loss factors are defined as those areas such as lobby, sidewalk window ledge, elevator shafts and stairways. The Contractor shall provide and maintain furnishings for each type of Field Office in the quantity specified in Table 6.40-I. The furnishings shall be new or used equipment satisfactory to the Engineer:

Refer to Page 368, TABLE 6.40-I, ADDITIONAL REQUIREMENTS;  Delete the requirements for a Photocopy Machine shows of TABLE 6.40-I, in its entirety;  Substitute the following revised requirements:		
Photocopying Machine – Stand-alone, heavy duty, electric, dry-process color photocopying type with a minimum production rate of 70 pages per minute and an adequate supply of sopy paper, toner, etc. The machine shall be capable of duplex copying paper sizes of 8-1/2 x 11 inches, 8-1/2 x 14 inches and 11 x 17 inches, and have separate trays for each paper size. It shall have a document feeder, collator, stapler, and the capability to reduce/enlarge copies between each paper size. The supply of each size copy paper, toner, etc. shall be replenished and the machines shall be maintained for the duration of the contract by the Contractor as required by the Engineer. Make and model can be Minolta, Canon, IBM, Epson, or an approved equivalent, and shall be networked to the office computers.	1 1	1 1

5. Refer to Page 368, TABLE 6.40-I, ADDITIONAL REQUIREMENTS SPECIFIC REQUIREMENTS;

Insert the following two additional requirements:

Heavy duty commercial grade diamond cut shredder with automatic start. The shredder shall be able to receive 8-1/2 inch wide paper and shred a minimum of 15 sheets simultaneously along with CDs and staples.	1	1	1	1	1	1
Projector – 1080p LCD with a min. of 2200 ANSI Lumins, 1920 x 1080, 16:9, 40,000:1 contrast ratio, HDMI, VGA, USB, and a 10 feet diagonal, 16:9 Projection Screen.	-	-	1	1	1	1

6. Refer to Page 496, Subsection 7.20.4. METHODS, last paragraph beginning with the words "When directed by the Engineer, due to the original conditions . . .";

Add the following sentence to the end of the last paragraph under Subsection 7.20.4:

"However, if the owner at his own expense supplies the replacement frame and doors or hatch covers the Contractor shall install the replacement frame and doors or hatch covers under this Item 7.20, as a basement access reset, in lieu of the steel safety closure plate."

#### [Added 07-16-2012]

7. Refer to Page 365, Subsection 6.40.2.(C)(c)(1) "Personal Computer(s) - Workstation Configuration";

Delete the text under Subsections (g) and (k), in their entirety;
Substitute the following revised text:

"(g) I/O Ports:

Must have at least one (1) Serial

Port, one (1) Parallel Port, and

three (3) USB Ports.

(k) Network Interface:

Integrated 10/100/1000 Ethernet

card."

- 8. Refer to Page 366, Subsection 6.40.2.(C)(c)(2) "All field offices requiring computers shall be provided with the following:";

  Delete the text under Subsection (a), in its entirety;
  Substitute the following revised text:
  - "(a) One (1) broad-band internet service account. Wideband Internet connectivity at a minimum throughput of 15 Mbps download and 5 Mbps upload is required at each field office location with 1-5 staffers. For larger field offices see table below for minimum required upload speeds. Telephone service should be bundled together with Internet connectivity. Because of throughput requirements Verizon FIOS is the preferred connectivity provider where available.

Office Personnel #	Upload Speeds (Minimum)
1 - 5	5 Mbps
6 - 10	10 Mbps
11 - 15	15 Mbps
16 - 20	20 Mbps

This account will be active for the life of the project. The e-mail name for the account shall be the DDC Field Office/project Id (e.g. FLD K HWK666 McGuinness@earthlink.com)."

#### [Added 08-09-2012]

- Refer to Page 366, Subsection 6.40.2.(C)(c)(b), as amended by Article 2 on page A1-2 of this Addendum; Delete the text under Subsection (b), in its entirety; Substitute the following words: "(b) (No Text)."
- 10. Refer to Page 368, TABLE 6.40-I, ADDITIONAL REQUIREMENTS SPECIFIC REQUIREMENTS; Delete the requirements for a Photocopy Machine shown in the 15th

row of TABLE 6.40-I, as modified by Article 4 on page Al-2a of

this Addendum, in its entirety;

Substitute the following revised requirements:

Photocopying Machine – Stand-alone, heavy duty, electric, dry-process color photocopying type with color scan and send capability via e-mail, a minimum production rate of 70 pages per minute and an adequate supply of copy paper, toner, etc. The machine shall be capable of duplex copying paper sizes of 8-1/2 x 11 inches, 8-1/2 x 14 inches and 11 x 17 inches, and have separate trays for each paper size. It shall have a document feeder, collator, stapler, and the capability to reduce/enlarge copies between each paper size. The supply of each size copy paper, toner, etc. shall be replenished and the machines shall be	1	1	1	1	1	1
paper, toner, etc. shall be replenished and the machines shall be maintained for the duration of the contract by the Contractor as required by the Engineer. Make and model can be Minolta,						
Canon, IBM, Epson, or an approved equivalent, and shall be networked to the office computers.						

#### [Added 11-26-2012]

11. Refer to Pages 504 through 508, SECTION 7.88 - Rodent and Waterbug Pest Control;

Delete Section 7.88, in its entirety;

Substitute SECTION 7.88 (Revised), as contained on the following pages A1-2d through A1-2i.

[Added 02-08-2013]

12. (NO TEXT)

# SECTION 7.88 (Revised) Rodent and Waterbug Pest Control

- **7.88.1. DESCRIPTION.** The Contractor shall provide all labor, materials, plant and equipment, and incidentals required to survey and monitor rodent activity and control any infestation or outbreak of rodents and waterbugs (American cockroaches) within the project limit.
- **7.88.2. MATERIALS.** All materials shall be approved by the New York State Department of Environmental Conservation and comply with the New York City Health Code for the intended usage.

Rodenticide weatherproof bait blocks shall be multiple dose anticoagulants such as Chlorophacinone or Dephacinone, or single feed rodenticides such as ContraMeal, ContracBait block, Quintox pellets or TalonG pellets, or an approved equivalent.

Tamper proof bait station boxes shall be designed to exclude other mammals and shall be used with poisoned bait to attract rats. Information on "tamper proof bait station boxes" is available from the NYC Bureau of Regulatory & Environmental Health Services, Pest Control Office (718-956-7103/4).

Live traps shall be of proper dimensions for trapping rats and shall <u>not</u> be used with poisoned bait.

Insecticide bait shall be a residual type such as phenol methyl carbamate (2%) bait or an approved equivalent.

# (A) SUBMITTALS

Prior to commencement of construction activities the Contractor shall submit to the Engineer manufacturer's installation instructions for all materials required for rodent and waterbug pest control work and product data which shall include illustrations, catalog data, product characteristics, typical use, performance, and limitation criteria of all rodent and waterbug pest control materials required.

- **7.88.3. PERSONNEL.** The Contractor shall employ two independent licensed exterminators: one to engage in survey and monitoring work to establish the level of infestation of rodents and insects and provide recommendations for specific Integrated Pest Management (IPM) actions, and one to execute the rodent and waterbug pest control work to deal with such infestations. All pest control personnel employed by each exterminator company must be supervised by an exterminator licensed in categories 7A & 8. The Contractor shall submit the names and license credentials of the two exterminator companies to the Engineer for approval prior to the commencement of any work under this section.
- **7.88.4. METHODS.** Application and dosage of all materials shall be done in strict compliance with the manufacturer's recommendations. All surveying, monitoring, baiting, and/or live trapping work shall be performed in the presence of the Engineer, without which no payment will be made under this Section.

## (A) GENERAL

The Contractor's construction activity is expected to disturb any established rodent and/or waterbug population that may exist within the project limits, possibly causing their dispersion. The Contractor shall take all appropriate action to eliminate and/or control these populations within the construction corridor: the construction corridor shall be defined as being the full width of streets under the contract and intersecting streets up to the limits of construction, from property line to property line, excluding buildings and under sidewalk building vaults.

Under the Maintenance of Site requirements for the contract, any unsanitary conditions, such as uncollected garbage or debris, resulting from the Contractor's activities which will provide food and shelter to the resident rodent population shall be corrected by the Contractor immediately after notification of such condition by the Engineer. Non-compliance shall be subject to the application of the "Nonconformance" provisions of the Item for Maintenance of Site, and no payment will be made for any additional application of rodenticide or insecticide needed to control resultant infestations.

# (B) SURVEY AND MONITORING WORK

- (1) Prior to Construction The Contractor's designated survey and monitoring exterminator shall execute a survey of the project area and estimate the level of rodent (Norway rat, House mouse) infestation and the waterbug population within the construction corridor. An appropriate sample of utility manholes (sewer, electrical, telephone, etc.) and catch basins should be opened and surveyed to the satisfaction of the Engineer. Contractor shall maintain all survey records in the manner described in 7.88.6., Records and Reports.
- (2) <u>During Construction</u> The Contractor shall monitor the rodent activity through trapping (snap, glue traps or live traps), fecal count methods, and inspection of the conditions of all installed baits every week during construction activity or as otherwise directed by the Engineer. Contractor shall maintain all monitoring records in the manner described in 7.88.6., Records and Reports.

# (C) RODENT CONTROL WORK

- (1) Wetlands, Woodlands and Areas Within Seventy-five (75') feet of a Stream. In wetlands, woodlands and areas adjacent to a stream, special precautions must be taken to protect water quality and to ensure the safety of other wildlife. To prevent poisoned bait from entering streams, no poisoned bait shall be used in areas within seventy-five (75') feet of either streambank. Live traps must be used in these seventy-five (75') feet buffer zone areas and within wetland and woodland areas.
- (2) Outside Wetland Areas, Woodland Areas and Beyond Seventy-five (75') feet of a Stream. In areas outside the seventy-five foot zone of protection adjacent to streams, and areas outside wetlands and woodlands, tamper proof bait stations with poisoned bait shall be established during the period of construction and any consumed or decomposed bait shall be replenished as directed.

Rodent control shall be achieved in two stages as follows:

Stage I. At least one month prior to initiation of the construction work, and periodically thereafter, live traps and/or rodenticide bait, as directed above, shall be placed at locations [e.g., burrows, utility manholes (sewer, electrical, phone, etc.), and catch basins] that are inaccessible to pets, human beings, children and other non-target species, particularly wildlife (e.g., birds) in the construction corridor. Locations of initial bait placement and quantities of bait shall be determined by the survey and monitoring exterminator's written report of his survey and monitoring results, or as otherwise directed by the Engineer.

Stage II. <u>During Construction</u> - Infested sites as determined by the survey and monitoring exterminator's monitoring report shall be baited and/or rebaited, and live traps shall be collected and replaced, the rates and quantities of which shall be determined by the written monitoring reports submitted weekly or as otherwise directed by the Engineer in consultation with the City's Office of Pest Control.

The baiting exterminator shall be responsible for collecting and disposing of all trapped and poisoned rodents found in live traps and tamper proof bait stations. The baiting exterminator shall also be responsible for posting and maintaining signs announcing the baiting of each particular location.

The Contractor, under his maintenance of site operations, shall be responsible for the immediate collection and disposal of any visible rodent remains found on streets or sidewalk within the project limits. Any visible remains shall be placed into double plastic bags. No more than five (5) carcasses shall be placed into each bag. Each bag shall be a minimum of 3 mils thick, black plastic. No additional payment will be made for this work.

It is anticipated that public complaints will be addressed to the Engineer's Field Office. The Contractor, where directed by the Engineer, shall take appropriate Integrated Pest Management (IPM) actions, such as baiting, trapping, proofing, etc., to remedy the source of a complaint within the next six (6) hours of normal working time, which is defined herein, for the purposes of this section, as 7 A.M. to 6 P.M. on Mondays through Saturdays.

# (D) WATERBUG (AMERICAN COCKROACH) CONTROL

Infested sites (e.g., sewers) shall be baited at least 2 times per month with insecticides, or as directed by the Engineer in consultation with the exterminator monitoring the work and the City's Office of Pest Control.

**7.88.5. EDUCATION & TRAINING.** The Contractor shall post notices in all Construction Bulletin Boards advising workers, employees, and residents to call the Engineer's Field Office to report rodent and waterbug infestations. The Contractor shall provide and distribute literature pertaining to IPM techniques of rodent control to affected businesses and superintendents of nearby residential buildings to ensure their participation in maintaining their establishments free of unsanitary conditions, harborage removal and rodent proofing.

Prior to application of any chemicals, the Contractor shall furnish copies or sample labels for each pesticide, antidote information, and Material Data Safety Sheets (MSDS) for each chemical used.

#### 7.88.6. RECORDS AND REPORTS.

# (A) GENERAL

The Contractor shall be responsible for assigning within the construction corridor an identifying number to each manhole, catch basin, and other location where bait and/or live trap placement and/or waterbug control work is proposed by the survey and monitoring exterminator. The Contractor shall then provide that list of locations and corresponding reference numbers along with a drawing showing the locations, as a reference for the exterminator(s) performing the work, to indicate locations of bait placement and waterbug control work and rodent and waterbug activity (droppings, bait consumed, dead rodents, etc.).

# (B) SURVEY AND MONITORING WORK

- (1) Prior to Construction Contractor shall submit to the Engineer, for approval, a written survey report including proposed IPM procedures, including specific materials, quantities, locations, methods, and time schedule for the implementation of the exterminating work. The written report shall also include a survey with a drawing (provided by the Contractor) marked with locations indicating all signs of rodent (Norway rat, House mouse) infestation and waterbug activity discovered during the execution of the survey indicating that rodent and waterbug pest control work is necessary.
- (2) <u>During Construction</u> Based on monitoring results, Contractor shall submit to the Engineer a weekly written monitoring report identifying all locations and conditions of installed bait and/or other rodent control work. The monitoring report shall also include any other recommended IPM techniques, such as baiting, trapping, proofing, etc., proposed for rodent and waterbug pest control.

The survey and monitoring exterminator shall keep a record of all rodent and waterbug infestation surveys s/he has conducted. The Contractor shall be required to submit a copy of all survey and monitoring reports to the Engineer each week, prior to payment.

# (C) RODENT AND WATERBUG CONTROL WORK

The baiting exterminator shall maintain records of all locations baited along with the type and quantity of rodenticide and insecticide bait used. These records will be kept by the City Inspector. A weekly report shall be prepared, signed and certified by the approved licensed exterminator, and such reports shall be submitted to the Engineer each week, prior to payment.

**7.88.7. NONCONFORMANCE.** If the Contractor fails to perform as directed to control the rodent and/or waterbug population at any location within the project limits for a period of more than one week, the Engineer will correct the adverse conditions by any means he deems appropriate, including but not limited to, the use of "outside services" and shall deduct the cost of the corrective work from any monies due to the Contractor. The deducted cost of this work shall be in addition to the non-payment for rodent and waterbug pest control.

#### 7.88.8. MEASUREMENT.

## (A) RODENT INFESTATION SURVEY AND MONITORING

The quantity to be measured for payment under Item No. 7.88 AA, RODENT INFESTATION SURVEY AND MONITORING, shall be a Lump Sum measurement.

# (B) RODENT BAIT STATIONS

The quantity to be measured for payment under Item No. 7.88 AB, RODENT BAIT STATIONS, shall be the number of tamper-proof rodent bait station boxes and/or live traps satisfactorily installed or reinstalled after inspection within the construction corridor, as approved by the Engineer. However, the initial baiting, and subsequent rebaiting as may be required, of any bait station will be paid for under Item 7.88 AC.

# (C) BAITING OF RODENT BAIT STATIONS

The quantity to be measured for payment under Item No. 7.88 AC, BAITING OF RODENT BAIT STATIONS, shall be the number of tamper-proof rodent bait station boxes, utility manholes, catch basins, or other locations approved by the Engineer, satisfactorily baited or rebaited to replenish consumed or decomposed bait within the construction corridor, as approved by the Engineer.

# (D) WATERBUG BAIT APPLICATION

The quantity to be measured for payment under Item No. 7.88 AD, WATERBUG BAIT APPLICATIONS, shall be the number of blocks satisfactorily treated with insecticide bait within the construction corridor, as approved by the Engineer. A block shall be defined as the area of street, measured between property lines, from intersection to intersection. Each rebaiting of any block shall be considered as a new block for measurement purposes.

#### 7.88.9. PRICES TO COVER.

#### (A) RODENT INFESTATION SURVEY AND MONITORING

Payment will be made at the lump sum price bid for RODENT INFESTATION SURVEY AND MONITORING which shall include the cost of furnishing all the labor, materials, plant, equipment (traps, etc.), insurance, and other incidentals required, including but not limited to providing all required maintenance of traffic equipment, to perform a rodent infestation survey of the project area and then monitor the site each week for rodent activity, all in accordance with the specifications and the directions of the Engineer.

Ten (10%) percent of the lump sum price bid will be paid when the initial survey of the project area has been completed and the written survey report has been submitted to the satisfaction of the Engineer. The remainder will be paid in proportion to the percentage of contract completion.

# (B) RODENT BAIT STATIONS

The Contract price bid for RODENT BAIT STATIONS shall be a unit price per each tamper proof bait station box and/ or live trap installed or reinstalled after inspection and shall cover the cost of furnishing all labor, materials, plant, equipment (bait stations, etc.), insurance, and other incidentals, including but not limited to providing all required maintenance of traffic equipment, required to control the rodent population found within the project limits in accordance with the specifications and the directions of the Engineer.

In addition to the payment for Rodent Bait Stations installed or reinstalled under this Item 7.88 AB, the Contractor will also be paid for each baiting or rebaiting, when required, of each bait station, under Item No. 7.88 AC.

# (C) BAITING OF RODENT BAIT STATIONS

The Contract price bid for BAITING OF RODENT BAIT STATIONS shall be a unit price per each bait station, utility manhole, catch basin or other location approved by the Engineer satisfactorily baited or rebaited, when required, and shall cover the cost of furnishing all labor, materials, plant, equipment (bait), insurance, and other incidentals, in accordance with the specifications and directions of the Engineer. Installation or resetting of the bait station will be paid for under Item 7.88 AB.

# (D) WATERBUG BAIT APPLICATION

The Contract price bid for WATERBUG BAIT APPLICATION shall be a unit price per block treated by the exterminator and shall include the cost of furnishing all the labor, materials, plant, equipment (bait, etc.), insurance, and other incidentals, including but not limited to providing all required maintenance of traffic equipment, necessary to control the waterbug population found within the project limits for the duration of the contract in accordance with the specifications and the directions of the Engineer.

#### Payment will be made under:

7.88 AC BAITING OF RODENT BAIT STATIONS EACH	Item No.	Item	Pay Unit
7.88 AD WATERBUG BATT APPLICATION BLOCK	7.88 AB	RODENT BAIT STATIONS	L.S. EACH EACH BLOCK

#### [Added 05-24-2013]

- 13. Refer to Page 366, Subsection 6.40.2.(C)(c)(1)(m) Software
  Requirements, as modified by Article 1 on page A1-2;
  Delete the text under Subsection (m), in its entirety;
  Substitute the following revised text:
  - "(m) Software Requirements: Microsoft Windows 7 Professional SP1, 32 bit; Microsoft Office Professional 2010; Microsoft Project 2010; Adobe Acrobat reader; Anti-Virus software package with 2 year updates subscription; and, either Auto Cad LT or Microsoft Visio Standard Edition, as directed by the Engineer."

#### [Added 09-04-2013]

14. Refer to Page 384, the end of Section 6.44 - White and Yellow Thermoplastic Reflectorized Pavement Markings;

Insert new SECTION 6.44 PO, after Section 6.44, as contained on the following pages A1-2k through A1-2m.

#### [Added 02-10-2014]

15. Refer to Pages 393 and 394, SECTION 6.52 - Uniformed Full-Time Flagperson;

Delete Section 6.52 on pages 393 and 394, but do not delete examples on pages 395 and 396;

<u>Substitute</u> SECTION 6.52 CG, as contained on the following pages A1-2n and A1-2o.

# SECTION 6.44 PO Lane Pavement Overlay

**6.44PO.1. DESCRIPTION.** This section describes the furnishing and application of an approved Green Asphalt Pavement Color Scheme along designated bicycle lanes and Brick-Red Asphalt Pavement Color Scheme matching Quest's StreetBondCL Terracotta color along designated Select Bus Service (SBS) lanes, as indicated in the Contract Drawings or as directed by the Engineer.

# 6.44PO.2. <u>REFERENCES</u>.

- A. ASTM D-4541 Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Tester.
- B. ASTM D-4060 Test Method for Abrasion Resistance of Organic Coatings by the Taber Abrasion.
- C. ASTM D-522-93A Standard Test Method for Mandrel Bend Test of Attached Organic Coatings.
- D. ASTM G-155 QUV Accelerated Weathering Environment. Standard Practice for Operating Fluorescent Light Apparatus for UV Exposure of Nonmetallic Materials.
- E. ASTM D-2486 MEK rub test for chemical resistance.
- F. ASTM D-570 Standard Test Method for water absorption of plastics.
- G. ASTM E-303 British Pendulum test for friction.
- H. EPA 24 ASTM D3960-05 Volatile Organic Compounds.

# 6.44PO.3. SUBMITTALS.

- A. A copy of the current year accreditation certificate available from the Contractor or subcontractor who will be performing this work, or written verification from the coating supplier that the Contractor or subcontractor is qualified to perform this Work.
- B. Written and published specification for the application of the selected asphalt pavement coating.
- C. Confirmation of coating color.
- D. Proof of coating performance through a Certificate of Analysis or equivalent document as provided by the Contractor or the coating supplier.

# 6.44PO.4. MATERIALS.

The following table outlines minimum performance properties of a typical asphalt pavement coating.

Characteristic	Test Specification	Measured result
Durability: Taber Abrasion resistance	ASTM D-4060 7 day cure, H-10 wheel (wet test)	< 5.0 g/1000
Water sensitivity	ASTM D-570 Water absorption after 9 days: Remaining absorption after 1 hour of recovery:	< 10% < 1.0%
Color stability	ASTM G-155 QUV 2,000 hours (CIE units)	New York City Bike Lane Green ΔE < 1.5
Color stability	ASTM G-155 QUV 2,000 hours (CIE units)	Brick color ΔE < 1.5

Flexibility: Mandrel Bend	ASTM D-522-93A Flexibility as measured by Mandre 0.5mm thick sample passes 10 mm at 21°C 0.5mm thick sample passes 125mm at -18°C	l bend
Chemical resistance	ASTM D-2486 Modified MEK scrubs 16 dry mils, number of scrubs until 50% substrate exposed	>5000
Adhesion to Asphalt	ASTM D-4541	Substrate Failure
Friction Wet	ASTM E-303 British Pendulum Tester	>55
Environmental Sensitivity	EPA 24 ASTM D-3960-05 Volatile Organic Compounds	VOC < 150

These properties shall be evidenced by Certificates of Analysis produced by an independent qualified testing facility.

Green Bicycle and Red Bus Lane Pavement Overlays furnished by the following manufacturers, or approved equivalent, are acceptable for use in this contract:

Ennis Paint, Inc. 1509 S. Kaufman Street Ennis, TX 75119

Integrated Pavement Concepts, Inc. 102-17957 55th Avenue Surrey, BC Canada V3S 6C4

Crafco, Inc. 420 N. Roosevelt Avenue Chandler, AZ 85226

**6.44PO.5. METHODS.** The asphalt pavement coating system shall be applied to the pavement in accordance with the manufacturer's specification. In its hardened state the color shall be as specified, and as approved by the Engineer. The material shall present a marking whose color and chemical resistance will not degrade under normal exposure to calcium chloride, sodium chloride or automotive oils and fuels. Color pigments used shall remain stable under exposure to ultra violet light. A minimum of four (4) layers of coating material shall be applied to the pavement surface.

The Contractor shall be required to use the proper equipment in the application of the asphalt pavement coating, as per the recommendation of the coating supplier, and as approved by the Engineer.

Asphalt pavement must be stable, well compacted and generally in excellent condition for the application of the asphalt pavement coating to be successful. The Engineer shall make the final determination as to the suitability of the existing asphalt pavement.

The asphalt pavement surface shall be dry and free from all foreign matter, including but not limited to dirt, dust, de-icing materials, and chemical residue.

The asphalt pavement coating shall only be applied in the correct environmental conditions as instructed by the coating supplier, and as approved by the Engineer.

Refer to the instructions provided by the coating supplier regarding when the painted lane may be opened to traffic. Wait time is typically a function of the dry rate of the coating, and climate conditions.

The Engineer may, at his discretion, require the Contractor to remove all extraneous marks on the pavement made by the agents or employees of the Contractor, or made by others due to improper control or protection of the work area by the Contractor, his agents or employees. Any installation which, in the opinion of the Engineer, is not acceptable, whether by reason of poor workmanship, poor appearance, poor performance, poor materials, improper width or improper alignment, shall be reworked by the Contractor at no cost to the City. The Contractor shall replace rejected installation as directed by the Engineer, within fifteen (15) days after receiving written notification of the rejection of such completed work.

**6.44PO.6. MEASUREMENT.** The quantities to be measured for payment shall be the number of square yards of Lane Pavement Overlay, of each color, placed as specified to the satisfaction of the Engineer.

**6.44PO.7.** PRICES TO COVER. The unit prices bid per square yard of Green Bicycle Lane Pavement Overlay and Red Bus Lane Pavement Overlay shall cover the cost of all labor, materials, plant, equipment, insurance, and necessary incidentals required including, but not limited to, testing, cleaning, preparation of surfaces, and application of the lane pavement overlay materials, all in accordance with the contract plans and specifications, and as directed by the Engineer.

# Payment will be made under:

Item No.	Heli Item	Pay Unit
6.44 POG	GREEN BICYCLE LANE PAVEMENT OVERLAY	S.Y.
6.44 POR	RED BUS LANE PAVEMENT OVERLAY	S.Y.

# SECTION 6.52 CG Crossing Guard

- **6.52CG.1. INTENT.** This section describes the employment of full-time uniformed crossing guards to direct and detour traffic.
- **6.52CG.2. DESCRIPTION.** The Contractor shall furnish an adequate number of competent crossing guards to control vehicular and pedestrian traffic when it is necessary to maintain alternating one-way traffic in one lane of a two-way roadway, and at all other locations where construction operations, construction vehicles and equipment, and temporary traffic patterns related to the construction operations require positive temporary traffic control for safe, efficient traffic operations.
- **6.52CG.3. METHODS.** All crossing guards, whether paid for under this item or not, shall be proficient in speaking, writing and reading English and adequately trained, as approved by the Engineer, in controlling vehicular and pedestrian traffic at construction sites.

All crossing guards, whether paid for under this item or not, their apparel, hand-signaling devices, and active two-way radios shall be appropriate for use at roadway construction sites as approved by the Engineer.

Prior to the start of crossing guard operations, the Contractor shall provide to the Engineer a list of crossing guards to be used in the contract, identifying the source of crossing guard training for each individual. When requested by the Engineer, crossing guards shall demonstrate their competency in crossing guard procedures. Crossing guards not competent in controlling vehicular and pedestrian traffic procedures to the satisfaction of the Engineer shall be retrained or replaced at once. Each crossing guard paid under this item must be a full-time crossing guard. If any worker performing services under this item is also assigned the task of directing construction equipment (as per attached Example #2, worker acting as a flagperson 'A') or any laborer tasks, then such worker shall be deemed to be subject to the provisions of Labor Law §220 Prevailing Wage Schedule and will not be paid for under this Item.

- **6.52CG.4. MEASUREMENT**. The quantity to be measured for payment shall be the number of person-hours of uniformed crossing guard service actually performed, as authorized by the Engineer. Laborers who are not full-time crossing guard will not be measured for payment as crossing guards under this or any other item. Each uniformed crossing guard shall be required to work a minimum of eight (8) hours a day and the Contractor will be given a minimum of twelve (12) hours advanced notice by the Engineer as to when to furnish a crossing guard.
- **6.52CG.5. PRICE TO COVER.** The contract price per person-hour shall cover the cost of all labor, materials, equipment, and insurance necessary to employ a uniformed full-time crossing guard, and equip him/her with safety vests, hard hats, and signaling devices, including all other incidental costs necessary to control and detour traffic, as shown on the Contract Drawings, the Examples #1 and #2 on pages 395 and 396 (excluding worker acting as a flagperson "A" in Example #2), or as directed by the Engineer.

Payment for flagperson "A" in Example #2, shall be deemed to be included under other items of work, as appropriate.

Where there is no scheduled item for Crossing Guard, the cost of furnishing Crossing Guards as required shall be deemed included in the unit price bid for the Maintenance and Protection of Traffic item.

Payment will be made under:

Item No.

Item

Pay Unit

6.52 CG

**CROSSING GUARD** 

PERSON-HOUR (P/HR)

#### [Added 02-24-2014]

16. Refer to PageS 480 and 481, Subsection 7.13.2.(B) MAINTENANCE OF STREETS, 4<sup>th</sup> paragraph, beginning with the words "The Contractor shall maintain the traveled way . . .;

Delete the 4<sup>th</sup> paragraph, in its entirety;
Substitute the following text:

"The Contractor shall maintain the traveled way in such a condition and conduct operations in such a manner that snow and ice may be readily removed by others as and when necessary, and in such a manner that proper drainage is provided for the melting of snow in the banks resulting from normal plowing. However, the Contractor will not be responsible for snow or ice removal on the pavement or traveled way opened for public usage, except within the limits of the work zone(s) which may include, but is not be limited to, stairways, promenades, esplanade areas, and sidewalk, including those fronting his office and the Engineer's field office all of which will be the responsibility of the Contractor."

#### ATTACH TO CONTRACT DOCUMENTS

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION INFRASTRUCTURE DIVISION BUREAU OF DESIGN

**PROJECT ID: SER002316** 

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN
WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

**INCLUDING WATER MAIN WORK** 

**Together With All Work Incidental Thereto** 

**BOROUGH OF STATEN ISLAND** 

ADDENDUM NO. 2

DATED: February 20, 2014

This Addendum is issued for the purpose of amending the requirements of the contract documents and is hereby made part of said contract documents to the same extent as if it was originally included therein.

The Standard Sewer Specifications of the Department of Environmental Protection (dated August 1, 2009), Sewer Design Standards of the Department of Environmental Protection (dated (September 2007) Revised January 2009), Standard Water Main Specifications of the Department of Environmental Protection (dated August 1, 2009), Water Main Standard Drawings of the Department of Environmental Protection (latest revisions), and the Standard Highway Specifications (Volumes I and II) of the Department of Transportation (dated November 1, 2010) of The City of New York, shall be included as part of the contract documents. These said specifications and standard drawings are hereby revised under the following section headings:

- A. NOTICE TO BIDDERS
- B. AMENDMENTS TO THE STANDARD HIGHWAY SPECIFICATIONS
- C. AMENDMENTS TO THE STANDARD SEWER SPECIFICATIONS
- D. AMENDMENTS TO THE STANDARD WATER MAIN SPECIFICATIONS

PROJECT ID.: SER002316

#### A. NOTICE TO BIDDERS

(1) (A) The Contractor is advised that copies of the Standard Sewer Specifications (dated August 1, 2009), Sewer Design Standards (dated (September 2007) Revised January 2009), Standard Water Main Specifications (dated August 1, 2009), Specifications For Trunk Main Work (dated March 2012) and Water Main Standard Drawings (latest revisions) are available to all prospective bidders at no cost upon presentation of receipt of purchase of Bid Package at the following location:

Department of Design and Construction Division of Infrastructure Design Services, Specifications, 3<sup>rd</sup> Floor 30-30 Thomson Avenue Long Island City, NY 11101

(B) The Contractor is advised that copies of the Standard Highway Specifications (Volume I and II) (dated November 1, 2010), Standard Highway Details of Construction (latest revisions), Division of Street Lighting Specifications (latest revisions), Division of Street Lighting Standard Drawings (latest revisions), Standard Specifications for Traffic Signals (latest revisions), and Standard Drawings for Traffic Signals (latest revisions) are available to all prospective bidders for a fee at the following location:

Department of Transportation 55 Water Street, Ground Floor New York City, NY 10041

- (2) The Contractor is notified that it is the intent of this Agency to commence work promptly after registration of the contract and to order the Contractor to commence work within two (2) months after registration.
- (3) The Contractor shall furnish, install, maintain and subsequently remove temporary Protective Tree Barriers. Protective Tree Barriers shall be Type B, unless otherwise directed by the Engineer, and shall be constructed and installed as shown on the Protective Tree Barrier sketch in Department Of Transportation, Standard Highway Details Of Construction, Drawing No. H-1046A, as directed by the Engineer, and in accordance with Department of Parks and Recreation requirements.
- (4) All utility locations and invert elevations are not guaranteed, nor is there any guarantee that all existing utilities, whether functional or abandoned within the project area are shown.
- (5) All existing house connections shall be maintained and supported during construction. The Contractor shall replace any existing house connection damaged as a result of the Contractor's construction operations as ordered by the Engineer at no cost to the City.
- (6) The Contractor is advised that any City owned light poles, traffic signals, traffic signs and encumbrances including, but not limited to, underground conduit displaced as the result of the installation of the new sewers, water mains, catch basins, catch basin connections and appurtenances shall be replaced in kind and as directed by the Engineer. The cost of such work shall be deemed included in the prices bid for all items of work under this contract.
- (7) The Contractor is notified that Victaulic Style 77 Coupling is no longer acceptable for use in any steel water main work. All reference to Victaulic Style 77 Coupling within the Standard Water Main Specifications of the Department of Environmental Protection (dated August 1, 2009), the Water Main Standard Drawings of the Department of Environmental Protection (latest revisions), the Specifications For Trunk Main Work (dated March 2012), and the contract drawings, shall be replaced with Bolted Split-Sleeve Restrained Coupling.
- (8) The Contractor is notified that the fuel cost per gallon used in the formula under **Sub-Article 26.2.8** of the Standard Construction Contract for **Extra Work** will be derived from the fuel price index for the

United States East Coast published weekly by the United States Energy Information Administration ("USEIA"), and available on its website at <a href="http://www.eia.gov/petroleum/gasdiesel/">http://www.eia.gov/petroleum/gasdiesel/</a>. The USEIA published cost per gallon for the applicable fuel on the East Coast for the week in which the first day of each calendar quarter during the contract term occurs (i.e., January 1st, April 1st, July 1st and September 1st) will be used in the reimbursement formula for all Extra Work invoiced that was performed during that calendar quarter. Should the USEIA stop publishing this fuel price index, the fuel cost per gallon will be determined by reference to a substitute index to be agreed upon by the Contractor and the City.

(9) The Contractor is responsible for any damage to the existing street and traffic signal equipment, including underground conduits and the safety of both pedestrian and vehicular traffic for the duration of the contract.

Should any conduits, cables or foundations need repair due to the Contractor's negligent operations during construction, all work shall be performed according to NYCDOT Bureau of Traffic's Standard Drawings and Specifications at the sole expense of the Contractor.

It is the Contractor's responsibility to secure an approved electrical contractor to perform all traffic signal work (if any). For list of approved electrical contractors, contact Mr. Michael R. LeFosse of New York City Department of Transportation at (718) 786-2236.

(10)The Contractor is advised that where the existing roadway pavement is designated to be replaced from curb to curb, then no full depth saw cutting of pavement for sewer and water main trenches will be required, except at the limits of full width pavement restoration. No separate or additional payment will be made for any saw cutting.

ADDENDUM NO. 2 PROJECT ID.: SER002316

# B. AMENDMENTS TO THE STANDARD HIGHWAY SPECIFICATIONS

(NO TEXT)

ADDENDUM NO. 2 PROJECT ID.: SER002316

# C. AMENDMENTS TO THE STANDARD SEWER SPECIFICATIONS

- (1) Refer to Subsection 1.06.3 Hours Of Work, Page I-4: Add the following to Subsection 1.06.3:
  - (A) <u>HOLIDAY CONSTRUCTION EMBARGO</u> A special Holiday Construction Embargo shall be in effect on the Friday of the week preceding Thanksgiving Day week from 6:00 AM to 11:59 PM and again from the Monday of Thanksgiving Day week from 6:00 AM through January 2, at 11:59 PM. Roadway and sidewalk construction activities will be restricted during the embargo period on the streets listed below\*.

Any permits issued prior to the date of this notice, for work during this embargo period on the streets listed below which do not already have the permit stipulation "410" are hereby suspended for the period noted above. All permittees must comply with this embargo unless a special waiver is granted by OCMC. Waiver requests must be filed at least thirteen (13) days before Thanksgiving Day, in the Permit Office by filing a "Request for Roadway/Sidewalk Permits During Embargo Periods" and submitting supporting documentation. Waiver requests should only be submitted for critical reasons for a specific project. If a waiver is granted, the applicant will be notified so they can apply for the approved permits. Waivers <u>are not</u> required for ongoing Building Construction Activity Permits which already include the "410" permit stipulation. Waiver request forms may be obtained at any Permit Office or on the Department of Transportation's website at:

#### http://www.nyc.gov/html/dot/downloads/pdf/holidayembapp.pdf

Prior to this embargo period all necessary measures must be taken so that all roadways and sidewalks are in proper condition to allow for the expeditious and safe movement of vehicular, bicycle and pedestrian traffic. Tool carts, cable reels, containers, and material stored on roadways must be removed during the embargo period.

The opening of utility access covers is prohibited on any of the streets noted below between the hours of 6:00 AM and midnight unless the utility or contractor files for an Emergency Authorization Number as required by section 2-07 of the Department of Transportation's Highway Rules. The planned opening of utility access covers may occur during the hours of 12:01 AM and 5:59 AM where no authorization number is required.

Temporary restoration of the streets and sidewalks and removal thereof, if required for the Holiday Embargo period, will be paid for under the appropriate scheduled items.

No extension of time due to the shutdown period will be granted to the Contractor for completion of the work.

- \* Please note that this embargo only applies to NYCDOT construction permits. List of street and maps of the affected locations are available by borough on the Department of Transportation's website at: <a href="http://www.nyc.gov/html/dot/html/motorist/trafalrt.shtml">http://www.nyc.gov/html/dot/html/motorist/trafalrt.shtml</a>
- (2) <u>Refer</u> to Subsection 1.06.14 Notice To Utility Companies, Etc., To Remove Structures Occupying Place Of Sewers, Water Mains Or Appurtenances, Page I-10: <u>Add</u> the following to Subsection 1.06.14:
  - (1) CONSOLIDATED EDISON COMPANY OF NEW YORK (CON EDISON)

There are CON EDISON facilities in the area of construction. The Contractor shall notify CON EDISON at least seventy-two (72) hours prior to the start of construction by contacting Mr. Dimitrios Karounis at (718) 275-4085.

(2) NATIONAL GRID

PROJECT ID.: SER002316

There are NATIONAL GRID facilities in the area of construction. The Contractor shall notify NATIONAL GRID at least seventy-two (72) hours prior to the start of construction by contacting Mr. Neville Jacobs Jr. at (718) 963-5612 or at <a href="MEVILLE.JACOBS@us.ngrid.com">NEVILLE.JACOBS@us.ngrid.com</a>.

#### (3) VERIZON

There are VERIZON facilities in the area of construction. The Contractor shall notify VERIZON at least seventy-two (72) hours prior to the start of construction by contacting Mr. David Reid at (718) 977-8138.

## (4) TIME WARNER CABLE OF NEW YORK CITY

There are TIME WARNER CABLE facilities in the area of construction. The Contractor shall notify TIME WARNER CABLE at least seventy-two (72) hours prior to the start of construction by contacting Mr. Mark Larm at (917) 335-9181

# (3) Refer to Subsection 1.06.20 - Contractor To Notify City Departments, Page I-12: Add the following to Subsection 1.06.20:

# (1) N.Y.C. D.E.P., BUREAU OF WATER AND SEWERS OPERATIONS

The Contractor shall notify Mr. James Garin, P.E., Assistant Commissioner, Engineering at the Department of Environmental Protection, 59-17 Junction Blvd., 3rd floor low rise, Corona N.Y. 11368, at least thirty (30) days prior to the start of construction.

#### (2) NEW YORK CITY FIRE DEPARTMENT

The Contractor shall notify the Bureau of Fire Communications at least thirty (30) days prior to the start of construction by contacting Mr. Nick Varone at (718) 624-4194.

#### (3) N.Y.C. DEPARTMENT OF TRANSPORTATION

The Contractor shall notify Mr. Steve Galgano, P.E. Chief of Signal/Street Lighting Operations, 34-02 Queens Blvd., Long Island City, N.Y. 11101 at (718) 786-3550, at least seventy-two (72) hours prior to the start of construction.

#### (4) N.Y.C. DEPARTMENT OF PARKS AND RECREATION

The Contractor shall notify the Parks Department at least seventy-two (72) hours prior to the start of construction by contacting Ms. Sibylle Menendez at (718) 393-7373.

## (5) N.Y.C. TRANSIT AUTHORITY

The Contractor is advised that bus routes as well as bus stops, within the scope of this project may be affected during construction operations. The Contractor shall notify the Transit Authority at least two (2) weeks prior to the start of construction, in order to make the necessary arrangements.

Arrangements shall be made through:

Ms. Sarah Wyss
Director Of Short Range, Bus Service Planning (SRB)
New York City Transit
2 Broadway, 17<sup>th</sup> Floor
New York, N.Y. 10004
Telephone No. (646) 252-5517

ADDENDUM NO. 2 PROJECT ID.: SER002316

#### sarah.wyss@nyct.com

(4) Refer to Subsection 1.06.27 - Salvageable Materials, Page I-14:

<u>Delete</u> the paragraph starting with the words, "No salvageable material...", and ending with the words, "...from the site.", in its entirety:

Substitute the following:

Except as specified below, no salvageable material shall be returned to the New York City Department of Environmental Protection regardless of condition. It shall become the property of the Contractor for removal and disposal, by the Contractor, away from the site.

The Contractor shall salvage and deliver to a designated NYCDEP yard all Metropolitan Valves (6" thru 20") removed during construction of the contract.

- (5) Refer to Subsection 1.06.29 Contractor To Provide For Traffic, Page I-15: Add the following to Subsection 1.06.29:
  - (1) Traffic Stipulations:

The Contractor shall refer to the Traffic Stipulations (three (3) pages) that are attached to the end of this addendum, and as directed by the Engineer.

(6) Refer to Section 1.08 - Miscellaneous Provisions, Page I-19: Delete Subsection 1.08.2 - Vendors in its entirety: Substitute the following new Subsection 1.08.2:

#### 1.08.2 **VENDORS**

Prior to starting work, the Contractor shall submit in writing to the Engineer the names of all vendors and manufacturers the Contractor intends to use. Unless otherwise specified in the contract documents or a written exception is granted by NYCDDC, the Contractor shall submit only one (1) vendor or manufacturer for each product that is to be incorporated in the contract. The use of multiple vendors or manufacturers to supply the same product will be prohibited, unless otherwise specified in the contract documents or a written exception is granted by NYCDDC. If the vendor or manufacturer is not approved, the Contractor will be notified to either submit another vendor or manufacturer, or have their proposed vendor or manufacturer submit a request for approval from NYCDDC. The Contractor will be prohibited from using the vendor or manufacturer until approval of the vendor or manufacturer has been acquired from NYCDDC.

(7) Refer to Section 1.08 - Miscellaneous Provisions, Page I-20: Add the following new Subsection 1.08.7:

#### 1.08.7 SUBMITTAL OF SCHEDULE LOG

The Contractor's attention is directed to **Article 9 - Progress Schedule** of the Contract. The Contractor shall submit along with the proposed progress schedule the following: A schedule log in Excel Format (tied to the proposed progress schedule) indicating a description of and the schedule submission dates for all required submittals, shop drawings, approval requests, design mixes, reports, samples, etc., as required by the specifications and the terms of the contract.

(8) Refer to Section 2.05 - Precast Reinforced Concrete Pipe, Subsection 2.05.4 - Materials, Workmanship And Finish, Page II-10:

Delete from Subsection 2.05.4, paragraph (A) CONCRETE in its entirety:

## Substitute the following:

(A) CONCRETE - The Concrete shall comply with the requirements of **General Specification 11 - Concrete**, **as modified in Section 2.15**, and be a homogeneous mixture of such proportions and quality that the pipe will conform to the design and test requirements of these specifications.

- (9) Refer to Section 2.15 Concrete, Subsection 2.15.3 Modifications, Page II-23:
  Delete from Subsection 2.15.3, Reference Number D 3.2.1 together with its paragraphs in their entirety:
  Substitute the following:
  - D 3.2.1 DELETE 3.2.1 to 3.2.9 of GS11 and SUBSTITUTE the following:

All concrete mix designs shall be subject to approval by DDC's Quality Assurance and Construction Safety (QACS) Bureau and in accordance with their "MIX DESIGN, LABORATORY AND PLANT APPROVAL PROTOCOL". Copies of this protocol may be obtained at the preconstruction meeting or from the Engineer. Before the Contractor begins to manufacture concrete, the Contractor shall secure DDC's QACS approval of the mix design the Contractor proposes to use.

The Contractor shall submit for this purpose a statement, in writing, of the sources of all ingredient materials, the type and brand of the cement and the number of pounds of each of the materials in a saturated surface-dry condition making up one (1) cubic yard of concrete. The range of water-cement ratios within which the concrete will be manufactured and the method of mixing to be employed shall also be stated. The mix design submittal shall include gradation of aggregates, specific gravities of ingredients, unit weight, mix proportion for each batch (a minimum of four (4) batches except in case of precast plants where one specific mix may be proposed), compressive strength test results for each mix at 7-days, 28-days (high-early strength mixes may require 6-hours, 24-hours, 3-days and shrinkage test as per the requirements), and graphical representation of strength vs. W/C projected in hours/days.

The Contractor may submit for approval concrete mixes that (within one (1) year of the contract) have been previously approved and used on other jobs with any Bureau of the Department of Environmental Protection or the Department of Design and Construction. Such submittals shall contain evidence that the concrete mix was approved within one (1) year of this contract and shall show that the concrete will be produced at the same mix plant, that the cement and admixtures are the same type (though not necessarily the same brand), that the water/cement ratio is the same and that adjustments have been made in the mix for air content, specific gravity and gradation of the aggregates.

If the Contractor elects to submit a concrete mix that was not previously approved, the Contractor shall submit the new concrete mix in accordance with Chapters 2 and 3 of General Specification 11 as modified herein.

- (10)<u>Refer</u> to Section 2.15 Concrete, Subsection 2.15.3 Modifications, Page II-26: <u>Add</u> to Subsection 2.15.3, before Reference Number D 8.2 the following:
  - D 7.3.3 ADD the following to Subsection 7.3.3 of GS11:

Each Portland cement concrete batching plant shall be subject to approval by DDC's Quality Assurance and Construction Safety (QACS) Bureau and in accordance with their "MIX DESIGN, LABORATORY AND PLANT APPROVAL PROTOCOL". Copies of this protocol may be obtained at the preconstruction meeting or from the Engineer. The minimum requirement for approval is that the proposed Portland cement concrete

ADDENDUM NO. 2 PROJECT ID.: SER002316

batching plant must be on the New York State Department of Transportation (NYSDOT) approved list for the current construction season.

The minimum requirement for approval of a precast concrete plant is that the proposed plant must be on the NYSDOT approved list. A waiver for this requirement may be granted by the DDC's Quality Assurance and Construction Safety (QACS) Director for special products that no NYSDOT approved plant is capable of producing.

Each Portland cement concrete batching plant shall also be subject to auditing and approval of the DDC's Director of Quality Assurance and Construction Safety (QACS). The Director of QACS may at any time discontinue the use of any previously approved equipment if nonconformance with the specifications results during the progress of the work. When the Director of QACS discontinues the use of the plant, production will not be acceptable for Department work until corrective measures satisfactory to the Director are carried out.

(11)Refer to Section 2.15 - Concrete, Subsection 2.15.3 - Modifications, Page II-26:

<u>Delete</u> from <u>Subsection 2.15.3</u>, <u>Reference Number D 16.3</u> together with its paragraphs in their entirety:

Substitute the following:

D 16.3 Testing Service - ADD the following:

The Contractor shall retain the services of an independent testing laboratory to provide for the services outlined in 16.3.1.4 to 16.3.1.11 of GS11, with the exception of those tests specified herein to be performed by the Engineer and the City Retained Laboratory.

All laboratories shall be subject to approval by DDC's Quality Assurance and Construction Safety (QACS) Bureau and in accordance with their "MIX DESIGN, LABORATORY AND PLANT APPROVAL PROTOCOL". Copies of this protocol may be obtained at the preconstruction meeting or from the Engineer. The minimum requirement for approval is that the laboratory must have the current AMRL/AASHTO R-18 accreditation in the category of service proposed and must be currently licensed by the NYC Department of Buildings (DOB).

(12) Refer to Section 2.15 - Concrete, Subsection 2.15.3 - Modifications, Page II-26:

<u>Delete</u> from Subsection 2.15.3, Reference Number D 16.8 together with its paragraphs in their entirety:

**Substitute** the following:

D 16.8 Responsibilities and Duties of Contractor - ADD the following:

The Contractor may, if the Contractor so desires, take cylinders corresponding to those taken by the Engineer for the City Retained Laboratory. However, determination of payment will be based solely on the cylinders taken by the Engineer for the City Retained Laboratory.

#### **CONCRETE TEST CYLINDERS**

The Contractor will be responsible for safe delivery of concrete cylinders to the Department of Design and Construction Laboratory, within two (2) days after molding, where they will be properly stored and cured until the date of test, and tested by others, upon removal from the curing room. The Department of Design and Construction testing laboratory will provide the services for the curing and breaking of the test cylinders.

PROJECT ID.: SER002316

The Contractor shall provide empty cylinder molds and facilities for the proper care of these cylinders while on the site, and shall safeguard them against injury and protect them from the elements.

The Engineer will be responsible for the preparation, documentation and labeling of the cylinders and for notifying the Contractor, at least twenty-four (24) hours in advance, when a shipment of cylinders is ready for delivery, so that cylinders can be tested for the standard twenty-eight (28) day and seven (7) day tests. Cylinders are to be delivered by the Contractor to a designated area near 30-30 Thomson Avenue, Long Island City, New York, or where otherwise directed within the City of New York.

The Contractor shall make arrangements to protect all cylinders from damage during loading, transport to, and unloading at a Department of Design and Construction designated testing laboratory, and shall obtain a receipt for delivered cylinders, which shall be submitted to the Engineer.

# (13)<u>Refer</u> to Section 4.06 - Backfilling, Subsection 4.06.3 - Method Of Depositing All Backfill, Page IV-18:

(A) Add the following paragraph to beginning of Subsection 4.06.3:

At the preconstruction meeting, the Contractor shall submit for approval a full description of the Contractor's proposed methods to be used for all backfilling operations including, but not limited to, equipment, backfill material, depth of compaction layers, and trench locations where each is to be employed. In the field, the Contractor shall be required to demonstrate that the Contractor's methods of backfilling and compaction shall obtain a minimum of ninety-five (95) percent of Standard Proctor Maximum Dry Density.

**(B)** <u>Delete</u> from **Subsection 4.06.3**, the fourth paragraph in its entirety: **Substitute** the following:

Unless otherwise approved in writing by the Engineer, backfilling of the remainder of the trenches and excavations from a point not less than two (2) feet above the top of the sewer conduit (i.e. sewer pipes on cradles or encasements, reinforced concrete sewers, basin and house connections, culverts, etc.) to the underside of the pavement shall be progressively deposited in uniform and successive horizontal layers not exceeding twelve (12) inches in depth for the entire width of the trench or excavation and each successive layer shall be solidly compacted by mechanical tamping or other approved means so as to achieve the required density. In deep trenches defined as those requiring sheeting, the Contractor may submit to the Engineer, for approval, an alternate backfill method (i.e. jetting, deeper deposited layers not exceeding twenty-four (24) inches, etc.) for depositing and compacting the backfill from two (2) feet above the top of the sewer conduit to a plane five (5) feet below final surface elevation. However, approval of any alternate backfill method shall not relieve the Contractor from obtaining a minimum of ninety-five (95) percent of Standard Proctor Maximum Dry Density. Should the Engineer determine that the specified density is not being obtained, the area must be re-excavated and backfilled at the Contractor's own cost until the required compaction density is achieved.

**(C)** <u>Delete</u> from **Subsection 4.06.3**, the seventh paragraph in its entirety: <u>Substitute</u> the following:

Backfill shall proceed simultaneously with the withdrawal of sheeting but at no time shall the withdrawal of sheeting exceed a height of six (6) inches above the deposited backfill. Withdrawal of sheeting below levels previously backfilled and compacted is prohibited.

(14)<u>Refer</u> to Section 5.01 - Reinforced Concrete Sewers, Subsection 5.01.4 - Precast Reinforced Concrete Sewer, Paragraph (C) - Details, second paragraph, first line, Page V-4:

ADDENDUM NO. 2 PROJECT ID.: SER002316

Change the words "C789 or C850 (as required)", to "C1433":

(15)Refer to Section 5.05C - Reconstruction Of Existing Sewers Using D.E.P. Approved Cured-In-Place-Pipe (CIPP) Lining Method, Subsection 5.05C.6 - Separate Payment, third paragraph, second line, Page V-49

Change the word, "nine", to "eleven":

(16)<u>Refer</u> to Section 5.11 - Outfall Structures, Subsection 5.11.2 - Materials, Page V-95:

<u>Delete</u> from Subsection 5.11.1, paragraph (A) in its entirety:

<u>Substitute</u> the following:

(A) Concrete used for outfall structure (including headwalls, reinforced concrete sewer outfalls, cradles and encasements, chambers, manholes and catch basins) shall comply with the requirements of **General Specification 11 - Concrete, as modified in Section 2.15**; and, shall contain entrained air of six percent (6%), and a corrosion inhibitor. The corrosion inhibitor shall consist of a calcium nitrite solution, containing 30 ±2% calcium nitrite solids by weight and having a specific gravity of 1.27 ±0.02. The corrosion inhibitor when used in the manufacturing process shall not produce a significant amount of chloride ions in the final product (less than 1,000-ppm). The ph shall be greater than 8. The admixture shall not contain chemicals that produce a condition injurious to the quality and durability of the concrete or reinforcing steel. Calcium nitrite, which acts as an accelerator, may be used in conjunction with compatible retarding admixtures to control setting time and workability of the concrete, consult the manufacturer of the product. The corrosion inhibitor must be added to the mix immediately after air entraining and retarding admixtures have been introduced into the batch. Acceptance of calcium nitrite based corrosion inhibitor shall be based upon it being listed in the most current New York State Department of Transportation's "Approved List Of Calcium Nitrite Based Corrosion Inhibitors".

(17)<u>Refer</u> to Section 5.18A - Sewer Cleaning, Subsection 5.18A.3 - Disposal, Page V-124: <u>Delete</u> from Subsection 5.18A.3, the first paragraph in its entirety: Substitute the following:

All material removed from the sewers and sewer portions through the manholes under this contract shall become the property of the Contractor and shall be properly disposed of away from the site, at the Contractor's expense.

(18)<u>Refer</u> to Section 5.23 - Decking, Subsection 5.23.1 - Description, Page V-161:

<u>Delete</u> from Subsection 5.23.1, the third paragraph in its entirety:

<u>Substitute</u> the following:

Steel plates that are resting on pavement, that are not part of a decking system, and are used to temporarily span trenches and excavations for vehicular traffic and for pedestrian crossings and walkways shall not be included for payment under this decking section. The cost of all labor, materials, equipment, insurance and incidentals necessary to furnish, place, anchor and ramp these temporary steel plates, when and where directed, in order to comply with the requirements of the NYCDOT Office of Construction Mitigation and Coordination (OCMC) traffic stipulations, the directions of the Engineer, and the Contractor's construction operations shall be deemed included in the prices bid for all contract items of work.

(19)<u>Refer</u> to Section 5.23 - Decking, Subsection 5.23.4 - Design Criteria, Page V-162: <u>Add</u> the following to Subsection 5.23.4:

(C) The Contractor may substitute skid resistant steel plates (Non-Skid Textured Plates) for timber mats, subject to approval in accordance with **Subsection 4.05.5**. These steel plates shall be placed

flush with the existing roadway and shall be installed in compliance with the requirements of **Subsection 4.05.6(G)**.

# (20)<u>Refer</u> to Subsection 5.32.4 - Specific Pavement Restoration Provisions, Page V-185: <u>Add</u> the following to Subsection 5.32.4:

- (E) Specific Pavement Restoration Provisions:
  - (1) In Rossville Avenue between Woodrow Road and Station 01+50; Woodrow Road between Station 06+25 and Station 18+75; and, Foster Road between Woodrow Road and Station 05+00 the restoration shall be as follows:
    - (a) The entire width of existing roadway shall be removed from **curb** to **curb** or **edge to edge** and the permanent restoration over the **entire width of roadway** shall consist of nine (9) inches of Asphaltic Macadam Pavement. The above areas are approximate the actual final areas of restoration shall be determined by the Engineer.
  - (2) In Marcy Avenue between Woodrow Road and Venus Place; Venue Place between Marcy Avenue and Powell Street; and, Powell Street between Dead End and Venus Place, the restoration shall be as follows:
    - (a) The entire width of existing roadway shall be removed from curb to curb or edge to edge and the permanent restoration over the entire width of roadway shall consist of six (6) inches of Asphaltic Macadam Pavement. The above areas are approximate the actual final areas of restoration shall be determined by the Engineer.
  - (3) In Woodrow Road between Rossville Avenue and Station 06+25; Woodrow Road between Station 18+75 and Station 24+25; Rossville Avenue between Mason Boulevard and Station 01+50; and, Wieland Avenue between Station 04+25 and Foster Road; the restoration shall be as follows:
    - (a) The permanent restoration over the **trench width and cutbacks only** shall consist of a top course of one and one-half (1-1/2) inches of binder mixture on a base course of a minimum of four and one-half (4-1/2) inches of binder mixture, to match the existing pavement as directed by the Engineer.
    - (b) Finally an overlay of two (2) inches of asphaltic concrete wearing course shall be installed over the entire width of the roadway from curb to curb or edge to edge of existing roadway.
  - (4) In Gilroy Street between Woodrow Road and Station 04+75; Powell Street between Venus Place and West Castor Place; West Castor Place between Powell Street and Station 23+75; and, Foster Road between Station 05+00 and Station 06+00; the restoration shall be as follows:
    - (a) The permanent restoration over the **trench width and cutbacks only** shall consist of a top course of one and one-half (1-1/2) inches of asphaltic concrete wearing course on a base course of a minimum of four and one-half (4-1/2) inches of binder mixture, to match the existing pavement as directed by the Engineer.
  - (4) The following requirements apply:
    - (a) Before the top course is installed, an additional width of asphalt beyond the edge of new base course shall be saw-cut and removed from all edges of trenches to a depth

to accommodate the specified top course and the entire area restored. This additional removal shall be in accordance with paragraph (b) below.

- (b) Pavement excavation along with saw cutting of pavements for sewer and water main trenches shall be in accordance with **Section 5.30 Pavement Excavation** of both the Standard Sewer Specifications and the Standard Water Main Specification.
- (c) At locations requiring the installation of a concrete base course, a reflective cracking membrane shall be installed over joints prior to restoration, the cost of which shall be deemed included in the prices bid for all pavement restoration items. Additionally, appropriate pavement keys as described below shall be used.
- (d) Pavement keys **Type B-1** shall be used to insure a desired four (4) inch curb reveal (two and one-half (2-1/2) inch absolute minimum). Pavement key **Type A** shall be used in all intersections. Both keys are to be per Bureau of Highways Operations Specifications and Standard Details of Construction.
- (e) Unless otherwise specified, the cost for tack coating, eradication of temporary roadway markings, stripping or milling of pavement keys and adjustment of city-owned castings shall be deemed included in the prices bid for all pavement restoration items.
- (f) Payment for placement of temporary pavement marking shall be made under Item No. 6.49 TEMPORARY PAVEMENT MARKINGS (4" WIDE).
- (g) Payment for removal of existing pavement markings shall be made under Item No. 6.53 REMOVE EXISTING LANE MARKINGS (4"WIDE).
- (h) Payment for removal and permanent placement of pavement marking with thermoplastic reflectorized pavement markings (crosswalk and lane dividers) shall be made under Item No. 6.44 THERMOPLASTIC REFLECTORIZED PAVEMENT MARKINGS (4" WIDE).
- (i) Payment for pavement restoration shall be made under the following items:

Item No.	<u>Item</u>	Payment Description
4.01 RAG	Asphaltic Macadam Pavement, 6" Thick	(For entire width of roadway restoration.)
4.01 RAJ	Asphaltic Macadam Pavement, 9" Thick	(For entire width of roadway restoration.)
4.02 AB-R	Asphaltic Concrete Wearing Course, 1-1/2" Thick	(For asphaltic concrete wearing course top course when <u>no</u> overlay is required.)
4.02 AF-R	Asphaltic Concrete Wearing Course, 2" Thick	(For 2" asphaltic concrete wearing course overlay from curb to curb or edge to edge.)
4.02 CA	Binder Mixture	(For binder mixture base course over trenches and cutbacks; binder mixture top course when overlay is required; binder mixture in Type A and B Keys; and binder mixture to fill in roadway depressions and to provide a leveling course prior to overlay where ordered.)

(21)Refer to Section 5.36 - Additional Earth Excavation Including Test Pits, Subsection 5.36.4 - Price To Cover, Paragraph (3), fifth line, Page V-195: Change 16", to 16'.

### D. AMENDMENTS TO THE STANDARD WATER MAIN SPECIFICATIONS

- (1) Refer to Subsection 1.06.3 Hours Of Work, Page I-4: Add the following to Subsection 1.06.3:
  - (A) <u>HOLIDAY CONSTRUCTION EMBARGO</u> A special Holiday Construction Embargo shall be in effect on the Friday of the week preceding Thanksgiving Day week from 6:00 AM to 11:59 PM and again from the Monday of Thanksgiving Day week from 6:00 AM through January 2, at 11:59 PM. Roadway and sidewalk construction activities will be restricted during the embargo period on the streets listed below\*.

Any permits issued prior to the date of this notice, for work during this embargo period on the streets listed below which do not already have the permit stipulation "410" are hereby suspended for the period noted above. All permittees must comply with this embargo unless a special waiver is granted by OCMC. Waiver requests must be filed at least thirteen (13) days before Thanksgiving Day, in the Permit Office by filing a "Request for Roadway/Sidewalk Permits During Embargo Periods" and submitting supporting documentation. Waiver requests should only be submitted for critical reasons for a specific project. If a waiver is granted, the applicant will be notified so they can apply for the approved permits. Waivers <u>are not</u> required for ongoing Building Construction Activity Permits which already include the "410" permit stipulation. Waiver request forms may be obtained at any Permit Office or on the Department of Transportation's website at:

#### http://www.nyc.gov/html/dot/downloads/pdf/holidayembapp.pdf

Prior to this embargo period all necessary measures must be taken so that all roadways and sidewalks are in proper condition to allow for the expeditious and safe movement of vehicular, bicycle and pedestrian traffic. Tool carts, cable reels, containers, and material stored on roadways must be removed during the embargo period.

The opening of utility access covers is prohibited on any of the streets noted below between the hours of 6:00 AM and midnight unless the utility or contractor files for an Emergency Authorization Number as required by section 2-07 of the Department of Transportation's Highway Rules. The planned opening of utility access covers may occur during the hours of 12:01 AM and 5:59 AM where no authorization number is required.

Temporary restoration of the streets and sidewalks and removal thereof, if required for the Holiday Embargo period, will be paid for under the appropriate scheduled items.

No extension of time due to the shutdown period will be granted to the Contractor for completion of the work.

- \* Please note that this embargo only applies to NYCDOT construction permits. List of street and maps of the affected locations are available by borough on the Department of Transportation's website at: <a href="http://www.nyc.gov/html/dot/html/motorist/trafalrt.shtml">http://www.nyc.gov/html/dot/html/motorist/trafalrt.shtml</a>
- (2) Refer to Subsection 1.06.27 Salvageable Materials, Page I-14:

<u>Delete</u> the paragraph starting with the words, "No salvageable material...", and ending with the words, "... from the site.", in its entirety:

Substitute the following:

Except as specified below, no salvageable material shall be returned to the New York City Department of Environmental Protection regardless of condition. It shall become the property of the Contractor for removal and disposal, by the Contractor, away from the site.

The Contractor shall salvage and deliver to a designated NYCDEP yard all Metropolitan Valves (6" thru 20") removed during construction of the contract.

(3) Refer to Standard Water Main Specifications (August 1, 2009), Subsection 1.06.29 - Contractor To Provide For Traffic, Page I-15:

Add the following to Subsection 1.06.29:

See amended Standard Sewer Specifications (August 1, 2009) **Subsection 1.06.29 - Contractor To Provide For Traffic** of this addendum.

(4) Refer to Section 1.08 - Miscellaneous Provisions, Page I-19: <u>Delete</u> Subsection 1.08.2 - Vendors in its entirety: <u>Substitute</u> the following new Subsection 1.08.2:

#### 1.08.2 **VENDORS**

Prior to starting work, the Contractor shall submit in writing to the Engineer the names of all vendors and manufacturers the Contractor intends to use. Unless otherwise specified in the contract documents or a written exception is granted by NYCDDC, the Contractor shall submit only one (1) vendor or manufacturer for each product that is to be incorporated in the contract. The use of multiple vendors or manufacturers to supply the same product will be prohibited, unless otherwise specified in the contract documents or a written exception is granted by NYCDDC. If the vendor or manufacturer is not approved, the Contractor will be notified to either submit another vendor or manufacturer, or have their proposed vendor or manufacturer submit a request for approval from NYCDDC. The Contractor will be prohibited from using the vendor or manufacturer until approval of the vendor or manufacturer has been acquired from NYCDDC.

(5) Refer to Section 1.08 - Miscellaneous Provisions, Page I-20: Add the following new Subsection 1.08.7:

#### 1.08.7 SUBMITTAL OF SCHEDULE LOG

The Contractor's attention is directed to **Article 9 - Progress Schedule** of the Contract. The Contractor shall submit along with the proposed progress schedule the following: A schedule log in Excel Format (tied to the proposed progress schedule) indicating a description of and the schedule submission dates for all required submittals, shop drawings, approval requests, design mixes, reports, samples, etc., as required by the specifications and the terms of the contract.

(6) Refer to Section 2.15 - Concrete, Subsection 2.15.3 - Modifications, Page II-11:
<u>Delete</u> from Subsection 2.15.3, Reference Number D 3.2.1 together with its paragraphs in their entirety:
<u>Substitute</u> the following:

#### D 3.2.1 DELETE 3.2.1 to 3.2.9 of GS11 and SUBSTITUTE the following:

All concrete mix designs shall be subject to approval by DDC's Quality Assurance and Construction Safety (QACS) Bureau and in accordance with their "MIX DESIGN, LABORATORY AND PLANT APPROVAL PROTOCOL". Copies of this protocol may be obtained at the preconstruction meeting or from the Engineer. Before the Contractor begins to manufacture concrete, the Contractor shall secure DDC's QACS approval of the mix design the Contractor proposes to use.

The Contractor shall submit for this purpose a statement, in writing, of the sources of all ingredient materials, the type and brand of the cement and the number of pounds of each of the materials in a saturated surface-dry condition making up one (1) cubic yard of concrete. The range of water-cement ratios within which the concrete will be

manufactured and the method of mixing to be employed shall also be stated. The mix design submittal shall include gradation of aggregates, specific gravities of ingredients, unit weight, mix proportion for each batch (a minimum of four (4) batches except in case of precast plants where one specific mix may be proposed), compressive strength test results for each mix at 7-days, 28-days (high-early strength mixes may require 6-hours, 24-hours, 3-days and shrinkage test as per the requirements), and graphical representation of strength vs. W/C projected in hours/days.

The Contractor may submit for approval concrete mixes that (within one (1) year of the contract) have been previously approved and used on other jobs with any Bureau of the Department of Environmental Protection or the Department of Design and Construction. Such submittals shall contain evidence that the concrete mix was approved within one (1) year of this contract and shall show that the concrete will be produced at the same mix plant, that the cement and admixtures are the same type (though not necessarily the same brand), that the water/cement ratio is the same and that adjustments have been made in the mix for air content, specific gravity and gradation of the aggregates.

If the Contractor elects to submit a concrete mix that was not previously approved, the Contractor shall submit the new concrete mix in accordance with Chapters 2 and 3 of General Specification 11 as modified herein.

- (7) Refer to Section 2.15 Concrete, Subsection 2.15.3 Modifications, Page II-13: Add to Subsection 2.15.3, before Reference Number D 8.2 the following:
  - D 7.3.3 ADD the following to Subsection 7.3.3 of GS11:

Each Portland cement concrete batching plant shall be subject to approval by DDC's Quality Assurance and Construction Safety (QACS) Bureau and in accordance with their "MIX DESIGN, LABORATORY AND PLANT APPROVAL PROTOCOL". Copies of this protocol may be obtained at the preconstruction meeting or from the Engineer. The minimum requirement for approval is that the proposed Portland cement concrete batching plant must be on the New York State Department of Transportation (NYSDOT) approved list for the current construction season.

The minimum requirement for approval of a precast concrete plant is that the proposed plant must be on the NYSDOT approved list. A waiver for this requirement may be granted by the DDC's Quality Assurance and Construction Safety (QACS) Director for special products that no NYSDOT approved plant is capable of producing.

Each Portland cement concrete batching plant shall also be subject to auditing and approval of the DDC's Director of Quality Assurance and Construction Safety (QACS). The Director of QACS may at any time discontinue the use of any previously approved equipment if nonconformance with the specifications results during the progress of the work. When the Director of QACS discontinues the use of the plant, production will not be acceptable for Department work until corrective measures satisfactory to the Director are carried out.

(8) Refer to Section 2.15 - Concrete, Subsection 2.15.3 - Modifications, Page II-14:
<u>Delete</u> from Subsection 2.15.3, Reference Number D 16.3 together with its paragraphs in their entirety:
<u>Substitute</u> the following:

D 16.3 Testing Service - ADD the following:

The Contractor shall retain the services of an independent testing laboratory to provide for the services outlined in 16.3.1.4 to 16.3.1.11 of GS11, with the exception of those tests specified herein to be performed by the Engineer and the City Retained Laboratory.

All laboratories shall be subject to approval by DDC's Quality Assurance and Construction Safety (QACS) Bureau and in accordance with their "MIX DESIGN, LABORATORY AND PLANT APPROVAL PROTOCOL". Copies of this protocol may be obtained at the preconstruction meeting or from the Engineer. The minimum requirement for approval is that the laboratory must have the current AMRL/AASHTO R-18 accreditation in the category of service proposed and must be currently licensed by the NYC Department of Buildings (DOB).

(9) Refer to Section 2.15 - Concrete, Subsection 2.15.3 - Modifications, Page II-14:

**Delete** from **Subsection 2.15.3**, **Reference Number D 16.8** together with its paragraphs in their entirety:

Substitute the following:

D 16.8 Responsibilities and Duties of Contractor - <u>ADD</u> the following:

The Contractor may, if the Contractor so desires, take cylinders corresponding to those taken by the Engineer for the City Retained Laboratory. However, determination of payment will be based solely on the cylinders taken by the Engineer for the City Retained Laboratory.

#### **CONCRETE TEST CYLINDERS**

The Contractor will be responsible for safe delivery of concrete cylinders to the Department of Design and Construction Laboratory, within two (2) days after molding, where they will be properly stored and cured until the date of test, and tested by others, upon removal from the curing room. The Department of Design and Construction testing laboratory will provide the services for the curing and breaking of the test cylinders.

The Contractor shall provide empty cylinder molds and facilities for the proper care of these cylinders while on the site, and shall safeguard them against injury and protect them from the elements.

The Engineer will be responsible for the preparation, documentation and labeling of the cylinders and for notifying the Contractor, at least twenty-four (24) hours in advance, when a shipment of cylinders is ready for delivery, so that cylinders can be tested for the standard twenty-eight (28) day and seven (7) day tests. Cylinders are to be delivered by the Contractor to a designated area near 30-30 Thomson Avenue, Long Island City, New York, or where otherwise directed within the City of New York.

The Contractor shall make arrangements to protect all cylinders from damage during loading, transport to, and unloading at a Department of Design and Construction designated testing laboratory, and shall obtain a receipt for delivered cylinders, which shall be submitted to the Engineer.

(10)Refer to Section 4.06 - Backfilling, Subsection 4.06.3 - Method Of Depositing All Backfill, Page IV-18:

(A) Add the following paragraph to beginning of Subsection 4.06.3:

At the preconstruction meeting, the Contractor shall submit for approval a full description of the Contractor's proposed methods to be used for all backfilling operations including, but not limited to, equipment, backfill material, depth of compaction layers, and trench locations where each is to be

PROJECT ID.: SER002316

employed. In the field, the Contractor shall be required to demonstrate that the Contractor's methods of backfilling and compaction shall obtain a minimum of ninety-five (95) percent of Standard Proctor Maximum Dry Density.

**(B)** <u>Delete</u> from **Subsection 4.06.3**, the fourth paragraph in its entirety: <u>Substitute</u> the following:

Unless otherwise approved in writing by the Engineer, backfilling of the remainder of the trenches and excavations from a point not less than twelve (12) inches above the top of the barrel of the water main pipe to the underside of the pavement shall be progressively deposited in uniform and successive horizontal layers not exceeding twelve (12) inches in depth for the entire width of the trench or excavation and each successive layer shall be solidly compacted by mechanical tamping or other approved means so as to achieve the required density. In deep trenches defined as those requiring sheeting, the Contractor may submit to the Engineer, for approval, an alternate backfill method (i.e. jetting, deeper deposited layers not exceeding twenty-four (24) inches, etc.) for depositing and compacting the backfill from twelve (12) inches above the top of the barrel of the water main pipe to a plane five (5) feet below final surface elevation. However, approval of any alternate backfill method shall not relieve the Contractor from obtaining a minimum of ninety-five (95) percent of Standard Proctor Maximum Dry Density. Should the Engineer determine that the specified density is not being obtained, the area must be re-excavated and backfilled at the Contractor's own cost until the required compaction density is achieved.

(C) <u>Delete</u> from Subsection 4.06.3, the seventh paragraph in its entirety: <u>Substitute</u> the following:

Backfill shall proceed simultaneously with the withdrawal of sheeting but at no time shall the withdrawal of sheeting exceed a height of six (6) inches above the deposited backfill. Withdrawal of sheeting below levels previously backfilled and compacted is prohibited.

(11)Refer to Section 5.02 - Laying Ductile Iron Pipe And Fittings, Subsection 5.02.3(F) - Bedding And Foundation Of Pipes. Page V-8:

<u>Delete</u> from **Subsection 5.02.3(F)**, Paragraph (5) - Pier And Plate, in its entirety: **Substitute** the following new Paragraph (5):

(5) Shallow Cover: Where mains 24-inches and smaller are laid with covers of 2'-0" or less, the Contractor shall provide protection in accordance with **Standard Drawing No. 42063-Y** or as directed by the Engineer.

Where mains 24-inches and smaller are laid with covers between 2'-6" and 2'-0", the Contractor shall provide steel plates only over the main with dimensions as shown on **Standard Drawing No. 46464-Z** or as directed by the Engineer.

Where mains 30-inches and larger are laid with covers of 2'-6" or less, the Contractor shall provide protection in accordance with **Standard Drawing No. 46464-Z** or as directed by the Engineer.

Covers over the new mains shall not be less than 1'-6".

(12)<u>Refer</u> to Section 5.02 - Laying Ductile Iron Pipe And Fittings, Subsection 5.02.3 - Construction Methods, Paragraph (M) - Laying Temporary Connections, Page V-12:

**Delete Paragraph (M)**, in its entirety:

Substitute the following:

(M) LAYING TEMPORARY CONNECTIONS AND INSTALLING TEMPORARY CAP ASSEMBLIES AND/OR BULKHEADS

(1) When new water mains are laid and it becomes necessary to provide a temporary connection between the existing main and new mains laid under this contract (regardless of whether the new and existing water mains are in the same trench or are offset in two different trenches), the Contractor shall, if ordered, provide all labor, equipment and facilities for laying, maintaining and removing when directed, temporary connections and appurtenances. If City forces do laying of temporary connections, the Contractor shall make all required equipment and facilities available to them. No payment will be made for providing temporary house services which may be required when making a temporary connection between the existing and new main.

- (2) (a) Temporary cap assemblies on distribution water mains (20" and less in diameter) shall consist of a 2-foot long spigot/spigot ductile iron pipe with a mechanical joint cap restrained to the pipe with a "wedge-type" retainer gland and a minimum 2-inch tap on the pipe section.
  - (b) Temporary cap assemblies on distribution water mains (20" and less in diameter) shall be restrained and braced in a manner sufficient to support system working pressures, and thrust forces.
  - (c) The 2-inch tap required as part of the temporary cap assembly is to be utilized to allow air to escape while filling the main in addition to allow for proper flushing of the main.
  - (d) Restraint and bracing as well as temporary cap assemblies/bulkheads for water mains greater than 20" in diameter shall be submitted for approval by the Engineer prior to being utilized.

(13)Refer to Section 5.02 - Laying Ductile Iron Pipe And Fittings, Subsection 5.02.5 - Price To Cover, Paragraph (10), Page V-16:

<u>Delete</u> Paragraph (10), in its entirety:

**Substitute** the following:

- (10)(a) No separate or additional payment will be made to the Contractor for furnishing, delivering, installing, restraining, bracing and removing temporary cap assemblies/bulkheads for water mains as ordered by the Engineer. The costs thereof shall be deemed included in the unit prices bid for all items of the contract.
  - (b) Payment for temporary valves (i.e. construction valves) and its associated fittings ordered by the Engineer during the course of the work to be installed will be paid for at the same rates as for valves and fittings permanently installed.
  - (c) If ordered by the Engineer, removal of valves (i.e. construction valves) and its associated fittings, including their transfer and disposal shall be deemed included in the prices bid for all items of the contract. No separate or additional payment will be made for this work.
  - (d) Payment For Temporary Connections: When new mains are laid and it becomes necessary to provide a temporary connection between the existing and new mains the following method of payment shall apply: The Contractor shall be paid once for furnishing and delivering pipes and fittings used in temporary connections. The Contractor shall also be paid for laying the temporary pipe connection and fitting using the appropriate pipe laying item for each time that the Contractor is directed to use them throughout the project as directed by the Engineer.
- (14)<u>Refer</u> to Subsection 5.04.4 Furnishing, Delivering And Installing Steel Tee, Paragraph (5), Item Numbers list, Page V-23:

<u>Delete</u> Item No. "60.23ST20T48", together with Description "FURNISHING, DELIVERING AND INSTALLING 48-INCH X 20-INCH STEEL TEE", and Pay Unit "EACH":

(15)Refer to Section 5.05 - Furnishing And Delivering Gate Valves, Page V-35:

**(A)** <u>Delete</u> from **Subsection 5.05.1 - Description**, the first paragraph in its entirety: <u>Substitute</u> the following:

This specification describes furnishing and delivering of double disc 3-inch to 20-inch gate valves, resilient seated 3-inch to 20-inch gate valves and resilient seated 3-inch to 12-inch tapping valves.

Unless otherwise specified in the contract documents or ordered in writing by the Engineer, only resilient seated gate valves and tapping valves shall be furnished and delivered by the Contractor on the contract.

(B) <u>Delete</u> from **Subsection 5.05.2 - Materials**, second paragraph, first line, the words, "6-inch hydrant":

Substitute the following words, "3-inch to 20-inch":

#### (16) Refer to Section 5.06 - Setting Gate Valves, Page V-38:

(A) <u>Delete</u> from **Subsection 5.06.1 - Description**, the first paragraph in its entirety: <u>Substitute</u> the following:

This specification describes the installation of double disc 3-inch to 20-inch gate valves, resilient seated 3-inch to 20-inch gate valves and resilient seated 3-inch to 12-inch tapping valves. It also describes the installing of manhole frames (skirts and heads) and covers.

Unless otherwise specified in the contract documents or ordered in writing by the Engineer, only resilient seated gate valves and tapping valves shall be installed by the Contractor on the contract.

**(B)** <u>Delete</u> from **Subsection 5.06.2 - Materials**, second paragraph, first line, the words, "6-inch hydrant":

Substitute the following words, "3-inch to 20-inch":

(17)<u>Refer</u> to Section 5.23 - Decking, Subsection 5.23.1 - Description, Page V-73:

<u>Delete</u> from Subsection 5.23.1, the third paragraph in its entirety:

<u>Substitute</u> the following:

Steel plates that are resting on pavement, that are not part of a decking system, and are used to temporarily span trenches and excavations for vehicular traffic and for pedestrian crossings and walkways shall not be included for payment under this decking section. The cost of all labor, materials, equipment, insurance and incidentals necessary to furnish, place, anchor and ramp these temporary steel plates, when and where directed, in order to comply with the requirements of the NYCDOT Office of Construction Mitigation and Coordination (OCMC) traffic stipulations, the directions of the Engineer, and the Contractor's construction operations shall be deemed included in the prices bid for all contract items of work.

- (18)<u>Refer</u> to Section 5.23 Decking, Subsection 5.23.4 Design Criteria, Page V-74:

  <u>Add</u> the following to Subsection 5.23.4:
  - (C) The Contractor may substitute skid resistant steel plates for timber mats, subject to approval in accordance with **Subsection 4.05.5**. These steel plates shall be placed flush with the existing roadway and shall be installed in compliance with the requirements of **Subsection 4.05.6(G)**.
- (19)<u>Refer</u> to Standard Water Main Specifications (August 1, 2009), **Section 5.32 Final Restoration Of Pavements**, Page V-99:

Add the following to Subsection 5.32.4 - Specific Pavement Restoration Provisions:

See amended Standard Sewer Specifications (August 1, 2009) **Subsection 5.32.4 - Specific Pavement Restoration Provisions** of this addendum.

(20)Refer to Section 5.36 - Additional Earth Excavation Including Test Pits, Subsection 5.36.4 - Price To Cover, Paragraph (3), fifth line, Page V-114:

<u>Change</u> 16", to 16'.

#### **END OF ADDENDUM NO. 2**

This Addendum consists of twenty-one (21) pages plus three (3) pages of attachments.

NO TEXT ON THIS PAGE



### Department of Transportation

JANETTE SADIK-KHAN, Commissioner

#### OCMC TRAFFIC STIPULATIONS

09.19.13

**OCMC FILE NO:** 

REC-13-284

CONTRACT NO:

SER002316

PROJECT:

CONSTRUCTION OF STORM, SANIRARY SEWERS ANDWATER MAIN IN WOODROW ROAD

LOCATION(S):

SEVERAL LOCATIONS STATEN ISLAND

PERMISSION IS HEREBY GRANTED TO THE NEW YORK CITY DEPARTMENT OF DESIGN AND CONSTRUCTION AND ITS DULY AUTHORIZED AGENT, TO ENTER UPON AND RESTRICT THE FLOW OF TRAFFIC AT THE ABOVE LOCATION AND ITS LOCAL ADJACENT STREETS FOR THE PURPOSE OF CARRYING OUT THE ABOVE NOTED PROJECT, SUBJECT TO THE STIPULATIONS, AS NOTED BELOW;

#### SPECIAL STIPULATIONS

- 1. BUS STOPS THE CONTRACTOR SHALL PROVIDE WRITTEN NOTICE TO NYC DOT OCMC AND NEW YORK CITY TRANSIT (NYCT) A MINIMUM OF FIVE (5) WEEKS IN ADVANCE FOR LANE/STREET CLOSURES THAT AFFECT BUS ROUTES/BUS STOPS.
- ACCESS TO ABUTTING PROPERTIES THE CONTRACTOR SHALL COORDINATE ALL ACTIVITIES WITH ABUTTING PROPERTY OWNERS TO ENSURE ACCESS IS PROVIDED TO/FROM ENTRANCES/DRIVEWAYS AT ALL TIMES.
- 3. AUTHORIZED PARKING PRIOR TO PERFORMING WORK WHICH IMPACTS AUTHORIZED PARKING, THE CONTRACTOR SHALL SUBMIT IN WRITING, AND COPY OCMC-STREETS, A REQUEST TO OCCUPY SPACE CURRENTLY USED BY AUTHORIZED VEHICLES. APPROVAL MUST BE RECEIVED FROM AUTHORIZED PARKING PRIOR TO OCCUPYING THESE AREAS.
- NOTIFICATION THE CONTRACTOR MUST AT LEAST TWO (2) WORKING DAYS BEFORE THE START OF CONSTRUCTION NOTIFY THE NYC FIRE DEPARTMENT, NYC POLICE DEPARTMENT, NYCEMS, LOCAL COMMUNITY BOARD, BOROUGH PRESIDENT'S OFFICE-CHIEF ENGINEER, NYCDOT OCMC OFFICE, AND ALL ABUTTING PROPERTY OWNERS.

#### **ENHANCED MITIGATIONS**

- O ENHANCED MITIGATIONS FOR PEDESTRIAN FLOW, INCLUDING METAL FENCING, SHALL BE PROVIDED TO ENSURE PEDESTRIANS STAY within their designated path/route, Flaggers shall be provided to assist with pedestrians at the designated crosswalk areas. THESE FLAGGERS SHALL BE ASSIGNED TO THIS FUNCTION ONLY.
- O VARIABLE MESSAGE SIGNS (VMS) SHALL BE PROVIDED FOR THIS PROJECT. THE LOCATIONS AND MESSAGES SHALL BE RECOMMENDED BY NYCDDC AND THEIR CONTRACTOR A MINIMUM OF TWO (2) WEEKS PRIOR TO WORK COMMENCING, FOR OCMC REVIEW AND APPROVAL.
- O "NO STANDING ANYTIME-TEMPORARY CONSTRUCTION" SIGNS AND TEMPORARY PAVEMENT MARKINGS SHALL BE INSTALLED AND MAINTAINED AS WARRANTED BY THE MAINTENANCE AND PROTECTION OF TRAFFIC (MPT) REQUIRED TO FACILITATE TRAFFIC MOVEMENTS THROUGH THE WORK ZONE. ALL TEMPORARY SIGNS AND PAVEMENT MARKINGS SHALL BE REMOVED UPON COMPLETION OF THE PROJECT.
- O COMMUNITY OUTREACH SHALL BE PROVIDED FOR THE DURATION OF THE PROJECT.

#### MAINTENANCE AND PROTECTION OF TRAFFIC SEWERS WORKS

#### WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND FOSTER ROAD WOODROW ROAD BETWEEN DESERRE AVENUE AND POWELL STREET

- Work hours shall be as follows: 7:00 AM to 6:00 PM, Monday through Friday.
- The contractor shall maintain 2 lanes for traffic all the time with proper approved MPT devices, 1 lane in each direction.
- The contractor shall provide and maintain either a 5 foot clear sidewalk or a 5 foot protected walkway in the roadway for the pedestrian access at all times.
- At intersections with cross street, the contractor shall maintain one 12 foot lane for local and emergency access in cross streets and 2 lanes for traffic, 1 lane in each direction on Woodrow Road.
- A School Construction Embargo will apply to Woodrow Road between Powell Street and Deserre Avenue, Work may occur only when school is not in a session from July 1 to September 1 of each year of the contract.

#### WOODROW ROAD BETWEEN GILROY STREET AND DESERRE AVENUE WOODROW ROAD BETWEEN FOSTER ROAD AND GILROY STREET

Work hours shall be as follows: 7:00 AM to 6:00 PM, Monday through Friday.

NYC Department of Transportation

reau of Permit Management and Construction Control

5 Water Street - 7th Floor, New York, NY 10041

T: 212.839.9621 F: 212.839.8970

www.nyc.gov/dot

09.19.13 Page 2 of 3

OCMC FILE NO: CONTRACT NO:

REC-13-284 SER002316

PROJECT:

CONSTRUCTION OF STORM, SANITARY SEWERS AND WATER MAIN IN WOODROW ROAD

 The contractor shall maintain 1-11 foot lane for 2 way traffic with flaggers at each end of work zone during working hours and maintain 2 lanes for traffic, 1 lane in each direction after working hours.

The contractor shall provide and maintain either a 5 foot clear sidewalk or a 5 foot protected walkway in the

roadway for the pedestrian access at all times.

 At Intersections with cross street, the contractor shall maintain one 12 foot lane for local and emergency access in cross streets and 1-11 foot lane for 2 way traffic with flaggers at each end of work zone during working hours on Woodrow Road.

ROSSVILLE AVENUE BETWEEN KRAMER AVENUE AND WOODROW ROAD FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR PLACE MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE VENUS PLASE BETWEEN MARCY AVENUE AND POWELL STREET WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE POWELL STREET BETWEEN WEST CASTOR PLACE AND DEAD END

Work hours shall be as follows: 7:00 AM to 6:00 PM, Monday through Friday.

The contractor shall maintain 1-12' lane for local and emergency traffic at all times.

- In areas where the roadway is not wide enough for an emergency lane, the contractor is permitted to close the roadway; however, the work area shall not exceed 100 linear feet at any given time, so that the N.Y. Fire Department/EMS and the N.Y. Police Department can have emergency access to the residents within the work zone. The work zone shall be the excavated trench including the equipment and stored materials necessary to perform the work.
- The contractor shall notify daily, in writing the N.Y. Fire Department/EMS, the N.Y. Police Department and the local Community Board, EMS as to the locations of the work zones and the layout plan for emergency access from either side of the work area. This notification shall be done using street and houses addresses and defining the nearest cross streets. Representatives of the local N.Y. Fire Department, the N.Y. Police Department EMS and the local Community Board shall acknowledge such notifications in writing.

• The contractor shall provide and maintain either a 5 foot clear sidewalk or a 5 foot protected walkway in the roadway for the pedestrian access at all times.

A School Construction Embargo will apply to Venus Place between Marcy Avenue and Powell Street. Work may
occur only when school is not in a session from July 1 to September 1 of each year of the contract.

#### WATER MAINS WORKS

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD POWELL STREET BETWEEN DEAD END AND WOODROW ROAD WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE

Work hours shall be as follows: 7:00 AM to 6:00 PM, Monday through Friday.

 The contractor shall maintain 1-11 foot lane on one-way streets and 2-11 foot lanes on two-way streets during working hours.

Full width of roadway shall be opened to traffic when site is unattended.

A School Construction Embargo will apply to Powell Street between Dead End and Woodrow Road. Work may
occur only when school is not in a session from July 1 to September 1 of each year of the contract.

#### **GENERAL NOTES**

- 1. **IHIS IS NOTA PERMIT.** THIS STIPULATION SHEET MUST BE SUBMITTED WITH ALL REQUESTS FOR PERMITS PERTAINING TO THE ABOVE CONTRACT AND PRESENT AT THE WORK SITE ALONG WITH ALL ACTIVE CONSTRUCTION PERMITS WHEN THE APPROVED WORK IS BEING PERFORMED.
- 2. ALL RELOCATION WORK BY THE UTILITIES SUCH AS; CON EDISON, TELEPHONE, GAS AND CABLE COMPANIES SHALL PRECEDE THE CONTRACTORS' START OF WORK ON ALL AFFECTED ROADWAYS IN THE IMPACTED CONTRACT AREA.
- THE CONTRACTOR IS ADVISED THAT OTHER CONTRACTORS MAY BE WORKING IN THE GENERAL AREA DURING THE TERM OF THIS STIPULATION. IN WHICH EVENT, THE CONTRACTOR MAY REQUIRE MODIFICATIONS BY THE OCMC-STREETS.
- 4. THE PERMITTEE IS NOT AUTHORIZED TO ENTER, OCCUPY OR USE ANY PUBLICLY-OWNED OR PRIVATELY OWNED, NON-PAVED, LANDSCAPE OR NON-LANDSCAPED LOCATION WITHOUT SPECIFIC WRITTEN PERMISSION. WHEN THE LOCATION IS WITHIN THE RIGHT-OF-WAY OF A LIMITED-ACCESS ARTERIAL HIGHWAY, WRITTEN APPROVAL FROM THE NYCDOT OCMC-HIGHWAYS IS REQUIRED. WHEN THE LOCATION IS WITHIN THE RIGHT-OF-WAY OF A PUBLIC STREET OR PUBLIC PARK, WRITTEN APPROVAL FROM THE NEW YORK CITY DEPARTMENT OF TRANSPORTATION OR NEW YORK CITY DEPARTMENT OF PARKS AND RECREATION IS REQUIRED. WHEN THE LOCATION IS WITHIN THE RIGHT-OF-WAY OF ANY OTHER JURISDICTION SUCH AS PRIVATE PROPERTY, STATE, FEDERAL ETC., IT IS THE PERMITTEE'S RESPONSIBILITY TO DETERMINE THE PROPERTY OWNER AND OBTAIN THE WRITTEN APPROVAL.

OCMC FILE NO:

REC-13-284

CONTRACT NO:

SER002316

PROJECT:

CONSTRUCTION OF STORM, SANITARY SEWERS AND WATER MAIN IN WOODROW ROAD

- 5. THE PERMITTEE SHALL ADHERE TO THE NYCDOT BUREAU OF BRIDGES' SPECIAL PROVISIONS FOR LANDSCAPE PROTECTION, MAINTENANCE AND RESTORATION, ITEMS 1, 18, 15 THROUGH 1, 18, 19, WHENEVER AND WHEREVER ANY OF THE PERMITTEE'S ACTIVITIES OCCUR WITHIN A LIMITED ACCESS ARTERIAL HIGHWAY RIGHT OF WAY.
- 6. NO DEVIATION OR DEPARTURE FROM THESE STIPULATIONS WILL BE PERMITTED WITHOUT THE PRIOR WRITTEN APPROVAL FROM THE OCMC-STREETS. REQUEST FOR SUCH MODIFICATIONS SHALL BE SUBMITTED TO THE OFFICE OF THE OCMC-STREETS, NEW YORK CITY DEPARTMENT OF TRANSPORTATION, A MINIMUM OF TWENTY (20) DAYS IN ADVANCE FOR CONSIDERATION.
- 7. FOR THIS PROJECT THE CONTRACTOR SHALL FURNISH, INSTALL AND MAINTAIN ALL NECESSARY ADVANCE WARNING AND DETOUR SIGNS, TEMPORARY CONTROL DEVICES, BARRICADES, LIGHTS AND FLASHING ARROW BOARDS IN ACCORDANCE WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES," THE TYPICAL SCHEMES INCLUDED IN THIS SPECIFICATION; AND AS ORDERED BY THE ENGINEER-IN-CHARGE AND THE OCMC-STREETS.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IDENTIFYING HIS CONSTRUCTION SIGNAGE, THE IDENTIFICATION SHALL INCLUDE THE CONTRACTOR'S NAME, SPONSORING AGENCY NAME AND THE CONTRACT NUMBER. THE IDENTIFICATION SHALL BE PLACED ON THE BACK OF THE SIGN. THE LETTERING SHALL BE THREE (3) INCHES HIGH.
- 9. THE OCMC-STREETS RESERVES THE RIGHT TO YOLD OR MODIFY THESE STIPULATIONS SHOULD CONSTRUCTION FAIL TO COMMENCE WITHIN TWO (2) YEARS OF THE SIGNED DATE OF THESE STIPULATIONS.
- 10. THE CONTRACTOR MUST COMPLY WITH ALL CONSTRUCTION EMBARGOS ISSUED BY THE NYCDOT INCLUDING THE HOLIDAY EMBARGO.

JOSEPHP, NORO

EXECUTIVE DIRECTOR

DOUBLES STREETS

IRMA TIAGUNSKY
PROJECT MANAGER

OCMC-STREETS

#### ATTACH TO CONTRACT DOCUMENTS

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION INFRASTRUCTURE DIVISION BUREAU OF DESIGN

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN
WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

**INCLUDING WATER MAIN WORK** 

**Together With All Work Incidental Thereto** 

**BOROUGH OF STATEN ISLAND** 

ADDENDUM NO. 2

DATED: February 25, 2014

This Addendum is issued for the purpose of amending the requirements of the Contract Documents and is hereby made part of said Contract Documents to the same extent as if it was originally included therein.

GAS COST SHARING (EP-7) STANDARD SPECIFICATIONS

### **EP-7 GAS COST SHARING STANDARD SPECIFICATIONS**

#### **TABLE OF CONTENT**

#### I - NOTICE TO ALL BIDDERS; GAS COST SHARING WORK

#### II - GENERAL PROVISIONS; GAS COST SHARING WORK

- 1. General
- 2. Gas Interferences And Accommodations2a. Water Main Accommodations2b. Sewer Accommodations
- 3. Quantity Overruns, EP-7 Funded Bid Items
- 4. Changes And Extra Work
- 5. Excavation
- 6. Backfilling And Street Restoration
- 7. Non-Responsive Bids
- 8. Minimum Clearances
- 9. Work By Facility Operator
- 10. Materials Furnished By Facility Operator
- 11. Liability And Insurance
- 12. Width And Depth Of Excavation
- 13. Depth And Crossing Angles Of Gas Facilities
- 14. Maintenance Of Traffic For Gas Work
- 15. Relocated Gas And Temporary Systems Installation
- 16. Role Of Company Inspector
- 17. Coordination With Gas Company

#### **III - TECHNICAL SECTION**

- SECTION 6.01 Trench Crossings; Support And Protection Of Gas Facilities And Services.
- SECTION 6.02 Extra Excavation For The Installation Of Catch Basin Sewer Drain Pipes With Gas Interferences.
- SECTION 6.02.1 Extra Excavation For The Installation Of Catch Basin Sewer Drain Pipes With Upstream Inverts Greater Than Six (6) Feet.
- SECTION 6.03 Removal Of Abandoned Gas Facilities. All Sizes.
- SECTION 6.03.1 Removal Of Abandoned Gas Facilities With Possible Coal Tar Wrap. All Sizes.
- SECTION 6.04 Adjust Hardware To Grade Using Spacer Rings/Adaptors. (Street Repaving.)
- SECTION 6.05 Adjust Hardware To Grade By Resetting. (Road Reconstruction.)
- SECTION 6.06 Special Care Excavation And Backfilling.
- SECTION 6.07 Test Pits For Gas Facilities.

#### IV - STANDARD SKETCHES; GAS COST SHARING WORK

- NO. 1 Support Requirements For Gas Mains And Services Crossing Excavation Greater Than 4'0" Wide At Any Angle
- NO. 1A Support Requirements For Gas Mains Over 16" Diameter Up To And Including 48" Diameter Crossing Excavation At Any Angle
- NO. 2 Typical Methods Of Measurement For Gas Crossings
- NO. 3 Utility Crossings During Catch Basin Chute Connection Pipe Installation
- NO. 4 Utility Crossings During Catch Basin Chute Connection Pipe Installation (Extra Depth)
- NO. 5 Gas Main Encroachment On And/Or Parallel To Excavation Of Unsheeted Trench

#### V - PRELIMINARY GAS WORK TO BE PERFORMED BY FACILITY OPERATOR

#### VI - LISTING OF APPROXIMATE LOCATIONS OF EP-7 BID ITEMS QUANTITIES

### I - NOTICE TO ALL BIDDERS; GAS COST SHARING WORK

All prospective bidders are hereby advised that, pursuant to the "Gas Facility Cost Allocation Act", ("the Act"), the City of New York has entered into an agreement ("the Agreement") with the gas companies (Con Edison or National Grid (formerly KeySpan Energy Delivery)) operating in their respective areas of the City to "share" the cost of facility relocation and/or support and protection of facilities disturbed by proposed water and/or sewer and related City work specified in this contract. Therefore, bid items, specifications and estimated quantities for the incremental costs of support and protection of certain gas facilities have been included in this contract. The low bid for this contract shall be determined by examining each bid for all work to be performed under this contract including any work of support and protection of gas facilities to be performed. The Contractor shall not seek additional compensation from gas companies except as specifically set forth in its contract.

### II - GENERAL PROVISIONS; GAS COST SHARING WORK

#### 1. General:

The Contractor shall perform City work with interferences from existing live and abandoned gas facilities. This shall be defined as utility work. Therefore, this contract includes bid items, specifications and estimated quantities designed to fully compensate him/her for the incremental costs of supporting, protecting, providing accommodations and, avoiding disturbing gas facilities located in the streets shown on the contract drawings. In the event that any other provisions of this contract related to gas facilities (or private utilities) conflict with these provisions, these provisions shall supersede and govern all work related to gas facilities owned by the companies operating in the project area. All utility work, as defined in these specifications, including changes and additions thereto shall be paid solely by the City except when specified otherwise in this contract. Contractor hereby agrees that the facility operator shall not be liable to pay him/her for any work performed including extra utility work. Contractor agrees that its bid prices include all compensation for loss of productivity and efficiency, idle time, delays (including any delays occasioned by negotiation of a contract change), change in operations, mobilization, demobilization, remobilization, added cost or expense, lost of profit, other damages or impact costs that may be suffered by or because of utility work, or the presence of gas facilities in the proximity of City work and that it will not seek additional compensation for these items. All disputes shall be resolved as specified in the contract.

Pursuant to the Act, Agreement, and the New York City Administrative Code, the gas company(ies) has been directed by the Commissioner and is required to perform all maintenance, repairs, replacement, shifting, alteration, relocation, and/or removal work that are not part of this contract. By having bid on this contract, the Contractor understands and agrees that the Commissioner has preasserted any right the City has to require, including the issuance of any directives or so called "order outs" under the New York City Administrative Code, any or all gas companies to maintain, repair, replace, protect, support, shift, alter, relocate, and/or remove all gas facilities that are about to be disturbed by the City contract work. The issuance of additional such directives during the performance of the contract work, where necessary in the sole judgment of the Commissioner, shall be initiated by such Commissioner as set forth in the relevant sections of the Act and Agreement. Contractor further agrees to insert such requirements as set forth herein above into any contracts with its approved subcontractors so that its subcontractors also understand and agree to such contract requirements.

#### 2. Gas Interferences And Accommodations:

During the performance of sewer and water main work funded by the New York City Department of Environmental Protection (NYCDEP), as instructed by the Engineer, the use of any applicable contract bid item is allowed in order to resolve and accommodate all gas facilities interferences with such City work, including the removal of contaminated soil in associated trench excavation. This is in addition to the specified EP-7 bid items in the contract. Payment for such accommodation shall be funded by EP-7 bid item "UTL-GCS-2WS - GAS INTERFERENCES AND ACCOMMODATIONS" (F.S. Fixed Sum). The value of such accommodation shall be computed by multiplying the appropriate unit prices bid to the quantity of work performed, as determined by the Engineer, and applying the total amount thus to be paid

A3-3

to EP-7 bid item "<u>UTL-GCS-2WS - GAS INTERFERENCES AND ACCOMMODATIONS</u>". When EP-7 bid item "<u>UTL-GCS-2WS - GAS INTERFERENCES AND ACCOMMODATIONS</u>" does not exist, such additional accommodation work shall be at no cost to the City but shall be a matter of adjustment between gas facility operator and Contractor. Private facilities, other than gas, that become in interference due to gas interferences accommodations shall also be accommodated, if so directed by the Resident Engineer, at no additional cost to the City and, provided that its owner agrees to be responsible for all additional costs to Contractor, otherwise, such facility shall be ordered by the City to be maintained, shifted, relocated or replaced by its owner at his/her expenses.

#### 2a. Water Main Accommodations:

When water main construction is to be performed in this contract, Contractor shall be required, if warranted by field conditions, and at locations designated by the Resident or Borough Engineer, to change the vertical or horizontal alignment of water mains including but not limited to all additional labor, material, work method accommodations, furnishing, delivering and laying offset fittings and pipes, etc., necessary in order to complete water main installation and, avoid gas interferences in the project area, including street intersections. Typical work method accommodations shall include, but not be limited to, pier and plate, installation of filter fabric and select fill, etc. Such work shall be performed as directed by the Engineer and in accordance with contract specifications and latest edition of water mains standards and specifications.

#### 2b.Sewer Accommodations:

When sewer construction is to be performed in this contract, Contractor shall be required, if warranted by field conditions, and at locations designated by the Resident or Borough Engineer, to change the horizontal alignment of sewer facilities (if possible) including but not limited to all additional labor, material, work method accommodations, furnishing, delivering and construction of additional manholes or modification of manholes/catch basins, extending chute connections, house connections, using alternate materials and methods, poured-in-place structures, etc., necessary in order to complete sewer installation and, avoid gas interferences in the project area, including street intersections. The term sewer facility shall include, but not be limited to, all sewer pipe and appurtenances, manholes, catch basins, catch basin chutes, etc. Such work shall be performed as directed by the Engineer and in accordance with contract specifications and latest edition of sewer standards and specifications.

#### 3. Quantity Overruns, EP-7 Funded Bid Items:

No quantity overrun, in excess of one hundred twenty five (125) percent, shall be permitted for EP-7 funded-bid items (gas) included in this contract, except when Resident Engineer determines that such overruns are caused by field modifications to planned City work, or approved construction methods, or contract scope changes. Overruns not paid by City shall be negotiated and paid to Contractor by gas facility operator who then shall be entitled to reimbursement by NYCDEP under established cost sharing procedures.

#### 4. Changes And Extra Work:

This section is not applicable to work defined under "Emergency Reconstruction Contracts" or so-called "Where and When Contracts" since these projects, by definition, inherently encounter unanticipated gas facilities and cannot be pre-engineered. In all other cases, any contract changes proposed for City work shall also cover and include all associated changes to support and protection of gas facilities affected by such changes to City work. In all other cases where the Contractor finds that City work cannot be performed as planned and specified and/or, as approved because of a need to support, protect and/or alleviate interferences from gas facilities that were not listed and/or shown, or incorrectly shown in contract plans and specifications, he shall immediately notify the Resident Engineer and the facility operators' representative of his findings. Resident Engineer shall promptly examine such claims and determine whether or not such work is covered by contract bid items and /or specifications (contract bid items and specifications shall include city contract items as well as EP-7 items). The Resident Engineer shall also examine the claim to determine if the application of EP-7 bid item "UTL-GCS-2WS - GAS INTERFERENCES AND ACCOMMODATIONS" is appropriate to resolve the claim. If upon examination, the Engineer determines that such field conditions were unanticipated (not shown and/or listed, or incorrectly shown in contract documents) and are not covered by bid items and contract specifications, he shall then direct the Contractor and the affected facility operator to negotiate the cost of supporting and

protecting, and/or alleviating the impact on City work caused by such unanticipated gas facilities with each other with the understanding that the performance of City work shall continue during negotiations. If a cost agreement is reached, the Contractor and facility operator shall adjust such costs between themselves at no additional costs to the City contract. If the Contractor and affected facility operator do not reach an agreement concerning the price to be paid for the extra work within five (5) business days of the Engineer's directive to engage into such negotiations and, after considering: public safety and inconvenience, requirements of laws and regulations applicable to private utilities, integrity of all utility systems, including but not limited to sewer and water, gas, electric, telephone and, cable TV facilities, sound engineering practices, cost (long and short term) to all affected parties, and potential City work delays, then the Resident Engineer, depending on nature and severity of interferences with City work, shall either, direct the facility operator to relocate or replace its facilities at its own discretion and cost, reimbursable by NYCDEP under established gas cost sharing procedures or, direct the Contractor to perform the utility work on actual time, material and equipment costs basis pursuant to relevant contract requirements and amendments. Contract bid prices for any applicable items of work involved shall be applied, or converted to an allowance for time and material charges. Changes shall be for affected portions of utility work and, shall be processed with EP-7 funds.

#### 5. Excavation:

All excavators shall notify the NYC/LI One Call Center at 1-800-272-4480 at least two (2) working days, not including the day of the call, but not more than ten (10) working days in advance of the start of any excavation work. The gas company(ies) will mark out its facilities within the project limits and provide Construction Inspector(s) during all excavation work in close proximity (within twelve (12) inches) to gas facilities. The Contractor shall exercise extreme caution when excavating in the vicinity of any gas facilities. Hand excavation shall be performed within twelve (12) inches of gas facilities. The Contractor prior to excavating underneath these facilities shall adequately support all gas facilities. Standard support details for gas facilities have been included in the specifications. Any damage to gas facilities shall be reported immediately to the gas company(ies). The Contractor shall be responsible for all cost associated with repairs made necessary by damages caused by his operations.

#### 6. Backfilling And Street Restoration:

Backfilling operations and street restorations shall be in accordance with contract requirements.

#### 7. Non-Responsive Bids:

Every gas (EP-7) bid item has a suggested "Not less than" value per unit indicated on contract bid sheet. Bids resulting in cost of less than suggested for EP-7 items are hereby prohibited and if submitted shall be considered NON-RESPONSIVE.

#### 8. Minimum Clearances:

Clearance requirements for City work shall govern and supersede any clearance requirement of gas facility operator. Therefore, a minimum of twelve (12) inches clearance between private utilities and City water mains, sewers or related structures to be installed in this contract shall be maintained. When this clearance is not attainable, the Resident Engineer may allow a minimum of four (4) inches clearance. With less than twelve (12) inches clearance a neoprene/polyethylene shield (to be provided by facility operator) shall be installed as part of all work item specifications. However, if Resident Engineer determines that City work cannot be performed within allowable clearance and no reasonable City accommodation (no-cost change to City work) is possible, the City shall direct the facility operator to remove, relocate, shift, or alter their facility(ies) pursuant to the New York City Administrative Code.

#### 9. Work By Facility Operator:

The facility operator may find it necessary to perform the following types of work during performance of City work: accommodating a contractor's request for gas facilities modifications (in order to facilitate City contractor's proposed construction method) or, remedial and emergency work on gas facilities proper with their own resources and materials if an approved method of construction for City work causes unanticipated disturbances to gas facilities or, replacing defective gas facilities when they are exposed by the Contractor and their actual conditions are observable by the facility operator. Also included in the above category of defective gas facilities are: the presence of environmental contaminants attributable to

the gas facility in or around gas facilities. If such work is deemed required by the facility operator or if facility operator is directed by the City to address such deficiencies at any time during the course of construction, the Contractor shall modify the construction schedule at no cost to the City and allow the facility operator five (5) business days to perform such work without interferences. Additional costs to the facility operator (in cases of accommodations) or, Contractor (in cases of defective gas facilities) due to such gas work, if any, shall be the responsibility of the parties involved and not of the City. Such costs shall be a matter of adjustment between the Contractor and the facility operator.

#### 10. Materials Furnished By Facility Operator:

It shall be the Contractor's responsibility to inspect material to be installed by him immediately upon delivery and advise the facility operator through its authorized representative, of all damaged materials. The Contractor at no additional costs to the City or the facility operator shall replace any material that is damaged or lost after the Contractor's inspection.

#### 11. Liability And Insurance:

Notwithstanding the provisions of this contract, the existing division of liabilities to third parties shall remain the same as between the City and the company. Therefore, it is specifically agreed by the City, company and Contractor (by bidding on this contract) that for the purpose of any liabilities to third parties, that the City contractor performing work directly and physically relating to gas company facilities in this project, shall be deemed an agent of the company and not an agent of the City, the New York City Municipal Water Finance Authority, or the New York City Water Board. Contractor shall include the company as an additional insured on all insurance policies maintained to comply with the City's insurance requirements.

#### 12. Width And Depth Of Excavation:

Contractor shall not be authorized to deliberately change trench or excavation widths and/or depth specified without Engineer's approval. Enlargement of any side of excavation up to eighteen (18) inches beyond pay limits (or inside face of sheeting) requested by the Contractor for the installation of certain types of sheeting may be granted. However, such enlargements or those greater than allowable shall not be approved when, in the sole judgment of the City, field conditions allow the water mains and sewer work to be performed within the limits specified and, the sole purpose of such enlargement request is to impact adjacent utilities (public or private) whose support and protection are part of this contract. Any approval shall be given at no additional cost to the City contract, including EP-7 funding, and all costs associated with unauthorized enlargements shall be the sole responsibility of the Contractor.

#### 13. Depth And Crossing Angles Of Gas Facilities:

Where gas facilities are shown (or specified as) crossing proposed alignment of sewers, water mains, catch basins and chute connections or any other proposed excavations at specific angles (as measured off plans or sketches or specified in contract), it shall be understood that actual field measurements may deviate (plus or minus) forty-five (45) degrees from those shown or specified. The cover, or depth from street surface to top of facilities, shall be as shown or specified in contract documents, no deviation is to be assumed. Where gas facilities are not shown on contract documents, but their support and protection are otherwise included in this contract then, all references to facilities crossing at "various angles and depth" in the gas sections shall mean that such facilities are crossing sewer, water, catch basin and, catch basin chute, and other excavations at a ninety (90) degree angle to the proposed sheeting line or side of excavation (for unsheeted trenches) with an allowable deviation of forty-five (45) degrees in any direction, except for catch basin chute excavation where the allowable deviation shall be sixty (60) degrees. Where the cover is not noted or specified, the bottom face of such facilities shall be assumed to be crossing catch basin chutes at a depth of three (3) foot eight (8) inches or less from the street surface. Paragraph No. 2 above shall apply in cases of distribution water main construction. Appropriate bid items and specifications are provided for cases where angle and depth are greater than stated above. This section also applies to work defined in "Emergency Reconstruction Contracts" or so-called "Where and When Contracts". These contracts are not pre-engineered and consequently have no drawings, sketches or determined locations and so, gas facilities encountered will be crossing existing and proposed sewer. water, catch basin/catch basin chutes and all appurtenances at various angles and depths.

#### 14. Maintenance Of Traffic For Gas Work:

All work pertaining to gas bid items and specifications shall be performed within the contract maintenance of traffic plan as specified in the contract document. The bid price for the Maintenance and Protection of Traffic shall cover all work pertaining to gas items. The City shall make compensation for additional maintenance and protection of traffic items in connection with gas item of work only when such additional work is deemed reasonable and necessary by the Resident Engineer and is approved by him prior to its performance.

#### 15. Relocated Gas And Temporary Systems Installation:

In cases where the Contractor is allowed to select the location for temporary construction such as, installation of dewatering headers, wells, well points, etc., he shall not disturb any gas facilities shown on sketches provided in this section. The only exception shall be, if the affected gas company agrees to such relocation and provided that the cost of such relocation is a matter of adjustment between the company and Contractor, and at no cost to the City.

#### 16. Role Of Company Inspector:

In any case in which the City elects to perform some or all support and protection work with its own employees, personnel or contractors, the facility operator shall provide onsite inspectors to approve and certify such support and protection work (exclusive of City accommodations) performed by the City's own employees, personnel, and contractors. Facility operator's inspectors are not authorized to direct City contractor during the performance of contract work. They shall act through the City Resident Engineer and provide him/her required approvals and certifications, prior to preparing partial payments of EP-7 items, in a format and frequency to be prescribed by the appropriate City Head of Construction.

#### 17. Coordination With Gas Company:

The Contractor shall be required to notify the gas company(ies), in writing, at least two (2) weeks prior to the start of final paving in order to allow companies to complete any unfinished gas work located within the area to be paved. Every effort shall be made to maintain gas service with minimum inconvenience to the public.

#### III - TECHNICAL SECTION

SECTION 6.01 - Trench Crossings; Support And Protection Of Gas Facilities And Services.

### 1. Description:

Under this section, the Contractor shall provide all labor, materials, equipment, and incidentals required to support and/or protect the integrity of gas mains, services and appurtenances of any sizes, configurations, and operating pressures crossing trench excavations above subgrade for planned construction of sewers and water mains facilities. A gas service shall be defined as a gas pipe of three (3) inches in diameter or less branching from the main to a customer pick up point or property valve box. A gas main may be any size pipe that is part of a distribution or transmission network other than services described above. Crossings shall be defined as gas facilities spanning the width of excavation (one side to the other side). These crossings may be at various angles and depth as shown on "Gas Cost Sharing Work Standard Sketches Nos. 1 and 1A", and as specified in "General Provisions; Gas Cost Sharing Work Paragraph No. 13" and, at the locations shown or listed in contract documents. The gas company operating in the area, (facility operator), owns these facilities. The work shall be performed in accordance with contract specifications, plans, and at the directions of the Resident Engineer in consultation with the authorized representatives of the facility operator.

#### 2. Method Of Construction:

- A. Protection: In general, the gas facilities shall be protected as required by New York State Industrial Code 753. In particular, the Contractor shall use hand excavation methods (pick and shovel or hand held power tools) directly below the pavement base to expose the gas facilities (marked out by facility operators) and to ascertain the clearances and cover of the facilities with respect to the proposed excavation. Upon exposing the affected facilities sufficiently, at the discretion of the Resident Engineer, to ascertain the foregoing, Contractor shall be permitted to proceed with a combination of hand and machine excavation, as appropriate, outside a zone of protection whose limit shall be defined as a perimeter located twelve (12) inches from the outside face of each gas facility crossings (See "Gas Cost Sharing Work Standard Sketch No. 2"). If the facilities are in direct interference with City work, meaning that "Minimum Clearances" described in "General Provisions; Gas Cost Sharing Work Paragraph No. 8" cannot be maintained, and excavation has to be temporarily or permanently abandoned then this particular location shall become a test pit and dealt with as specified in Section 6.07, and "General Provisions; Gas Cost Sharing Work Paragraphs Nos. 2 and 8".
- B. Support: Gas mains or services crossing excavations equal or less than four (4) feet wide are generally self supporting, unless field conditions as determined by the Resident Engineer require otherwise. The support requirements for gas mains and services crossing excavations greater than four (4) feet wide shall be as shown on the attached "Gas Cost Sharing Work Standard Sketch No. 1" and Contractor shall use sheeting methods that permit the maintenance of gas facilities in their existing locations and configurations. Alternate methods equivalent to those shown on the sketch or accommodations by the facility operator proposed by the Contractor in order to facilitate the execution of the specified work shall be allowable, provided that prior approval is obtained by the Contractor from the Engineer and the facility operator. The support and protection of gas facilities crossings shown on plans, drawings, listings or otherwise identified in this contract shall not be circumvented with the issuance of so called "order outs".

#### 3. Method Of Measurement:

The Contractor shall be paid for supporting and/or protecting gas facilities crossing trench excavations under the appropriate bid items covered by this section. The Contractor shall be directly responsible to the facility operator for the total cost of using any alternate method requiring the use of resources owned by the facility operator. Regardless of the method used, the City shall pay the bid price for the appropriate support and/or protect item of work. The average rate charged by the facility operator for alternate support and protection work such as, disconnecting and reconnecting gas services is listed in attached "Schedule GCS-A".

#### 4. Payment Restrictions:

These items shall not be paid for: gas services crossing unsheeted water main trench excavation; abandoned gas main/services identified by facility operator; gas mains/services crossing trench excavations for fire hydrant branch connections pipes, catch basins and/or chutes (sewer drain pipe), house sewer and/or water services; gas facilities encroaching any face of excavation for sewer and/or water construction, all of which are covered under other contract sections. Also this item shall not be paid for new gas mains and services crossing water trenches when trenching for such new facilities has been performed by the Contractor in common with trench excavation for City work (overlapping trench limits). The cost of supporting and protecting such gas facilities crossings shall be deemed included in the cost of trench excavation for the new gas facilities. This payment restriction shall apply even if such common trench gas excavation is not part of the contract. The prices bid for items covered by this section represent full compensation to Contractor to completely perform the work described. No other bid items shall be combined with these items in order to pay for gas main and/or services crossing excavations specified herein.

#### 5. Method Of Payment:

Each (Ea.) gas facility crossing trench excavation as described in these specifications shall be counted for payment.

#### 6. Price To Cover:

The cost of timber/steel supports installed for gas facilities shall be included in the bid price. The bid price for each crossing shall also cover all additional supervision, labor, material (except those provided by the facility operator), equipment and insurance necessary to completely maintain the gas facilities without disruption of service to the customers and in accordance with contract plans, specifications and facility operator standards. The price shall also include: changes of method of operations; sheeting modifications where necessary to accommodate the gas facilities crossings; installation and removal of water pipe under gas facilities (so called "snaking"); extra care during excavation (including hand excavation under existing single and multiple gas facilities); extra backfilling and compaction around, over and under gas facilities; installation and removal of sheeting around gas facilities; associated maintenance and protection of traffic; barricades; and traffic plates that may be required to temporarily close and/or complete the work.

# SECTION 6.02 - Extra Excavation For The Installation Of Catch Basin Sewer Drain Pipes With Gas Interferences.

#### Description:

Under this item, the Contractor shall provide all labor, materials, equipment, insurance, and incidentals for the extra excavation associated with the installation of catch basin sewer drain pipes (chute) under gas facilities of various sizes crossing the trench excavation at various angles and depth at the locations shown in the contract documents and also, for the support and protection of these facilities during associated excavation and backfill operations. The gas company operating in the area, (facility operator), owns these facilities.

#### Method Of Measurement:

The bid price shall be per location (Each) where extra excavation is required when catch basin sewer drain pipes are installed at an upstream invert depth lower than four (4) feet (up to a maximum of six (6) feet) from the proposed pavement grade because the bottom faces of interfering gas mains and appurtenances are located at a depth greater than three (3) foot eight (8) inches from proposed pavement surface (See "Gas Cost Sharing Work Standard Sketch No. 4").

#### 3. Method Of Construction:

Incremental cost responsibility for chute excavation is determined by the first private facility encountered starting from catch basin structure proper and that prevents the installation of the chute connection at an upstream cover less than or equal to three (3) feet or any other minimum cover required to avoid City facilities (e.g. water, sewer, etc.) as directed by the Resident Engineer.

#### 4. Payment Restrictions:

This item shall not apply and related bid item shall not be paid in cases where:

- A. Upstream invert chute is more than six (6) feet deep because of gas facilities.
- B. Chute cannot be installed above existing gas facilities because of interferences with other private facilities that are not otherwise covered under this contract, regardless of upstream invert depth.

The above cases shall be at no cost to the City, but shall be a matter of adjustment between the Contractor and the facility operator(s).

#### 5. Price To Cover:

The bid price shall cover the additional cost of all additional supervision, labor, materials, equipment and insurance, to complete the installation of catch basins and associated sewer connections in accordance with the contract plans and specifications. The price shall include: excavation by hand around and under single and multiple gas facilities; locating, supporting and protecting gas facilities; backfilling and all other items necessary to perform all work incidental thereto including: installation and removal of drain pipe under gas facilities ("snaking"); widening of trenches to facilitate the above work; subsequent additional

backfill and pavement restoration; modifying precast catch basin window to accommodate connection; changing sheeting method and configuration to accommodate gas facility crossings; maintenance and protection of traffic; barricades; and installation of traffic plates that may be required to temporarily close and/or complete the work. The price shall not include removal of ledge rock and/or excavation of boulders in open cut.

# SECTION 6.02.1 - Extra Excavation For The Installation Of Catch Basin Sewer Drain Pipes With Upstream Inverts Greater Than Six (6) Feet.

#### 1. Description:

Under this item, the Contractor shall provide all labor, materials, equipment, insurance and incidentals for the extra excavation of catch basin chutes where the upstream invert is greater than six (6) feet under gas facilities of various sizes crossing the trench excavation at various angles and depth at the locations shown in the contract documents or as determined by field conditions and also, for the support and protection of these facilities during the associated excavation, sheeting and backfilling operations.

#### 2. Method Of Measurement:

The bid price shall be per location (Each) where extra excavation and sheeting is required when the catch basin chute installed at an upstream invert depth lower than six (6) feet from the proposed pavement grade because the bottom faces of the interfering gas mains and appurtenances are located at a greater depth than three foot eight inches from the proposed pavement surface only.

#### 3. Method Of Construction:

Incremental cost responsibility for chute excavation is determined by the first private facility encountered during such excavation when initiated from catch basin structure and that prevents the installation of the chute at an upstream cover less than or equal to three (3) feet or any other cover required to avoid City facilities as directed by the Resident Engineer.

#### 4. Payment Restriction:

This item shall not apply and related bid item shall not be paid in cases where:

Upstream invert chute is less than or equal to six (6) feet deep because of gas facilities. Section 6.02 shall be paid.

#### 5. Price To Cover:

The bid price shall cover the additional cost of all supervision, labor, materials, equipment and insurance to complete the installation of catch basin and associated sewer connections in accordance with the contract plans and specifications. The price shall include: excavation by hand around and under single and multiple gas facilities; locating, supporting and protecting gas facilities incidental thereto; widening of trenches to facilitate the above work; subsequent additional backfilling and pavement restoration; modifying pre-cast basin window to accommodate connection; the installation of catch basin with deeper sumps as specified; additional sheeting and changes in sheeting method and configuration to accommodate gas facility crossings; maintenance and protection of traffic; barricades; and installation of traffic plates that may be required to temporarily close and/or complete the work.

#### SECTION 6.03 - Removal Of Abandoned Gas Facilities, All Sizes.

#### 1. Description:

Under this section the Contractor shall provide all labor, materials, equipment, insurance and, incidentals required for the removal of abandoned gas mains, services, or appurtenances thereof, located within the street shown on the contract plans, owned by gas company operating in the project area (facility operator), used or to be used for or in connection with or to facilitate the conveying, transportation, distribution or

furnishing of gas (natural or manufactured or mixture of both) for light, heat, or power, but does not include property used solely for or in connection with business of selling, distributing or furnishing of gas in enclosed containers. Such removal shall include only abandoned gas facilities that interfere with (i.e. cause additional work) City work.

#### 2. Determination Of Operating Status Of Gas Facilities:

The Contractor shall notify facility operator, as required by New York State Industrial Code 753. Gas facilities shall not be removed without the approval of the facility operator whose authorized representative shall certify in writing (specific facility or area wide facilities certification) and in a timely manner acceptable to the Resident Engineer that abandoned facilities are free of combustible gas and any other environmental contaminants prior to removal. The Resident Engineer shall rely on facility operator's certification. The facility operator may request the excavation of test pits (See Section 6.07) for this determination ahead of City work and, Contractor shall provide safe access, facilitate and permit facility operator to enter test pit excavations for the purpose of testing gas facilities to be removed by the Contractor. However, facility operator may prefer to make this test during performance of City work, in order to issue the above certification. This shall be permitted provided that it is agreed that additional costs, if any resulting from this choice shall be a matter of adjustment between the Contractor and facility operator only, and at no cost to the City.

#### 3. Restrictions:

The facility operator shall be solely responsible for its contaminated gas facilities, surrounding contaminated soil and their disposal and abatement procedures, unless contract bid items are applicable and provided for such work. In such cases, the quantity removed shall be charged to EP-7 bid item "<u>UTL-GCS-2WS - GAS INTERFERENCES AND ACCOMMODATIONS</u>" at the City bid prices.

#### 4. Method Of Measurement:

Abandoned gas pipeline removal shall be measured for payment per linear foot of pipe and appurtenances removed.

#### 5. Price To Cover:

The price shall cover all additional cost of supervision, labor, materials, equipment, and insurance necessary to complete this work in accordance with the contract plans and specifications, including excavation by hand around and under other City and facility operator owned properties and, where necessary, support and protection of such properties. The price shall also cover breaking, cutting, and/or burning of abandoned gas pipes and their disposal from the site; sealing open ends remaining in the excavation with concrete or caps (caps to be provided by the facility operator) and backfilling of the area where the pipeline has been removed with clean backfill. The price shall also include any required dump charges. This item does not include any type of extra excavation, backfilling, compaction, pavement removal and restoration associated with abandoned gas facilities removal, all of which are covered under Section 6.06.

# SECTION 6.03.1 - Removal Of Abandoned Gas Facilities With Possible Coal Tar Wrap. All Sizes. (For National Grid Work Only)

#### 1. Description:

Under this section the Contractor shall provide all labor, materials, equipment, insurance and, incidentals required for the removal of abandoned gas mains, services or appurtenances thereof, located within the street shown on the contract plans, owned by the gas company operating in the project area (facility operator), used or to be used for or in connection with or to facilitate the conveying, transportation, distribution or furnishing of gas (natural or manufactured or mixture of both) for light, heat, or power, but does not include property used solely for or in connection with business of selling, distributing or furnishing of gas in enclosed containers. Such removal shall include only abandoned gas facilities that interfere with (i.e. cause additional work) City work. These gas facilities may be coated with Coal Tar Wrap and so, may require special handling and disposal methods as specified in National Grid Standard Operating Procedure 12-2, Coal Tar Wrap Handling and 12NYCRR56.

#### 2. Determination Of Operating Status Of Gas Facilities:

The Contractor shall notify facility operator, as required by New York State Industrial Code 753. Gas facilities shall not be removed without the approval of the facility operator whose authorized representative shall certify in writing (specific facility or area wide facilities certification) and in a timely manner acceptable to the Resident Engineer that abandoned facilities are free of combustible gas and any other environmental contaminants prior to removal. The Resident Engineer shall rely on the facility operator's certification. The facility operator may request the excavation of test pits (See Section 6.07) for this determination ahead of City work and, the Contractor shall provide safe access, facilitate and permit facility operator to enter test pit excavations for the purpose of testing gas facilities to be removed by the Contractor. However, the facility operator may prefer to make this test during performance of City work, in order to issue the above certification. This shall be permitted provided that it is agreed that additional costs, if any, resulting from this choice shall be a matter of adjustment between the Contractor and the facility operator only, and at no cost to the City contract. Should such investigation result in the determination that the abandoned gas facilities do not contain Coal Tar Wrap then the removal of said facilities shall be covered under separate item (See Section 6.03).

#### 3. Requirements:

The City Contractor shall excavate abandoned gas facility sufficiently, either in its entirety, or at locations determined by Contractor to allow the removal of Coal Tar Wrap (if present on the abandoned gas facility) and to facilitate the safe extraction of manageable lengths of abandoned pipe without damage to adjacent facilities, utilities or City structures either parallel to or crossing above or below abandoned gas facility. The Contractor is to allow access to the designated cutting points within the Contractor's trench by authorized National Grid personnel who will remove the Coal Tar Wrap as per National Grid procedures. This work by National Grid personnel shall be performed in a timely fashion and shall not unduly impede the Contractor's progress and/or productivity. Upon completion of the coating removal, the Contractor shall be allowed to cut, burn or grind the gas facility and remove the section of abandoned pipe. The Contractor at a site designated by the Contractor shall stockpile the removed pipe. The facility operator will be responsible to provide trucking and disposal services with its own personnel and shall remove the stockpiled pipes during off hours or during such time as agreed to by the Contractor. Since the pipe removed will remain the property of the facility operator and is to be disposed of by the facility operator, the facility operator shall be responsible for any required notifications, filings, dump charges and incidentals associated with the disposal of abandoned gas facilities found to contain Coal Tar Wrap.

#### Wethod Of Measurement.

Abandoned gas pipeline removal shall be measured for payment per linear foot of pipe and appurtenances removed.

#### 5. Price To Cover:

The price shall cover all additional cost of supervision, labor, materials, equipment and insurance necessary to complete this work in accordance with the contract plans and specifications, including excavation by hand around and under other City and facility operator owned properties and, where necessary, the support and protection of such properties. The cost shall also include hand excavation in the area(s) of proposed abandoned pipe cut(s), cutting and/or burning of abandoned gas pipes and stockpile of removed sections of abandoned pipe and associated maintenance and protection of traffic, blocking and temporary fencing if required. The unit price shall also cover sealing open ends remaining in the excavation with concrete or end caps (end caps to be provided by the facility operator) and backfilling of the area where the abandoned pipeline has been removed with clean backfill material. This item does not include any type of extra excavation, backfilling, compaction, pavement removal and/or restoration (temporary and permanent) associated with abandoned pipe removal ("lost trench"), all of which are covered under separate Section 6.06. The price shall also include allowance for any loss of productivity by the Contractor due to required facility operator work to remove pipe coating and prepare pipe for cutting as well as any change in Contractor's excavation method, additional trucking and/or stockpiling costs.

# SECTION 6.03.1a - Removal Of Abandoned Gas Facilities With Possible Coal Tar Wrap. All Sizes. (For Con Edison Work Only)

#### 1. Description:

Under this section the Contractor shall provide all labor, material, equipment, insurance and, incidentals required to prepare abandoned gas mains, services and appurtenances thereof located within the street shown on contract plans, owned by the gas company operating in the project area (facility operator), for removal due to interference with proposed City work. These abandoned gas facilities were, at one time, used for or in connection with or to facilitate the conveying, transportation, distribution or furnishing of gas (natural, manufactured or a combination of both) for light, heat, or power, but does not include property used solely for or in connection with business of selling, distribution or furnishing of gas in enclosed containers. Such preparation for removal shall include only abandoned gas facilities that interfere with (i.e. cause additional work) City work. These gas facilities may be coated with Coal Tar Wrap which may contain asbestos or PCB's and so, may require special handling and disposal methods as specified in Con Edison - ASBESTOS MANAGEMENT MANUAL, CHAPTER 6 - ASBESTOS WORK PROCEDURES, SECTION 06.04 - COAL TAR WRAP REMOVAL. For under 25' (feet) in length and an approved NYC-DEP variance for over 25' (feet).

#### 2. Determination Of Operating Status Of Gas Facilities:

The Contractor shall notify facility operator, as required by New York State Industrial Code 753. Gas Facilities shall not be removed without the approval of the facility operator whose authorized representative shall certify in writing (specific facility or area wide facilities certification) and in a timely manner acceptable to the Resident Engineer that abandoned facilities are free of combustible gas and any other environmental contaminants prior to removal. The Resident Engineer shall rely on the facility operator's certification. The facility operator may request the excavation of test pits (See Section 6.07) for this determination ahead of City work and Contractor shall provide safe access, facilitate and permit facility operator to enter test pit excavations for the purpose of testing gas facilities. However, the facility operator may prefer to make this test during performance of City work in order to issue the above certification. This shall be permitted provided that it is agreed that additional costs, if any, resulting from this choice shall be a matter of adjustment between the Contractor and the facility operator only, and at no cost the City contract. Should such investigation result in the determination that the abandoned gas facilities do not contain Coal Tar Warp then the removal of said facilities shall be covered under separate item (See Section 6.03).

#### Requirements:

The Contractor shall excavate abandoned gas facility sufficiently, either in it's entirety, or at locations determined by Contractor to allow the removal of Coal Tar Wrap (if present on the abandoned gas facility) and to facilitate the safe extraction of manageable lengths of abandoned pipe without damage to adjacent facilities, utilities or city structures either parallel to or crossing above or below abandoned gas facility. The Contractor is to allow access to the designated cutting points within the Contractors trench by authorized Con Edison personnel who will remove the Coal Tar Wrap as per Con Edison and/or NYC-DEP approved procedures. This access shall conform to all applicable codes, rules & regulations. This work by Con Edison personnel shall be performed in a timely fashion and shall not unduly impede the Contractors progress and/or productivity. Upon completion of the coating removal, the Contractor shall be allowed to cut, burn or grind the gas facility and remove the section of abandoned pipe. Contractor shall designate a specific site to stockpile those removed pipes. The facility operator will be responsible to provide trucking and disposal services with its own personnel and shall remove the stockpiled pipes during off hours or during such time as agreed to by the Contractor. Since the pipe removed will remain the property of the facility operator and is to be disposed of by the facility operator, the facility operator shall be responsible for any required notifications, filings, dump charges and incidentals associated with the disposal of abandoned gas facilities found to contain Coal Tar Wrap.

#### 4. Method Of Measurement:

Abandoned gas facility removal shall be measured for payment per linear foot of pipe and appurtenances removed.

#### 5. Price To Cover:

The price shall cover all additional cost of supervision, labor, materials, equipment and insurance necessary to complete this work in accordance with the plans and specifications, including, but not limited to, excavation by hand around and under other City and facility operator owned properties and, where necessary, the support and protection of such properties. The cost shall also include hand excavation in the area(s) of proposed abandoned pipe cut(s), cutting and/or burning of abandoned gas pipes and stockpile of removed sections of abandoned pipe and associated maintenance of traffic, blocking and temporary fencing if required. The unit price shall also cover sealing open ends remaining in the excavation with concrete or end caps (end caps to be supplied by facility operator) and backfilling of the area where the abandoned pipeline has been removed with clean backfill material. This item does not include any type of extra excavation, backfilling, compaction, pavement removal and/or restoration (temporary and permanent) associated with abandoned pipe removal ("lost trench"), all of which are covered under separate Section 6.06. The price shall also include allowance for any loss of productivity by the Contractor due to required facility operator work to remove pipe coating and prepare pipe for cutting as well as any change in Contractor excavation method, additional trucking and/or stockpiling costs.

# SECTION 6.04 - Adjust Hardware To Grade Using Spacer Rings/Adaptors. (Street Repaving.)

#### Description:

Under this section, the Contractor shall provide all labor, supervision, materials, equipment, insurance and incidentals required to adjust to final grade gas street surface hardware located within the contract area boundaries shown on the plans. The gas company operating in the area, (facility operator), owns these facilities. The work shall be performed in accordance with the contract plans, specifications and at the directions of the Resident Engineer in concurrence with authorized representative of the facility operator.

#### 2. Materials:

The facility operator shall furnish and deliver all prefabricated hardware parts required. These include adaptors for the grade adjustment proper and new street hardware if existing ones are found to be defective, all in accordance with the facility operator standards and City rules and regulations. The Contractor shall notify the facility operator of the installation schedule at least three (3) business days before materials are required on the site. Should the facility operator fail to deliver the necessary material according to any schedule mutually agreed upon by the Contractor and facility operator, the City shall not be responsible for any delays attributable thereto, nor for the failure of delivery of such materials. On project where material storage is not permitted on site, the facility operator shall deliver the required material to the Contractor's yard and it shall be the Contractor's responsibility to transport the material to the work site when needed for installation. It shall also be the Contractor's responsibility to inspect the materials to be installed by him immediately upon delivery and advise the facility operator through its authorized representative, of all damaged materials. The Contractor at no additional expense to the City or the facility operator shall replace any material that is damaged or lost after the Contractor's inspection.

#### 3. Method Of Measurement:

The Contractor shall be paid for each six (6) inch round box and/or nine (9) inch square box adjusted to grade regardless of adjustment height requirements.

#### 4. Price To Cover:

The unit price bid for this item shall include all additional labor, supervision, insurance, equipment and, material (except those to be provided by the facility operator), required to adjust each box to grade as required in the contract plans and specifications. The bid price shall also include the removal of existing frames and covers from existing facilities to be salvaged and returned to the facility operator and, all material transportation from the Contractor's material storage yard to the work site. In addition the bid price shall include "chipping" around existing box using appropriate means and methods where grinding is required.

### SECTION 6.05 - Adjust Hardware To Grade By Resetting. (Road Reconstruction.)

#### 1. Description:

Under this item, the Contractor shall provide all labor, supervision, materials, equipment, insurance and incidentals required to adjust to the proposed grade gas street surface hardware located within the contract area boundaries shown on the plans. The gas company operating in the area, (facility operator), owns these facilities. The work shall consist of either building up or lowering or resetting the casting by removing the existing frame and cover building up or decreasing the existing installation, replacing the frame and/or cover if damaged or worn out, as determined by the Resident Engineer, with a new frame and/or cover furnished by the owner, and setting the frame and cover to new elevation. The work shall be performed in accordance with the contract plans, specifications and at the directions of the Resident Engineer.

#### 2. Materials:

The facility operator shall furnish and deliver all new hardware parts required. The Contractor shall furnish materials such as mortar, bricks and concrete in compliance with contract requirements. At locations where high-early strength concrete is required under this contract to be placed adjacent to gas facilities, then the requirement for concrete shall be high-early strength complying with the current New York State Department of Transportation, Standard Specifications for Class F concrete. Existing castings may be replaced as required and deemed necessary by the Engineer and by City rules and regulations. The Contractor shall install the new castings of various sizes furnished by the facility operator. The Contractor shall notify the facility operator of the installation schedule at least three (3) business days before materials are required on the site and, shall provide off-loading services to the facility operator. Should the facility operator fail to deliver the necessary material according to any schedule mutually agreed upon by the Contractor and facility operator, the City shall not be responsible for any delays attributable thereto, nor for the failure of delivery of such materials. Such delays shall be a matter of adjustment between the Contractor and the facility operator. On project where material storage is not permitted on site, the facility operator shall deliver the required material to the Contractor's yard and it shall be the Contractor's responsibility to transport the material to the work site when needed for installation. It shall also be the Contractor's responsibility to inspect the materials to be installed by him, immediately upon delivery and advise the facility operator through its authorized representative, of all damaged materials. Contractor at no additional expense to the City or the facility operator shall replace any material that is damaged or lost after the Contractor's inspection.

#### 3. Methods Of Construction:

The Contractor shall remove and reinstall existing castings or install new castings to the proposed grade. Setting and resetting the castings shall be done with mortar and brick according to the standards of the facility operator. Work shall be performed in a workmanlike manner. Castings that are deemed unacceptable for resetting shall remain the property of the facility operator and he shall be responsible for their removal and proper disposal from site. No traffic shall be allowed on adjusted street hardware until permitted by the Engineer.

#### 4. Method Of Measurement:

The Contractor shall be paid for each gas hardware adjusted to grade regardless of size or adjustment height requirements (up or down).

#### 5. Price To Cover:

The unit price bid for this item shall include all additional labor, supervision, insurance, equipment and, material (except those to be provided by the facility operator), required to adjust each gas hardware to grade as required in the contract plans and specifications. The bid price shall also include the removal of existing frames and covers from existing facilities; building up the existing installations with bricks and mortar, or lowering the existing installation by removing bricks and mortar; replacing damaged frames and/or covers with new frames and/or covers furnished by the facility operator; setting the frames and covers to the new elevations; protect existing installations; repair minor structural damages to existing installations prior to resetting frames; unloading of furnished castings at the Contractor's yard and transporting castings from the Contractor's yard to the job site as required; completing the work in

accordance with the contract plans, specifications and, at the directions of the Engineer. In addition the bid price shall include "chipping" around existing gas facilities using appropriate means and methods where grinding is required.

#### SECTION 6.06 - Special Care Excavation And Backfilling.

#### 1. Description:

Under this section, the Contractor shall provide all labor, materials, equipment, insurance and incidentals required to support and protect the integrity of live gas facilities including mains, services, related structures and appurtenances during excavations. The gas company operating in the area, (facility operator), owns these facilities. The work shall be performed in accordance with the contract plans, specifications and at the directions of the Resident Engineer in consultation with authorized representatives of the facility operator.

#### 2. Applicability Of Section:

This section shall apply to live gas facilities of various sizes located within two (2) feet of any face of unsheeted excavation (unsheeted excavation refers to any excavation performed for city work and includes excavations performed that are to be subsequently sheeted using approved methods) and paralleling or, encroaching any face of excavation. Also, for crossings greater than forty-five (45) degrees and/or located at a cover depth greater than five (5) feet from existing street surface. Parallel facilities are not exposed at any time during excavation (See "Gas Cost Sharing Work Standard Sketch No. 5"). Encroaching facilities are partially exposed inside the limit of excavation (See "Gas Cost Sharing Work Standard Sketch No. 5"). This section shall also apply to gas facilities crossing catch basins excavation. and catch basins sewer connections (chutes) trench excavation only when extra depth (covered in other section), is not required for chutes installations because of such utilities interferences (See "Gas Cost Sharing Work Standard Sketch No. 3"). This section shall also apply to gas services (if shown or otherwise listed in contract documents) crossing unsheeted excavations for water mains, gas facilities crossing fire hydrant branch connections, house sewer and/or water service connections excavations. This section shall also apply for so called "loss trench", as described further, and for additional excavation (pavement and/or soil), backfilling, compaction, roadway base and pavement restoration due to abandoned gas facilities, only if removed by Contractor. If operating status of gas facilities cannot be determined prior to excavation then such facilities shall be considered live and this section shall fully apply. The excavation around fully exposed live gas facilities along and within limits of excavation (not crossings) shall be covered by this section also (not shown on "Gas Cost Sharing Work Standard Sketch No. 5"), however the support requirement, if any is required, of such facilities is beyond the scope of these specifications and therefore shall be the responsibility of facility operator to determine and prescribe, at no cost to the City contract, but shall be a matter of adjustment between the Contractor and facility operator.

#### 3. Payment Restriction:

No special care excavation shall be paid for abandoned gas facilities paralleling and/or encroaching excavation and therefore are not in direct interference with City work. Except as allowed in this section, the bid item specified under this section shall not be used in combination with items covered under other sections for work done due to a particular gas facility. This item shall not be paid for new gas facilities when trenching for such new facilities has been performed by the Contractor of record in common with trench excavation for City Work (overlapping trench limits). The cost of excavating with care as defined in this section shall be deemed included in the cost of trench excavation for the new gas facilities. This restriction shall apply even if such gas common trench excavation is not part of the contract. If facilities are in direct interference with City work, meaning that "Minimum Clearances" described in "General Provisions; Gas Cost Sharing Work Paragraph No. 8" cannot be maintained and excavation has to be temporarily or permanently abandoned then this particular location shall become a test pit and dealt with as specified in Section 6.07 and "General Provisions; Gas Cost Sharing Work Paragraphs Nos. 2 and 8".

#### 4. Method Of Construction:

All excavation in the vicinity of gas facilities shall be as required by NYS Industrial Code 753. Where these facilities are paralleling and located two (2) feet or less from the limits of the proposed excavation, the Contractor shall use hand excavation methods (pick and shovel or hand held power tools) to ascertain

the clearances of these facilities with respect to the proposed excavation. Once the location of these facilities with respect to the proposed excavation is verified to the satisfaction of the Resident Engineer, the Contractor shall then proceed with a combination of hand and machine excavation as required preserving the integrity of the facilities. The installation of timber supports or underpinning, when soil foundation cannot fully support partially exposed pipes, may be required to prevent pipe movement as directed by the Resident Engineer.

#### 5. Method Of Payment:

The unit price for this work item shall be based on cubic yard (CY) of average excavation with care and, is to be considered as an incremental cost for performing City work with gas facilities interferences.

#### Method Of Measurement:

- A. For Paralleling Facilities: Volume calculated as: Depth as measured from existing street surface to the bottom of unsheeted trench excavation allowable by OSHA regulations, multiplied by, the width measured as one (1) foot from the face of excavation toward the center of excavation, multiplied by the length of parallel facility, divided by twenty-seven (27) cubic feet per cubic yard (See "Gas Cost Sharing Work Standard Sketch No. 5"). The gas facility is no longer considered to be in interference once sheeting has been installed, therefore no further compensation for paralleling facilities as described above will be made.
- B. For Encroaching Facilities: Volume calculated as: Depth of trench excavation multiplied by, the width of partially exposed pipe plus one (1) foot, multiplied by the length of facility encroachment, divided by twenty-seven (27) cubic feet per cubic yard (See "Gas Cost Sharing Work Standard Sketch No. 5").
- C. Fully Exposed Gas Facilities: (Not shown on "Gas Cost Sharing Work Standard Sketch No. 5") along and inside trench and/or crossing trench at an angle greater than forty-five (45) degrees and/or a cover depth greater than five (5) feet from the existing street surface. The volume shall be measured as the depth of trench excavation multiplied by the distance measured along the sheeting line between two (2) points of intersections of the gas facilities and the sides of trench excavation, multiplied by the width of trench excavation.
- D. For Additional Excavation And Restoration Due To So Called "Loss Trench", When The Integrity Of Pavement And Soil Above And Around Existing Live Gas Facilities Cannot Be Maintained Due To Its Lack Of Cohesiveness: Volume shall be calculated as: Depth of unsheeted trench excavation multiplied by width measured as distance of facility from closest edge of unsheeted excavation plus, width of facility proper plus, one (1) foot or a maximum width of three (3) feet multiplied by length of facility fully exposed divided by, twenty-seven (27) cubic feet per cubic yard (not shown on "Gas Cost Sharing Work Standard Sketch No. 5").
- E. For Facilities Crossing Excavation For Catch Basins, Or Chutes Installations (When NYCDEP Funded) Or Fire Hydrant Branch Connections, Or Unsheeted Water Main Trench, Or House Sewer And/Or Water Services: Volume calculated as: Depth as defined above multiplied by, the width taken as the outside diameter of pipe or the width of structure plus one (1) foot on either side (two (2) feet), multiplied by, the length of exposed facility crossing the trench, divided by twenty-seven (27) cubic feet per cubic yard (not shown on "Gas Cost Sharing Work Standard Sketch No. 5").

Overlapping volume dimensions measured as described above may occur when multiple facilities are paralleling excavations, encroaching excavations or crossing catch basins and catch basin chute installations. In such cases, all such facilities shall be counted as one limited by the extreme pipes, faces (See "Gas Cost Sharing Work Standard Sketch No. 2"). The volume shall then be calculated as described above.

#### 7. Price To Cover:

The bid price shall also cover all additional supervision, labor, material, equipment and insurance necessary to excavate while protecting and maintaining (excluding supports for fully exposed live gas) gas facilities without disruption of service to the public and in accordance with contract specifications. The price shall also include, changes of sheeting method and excavation width configuration where necessary to accommodate gas facilities in their existing locations; difficulties during the installation of catch basins,

chute connections, hydrant branch, and house sewer and water connections under or over gas facilities; loss of productivity due to slower rate of excavation (special care) during excavation, including the use of such methods as: hand excavation around existing single and multiple facilities, extra excavation and backfilling due to lost trench because of existing and adjacent gas facilities, compaction, removal of sheeting from the facilities, extra roadway base restoration and temporary pavement, associated maintenance and protection of traffic, barricades, and traffic plates that may be required to temporarily close and/or complete the work.

#### SECTION 6.07 - Test Pits For Gas Facilities.

#### 1. Description:

Under this section, the Contractor shall furnish all labor, materials, insurance, equipment and appliances necessary to excavate, sheet and, maintain test pits at locations approved by the Resident Engineer in consultation with the facility operator. Test pits shall be dug in order to ascertain exact locations, cover and invert elevations, clearances, alignment and operating status (live or dead) of existing gas facilities. The Contractor shall inspect jointly with the Resident Engineer and facility operator, gas facilities and other structures uncovered, take all relevant measurements and elevations as directed by the Resident Engineer. Tests to determine operating status of gas facilities shall be performed by facility operator. The pits shall be covered with steel plates during daytime nonworking hours, and uncovered, as required, until the inspection work is completed. Testing of gas facilities may require a maximum of four (4) hours. Then, the pits shall be backfilled with clean fill, and resurfaced with temporary pavement. All traffic shall be maintained and all safety measures as stipulated shall be complied with.

#### 2. Methods Of Construction:

- A. Excavation: Existing pavement to be removed shall be neatly cut along lines of removal with a saw or other approved equipment which leaves a neat straight joint line along the juncture with subsequently replaced pavement. Excavation in the vicinity of utilities and other structures shall be performed using hand tools. Use of hand operated pneumatic and electric jackhammers will be permitted only for breaking pavement and removal of masonry, concrete and boulders, or as otherwise directed by the Resident Engineer. The Contractor shall properly dispose of all materials excavated from test pits away from site. Test pits shall be excavated at locations shown on the contract drawings or as directed by the Resident Engineer. Additional test pits may be required and shall be excavated where required, as ordered by the Resident Engineer. All test pits shall be excavated to a depth and size necessary to locate the existing facilities. Sheeting shall be used when depth of excavation exceeds five (5) feet. The sneeting required shall be furnished and installed in full compliance with the State of New York and Federal Safety Codes requirements and as specified in contract, whichever is more stringent. Care shall be taken that no existing gas facilities or other structures are broken or damaged. All broken or damaged facilities shall be reported immediately to facility operator who shall decide whether such facilities shall be repaired or replaced by company forces or by City contractor and in conformance with "General Provisions; Gas Cost Sharing Work Paragraph No. 9". Contractor shall excavate all material encountered, including large masses of concrete, cemented masonry and boulders, as directed by the Resident Engineer. Any type of excavation protection used, shall satisfy the following:
  - (a) Industrial Code Rule 753.
  - (b) Prevent injury to workers and the public, and avoid damage to existing water, sewer, and gas pipes or other structures, and to pavements and their foundations, through caving or sliding of the banks of the excavation.

Should it become necessary, as determined by the Resident Engineer, to enlarge any test pit in any dimension after sheeting has been placed, the Contractor shall remove portions of the sheeting, as necessary, enlarge the test pits as directed, and replace the sheeting without additional compensation for this work other than for the additional volume of material excavated.

B. Maintenance Of Test Pits: Excavated test pits shall be maintained free of debris and kept dry by the Contractor in order to permit the inspection and measurements and to determine the locations of facilities. In order to accomplish this, Contractor shall, upon completion of excavation and placement of sheeting (if depth greater than five (5) feet), furnish and install adequate steel plates and posting

over the excavated pits and shall temporarily remove all equipment debris and workers, and relocate barricades in order to open the full width of street to traffic during nonworking hours. The Contractor shall then, at no additional cost, relocate such barricades, barrels, cones and other warning devices and remove steel plates, as and when directed by the Resident Engineer to facilitate the inspection of exposed facilities. When work is being performed and the pits are not covered with steel plates, the Contractor shall provide complete and safe access to the test pits as may be required, and he shall provide construction barricades and maintain traffic at all times as shown or as directed by the Resident Engineer. Upon completion of test pit inspection by the Resident Engineer, the pit shall be backfilled by the Contractor as specified in contract, except that backfill material shall conform to contract specifications for such purpose.

C. Pavement And Sidewalk Restoration: After backfilling is completed, the Contractor shall construct a temporary pavement consisting of a minimum of four (4) inches thick asphaltic concrete mixture in roadway areas or a two (2) inches thick asphaltic concrete mixture in sidewalk areas in order to maintain existing pedestrian and vehicular traffic. This temporary pavement shall be maintained until permanent pavement and sidewalk replacement is constructed as specified in contract.

#### 3. Measurements:

The quantity to be measured for payment shall be the number of cubic yards of material removed from within the limits of the pit dimensions as directed by the Resident Engineer. The volume occupied by existing pipes or other structures remaining within the maximum payment lines will not be deducted from the total volume measured except, where the cross sectional area of these facilities exceeds four (4) square feet. As determined by the Resident Engineer, the quantity measured for payment may be proportionate to a fair and reasonable estimate of gas responsibility in the total volume excavated.

#### 4. Price To Cover:

The contract price bid per cubic yard for test pits shall cover all additional costs of labor, material, insurance, equipment, appliances and incidentals required to excavate test pits, including removal and disposal of excavated materials, sheeting, steel plating, backfill, compaction and temporary pavement and sidewalk restoration all in accordance with the specifications and as directed by the Resident Engineer. The price shall also include the cost of providing safe access to the excavation by facility operator for the performance of certain test to determine operating status of gas facilities prior to City work. The price shall also include support and protection of all gas facilities crossing excavation, paralleling and/or encroaching any face of excavation.

# GAS COST SHARING STANDARD SPECIFICATIONS SCHEDULE GCS-A

### Average rate charged by utility companies to Disconnect and Reconnect Gas Services:

1. National Grid

- \$586.90 per Service/and Visit

2. Con Edison

- \$524.00 per Service/and Visit


### IV - STANDARD SKETCHES; GAS COST SHARING WORK

Hereinafter attached are the following Standard Sketches for Gas Cost Sharing Work:

- Sketch No. 1 Support Requirements For Gas Mains And Services Crossing Excavation Greater Than 4' 0" Wide At Any Angle
- Sketch No. 1A Support Requirements For Gas Mains Over 16" Diameter Up To And Including 48" Diameter Crossing Excavation At Any Angle
- Sketch No. 2 Typical Methods Of Measurement For Gas Crossings
- Sketch No. 3 Utility Crossings During Catch Basin Chute Connection Pipe Installation
- Sketch No. 4 Utility Crossings During Catch Basin Chute Connection Pipe Installation (Extra Depth)
- Sketch No. 5 Gas Main Encroachment On And/Or Parallel To Excavation Of Unsheeted Trench


### GAS COST SHARING WORK (SKETCH NO. 1)

# SUPPORT REQUIREMENTS FOR GAS MAINS AND SERVICES CROSSING EXCAVATION GREATER THAN 4'-0" WIDE AT ANY ANGLE




#### GAS COST SHARING WORK (SKETCH NO. 1A)


SUPPORT REQUIREMENTS FOR GAS MAINS OVER 16" DIAMETER UP TO AND INCLUDING 48" DIAMETER CROSSING EXCAVATION AT ANY ANGLE



A3-21B




# GAS COST SHARING WORK (SKETCH NO. 3) UTILITY CROSSINGS DURING CATCH BASIN CHUTE CONNECTION PIPE INSTALLATION




TYPICAL SEWER MANHOLE

# GAS COST SHARING WORK (SKETCH NO. 4) UTILITY CROSSINGS DURING CATCH BASIN CHUTE CONNECTION PIPE INSTALLATION (EXTRA DEPTH)



A3-21E

# GAS COST SHARING WORK (SKETCH NO. 5) GAS MAIN ENCROACHMENT ON AND/OR PARALLEL TO EXCAVATION OF UNSHEETED TRENCH



#### NOTES:

- (1) GAS MAIN LOCATED AS SHOWN MAY HAVE TO BE REMOVED BY THE FACILITY OPERATOR PRIOR TO THE START OF CITY EXCAVATION, OTHERWISE, THE CONTRACTOR WILL BE PAID UNDER SECTION 6.06 FOR THE SAID WORK. IF GAS MAIN IS ABANDONED THEN SECTION 6.03 SHALL APPLY.
- (2) EIGHTEEN (18) INCHES FROM STANDARD NEAT LINE IS THE MAXIMUM ALLOWABLE WIDTH, OF AREA THAT MAY BE DISTURBED OR EXCAVATED DURING INSTALLATION OF CERTAIN TYPES OF SHEETING SYSTEMS THAT MEET THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS OF THE DEPARTMENT OF DESIGN AND CONSTRUCTION OF THE CITY OF NEW YORK.

NO TEXT THIS PAGE

## V - PRELIMINARY GAS WORK TO BE PERFORMED BY FACILITY OPERATOR

#### APPLICABLE TO ALL GAS DRAWINGS:

- ALL RELOCATION WORK SHOWN IN THIS ADDENDUM IS TO BE PERFORMED BY FACILITY OPERATOR.
- ALL SUPPORT AND PROTECTION WORK TO BE PERFORMED BY CITY CONTRACTOR
- IF ADDITIONAL INFORMATION IS NEEDED REGARDING THE FACILITY OPERATOR RELOCATION WORK, THE CONTRACTOR IS ADVISED TO CONTACT THE GAS COMPANY REPRESENTATIVE:

MR. GERARD LUNDQUIST NATIONAL GRID 287 MASPETH AVENUE BROOKLYN, NY 11211 TEL.: 718-963-5506

(NO TEXT IN THIS AREA, TURN PAGE)


## national**grid**


#### **SER002316 GAS MAIN INSTALLATION**

ON STREET	1ST X-STREET	2ND X-STREET	SIZE/MAT'L	FOOTAGE	PRESSURE	REMB
WOODROW					TRESCORE	1/14141
RD	ROSSVILLE AVE	POWELL ST	6" PL	3705'	HP-60#	Y
FOSTER RD	WEILAND AVE	INTERSECTION	2" PL			Y
GILROY ST	WOODROW RD	WEST CASTOR PL	2" PL	295'		Y
VENUS PL	MARCY AVE	POWELL ST	2" PL	1545'	HP-60#	Y
	WOODROW RD FOSTER RD GILROY ST	WOODROW RD ROSSVILLE AVE FOSTER RD WEILAND AVE GILROY ST WOODROW RD	WOODROW RD ROSSVILLE AVE POWELL ST FOSTER RD WEILAND AVE INTERSECTION WEST CASTOR PL	WOODROW RD ROSSVILLE AVE POWELL ST 6" PL FOSTER RD WEILAND AVE INTERSECTION 2" PL GILROY ST WOODROW RD PL 2" PL	WOODROW RD ROSSVILLE AVE POWELL ST 6" PL 3705' FOSTER RD WEILAND AVE INTERSECTION 2" PL 145' WEST CASTOR PL 2" PL 295'	WOODROW RD         ROSSVILLE AVE ROSSVIL

#### **SER002316 GAS MAIN RETIREMENT**

17-004	0110555		T				
ITEM#	ON STREET	1ST X-STREET	2ND X-STREET	SIZE/MAT'L	FOOTAGE	PRESSURE	REME
.	WOODROW						17-101
2	RD	ROSSVILLE AVE	POWELL ST	6" WR ST	3375'	HP-60#	Y
4	FOSTER RD	WIELAND AVE	INTERSECTION	2" WR ST	125'	HP-60#	Y
	011 001/07		WEST CASTOR		1=0	VII 00#	<u> </u>
_ 6	GILROY ST	WOODROW RD	PL	2" PL	255'	HP-60#	Y
8	VENUS PL	MARCY AVE	POWELL ST	2" PL	1405'	·HP-60#	Y





A3-22C

## VI - LISTING OF APPROXIMATE LOCATIONS OF EP-7 BID ITEMS QUANTITIES

(NO TEXT IN THIS AREA, TURN PAGE)

#### SCOPE OF WORK SUPPORT AND PROTECTION FOR CONTRACT NUMBER SER-002316

The City of New York Department of Design and Construction is planning to install sewers and/or water mains and all appurtenances in various locations in The City of New York along with all work incidental thereto.

### 6.01.1 - Support & Protect Gas Main Crossing Sewer Up To 24" In Diameter (Ea.)

- 1 in Wieland Ave. Bet. Foster Rd. & Lenevar Ave.
- 1 in Foster Rd. Bet. Wieland Ave. & Ramapo Ave.
- 1 in Marcy Ave. @ Woodrow Rd.
- 2 in Powell St. Bet. Venus Pl. & West Castor Pl.
- 2 in West Castor Pl. @ Powell St.
- 1 in Woodrow Rd. @ Gilroy St.
- 1 in Foster Rd. Bet. Woodrow Rd. & Wieland Ave.
- 1 in Rossville Ave. Bet. Woodrow Rd. & McBaine Ave.

### 6.01.3 - Support & Protect Gas Main Crossing Sewer 36" Thru 42" In Diameter (Ea.)

- 1 in Marcy Ave. @ Woodrow Rd.
- 1 in Woodrow Rd. @ Gilroy St.

#### 6.01.8 - Support & Protect Gas Services Crossing Trenches And/Or Excavations (Ea.)

- 3 in Woodrow Rd. Bet. Alverson Ave. & Gilroy St.
- 2 in Rossville Ave. Bet. Woodrow Rd. & McBaine Ave.
- 2 in West Castor Pl. Bet. Wycliff Ln. & Powell St.
- 6 in Gilroy St. Bet. Woodrow Rd. & West Castor Pl.
- 1 in Foster Rd. Bet. Woodrow Rd. & Ramapo Ave.
- 14 in Woodrow Rd. Bet. Gilroy St. & Powell St.
- 1 in Woodrow Rd. Bet. Foster Rd. & Alverson Ave.

### 6.01.9 - Support & Protect Gas Main Crossing Water Main Up To 20" In Diameter (Ea.)

- 1 in Woodrow Rd. @ Gilroy St.
- 1 in Marcy Ave. @ Woodrow Rd.
- 1 in Rossville Ave. @ McBaine Ave.
- 1 in Rossville Ave. @ Mason Blvd.
- 1 in Foster Rd. Bet. Woodrow Rd. & Wieland Ave.
- 1 in Foster Rd. Bet. Wieland Ave. & Ramapo Ave.

#### SCOPE OF WORK SUPPORT AND PROTECTION FOR CONTRACT NUMBER SER-002316

The City of New York Department of Design and Construction is planning to install sewers and/or water mains and all appurtenances in various locations in The City of New York along with all work incidental thereto.

6.02 - Extra Excavation For The Installation Of Catch Basin Sewer Drain Pipes With Gas Interferences (Ea.)

1 in Marcy Ave. @ Venus Pl.

1 in Woodrow Rd. @ Alverson Ave.

4 in Venus Pl. Bet. Marcy Ave. & Powell St.

1 in Woodrow Rd. Bet. Ellworth Ave. & Powell St.

1 in Woodrow Rd. Bet. Deserre Ave. & Ellsworth Ave.

1 in West Castor Pl. @ Powell St.

6.03 - Removal Of Abandoned Gas Facilities. All Sizes (L.F.)

3200 in Various Locations As Required

6.03.1 - Removal Of Abandoned Gas Facilities With Possible Coal Tar Wrap. All Sizes. (For National Grid Work Only) (L.F.)

800 in Various Locations As Required

6.04 - Adjust Hardware To Grade Using Spacer Rings / Adaptor (Street Repaying) (Ea.)

25 in Various Locations As Required

6.05 - Adjust Hardware To Grade By Resetting (Road Reconstruction) (Ea.)

30 in Various Locations As Required

6.06 - Special Care Excavation & Backfilling (C.Y.)

1000 CY In Various Locations As Required, Including But Not Limited . To All Gas Services Crossing Unsheeted Water Main Trenches.

6.07 - Test Pits For Gas Facilities (C.Y.)

100 in Various Locations As Required.

End of Addendum No.3 This addendum consists of thirty-five (35) pages.

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION INFRASTRUCTURE DIVISION BUREAU OF DESIGN

PROJECT ID: SER002316

FOR THE RECONSTRUCTION OF SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE - BETWEEN KRAMER AVENUE AND WOODROW ROAD
WOOD ROAD - BETWEEN ROSSVILLE AVENUE AND POWELL STREET
FOSTER ROAD - BETWEEN WOODROW ROAD AND RAMAPO AVENUE
WIELAND AVENUE - BETWEEN LENEVAR AVENUE AND VERNON AVENUE
GILROY AVENUE - BETWEEN WOODROW ROAD AND WEST CASTOR PLACE
MARCY AVENUE - BETWEEN WOODROW ROAD AND VENUS PLACE
VENUS PLACE - BETWEEN MARCY AVENUE AND POWELL STREET
WEST CASTOR PLACE - BETWEEN POWELL STREET AND MARCY AVENUE

FOR THE INSTALLATION OF WATER MAINS AND APPURTENANCES IN:

ROSVILLE AVENUE - BETWEEN MASON BOULEVARD AND WOODROW ROAD

POWELL STREET - BETWEEN DEAD END AND WOODROW ROAD

WOODROW ROAD - BETWEEN ROSSVILLE AVENUE AND POWELL STREET

FOSTER ROAD - BETWEEN WOODROW ROAD AND RAMAPO AVENUE

## BOROUGH OF STATEN ISLAND CITY OF NEW YORK

## ADDENDUM NO.4 DATED: JANUARY 17, 2014

#### THIS ADDENDUM IS HEREBY MADE A PART OF THE CONTRACT DOCUMENTS

- 1. The Contractor shall be responsible for compliance with all the provisions of the following Sections and Schedules, which are hereby made a part of the original contract documents:
  - A. "SECTION U: Additional Contract Requirements Applying to Work Performed in the Presence of Privately Owned Utility Facilities" (Pages A4-4 through A4-14)
  - B. Schedule U-1 (Page A4-15)
  - C. Schedules U-2 (one for each Utility Company) (Pages A4-16 through A4-28)
  - D. Section U-3 Page A4-29 (as per the Private Utilities reference document for SECTION U called "CET SPECIFICATIONS AND SKETCHES", dated November 2010), in this Addendum.
  - E. Utility drawings consisting of:
    Con Edison Overhead Electrical Conditions Report (12)
    Con Edison Conduit and Duct Occupancy Plates (2)
    Con Edison Low Tension Mains and Service Plate (2)
    Verizon Existing Facilities Plans (3), attached to the Plans.

- 2. Each facility operator shall provide inspectors at the work site to inspect methods of interference work, verify quantities and items of Utility Work, and coordinate all phases of the facility operator operations.
- 3. In addition, the following statements are made to provide clarification of various paragraphs under Section U:
  - A. Section U, ¶4, requires the Contractor to immediately commence negotiations with each Company for an Interference Agreement under which the Company will compensate the Contractor for any Interference Work which the Company does not elect to perform with its own forces or by specialty contractors retained by the Company. Thus the Contractor is on notice that its work under the Contract may be affected by Interference Work performed by (a) the Contractor pursuant to a separate Interference Agreement with the Company, (b) the Company, or (c) partly by each.
  - B. Section U, ¶2, informs the Contractor that the duration of the Contract as shown in Schedule A includes the time which may be necessary for the Contractor to perform the necessary Interference Work.
  - C. The Contractor is hereby informed that the duration of the Contract as shown in Schedule A includes the time which may be necessary for the Company to perform whatever portion of the Interference Work which the Company elects to perform with its own forces or by specialty contractors retained by the Company.
  - D. Section U informs the Contractor that the City has entered into a Utility Agreement with the Companies regarding interferences to the City work in this Contract created by the facilities owned and/or operated by such Companies. Pursuant to this Addendum, a sample of the Utility Agreement letter as executed by the Companies is annexed on page A4-14, as an Exhibit to the Contract. Signed copies of those Utility Agreement letters are on file with NYCDDC.
  - E. The City has no contract with any of the Companies for work on or adjacent to the site of work under this Contract, and the Companies are not "Other Contractors" as defined for the purposes of this Contract. The Contractor is reminded, however, that pursuant to Section U, ¶4, the City will not compensate the Contractor for any direct and/or indirect costs related to Interference Work, regardless of whether such Interference Work is covered by an Interference Agreement between the Contractor and the Company or is performed by the Company using its own forces or by specialty contractors retained by the Company.
  - F. Section U, ¶14, provides that the provisions of Section U are material provisions of the Contract and that the Contractor's

failure to comply with the procedures set forth in Section U are sufficient for the Commissioner to declare the Contractor in default pursuant to Article 48 of the Contract.

Pursuant to this Addendum, the Contractor is informed that the Performance Bond required of the Contractor pursuant to the Contract is not deemed to guarantee performance of any of the Interference Work.

## Section U: Additional Contract Requirements Applicable to Work Performed in the Presence of Privately Owned Utility Facilities

The Contractor is hereby notified that pursuant to the law and franchise agreements issued by the City, certain private utility and public service companies named in Schedule U-1 ("the Companies") own and/or operate surface and/or subsurface facilities within the limits of this contract. The existence of these facilities impacts the productivity of the City work called for in the contract. In order to improve coordination of the City construction with the private utility facilities owned and/or operated by the Companies named in Schedule U-1, Article 1.06.30 of the Standard Highway Specifications of the New York City Department of Transportation, Dated November 1, 2010; Articles 1.06.14 through 1.06.17 of the General Provisions of the Standard Water Main Specifications of the New York City Department of Environmental Protection, dated August 1, 2009; and/or Articles 1.06.14 through 1.06.17 of the Standard Sewer Specifications of the New York City Department of Environmental Protection, Dated August 1, 2009; as applicable, are amended and will be implemented as follows:

#### 1. Pre-engineering:

The anticipated scopes of private utility facilities interferences and anticipated work items and specifications are included in this contract. The locations of these interferences are indicated on the plans and/or listed in the specifications for this contract, and a schedule of estimated quantities by type of interference expected to be encountered within the limits of this project area have been listed on Schedule U-2. In addition, in Section U-3 the Companies have provided standard details and methods for supporting, protecting, relocating, and/or working around their facilities when they are in interference with City contract work.

#### 2. Means and methods for City work:

- a) The Contractor is hereby notified that the utility interferences identified on the plans and/or listed in the Specifications to be known conditions which may impact the performance of, and/or interferes with, City work. The contractor will be required to perform such utility work as directed by the Resident Engineer in order to clear all utility interferences from the project site as required for satisfactory completion of City work within specified contract schedule.
- b) In areas serviced by overhead electric system, the contractor understands and by bidding for this contract agrees that he/she has reviewed the section 'U' package and that he/she will be required to perform the public work in the presence of energized

electrical overhead lines and appurtenances located in areas adjacent and/or within the project area. As a consequence he/she will select means and method of construction appropriate to maintain the safety clearances required or as permitted by contract specifications (e.g. "CET 350 – Overhead Accommodation Protection of Overhead Facilities, Poles, and Appurtenances") in order to avoid damaging the insulation or shielding of these lines and also to prevent knocking them down. The duration of the contract as shown in Schedule A thus includes the time which may be necessary for the Contractor to remove, repair, protect, support, shift, relocate, temporarily remove and replace, work around and/or work in the presence of the Companies' facilities ("Interference Work") as described on the plans and/or specifications of the contract during the progress of the City work.

#### 3. Field inspection prior to construction:

Prior to the start of any contract work in areas serviced by overhead electric lines, and after the award to the apparent low bidder for this contract, the contractor must request a field walk of the project area along with the operator of the overhead electrical facilities and the DDC Engineer-In-Charge. At that time the facility operator, pursuant to contract specification (e.g. "CET 350 — Overhead Accommodation Protection of Overhead Facilities, Poles, and Appurtenances") will confirm the type and condition of the overhead electrical lines and the sufficiency of their insulating properties with respect to the means and methods proposed by the contractor. The contractor must be prepared to describe in enough details his/her proposed means and methods of construction operations in order to anticipate the likelihood that electric lines insulation would be cut or otherwise compromised. Also such details will allow the facility operator to anticipate the need for added insulation and/or shielding of non-insulated lines.

#### 4. Compensation for interference work:

Compensation for Interference Work is a matter of adjustment between the Contractor and each private utility company located within the limits of the project area and whose utility facilities are affected by City contract work. In particular, the City will not compensate the Contractor for any direct and/or indirect costs related to Interference Work, including, but not limited to, lost profit, increased overhead, or any other impact costs. Upon receipt of a Notice of Award from the City, the Contractor shall immediately commence negotiations with each of the Companies concerning the manner in which and the price for which the Contractor, through its own forces or by others hired by it, will perform and be paid by the Company for all necessary Interference Work as defined above that the Company(ies) choose(s) not to perform

with its(their) own forces or by specialty Contractors hired by it (them) (as per "Interference Agreement"). (Specialty contractors' work is Iimited to (i) insulation installation and removal, (ii) live gas and steam work, (iii) cleanup and disposal of hazardous materials, (iv) splicing live electrical and telecommunications facilities, and (v) work not traditionally performed by general construction contractors).

#### 5. Interference Agreement:

- 1. The Companies have provided estimate of the quantity of each of the types of interferences expected to be encountered in the contract in Schedule U-2. Although the parties may negotiate an Interference Agreement in any format or manner they deem fit, the Contractor is hereby advised that the Companies have indicated to the City that they will agree to compensate the Contractor on a unit price basis according to the Quantity and Types of Interferences expected to be encountered on this Contract as stated in Schedule U-2.
- 2. Furthermore, in Section U-3, standard unit work measurement and payment provisions are specified and shall apply only if the Contractor and affected Utility companies enters into a unit price based Interference Agreement, otherwise the unit of work measurement, and payment provisions set forth in Section U-3 shall not apply. The Contractor shall notify the City upon concluding an Interference Agreement with each of the Companies, which shall be binding and final once concluded.

#### 6. City contract work to continue without Interference Agreement:

If, prior to the start of construction, as directed by the City's Order to work / Notice To Proceed (OTW/NTP) date any of the Companies and the Contractor have not concluded an Interference Agreement as described above, then the City construction will proceed as ordered and the Contractor will be directed by the Resident Engineer to perform the City work on Time, Material and Equipment basis (T&M) as specified in standard City contract agreement Article 26.2. T&M records will include identification of types of utility facilities interfering with City work, utility facility owners, specifying the nature and quantity of any materials, plant and equipment furnished or used in connection with the performance of such work and crew size, such as: name and number of each worker employed on such work. T&M records will also indicate the hours of, active time, standby time and idle time. The Company (ies) and the Contractor will maintain separate records of the actual quantity and cost of labor, materials, and equipment expended, and will provide copies of this information to the other party on a daily basis for reconciliation. These T&M records along with cost evaluations will be submitted daily to the Resident Engineer for review and approval. The total cost of City work

will be based on quantity of work performed multiplied by unit price contract bid items. The total interference cost will be calculated as the difference between the total T&M cost and total cost for City work. The Resident Engineer will conduct a monthly reconciliation session of the daily T&M records with the affected Company (ies) and contractor. If the contractor and affected utility companies cannot reconcile their T&M records, by the last day of each month, then the Resident Engineer will submit the approved City's T&M records along with total cost evaluations to the DDC Director of Construction who will review these records and recommend approval and validity certification by the DDC Deputy Commissioner.

- 1. Copies of the DDC approved and certified T&M records will then be transmitted by the DDC to the contractor and the utility companies. These certified records may be used by the contractor for compensation claims against the responsible private facility owners, or may be used by any party as supporting documentation in dispute regarding compensation for performing Interference Work as identified in Schedule U-2. The contractor will be required to perform City work while invoices are submitted by the contractor to the Utility companies for payment within 30 days, or while compensation disputes between contractor and affected company (ies) are submitted to Binding Arbitration process described in Paragraph 10.
- 2. All issues related to utility work and/ or delays due to compensation disputes or claims against utility companies are not allowable as justification for granting contract time extensions. The City may assess liquidated damages specified in the contract for net overall delays suffered by City contract work as a result of utility issues, disputes and claims.
- 3. The standard City contract dispute resolution process specified in Article 27 "Presentation of disputes to Commissioner", of the standard City contract agreement is not applicable to any disputes related to utility work and/ or compensation for such work or claim against utility companies. Utility work issues, disputes and claims may only be submitted to Binding Arbitration process described in Paragraph 10.
- 4. The contractor will notify the Resident Engineer when utility capital work not specified in Schedule U2 and/ or for utility work that require the intervention of company utility specialty crews causes excessive contractor's labor and equipment standby or idleness and, thereby jeopardizing the City project schedule. The Resident Engineer will submit the facts to the DDC Director of construction who will recommend to the Deputy Commissioner regarding the issuance of a "48 hours notice" to the concerned utility

- company as authorized by the New York City administrative Code Section 19-143 and/ or Section 24-521 as applicable.
- 5. Utility delays caused by utility capital work not listed in Schedule U2 and/ or by unavailability of utility specialty crews cannot be discounted for earning any contractual bonus when such bonus clause is included in a contract. However, if such specified bonus is not earned or disallowed by the City or if the City assesses specified liquidated damages as a result of such excessive delays, the contractor may seek damages from the responsible utility company (ies).

#### 6. Extra utility work with Utility Agreement:

If during construction the Contractor encounters utility facilities interferences or utility scope of work that it believes is not covered by the Interference Agreement as described above, then the Contractor shall immediately notify the Company in writing, with a copy to the City, describing the nature and location of the extra work in question. The Company then has five (5) business days to investigate the conditions and then:

- 1. Advise the Contractor and the City in writing that no interference with its facilities exists at the location in question, and hence that the Contractor may proceed with City work without providing for any impact from Company facilities;
- 2. Advise the Contractor and the City in writing that the Interference Agreement negotiated pursuant to Paragraph (6), above, provides for the scope of work encountered, specifying the exact unit items and/or terms of the agreement that cover the work;
- 3. Advise the Contractor and the City in writing that it intends to perform the necessary utility Work with company forces or with its own contractor including, but not limited to, relocating its facility out of the way of the proposed City work. In this case, the Company shall provide a written schedule for the performance of the utility work it proposes to perform, which shall be subject to approval by the City based on its impact to the Contractor's currently approved progress schedule. Upon approval of the Company's schedule by the City, the Contractor shall provide access to the worksite to the Company and/or any contractors hired by it to perform this utility work. If necessary, the City may grant a contract time extension for delays caused by the performance of such utility work by the company.
- 4. Reasonably specify in writing the scope of work to be performed by the Contractor on behalf of the Company that is not covered under the Interference Agreement negotiated pursuant to Paragraph (6), including, but not limited to, relocating, supporting, and/or

protecting the Company's facilities, and/or shifting the City facility if approved by the Resident Engineer, and/or otherwise changing its operations to work in the presence of the Company's facilities. Should the Company elect this option, it must adequately define and provide an initial price offer for the work required to be performed.

#### 7. Means and Methods for utility work:

Upon receipt of the Company's determination pursuant to paragraphs 7.2, or 7.4, above, the Contractor shall determine reasonable means and methods of performing the work defined by the Company. These means and methods are subject to approval of the Company, which shall not be unreasonably withheld. If, however, the Company objects to the Contractor's proposed means and methods then it shall define an alternate method of construction. Upon receipt of the Company's approval or its proposed alternate method of construction, the Contractor shall commence performance of the work defined by the Company as soon as possible, and shall perform the work in a good, workmanlike, and efficient manner, using the means and methods approved by the Company, in order to permit the City work to proceed in the most expeditious manner possible, but without imposing unreasonable and/or unnecessary costs on the Company. It is expressly understood by all parties that the City's rights pursuant to Article 4 of the Contract apply to Utility Work performed pursuant to this section.

#### 8. Disputed utility work covered by a utility agreement:

The City Work will continue as described in paragraph 6 above. In the event of any dispute between the Company (ies) and the Contractor regarding any issue related to the performance of, or payment for, utility work, including, but not limited to, any indirect or impact costs incurred by the Contractor due to the Utility Work and/or to the existence of facilities owned or operated by the Company (ies) on the line of the work. The Company (ies) and the Contractor hereby agree to submit to each other a "Final Offer," in writing, by certified mail. Each party shall then have three business days to consider each other's Final Offer. In the event that neither party accepts the other's Final Offer within those three days, the Company (ies) and the Contractor agree to immediately submit the dispute to binding arbitration as described in Paragraph 10. During the pendency of any arbitration, the Company (ies) and the Contractor shall maintain separate records of the actual quantity and cost of labor, materials, and equipment expended, and to provide copies of this information to the other party on a daily basis for reconciliation. Any and all disagreement with the records maintained and provided by the other, must be documented in writing to all parties. However, these records are solely for the benefit of presentation to the arbitrator, whose decision may not necessarily be based on these records and in any event is final. Both parties should be aware that the City will not confirm or deny the accuracy of any records maintained by either party for Utility work performed pursuant to a Utility Agreement. While the arbitration is pending, the Company shall pay the Contractor on a monthly basis, based on the price offered by the Company to the Contractor for the performance of the work.

#### 9. Arbitration of utility work:

The arbitration of the issues described above shall be conducted pursuant to the Construction Industry Arbitration Rules of the American Arbitration Association (hereinafter "the Rules" and "AAA") in effect on the date the arbitration is initiated except as set forth herein. The arbitration award shall be final and binding upon the parties to the arbitration and judgment upon the award may be entered in a court having jurisdiction.

- (a) Once an arbitrator(s) has been appointed by the AAA, the arbitration shall be scheduled as promptly as possible given the arbitrator(s) and the parties' schedules.
- (b) No later than seven days prior to the first arbitration hearing, Company and Contractor shall submit to the arbitrator(s), and to each other, a summary of each party's respective position and such other information as is deemed appropriate, along with a copy of each party's Final Offer as specified in paragraph 9.
- (c) The arbitration shall be conducted and concluded in two days.
- (d) On the morning of the first day of the arbitration, Contractor and/or representatives shall have 3 ½ hrs to make a presentation of its claim to the arbitrator. During its presentation, Contractor shall not be permitted to produce any documents or cost records which have not already been provided to the Company. Contractor shall be permitted to produce any analysis or description of its claim which has been prepared for the purpose of its presentation.
- (e) After lunch, Company and/or its representatives shall have two hours to ask Contractor questions about its claim and its presentation. Thereafter the arbitrator(s) shall have two hours to ask Contractor questions about its claim and its presentation.
- (f) On the morning of the second day of the arbitration, Company and/or its representatives shall have 3 ½ hours to make a presentation of its claim to the arbitrator. During its presentation, the Company shall not be permitted to produce any documents or cost records which have not already been provided to the Contractor. The Company shall be permitted to produce any analysis or description of its claim which has been prepared for the purpose of its presentation.

- (g) After lunch, Contractor and/or its representatives shall have two hours to ask Company questions about its claim and its presentation. Thereafter the arbitrator(s) shall have two hours to ask Company questions about its claim and its presentation.
- (h) Subject to the above time limitations, the arbitrator(s) may conduct the arbitration in such manner as the arbitrator(s) deems reasonable.
- (i) The arbitrator(s) shall then have one week to select in writing, as the arbitrator ('s) award, that party's Final Offer which appears to be more reasonable, based on the presentations at the arbitration hearings.
- (j) The arbitrator shall have no discretion to grant an award other than one of the two Final Offers submitted by the parties.
- (k) Any award for work that has already been performed shall be paid on the 7<sup>th</sup> day after receipt of the arbitrator's decision, or on the 30<sup>th</sup> day after completion of the work, whichever is later. Payment for work not yet completed at the time of the arbitrator's decision shall be paid within 30 days of completion of work. Interest shall accrue from the date payment is due at the rate of 9% per annum. Either party may cause judgment to be entered in accordance with the arbitrator(s) decision in a court in the State of New York, County of New York.
- (l) The arbitrator's fees and any other costs of the arbitration shall be initially shared equally by Company and Contractor. The non-prevailing party shall then pay all arbitrator's fees and costs of the arbitration and shall reimburse the prevailing party for its share of such fees and costs theretofore paid.
- (m) The parties may, at any time, settle any matter submitted to arbitration.

#### 11. Order-out waiver:

The Contractor and all subcontractors hired by it, if an Interference Agreement is executed as specified between the concerned parties, agree to waive any rights they may have, if any, under law, contract or otherwise to compel the City to assert any right the City may have, including the issuance of any directives required under the New York City Administrative Code, Section 19-143 and Section 24-521, to require any or all of the Companies to maintain, repair, replace, protect, support, shift, alter, relocate, and/or remove utility facilities in connection with the work to be performed under this contract. However, nothing in this section shall preclude the City from exercising its rights under the Law to issue such a directive to the Company.

#### 12. Cost of insurance:

Each of the named Companies, at their option and if an Interference Agreement is executed as specified between the concerned parties, may be named as an additional insured on all insurance policies required to be maintained under this contract. In the event that a Company opts to be so named as an additional insured, the actual incremental cost, if any, to the Contractor of providing such insurance coverage shall be borne by that Company. The Contractor shall provide a written statement from its insurance provider documenting the actual cost of this added coverage to the Company. Under no circumstances shall the cost of insurance coverage on behalf of any Company be borne by the City. Nothing in this paragraph shall be interpreted to imply the City's acceptance of any additional responsibility or liability for any matter related to the performance of Utility Work. In particular, the Company and the Contractor bear joint and full responsibility to ensure that any Utility Work performed by the Contractor is in compliance with all applicable government and Company regulations.

#### 13. Cost of utility interference work:

The Companies, by virtue of a prior agreement with the City, have agreed to perform their obligations described in this section. It is expressly understood that the cost of Utility Work shall not be a charge against the City, but shall be a matter for adjustment between the Contractor and the Company or Companies concerned. The City and the Contractor agree that the Companies are third party beneficiaries of this section of the contract, if a Utility Agreement is executed between the contractor and utility company (ies). The provisions of this section shall govern in all cases where Company property interferes with or is about to be disturbed by the City work, notwithstanding any other provision of the Contract, except for Natural Gas transmission/distribution facilities covered subject to the Gas Facility Cost Allocation Act (GFCAA) and covered separately in this contract.

#### 14. Default declaration:

The Contractor agrees that the provisions of this section are material provisions of the contract, and that the Contractor's failure to comply with the procedures set forth above are sufficient for the Commissioner to declare the Contractor in default pursuant to Article 48 of the Contract.

#### 15. NYS Labor Law:

The Contractor is hereby advised that New York State Labor Law applies to public work. The work described in this Section U of the contract performed by utility company (ies) with their own forces or vendors hired by such company (ies) is not public work.

#### 16. Facility operators:

The insurance requirements in Paragraph 12 of this Section U apply to: (i) additional Companies, if any, who were not named in Schedule "A" but which have executed a Utility Agreement with the contractor for utility work; and (ii) additional coverage, if any, paid for by Utility Companies whose utility facilities are located within the project limits, that they may require for the utility work pursuant to an utility agreement between the contractor and such utility companies.

[End]

## "STANDARD UTILITY LETTER OF AGREEMENT"

(Name)

Deputy Commissioner, Infrastructure Divisio	n		
Department of Design and Construction			
30-30 Thomson Avenue			
Long Island City, NY 11101			
DE City Waste Dances and in the D	CD:	*******	
RE: <u>City Work Performed in the Project No:</u>	esence of Private	Utility Facili	<u>ties</u>
110/001140.			<del></del>
Dear (Name):			
This letter is to certify that	, has re	equested the	inclusion
of the attached "Section U: Additional contra	act requirements at	pplying to wo	ork
performed in the presence of privately owned	utility." The com	pany agrees	to abide by
the terms of this Section U and to submit a so the items and estimated quantities, and types	nequie listing the	scope of work	k, including
protected at the company's own expenses due	or utility facilities	with the Publi	ed and
prosecution are and company to over expenses and	· co microronoes v	vitil the I don	C WOIK.
		•	
Sincerely,			
	•		
By: Authorized Company Representative			
Title			
NOTADY DUDI IC			
NOTARY PUBLIC			
CERTIFIED AS TO FORM			
AND LEGAL AUTHORITY:			
D			
By:			

### SCHED ULE U-1

SER-002316 WOODROW AVENUE

#### LISTING OF COMPANIES FOR THIS CONTRACT

COMPANY NAME	CONTACT NAME	CONTACT TELEPHONE
CON EDISON	THERES A KONG	212-460-4834
TIME WARNER	JOHN PLAZZA	718-888-4261
VERIZON	JOSEPH MARESCA	718-977-8138

#### SCHEDULE U-2

#### FOR INFORMATION ONLY

## ENGINEER'S ESTIMATE OF QUANTITY AND TYPES OF INTERFERENCE FOR CONSOLIDATED EDISON

### SER002316

Woodrow Rd Btw. Rossville Av & Powell St., Etc.

CET ITEM	DESCRIPTION	UNITS	ESTIMATED QUANTITY
CET 100.1	UTILITIES CROSSING TRENCH FOR CATCH BASIN CHUTE CONNECT. AND/OR TESTPIT (TYPE .1)	EA	1
CET 101.1	UTILITIES CROSSING TRENCH FOR SEWERS UP TO AND INCL. 24" DIAMETER (TYPE .1)	EA	12
CET 102.1	UTILITIES CROSSING TRENCH FOR SEWERS OVER 24" TO 36" DIAMETER (TYPE .1)	EA	2
CET 103.1	UTILITIES CROSSING TRENCH FOR SEWERS OVER 36" TO 48" DIAMETER (TYPE .1)	EA	2
CET 108.1	UTILITIES CROSSING TRENCH FOR WATERM AIN UP TO AND INCL. 12" DIAMETER (TYPE .I)	EA	5
CET 350	OVERHEAD ACCOMMODATION, PROTECTION OF OVERHEAD FACILITIES AND APPURTENANCES	L.S.	1
CET 351	INSTALL AND REMOVE "A" FRAME ON UTILITY POLES	EA	2
CET 1008V	8" VERTICAL OR ROLLED WATER MAIN OFFSET	EA	
CET 1012V	12" VERTICAL OR ROLLED WATER MAIN OFFSET	EA	1

## CON EDISON SCOPE OF WORK SUPPORT AND PROTECTION

#### SER002316

Woodrow Rd Btw. Rossville Av & Powell St., Etc.

UTILITIES CROSSING TRENCH FOR CATCH BASIN CHUTE CONNECT. AND/OR TESTPIT (TYPE .1) **CET 100.1** EA At the following locations: N/W/C POWELL ST & VENUS PL (1-4P) Total quantity for CET 100.1 UTILITIES CROSSING TRENCH FOR SEWERS UP TO AND INCL. 24" DIAMETER (TYPE .I) CET 101.1 ΕA At the following locations: F/O #1276 WOODROW RD (DBC) F/O #1276 WOODROW RD (1-4C) E/S FOSTER RD; 25' S/S/C WEILAND AVE (1-4C) F/O #119 WEILAND AVE (DBC) N/E/C MARCY AVE & VENUS PL (1-4P) S/E/C MARCY AVE & VENUS PL (PRI) INTERSECTION POWELL ST & VENUS PL (1-4P) X 4 INTERSECTION W. CASTOR PL & POWELL ST (1-4P) X 2 Total quantity for CET 101.1 UTILITIES CROSSING TRENCH FOR SEWERS OVER 24" TO 36" DIAMETER (TYPE .1) ET 102.1 At the following locations: N/E/C MARCY AVE & VENUS PL (1-4P) S/E/C MARCY AVE & VENUS PL (PRI) Total quantity for CET 102.1 UTILITIES CROSSING TRENCH FOR SEWERS OVER 36" TO 48" DIAMETER (TYPE .1) CET 103.1 EΑ At the following locations: F/O #1276 WOODROW RD (DBC) F/O #1276 WOODROW RD (1-4C) Total quantity for CET 103.1

## CON EDISON SCOPE OF WORK SUPPORT AND PROTECTION

#### SER002316

Woodrow Rd Btw. Rossville Av & Powell St., Etc.

CET 108.1	UTILITIES CROSSING TRENCH FOR WATERMAIN UP TO AND INCL. 12" DIAMETER (TYPE .1)	
	At the following locations:	EA
	E/S FOSTER RD; 25' S/S/C WEILAND AVE (1-4C)  N/E/C MARCY AVE & VENUS PL (1-4P)  INTERSECTION POWELL ST & VENUS PL (1-4P) X 2  F/O #1276 WOODROW RD (DBC)  F/O #1276 WOODROW RD (1-FC)	
	Total quantity for CET 108.1 = 5	
CET 350	OVERHEAD ACCOMMODATION, PROTECTION OF OVERHEAD FACILITIES AND APPURTENANCES  At the following locations:  VARIOUS  AS SHOWN ON CONTRACT DOCUMENTS	L.S.
	Total quantity for CET 350 = 1	
CET 351	INSTALL AND REMOVE "A" FRAME ON UTILITY POLES  At the following locations:	EA
•	N/E/C WOODROW RD & MARCY AVE N/E/C WOODROW RD & GILROY ST	
	Total quantity for CET 351 = 2	
CET 1008V	8" VERTICAL OR ROLLED WATER MAIN OFFSET  At the following locations:  VARIOUS  AS ENCOUNTERED AND DIRECTED BY A CON EDISON REPRESENTATIVE	EA
	Total quantity for CET 1008V = 1	
CET 1012V	12" VERTICAL OR ROLLED WATER MAIN OFFSET  At the following locations:  VARIOUS  AS ENCOUNTERED AND DIRECTED BY A CON EDISON REPRESENTATIVE  Total quantity for CET 1012V = 1	EA

## FOR INFORMATION ONLY ENGINEER'S ESTIMATE OF QUANTITIES AND TYPES OF INTERFERENCE TIME WARNER CABLE OF NEW YORK CITY

SER002316 Woodrow Road, etc. Borough of Staten Island

CETITEM	DESCRIPTION	UNITS	ESTIMATED QUANTITY
100.1	UTILITIES CROSSING TRENCH FOR CATCH BASIN CHUTE CONNECTION	EA	3
101.1	UTILITIES CROSSING TRENCH FOR SEWERS UP TO & INCLUDING 24" DIAMETER	EA	14
108.1	UTILITIES CROSSING TRENCH FOR WATER MAIN UP TO & INCLUDING 12" DIAMETER	EA	1
350	OVERHEAD ACCOMMODATION, PROTECTION OF OVERHEAD FACILITIES, POLES & APPURTENANCES	LS	1
400	TEST PITS FOR UTILITY FACILITIES	CY	3

#### TIME WARNER CABLE SUPPORT & PROTECTION SER002316 Woodrow Road, etc. Borough of Staten Island

CET 100.1	UTILITIES CROSSING TRENCH FOR CB CHUTE CONNE CTION		EA
	At the following location:		
	F/O 15 Powell Street		1
	F/O 47 Powell Street		1
	Intersection of Powell Street & Venus Place		1
		<u></u>	
		Total quantity for CET 100.1	3
	UTILITIES CROSSING TRENCH FOR SEWERS UP TO & INCLUDING	•	
CE1 101.1	24" DIAMETER		EA
	At the following locations:		
	Intersection of Powell Street & Venus Place		•
	Intersection of Powell Street & West Castor Place		2
	F/O 15 West Castor Place		2
	F/O 16 West Castor Place	•	1
	F/O 25 West Castor Place		1
	F/O 26 West Castor Place		1
	F/O 35 West Castor Place		1
	F/O 47 West Castor Place		1
	F/O 445 Powell Street		1
			1
	F/O 455 Powell Street F/O 463 Powell Street		1
•	F/O 473 Powell Street		1
	F/O 4/3 Fower Suger		1
		Total quantity for CET 101.1	14
	•	Total qualitity for OLI TOTAL	14
CET 108.1	UTILITIES CROSSING TRENCH FOR WATER MAIN UP TO &		ΕA
	INCLUDING 12" DIAMETER	•	
	At the following location:		
	Intersection of Powell Street & Venus Place		1
		Total quantity for CET 108.1	1
		• •	
CET 350	OVERHEAD ACCOMMODATION, PROTECTION OF OVERHEAD		LS
	FACILITIES, POLES & APPURTENANCES		
	At the following locations:		
	AS ENCOUNTERED		1
		Total quantity for CET 350	1
AFT 484	TECT DITC TOD LITE ITY EACH ITIES		
CET 400	TEST PITS FOR UTILITY FACILITIES		CY
	At the following locations: AS DIRECTED BY TIME WARNER CABLE REPRESENTATIVE		•
	AS DIRECTED BY HIME WARREN GABLE REFRESENTATIVE		3
		Total quantity for CET 400	

#### SECTION U WORKSHEET

#### SER002316

#### FOR INFORMATION ONLY

#### ENGINEER'S ESTIMATE OF QUANTITY AND TYPES OF INTERFERENCE

#### FOR VERIZON

### RECONSTRUCTION OF SANITARY AND STORM SEWER

#### IN WOODROW ROAD

CET			
ITEM	DESCRIPTION	Unit of	Estimated
NUMBER	22001412011		
NOMBER		Measure	Quantity
CET 100.1	UTILITIES CROSSING TRENCH FOR CATCH BASIN CHUTE CONNECT.	EA.	4.00
021 100.1	AND/OR TEST PIT (TYPE .1)	EA.	4.00
CET 100.2	UTILITIES CROSSING TRENCH FOR CATCH BASIN CHUTE CONNECT.	EA.	4.00
	AND/OR TEST PIT (TYPE .2)	EA.	4.00
CET 101.1	UTILITIES CROSSING TRENCH FOR SEWERS OVER 12" TO 24"	EA.	4.00
	DIAMETER (TYPE .1)		4.00
CET 101.2	UTILITIES CROSSING TRENCH FOR SEWERS OVER 12" TO 24"	EA.	3.00
	DIAMETER (TYPE .2)	"	3.00
CET 101.3	UTILITIES CROSSING TRENCH FOR SEWERS OVER 12" TO 24"	EA.	1.00
	DIAMETER (TYPE .3)		,,,,,
CET 103.1	UTILITIES CROSSING TRENCH FOR SEWERS OVER 36" TO 48"	EA.	2.00
	DIAMETER (TYPE .1)		
CET 108.1	UTILITIES CROSSING TRENCH FOR WATERMAIN UP TO AND INCL. 12"	EA.	6.00
	DIAMETER (TYPE .1)		
CET 108.2	UTILITIES CROSSING TRENCH FOR WATERMAIN UP TO AND INCL. 12"	EA.	8.00
OFT 000 4	DIAMETER (TYPE .2)		
CET 200.1	EXTRA DEPTH EXCAVATION OF CATCH BASIN CHUTE CONNECTION PIPES	L.F.	75.00
CET 225 1 A	REMOVAL AND INSTALLATION OF CATCH BASINS WITH UTILITY		
CE1 225.1A	INTERFERENCES	EA.	2.00
CET 225 1B	INSTALLATION OF CATCH BASINS WITH UTILITY INTERFERENCES		
OE 1 220.1D	INTO TARBATION OF GATOTIBACING WITH CITED INTERFERENCES	EA.	3.00
CET 225.1C	REMOVAL OF CATCH BASINS WITH UTILITY INTERFERENCES	EA.	1.00
	The state of the s	EA.	1.00
CET 300	SPECIAL CARE EXCAVATION & BACKFILLING	C.Y.	20.00
		J.,,	20.00
CET 330T	SUPPORT & PROTECTION OF COMMUNICATION UTILITY FACILITIES	L.F.	890.00
	DURING EXCAVATION OF CITY TRENCH WHEN FACILITIES LIE IN OR	<del></del>	,
	CLOSE PROXIMITY TO TRENCH LIMITS		
CET 350	OVERHEAD ACCOMMODATION, PROTECTION OF OH FACILITIES &	L.S.	1.00
	APPURTENANCES		
CET 351	INSTALL AND REMOVE "A" FRAMES ON UTILITY POLES	EA.	1.00
CET 400	TEST PITS	C.Y.	40.00
OFT 401	TREADU EVOLVATION SOR AR HISTORIA		
CET 401	TRENCH EXCAVATION FOR ADJUSTMENT OF UTILITIES	C.Y.	275.00
NET ADOT 4A	EVICT COOLIDIED CONOD ENGAGED CONDUITO TO		
EI 4021.1A	EXIST. OCCUPIED CONCR. ENCASED CONDUITS PLCD. IN FINAL POS.	L.F.	50.00
CET	WITH CONCR. ENCSMNT.  EXIST. VACANT CONCR. ENCASED CONDUITS PLCD. IN FINAL POS.		
	WITH CONCR. ENCAMENT.	L.F.	50.00
	EXIST. OCCUPIED NON-CONCR. ENCASED CONDUITS PLCD. IN FINAL		
	POS. WITHOUT CONCR. ENCSMNT.	L.F.	3,780.00
	EXIST. OCCUPIED NON-CONCR. ENCASED CONDUITS PLCD. IN FINAL		50.00
	POS. WITH CONCR. ENCSMNT.	L.F.	50.00

## SECTION U WORKSHEET

#### SER002316

#### FOR INFORMATION ONLY

## ENGINEER'S ESTIMATE OF QUANTITY AND TYPES OF INTERFERENCE

#### FOR VERIZON

## RECONSTRUCTION OF SANITARY AND STORM SEWER

#### IN WOODROW ROAD

CET ITEM NUMBER	DESCRIPTION	Unit of Measure	Estimated Quantity
CET 403	PLACING STEEL PROTECTION PLATES FOR UTILITIES	S.F.	200.00
CET 500	REMOVAL OF ABANDONED UTILITY CONDUITS (NON-CONCRETE ENCASED)	L.F.	50.00
RD	ADJUSTMENT OF UTILITY HARWARE ( 34" TO UNDER 41" WIDTH ) IN ROADWAY	EA.	3.00
CET 636 RM	REBUILDING AND MODIFICATIONS TO UTILITY STRUCTURES	C.Y.	25.00
CET 711	USE SHEETING LINE AS FORM	L.F.	40.00
CET 1006V	6" VERTICAL OR ROLLED WATER MAIN OFFSET	EA.	1.00
CET 1008V	8" VERTICAL OR ROLLED WATER MAIN OFFSET	EA.	1.00
CET 1012V	12" VERTICAL OR ROLLED WATER MAIN OFFSET	EA.	1.00

#### VERIZON CET SCOPE OF WORK

#### SUPPORT & PROTECTION

#### SER002316

## RECONSTRUCTION OF SANITARY AND STORM SEWER IN WOODROW RO AD

CET 100.1	UTILITIES CROSSING TRENCH FOR CATCH BASIN CHUTE CONNECT. AND/OR TEST PIT (TYPE .1)	EA.
	At the following locations:	
	GILROY STREET BTW WEST CASTOR PLACE AND WOODROW ROAD INT. OF GILROY STREET AND WOODROW ROAD MARCY AVENUE BTW WOODROW ROAD AND VENUS PLACE	1.00 1.00 2.00
	Total quantity for CET 100.1 = 4.00	
CET 100.2	UTILITIES CROSSING TRENCH FOR CATCH BASIN CHUTE CONNECT. AND/OR TEST PIT (TYPE .2)	EA.
	At the following locations:	
	ROSSVILLE AVENUE BTW MCBAINE AVENUE AND WOODROW ROAD INT. OF FOSTER ROAD AND WOODROW ROAD FOSTER ROAD BTW WIELAND AVENUE AND RAMAPO AVENUE	1.00 2.00 1.00
	Total quantity for CET 100.2 = 4.00	
CET 101.1	UTILITIES CROSSING TRENCH FOR SEWERS OVER 12" TO 24" DIAMETER (TYPE .1)	EA.
	At the following locations:	
•	ROSSVILLE AVENUE BTW MCBAINE AVENUE AND WOODROW ROAD FOSTER ROAD BTW WOODROW ROAD AND WIELAND AVENUE INT. OF FOSTER ROAD AND WIELAND AVENUE	2.00 1.00 1.00
	Total quantity for CET 101.1 = 4.00	
CET 101.2	UTILITIES CROSSING TRENCH FOR SEWERS OVER 12" TO 24" DIAMETER (TYPE .2)	EA.
	At the following locations:	
	INT. OF FOSTER ROAD AND WOODROW ROAD INT. OF FOSTER ROAD AND WIELAND AVENUE	2.00 1.00
	Total quantity for CET 101.2 = 3.00	
CET 101.3	UTILITIES CROSSING TRENCH FOR SEWERS OVER 12" TO 24" DIAMETER (TYPE .3)	EA.
	At the following locations:	
	WOODROW ROAD BTW ROSSVILLE AVENUE AND FOSTER ROAD	1.00
	Total quantity for CET 101.3 = 1.00	

### VERIZON CET SCOPE OF WORK

### SUPPORT & PROTECTION

### SER002316

# RECONSTRUCTION OF SANITARY AND STORM SEWER IN WOODROW RO AD

CET 103.1	UTILITIES CROSSING TRENCH FOR SEWERS OVER 36" TO 48" DIAMETER (TYPE .1)	EA.
	At the following locations:	
	ROSSVILLE AVENUE BTW MCBAINE AVENUE AND WOODROW ROAD WOODROW ROAD BTW ROSSVILLE AVENUE AND FOSTER ROAD	1.00 1.00
	Total quantity for CET 103.1 = 2.00	
CET 108.1	UTILITIES CROSSING TRENCH FOR WATERMAIN UP TO AND INCL. 12" DIAMETER (TYPE .1)	EA.
	At the following locations:	
	ROSSVILLE AVENUE BTW MCBAINE AVENUE AND WOODROW ROAD FOSTER ROAD BTW WOODROW RO AD AND WIELAND AVENUE INT. OF FOSTER ROAD AND WIELAND AVENUE INT. OF MASON BLVD. AND ROSSVILE AVENUE	1.00 1.00 1.00
	ROSSVILLE AVENUE BTW MASON BLVD. AND MCBAINE AVENUE	2.00
	Total quantity for CET 108.1 = 6.00	
CET 108.2	UTILITIES CROSSING TRENCH FOR WATERMAIN UP TO AND INCL. 12" DIAMETER (TYPE .2)	EA.
	At the following locations:	
	INT. OF ROSSVILLE AVENUE AND WOODROW ROAD INT. OF FOSTER ROAD AND WOODROW ROAD INT. OF FOSTER ROAD AND WIELAND AVENUE FOSTER ROAD BTW WIELAND AVENUE AND RAMAPO AVENUE INT. OF FOSTER ROAD AND RAMAPO AVENUE INT. OF MASON BLVD. AND ROSSVILE AVENUE	2.00 2.00 1.00 1.00 1.00
	Total quantity for CET $108.2 = 8.00$	
<b>CET 200.1</b>	EXTRA DEPTH EXCAVATION OF CATCH BASIN CHUTE CONNECTION PIPES	L.F.
	At the following locations:	
	ROSSVILLE AVENUE BTW MCBAINE AVENUE AND WOODROW ROAD INT. OF FOSTER ROAD AND WOODROW ROAD FOSTER ROAD BTW WIELAND AVENUE AND RAMAPO AVENUE	10.00 55.00 10.00
	Total quantity for CET 200.1 = 75.00	
CET 225.1A	REMOVAL AND INSTALLATION OF CATCH BASINS WITH UTILITY INTERFERENCES	EA.
	At the following locations:	
	INT. OF GILROY STREET AND WOODROW ROAD MARCY AVENUE BTW WOODROW ROAD AND VENUS PLACE	1. <b>00</b> 1. <b>00</b>
	Total quantity for CET 225.1A = 2.00	7.00

### VERIZON CET SCOPE OF WORK

### SUPPORT & PROTECTION

#### SER002316

# RECONSTRUCTION OF SANITARY AND STORM SEWER IN WOODROW ROAD

CET 225.1	B INSTALLATION OF CATCH BASINS WITH UTILITY INTERFERENCES	EA.
	At the following locations:	
	FOSTER ROAD BTW WOODROW ROAD AND WIELAND AVENUE FOSTER ROAD BTW WIELAND AVENUE AND RAMAPO AVENUE MARCY AVENUE BTW WOODROW ROAD AND VENUS PLACE	1.00 1.00 1.00
	Total quantity for CET 225.1B = 3.00	
CET 225.1	C REMOVAL OF CATCH BASINS WITH UTILITY INTERFERENCES	EA.
	At the following locations:	
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	1.00
	Total quantity for CET 225.1C = 1.00	
CET 300	SPECIAL CARE EXCAVATION & BACKFILLING	C.Y.
	At the following locations:	
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	20.00
	Total quantity for CET 300 = 20.00	
CET 330T	SUPPORT & PROTECTION OF COMMUNICATION UTILITY FACILITIES DURING EXCAVATION OF CITY TRENCH WHEN FACILITIES LIE IN OR CLOSE PROXIMITY TO TRENCH LIMITS  At the following locations:	L.F.
•	WOODROW ROAD BYW VERNON AVENUE AND GILROY STREET FOSTER ROAD BYW WOODROW ROAD AND RAMAPO AVENUE GILROY STREET BYW WEST CASTOR PLACE AND WOODROW ROAD MARCY AVENUE BYW WOODROW ROAD AND VENUS PLACE INT. OF MARCY AVENUE AND VENUS PLACE	320.00 10.00 340.00 190.00 20.00 10.00
	Total quantity for $CET 330T = 890.00$	
CET 350	OVERHEAD ACCOMMODATION, PROTECTION OF OH FACILITIES & APPURTENANCES	L.S.
	At the following locations:	
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	1.00
	Total quantity for $CET 350 = 1.00$	

### VERIZON CET SCOPE OF WORK

### SUPPORT & PROTECTION

### SER002316

# RECONSTRUCTION OF SANITARY AND STORM SEWER IN WOODROW RO AD

IN WOODROW RO AD	
INSTALL AND REMOVE "A" FRAMES ON UTILITY POLES	EA.
At the following locations:	
AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	1.00
Total quantity for CET 351 = 1.00	
TEST PITS	C.Y.
At the following locations:	
AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	40.00
Total quantity for CET 400 = 40.00	
TRENCH EXCAVATION FOR ADJUSTMENT OF UTILITIES	C.Y.
At the following locations:	
WOODROW ROAD BTW ROSSVILLE AVENUE AND FOSTER AVENUE FOSTER ROAD BTW WIELAND AVENUE AND RAMAPO AVENUE GILROY STREET BTW WEST CASTOR PLACE AND WOODROW ROAD MARCY AVENUE BTW WOODROW ROAD AND VENUS PLACE	180.00 45.00 20.00 30.00
Total quantity for CET 401 = 275.00	
EXIST. OCCUPIED CONCR. ENCASED CONDUITS PLCD. IN FINAL POS. WITH CONCR. ENCSMNT.	L.F.
At the following locations:	
AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	50.00
Total quantity for CET 402T.1A = 50.00	
EXIST. VACANT CONCR. ENCASED CONDUITS PLCD. IN FINAL POS. WITH CONCR. ENCSMNT.	L.F.
At the following locations:	
AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	50.00
Total quantity for CET 402T.V1A = 50.00	
EXIST. OCCUPIED NON-CONCR. ENCASED CONDUITS PLCD. IN FINAL POS. WITHOUT CONCR. ENCSMNT.	L.F.
At the following locations:	
WOODROW ROAD BTW ROSSVILLE AVENUE AND FOSTER AVENUE FOSTER ROAD BTW WIELAND AVENUE AND RAMAPO AVENUE GILROY STREET BTW WEST CASTOR PLACE AND WOODROW ROAD MARCY AVENUE BTW WOODROW ROAD AND VENUS PLACE	2700.00 600.00 240.00 240.00
	•
	As the following locations:  AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE  Total quantity for CET 351 = 1.00  TEST PITS  At the following locations:  AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE  Total quantity for CET 400 = 40.00  TRENCH EXCAVATION FOR ADJUSTMENT OF UTILITIES  At the following locations:  WOODROW ROAD BTW ROSSVILLE AVENUE AND FOSTER AVENUE FOSTER ROAD BTW WIELAND AVENUE AND RAMAPO AVENUE GILROY STREET BTW WEST CASTOR PLACE AND WOODROW ROAD MARCY AVENUE BTW WOODROW ROAD AND VENUS PLACE  Total quantity for CET 401 = 275.00  EXIST. OCCUPIED CONCR. ENCASED CONDUITS PLCD. IN FINAL POS. WITH CONCR. ENCSMNT. At the following locations:  AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE  Total quantity for CET 402T.1A = 50.00  A EXIST. VACANT CONCR. ENCASED CONDUITS PLCD. IN FINAL FOS. WITH CONCR. ENCSMNT. At the following locations:  AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE  Total quantity for CET 402T.1A = 50.00  EXIST. OCCUPIED NON-CONCR. ENCASED CONDUITS PLCD. IN FINAL POS. WITHOUT CONCR. ENCSMNT.  At the following locations:  WOODROW ROAD BTW ROSSVILLE AVENUE AND FOSTER AVENUE FOSTER ROAD BTW WIELAND AVENUE AND FOSTER AVENUE FOSTER ROAD BTW WIELAND AVENUE AND RAMAPO AVENUE

## <u>VERIZON CET SCOPE OF WORK</u> <u>SUPPORT & PROTECTION</u>

#### SER002316

## RECONSTRUCTION OF SANITARY AND STORM SEWER IN WOODROW ROAD

CET 402T.2	EXIST. OCCUPIED NON-CONCR. ENCASED CONDUITS PLCD. IN FINAL POS. WITH CONCR. ENCSMNT.	L.F.
	At the following locations:	
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	50.00
	Total quantity for CET 402T.2A = 50.00	
CET 403	PLACING STEEL PROTECTION PLATES FOR UTILITIES	S.F.
	At the following locations:	
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	200.00
	Total quantity for CET 403 = 200.00	
CET 500	REMOVAL OF ABANDONED UTILITY CONDUITS (NON-CONCRETE ENCASED)	L.F.
	At the following locations:	
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	50.00
	Total quantity for CET 500 = 50.00	
CET 636 EE RD	ADJUSTMENT OF UTILITY HARWARE ( 34" TO UNDER 41" WIDTH ) IN ROADWAY	EA.
	At the following locations:	
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	3.00
	Total quantity for $CET 636 EE RD = 3.00$	
CET 636 RM	REBUILDING AND MODIFICATIONS TO UTILITY STRUCTURES	C.Y.
	At the following locations:	
	ROSSVILLE AVENUE BTW MCBAINE AVENUE AND WOODROW ROAD WOODROW ROAD BTW ROSSVILLE AVENUE AND FOSTER ROAD	5.00
	FOSTER ROAD BTW WOODROW ROAD AND WIELAND AVENUE INT. OF FOSTER ROAD AND RAMAPO AVENUE	15.00 5.00
	Total quantity for CET 636 RM = 25.00	5.00
CET 711	USE SHEETING LINE AS FORM	
	At the following locations:	L.F.
ROSSVILLE AVENUE BTW MCBAINE AVENUE AND WOODROW ROAD INT. OF FOSTER ROAD AND RAMAPO AVENUE 20.00		
	Total quantity for $CET 711 = 40.00$	

### <u>VERIZON CET SCOPE OF WORK</u> <u>SUPPORT & PROTECTION</u>

#### SER002316

# RECONSTRUCTION OF SANITARY AND STORM SEWER IN WOODROW ROAD

CET 1006V	6" VERTICAL OR ROLLED WATER MAIN OFFSET	EA.
•	At the following locations:	·
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	1.00
	Total quantity for CET 1006V = 1.00	
<b>CET 1008V</b>	8" VERTICAL OR ROLLED WATER MAIN OFFSET	EA.
	At the following locations:	·
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	1.00
	Total quantity for CET 1008V = 1.00	
CET 1012V	12" VERTICAL OR ROLLED WATER MAIN OFFSET	EA.
	At the following locations:	
	AS ENCOUNTERED OR DIRECTED BY VERIZON FIELD REPRESENTATIVE	1.00
•	Total quantity for CET 1012V = 1.00	

# SECTION U-3

(NO TEXT IN THIS SECTION)

### END OF ADDENDUM No.4

This Addendum consists of Thirty (30 pages) And Nineteen (19) sheets of Contract Drawings

#### ATTACH TO CONTRACT DOCUMENTS

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION INFRASTRUCTURE DIVISION BUREAU OF DESIGN

PROJECT ID: SER002316

#### FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN
WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

**INCLUDING WATER MAIN WORK** 

**Together With All Work Incidental Thereto** 

**BOROUGH OF STATEN ISLAND** 

ADDENDUM NO. 5		
DATED: May 7, 2014		

This Addendum is issued for the purpose of amending the requirements of the Contract Documents and is hereby made part of said Contract Documents to the same extent as if it was originally included therein.

Refer to the Contract Drawings;

Add the following drawings (attached to the end of this addendum) to the end of the contract drawings:

Verizon Drawings, sheets No. 1 to 3.

Con Edison Drawings, sheets No. 1 to 16.

By signing in the space provided below, the bidder acknowledges receipt of one (1) page of this Addendum plus nineteen (19) sheets of contract drawings.

THIS ADDENDUM MUST BE SIGNED BY ALL BIDDERS AND ATTACHED TO THEIR BIDS.

GURDIP SAINI, P.E.

Assistant Commissioner/Design

A5-1

# CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION DIVISION OF INFRASTRUCTURE

# **ADDENDA CONTROL SHEET**

BID OPENING DATE: MAY 28, 2014
PROJECT NO.: SER002316
TITLE: CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES

ADDENDA ISSUED	No. OF DRAWINGS	DATE
#1: Amendments to Standard Highway Specs.		02/24/2014
#2: Sewer and Water Main Specifications		02/20/2014
#3: Gas Cost Sharing (EP-7) Std. Specifications		02/25/2014
#4: To CET Specifications		01/17/2014
#5: Additional Amendments		05/07/2014
#6: Additional Amendments		05/22/2014
		-

#### ATTACH TO CONTRACT DOCUMENTS

# THE CITY OF NEW YORK DEPARTMENT OF DESIGN AND CONSTRUCTION INFRASTRUCTURE DIVISION BUREAU OF DESIGN

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES IN:

ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET BETWEEN
WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

#### **INCLUDING WATER MAIN WORK**

**Together With All Work Incidental Thereto** 

#### **BOROUGH OF STATEN ISLAND**

DATED: May 22, 2014

This Addendum is issued for the purpose of amending the requirements of the contract documents and is hereby made part of said contract documents to the same extent as if it was originally included therein.

- (1) Refer to the Bid and Contract Documents, Volume 1 of 3, BID SCHEDULE, page B-13, Item No. 6.67, Sequence No. 057;

  Delete "3,300.00" under COL. 2, ENGINEER'S ESTIMATE OF QUANTITIES, and;
  Substitute "3,800.00".
- (2) Refer to the Bid and Contract Documents, Volume 1 of 3, BID SCHEDULE, page B-13, Item No. 6.68, Sequence No. 058;

  Delete "10,500.00" under COL. 2, ENGINEER'S ESTIMATE OF QUANTITIES, and;

  Substitute "46,000.00".
- (3) Refer to the Bid and Contract Documents, Volume 3 of 3, ADDENDUM NO. 2, Article (20), paragraph (E)(1), subparagraph (a), Page A2-12;

  Delete subparagraph (a), in its entirety;

  Substitute the following:
  - "(a) The entire width of existing roadway and six (6) inches of existing roadway subgrade shall be removed from curb to curb or edge to edge and the permanent restoration over the entire width of roadway shall consist of nine (9) inches of Asphaltic Macadam Pavement on a subbase course of six (6) inches of Select Granular Material (Material D only) on Plastic Filter Fabric. The above areas are approximate the actual final areas of restoration shall be determined by the Engineer."

ADDENDUM NO. 6 PROJECT ID.: SER002316

(4) Refer to the Bid and Contract Documents, Volume 3 of 3, ADDENDUM NO. 2, Article (20), paragraph (E)(2), subparagraph (a), Page A2-12;

**Delete** subparagraph (a), in its entirety;

Substitute the following:

- "(a) The entire width of existing roadway and six (6) inches of existing roadway subgrade shall be removed from **curb to curb** or **edge to edge** and the permanent restoration over the **entire width of roadway** shall consist of six (6) inches of Asphaltic Macadam Pavement on a subbase course of six (6) inches of Select Granular Material (Material D only) on Plastic Filter Fabric. The above areas are approximate the actual final areas of restoration shall be determined by the Engineer."
- (54)<u>Refer</u> to the Bid and Contract Documents, Volume 3 of 3, ADDENDUM NO. 2, Article (20), paragraph (E)(4), table under subparagraph (i), Page A2-13;

  Add the following to the end of the table under the appropriate headings shown:

Item No.	<u>ltem</u>	Payment Description
6.67	Subbase Course, Select Granular Material	(For 6" sub-base course under entire width of roadway restoration.)
6.68	Plastic Filter Fabric	(For placement under sub-base course.)

By signing in the space provided below, the bidder acknowledges receipt of two (2) pages of this Addendum.

GURDIP SAINI, P.E. Assistant Commissioner/Design

Name of Bidder
By:



### INFRASTRUCTURE DIVISION BUREAU OF DESIGN

### **VOLUME 3 OF 3**

PROJECT ID: SER002316

FOR THE CONSTRUCTION OF STORM AND SANITARY SEWERS AND APPURTENANCES
IN: ROSSVILLE AVENUE BETWEEN MASON BOULEVARD AND WOODROW ROAD;
WOODROW ROAD BETWEEN ROSSVILLE AVENUE AND POWELL STREET;
FOSTER ROAD BETWEEN WOODROW ROAD AND RAMAPO AVENUE;
WIELAND AVENUE BETWEEN LENEVAR AVENUE AND VERNON AVENUE;
GILROY STREET BETWEEN WOODROW ROAD AND WEST CASTOR AVENUE;
MARCY AVENUE BETWEEN WOODROW ROAD AND VENUS PLACE;
VENUS PLACE BETWEEN MARCY AVENUE AND POWELL STREET; POWELL STREET
BETWEEN WOODROW ROAD AND WEST CASTOR PLACE; AND,
WEST CASTOR PLACE BETWEEN POWELL STREET AND MARCY AVENUE

INCLUDING WATER MAIN WORK

Together With All Work Incidental Thereto BOROUGH OF STATEN ISLAND CITY OF NEW YORK

The state of the s	Contractor
Dated	